

## National Aeronautics and Space Administration

(MASA-CR-159830) CF6-6D ENGINE SHORT-TERM PERPORMANCE DETERIORATION (General Electric Co.) 154 p HC A08/MF A01

N80-23316

Unclas G3/07 20310

# CF6-6D ENGINE SHORT-TERM PERFORMANCE DETERIORATION

by

W.H. Kramer, J.E. Paas, J.J. Smith, and R.H. Wulf

GENERAL ELECTRIC COMPANY AIRCRAFT ENGINE GROUP CINCINNATI, OHIO 45215

Prepared For

National Aeronautics and Space Administration

NASA Lewis Research Center Contract NAS3-20631



#### **PREFACE**

The work was performed by the General Electric Aircraft Engine Business Group located in Evendale, Ohio. This CF6 Jet Engine Diagnostics Program was conducted for the National Aeronautics and Space Administration Lewis Research Center, Cleveland, Ohio. The NASA Project Engineers for this program were Robert Dengler and Charles M. Mehalic.

The General Electric Company would like to express its appreciation to American Airlines for their cooperation in supplying CF6-6D ESN 451507 for use in this program; and to the Douglas Aircraft Company for data supplied.

The requirements of NASA Policy Directive NPD 2220.4 (September 14, 1970) regarding the use of SI Units have been waived in accordance with the provisions of paragraph 5d of that Directive by the Director of Lewis Research Center.

PRECEDING PAGE BLANK NOT FILMED

## TABLE OF CONTENTS

Section		Page
1.0	SUMMARY	1
2.0	INTRODUCTION	2
3.0	APPARATUS AND PROCEDURES	4
	3.1 Engine Description (ESN 451507) 3.2 Test Facilities	4
	3.2.1 Evendale Production CF6 Test Cells	6
	3.2.2 ASO/Ontario Test Cell	13
	3.3 Instrumentation 3.4 Procedure	13 20
	3.4.1 Production Acceptance Test 3.4.2 Aircraft Acceptance Test 3.4.3 Inbound Test 3.4.4 Analytical Teardown and Reassembly	20 20 23 23
4.0	RESULTS AND DISCUSSION	24
	4.1 Performance Results	24
	4.1.1 Cruise Performance Trends 4.1.2 Inbound Test Cell Results 4.1.3 Summary of Performance Data	24 33 35
	4.2 Hardware Inspection Results	37
	4.2.1 Fan Section 4.2.2 High Pressure Compressor Section 4.2.3 High Pressure Turbine Section 4.2.4 Low Pressure Turbine Section 4.2.5 Summary of Hardware Inspection Data	37 38 38 39 39
	4.3 Comparison and Deterioration Assessment	39
5.0	RECOMMENDATIONS	42
APPENDIX	A - TEST PLAN/WORKSCOPE	43
APPENDIX	B - HARDWARE INSPECTION DATA	53
APPENDIX	C - QUALITY ASSURANCE REPORT	126
APPENDIX	D - SYMBOLS AND ACRONYMS	142
DISTRIBU	TION	146

PRECEDING PACE BLANK NOT FILMED

v

## LIST OF ILLUSTRATIONS

Figure		Page
3-1	General Electric CF6-6 Engine Cross Section.	5
3-2	Aerial View of Production En ine Test Facility.	7
3-3	Engine "Prep" Area, Production Engine Test Facility.	8
3-4	Production Engine Test Facility Control Room.	9
3-5	Test Engine Installed in Cell M34, Production Engine Test Facility.	10
3-6	Production Engine Test Facility Data Center.	12
3-7	CF6 Engine Installed in Ontario Test Cell.	14
3-8	CF6 Test Facility Control Room, Ontario.	15
3-9	CF6-6D Performance Instrumentation.	16
3-10	CF6-6D Performance Instrumentation.	17
3-11	EGT Thermocouple Harness.	19
3-12	EGT - Indicating System Circuit.	19
3-13	Schematic of DC-10-10 Initial Acceptance Test Flight.	22
4-1	EGT Cruise Margin - First Airplane/Engine Checkout Flight.	27
4-2	Short-Term EGT Cruise Losses - First Airplane/ Engine Checkout Flight.	28
4-3	Short-Term EGT Cruise Losses - Multiple Checkout Flights/Early Revenue Service.	30
4-4	Early Revenue Service EGT Cruise Losses	31

# LIST OF ILLUSTRATIONS (CONTINUED)

Figur	<u>e</u>	
		Page
A-1	Notched HP Turbine Blades.	
B-1	Fan Section.	50
B-2	Locations of Stage 1 Fem Di	55
	Locations of Stage 1 For Blade Tip Clearance Measurements.	56
B-3	HP Compressor Rotor in Runout Fixture.	
B-4	Location of Surface Pints	61
D r		63
B-5	Forward CDP Seal, Rotating.	
B-6	HP Compressor Stator Assembly - Rubs and Chipped	63
B 7		67
- •	Location of Surface Finish Measurements - HP Compressor Stator Vane.	70
B-8	Forward CDP Seal, Stationary.	
B-9	No. 4B Pressure Balance Seal (Mini-Nozzle).	72
B-10	Stage 1 HPTN Vanes - Leading Edge.	72
B-11		78
B-12	Stage 1 HPTN Vanes - Trailing Edge.	79
	Dimension "D" - Drop From CRF To Stage 1 HPTN Vane.	80
B-13	HP Turbine Stage 1 Vane.	
B-14	Stage 1 HPT Shrouds - Rub.	83
B-15	Stage 2 HPTN Assembly - Typical Stage 2 Shroud Rubs.	86
B-16	Dimension "K" - Stage 2 Up m	
	Dimension "K" - Stage 2 HP Turbine Nozzle Support	88
B-17	Typical Stage 1/Stage 2 Shroud Measurement Locations.	_
B-18	Stage 2 HPT Nozzle Support - Location of Dimensional	91
	inspections.	94

/9

## LIST OF ILLUSTRATIONS (CONCLUDED)

Figure		Page
B-19	Stage 2 HPTN Support and Stage 2 Shroud Runouts.	96
B-20	Stage 2 HPTN Support and Stage 1 Shroud Runouts.	97
B-21	Typical HPTR Blade Concave/Convex Surface Finish Measurement Locations.	99
B-22	HP Turbine Rotor in Runout Fixture.	101
B-23	HPT Rotor Blade Tip Notch Data.	104
B-24	HP Turbine Notched Blades at Teardown.	105
B-25	CF6-6 HPT Blade Tip Notch Results - Stage 1 Blade Tip Rubs.	108
B-26	CF6-6 HPT Blade Tip Notch Results - Stage 2 Blade Tip Rubs.	109
B-27	HP Turbine Rotor Forward Shaft Seals and Thermal Shield.	110
B-28.	Location of Surface Finish Measurements on LPT Vanes.	116
B-29	Low Pressure Turbine Rotor.	119
B-30	Location of Surface Finish Measurements on LPT Blades.	122
B-31	LPTS Shroud and Interstage Seal Rub Impressions.	123
B-32	LP Turbine Stator Assembly - View of Shroud and Seal Rubs.	124
C-1	EABR Card.	130
C-2	EACR Card.	132
C-3	Test Operating Requirements Document.	135
C-4	Prep-to-Test and Test Check-Off Sheet.	137
C-5	Instrumentation Check Sheet.	138
C-6	Inspection Check Sheet.	139
C-7	Work Order Sample.	140
C-8	UPTE Blade Ingrestion Sheet	14

## LIST OF TABLES

Table		Page
3-I	Instrumentation Ranges and Accuracies.	21
4-I	Short-Term Performance Deterioration Assessment-Inbound Test ESN 451487.	34
4-II	ESN 451507 Test Cell Results.	36
4-111	Short-Term Performance Deterioration Study Assessment - Inbound Test ESN 451507.	36
4-IV	Analytical Assessment of ESN 451507.	40
B-I	Stage 1 Fan Blade Tip Clearances at E12 (Rotor Runout).	57
B-II	Stage 1 Fan Blade Tip Clearances at E13 (Rotor Runout).	58
B-III	Stage 1 Fan Shroud/Long Blade Minimum Clearance Measurements.	59
B-IV	Stage 1 Fan Blade Tip Clearances.	59
B-V	HPC Rotor Airfoil Surface Finish Inspection Results.	62
B-VI	HPCR Seal Teeth Inspection Results.	64
B-VII	Forward CDP Seal Clearances.	65
B-VIII	HPC Stator Airfoil Surface Finish Inspection Results.	68
B-IX	Stationary CDP Seal, Forward Dimensional Inspections.	73
B-X	No. 4B Pressure Balance Seal, Forward Seal (Aft CDP) Dimensional Inspections.	74
B-XI	No. 4B Pressure Balance Seal, Aft Seal (HPT Balance Piston) Dimensional Inspections.	75
3-XII	Aft CDP Seal Clearances.	76
3-XIII	HP Turbine Balance Piston Seal Clearances.	76
3-XIV	CRF to Stage 1 HPTN Vanes Drop Dimension - Dim."D"	80

## LIST OF TABLES

Table		
B-XV	Stage 1 HPTN Volume	Pag
	Stage 1 HPTN Vane Segment Gaps.	8.
B-XVI	Stage 1 HPT Nozzle Area Measurements (A4).	82
B-XVII	Stage 1 HPTN Vane Surface Finish Inspection Results.	84
B-XVIII	Stage 2 HPT Nozzle Support - Dimension "K".	88
B-XIX	Stage 2 HPTN Interstage Seal Groove Measurements.	89
B-XX	Stage 1 HPT Shroud Dimensions.	92
B-XXI	Stage 2 HPT Shroud Dimensions.	93
B-XXII	Stage 2 HPT Nozzle Support Diameters Measurements.	94
B-XXIII	Stage 2 HPT Shroud Runouts, Unrubbed Path.	95
B-XXIV	HPT Rotor Airfoil Finish Inspection Results.	100
B-XXV	Stage 1 HPTR Blade Tip Dimensions.	102
B-XXVI	Stage 2 HPTR Blade Tip Dimensions.	103
B-XXVII	HP Turbine Blade Tip Clearances.	106
B-XXVIII	HPTR Thermal Shield Seal Teeth Measurements.	111
B-XXIX	HPTR Forward Shaft Forward Seal Teeth Measurements (AFT CDP Seal).	112
B-XXX	HPTR Forward Shaft Aft Seal Teeth Measurements (Balance Piston Seal).	113
B-XXXI	TMF Forward Flange (Diameter "U") Measurements.	115
B-XXX1I	LPT Pressure Balance Seal (Stationary) Measurements.	115
B-XXXIII	LPTS Airfoil Surface Finish Inspection Results.	117
B-XXXIV	LP Turbine Rotor Radii Measurements.	120
B-XXXV	LPTR Airfoil Surface Finish Inspection Results.	121

#### 1.0 SUMMARY

This report summarizes the efforts to quantify the extent and magnitude of short-term performance deterioration of the General Electric CF6-6D engine. These efforts included the analysis of cruise cockpit recordings for a large sample of engines along with inbound test-cell and analytical teardown data for a selected engine. Short-term deterioration has been defined as those losses that occur during the aircraft/engine checkout flights prior to customer delivery and initiation of revenue service. The other major area of engine deterioration - long-term - is defined as those losses that occur during revenue service.

An analysis of initial checkout flight cruise data for 82 CF6-6D engines indicated that the average short-term deterioration in cruise fuel burn was 0.9 percent. While this loss is real and nonreversible, little additional loss occurs during subsequent aircraft checkout flights and during the first several hundred hours of revenue service.

To supplement and substantiate the 82-engine sample, CF6-6D production engine serial number (ESN) 451507 was removed immediately following all checkout flights of DC-10-10 aircraft, fuselage number (F/N) 250. After receiving an inbound performance calibration run, the engine underwent an analytical disassembly and detailed inspection of all its modules and parts to document the performance deterioration modes.

The short-term performance losses measured for ESN 451507 agreed well with the 82-engine average. Additional analysis substantiated that ESN 451507 was a representative CF6-6D model engine, thereby validating that the short-term hardware inspection results are typical of the CF6-6D fleet. These results indicate that approximately 90 percent of the assessed loss results from high pressure turbine deterioration caused by rubs between the blade tips and static shrouds. No other significant deterioration mode was identified.

Finally, short-term performance deterioration data obtained from other sources, most notably supplementary hardware data and additional test cell results, are presented to substantiate the short-term performance results.

ORIGINAL PAGE IS OF POOR QUALITY

#### 2.0 INTRODUCTION

The recent energy demand has outpaced domestic fuel supplies, increasing the dependence of the United States on foreign oil. This increased dependence was accentuated by the OPEC embargo in the winter of 1973/74 which triggered a rapid rise in the price of fuel. This rise, along with the potential for further increases, brought about a set of changing economic circumstances with regard to the use of energy. These events were felt in all sectors of the transportation industry, including the air transport industry. As a result, the Government, with the support of the aviation industry, has initiated programs aimed at both the supply and the demand aspects of the problem. The supply problem is being investigated by determining the fuel availability from new sources such as coal and oil shale, with concurrent programs in place to develop engine combustor and fuel systems to accept these broader-based fuels.

Reducing fuel consumption is the approach being used to decrease fuel demand. Accordingly, NASA is sponsoring the Aircraft Energy Efficient (ACEE) program, directed toward reducing the fuel consumption of commercial air transports. The long-range propulsion effort to reduce fuel consumption is expected to evolve new technology that would permit the development of a more energy efficient turbofan, or the use of an improved propulsion cycle such as that used for turboprops. Studies have indicated that either approach could yield large reductions in fuel usage - as great as 15 to 40 percent for turboprops. But a significant impact in fuel usage is considered to be fifteen or more years away. In the near term, the only practical propulsion approach is to improve the fuel efficiency of current engines because these engines will continue to be the most significant users of aircraft fuel for the next 15 or 20 years.

Within the ACEE program, the Engine Component Improvement (ECI) program is the element directed toward improving the fuel efficiency of current engines. The ECI program consists of two parts: (1) Performance Improvement, and (2) Engine Diagnostics. The Performance Improvement program is directed toward developing component performance improvements and improved performance retention for new production and retrofit engines. The Engine Diagnostics effort is to provide information to identify the sources and causes of engine deterioration.

#### OBJECTIVES

As part of the Engine Diagnostic effort, NASA-Lewis initiated a program with the General Electric Company to conduct performance deterioration studies for the CF6-6D and CF6-50 engines. The basic objectives of the program were (1) to determine the specific causes of engine deterioration that increase fuel burn, (2) to isolate short-term losses from the longer-term losses, and (3) to identify potential ways to minimize deterioration. This report covers the results of an investigation of the CF6-6D short-term losses. The remaining results for the CF6-6D and CF6-50 model engines will be presented in separate reports.

### APPROACH

The investigating of short-term deterioration began with the gathering of a large sample of DC-10-10 cock, it cruise checkout data. These data established the magnitude of the CF6-6D short-term (pre-delivery) performance losses, and were supplemented by a special program utilizing CF6-6D ESN 451507. This engine was removed from the wing of a DC-10-10 after the Douglas Aircraft Company (DACo) conducted its acceptance flights but before the aircraft was initiated into revenue service. The engine was tested inbound, and an analytical teardown was conducted to document the condition of the deteriorated ware influence coefficients to isolate the short-term deterioration mechanisms. The overall losses assessed independently from the hardware and from performance data were compared. These comparisons were used along with supplementary hardware data to determine the validity of the results and to verify that the ESN 451507 short-term deterioration was representative.

#### 3.0 APPARATUS AND PROCEDURES

#### 3.1 ENGINE DESCRIPTION

The CF6-6D engine model was type-certificated on September 16, 1970, and was introduced into revenue service in mid 1971. This engine model, which has a 40,000-pound ideal thrust takeoff rating, is in use by six of the seven DC-10-i0 aircraft operators. An updated version of the CF6-6D model with a 41,000 pound ideal thrust takeoff rating, termed the CF6-D1, is currently being used by one operator.

The CF6-6D engine is a dual-rotor, high-bypass-ratio (5.6 to 5.8:1) turbofan engine expressly designed for airline operation. The low-pressure system consists of a two-stage front fan connected to a five-stage low-pressure turbine by a fan midshaft passing through the core engine. The first-stage fan rotor blades incorporate a part-span shroud, while the second- or quarter-stage fan supercharges the high pressure compressor. Fixed stator vanes are mounted behind both stages of the fan rotor. The low pressure turbine consists of a five-stage rotor that has low-tip-speed, high-aspect-ratio shrouded blades. Fixed stator vanes are located in front of each low pressure turbine rotor stage.

The high pressure gas generator or core engine consists of the high pressure compressor, the combustor, and the high pressure turbine. The HP compressor is a 16-stage, high-pressure-ratio (approximately 16:1), axial-flow design. The inlet guide vanes and the first six stator-vane stages are variable. The compressor provides bleed air for hot-section cooling along with airframe pressurizing and anti-icing air. The annular combustor contains 30 duplex fuel nozzles and two ignition plugs. The two-stage HP turbine is air cooled with nonshrouded blades and cooling/purge features for tip clearance control. Fixed convection cooled stator vanes are provided upstream of two HPT rotor stages, with the Stage 1 vanes also incorporating film cooling.

The four main support structures are: the fan frame, the compressor rear frame, the turbine midframe, and the turbine rear frame. These frames include mountings for the bearings, service tubes for lube supply and scavenge, and air pressurization and venting for the four internal sumps. The accessory drive section extracts energy from the high-speed rotor to (1) drive the engine-mounted accessories, (2) provide core engine speed signal, and (3) provide pods to mount the aircraft-supplied hydraulic pumps, constant-speed drive, and alternator.

A cross section of the CF6-6D model engine is presented as Figure 3-1.

the engine selected for this short-time performance deterioration investigation was CF6-6D engine ESN 451507. This engine is typical of those shipped in the September 1977 time period, and was chosen primarily because of its availability for this program. American Airlines (AAL) expressed an interest in participating in the CF6 Jet Engine Diagnostics Program efforts and consented to remove CF6-6D ESN 451507 from DC-10-10 aircraft fuselage number




Figure 3-1. General Electric CF6-6 Engine Cross Section.

(F/N) 250 following flight-acceptance tests and prior to initiation of revenue service. The engine was returned, as a ready spare, to AAL following the completion of the short-term performance deterioration investigation.

## 3.2 TEST FACILITIES

This section of the report describes the test facilities, data acquisition system, and instrumentation utilized for the special test engine.

## 3.2.1 EVENDALE PRODUCTION CF6 TEST CELLS

The General Electric CF-6 Production Engine Test Facility, (Figure 3-2) is 'ocated in Evendale, Ohio. It consists of two cells, M34 and M35, separated by a common access aisle (the engine prep area) on the lower level (Figure 3-3) and by a control room (Figure 3-4) on the second level. Auxiliary equipment rooms are located fore and aft of the control room and above the cells. A radio-frequency-shielded room is located at the rear of the access aisle. The cells, each 30 feet wide by 20 feet high by 188 feet in overall length, have horizontal air inlets and vertical exhaust systems. Engine access is through a large, vacuum-sealed door in the side wall of the cell. Figure 3-5 shows a typical test engine installation in one of the cells.

Each cell is equipped with:

- An air intake system
- An exhaust gas system
- A fuel system
- Lube oil and hydraulic oil fill systems
- An air system for engine starting
- A CO<sub>2</sub> fire extinguishing system
- 24-volt DC and 400-cycle electrical power packages
- Automatic data handling equipment
- Display instrumentation for airflow, fuel flow, thrust, oil consumption, vibrations, pressures, and temperatures
- Special instrumentation wiring for high speed recorders
- Other high accuracy equipment used for transient and dynamic measurements



Figure 3-2. Aerial View of Production Engire Test Facility.



Figure 3-3. Engine "Prep" Area, Production Engine Test Facility.

OF POOR CATTER




Figure 3-4. Production Engine Test Facility Control Room.

9




Figure 3-5. Test Engine Installed in Cell M34, Production Engine Test Facility.

The data-handling equipment (Figure 3-6) is wired directly to the General Electric Computer Facilities for rapid computation of engine performance.

A digital Automatic Data Acquisition System (ADAS) is available to process performance data in the Production Engine test cell facility. The actual calculations on the data, with the associated conversion to engineering units and calculations for determining performance characteristics, are accomplished by a time-sharing computer system.

The data are input directly to the computer system via a data phone and are simultaneously recorded on a backup paper tape. In the event of a computer bottleneck, the paper tape can be generated and off-line information can be fed automatically to the computer via the same phone system (operating at a 1200 baud rate). Performance results are printed out at the test control room station on a General Electric Terminet 1200.

The recording system itself can accommodate all of the normal sensors encountered in engine testing. Temperature signals are processed through a reference junction maintained at 150° F from the alloy wire to the copper wire; the actual value of this reference junction is checked by the insertion of a 32° F reference signal generated from a Joseph Kaye ice point reference. The signals are multiplexed through solid-state switches to fixed-gain differential amplifiers to the analog-to-digital (A-D) converter. The computer program converts the millivolt level to a temperature value through a table

Like the other raw data, voltage and millivolt calibration standard signals are simultaneously recorded into the computer and on to paper tape so that corrections can be made for overall system drift in the amplifier/A-D converter components. The system has a resolution of one part in 10,000 and, in general, precision can be expected to three parts in 10,000 (99.7 percent) or eight  $\mu\nu$ , whichever is larger.

Pressure parameters are processed through a sequencing of pneumatic twelveport scanning valves, each valve having an individual transducer. Each of eleven parameters on a valve is referenced to the control room barometer utilizing the twelfth port of the scanning valve, making any errors in the pressure signals appear as a percentage of the reading accuracy.

In order to accommodate the dynamic characteristics exhibited by an engine, key parameters (such as thrust, speed, and fuel flow) are programmed and interspersed at predescribed intervals throughout the data scan. The value for each of these parameters utilized in performance calculations is the average of these multiple readings.

The basic data-scan rate is approximately eight channels per second with voltage indirectly connected to the signals, and two channels per second with pressure signals that are pneumatically switched. This scan rate allows a stabilization that is sufficient to obtain the 99.97 percent/8 µv accuracies mentioned above.

Figure 3-6. Production Engine Test Facility Data Center.

# 3.2.2 ASO/ONTARIO TEST CELL

The ASO/Ontario CF6 test cell is fully enclosed and constructed to the same cross-sectional dimensions (20 x 30 ft) as the Evendale production cells M34 and M35. The cell inlet consists of two rows of acoustic panels and a foreign object damage (FOD) screen. The engine exhaust flows through the augmentor and the acoustically treated exhaust stack. Figure 3-7 shows a CF6 engine installed in the Ontario test cell. Note the inlet acoustic panels and FOD screen. The CF6 lightweight bellmouth is supported by the overhead rail system against the left wall of the test cell.

The test cell, capable of handling engines having up to 100,000 pounds of thrust, presently contains a 50,000-1b load cell. The cell duplicates the Evendale, Ohio, production facilities and permits complete engine performance testing and functional testing. It has been correlated to the Evendale CF6 production test cells through back-to-back tests, the most recent of these using CF6-50 ESN 517650. In addition, other engines (both CF6-6 and CF6-50) between tested back-to-back, with only nonperformance modifications made locations with full performance instrumentation (including nozzle discharge surement system at the test cell being correlated. Cell correlations include but also setting the correct fan and core nozzle discharge areas.

The data recording system used at the GE/Ontario CF6 test cell is supplied by the manufacturer, VIDAR. The system capability includes 132 pressures, 130 temperatures, and 10 frequencies. The pressure capability consists of 11 transducers for 0-500 psia, 11 for 0-150 psia, 44 for 0-25 psia, and 66 for 0-10 psig. The transducers are 12-port scanner valves, each having one port up to a 10-second time base. The temperature capability includes recording both C-C (copper-constantan) and C-A (chromel-alumel) thermocouples. The flowmeters (main and verification fuel flow) are connected in series upstream of the engine fuel inlet.

The VIDAR system stores the test data reading on a punched paper tape. This tape, containing coded raw output in millivolt units, is loaded into the General Electric time-sharing computer system for data reduction and analysis. Figure 3-8 shows the Ontario CF6 test cell control room.

## 3.3 INSTRUMENTATION

## DESCRIPTION

All parameters were measured and recorded in the Evendale and Ontario CF6 test-cell control rooms. Figure 3-9 depicts the performance instrumentation locations. Figure 3-10 shows rake locations and immersion depths. The test-the following items:



Figure 3-7. CF6 Engine Installed in Ontario Test Cell.




Figure 3-8. CF6 Facility Control Room, Ontario.

ORIGINAL PAGE IS OF POOR QUALITY




Figure 3-9. CF6-6D Performance Instrumentation.

ORIGINAL PAGE IS OF POOR QUALITY




Figure 3-10, CF6-6D Performance Instrumentation

/9

- Barometric Pressure (PBAR) The local (control room) barometric pressure.
- Humidity (HUM) The absolute humidity in grains of moisture per pound of dry air.
- Ambient Temperature (T2) C-C thermocouples mounted on the testceli screen.
- Cell Static Pressure (PO) Test cell wall static pressure.
- Fan Speed (N1) Low pressure rotor speed.
- Core Speed (N2) High pressure rotor speed.
- T49 Exhaust Gas Temperature (EGT) LPT inlet temperature indicating system consisting of eleven dual-immersion C-A thermocouple probes electrically averaged. The system is composed of four harnesses joined together by means of an aft lead which in turn connects to a forward lead. The forward lead has another electrical connector for transmission of the signal to the EGT indicator (Figures 3-11 and 3-12).
- Main Fuel Flow (WFM) Facility engine fuel flow measured on a volumetric turbine flowmeter.
- Verification Fuel Flow (WFV) Facility engine fuel flow measured on a volumetric turbine flowmeter.
- Fuel Temperature (TF) Facility engine fuel temperature measured at the flowmeters using a C-C thermocouple.
- Bellmouth Total Pressure (PT2) Four 6-element pitot-static rakes (manifolded by rake) located in the engine bellmouth forward of the fan face. Rake Part No. (P/N) 4013034-682G01 and -682G02 (two each).
- Bellmouth Static Pressure (PS2) Four 6-element pitot-static rakes (read individually) located in the engine bellmouth forward of the fan face. Rake P/N 4013034-682G01 and -682G02 (two each).
- Fuel Sample Specific Gravity (SGSAMP) Specific gravity of the fuel sample.
- Fuel Sample Temperature (TSAMP) Fuel sample temperature read during the specific-gravity measurement.
- Fuel Lower Heating Value (LHV) Lower heating value of the fuel sample as determined by a bomb calorimeter.
- Load Cell Thrust (FG) Thrust frame axial force measured using a 50,000-1b load cell.




Figure 3-11. EGT Therrocouple Harness.

Figure 3-12. EGT Indicating System Circuit.

- Compressor Discharge Temperature (T3) Five-element C-A thermocouple rake measured individually. Rake P/N 4012403-847601.
- Compressor Discharge Static Pressure (PS3) Wall static located in a combustor borescope port.
- LP Turbine Inlet Total Pressure (P49) Five four-element probes manifolded by probe. Probe P/N 9554M54G06.
- Variable Stator Position (VSV) LVDT readout measured on a 0 to 5volt scale.

#### RANGES AND ACCURACIES

Table 3-I summarizes the range requirements and instrumentation accuracies for the test-cell instrumentation described in the previous section. The accuracies quoted are 20 values (i.e., 95 percent confidence limits).

#### 3.4 PROCEDURE

The Short-Term Performance Deterioration Program, utilizing ESN 451507, consisted of an Evendale Production Acceptance Test, a DACo DC-10 Aircraft/Engine Acceptance Test, an ASO/Ontario Inbound Test, and an Analytical Teardown/Reassembly.

### 3.4.1 PRODUCTION ACCEPTANCE TEST

The Evendale Production Acceptance Test verifies that the engine can be safely operated to takeoff power without exceeding certified redlines while achieving guaranteed performance levels. The test includes a

- Seal break-in run and functional test to check variable stator vanes (VSV's) and engine vibrations.
- A performance test to measure component levels and overall engine performance parameters. The test included the reading and recording of the performance parameters described in Section 3.3.

### 3.4.2 AIRCRAFT ACCEPTANCE TEST

After extensive aircraft/engine ground testing, the DC-10-10 aircraft undergoes the initial acceptance test flight. The segments of this flight are presented schematically in Figure 3-13. After normal takeoff and climb to medium altitude, a number of system checks are conducted, including an airplane stall check which produces large excursions in engine power. These checks are followed by a climb to high altitude, during which acceleration checks from flight

Table 3-I. Instrumentation Ranges and Accuracies.

Parameter	Range	Accuracy
PBAR	28 to 31-in. Hg.	0.1% absolute
HUM	0 to 200 grains	5% relative humidity
T2	-10 to 110° F	1* F
PT2	0 to -10 in. H <sub>2</sub> 0	0.5% gage
PS2	0 to -85 in. H <sub>2</sub> O	0.5% gage
N1	0 to 4200 rpm	5 rpm
N2	0 to 11,000 rpm	20 rpm
EGT	0 to 2000° F	10° F
WFM	0 to 70 gpm	0.5% of reading
WFV	0 to 70 gpm	0.5% of reading
TF	-10 to 110° F	2* F
SGSAMP	0.7 to 0.8	0.15% of reading
TSAMP	-10° to 110°	1* F
LHV	18,000 to 19,000 Btu/lb	0.3% of reading
FG	0 to 50,000 lb	0.5% of reading
<b>T</b> 3	0 to 1200° F	10° F
PS3	0 to 500 psig	0.5% of reading
P49	0 to 100 psig	0.5% of reading
vsv	0 to 5 volts	




Figure 3-13. Schematic of DC-10-10 Initial Acceptance Test Flight.

idle to maximum climb power are conducted on each engine, one at a time. (These acceleration checks potentially result in "hot rotor rebursts" which will be discussed later.) Stabilized cruise recordings, which are used to establish the short-term deterioration, are obtained upon reaching a high altitude - typically 35,000 to 39,000 feet. Additional acceleration and system checks are then performed at cruise, and are followed by a shutdown and relight for each engine during aircraft descent. Approach operation during the initial flight includes several go-arounds, and the flight is terminated with a landing utilizing full reverse power.

## 3.4.3 INBOUND TEST

The ASO/Ontario Inbound Test establishes the performance level of the engine relative to the as-shipped performance measured in Evendale (see Section 3.4.1). The inbound test includes a

- Functional test to check variable stators and engine vibration as well as to assure that the engine could be safely operated at take-
- A performance test to measure component levels and overall engine performance parameters. The instrumentation that is read and recorded is the same as that which was used during the Production Acceptance Test (Section 3.4.1).

# 3.4.4 ANALYTICAL TEARDOWN AND REASSEMBLY

The analytical teardown included a detailed dimensional and visual inspection of the engine modules as they were being disassembled. Special attention was given to the three major sources of deterioration: increased clearances, decreased airfoil quality, and leakages. These inspection results were used in conjunction with hardware influence coefficients to isolate the deterioration mechanisms and assign a fuel burn deterioration level to each source. Influence coefficients are empirically or analytically derived factors which equate a change in hardware condition with a change in component performance.

## 4.0 RESULTS AND DISCUSSION

The detailed results from the short-term deterioration studies included cruise and test cell performance results for more than 80 CF6-6D production engines and assessments of short-term deterioration mechanisms. These deterioration assessments were based primarily on the hardware inspection results from ESN 451507 as well as special ground and flight tests.

## 4.1 PERFORMANCE RESULTS

Two sources of performance data were available for the investigation of CF6-6D short-term deterioration. The first source consisted of cruise performance cockpit measurements which are routinely recorded by DACo during each initial engines delivered to the airlines on new DC-10-10 airplanes, and data were analyzed for all engines beginning with ESN 451406. (Major product improvements for engine durability considerations have been introduced into production engines starting with ESN 451406. These items have been retrofitted into revenue service configuration.) The second source consisted of inbound tests of ESN 451507 and one other CF6-6D engine after undergoing airplane/engine checkout flights but prior to entry into revenue service. ESN 451507 was tested inbound specifically as part of this short-term investigation.

The large sample of cruise performance measurements from the initial airplane checkout flight was used to establish the average short-term loss. Moreover, the inbound test results were used to demonstrate that the losses were the assessment of real, nonreversible deterioration; and further, to substantiate the engines was also examined to determine if some amount of the short-term losses were related to the airplane checkout procedure itself. In all instances, deterioration assessments were based on the analysis of individual engines and the results will be presented herein as cruise levels unless otherwise noted.

## 4.1.1 CRUISE PERFORMANCE TRENDS

Cruise cockpit data recorded at stabilized conditions during the first check-out flight of each DC-10-10 aircraft included both engine and airplane flight parameters. Significant engine performance parameters recorded during the cruise setting consisted of fuel flow (WFM), exhaust gas temperature (EGT, fan speed (N1), and core speed (N2), while airplane conditions included altitude, Mach number, and ambient temperature. In order to assess performance deterioration, it was necessary to compare these cruise measurements at altitude with measurements of uninstalled, sea level static performance data obtained during the engine production acceptance testing.

Prior efforts had indicated that a reasonable correlation of EGT measurements was possible between production acceptance test cell levels and intial cruise readings. This correlation was derived by separately establishing the relation of each (test cell and cruise EGT measurements) to a common reference temperature, namely the maximum EGT certified for the CF6-6D. Both test cell and cruise EGT's were independently projected to hot-day (30°C) transient takeoff conditions (in order to yield maximum expected temperatures) and compared to the certified maximum EGT to determine the respective EGT margins. These projections were based on previous experience, including comparisons of actual takeoff data with cruise readings for various engine fan speeds and airplane conditions. Direct comparisons between test cell and cruise EGT margins were then used to identify changes in performance. This correlation between test cell and cruise temperatures was developed primarily because of the historic interest in EGT as an indication of engine health; experience indicates it produces acceptable results.

However, comparisons of fuel flow between test cell and cruise measurements have been very difficult; a suitable correlation procedure has not been accurately developed. Experience has shown that cruise fuel flow levels have been useful primarily to trend changes with time; absolute levels have been less consistent than EGT measurments. Several conditions are known to contribute to the greater inconsistencies of fuel flow compared with those of EGT measurments. First, small differences in core exhaust nozzle area that exist between the individual thrust reversers or fixed nozzles can produce large changes in fuel flow but small changes in EGT. Similarly, changes in thrust as the engine deteriorates produce relatively large changes in fuel flow with smaller changes in EGT.

Based on these considerations, the procedure used to establish short-term fuel burn deterioration was to determine the change in EGT margin between test cell and initial cruise measurments. The corresponding change in fuel flow was then calculated from the delta temperature, using a computer cycle deck, engine derivatives, and component models. This fuel flow calculation procedure was substantiated with inbound test cell performance runs, where deterioration in both fuel flow and EGT can be more properly assessed.

### Analysis of Initial Flight EGT Measurements

Cruise performance data recorded during initial DC-10-10 acceptance chekout flights were analyzed for 90 engines. These include all CF6-6D engines flown on initial DACo checkout flights between January 1974 and February 1978 (engine serial numbers 451406 to 451512). Apparent measurement errors were noted for eight engines; their data were not considered. Analysis of the cockpit data for the remaining 82 engines have been summarized in terms of equivalent margins relative to the CF6-6D certified maximum EGT, as follows:

	Average	Std. Deviation
Production EGT Margin	45.3° C	8.8° C
Checkout Flight EGT Margin	31.2° C	8.9° C
Short-Term EGT Determination	14.1° C	7.4° C

Thus, the deterioration manifested itself as a loss in EGT margin. As will be shown from comparisons of shipped to inbound test cell performance, this loss in EGT margin was real and not an installation effect.

The assessment of deterioration was based on cruise measurements taken during stabilized cruise conditions after the airplane attained high altitude flight for the first time. Prior to these cockpit readings, the engines had undergone a series of ground checks, their first takeoff rotation, operation at altitude, and in-flight systems tests. Some deterioration of engine performance would normally be expected during initial on-wing operation of the engine following the production test cell calibration run; however, neither factory test nor airline experience would support as much short-term deterioration as experienced during airplane acceptance testing.

One checkout sequence not typically encountered during revenue service operation was identified, however, that could contribute significantly to the short term deterioration. This sequence was the acceleration checks from flight idle to maximum climb power, during which the potential exists for a "hot rotor reburst." This was considered very significant since it is known that a hot rotor reburst — that is, rapid acceleration of the engine from low power with the engine still hot from previous operation at high power — can result in thermal closure of engine clearances, notably between high pressure turbine blade tip and shroud. Should a tip rub occur, turbine clearances would be increased, resulting in a loss of performance. Analysis of turbine hardware from ESN 451507 did indicate that significant tip rubs had occurred, thus indicating a potential cause for the observed short-term losses.

Considering further the intial checkout EGT performance for the 82 engines, EGT data were examined to identify any apparent trends. While the confidence level in the first flight average deterioration was high, large engine-to-engine variations were observed. The EGT margins, relative to the maximum EGT level certified for the CF6-6D, are shown for these engines in Figure 4-1 was projected from production acceptance test cell measurements and initial-checkout flight readings. The same data are presented in Figure 4-2 which show loss of EGT margin (acceptance test cell margin minus initial flight cruise margin) as a function of test cell EGT margin. Statistical analysis indicated a tendency whereby the short-term deterioration varied from the average loss of 14°C as a function of the production test cell EGT margin (EGTM). Although not a strong trend, engines with better as-shipped production margin tended to deteriorate more during the airplane checkout, as shown in Figure 4-2. However, the significance of this trend was considered questionable based on the degree to which it reduced the data scatter.




Figure 4-1. EGT Cruise Margin, - First Airplane/Engine Checkout Flight.




Figure 4-2. Short-Term EGTM Cruise Losses - First Checkout Flight.

There are several measures of the quality for the statistical fit. The standard error of estimate (SEE) indicates the deviation about a fitted curve. This parameter is a measure of the data spread and is similar to a standard deviation but is the root-mean-square deviation about the curve fit instead of about the mean of the data. In this case, the SEE associated with the data-fit of EGTM loss was only slightly lower than the standard deviation ( $\sigma$ ) associated with the means of the data (2 SEE = 13.6° C versus  $2\sigma$  = 14.8° C); thus, the derived trend did not significantly reduce the data scatter. Another measure of how well the statistical fit matches the data is provided by the coefficient of determination ( $R^2$ ), which is a numerical measure of the proportion of variation accounted for by the fit (where 100% indicates a perfect fit). The  $R^2$  level indicated that only 17 percent of the variation in the data was accounted for by the linear fit of EGTM loss versus test-cell margin.

Cruise performance levels of the two designated engines, ESN 451487 and 451507, which were tested inbound, will be discussed later.

### Analysis of Multiple DACo Flight Data

The DC-10 checkout procedure typically consists of three to four different flights, including an airline acceptance flight. The question arises whether additional short-term EGT margin losses are typically incurred during these later flights, or for that matter during the remainder of the first flight after the cruise performance measurements have been obtained. To answer this question, the first flight cruise performance was compared with successive DACo flight data and with early revenue service cruise trends for a limited number of engines.

Multiple check flight cruise data were available for 10 of the 82 engines. The EGT losses for these engines during DACo flight tests and early revenue service are presented in Figure 4-3. The average of EGT margin for the seven engines for which cruise data from three DACo flights were obtained, were 15.7°C, 15.6°C, and 15.9°C, respectively - indicating that there was no additional loss during the remainder of the aircraft checkout flights. Likewise, no general trends of increasing EGT losses were evident from early revenue service cruise data for these 10 individual engines.

### Initial Revenue Service Data

Airline trend data were available for 48 engines within about the first 300 hours of revenue service operation, and these EGT levels were compared with the performance levels during the DACo initial aircraft checkout flight. The average EGT increase was about 2°C; these short-term losses of EGT cruise margin are shown versus production test cell EGT margin in Figure 4-4. While there were the expected engine-to-engine variations, one airline recorded average additional early revenue service losses of more than 6°C, which compared with less than a degree average change experienced by two other airlines as follows:




Figure 4-3. EGT Margin Through Early Revenue Service.




Figure 4-4. Early Revenue Service EGT Cruise Losses.

	Number of Engines	Average EGT Change	Standard Deviation
Airline "A"	28	-0.8° c	8.4° C
Airline "B"	15	+6.5° C	8.2° C
Airline "C"	5	-0.6° c	10.1° C

In general, there appears to be little additional short-term deterioration after the initial DACo checkout flight. Some variation was observed between the different airlines; but it is not certain whether these differences are real, due to the different operating procedures (such as dissimilar use of reduced-thrust takeoff), or only indicated, due to variations in cruise data reduction procedures. These differences were not considered to be of major importance and did not warrant further investigations with the available information.

## Initial Loss For Spare Engines

In an effort to verify the belief that significant short-term losses occur as a result of a specific, nonstandard revenue service operation during airplane checkout, data were analyzed for a limited number of new engines which entered revenue service without undergoing airplane checkout. These were 11 new CF6-6D spare engines (ESN 451406 and above) which was delivered directly to the airlines from the factory, thus bypassing the DACo airplane checkout.

The cruise EGT levels during early airline service were examined for the 11 new spare engines. The average short-term deterioration of these spare engines was found to be 9° C ( $\sigma$  = 6° C) after an average of 351 hours of airline operation. This compared with an average 16° C loss of EGT margin during early revenue service as determined for the 48 engines which underwent airplane checkout (shown in Figure 4-4). The average production test cell EGT margin for the eleven spare engines was 43° C while the early cruise EGT margin was 34° C, versus 44° C test cell EGT margin and 28° C early revenue service cruise EGT margin for the 48 engine sample. Thus 7° C additional deterioration was observed for engines undergoing airplane checkout.

The spare engine EGT deterioration of 9°C was about one-half of that recorded for the 48 engines which had undergone airplane checkout at approximately the same number of revenue service hours. While the spare engine sample size was small, the lower observed short-term EGT deterioration for these engines does support the belief that nonrepresentative engine operation during the airplane checkout results in a significant amount of short-term loss.

# Assessment of Fuel Burn From Cruise Data

As previously noted, the measured loss in cruise EGT margin was used to predict the short-term fuel burn increase. A component deterioration model was utilized to assign the overall loss in EGT margin to the various engine components (or modules). Engine derivatives were available for the individual modules that equate unique fuel burn effect for a given change in EGT margin. The fuel burn equivalent to the total measured EGT margin loss were merely the sum of the fuel burn deltas calculated for the individual components. Using this method, the average loss of 14°C in cruise EGT margin for the 82 engines was equivalent to a cruise fuel burn increase of 0.9 percent.

These comparative fuel burn and EGT increases were substantiated based on inbound test cell recalibrations of ESN 451487 and 451507 prior to revenue service, as will be shown.

# 4.1.2 INBOUND TEST-CELL RESULTS

Few inbound performance calibrations have been conducted for CF6-6D engines which had undergone an aircraft manufacturer's airplane checkout procedure but had not entered revenue service. The available test cell data were used to demonstrate that short-term deterioration was both real and nonreversible. As noted previously, cruise EGT data were relied upon to establish the magnitude of the short-term loss because of the limited nature of the test-cell data. However, engine performance deterioration assessments based on available test cell calibrations were used to verify the procedure used to calculate cruise fuel-burn increases from cruise EGT deterioration assessments.

Inbound test cell performance calibrations for short-term deteriorated engines were available for two engines. The first, ESN 451487, had been removed to be investigated for a vibration complaint and was tested at Ontario, California (ASO/O) during 1975. The second, ESN 451507, was removed specifically for this investigation and was also tested at the General Electric facilities at Ontario, California (ASO/O).

## ESN 451487 Inbound Test

Prior to its inbound test cell calibration, ESN 451487 was installed on two different DC-10-10 airplanes during their respective initial checkout flights. This engine was initially flown on the first flight of fuselage number (F/N) 209 during which it lost 14° C in EGT margin, matching the average cruise loss for the 82 CF6-6D engines. The engine was removed after this first flight and installed on F/N 210 for the first checkout flight of that aircraft. During this flight (the second flight of the engine), an additional loss of 5° C cruise EGT margin was noted, making the total 19° C since the production acceptance test. The EGT deterioration derived from this second flight is shown relative to the short-term performance of the other 81 engines in Figure 4-2.

While the engine was removed after the second flight to investigate a vibration complaint, a performance calibration test was conducted. The short-term deterioration assessment was based on a comparison between the inbound test cell results and the factory performance. These test cell data indicated a sea level static sfc increase of 2.2 percent at constant thrust for this engine as well as a 21° C EGT and 1.8 percent fuel flow increase at constant fan speed relative to the factory performance. These data thus verified that the short-term losses incurred prior to introduction to revenue service were both real and nonreversible.

These test cell results for ESN 451407 were compared to a short-term sea level static deterioration model as shown in Table 4-I. Further, the test cell deterioration assessment of ESN 451487 was also projected to cruise conditions and compared to a model of installed cruise short-term deterioration. Both the test cell and projected cruise performance were higher than those assessed for an average engine. However, the cruise EGT loss determined from checkout flight measurements for this engine had likewise indicated that the engine deteriorated more than average at the time of its second flight. In fact, the cruise EGT loss projected from the measured test cell data (analytically derived as 80 percent of the sea level static EGT loss) was within 2°C of the EGT deterioration assessed from the cruise checkout results. This comparison, also shown in Table 4-I, indicated that the calculation and comparison procedure used to equate cruise and test cell EGT levels was reasonable.

Table 4-I. Short-Term Performance Deterioration Assessment Inbound Test of ESN 451487.

	SLS Test Cell		Installed Cruise		
Overall Performance (Delta From New)	Measured	Analytical Model	Projected From SLS	Analytical Model	Airplane Checkout
Δ SFC At FN	2.2%	1.3%	1.5%	0.9%	
Δ EGT At N1	21° C	18° c	17° C	14° C	19° C
Δ WFM At N1	1.3%	1.5%	1.6%	1.3%	

### ESN 451507 Inbound Test

As noted previously, the activities to quantify short-term performance deterioration included special testing of ESN 451507. This engine had completed the entire DC-10-10 aircraft/engine checkout at DACo on F/N 250 before being

removed for the test cell performance calibration. Performance testing of this engine included the standard factory production acceptance test calibration as well as the special inbound test at the Ontario, California (ASO/O) facilities. The inbound performance calibration test following the DACo acceptance flights consisted of three separate runs: two calibrations with the engine in the as-received condition, and the third following cleaning of the Stage I fan blades. (No measureable difference was observed.) The instrumentation was identical to that used at Evendale. The overall performance levels from these tests are summarized in Table 4-11. These data, recorded at both takeoff and maximum continuous power settings, were used to determine the short-term deterioration of this engine.

Unfortunately, an undetected thrust measurement error during the inbound caliration made changes in thrust levels and thus the resultant sfc values unreliable. However, test cell measured changes in fuel flow along with ECT at constant fan speed were available to assess deterioration. The measured deterioration based on the comparison of the inbound test cell data and the production acceptance performance was 15° C ECT and 1.6 percent fuel flow at constant fan speed, as shown in Table 4-III. Analytically adjusted to cruise conditions, the losses were 12° C ECT and 1.4 percent fuel flow. It can be observed that the sea level test cell data as well as the projected cruise losses for this engine matched the derived deterioration model. These projected cruise ECT and WFM increases thus support the sfc deterioration predicted by the model. While the cruise ECT loss measured for ESN 451507 during the initial airplane checkout flight (22° C) appeared high (Figure 4-2), this level dropped to 17° C during the initial revenue service - a magnitude which was more in line with the expected loss.

These inbound test results again demonstrated that short-term performance deterioration was both real and nonreversible. Further, the similarity between the measured performance loss for ESN 451507 and the sea level static deterioration model indicated that the observed short-term deterioration of this particular engine should be representative of typical CF6-6D engines after airplane/engine checkout procedures; that is, prior to entry inco revenue service. As such, the observed hardware conditions of ESN 451507 should likewise be representative and can be used to quantify short-term parts deterioration of the CF6-6D engine model.

### 4.1.3 SUMMARY OF PERFORMANCE DATA

Analysis of cruise performance data indicates that significant losses do occur for the CF6-6D model engine during the first checkout flight at DACo, but that thereafter, the performance generally remains stable through at least the first 300 hours of revenue service operation. Losses which occur during aircraft checkout prior to revenue service are therefore representative of short-term deterioration. Further, test cell performance results demonstrated that these losses are both real and nonreversible.

Table 4-11. ESN 451507 Test Cell Results.

Run	Power Setting	Hot Day EGT	SFC Margin	WFK @ N1K (PPM)	Thrust Margin
Evendale Outbound Average	T/O M/C	858 822 858/ 822	0.1 0.1 0.1	14625 13905 14625/ 13905	1.6 1.1 1.4
ASO/O Inbound	T/O T/O M/C M/C T/O T/O M/C M/C	874 872 837 836 873 873 838 838	-2.5* -2.6* -2.5* -3.0* -2.3* -2.6* -2.5*	14843 14841 14116 14092 14861 14811 14169 14088	0.8* 0.6* 0.2* 0.2* 0.4* 0./* 0.5*
ASO/O After Fan Cleaning Average	T/O T/O M/C M/C	873 872 836 838 873/ 837	-2.9* -2.5* -2.8* -2.6* -2.6*	14874 14957 14193 14172 14865/ 14138	0.5* 1.4* 0.5* 0.6* 0.5*
Deterioration		+15° c		+1.6%	• · · · · •

Table 4-III. Short-Term Performance Deterioration Assessment Inbound Test of FSN 451507.

	SLS T	est Cell	Ins	talled Cruis	ie	
Overall Performance (Delta From New)	Measured	Analytical Model		Analytical Model	Airplane	Initial Rev. Serv.
A SFC at FN	***	1.32		0.92		
Δ EGT at N1	15° c	18° C	12° c	14° c	22 ° C	17° C
A JFM at N1	1.62	1.5%	1.42	1.3%		

Based on the average of 82 engines, the magnitude of short-term deterioration was analytically established as 0.9 percent in cruise fuel burn. The available cruise and inbound test cell results were found to be consistent. Also, results from the analysis of new spare engines support the belief that a significant amount of the short-term loss is due to nontypical engine operation during the airplane checkout, such as a "hot rotor reburst."

It was also shown that the short-term performance loss for program ESN 451507 was representative of that established for the CF6-6D model engine; so it logically follows that the hardware inspection results should also be considered to represent the CF6-6D fleet.

# 4.2 HARDWARE INSPECTION RESULTS

The second major part of the short-term studies was to obtain and analyze hardware inspection data in order to isolate the sources or causes of the performance deterioration.

The inspection of ESN 451507 was conducted at the General Electric facility located in Ontario, California. All engine modules were inspected, and attention was directed toward the three major sources of deterioration: clearances, airfoil quality, and leakages. These inspection results, in conjunction with influence coefficients, were used to isolate the deterioration mechanisms and assign a fuel burn deterioration to each source. Influence coefficients are empirically or analytically derived factors which equate a change in a hardware condition with a change in component performance.

The CF6-6D engine is of modular construction, such that the major components of the engine can be independently repaired and modified with complete interchangeability with other modules. Hardware inspections data are generally summarized in the same manner, i.e., by individual sections of the engine. Since the CF6-6D is a dual-spool, turbofan model engine, it is logical to and high pressure systems. Accordingly, the hardware data have been summarized into four major categories: fan, high pressure (HP) compressor, high section of the engine showing these major divisions. Note that the following paragraphs only summarized the hardware findings and that detailed data are

## 4.2.1 FAN SECTION

Hardware inspections included measurement of Stage l fan blade-to-shroud clearance, leading edge shape (profile) of Stage l fan blades, and determination of surface finish change for the various airfoils.

There was no measured short-term loss associated with the fan (and booster) section. A back-to-back test cell run was completed which indicated no change

in performance after cleaning the fan blades. Six fan blades were removed, and leading edge inspection by means of comparison with a glassine master indicated no change in contour.

# 4.2.2 HIGH-PRESSURE COMPRESSOR SECTION

The high pressure rotor and stator subassemblies were removed from the engine for measurements. Ten blades per stage (Stages 3 through 16) and ten vanes per stage (Stages 7 through 0GV) were removed to obtain representative surface finish data. The flowpath coating was inspected for spalling and evidence of rubs to ascertain potential clearance changes. The radial CDP rotating-to-stationary-seal clearance was determined in order to isolate any potential internal leakage (parasitic) effects.

Rubs were noted on the stator casing rub coat from compressor blade tips, particularly in the upper half in the vicinity of 12 o'clock. These local rubs were noted in most stages, ranging from a kiss (no depth) up to 0.008 inch. Minor spalling of the casing rub coat was also noted. The performance effect for the estimated clearance change is 0.05 percent in compressor efficiency – equivalent to 0.03 percent in cruise fuel consumption. All other measured conditions were within new engine tolerances.

# 4.2.3 HIGH-PRESSURE TURBINE SECTION

Detailed measurements to determine the change in blade tip-to-shroud clearance were accomplished. Selected Stage 1 and 2 blades and vanes were subjected to surface determination, and the static parts (shrouds, supports, and vanes) were inspected for distortion that could result in an internal leakage (parasitic) loss.

Degradation of the high pressure turbine is the dominant factor in short-term deterioration. Over 90 percent of the assessed cruise sfc loss for ESN 451507 was attributed to this section of the engine. Turbine blade rubs had occurred on both stages, resulting in shortening of the Stage 1 and 2 blade tips by 0.021 inch and 0.011 inch, respectively. This was almost all of the turbine degradation and is equivalent to 0.71 percent in increased cruise fuel consumption. Based on this result, notches were incorporated into the tips of inspection (which does not require engine disassembly), obtained on these engines (see Appendix B.3.3) after completion of aircraft acceptance testing, validated the results noted for ESN 451507 and verified that blade tip rubs are the dominant mode of short-term deterioration.

Surface finish measurements of all airfoils indicated a slight roughness of the Stage 1 nozzle vanes, resulting in a 0.02 percent increase in cruise sfc. Measurement of turbine seals and Stage 1 vanes for distortion indicated no parasitic loss, and the measured Stage 1 nozzle vane throat area (A4) was nominal.

### 4.2.4 LOW-PRESSURE TURBINE SECTION

Inspections to assess deterioration mechanisms included determination of blade tip-to-shroud and interstage seal clearances. In addition, representative surface finish data were obtained for each airfuil stage by measurement of six randomly selected parts.

Two areas of minor deterioration were assessed in the low pressure turbine section, including surface finish change—for the Stage 1 vane and interstage seal radial clearance. The Stage 1 vane surface finish was 80  $\mu$  in. (AA) compared with new engine requirement of 63  $\mu$  in. The rotating interstage seal teeth were found to be from 3 to 10 mils smaller than new-engine minimum, which calculated to be a 0.04 percent increase in cruise sfc. The vane surface finish effect was negligible.

## 4.2.5 SUMMARY OF HARDWARE INSPECTION DATA

The short-term losses assessed from hardware inspection data for the various engine section are summarized in Table 4-IV. As shown, losses in the high-pressure turbine are the major source of, and blade tip-to-shroud rubs the dominant factor in, short-term deterioration. The calculation of fuel consumption effects carried to the second decimal point is not intended to convey that the Contractor believes this is the level of accuracy. Rather, the loss mechanisms that were isolated for the compressor and turbine sections have a minor influence on fuel consumption and the measured deltas were also very small. Realistically, the only condition isolated that is a significant contributor to short-term deterioration is Stage 1 and 2 high pressure turbine blade tip rubs.

### 4.3 COMPARISON AND DETERIORATION ASSESSMENT

It can be concluded from these data that ESN 451507 is typical of the average short-term deterioration for the CF6-6D model engine, since measured cruise performance loss and the dominant deterioration source agree well with similar data from other CF6-6D engines. However, the short-term loss assessed from hardware inspection data taken from ESN 451507 must be compared with the total measured loss based on performance data before the hardware results can be established to be reasonable.

The performance and analytical teardown hardware data indicated that the total fuel consumption increase derived from the two independent methods for ESN 451507 was 0.8 percent based on the hardware inspections and 0.9 percent based on the cruise performance data. As noted, those independent studies produced results within 0.1 percent of each other, and the hardware data isolated over 88 percent of the loss expected from cruise performance data. This comparison is considered excellent, and substantiates that the hardware assessments are a realistic representation of short-term deterioration.

Table 4-IV. Analytical Assessment of ESN 451507 (Sea Level Takeoff).

		Assessment	
	<u>n</u>	EGT	SFC
HP Compressor	0.05%	1° F	0.04%
Airfoil Surface Finish Stator Land Rubs	0.05		
HP Turbine	0.95%	24° F	1.05%
Stage 1 Nozzle Surface Finish	0.03		
Blade Surface Finish	0.00		
Stage 1 Blade Tip Clearance (+ 21 mils)	0.70		
Stage 2 Blade Tip Clearance (+ 11 mils)	0.22		
Parasitics			
All Seals Nominal	0.00%	0	0.00%
LP Systems	0.07%	0	0.05%
I/S Seal Clearance	0.07		
Stage 2 (-3 mil)	0.02		
Stage 3 (-3 mil)	0.01		
Stage 4 (-8 mil)	0.02		
Stage 5 (-10 mil)	0.02		
Total		25° F	1.14%

Therefore, based on (1) these test results, which indicated that ESN \(^{51507} performance and hardware results were typical of those expected for other CF6-6D model engines, and (2) the excellent agreement between cruise performance data for ESN 451507 and the short-term deterioration independently assessed from hardware inspection, it is concluded that the short-term deterioration for the CF6-6D model engine is 0.9 percent in cruise fuel burn and that the major source of this loss is high-pressure turbine Stage 1 and 2 blade tip-to-shroud rubs.

## 5.0 RECOMMENDATIONS

Three separate courses of action have been initiated to eliminate or alleviate the short-term deterioration losses. It was noted that each engine is decelerated from high power to flight idle and then subjected to a rapid acceleration during aircraft climb prior to recording stabilized performance data during the aricraft acceptance flights (see Section 4.1.1). It is known that this type of thermal transient (termed "hot rotor reburst") can cause HP turbine blade tip rubs due to different thermal rates for the rotating and stationary structures. The aircraft acceptance flight test procedure is being reviewed by DACo/GE in an effort to eliminate this operational requirement which is untypical of, but permissible for, revenue service operation.

The comparison Performance Improvement Program, also sponsored by NASA-Lewis, is developing generic items for HP turbines. Both of these - the Roundness Control Program, which is developing improved and more efficiently cooled static structures, and the HPT Active Clearance Control, which will meter cooling air based on thermal and operational considerations rather than by fixed orifices - can help to eliminate these short-term losses.

A third approach being developed by the Contractor (General Electric) is to utilize an abrasive coating on the high-pressure turbine blade tips. This coating is to provide the mechanism to "machine" the shroud during adverse thermal conditions, thus producing local removal of shroud material rather than shortening of all the blades. Since studies to date have indicated that the rubs are very local, this approach eliminates the performance effect from the rubs, and the total shroud material removal and resultant clearance increase will be minimal.

### APPENDIX A

## TEST PLAN/WORKSCOPE

This appendix presents the actual test plan and workscope used to conduct the engine test on engine serial number 451507 and to conduct the engine disasembly and parts inspections.

#### A.1 INBOUND TEST

The following sequence of testing is required for the CF6-6D short-term deterioration engine. The testing will be conducted in the ASO-Ontario CF6 test cell with a lightweight bellmouth and the standard CF6-6 Acceptance Test Cowling configuration.

- Install engine in the CF6 test cell and set up per CF6 Shop Manual, 72-00-00 Testing.
- Check variable stator vanes cold rig, but do not adjust unless VSV tracks outside of the open limit by more than one degree during engine operation. No adjustment is to be made without the concurrence of ASE Engineering.
- Install instrumentation as defined by the Instrumentation Plan for the short-term deterioration engine (Section 3.3).
- 4. Conduct the following performance test:
  - a. Perform normal prefire checks including a leak check.
  - b. Start engine and stabilize for five minutes at ground idle.
  - c. Set the following two steady-state data points and take full data readings after four minute stabilization:

Power Setting	Corrected Fan Speed
50%	76.42% (2623 rpm)
75%	90.11% (3093 rpm)

d. Slow decel to ground idle, and analyze the two points to determine if the engine can be safely operated to takeoff power without exceeding any limits (N2, EGT, VSV). Also ascertain that all instrumentation, including the recorder, is functioning properly.

e. Set the following steady-state data points and take two back-to-back data readings after four minutes stabilization. The engine should be operated at maximum continuous power for a minimum of six minutes prior to setting the following points. Take one data reading after six minutes.

Power Setting	Corrected Fan Speed
Takeoff Maximum Continuous Maximum Cruise 75%	100.30% (3443 rpm) 98.70% (3388 rpm) 95.85% (3290 rpm) 90.11% (3093 rpm)

f. Shut down for a minimum of 30 minutes and then repeat steps b and e.

## 5. SPECIAL INSTRUCTIONS

The following special instructions apply for testing the CF6-6D short-term-deterioration engine:

- a. Obtain a fuel LHV sample between the dual-performance power calibrations. A bomb calorimeter will be used to obtain the LHV.
- b. No performance data are to be taken when visible precipitation exists or when the relative humidity exceeds 85 percent.
- c. Pressure transducers, fuel meters, and the thrust-load cell must be within FAA calibration limits and the calibrations traceable to the National Bureau of Standards.

# A.2 ANALYTICAL TEARDOWN, REFURBISHMENT, AND REASSEMBLY

### General

Engine disassembly and analytical inspection requirements are discussed in the following sections as sequentially related to the Short-Term Deterioration test objectives. In all cases, engine disassembly, inspections, data recording, and engine rebuild procedures shall be in accordance with the applicable sections of the CF6-6 Shop Manual, GEK 9266. Inspection forms for each of the individual requirements will be furnished to ASO by Evendale Engineering.

The following instructions may be modified as required by the Evendale onsite observer. Any observed hardware distress, in addition to that described in this detailed test plan, will be investigated relative to its effect on engine performance and sfc deterioration. Inspection results are documented in Appendix B of this report. This includes a tabulation and analysis of the dimensional and surface finish measurements. In addition, photographs (detailed and overall) of the deteriorated parts are presented to emphasize the written description. Sketches are included where necessary and where photographs are unavailable.

#### LPT Inpections

Remove and disassemble the LPT module sufficiently to perform the following inspection checks:

### Turbine Midframe (Reference 72-54-00)

- Measure and record eight-point-diameter check (dia. AM) of the LPT pressure balance seal.
- Measure and record outside diameter of forward mounting flange (dia. U) at twelve o'clock; take runnout relative to No. 5 bearing, at twelve equally spaced locations starting at twelve o'clock.

### Stage 1 LPT Nozzles (Reference 72-55-00)

- Remove four Stage 1 LPT nozzle segments, and measure the surface finish of the vane airfoils at each end of each segment at the following locations:
  - Suction (Convex) Side

Measure at pitch line and 0.5 inch below the outer platform 0.45/0.50 inch from the leading edge (LE) and 0.45/0.50 inch from the trailing edge (TE).

• Pressure (Concave) Side

Measure at pitch line 0.45/0.50 inch from the LE and 0.45/0.50 inch from the TE.

2. After completion of surface finish measurements, reinstall the nozzle segments per the Shop Manual (SM).

### Low Pressure Turbine Stator Assembly (Reference 72-56-00)

- 1. Take Castone impressions of shrouds and interstage seals as follows:
  - Take impressions at maximum rub areas of each stage for each casing half. Appropriately identify each castone. Note approximate clock position of each.

- Each impression should cover the full axial length of the seal (i.e., both rubbed and unrubbed surfaces).
- Use care not to damage the impressions.
- Per the Shop Manual (as required), remove the following from each casing half: one nozzle segment each from Stages 2 and 3, three nozzle segments each from Stages 4 and 5. Position-mark all hardware prior to removal.
  - Measure surface finish of the vane airfoils in the same manner as defined for Stage 1. (Reference "Stage 1 LPT Nozzles.").

Note: More parts may be required to be checked, depending on the condition of the hardware.

 After surface finish checks are acceptable, rebuild the LPTS assembly per the SM.

# Low Pressure Turbine Rotor Assembly (Reference 72-57-00)

- Set up the rotor in a lathe bed (or equivalent) on the No. 6 and 7
  journals. Take and record the maximum radius and FIR or each of
  the following:
  - Blade tip shroud seal serrations, forward and aft, each stage.
  - Air seal teeth, forward and aft, each stage.
  - Pressure balance seal, each tooth.
- 2. Measure and record the airfoil surface finish of six blades per stage for Stages 1, 3, 4, and 5. (Remove only the number of blade retainers required to remove the six blades per stage; position—mark blades for reinstallation.) Measurements are to be taken at the same airfoil locations defined for the Stage 1 LPT nozzles. (Reference "Stage 1 LPT Nozzles.")
- When surface finish checks are acceptable, reinstall blades per position marks.

## Reassembly

After all inspection checks are completed, rebuild the LPT module per the SM.

### Fan Section Inspections

No disassembly is planned in the fan section, other than removal of the spinner to install the shimming tool under the blades (Stage 1). Tip clearances are to be taken prior to removal of the LPT engine maintenance unit (EMU).

### Stage 1 Fan Blade Inspection and Cleaning (Reference 72-20-00)

- Record the Stage 1 blade leading edge condition and surface condition (i.e. dirt, nicks, etc.).
- Record the condition of the Stage 1 and 2 shrouds and vanes.
- Note any unique conditions observed in the fan section.
- Thoroughly clean the Stage 1 blades using a soft cloth and solvent MEK for light deposits. Remove heavy deposits using Scotch Brite Pads No. 7447. (Do not remove the blades for cleaning.)
- Measure and record Stage 1 blade tip minimum, maximum, and average clearances at locations E12 and E13 per SM Section 72-20-01.

### Core Engine Inspections

Disassemble the engine as necessary to obtain the required data on the noted EMU's. Disassembly will be performed per the following sequence of events:

- Note 1: Photographs (detailed and overall) will be taken of each subassembly prior to its disassembly, with particular emphasis on deteriorated parts, or any unique condition.
- Note 2: Prior to removal of the Stage 1 HPTN assembly, obtain drop checks from the aft face of the CRF outer flange to the aft face of Stage 1 HPTN vane outer platforms in eight equally spaced locations. At each location, obtain drops to both ends of each segment (16 individual readings).
- Note 3: Record inspection requirements on sheets supplied by the Evendale engineer.
  - Split the core engine away from the fan module and route the core to Hanger No. 2.
  - Position-mark and remove the Stage 2 HPTR blades. Preserve the Stage 2 blade retainer seal wire for engineering inspection.
  - Remove the Stage ? HPTN assembly.

- Remove the HPT rotor. Reinstall the Stage 2 blades per position marks and route the rotor to the rotor area.
- Comply with Note 2 above (drop checks), then remove the Stage 1 HPTN assembly.
- Position-mark, then remove the 4B pressure balance seal (mininozzle.
- Remove the CRF.
- Remove the HPCS cases.
- Send the HPC rotor to the rotor area.

### High Pressure Turbine Rotor (Reference 72-53-00)

- Install the rotor into the lathe bed. Shim the blades per the SM, and mesure each Stage 1 and 2 blade tip at 0.1 inch from the leading and trailing edges as follows:
  - Measure and record the radius of Blade No. 1, 0.1 inch from the LE of each stage.
  - Install a dial indicator and zero on the measured blade, each stage.
  - Record runouts of each blade, for each stage, in mils (+ = long blade, = shorter blade).
- Measure and record all forward shaft seal teeth (i.e., Gl through G6 and H1 through H6) as follows:
  - Arbitrarily select and mark a position on each seal tooth as 12 o'clock.
  - Record the diameter of each tooth at this marking.
  - Install a dial indicator and zero at each of these marks.
  - Record runouts at twelve equally spaced positions, for each tooth.
- Measure and record all thermal shield seal teeth (VI through V4) in the same manner as described for the forward shaft seal teeth: i.e., a diameter versus twelve-point runout for each tooth.
- Inspect the Stage I blade retainer sea! wire. (Depending on the wire's condition, the inspector may wish to return seal wires to Evendale.)

- Position-mark and remove six blades from each stage, and measure the surface finish at the pitch line:
  - On the suction (convex) side at 10, 50, and 90 percent of the blade chord.
  - On the pressure (concave) side at 10, 50, and 90 percent of the blade chord.
- Reinstall blades, per position marks.
- Measure and record the depths of the notches on the designated blades. (Four blades per stage were notched during the initial assembly of the engine in order to estimate the amount of wear caused by rubbing; see Figure A-1.)
- Record the overall general condition of the blades, taking into account burns, cracks, missing pieces, surface appearance, etc.

### Stage 2 HPTN Assembly (Reference 72-52-00)

- Restrain the Stage 2 HPTN assembly in the grind fixture, center assembly. Measure the Stage 1 and 2 shrouds at each of two axial locations, for each stage (1/2 inch from LE and 1/4 inch from TE) as follows:
  - Measure the diameter between twelve and six o'clock at each axial location (four places).
  - Install a dial indicator and zero at twelve o'clock at each axial location.
  - Record runouts at the ends and the center of each shroud, at each location.
- Record the depth and width of the interstage seal grooves starting at twelve o'clock, and obtain four equally spaced readings for each seal land.
- Record the drop dimension from the forward face of the aft flange of the support to the forward face of the lugs that support the Stage I vane outer hook (Dim. K) at 16 equally spaced locations starting at twelve o'clock and working CW, ALF. Also, note the condition of the flange that supports the Stage I vanes, paying attention to areas where centact has/has not occurred.
- Record the average thickness of the shim located between the Stage 2 support aft flange and the CRF.

Blade	Not	ch De	pth	(mils)
No.	_ A	_ B	<u> </u>	
1	10	20	30	
28	10	20	30	
14	15	35	60	
41	15	35	60	

Blade	Not	ch Depth	(mils)
No.	D	E	
1	10	20	
30	10	20	
16	20	50	
45	20	50	




Figure A-1. Notched HP Turbine Blades.

- Record the overall general assembly condition, noting:
  - The condition of the vanes.
  - The number of cooling holes plugged in the support (and the approximate percentage of shroud holes plugged if disassembled).
  - The condition of the Stage 1 and 2 shroud filler material with respect to cracks, oxidation, and missing pieces. (Estimate the average clearance due to erosion/oxidation).

# Stage 1 High Pressure Nozzle Assembly (Reference 72-51-00)

- Position-mark the vanes per the Shop Manual, using a heavy felt-tip marker.
- Measure and record the area of each vane and total (A4).
- Measure the gap between outer platforms on adjacent vanes at 16 equally spaced locations. Measurements are to be taken at the aft end of the vanes.
- Record the overall general condition of the vanes as related to burned areas, any missing pieces, surface condition, etc.
- Disassemble, as required, to remove six vane segments. Measure surface finish on six vanes at the pitch line on the concave and convex sides at 10, 50, and 90 percent chord.

# Compressor Rear Frame Assembly (Reference 72-34-00)

- Position-mark and remove the CDP seal.
- Measure and record eight equally spaced diameters for <u>each land</u> of each of the following seals:
  - CDP seal (Forward and Aft)
  - No. 4B pressure balance seal (mininozzle)
- Reinstall the CDP seal and mininozyle per match marks.

# High Pressure Compressor Rotor (Reference 72-31-00)

• Install the rotor in the R/O fixture. Measure and record the diameter of each seal cooth of the CDP seal at twelve o'clock (arbitraily chosen), together with a twelve-point runout for each tooth, relative to the twelve o'clock position.

- Record the overall general appearance, specifically noting:
  - The depth and location of any spool rubs and the condition of the spool coating in terms of spalling.
  - The condition of the airfoils, taking into account aluminum deposits, tip curl, and erosion.
- Remove ten blades per stage, Stages 7 through 16. Measure and record the surface finish at 15, 50, and 85 percent of blade height at:
  - 10-15 percent of the chord from the LE on the suction side.
  - 10-15 percent of the chord from the TE on the pressure side.

Note: Position-mark the blades prior to removal.

Reinstall the blades into the rotor per position marks.

# HP Compressor Stators, Forward and Rear (References 72-32-00 and 72-33-00)

- Record the overall general appearance, specifically noting:
  - The condition of the VSV bushings by stage (i.e., loose, metalto-metal, pieces missing, etc.)
  - The condition and location of stator land rubs (depth and length per stage).
  - The amount/degree of aluminum coating spalling.
  - The condition of the airfoils, taking into account aluminum deposits, tip, curl, and erosion.
- Position-mark and remove a quantity of ten vanes per stage (five each from each side of lower case), for Stages 7 through the OGV's.
   Record the surface finish at the same locations defined for the compressor blades.
- Reinstall the vanes per position marks.

# A.3 ENGINE REASSEMBLY AND TESTING

At the completion and acceptance of all the inspection checks, reassemble the engine per the Shop Manual, using all of the original hardware, except where non-serviceable.

Test the engine per the CF6 Shop Manual and return it to American Airlines.

### APPENDIX B

# HARDWARE INSPECTION DATA

In accordance with the Test Plan presented in Appendix A of this report, ESN 451507 was subjected to a disassembly and detailed inspection of engine modules and component parts. Included were dimensional inspection checks of seals, blades, shrouds, etc. (to measure such distortion and clearance changes), and airfoil surface finish measurements on a sampling of blades and vanes throughout the engine. Overall, the engine was in excellent condition, with heavy that produced a significant loss in engine performance.

The detailed hardware inspection results are presented in this Section of the report. These observations are specifically those that are performance related; they do not imply that no other discrepancies were noted. The analytical assessment of these results in regard to performance loss is discussed in Section 4.0.

## B.1 FAN SECTION

An overall visual inspection of the fan section revealed that it was in excellent condition with no significant discrepancies.

## B.1.1 FAN ROTOR

The Stage 1 fan blades, as received, were only slightly dirty, with no nicks, dents, or other evidence of FOD. Six Stage 1 fan blades were removed and the leading edges were inspected on the glassine contour master. All had similar profiles, and were within the acceptance requirements.

A visual inspection of the Stage 2 blades likewise revealed no discrepancies.

## B.1.2 FAN STATOR

The fan stator case assembly had the open-faced aluminum honeycomb Stage 1 fan shroud material, with no notable discrepancies. Figure B-1 is a photograph of the fan section, with a view of the shroud. The Stage 2 shroud was of the same material as Stage 1 and was also in excellent condition.

# B.1.3 STAGE 1 FAN BLADE TIP CLEARANCE

Stage 1 fan blade tip clearances are regulated at the E12 and E13 locations of the Stage 1 fan shroud. E12 is located 7.8 inches aft of the forward

flange of the fan stator case, while El3 is located 10.6 inches from the forward flange, as shown in Figure B-2. The average tip clearance at each of the two locations is calculated by adding the average rotor runout to the average case clearance of the longest blade.

Average rotor runout is determined at each location by measuring the clearance between each of the 38 blade tips and the shroud at the six o'clock position. The smallest clearance (belonging of course to the longest blade) is then subtracted from the average of the measured clearances at each location. Using the established long blade, clearances to the shroud are measured at twelve equally spaced positions, from the sum of which its average case clearance is calculated.

The Stage I fan blade tip clearances for ESN 451507, as calculated from the blade data (Tables B-I and B-II) and the shroud data (Table B-IJI), are presented in Table B-IV. The results reveal very little differences from the Shop Manual requirements.



Figure B-1. Fan Section.

ORIGIN PAGE IN QUALITY




Figure B-2. Locations of Stage 1 Fan Blade Tip Clearance Measurements.

Table B-I. Stage 1 Fan Blade Tip Clearances at El2 (Rotor Runout).

Blade No.	Clearance	Blade No.	Clearance
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19	0.154 0.165 0.165 0.165 0.155 0.154 0.159 0.159 0.170 0.176 0.155 0.162 0.165 0.170 0.164 0.175 0.175 0.175 0.170 0.170	20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38	0.163 0.162 0.171 0.170 0.171 0.170 0.166 0.170 0.175 0.180 0.165 0.175 0.164 0.173 0.162 0.165 0.165 0.173

Average Clearance = 0.166 in. Smallest Clearance = 0.154 in. (Blade No. 6)

Average Rotor Runout = 0.012 inch

Table B-II. Stage 1 Ban Blade Tip Clearances at E13 (Rotor Runout).

Blade No.	Clearance	Blade No.	Clearance
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17	0.170 0.160 0.181 0.193 0.170 0.170 0.181 0.176 0.194 0.170 0.173 0.186 0.180 0.170 0.184 0.176	20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36	0.175 0.173 0.181 0.175 0.187 0.176 0.166 0.182 0.182 0.176 0.169 0.167 0.169 0.167 0.162 0.177 0.177
18 19	0.169 0.167	37 38	0.175 0.170

Average Clearance = 0.175 in.

Smallest Clearance = 0.160 in. (Blade No. 2)

Average Rotor Runout = 0.015 in.

Table B-III. Stage 1 Fan Shroud/Long Blade Minimum Clearance Measurements.

Position No.	Clearances at E12	Clearances at El3
12 O'Clock 1 O'Clock 2 O'Clock 3 O'Clock 4 O'Clock 5 O'Clock 6 O'Clock 7 O'Clock 8 O'Clock 9 O'Clock 10 O'Clock	0.159 0.149 0.159 0.164 0.166 0.167 0.154 0.159 0.150 0.176 0.176	0.155 0.142 0.153 0.165 0.161 0.164 0.160 0.152 0.143 0.173 0.170 0.158
Average	0.162	0.158

Table B-IV. Stage 1 Fan Blade Tip Clearances.

	E12	E13	Shop Manual			
Minimum	0.149	0.142	0.145 minimum			
Average	0.174	0.173	0.171 maximim			

## B.2 HIGH PRESSURE COMPRESSOR SECTION

# B.2.1 HP COMPRESSOR ROTOR ASSEMBLY

#### General

The high-pressure compressor rotor (HPCR) was in excellent condition. There were no vane-to-spool rubs, nor any other discrepancies observed in the rotor land coating. Some of the blade tips were shiny, a condition caused by insignificant rubs. As a result of these rubs, there was a trivial amount of aluminum rub coating splatter on the airfoils in Stages 12 through 16. Figure B-3, which shows the rotor set-up in the fixture for the CDP seal teeth runout measurements, shows this condition.

## HPCR Airfoil Surface Finish

Ten blades per stage (Stages 3 through 16) were removed from the rotor for measurement of the airfoil surface finish. However, during the checks, when it was noted that the readings being taken were approximately in new-part condition (16  $\mu$  inch maximum), a smaller sample from each stage was actually measured. The results are presented in Table B-V.

Measurements were taken at 10/15 percent chord distance from the leading and trailing edges at 15, 50, and 85 percent of blade height for both surfaces, for a total of twelve measurements per blade (see Figure B-4).

## Rotating CDP Seal

A visual inspection revealed no discrepancies. Diameter and runout measurements of each of the CDP seal teeth, Figure B-5, were made and the results are shown in Table B-VI. (NOTE: The twelve o'clock position was arbitrarily chosen, and all measurements are relative to that point.) Calculations of the rotating seal to stationary seal (Table B-IX later in this report) clearances, as shown in Table B-VII indicated no measurable change from production nominal clearances.





Figure B-3. High Pressure Compressor Rotor in Runout Fixture.

Table B-V. HPC Rotor Airfoil Surface Finish Inspection Results.

l					Convex				Τ			Co-			n Resi	
Sta	ge	Tip	Pito	ch R	oot Ave	Stage Verage Average		-	7		Conc	ave	/e		s	
	3	12	12	- 1	12	12	Avei	age	Tip	_	t ch	Roo	Aver	age	Stag Avera	e Ove
4	+	12	15		10	12	12	2	24 22		14 11	13 19	1 1:		17	
		13	10	- 1 '	10 1	1	11		25 22		2	15 19	17			
5		10	12 12		2 1	1 1	11		22 25	1	2	17	17		18	
6		3	11	1	9 1			+	23	1		12	16		17	
7		1	9	10	0 10		11	$\dashv$	21	10	0	15	17 15		16	1
	1	1	10 11	1:	2   11	.	11		18 17 23	11 15 13	5	12 12	14 15			
8	1 1:	3	13 12	10				+	22	20	$\dashv$	10	15	+	15	1
9	21		14	12	13		13		21 21	18 23		16 17	18 20		19	
	12		13	14 10 12	16 12 12				17 16	14 16		18 17	16 16			10
10	15 15	1	14	12	14		13		19 21		+	20	19		17	15
<del></del> _	17		14 15	13 16	14		15		17 17	17 17 17		20 19 21	19 18			
11	13 25		13 20	13 18	13 21	1			23	24	-+-	26	24	+	18	17
	17		15	14 14	15 14		16	2	21   25   27	21 27 23		24 27 26	22 26			
12	11 14	1	2 5	18 15	14 15				0	20	+-	7	25 19	+	24	20
	17 10 13	1		15 16	16 12			1 2:	0	16 19	1	20   7	17 19			ì
13	15	1	$\dashv$	11	16	-	15	ļ i		17 16	1	6	17 16		18	16
	15 15	12	2	11 12	12 13 13			18	1	16 16	1 1		18 16			
4	15	11		11	12	┼	13	18		18 14	10		17 16		17	15
	16 18	17 14	1	17 14 19	18 16 17		17	19 20		18 19	17		18 20			
5	20 16	23 14	+	23	22	+-	17	26	+-	21	17		17		18	16
-	17	14	$\perp$	14	15 15		17	20 19	1	21 21 20	24 22 18		22 21 19		.	
ł	24 27 22	23 22	:	24 22	24 24			28		24	21	+	24		21	19
	18	27 21		22 22	23 20	2	3	21 23 17	2	25 23 .7	26 26		23 24			
age Ai	irfoil	Sur! t Fir	Ence	Fire	h = 16; ii				Ι.		18		17	2	2	22



Typical Concave/Convex

Figure B-4. Location of Surface Finish Measurements - HP Compressor Rotor Blade.




Figure B-5. Forward CDP Seal, Rotating.

Table B-VI. HPCR CDP Seal Teeth Inspection Results.

Runout Data											
		Toot		T							
Position	6	5	4	3	2	1					
12 0'Clock	0.0	0.0	0.0	0.0	0.0	0.0					
1 0'Clock	0.0	0.6	0.1	-0.1	-0.5	1					
2 O'Clock	-0.5	-0.2	-0.3	0.1	-0.5	0.5					
3 O'Clock	-0.9	-0.5	-0.1	-0.2	-0.5	0.5					
4 O'Clock	-0.7	-0.3	-0.4	-1.0	-1.0						
5 0'Clock	0.5	0.5	-0.1	-0.5	0.0	-1.6					
6 0'Clock	-0.1	0.0	0.0	-0.1	0.1	0.0					
7 O'Clock	-0.5	-0.3	0.2	0.1	0.1	1.5					
8 0'Clock	0.0	0.0	0.3	-0.2	0.5	1.5					
9 O'Clock	-0.3	-0.5	0.0	-0.5	-1.3	2.6 2.1					
10 0'Clock	0.0	0.0	0.1	0.5	-1.0	1.4					
11 O'Clock	-0.5	0.0	0.5	-0.8	-0.9	0.7					
Diameters											
12 O'Clock	17.135	17.335	17 500			-					
Maximum	17.135	17.335	17.532	17.737	17.934	18.133					
Minimum	17.134	17.336	17.532	17.737	17.934	18.135					
Average	17.135	17.334	17.532	17.736	17.932	18.131					
	17.133	17.555	17.532	17.736	17.933	18.133					
Shop Manual Dimensions											
M- 1	İ			1							
Maximum	17.134	17.334	17.534	17.734	17.934	18.134					
Minimum	17.132	17.332	17.532	17.732	17.932	18.132					
Serv. Limit	17.129	17.329	17.529	17.729	17.929	18.129					
	<del></del>										

Runout data are in mils and are positive, unless otherwise indicated. Diameters are in inches.

Table B-VII. Forward CDP Seal Clearances.

		Posit	ion Number				
Diameter	1	2	3	4	5	6	
Minimum	.006	.007	.006	.008	.007	.007	
Maximum	.010	.000	.007	.009	.008	.009	
Average	.008	.008	.006	.009	.008	.008	

Overall Average Clearance = 0.008 lnch.

Production New Hardware = 0.0085 Inch Nominal.

## B.2.2 HIGH PRESSURE COMPRESSOR STATOR ASSEMBLY

### General

Except for blade tip-to-casing rubs, the high pressure compressor stator (HPCS) assembly was in excellent condition. A visual inspection of the airfoils revealed no nicks, dents, or other discrepancies, other than a negligible amount of aluminum splatter on the vanes in Stages 12 through 16. A photograph of the upper HPCS assembly is shown in Figure B-6.

## Condition of Variable Stator Bushings

A shake test of each of the variable vanes showed no loose or missing bushings. All vanes appeared to have retained their original torque.

### Coating Condition


Some degree of blade tip-to-casing rubs were seen in all stages of the upper case, ranging from 0.001 to 0.008 inch in depth. Rubs were either at or in the vicinity of twelve o'clock. Rubs also were noted in the lower case in Stages 11 through 16. These were up to 0.006 inch in depth and were located generally about six o'clock.

Some stator land coating was missing from the top half of the casings of Stages 12 and 14. Stage 14 had lost approximately 1/4 inch axially x 3/4 inch circumferentially at the leading edge. Stage 12 had several places where the coating was chipped out at the aft end of the forward case, located between one and two o'clock. The loss was an area of approximately 1/4 inch wide times a total of seven inches in length (see Figure B-6). These rubs and coating losses are considered insignificant.

### HPCS Vane Surface Finish

A representative number of vanes from each of the fixed stages (7 through OGV's) were removed for measurement of the airfoil surface finish. As shown in Table B-VIII, the vanes in Stages 7 and 9 through OGV's were still within average new-part surface finish limits. No limits are defined for Stage 8 vanes.

Measurements were taken at the same locations as on the rotor blades; i.e., at 10/15 percent chord distance from the leading and trailing edges at 15, 50, and 85 percent of blade height for both surfaces, for a total of twelve measurements per vane (see Figure B-7).



High Pressure Compressor Stator Assembly - Rubs and Chipped Coating. Figure B-6.

ORIGINAL PAGE IS OF POOR QUALITY

Table B-VIII. HPC Stator Airfoil Surface Finish Inspection Results.

		<u> </u>	,	onve	<u>.                                    </u>				Conc	ave		Ţ · · · · ·
Stage	Position No.	Tip	Pitch	Root	Avg.	Stg. Avg.	Tip	Pitch			Stg.	
7	37	20	20	23	21	1	30	37				
	38	15	15	15	15	i	20	30	37	35	1	ſ
	39	10	15	15	13	1	20	18	30	30	1	1
	40	14	15	20	16	i i	18	22	33	24		1
	41 68	19	26	22	22	ĺ	35	37	42	38		ł
	69	24 15	25	20	23	i	15	22	28	22		í
	70	18	20	19	18	i	20	30	32	27	1	İ
	71	12	22 22	20	20	ł	17	25	28	23	1	1
	72	17	15	21	18		18	25	37	27	1	1
8				22	18	18	25	35	38	33	28	23
°۱	21 22	40	35	45	40	i	40	37	40	39		1
j	30	40 45	40	37	39	[	38	37	35	37		1
l	31	40	42 40	55	47		40	42	55	46	l	ĺ
- 1	32	45	45	60 50	47		42	50	65	52	l	]
	33	47	60	50 50	47 52		50	65	57	57	İ	İ
i	34	42	55	52	50	46	45	65	55	55	ľ	Ĭ
9	38	22	27			40	45	55	_57	52	48	47
1	39	25	25	30	26		16	23	23	21		
- 1	40	12	15	27 15	26		20	23	23	22		
	41	35	33	38	14 35		16	18	20	18		
- 1	42	25	28	30	28		25	25	30	27		
1	70	16	18	22	19		25 15	22	20	22	j	
- 1	71	25	30	30	28		25	16 25	15	15	j	
- 1	72	22	25	25	24	- 1	16	20	30 20	27	l	
ł	73	15	22	28	22	- 1	15	18	20	19 18	j	
	74	33	35	30	33	_25	22	22	26	23	21	22
10	41	18	15	21	18		20					23
	42	20		25	22	- 1	24	24	25	23		
	43	18	18	20	19	1	32	20	32	27	ľ	
- 1	44	30	30	32	31	1	22	23	22	25 23	- 1	
i	45	20		25	22	ł	20	22	23	23		
- 1	76 77	20			17	1	21	32	27	27	- 1	
- 1	78	16			20	j	23	20	22	22	- 1	
[	79	26			23	1	20	18	24	21	- }	
	80	25			23		26	25	30	27	1	ļ
1		25	24	22	24	22	18	24	30	24	24	23

Table B-VIII. HPC Stator Airfoil Surface Finish Inspection Results (Concluded).


	_			Conve	x		$\perp$		Con	cave		
Stage	Position No.	Tip	Pitcl	Roo	t Avg	Stg.	Ti	p Pite			St	
11	41	١,,	1		<u> </u>		-	7	-11   KO	OL AV	'g. Av	Average
••	42	15	16	25	19	ł	2	0 2	3   2	, ,	2	1
	43	18	25	25	23		2	0 29	, -		4	ľ
	44	.34	24	32	30		2				2	1
	45	25	30	28	28	İ	1			. 1 -	ō	1
	76	15	18	16	16	1	3					1
	77	23	20	23	22	1	3			. , -		1
- 1	78	20	25	30	25		2		,	1 -		ı
i	79	15	20	20	18		20		2			1
I	80	24	24	26	25		21		30		- 1	
	- 80	20	15	15	17	22	3		35			1
12	41	17	15	20	17		T.,			<del></del> -		24
j	42	16	19	20	18	1	21		20	l -,		
1	43	15	15	20	1 17		20	,	25			Į.
	78	20	25	21	22	1	16		22			
1	79	11	14	20	15		19		22	22	: [	1
	80	20	20	21	20	18	20		24	22		i
13	41	15		<del>                                     </del>	1	1-10	25	26	30	27	22	20
	42	19	16	20	17	1	20	25	20	22	ı	
- 1	43	20	20	21	20	I	20	20	26	22		1
- 1	78	14	15	17	17	1	15	20	23	19	1	
1	79	15	14	18	15		16	20	20	19		1
- 1	80	15	15	16	15	!	15	20	20	18	1	1
			14	15	15	17	25	25	22	24	21	19
14	45	20	20	21	20	ł	20	15	24	1	<del> </del>	<del>                                     </del>
- 1	46	20	25	30	25	i	20	20		20		
- 1	47	30	30	30	30	l	20	22	25	22	1	1
1	86	30	25	25	27	1	20	18	25	22	İ	İ
- 1	87	15	10	10	12	ł	15	18	20	19	İ	l
	88	12	13	13	13	21	16	20	18	19	1	1
15	45	20	19	20	20				1	18	20	20
1	46	26	18	15	20		25	30	30	28	1	İ
1	47	20	15	18	18		20	21	25	22	1	
- 1	86	17	15	15	16	ļ	30	35	30	32	1	
ı	87	15	25	16	19	- 1	26	20	26	24		
	88	15	15	20	17	10	23	26	22	24	1 1	
ogv	59						22	25	22	23	26	22
	60	20	21	21	21		22	20	24	22		
Ι,		20	15	18	18	1	25	26	30	27	1 1	
		15	15	20	17	1	15	18	18	17		
	.07	24	18	19	20	19	19	24	22	22	22	21

Average Vane Airfoil Surface Finish -

24μ Inches ΛΑ

Average New Part Finish

28µ Inches AA



Typical Concave/Convex

Figure B-7. Locations of Sucface Finish
Measurements - HP Compressor
Sataor Vane.

#### **B.2.3 COMPRESSOR REAR FRAME**

#### General

A general inspection of the compressor rear frame revealed no discrepancies. The combustor was in excellent condition, showing no signs of burning, cracking, or other types of distress.

#### Stationary CDP Seal, Forward

Diameter measurements of each land of the forward CDP seal, Figure B-8, were obtained at eight equally spaced positions and the results were compared to the Shop Manual requirements, as shown in Table B-IX. Clearance data have been presented in Table B-VIII.

#### No. 4B Pressure Balance Seal

A visual inspection of the No. 4B pressure balance seal, Figure B-9, showed it to be in excellent condition with only very slight rubs located at approximately the six o'clock position. Dimensional inspections consisting of measurements of eight equally spaced diameters were made on each land of each of the aft seals. This seal structure provides the stationary seal surface for both the aft CDP seal and balance piston seal. These measurements are presented in Tables B-X and B-XI, while the inspection data for the rotating seals are presented in Tables B-XXIX and B-XXX in Section B.3.3 of this report. The resultant clearances are shown in Tables B-XII and B-XIII. Note that the 0.010 inch average clearance of the aft CDP seal is the nominal value for stackup of production/new hardware. The balance piston seal was within 0.0005 inch of its nominal stackup of 0.010 inch.




Figure B-8. Forward CDP Seal, Stationary.




Figure B-9. No. 4B Pressure Balance Seal (Mini-Nozzle).

Table B-IX. Stationary CDP Seal, Forward Dimensional Inspection.

	_		Land Number			
Diameter	1	2	3	4	5	6
1	18.150	17.948	17.749	17.550	17.351	17.150
2	18.148	17.949	17.749	17.550	17.351	17.150
3	18.148	17.948	17.749	17.550	17.350	17.149
4	18.148	17.948	17.748	17.549	17.350	17.149
5	18.148	17.948	17.748	17.549	17.350	17.150
6	18.149	17.947	17.749	17.549	17.350	17.150
7	18.149	17.948	17.750	17.550	17.351	17.151
8	18.149	17.949	17.750	17.550	17.351	17.150
Avg.	18.149	17.948	17.749	17.550	17.351	17.150
	She	op Manual R	equirements			
Minimum	18.148	17.948	17.748	17.548	17.348	17.148
Maximum	18.152	17.952	17.752	17.552	17.352	17.152
Serv. Limit	18.156	17.956	17.756	17.556	17.356	17.156
Serv. Limit		17.956	17.756	17.556	17.356	17.15

Table B-X. No. 4B Pressure Balance Seal, Forward Seal (Aft CDP) Dimensional Inspection.

			Land Numbe	r		
Diameter	1	2	3	4	5	6
1	7.942	8.103	8.262	8.422	8.583	8.745
2	7.943	8.102	8.261	8.422	8.582	8.744
3	7.943	8.102	8.261	8.422	8.582	8.744
4	7.943	8.102	8.261	8.421	8.585	8.745
5	7.942	8.102	8.261	8.422	8.584	8.744
6	7.942	8.101	8.261	8.422	8.582	8.744
7	7.942	8.101	8.262	8.423	8.583	8.744
8	7.942	8.102	8.262	8.422	8.582	8.745
Avg.	7.942	8.102	8.261	8.422	8.583	8.744
		Shop Manua	l Requireme			1 0.744
Minimum	7.942	8.102	8.262	8.422	8.582	8.742
Maximum	7.945	8.105	8.265	8.425	8.585	8.745
Serv. Limit	7.947	8.107	8.267	8.427	8.587	8.747
Readings are	in inches.					

Table B-XI. No. 4B Pressure Balance Seal, Aft Seal (HPT Balance Piston) Dimensional Inspection.

1 10.440 10.440 10.440 10.441 10.441	2 10.600 10.600 10.601 10.600	3 10.760 10.760 10.760 10.760	10.920 10.920 10.921 10.921	5 11.079 11.079 11.079	6 11.239 11.239 11.241
10.440 10.440 10.440 10.441	10.600 10.601 10.600	10.760	10.920	11.079	11.239
10.440 10.440 10.441	10.601	10.760	10.921	11.079	11.239
10.440	10.600			İ	1
10.441		10.760	10,921		
	10.601	1		11.080	11.240
10.441	j.	10.761	10.921	11.081	11.241
	10.600	10.761	10.921	11.081	11.241
10.440	10.600	10.760	10.920	11.080	11.241
10.440	10.599	10.760	10.921	11.080	11.240
10.440	10.600	10.760	10.921	11.080	11.240
Sho	p Manual R	equirement	s		
10.442	10.602	10.762	10.922	11.082	11.242
10.446	10.606	10.766	10.926	11.086	11.246
10.448	10.608	10.768	10.928	11.088	11,248
	10.440 10.440 Sho 10.442 10.446	10.440 10.599 10.440 10.600  Shop Manual R 10.442 10.602 10.446 10.606 10.448 10.608	10.440	10.440	10.440

Table B-XII. Aft CDP Seal Clearances.

	<b> </b>	Position Number							
	1	2	3	4	5	6			
Minimum	.018	.009	.007	.007	.007	<del> </del>			
Maximum	.020	.011	.009	.009	.010	.008			
Average	.019	.010	.008	.008	.008	.009			

Overall Average Clearance = 0.010 Inch.

Production New Hardware = 0.010 Inch Nominal.

Table B-XIII. HP Turbine Balance Piston Seal Clearances.

		Position Number							
	1	2	3	4	5	T -			
Minimum	.012	.007	.008	.007	.008	6			
Maximum	.014	.009	.010	.009	.012	.007			
Average	.013	.008	.009	.008	.010	.010			

Overall Average Clearance = 0.0095 Inch.

Production New Hardware = 0.010 Inch Nominal.

## B.3 HIGH PRESSURE TURBINE SECTION

# B.3.1 STAGE 1 HIGH PRESSURE TURBINE NOZZLE ASSEMBLY

### General

The Stage 1 High Pressure Turbine Nozzle (HPTN) Assembly also was in excellent condition. There were no burns, cracks, vane trailing edge bowing, or other discrepancies. All vane cooling holes were open with no splatter buildup on the leading edges. Photographs of the assembly were taken and are presented in Figures B-10 and B-11.

The aft face of the Stage 1 vane outer hook showed good contact over the full 360° circumference. Drop dimensions to the vanes from the compressor rear frame aft flange revealed little, or no, distortion of the vanes that could have resulted in an internal parasitic leakage.

## Drop Dimension - CRF to Stage 1 Vanes

Drop dimensions (Dim. "D") from the compressor rear frame (CRF) aft flange to the aft face of the Stage 1 vane outer hook (see Figure B-12) were taken at eight equally spaced vane segments. At each location, measurements were taken to each end of the segment. Results are presented in Table B-XIV.

The gap between the aft face of the Stage I vane outer hook and the forward face of the Stage 2 HP turbine nozzle support was calculated to be 0.037 inch, which is within specification limits.

## Vane Outer Platform Gap Measurements

The gaps between the outer platforms on adjacent vane segments were measured at 16 equally spaced locations at the aft end of the vanes. The results, presented in Table B-XV, show the gaps to be nearly equal and approximately the nominal Shop Manual value.

## Stage 1: "TN Area Check (A4)

Measurement of the individual nozzle vane area and total calculated flow area is presented in Table B-XVI. As noted, the measured flow area is approximately the nominal Shop Manual value.

# Stage ! HPTN Airfoil Surface Finish Checks

Six nozzles were removed from the Stage 1 high pressure turbine nozzle assembly to have their airfoil surface finishes inspected. Measurements were taken at the pitch line at 10, 50, and 90 percent chord on both the convex and concave surfaces (see Figure B-13). The results, as presented in Table B-XVII, show a small increase over the Shop Manual maximum limits of 39 % inch for the convex (suction) side and 150 % inch for the concave (pressure) side.





Figure B-10. Stage 1 HPTN Assembly - Forward.

78

ORIGINAL PAGE IC OF POOR QUALITY



ORIGINAL PAGE IS OF POOR QUALITY




Figure B-12. Dimension "D" - Drop from CRF to Stage 1 HPTN Vane.

Table B-XIV. CRF to Stage 1 HPTN Vanes Drop Dimension - Dimension "D".

Vane Segment Position No.	CCW End	CW End
1	4.867	4.866
5	4.876	4.875
9	4.872	4.872
13	4.872	4.871
17	4.879	4.878
21	4.876	4.875
25	4.876	4.874
29	4.873	4.871
Average	4.8	73 inches

Table B-XV. Stage 1 HPTN Vane Segment Gaps.

No.	Gap	No.	Gap
1	0.023	9	0.026
2	0.027	10	0.026
3	0.026	11	0.026
4	0.026	12	0.027
5	0.025	13	0.029
6	0.026	14	0.029
7	0.020	15	0.029
8	0.026	16	0.023
	verage Gap = 0. /M Limits = 0.(		nch

Table B-XVI. Stage 1 HPT Nozzle Area Measurements (A4). (Square Inches)

Nozzle No.	Area	Nozzle No.	Area	Nozzle No.	Area	Nozzle No.	Area
1	827	17	800	33	805	49	818
2	815	18	809	34	826	50	830
3	821	19	824	35	812	51	810
4	868	20	813	36	822	52	837
5	825	21	819	37	803	53	820
6	826	22	826	38	825	54	816
7	794	23	837	39	802	55	833
8	810	24	826	40	831	56	815
9	813	25	814	41	807	57	822
10	816	26	830	42	804	58	818
11	80 <i>6</i> .	27	823	43	821	59	801
12	824	28	831	44	824	60	821
13	825	29	815	45	813	61	838
14	803	30	822	46	829	62	807
15	813	31	811	47	826	63	816
16	832	32	825	48	830	64	822

Total = 52.447

= 52.447 Square Inches

Corr. Factor = 0.366

Actual A4 = 52.813 Square Inches

**Shop Manual** = 52.3.3/53.373 Square Inches




Figure B-13. HP Turbine Stage 1 Vanc.

Table B-XVII. Stage 1 HPTN Vane Surface Finish Inspection Results.

		Con	vex		Concave				
Vane	Fwd	Mid	Aft	Avg	Fwd	Mid	Aft	Avg	
1	65	35	40	46	69	200	200	153	
2	58	40	43	47	75	250	200	175	
3	58	52	45	52	78	200	240	173	
4	58	33	45	45	75	240	200	172	
5	58	35	35	43	69	190	230	163	
6	50	25	45	40	67	195	250	171	
<b>AV</b> G				46				168	

## B.3.2 Stage 2 High Pressure Turbine Nozzle Assembly

#### General

Except for the rubs and the typical interstage seal grooves, the Stage 2 high pressure turbing nozzle assembly was in excellent condition. Stage 2 vanes were like new, with no cracks, burns, or other distress.

### Shroud Rubs and Condition

A visual inspection of the Stage 1 shrouds revealed a moderate rub at one o'clock extending across two adjoining shrouds, approximately 3-1/2 inches in total length. A photograph of the rub is presented in Figure B-14. Except for this, the Bradelloy was in good condition.

Moderate to heavy rubs were seen on the Stage 2 shrouds. These occurred at one end or the other on Shrouds No. 1, 2, 7, 8, 9, and 10 and just off-center of Shroud No. 6 (Shroud No. 1 of 11, is positioned at 12 o'clock; shrouds are numbered CW ALF). Photographs of several of the rubbed areas are shown in Figure B-15.

### Nozzle Support

A visual inspection of the forward flange that supports the Stage 1 HP turbine nozzle showed contact throughout the full 360° circumference.

Measurements from the forward face of the aft mounting flange to the forward face of the flange that supports the Stage 1 vane outer hook (Dim. "K"; Figure B-16) were taken at 16 equally spaced locations. The results are presented in Table B-XVIII.

Corresponding dimensions from the CRF aft flange to the aft face of the Stage 1 vane outer hook (Dim. "D") averaged 4.873 inches (Table B-XIV). The average thickness of the shim that mounts between the nozzle support and CRF flanges was 0.020 inch.

Thus, the gap between the Stage 1 vane outer hook and the Stage 2 support's forward flange was calculated to be 0.037 inch versus the 0.042 inch maximum allowed.

### Interstage Seal Grooves

Measurements of the interstage seal grooves were made at four equally spaced positions for each seal land, and are presented in Table B-XIX. The groove depths were approximately the same as those noted for production acceptance engines, and are not believed to represent a short-term deterioration.




Figure B-14. Stage 1 HPT Shroud - Rub.






Figure B-15. Stage 2 HPTN Assembly - Typical Stage 2 Shroud Rubs.




Figure B-16. Dim. "K" - Stage 2 HP Turbine Nozale Support Measurement.

Table B-XVIII. Stage 2 HPT Nozzle Support, Dimension "K".

No.	Dimension	No.	Dimension
1	4.859	9	4.855
2	4.855	10	4.853
3	4.855	11	4.854
4	4.856	12	4.854
5	4.857	13	4.857
6	4.855	14	4.857
7	4.856	15	4.855
8	4.857	16	4.857

Shop Manual = 4.857/4.861

Serviceable = 4.853/4.865

All readings are in inches

Table B-XIX. Stage 2 HPTN Interstage Seal Groove Measurements.

Seal Land No.									
		1	2			3		4	
Location	Width	Depth	Width	Depth	Width	Depth	Width	Depth	
12 O'Clock	.100	.050	.112	.050	.115	.050	.114	.050	
3 O'Clock	.118	.070	.125	.080	.122	.080	.112	.070	
6 O'Clock	.115	.040	.120	.040	.118	.035	.116	.035	
9 O'Clock	.104	.070	.115	.080	.125	.080	.125	.070	
Average	.109	.057	.118	.062	.120	.061	.117	.056	
	All readings are in inches								

### Shroud Radii, Stages 1 and 2

The Stage 2 high pressure turbine nozzle assembly was restrained on the shroud grind fixture and centered in the lathe bed. Each stage of shrouds was measured at axial locations 1/2 inch from the leading edge and 1/4 inch from the trailing edge, at each end and in the center of each shroud as depicted in Figure B-17. Measurements at each of these axial locations consisted of a diameter at the 12 o'clock position and runouts relative to that point at each of the other positions. The data and results are presented in Tables B-XX and B-XXI.

A study of the shroud runout data revealed that, even though the engine was in operation only a short period of time, the Stage 2 shroud geometry no longer conformed to the elliptical grind shape. (Original buildup records for ESN 451507 were researched and they verified that the elliptical grind had been performed.) In addition, a comparison of the diameters taken during the analytical teardown, with the original grind dimensions, show them to be smaller than new. At 12/6 o'clock, the measured diameters were 34.618/34.613 inches versus 34.625 inches new. At 3/9 o'clock, the diameters were 34.625/34.619 inches versus 34.644 inches when new.

The shroud runout data also showed that the Stage 2 shroud ends were bowed inward, some by as much as 0.010 inch. A review of previous data from several "long-time" engines revealed this same characteristic. Up to 0.014 inch inward bowing at the ends had been recorded.

Although the runout data for the Stage 1 shrouds exhibited an elliptical shape, the measurements show that Stage 1, like Stage 2, was smaller in size than the original grind dimensions. The diameters at 12/6 o'clock measured 323.301/33.302 inches versus 33.308 inches new. At 3/9 o'clock, the measured diameters were 33.321/33.320 inches versus 33.338 inches new.


In an effort to understand the shroud deformation and consequently the associated rubs, measurements over and above those contained in the Test Plan were taken on the Stage 2 nozzle support (see Figure B-18) and are presented in Table B-XXII. The results appear to exhibit some minor amounts of waviness but do not fully answer the overall problem. Further studies are in process as part of the NASA-Lewis Performance Improvement Program, Contract NAS3-20629.

An additional measurement of the Stage 2 shrouds was made at approximately 0.100 inches from the leading edge, which was outside the blade path and, consequently, the rubbed areas. The results are presented in Table B-XXIII. As can be seen, at this axial location there was up to 0.017 inch inward creep of the shroud ends.

Figures B-19 and B-20 depict the shrouds and the support runout data, together with the locations of the shroud rubs.

90

6-2



• All Dimensions are in inches

Figure B-17. Typical Stage 1/Stage 2 Shroud Measurement Locations.

Table B-XX. Stage 1 HPT Shroud Dimensions.

	1/2	" from L	E.	1/-	4" from T	.E.
Shroud No.	1	2	3	1	2	3
1	0	3	4	0	2	1
2	5	6	6	1	2	2
3	4	4	4	2	1	-1
4	5	8	10	0	3	7
5	10	12	13	8	10	11
6	13	14	14	11	11	8
7	14	13	12	10	10	8
8	11.	14	14	8	9	10
9	14	17	15	10	13	12
10	16	15	14	13	12	10
11	14	10	8	9	6	2
12	7	5	3	2	1	-2
13	2	1	0	-2	-2	<b>-</b> 5
14	0	2	1	-3	-2	-2
15	-1	0	3	-3	-3	-3
16	5	11	14	0	5	9
17	14	16	16	10	13	13
18	16	1.5	12	13	10	8
19	12	9	7	7	5	3
20	7	6	8	3	3	2
21	6	8	8	2	4	4
22	10	8	7	5	5	2
23	6	6	7	1	0	-2
24	7	2	0	0	0	0
			Lea	ading	Traili	ıg
Radius Minimu Maximu	er at 12 at 12 0 m Radius m Radius e Radius		16 16 16	.301 .650 .650 .667	33.302 16.652 16.647 16.665 16.656	

Table B-XXI. Stage 2 HPT Shroud Dimensions.

	Runout data						
	1/2" from L.E.				1/4" from T.F		
Shroud No.	1	2		3	1	2	3
1	0	0	-1	.0	0	- 1	- 9
2	-11	- 3	-	9	- 6	4	6
3	- 8	0	_	5	4	1	0
4	- 3	1	-	9	2	5	1
5	-12	- 6	-	9	0	- 8	- 7
6	-11	- 8	-13		- 4	- 5	- 9
7	-10	- 1	1		-10	- 3	4
8	0	5	5 - 2		5	8	3
9	0	1	1 - 5		- 2	1	- 3
10	5	- 2	_	6	0	0	- 3
11	- 4	4	2		- 4	0	1
					eading Trailing		ling
Diameter at 12 O'Clock Radius at 12 O'Clock Minimum Radius Maximum Radius Average Radius					34.618 17.313 17.300 17.300 17.318 17.309 17.308		309 299 31 <i>7</i>

Runout data are in mils and are positive, unless otherwise indicated. Other measurements are in inches.




Figure B-18. Stage 2 Nozzle Support - Locations of Dimensional Inspections.

Table B-XXII. Stage 2 HPT Nozzle Support Diameters Measurements.

Clock		Run	out Data	
Position	ВВ	н	В	N
12 1 2 3 4 5 6 7 8 9 10	0 4l <sub>2</sub> 4l <sub>3</sub> 9 7l <sub>2</sub> 9l <sub>3</sub> 5l <sub>3</sub> 9l <sub>3</sub> 9l <sub>3</sub>	0 9 6 11 9 17 11 14 8 10 8	0 3 5 8 4 12 6 10 8 7	0 5 8 10 3 12 8 7 5 10 9
Diameter at 12 O'Clock Avg Dia	38.921 39.914	36.707 36.699	33.858 33.851	33.590 33.584
	Shop Manua	al Dimension	ns	
Maximum Minimum Serv. Limit	38.923 38.913 38.913	36.715 36.709 36.707	33.854 33.850 33.846	33.594 33.582 33.560

Runout data are in mils and are negative (smaller) unless otherwise indicated. Diameters are in inches.

Table B-XXIII. Stage 2 HPT Shroud Runouts, Unrubbed Path.

	0.100" from L.E.							
Shroud No.	1	2	3					
1	0	4	-10					
2	-12	- 3	-13					
3	-13	1	- 6					
4	~ 5	2	-15					
5	-18	- 7	- 8					
6	-11	- 7	-12					
7	- 8	- 1	2					
8	1	5	- 3					
9	1	3	- 6					
10	<b>-</b> 5	0						
11	- 5	4	- 6 3					

Data are in mils and are positive (larger) unless otherwise indicated.




Figure B-19. Stage 2 HPTN Support and Stage 2 Shroud Runouts.




Figure B-20. Stage 2 HPTN Support and Stage 1 Shroud Runouts.

## B.3.3 HIGH PRESSURE TURBINE ROTOR ASSEMBLY

#### General

Except for heavy blade-tip rubs, the high-pressure turbine rotor was in excellent condition. No visible discrepancies were noted in any of the spool parts. The blade retainer seal wires were visually inspected and revealed good sealing contact.

## HP Turbine Rotor Airfoil Surface Finish Inspection Results

A profilometer was used to measure the airfoil surface finish on each of four blades from each stage of the high-pressure turbine. Measurements were taken on both sides at 10, 50, and 90 percent of the blade chord, as depicted in Figure B-21. The results are shown in Table B-XXIV.

### HP Turbine Rotor Blade Tip Measurements

The high-pressure turbine rotor was installed on its gearing axis in a runout fixture, with the blades shimmed in accordance with the Shop Manual (see Figure B-22). Runouts at two axial locations (0.100 inch from both the leading and trailing edges) of each blade, together with the maximum blade radius of each stage, were taken and are presented in Tables B-XXV and B-XXVI.

An examination of the data shows how unevenly the blades had worn, both blade-to-blade and forward-to-aft. It also revealed how severe the tip rubs were. According to production records, the blade tip radii during the initial build-up were 16.589 inches for Stage 1 and 17.242 inches for Stage 2. Therefore, the average tip loss for Stage 1 was 0.025 inch; and for Stage 2, 0.020 inch. This condition was shown to be the major source of engine performance loss noted during parts inspection.

Four equally spaced blade tips in each stage of 451507 were notched to various predetermined depths. During the analytical teardown, the notches were remeasured and the results are presented in Figure B-23. Photographs of the notched blades at teardown are shown in Figure B-24. The data show an average loss of 0.030 inch for Stage 1 and 0.028 inch for Stage 2, agreeing favorably with the average change calculated from the blade tip radii measurements (Tables B-XXV and B-XXVI) and the shroud radii measurements (Tables B-XX and B-XXI). Calculated clearances are presented in Table B-XXVII.




Figure B-21. Typical HPTR Blade Concave/Convex Surface Finish Measurement Locations

Table B-XXIV. HPT Rotor Airfoil Finish Inspection Results.

		Convex			Concave				
Stage	Blade No.	Fwd	Mid	Aft	Avg	Fwd	Mid	Aft	Avg
1	1	55	50	40	48	55	100	140	98
	2	47	42	42	44	75	100	170	115
	3	45	45	40	43	60	110	170	113
	4	45	27	43	38	60	100	150	103
	Average				43				107
2	1	41	40	38	40	38	32	38	36
	2	50	40	40	43	37	41	40	39
	3	60	32	33	42	39	30	35	35
	4	48	40	32	40	43	35	37	38
	Average				41				37

Readings are in  $\mu$  inch AA New Blade Specification - 63  $\mu$  inch AA maximum Average




Figure B-22. High Pressure Turbine Rotor in Runout Fixture.

ONIEMAI PACK S

Table B-XXV. Stage 1 HPTR Blade Tip Dimensions.

				Blade	Runou	t Data						-
No.	Pwd	Aft	No.	Pwd	Aft	No.	Fwd	Aft	No.	Fwd	Aft	_
1	16	10	28	19	5	55	17	10	82	14		_
2	14	7	29	19	9	56	18	9	83	17	3	
3	19	9	30	16	5	57	16	,	84	16	5 2	
4	15	4	31	20	7	58	17	4	85	17	ı	
5	18	11	32	16	2	59	17	8	86	15	5	
6	13	5	33	20	11	60	18	6	87	15	3	
7	18	11	34	16	6	61	18	10	88	16	2	
8	14	5	35	18	9	62	16	5	89	18	2	
9	19	11	36	16	5	63	16	,	90	19	2	
10	17	5	37	24	13	64	15	5	91	15	4	
11	20	12	38	18	6	65	16	9	92	18	4	
12	16	5	39	20	10	66	17	5	93	13	7	j
13	18	13	40	18	4	67	16	11	94	16	8	ı
14	15		41	20	8	68	17	6	95	16	4	ı
15	18	10	42	17	3	69	16	111	96	18	3	I
16	15	6	43	18	8	70	14	6	97	17	2	l
17	20	12	44	17	5	71	17	10	98	22	3	J
18	14	7	45	22	8	72	14	5	99	17	4	
19	17	11	46	20	6	73	16	9	100	20	4	I
20	14	5	47	15	7	74	13	2	101	16	0	ı
21	18	14	48	14	5	75	15	11	102	19	1	I
22	15	9	49	19	8	76	13	5	103	18	2	l
23	18	11	50	14	4	77	16	10	104	20	2	I
24	14	6	51	18	10	78	14	3	105	21	2	
25	18	10	52	14	4	79	14	9	106	24	4	I
26	16	5	53	15	9	80	14	4	107	22	10	۱
27	20	9	54	16	5	81	13	9	108	24	8	
							!	1			•	

## Blade Redii

	Forward	<u>Aft</u>
Maximum	16.563	16.576
Minimum	16.552	16.562
Average	16.559	16.570

Runout Data are in Mils and are Negative.

O Mil Runout = 16.576 inches = Maximum Blaje Radius Radii are Recorded in inches.

Table B-XXVI. Stage 2 HPTR Blade Tip Dimensions.

				Blad	e Runou	t Data					
No.	Fwd	Aft	No.	Fwd	Aft	No.	Fwd	Aft	No.	Fwd	Aft
1	8	7	30	11	3	59	11	11	88	13	5
2	12	5	31	9	4	60	7	6	89	11	5
3	8	2	32	9	4	61	10	12	90	12	5
4	11	7	33	9	5	62	11	4	91	8	8
5	14	0	34	11	7	63	10	7	92	10	9
6	16	8	35	8	3	64	7	4	93	13	8
7	10	8	36	12	4	65	10	10	94	15	8
8	17	1	37	9	4	66	10	4	95	8	7
9	9	7	38	12	7	67	7	9	96	11	7
10	15	2	39	11	4	68	9	6	97	17	11
11	8	6	40	15	6	69	10	7	98	20	5
12	13	2	41	9	7	70	11	5	99	9	11
13	10	4	42	14	9	71	10	8	100	15	14
14	16	4	43	10	9	72	9	7	101	8	7
15	9	8	44	15	12	73	11	5	102	11	11
16	15	2	45	13	4	74	10	4	103	9	3
17	7	6	46	16	5	75	10	7	104	11	4
18	13	2	47	9	3	76	11	3	105	8	5
19	8	6	48	10	4	77	9	7	106	13	5
20	14	8	49	13	5	78	11	6	107	9	3
21	11	5	50	16	3	79	8	6	108	11	6
22	16	9	51	11	1	80	9	4	109	9	3
23	10	0	52	13	2	81	12	5	110	13	5
24	15	3	53	8	5	82	7	4	111	9	4
25	12	1	54	6	7	83	õ	11	112	12	5
26	16	3	55	10	11	84	6	5	113	11	4
27	10	5	56	8	1	85	9	7	114	9	6
28	9	5	57	11	8	86	10	5	115	14	7
29	8	4	58	11	4	87	10	8	116	12	6

Blade Radii

	Forward	Aft
Maximum	17.225	17.231
Minimum	17.211	17.217
Average	17.220	17.225


Runout Data are in Mils and are Negative
0 Mil Runout = 17.231 inches = Maximum Radius
Radii are Recorded in inches.


Stage 1


Blado No.	A	_ B	c
1	10	20	30
20	10	20	30
14	15	35	60
41	15	33	60


Stage 2

Blade	1	
Ko,	B	•
1	10	30
30	10	20
36	20	50
45	20	50









Notch Depth at Teardown, mils

Blade No.	A	В	C
1	0	0	0
28	0	0	0
14	0	01	30
41	0	04	33

Blade		1
No.	D	E
1	0	0
30	0	0
16	0	23
45	0	21

Figure B-23. HPT Rotor Blade Tip Notch Data.




Figure B-24. High Pressure Turbine Notched Blades at Teardown.

ORIGINAL PAGE IS OF POOR QUALITY

Table B-XXVII. HP Turbine Blade Tip Clearances

Stage No.	Blueprint	Minimum	Maximum	Average	Δ Blueprint
1 LE	0.072	0.087	0.115	0.099	0.027
TE	0.072	0.071	0.103	0.086	0.014
AVG	0.072	0.079	0.109	0.093	0.021
2 LE	0.075	0.075	0.107	0.089	0.014
TE	0.075	0.068	0.100	0.083	0.008
AVG	0.075	0.072	0.103	0.086	0.011

All readings are in inches


A second and supplementary source of short-term HPT hardware data was obtained from the High Pressure Turbine Tip Notch Program. This Contractor-funded program is designed to evaluate HPT blade tip-to-shroud rubs and the resultant effect on blade lengths by use of blade tip notches as utilized on 451507. The notches, of varying depths, are put into selected blade tips during new engine assembly. Borescope inspections at test intervals permit assessment of blade length change due to rubs. Figures B-25 and B-26 present the Stage 1 and Stage 2 tip notch data for a group of eight new CF6-6D engines. Note that the average blade rubs of 22 mils (Stage 1) and 15 mils (Stage 2) agree well with the ESN 451507 blade tip rubs of 25 mils and 20 mils respectively, as determined from the average blade tip radii at teardown compared to the average blade tip radii at buildup. It is also of interest that the blade lengths appear to remain relatively constant during the first 2000 hours of revenue service operation. This lends credence to the theory that blade tip rubs are event-related, not time-related.

#### Thermal Shield Seal Teeth

While the HP turbine rotor was in the runout fixture, measurements of the thermal shield seal teeth (see Figure B-27) were made. To accomplish this, a position, designated as 12 o'clock, was arbitrarily selected and marked on each tooth. The diameters were measured at these positions, together with runouts at 12 equally spaced locations relative to these positions. Data and results are shown in Table B-XXVIII. The results show that the average seal diameters are six mils smaller than the nominal shop manual value.

## HP Turbine Rotor Forward Shaft Seals

Measurements of the HP turbine rotor forward shaft seal teeth, also shown in Figure B-27, were made in the same manner as those that were made for the thermal shield teeth; that is, a diameter and 12 equally spaced runouts. Tables B-XXIX and B-XXX show the results. Clearances between these and the stationary seals were presented in Tables B-XII and B-XIII and discussed in Section B.2.3.







Figure B-25. CF6-6 HPT Stage 1 Blade Tip Notch Results.






Figure B-26. CF6-6 HPT Stage 2 Blade Tip Notch Results.




Figure B-27. HP Turbine Rotor Forward Shaft Seals and Thermal Shield.

Table B-XXVIII. HPTR Thermal Shield Seal Teeth Measurements.

	Ku	nout Data					
Position	1	Tooth Numbe					
12 O'Clock	0.0	0.0	0.0	0.0			
1 0'Clock	-0.1	-1.5	0.5	0.1			
2 O'Clock	0.4	-0.9	0.6	0.5			
3 O'Clock	2.2	1.6	2.9	3.1			
4 0'Clock	3.8	4.2	5.0	6.2			
5 0'Clock	3.5	2.6	3.1	3.5			
6 O'Clock	1.8	0.9	2.1	1.6			
7 O'Clock	1.5	0.3	1.9	1.6			
8 O'Clock	0.9	-0.2	1.5	1.5			
9 0'Clock	0.6	-0.5	1.0	1.6			
10 O'Clock	-0.6	-2.0	0.0	0.4			
11 0'Clock	-1.0	-1.5	0.0	1.4			
	Dia	ameters					
12 O'Clock	26.621	26.462	26.297	26.043			
Maximum	26.622	26.463	26.300	26.048			
Minimum	26.620	26.460	26.297	26.043			
Average	26.621	26.462	26.298	26.045			
	Shop Manu	ual Dimension	ıs				
Maximum	26.630	26.470	26.308	26.058			
Minimum	26.622	26.462	26.300	26,050			
Serv. Limit	26.615	26.455	26.293	26.043			

Runout data are in mils and are positive, unless otherwise indicated. Diameters are in inches.

Table B-XXIX. HPTR Forward Shaft Forward Seal Teeth Measurements (Aft CDP Seal).

	Tooth Number							
Position	1	22	3	4	5	. 6		
12 O'Clock	0.0	0.0	0.0	0.0	0.0	0.0		
1 O'Clock	-1.0	-0.5	-0.5	-1.0	-0.6	-0.5		
2 O'Clock	-0.5	-0.2	-0.7	0.0	0.0	-1.6		
3 O'Clock	0.5	0.5	-0.5	0.5	0.3	-1.4		
4 O'Clock	0.5	1.0	0.0	0.1	0.1	-0.2		
5 O'Clock	-0.5	1.0	0.4	0.0	0.5	0.2		
6 O'Clock	0.0	1.0	0.5	0.9	0.6	0.0		
7 O'Clock	0.5	0.2	-0.5	1.0	1.5	0.1		
8 O'Clock	1.0	2.0	1.0	2.0	2.2	1.0		
9 O'Clock	1.5	2.0	1.6	1.6	2.0	1.3		
10 O'Clock	1.5	1.0	1.5	1.6	1.8	1.1		
11 O'Clock	1.0	0.5	-0.5	1.0	1.2	-0.1		
			Diameters			<del> </del>		
12 0'Clock	7.903	8.082	8.245	8.405	8.566	8.726		
Maximum	7.905	8.084	8.246	8.407	8.567	8.727		
linimum	7.903	8.081	8.243	8.404	8.566	8,725		
lverage	7.904	8.083	8.245	8.406	8.567	8.726		
		Shop 1	Manual Dim	ensions	<del></del>			
Maximum	7.909	8.087	8.250	8.410	8.570	8,730		
linimum	7.899	8.083	8.246	8.406	8.566	8.726		

Runout data are in mils and are positive, unless otherwise indicated. Diameters are in inches.

Table B-XXX. HPTR Forward Shaft Aft Seal Teeth Measurements (Balance Piston Seal).

			Runout D	ata		
Position	,		Tooth	Number		
12 0101	1 1	2	3	4	5	6
12 0'Clock	0.0	0.0	0.0	0.0	0.0	0.0
1 0'Clock	-1.5	-1.1	-0.5	-1.4	-1.5	-1.6
2 O'Clock	-1.5	-1.5	0.4	-2.5	-2.4	-2.0
3 O'Clock	-1.5	-1.7	0.0	-1.8	-1.8	-3.0
4 O'Clock	-2.0	-1.0	-0.6	-1.5	-1.5	-2.6
5 O'Clock	0.1	0.4	0.6	0.3	0.0	-0.7
6 O'Clock	0.9	1.0	0.6	-3.0	0.5	-2.4
7 0'Clock	1.8	0.1	0.5	1.1	0.0	1
8 O'Clock	2.6	1.0	-1.0	-1.6	-3.6	-1.6
9 O'Clock	2.7	1.4	-0.7	-2.6	-3.4	-2.9
10 O'Clock	1.7	1.5	0.2	-0.4		-2.6
11 O'Clock	1.0	1.1	1.2	0.6	0.4 0.6	-0.5 -1.0
			Diamet			
12 0101		· · · · · · · · · · · · · · · · · · ·	Diameters			
12 O'Clock	10.414	10.585	10.743	10.903	11.064	11.224
Maximum	10.415	10.585	10.745	10.907	11.064	11.225
Minimum	10.413	10.583	10.742	10.902	11.057	11.221
Average	10.414	10.584	10.743	10.904	11.061	11.223
		Shop N	Manual Dime	ensions		
Maximum	10.417	10.587				
finimum	10.413	10.583	10.747	10.907	11.067	11.227
erv. Limit	64.898 M	•	10.743	10.903   Teeth Diam	11.063	11.223

Runout data are in mils and are positive unless otherwise indicated. Diameters are in inches.

#### B.4 LOW PRESSURE TURBINE SECTION

### B.4.1 TURBINE MID FRAME

#### General

A visual inspection of the turbine mid-frame (TMF) assembly showed it to be in excellent condition with no defects seen in any of its parts.

#### TMF Forward Flange (Diameter U)

The TMF forward flange outer dismeter (Diameter U) serves as the primary control of concentricity of the Stage 2 HPT nozzle support, affecting HPT blade-to-shroud clearances. Diameter U was measured at the 12/6 o'clock position, together with runouts of the flange in relation to the No. 5 bearing housing. The results were acceptable, as shown in Table B-XXXI.

#### LPT Pressure Balance Seal

An eight-diameter measurement of the stationary LPT pressure balance seal was obtained; the results are shown in Table B-XXXII. Average clearance with the rotating seal (Table B-XXXIV) was calculated to be 0.030 inch. Stackup of production new hardware produces a nominal clearance of 0.031 inch.

### Stage 1 LPTN Airfoil Surface Finish


Surface finish measurements of the Stage 1 low pressure turbine nozzle airfoils were made on the end vanes of each of four segments. The readings were taken 0.45/0.50 inch from the leading edge (LE) and trailing edge (TE) on each side; tip readings were taken 0.45/0.50 inch below the outer platform as depicted in Figure B-28. The results are grouped with the other low-pressure-vane data in Table B-XXXIII.

Table B-XXXI. TMF Forward Flange (Diameter U) Measurements.

	Runout	Data									
12 O'Clock	.000	6 O'Clock	.001								
1 0'Clock	.003	7 0'Clock	.000								
2 0'Clock	.006	8 0'Clock	.001								
3 0'Clock	.006	9 0'Clock	001								
4 O'Clock	.006	10 0'Clock	003								
5 0'Clock	.004	11 O'Clock	004								
	Diamet	ers									
12 0'Clock											
Maximum											
Minimum	= 38.7	27									
Average											
Shop Manual	= 38.7	29/38.735 Avera	ge								
All readings	are in inc	hes.									

Table B-XXXII. LPT Pressure Balance Seal (Stationary Measurements).

No.	Diameter	No.	Diameter
1	19.046	5	19.055
2	19.048	6	19.059
3	19.047	7	19.059
4	19.051	8	19.059
	Average = S/M = 19.0		4 Avg.
	Readings a	re in in	ches.



TYPICAL ALL STAGES CONCAVE/CONVEX ON END VANES OF SEGMENT

Figure B-28. Location of Surface Finish Measurements on LPT Vanes

Table XXXIII. LPTS Airfoil Surface Finish Inspection Results.

				Conve	×				Conc	ave	
		Т	ip	Pí	tch				Pi	tch	
Stage	S/N	LE	TE	LE	TE	Avg	Stage Avg	LE	TE	Avg	Stage
1	R2728 A8818 A8847 A8747	73 85 90 89	90 76 89 88	72 67 85 75	78 67 87 83	78 74 85 84	80	56 55 55 73	78 80 54 80	67 68 55 77	67
2	B3941	56	57	58	57	57	57	60	65	63	63
3	T2057	60	58	65	66	62	62	52	57	54	54
4	V0880 V0404 V0358	45 88 58	47 50 40	44 65 67	46 54 40	46 64 51	54	40 70 50	38 46 42	39 58 46	48
5	V1748 V1360 V1760	80 58 47	50 63 77	65 50 53	60 55 55	64 57 58	59	53 65 60	50 45 34	51 55 47	51
Avg	Stator						65				57
Surface	finish o	f new	airfo	ils	= 63	µ inch	maximum	<u>L</u>			

117

### B.4.2 LOW PRESSURE TURBINE ROTOR

#### General

Visually, the low pressure turbine (LPT) rotor assembly was in excellent condition. No FOD or other type of damage was noted on the airfoils, nor on the spool parts. A photograph of the rotor installed in its transportation fixture is presented in Figure B-29.

### Dimensional Inspections

The rotor was set up in a lathe bed on the No. 6 and No. 7 bearing journals for radii meaurements of the blade tip shroud seal serrations, the interstage air seals and the pressure balance (P/B) seal teeth. The results are shown in Table B-XXXIV.

## LPT Rotor Airfoil Surface Finish

After the dimensional inspections were completed, six blades from each stage were removed to measure the airfoil surface finish. When the initial measurements showed the finishes to be at Shop Manual quality, a reduced sample of blades from each stage was actually inspected; the results of these inspections are presented in Table B-XXXV. The checks were made at the same locations that were measured on the Stage 1 LPT nozzle vanes (see Figure B-30).

## B.4.3 LOW PRESSURE TURBINE STATOR ASSEMBLY

#### General

The low-pressure turbine stator assembly, like most of the engine, was in excellent condition. No defects were noted in any of the hardware. Rub patterns on the shrouds and interstage seals were normal. Castone impressions were made of the maximum depth rub visually observed in each stage of shrouds and seals from each casing half. A sketch of each is shown in Figure B-31. The impressions are in the files of Airline Support Engineering, Evendale, Ohio. An end view of the shroud and seal rubs is shown in Figure B-32. These rubs were shown to be insignificant.

## LP Turbine Stator Airfoil Surface Finish

Based on surface finish results obtained for other airfoils throughout the engine, only a small sample of Stage 2 through 5 LPT vanes were removed to inspect airfoil surface finish. These results are presented with the Stage 1 vane data in Table B-XXXIII. The inspection checks were made at the same locations as defined for the Stage 1 vanes (see Figure B-28).

Figure B-29. Low Pressure Turbine Rotor.

ORIGINAL PAGE IS OF POOR QUALITY

Table B-XXXIV. LP Turbine Rotor Radii Measurements.


			Blade	Radii			
	For	ward	A:	ft	0verall	S/M Dime (Aver	
Stage	Maximum	Minimum	Maximum	Minimum	Average	Maximum	Minimum
1 2 3 4 5	24.137 24.131 24.112 24.115 24.118	24.122 24.121 24.098 24.106 24.108	24.143 24.132 24.113 24.115 24.116	24.123 24.119 24.101 24.104 24.104	24.131 24.126 24.106 24.110 24.112	24.144 24.137 24.125 24.135 24.135	24.121 24.114 24.102 24.112 24.112

		I	nterstage	Seal Radii			<u>:</u>
	For	ward	A	ft	Overal1	S/M Dime (Ave	ensions rage)
Stage	Maximum	Minimum	Maximum	Minimum	Average	Maximum	Minimum
1 2 3 4 5	18.200 18.004 16.848 15.573 14.214	18.195 18.001 16.846 15.570 14.208	N 18.007 16.848 15.573 14.224	/A 18.005 16.846 15.571 14.215	18.198 18.004 16.847 15.572 14.215	18.207 18.015 16.858 15.588 14.233	18.199 18.007 16.850 15.580 14.225

1								
9.494	9.495							
9.494	9.495							
9.494	9.495							
9.494	9.495							
9.493	9.495							
5   9.496   9.493   9.495 6   9.496   9.493   9.494								
lameters = 113.934/113								
	9.494 9.494 9.493 9.493							

Table B-XXXV. LPTR Airfoil Surface Finish Inspection Results.

				Conv	ex				Conca	ive	
		Ti	p	Pit	ch				Pit	ch	
Stage	s/N	LE	TE	LE	TE	Avg	Stage Avg	LE	TE	Avg	Stage Avg
1	K3948 K4594 K3336	40 30 45	35 45 35	50 28 45	40 35 38	41 35 41	39	40 40 45	40 40 40	40 40 42	41
3	B9125 B9201 B8896	48 58 59	38 47 50	30 50 45	35 80 35	38 59 47	48	45 58 40	42 50 32	43 54 36	45
4	B4009 B3502 B4012	63 70 70	77 62 60	40 47 62	40 32 55	55 53 62	57	36 40 38	38 36 42	37 38 40	38
5	Y5463 Y7404 Y5468 Y7368 Y6754 Y8637	40 45 35 50 45 40	35 35 40 40 40 55	35 35 35 45 38 50	35 30 35 45 38 55	36 36 36 45 40 50	41	41 45 35 45 40 45	38 38 40 50 40 35	40 41 38 47 40 40	41
Average	Rotor		1				45				41
Surface	finish o	f new	airf	oils	= 4	5µ in	ch maxi	num			



TYPICAL CONCAVE/CONVEX

Figure B-30. Location of Surface Finish Measurements on LPT Blades




Figure B-31. LPTS Shroud and Interstage Seal Rub Impressions.



Figure B-32. Low Pressure Turbine Stator Assembly - View of Shroud and Seal Rubs.

## LP Turbine Stator Airfoil Surface Finish

Based on surface finish results obtained for other airfoils throughout the engine, only a small sample of Stage 2 through 5 LPT vanes were removed to inspect airfoil surface finish. These results are presented with the Stage 1 vane data in Table B-XXXIII. The inspection checks were made at the same locations as defined for the Stage 1 vanes (see Figure B-28).

## APPENDIX C

# QUALITY ASSURANCE REPORT

## Introduction

It is the fundamental precept of the Aircraft Engine Group to provide products and services that fulfill the Product quality expectations of customers and maintain leadership in product quality reputation, in conformance to the policy established by the Executive Office.

The Quality System as documented in Aircraft Engine Group Operating Procedures provides for the establishment of Quality assurance requirements through the design, development, manufacture, test, delivery, application, and post-delivery servicing of the product. These instructions and Operating Procedures clearly delineate the cross-functional responsibilities and procedures for implementing the system, which includes coordination with cognizant FAA/AFPRO functions prior to issue and implementation.

The Quality Organization implements the Quality System requirements in each of their assigned areas of responsibility, providing design review participation, quality planning, quality input to Manufacturing planning, quality assurance and inspection, material review control, production testing and instrumentation calibration.

The Aircraft Engine Group has additional Manufacturing facilities, and Overhaul/Service Shops such as the one at Ontario, California. These various facilities are termed "satellite" plants or locations. They are not considered vendors or suppliers for quality control purposes and have the same status and requirements they would have if located in the Evendale Manufacturing Facility.

The specific requirements for this contract was accomplished at the following locations:

- Production Assembly and Engine Test Evendale
- Ontario Service Shop Ontario

A summary of activities for each location is included in this report.

# Quality System

Quality Systems for Evendale and Ontario are constructed to comply with Military Specifications MIL-Q-9858A, MIL-I-45208A, and MIL-C-45662A, and with Federal Aviation Regulations FAR-145 and (where applicable) FAR-21. The total under prior contracts.

Inherent in the system, is the assurance of conformance to the quality requirements. This includes the performance of required inspections and tests. In addition, the system provides change control requirements which assure that design changes are incorporated into manufacturing, procurement, and quality documentation, and into the products.

Engine parts are inspected to documented quality plans that define the characteristics to be inspected, the gages and tools to be used, the conditions under which the inspection is to be performed, the samping plan, laboratory and special process testing, and the identification and record requirments.

Work instructions are issued for compliance by operators, inspectors, testers, and mechanics. Component part manufacture provides for laboratory overview of all special and critical processes, including qualification and certification of personnel, equipment, and processes.

When work is performed in accordance with work instructions, the operator/inspector records that the work has been performed. This is accomplished by the operator/inspector stamping or signing the operation sequence sheet to signify that the operation has been performed.

Control of part handling, storage, and delivery is maintained through the entire cycle. Engines and assemblies are stored ir special dollies and transportation carts. Finished assembled parts are stored so as to preclude damage and contamination, openings are covered, lines are capped, and protective covers are applied as required.

A buildup record and test log is maintained for the assembly, inspection, and test of each major component or engine. Component and engine testing is performed according to documented test instructions, test plans, and instrumentation plans. Test and instrumentation plans were submitted to NASA for approval prior to the testing.

Records essential to the economical and effective operation of the Quality Program are maintained, reviewed, and used as a basis for action. These records include inspection and test results, nonconforming material findings, laboratory analysis, and receiving inspection.

Nonconforming hardware is controlled by a system of material review at the component source. Both a Quality representative and an Engineering representative provide the accept (use-as-is or repair) decision. Nonconformances are documented, including the disposition and corrective action if applicable to prevent recurrence.

#### Calibation

The need for product measurement is identified and the design, procurement, and application of measuring equipment specified at the start of the product cycle. Measuring devices used for product acceptance and instruments used to

control, record, monitor, or indicate results of, or readings during, inspection and test are initially inspected, calibrated, and periodically reverified or recalibrated.

Documented procedures are used to define methods of calibration and verification of characteristics which govern the accuracy of the gage or instrument. Provisions are made for procurement of instrument calibration capability as a part of instrument system acquisition.

Frequency of recalibration is specified and measuring gages and instruments are labeled to indicate the period of use before recalibration is necessary. Records are maintained for each gage or instrument which lists the identification, serial number, calibration frequency, procedure, and results of each calibration.

Recalibration periods (frequency of calibration) are prescribed on the basis that the gages and instruments are within calibration tolerance limits at the end of the recalibration period. The results of recalibration are analyzed to determine the effectiveness of the recalibration period, and adjustments are made to shorten or lengthen the cycle when justified.

Standards used to verify the gages and instruments are traceable to the National Bureau of Standards.

# Quality Assurance for Instrumentation

Items defined as Standard Instrumentation (items appearing on the engine parts lists) will have Quality Assurance Control to the same degree as other engine components. Instrumentation on engines for Revenue Service will be subjected to the test and inspection criteria identified in the applicable Shop Manual.

Items defined as "Test Instrumentation" (standard test instrumentation as identified in the applicable engine manual GEK 9266 for CF6 test section 72-00) will be subject to the same controls required for measuring and test equipment. This intrumentation is periodically reverified by the technician and recalibrated, at a prescribed frequency, against standards traceable to the National Burearu of Standards.

Items identified as "Special Instrumentation" (non-parts list or non-Tech Manual instrumentation supplied for this program) will have Quality Assurance Control consistent with the stated objectives of this program.

The instrumentation used for obtaining data for this contract fulfillment has not affected the engine operations or performance.

## ACTIVITY SUMMARY BY LOCATION

#### PRODUCTION ASSEMBLY

In Production Assembly, the standard engine build procedures were used to ensure compliance to Quality Systems. These procedures and practices are approved under FAA Production Certificate 108. The operating procedures utilize an Engine Assembly Build Record (EABR) and an Engine Assembly Configuration Record (EACR). These documents, incorporated into an Engine Record Book, serve as a historical record of the compliance to the Assembly Procedure, a record of critical assembly dimensions, and a record of the engine configuration. Work performed is claimed by the applicable inspector or assembler. (Samples of the EABR and EACR cards are provided in Figures C-1 and C-2 respectively.)

Production Assembly releases the engine to Test, and upon successful completion of the required test, performs the necessary work and inspection in preparation for shipment to the customer.

### PRODUCTION ENGINE TEST

In Production Engine Test, the engine is inspected and prepared for test per Engine Test Instruction (ETI) Number C15.

Limits and restrictions of Production Test Specifications were applied during the testing of engines under this contract. The safety of the test crew and engine is ensured by conducting ETI C-18 CF6 cell check sheets prior to the performance of the test.

The engine performance data and safety parameters are recorded by automatic data recording (ADR). The data systems, test cell, thrust frame, fuel measuring systems, are calibrated on a periodic basis by specialized technicians. During testing, the ADR system is continually monitored by test engineers to ensure the quality of the data being recorded.

DATE ISSUED		ENGINE ASSEMBLY BUILD-UP RECORD	ORD				
WORK ENGINE STAT. MODEL MSG56 CF6-60	*	IME PF	E B-ASSY		- PAGE U PROCEDURE DATE	U 2 OF 04. REV. NO.	
DATA IDENTIFICATION	ON O	5		GREEN	FINAL	EPR	0
		C THE SOLIS		4265	A	_	1
	- <del> -</del>	1.19.3 1.19.3 REF DIN 1.		- (SE-)			15
		C. 642 , 402 , 400/ REF LINIT	<b>8-</b> .002	1 (1.38)			1
		MET DIR 1			-		<del> </del> -
NO28HBF	038				1		<del> </del>
10 SRHBF	0,1	EORE . 008	010	(R)	I		<del> -</del>
	043 A	30 0 0 E	•00•	(SE)	1		0
	7 723			34245			5
	056 T	TORQUE 2 SCREWS TO 25 IN LB AND ASSURE SCREW MEANE ADD		424.5			6
	+						0
	050	CHECK NO 2 BRG HOUSING SEATING	-	41.45			0
	061 PL	PLUS GAGE INTO 10 OF SEAL AUT	*	WP			0
	064 TO	TORQUE NO 1 BRG HOUSING BOLTS		N/V			0_
NOZF IR	065 RE	RECORD MAN FIR		alu			<u></u>
0	071 CH	CHECK FOR . UGO CLEARANCE BETWEEN TURES AND FRAME		d/n			<u> -</u>
0	075 CH	CHECK NO 2 BRG SEATING	•	ND			<u> o</u>
3	2 72	FOR QUE NC 2 B 95 BCLTS	-	W.			0
	<del> </del>			, y			ا_ا
				<del></del>	<u></u>		

Figure C-1. EASR Card.

	TRANSFERED	HOM REASON							DATE INSP									_	
	FUNCT	┿	+		+	+		-	ENTERED										
	PENALTY							SPECIAL NOTES 10 BE CLEARED	MADE										
	TOTAL		-	-	-		1	NOTES	DATE CORPECTION MADE										
ANSFERS	SIA:AI DA.TE							SPECIA	DATE		1			 -	-		$\dagger$		
PART IZ	SIA	···							۵										
	SERIAL NO								ENTCRLD										
VENDOR	100						<del>  -</del>												
· · · · · · · · · · · · · · · · · · ·	SOMEONE LATORE								Š										
2	5	1															7	-	
DRAWING NUMBER								OCI & SPECIAL CHECKS						After ality of	O REIEASE	INA; ATLEASE	is Release		

Figure C-1. EABR Card (Concluded).

	?										
ğ	BOOK-FING	MOM	DATE		ENGINE ASSEMBLY		CONFIGU	JRAT	CONFIGURATION RECORD	ORD	
Z	CMBER	NOITAIS	ISSUED		WORK STATION DESCRIPTION	CRIPTION	1300%	5	2004 8112		
53	451-507	48686	09-02-77	_	FAN FRAME SZA	ļ				DRAWING NO 5.4	S'A SERIAL
PATA		G.E DRAWING NUMBER	UMBER	-3	NOMENCIATURE	PART POSITION	OIY.	2.0	VENDOR		
98	<del> </del>	MIL-L-25681C	-!		\$0-50 40LY	000000	+-		1000	3	21
NES	<del>+</del>	9155M67F01		+	NO 3 BEARING		_	<u> </u>	42444 4247£	**************************************	
9.8	<b>├</b>	459217-F6			BOLT-STA S	01121	1.5	i_	499	26	m
80	R584	R584P055L		İ	BOLT BRG 3+4	01122	12		****	M	
9.0	rs920	FS9208-10			BOLT STA S	01123	vč		XXXX		
80	#59321-PO	1-60		<del> </del> -	WASHER	01130	۵Z		XXXX	H H H H H H H H H H H H H H H H H H H	
g G	MZ 095	80450M2095			PKG PRFFOR	01152	-  -	+	XXXX	H H H H H H	
HAA	765¢M	7654M23Pp4		<del></del>	HO 3 B96 SEAL	01153	-	+-	111512	\$ : 2.2	†
i								-	14 44	S CHM 01269	1-
96	198 - 814 9Pij <u>5</u> A	0.5a		•	PKG PREFOR	01155	-	_!_	XXXXX	***	<del></del>
:	: 7596	50020:7596		<del> </del>	SEAL COMP INLE	01156			0.26.97	S	<del>-                                    </del>
?±	A14 9009M78627	7 862 7		<del>  -</del>	G/B ASSY INLET	0 300 0	-		<del>- j -</del>	_!_	7
32 32	n1374P015	0115		<del> </del>	BOLT	03050				11/A 00 203	
60	4496064161	1917		-	WASHER	03n30	1,	$\frac{1}{1}$	XXXX	, , , , , , , , , , , , , , , , , , ,	+
	40977K5904	. 4601			TUBE LUBE	00077	-	<del>-</del>	XXXX	××××	+
	90 6 LM 1 CGD 1	เตม 1		<u> </u>	MANTO LUGE	10077	-	•	50590	****	<del> </del> -
	2095745996	2095		1.2	MANIFOLD	20077	-		XXXXX	**************************************	+-
6			+	+	<del>+</del>			_	_	-	_

Figure C-2. EACR Card.

WORKSTATION MCGS6

CONTINUED ON NEXT PAGE

Gr 4174

YXXXXX

XXXX XXXX

44910

PRACKET BOLT

1002117906

8

BR MS9208-C7

XXXXXXX XXXXXXX

1556

CURE

**≈**0⊃

ŏ

S'A SERIAL NO

+		
115 COND HAIR HANDINGS 43 Spt 27 Valence Genetic	24.3c 7.1b. 7	
13 \$ 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		26 50 77
OPERATION ASSIGNMENT AND THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE STREET OF THE S		120 4245 95. Sme
42.45 42.45		120 4245 ATION IN HISAVY BLACK LIIAES
24 760		120 PEHATION IN 115.
e liver		SIGN OUT LAST UPEH

START FINISH INSP BAUGE INSPECTION AND DATE DATE		REMARKS		
INISH INSP BADGE	VSPECTION OPERATION BECORE	INSPECTOR HAVE		
1.5 ) . [ ] . [ ] . [ ] . [ ]		INISH INSP BADGE		

Figure C-2. EACR Card (Concluded).

ORIGINAL PAGE IS OF POOR QUALITY

## ONTARIO SERVICE SHOP

At the Ontario facility, a Quality Control Work Instrumention (QCWI DF015) was written and coordinated with NASA LeRC. The QCWI provided instrumentions on these specific items as applicable to the CF6 Diagnostic program.

Assembly/Disassembly Control
Rework Control
Workscope Definition
Nonconformance
Quality Planning
Auditing
Instrumentation Control (Safety)
Measuring and Test Equipment
Engine Test
Witnessing
Records
Failure Recording

To document the condition of the engine hardware, photographs were taken of the LPT shrouds and seals, representative HPT blades, LPT blades, compressor rotor, stator case, fan inlet guide vanes, CDP seal, HPT seals and shroud, HPT rotor, and HPT nozzles. These photographs were of high quality and are available for review.

Work orders were written to provide work direction for engine test, prep-to-test inspections and for assembly and disassembly instructions. Inspections as requested were witnessed by the designated DCAS representative.

Examples of the work documents as issued to the Test and Assembly personnel are presented in figures:

- Figure C-3 Test Operating Requirements Document
- Figure C-4 Prep-to-Test & Test Check-Off Sheet
- Figure C-5 Instrumentation Check Sheet
- Figure C-6 Inspection Check List
- Figure C-7 Work Order Sample
- Figure C-8 HPTR Blade Inspection Sheet

### GENERAL ELECTRIC COMPANY

AVIATION SERVICE OPERATION/ONTAR
WORK ORDER

RX H 5/8/71

Page 2 of 3 Pages

AMENDMENT NO

#### PERFORMANCE TESTS

#### 5.1 INBOUND TEST

THE FOLLOWING SECUENCE OF TESTING IS REQUIRED FOR THE CF6-6 TASK III ENGINE. THE TESTING WILL BE CONDUCTED IN THE ASO-CHTARIO CF6 TEST CELL WITH A LIGHTWEIGHT BELLMOUTH AND THE STANDARD CF6-6 / CCEPTANCE TEST COWLING CONFIGURATION.

- 1. INSTALL ENGINE IN THE CF6 TEST CELL AND SET UP PER CF6 SHOP MANUAL, 72-00-00 TESTING.
- 2. CHECK VARIABLE STATOR VANES COLD RIG, BUT DO NOT ADJUST UNLESS VSV TRACKS OUTSIDE OF THE OPEN LIMIT BY MORE THAN ONE DEGREE DURING ENGINE OPERATION. NO ADJUSTMENT IS TO BE MADE WITHOUT THE COND-CURRENCE OF ASE ENGINEERING.
- 3. INSTALL INSTRUMENTATION AS DEFINED BY THE INSTRUMENTATION PLAN FOR THE TASK 111 ENGINES.
- 4. CONDUCT THE FOLLOWING PERFORMANCE TEST:
  - a. PERFORM NORMAL PREFIRE CHECKS INCLUDING A LEAK CHECK.
  - b. START ENGINE AND STABILIZE FOR FIVE MINUTES AT GROUND IDLE.
  - C. SET THE FOLLOWING TWO STEADY-STATE DATA POINTS AND TAKE FULL DATA READINGS AFTER FOUR MINUTES STABLICIATION:

POWER SETTING	CORRECTED FAN SPEED
50%	76.42% (2623 rpm)
75%	90.111 (3093 TDP)

## NOTE: PERFORM FULL FUNCTIONAL TEST

- d. SLOW DECEL TO GROUND IDLE, AND ANALYZE THE TWO POINTS TO DETERMINE IF THE ENGINE CAN BE SAFETY OPERATED TO TAKEOFF POWER WITHOUT EXCEEDING ANY LIMITS (NZ. EGT. VSV). ALSO ASCERTAIN THAT ALL INSTRUMENTATION, INCLUDING THE RECORDER, IS FUNCTIONING PROPERLY.
- e. SET THE FOLLOWING STEADY-STATE DATA POINTS AND TAKE TWO BACK-TO-BACK DATA READINGS AFTER FOUR MINUTES STABILIZATION. THE ENGINE SW. NOT BE OPELLYED AT A WIMM CONTINUOUS POWER FOR A MINUTES PLAN TO SETTING THE FOLLOWING POINTS. TAKE ONE DATA READING AFTER SIX MINUTES.

104

PRODUCTION

Figure C-3. Test Operating Requirements Document

ORIGINAL PAGE IS OF POOR QUALITY

135

## GENERAL ELECTRIC COMPANY

AVIATION SERVICE OPERATION, ONTARI WORK ORDER

K. L. A. 5/8/78 AMENDMENT NO

Page 3 of 3 Pages

POWER SETTING	CORRECTED FAN SPEED
TAKEOFF	100.30% (3443 rpm)
MAXIMUM CONTINUOUS	98.70% (3388 rpm)
MAXIMUM CRUISE	95.85% (3190 rpm)
75\$	90.11% (3093 rpm)

f. SHUT DOWN FOR A MINIMUM OF 30 MINUTES AND THEN REPEAT STEPS b AND e.

#### 5.2 SPECIAL INSTRUCTIONS:

THE FOLLOWING SPECIAL INSTRUCTIONS APPLY FOR TESTING THE CF6-5D TASK III ENGINE:

- 1. GENERAL ELECTRIC-EVENDALE PERSONNEL WILL BE ON SITE AND WILL ASSURE DATA QUALITY BEFORE THE ENGINE CAN BE RELEASED FROM THE TEST CELL.
- 2. OBTAIN A FUEL LHV SAMPLE BETWEEN THE DUAL-PERFORMANCE POWER CALIBRATIONS. A BOMB CALORIMETER WILL BE USED TO CETAIN THE LHV.
- 3. NO PERFORMANCE DATA IS TO BE TAKEN WHEN VISIBLE PRECIPITATION EXISTS OR THE RELATIVE HUMIDITY EXCEEDS XXX 85%.
- 4. PRESSURE TRANSDUCERS, FUEL METERS, AND THE THRUST LOAD CELL MUST BE WITHIN FAA CALIBRATION LIMITS AND THE CALIBRATIONS REXTRACEABLE TO THE NATIONAL BUREAU OF STANDARDS.
- 5. AFTER FIRST INBOUND PERFORMANCE RUN, CLEAN FAN BLADES USING MCK. PERFORM ANOTHER SINGLE FERFORMANCE TEST.

RLA:mjs

PRODUCTION

Figure C-3. Test Operating Requirements Document - Concluded

W/O	CF6 PRED TO TEST	FORM NO. CF6-TEST-1 2/3/78		
	TEST CHECKOFF SHEET	Page 4 Of 8 Revision 21		
TEP	OPERATION	NECII. SIGNATURE DATE		HAND
	Engine mount bolts placed correctly, secured and lockwired. Front mount bolt		\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	ر ا
	Left bolt stretch '006" " 500 "	J. K.	,2 <sup>2</sup> 3	. 14
	Right bolt stretch .008"	30.12	<del></del>	
2.	Check accessory gearbox customer pads for proper installation of gear shaft	The second	(5.2°2)	ا ان ان
<b>m</b>	Check all engine mounts for proper installation and lockwired.	of the	<del></del>	6-22
4	Check all tequified vibration pickups for installation, leads connected to Litheir respective amplifier, lockwire. Check cooling air to T.R.F. pickup.	of while		3,0
re	Check throttle operation and for positive fuel abutoff in zero position of fuel shutoff lever.	Source of the	(22g)	12
9	Check both ignition systems for operation of plug.	The cone	(E2)	2
7.	Check air starter piping, secure clamp and lockwire.	Masone	0 -29	?
œ		Manc (	<u>ن</u> نوي:	7
6.	Check to see that specific gravity setting on M.F.C/ in -36-11 JP4 fuel is cased.	Thomas .	(E.23)	$_{n}^{\gamma}$
10	Visually check inlet instrumentation shoes/probes for condition and security.	$\bigvee$		-J.2
$\times$	See engineer rework instruction for steps the page. Vold sign-off for steps and modify por instruction on back of this page.	X		

PRICIPAL PAGE IS OF POOR QUALITY

figure C-4. CF6 Prep-to-Test and Test Checkoff Sheet.

FORM NO. CF6- TEST-3 12/12/73 Fage 1 Of 4 Revision 1	MECH INSP DATE	Miloson (P) 6-32->y	The state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the state of the s		2 - 2 (F) 6 - 25	3	1/2 (m) 63					1 1 1	(SS)	
ENGINE S/N 72/-50/ CF6-65-50  W/C 182560 INSTRUMENTATION CHECKLIST P	OPERATION	Check air starter for proper servicing.	Vibration: Pick-ups (Lockwire) A. Generals rear frame horizontal	The line of the location of the strut helow 9/o/c spilt	B. Turbino wear frame horz.	Location: 9 o/c, second & third bult holes fwd, of T.R.F. flange "v"	C. Fan rear stator case horizontal	Logation: 3 o/c fourth bolt above the upper ignition exciter.	D. No. one hearing - horizontal	Location: 4 o/c no. 4 fan exit strut below stator actuator.	Variable stator vane position ind.	Location: Transducer bracket at approx. 3 o/c on comp. front casing.	Check fig marks! Ref. LAASS T.R. #CT0/082	Synchronize indicator to read zero 1 0.005 volts full open - record full closed 4.74 1.01.5
u 3	Mari	Ţ	~		and to the square									

Figure C-5. CF6-6D, -50 Instrumentation Checklist,

6:22

Transducer bracket at V.B.V. - Bellerank at 9 0/c position. Check rig plate alignment har is centered in shaft cover "V" noteh: - synchrenize indicator to read 5.0 + 0.02 volts. Record

full open\_

Luckwire,

Variable bleed valve position ind.

Incat ion:

CF6-bg, -50 INSPECTION CHECKLIST

FORM NO. Q.C.-/32 3/10/76 Page 2 Of 3 Revision 3

TEM	Antas inspected	CLEAN	NOIMUE	CONTAM- INATED	INSP/MTE	1 ~
2.	Starter magnetic plug					TASKI JE TASKITE
	Starter valve filter					1
	Explain on squawk sheet, the condition of filters are to be clean prior to re-installation.	condition Installatio	Ē	Ny filiter that is contaminated. A Report any abnormal contamination	contaminate ni contami	ed. All
m' =	Inlet area for "FOD" & loome or missing hardware, overnil condition.	ardware, c	yerall con	alt lon.		1/2007
4.	Incoming check blocker doors; open close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close close c	closed [] (Check one).		If re-		X
5.	Fan Blator case & frame not including accessory gearbox area.	essory des	rbox area.			
9.		plumbing	- right har	d side,		
7.	fligh pressure compressor stator & related plumbing hand side.	թյանվանգ	- left			84,
e	Compressor rear frame - right half to forward side of fire-	ward side	of fire-			
6	Compressor Kear frame - left half to forward side of fireseal.	ard side o	f flreseal.			<u>,</u> 2.
10:	Compressor rear frame - right half aft of firegeal	[lreseal,				
11.	Compressor rear frame - left half aft of firegeal,	firegeal.	-			. 6
12.	Low pressure turbing module - right half.					(SS)
	Jow pressure turbine module - Jett half.					1 (1)
14.	low pressure exhaust including turbine reverner confeal nozzle.	verner or				
	Prep to ship; If received with blocker doors open, close them.	s open, cl	ose them.		X	
					•	, ·

Figure C-6. CF6-6D,-50 Inspection Checklist.

KCA. 5/12/78

#### REASSEMBLY

After all inspection checks are completed, rebuild the LPT module per the SM.

## 5. CORE ENGINE INSPECTIONS

Disassemble the engine as necessary to obtain the required data on the noted EMU's. Disassembly will be performed per the following sequence of events; visually inspect- EMU's to H.M.M.

NOTE 1: Photographs (detailed and overall) will be taken of each subassembly prior to its disassembly, with particular emphasis on
deteriorated parts, or any unique condition. Mogace
PHOTOGRAPHO NOTE 2: Prior to removal of the Stage L HPTN assembly, obtain drop
checks from the aft face of the CRF outer flange to the aft
face of Stage 1 HPTN vane outer platforms in 8 equally spaced
locations. At each location, obtain drops to both ends of each
segment (16 individual readings) Calebrate (1977)

- NOTE 3: Record inspection requirements on sheets supplied by Evendale engineer.
  - B. Split core engine away from fan module and route core to  $5/\mathrm{N}$ Remove HPT module.
  - C. Position-mark and remove Stage 2 HPTR blades. Remove stage nozzie.
  - D. Remove second stage nozzle, preserve the stage 2 blade retainer seal wire for engineering inspection.
  - E. Comply with Note 2 above (drop checks). Then remove the Stage 1 HPTN assembly.
  - F. Position-mark, then remove the 4B pressure balance seal (mininozzle).
  - G. Remove the CRF.
  - H. Remove the HPCS cases.
  - Send the HPC rotor to the rotor area.
- 4. HIGH PRESSURE TURBINE ROTCR (REFERENCE 72-53-00)
  - A. Install the rotor in the Runcut Fixture. Shim the blades per the SM, and measure each Stage 1 and 2 blade tip at 0.1 inch from the leading and trailing edges as follows:

1. Measure and record the radius of blade No. 1 0.1 inch from the LE of each stage. JWS

PRODUCTION

Figure C-7. Example of Work Order.

460/0-77775 pay, 5.34

140

ORIGINAL PAGE IS OF POOR QUALITY

STAGE / H	PTR BLACE	RUNOUT DATA
-----------	-----------	-------------

	RUNAUT	's TAK	EN A	100	PRAM L	E- p.	10 TE	E EAC	A BLADE
No.	Fno.	AFF	No.	Fws	AF	1/2	Fno	95-	No. FNO AFT
	000	000	28	003	+ 05	5-	-1001	000	Pi + 002 + 007
2	1.002	4.003	29	003	+.00/	56	002	+ 001	P3 -001 + c05
3	003	7.001	30	000	+.005	57	000	+ .003	84 000 + 008
4	4.001	4.006	31	- 004	4.003	12	001	4.006	- · · · · · · · · · · · · · · · · · · ·
-5	002	001	3:	000	+ .008	59	001	4.002	26 +001 +07
	+ .003	+.005	33	004	001	10	002	+ .004	27 + 201 + 207
7	002	001	34	000	+ .004	61	- 002	+ 002	2:0 + 100 - 05
2	+.002	+.005	35	002	+ .001	62	000	+.005	89 - 002 + 008
Ĵ	003	001	136	000	+ 005	6.7	000	+ .003	90 - 003 + 000
10	001	+.005	37	008	003	14	+.001	4 005	7/ 4.001 4 OOL
11	- 004	- 002	نهو	- 002	+ .004	6.	000	+.001	72 + 002 + 000
12	000	4.005	19	- 004	006	66	001	4.005	924.0034.023
13	002	003	40	402	¥ 006	67	400	001	74 000 4.002
14	4.001	4.004	41	- 004	7.002	62	001	7.004	7- 000 + OK
150	002	000	42	001	1.007	62	100	- 001	76 - w2 + x7
16	7.001	+.004	43	- 202	+ 000	70	+.002	+.004	97 -001 +105
17	-:00"	- 002	44	- 001	4.005	12/	- 001	000	90 - 006 + m7
10	4.002	+.003	45	006	+ 002	124	+.002	+.005	+y - UU + 1:06
13	- 1001	1001	46	- 004	+ .004	77	200	+ 001	100 - 004 - 006
دد	+.002	+.005	47	1001	+ 003	74	+.003	+ 008	101 000 + 0101
÷/	002	- 004	40	+ .002	+.0e5	12:	7.001	001	102 - 003 + 009
2 3	+.001	+ 002	49	- 003	1 .002	76	t 003	+ 005	10 102 + 018
تنا	002	001	50	+.002	+ 000	77	0,00	000	104 - 404 4.008
4	7.002	+.004	51	- 002	000	72	+.002	r 007	105-0657 068
كف	002	4.001	خكا	7.002	¥ .006	72	7.002	7.001	106 - 006 + 006
26	000	+.005	53	+ 001	7.001	20	7 002	7 006	107-00 000
127	- 004	+·001	54	000	F 005	18/	1.001	7.001	120 - 609 + 002

RADIUS AT = 1 = 16.560 " AFT=16.566

FNO. MAX = 16.563 MIN - 16.552 Are = 16.559
APT MAX - 16.576 MIN - 16.562 Are = 16.570

Figure C-8. HPTR Blade Inspection Sheet

ORIGINAL PAGE IS OF POOR QUALITY

# APPENDIX D

# SYMBOLS AND ACRONYMS

A4	Stage 1 High Pressure Turbine Nozzle Area
A54	Stage 1 Low Pressure Turbine Nozzle Area
AAL	American Airlines
A/C	Aircraft
ACEE	Aircraft Energy Efficiency Program
ACT	Actual
ADAS	Automatic Data Acquisition System
ALF	Aft Looking Forward
ASO/0	Aviation Service Operation/Ontario, California
C-A	Chromel-Alumel (Thermocouple)
C-C	Copper-Constantan (Thermocouple)
CDP	Compressor Discharge Pressure
CRF	Compressor Rear Frame
CSN	Cycles Since New
CSO	Cycles Since Overhaul
CW	Clockwise
DACo	Douglas Aircraft Company
DELT5X	Delta Exhaust Gas Temperature (Calculated-Indicated)
EABR	Engine Assembly Build Record
EACR	Engine Assembly Configuration Record
ECI	Engine Compo ent Improvement Programs
EGT	Exhaust Gas Temperature
EGTM	Exhaust Gas Temperature Margin
EMU	Engine Maintenance Unit
EPR	Engine Pressure Ratio
ESN	Engine Serial Number

# SYMBOLS AND ACRONYMS - Continued

ETAC High Pressure Compressor Efficiency

ETALPS Low Pressure System Efficiency

ETAT High Pressure Turbine Efficiency

FAA Federal Aviation Administration

FG Load Cell Thrust
F/N Fuselage Number

FN at N1 Net Thrust at Constant Fan Speed

FOD Foreign Object Damage

FPCCM Flight Planning and Cruise Control Manual

FPS Feet Per Second

GE General Electric Company

GPM Gallons Per Minute

HP High Pressure

HPC High Pressure Compressor

HPCR High Pressure Compressor Rotor
HPCS High Pressure Compressor Stator

HPT High Pressure Turbine

HPTN High Pressure Turbine Nozzle
HPTR High Pressure Turbine Rotor

HUM Humidity

IDR Instrumentation Data Room

LE Leading Edge

LHV Fuel Lower Heating Valve

LP Low Pressure

LPT Low Pressure Turbine

LPTN Low Pressure Turbine Nozzle

LPTR Low Pressure Turbine Rotor

LPTS Low Pressure Turbine Stator

M/C, MCT Maximum Continuous Thrust

MAX Maximum
MIN Minimum
N1 Fan Speed

N1K Fan Speed, Corrected

# SYMBOLS AND ACRONYMS - Continued

N2 Core Speed

N2K Core Speed, Corrected

NASA National Aeronautics and Space Administration

NO.4B Number 4 Ball Bearing

P49 Low Pressure Turbine Inlet Total Pressure

PARAS Parasitics

PBAR Barometric Pressure

PDS Portable Digital Subsystem

P/N Part Number

PPH Pounds Per Hour

PPS Pounds Per Second

PSO Cell Static Pressure

PS2 Fan Inlet Static Pressure

PS3 Compressor Discharge Static Pressure

PSF Pounds Per Square Foot

PSIA Pounds Per Square Inch Absolute

PSIG Pounds Per Square Inch Gauge

PT2 Fan Inlet Total Pressure

R<sup>2</sup> Coefficient of Determination

Y/O Runout

RPM Revolutions Per Minute

SFC Specific Fuel Consumption at Constant Thrust

SGSAM Fuel Sample Specific Gravity

SEE Standard Error of Estimate

SI International System of Units (Metric)

SL Sea Level

SLS Sea Level Static

SM, S/M Shop Manual

S/N Serial Number

SPEC Specification

STA Station

STG Stage

T2 Ambient Temperature

## SYMBOLS AND ACRONYMS - Concluded

T3 Compressor Discharge Total Temperature

T51 Indicated Exhaust Gas Temperature

T5X Calculated Exhaust Gas Temperature

TC Thermocouple

TE Trailing Edge

TF Fuel Temperature

TFF2 Low Pressure Turbine Flow Function (Area)

TMF Turbine Midframe

T/0, TO Takeoff

TRF Turbine Rear Frame

TSAMP Fuel Sample Temperature

TSN Time Since New

TSO Time Since Overhaul

VIDAR Data Recording System at General Electric/Ontario

VSV Variable Stator Vane

WFK Fuel Flow Corrected

WFM Fuel Flow, Main

WFV Fuel Flow, Verification

Δ Delta

η Efficiency

 $\mu$  inco AA Microinch, Arithmetic Average

σ Standard Deviation