NASA-TM-107974



#### JUHNSON IN-12-CR

## 3rd SEI TECHNICAL INTERCHANGE Proceedings

1.2



(NASA-TM-107974) THIRD SEI TECHNICAL INTERCHANGE: PROCEEDINGS (NASA) 60₽ p N92-33309 --THRU--N92-33349 Unclas

G3/12 0115500

Sponsored by the



and the Univ. of Houston Clear Lake

3rd Technical Interchange Meeting May 5 & 6 1992

Coordinated by Doug Peterson (713)283-5556

National Aeronautics and Space Administration

Lyndon B. Johnson Space Center Houston, Texas 77058



Reply to Attn of

XA

Dear Colleague:

Thank you for your participation in the 3rd SEI Technical Interchange held May 5 & 6 in Houston. We continue to be very pleased with these meetings and your feedback suggests that you also feel the interchange is valuable. SEI and NASA management as well as those in Congress see this type of "outreach" activity as an important part of the overall planning, analysis and decision making process for future programs. The whole spectrum of new concepts, alternatives and options must be identified and reviewed to enable the critical decisions required to undertake challenging SEI goals.

This meeting with over 300 participants from about 100 different organizations brings together the dispersed supporters of SEI to begin building the team necessary for the long-term. The interaction between industry, academia, and government organizations including DoE, DoD, and NASA provides the focus for working closer together on SEI related activities.

This book of proceedings should capture the "black and white" of the meeting to provide a record for on-going activities. Hopefully the material within will be as valuable to you as it is to those in the Exploration Programs Office and other SEI organizations.

Thanks again for your participation.

Sincerely,

4-Douglas R. Cooke

Manager, Exploration Programs Office

ORIGINAL PAGE IS OF POOR QUALITY

# 3rd Space Exploration InitiativeTechnical Interchange Hosted by the Exploration Programs Office

NASA



Υ¦

্য	Tuesday, May 5, 1992		Wednesday, May 6, 1992
8:30 a.m.	Welcome Dr. James Lester, Interim Dean, School of Natural and Applied Sciences, UH-CL Meeting Objectives and Near-Term Activities Doug Cooke, Manager, Exploration Programs Office (ExPO)	8:00 a.m.	Second Series of Short Technical Subject Presentations, followed by splinter sessions on FLO mission overview, surface systems, space transportation, risk, science, habitats, and Artemis
9:00 a.m.	SEI Master Plan	9:30 a.m.	Break
9:15 a.m.	Dwayne Weary, ExPO 1 57	9:50 a.m.	<b>Organizational Change: Incentives and Resistance</b> Dr. Peter Bishop, UH-CL, Studies of the Future 1615
9:30 a.m.	Mike Conley, ExPO 9-2 Artemis, the common lunar lander, an update	10:10 a.m.	,
9.30 a.m.	Steve Bailey, New Initiatives Office, JSC 16-53		David Peterson, Ventana Systems, Inc.
9:45 a.m.	Science Themes for Early Robotic Missions: LPI Workshops Paul Spudis, Lunar and Planetary Institute $40 \varsigma_{j}$	10:40 a.m.	DOD Acquisition Streamlining Initiatives Jesse Stewart, Defense Systems Management College 178 5; 2
10:00 a.m.	Break	11:00 a.m.	<b>SEI Management and implementation</b> Hum Mandell, ExPO 206 <sup></sup>
10:20 a.m.	Review of Rover/Mobility Systems Workshop Dave Weaver, ExPO 49.55	11:30 a.m.	Streamlined NASA Acquisition Gene Easley, Director of Procurement, JSC
10:35 a.m.	FLO Mission OverviewB. Kent Joosten, ExPO59 5	12:00 p.m.	
11:05 a.m.	FLO Science and Payloads Dave McKay, Solar System Exploration Div, JSC 75-5-7	1:00 p.m.	Effecting Workforce/Cultural Change Richard Grant, Boeing 207¢
11:35 a.m.		1:30 p.m.	A. Guastalerro, Lockheed 2120,3
12:00 p.m.	Lunch	2:00 p.m.	Skunk Works Type Approach for F-SAT Gary Tumer, Lockfieed 228-54
1:00 p.m.	<b>The Space Exploration Initiative</b> — — — — — — — — — — — — — — — — — — —	2:30 p.m.	Single Stage Bocket Technology Programe
2:00 p.m.	FLO Surface Systems Concepts and Issues John Connolly, New Initiatives Office, JSC —		Paul Klevatt, McDonnell Douglas, SSRT Program 239
2:20 p.m.	FLO Lunar Habitat Concepts and Issues Molly Elrod, Marshall Space Flight Center 139,29	3:00 p.m.	MTS Report on New Ways of Doing Business Bruce McCandless II, Martin Marietta
2:40 0 0		3:30 p.m.	Break
2.40 p.m.	FLO Earth-to-Orbit Concepts and Issues Gene Austin, Marshall Space Flight Center 150 Srco	4:00 p.m.	Science and Payloads Session Report Session Leads
3:00 p.m.	Break -70	4:15 p.m.	Surface Systems Session Report Session Leads
3:15 p.m.	First Series of Short Technical Presentations	4:25 p.m.	
5:00 p.m.	Adjourn	4:35 p.m.	

#### CONTENTS - continued

Main Auditorium

Main Auditorium		s .
First Series of 5 min. Tec	ch Briefings Tuesday 3:30 pm	to 5:15 pm
1. Steve Jolly lunar shelter construct		274 <i>5</i> 16
2. Milton Schwartz lunar base concept	LANL	<sup>284</sup> <i>5</i> <sub>17</sub>
3. Gerald Leigh Center for Extra-terres		303 518
4. John Schuster cryogenic storage	General Dynamics	317 <i>51</i>
5. Willy Sadeh inflatable structures f		336 omi T
6. Dave Criswell lunar pwr sys's relevar		3475:20
7. Maribeth Hunt dynamic isotope power f	-	364 <i>5</i> 2/
8. Jerry Peterson thermoelectric nuclear	GE pwr sys's for SEI	373 222
9. Robert Burke lasers for power beamin		386523
10.Gerald Falbel Moon as a solar power s		406524
11.Stan Borowski "Fast Track" lunar NTR	LeRC	421 525
12.Steve Howe NTR for FY 2000: a DOE	LANL perspective	437526
Second Series of 5 min. Te	ch Briefings Wednesday 8:00	am to 9:30 am
1. Bryce Relmer SDIO propulsion techno	Aerojet blogy for SEI	445527
2. Robert Sackhelm low cost booster syste	TRW m for LEO	460 5 <sub>2</sub> 8

3. Mike Jordan Mitre  $4715_29$  space network for lunar communications

- 4. Don Brown NASA/JSC/EG  $4835_{30}$  network quality function deployment avionics
- 5. Hatem Nasr Honeywell 48951 off the shelf avionics for future SEI missions

6.	Dana Andrews common modules for SEI		498.532
7.	John Hodge multi-stage lander; st		507533
8.	Dave Plachta benefits of cryo vs. s	LeRC torable for return	522 <i>534</i>
9.	Larry Schooley self contained module n		540535
10.	Donald Curry crew module TPS design		555_536
11.	Carolyn Cooley habitat design and hal	Martin Marietta bitability test facility	570537
12.	Rob Meyerson Earth landing options	JSC EG	577 538
13.	Bradley Salles pneumatically erected ;		592 339
14.	Bill Rochelle plume induced environma		597 540

### NASA

-<u>-</u>-\_\_\_

### **Space Exploration InitiativeTechnical Interchange**

Hosted by the Exploration Programs Office



<u>Main Auditorium</u> First Series of 5 min, Tech Briefings Ti	uesday 3:30p.m to 5:15 p.m.	Main Auditorium Second Series of 5 min. Tech Briefings Wedne	esday_8:00 a.m. to 9:30 a.m.
1 Steve Jolly Ctr for Sp Const.	8 Maribeth Hunt Rockwell-Rocketdyne	1 Bryce Reimer Aerojet	8 Dave Plachta LeRC
Junar shelter construction analysis	dynamic isotope power for FLO	SDIO propulsion technology for SEI	benefits of crycess. storebie for return
2 Milton Schwartz LANL	<b>9 Jerry Peterson</b> GE	2 Robert Sackheim TRW	9 Larry Schooley 5 b Eng. Res Ctr
lunar base concept	thermoelectric nuclear pwr sys's for SEI	low cost booster system for LEO	self contained module meterials processing
3 Geraid Leigh U. N. M	10 Robert Burke Rockwell-Rocketdyne	3 Mike Jordan Mitre	10 Donald Curry JSC/ES3
Center for Extra-terrestrial Eng/Const.	lasers for power beaming	space network for lunar communications	crew module TPS design sensitivities
4 Ray Leonard LANL	<b>11 Geraid Faibel</b> Consultant	4 Don Brown NASA/JSC/EG	11 Carolyn Cooley Martin Marietta
innovative radiation shields	Moon as a solar power satellite	network quality function deployment - avionics	habitat design and habitability test facility
5 Willy Sadeh Colorado St U	12 Roger Lenard Phillips Lab	5 Hatem Nasr Honeywell	<b>12 Rob Meyerson</b> JSC EG
inflatable structures for a lunar base	nuclear propulsion for lunar operations	off the shelf avionics for future SEI missions	Earth landing options
6 Costas Cassapakis L'Garde Inc.	13 Stan Borowski LeRC	6 Dana Andrews Boeing	13 Gordon Woodcock Boeing
advances in large inflatable structures	"Fast Track" lunar NTR	common modules for SEI, ACRV, & LPLS	intg'd sys's for direct mode lunar operations
7 Dave Criswell U. of Houston	14 Steve Howe LANL	7 John Hodge Martin Marietta	14 Bradley Sallee Tracor
Junar pwr sys's relevance to landers	NTR for FY 2000: a DOE perspective	multi-stage lander; storable vs. cryo	pneumatically erected rigid habitat

#### Technical Splinter Sessions Wednesday, May 6

Room 2-311	9:30 a.m.	<u>11:00 a.m.</u>	1:00 p.m.
	MISSION OVERVIEW (Kent Joosten) General FLO discussion Initial Capability: Is it enough? Supportability Issues. EVA Emphasis Evolution: Can it happen? Paths Timescales Earth landing alternatives Mission operations approaches Navigation and communication	Surface Systems and Rovers (Cab Calloway) General FLO Discussion Resupply Rover designs Habitat designs Overall operational philosophy Science/ISRU Operations on the surface	Space Transportation and Lander (Ron Kahl) General FLO Discussion Earth landing alternatives and systems- land or water Ascent vehicle propulsion optimization Reusable vs. expendable crew module design Radiation protection implementations and capabilities Lunar landing risk mitigation Fire in the hole assessment for return stage Weight reduction methods-lightweight materials, TPS Risk vs. performance of return stage alternatives
Room 1-417	9:30 a.m.	<u>11:00 a.m.</u>	1:00 p.m.
	Science & Payloads (Dave McKay)	Artemis (D. Weav <sup>e</sup> r/S. Balley)	Lunar Habitat (Molly Elrod)
	General FLO Discussion Site Selection Criteria Power/Comm accommodations for surface science payloads Robotic rovers support to manned exploration traverses Safety issues w/ extended pressurized rover exploration EVA's Science in FLO-How are we doing?	General discussion Payloads Objectives Priorities Interfaces Schedules Relationship to FLO	General FLO Discussion Lightweight structure materials radiation protection requirements and concepts
Room 2-518	9:30 a.m.	Open for ad hoc splinter	sessions
5/3/92	Review of survey results		NASA-ISC



## SEI Reference Mission

#### Presented at the ExPO Technical Interchange Meeting

May 5, 1992

## NV2V

**Reference Mission Statement** 



Expand human presence to the moon and Mars to enhance our understanding of the universe, to seek terrestrial benefits from this exploration, and to establish the beginnings of a sustainable spacefaring civilization.

## Approach

Encourage wide participation in the Initiative and aggressively pursue a broad set of exploration goals, while assuring the basic objectives of enabling a human return to the Moon as early as 1999 and human missions to Mars as early as 2005.




ĩ., st.

- □ The SEI actually involves the simultaneous pursuit of two highly interactive tracks of activity, i.e.
  - "Return to the Moon to Stay", and
  - "Human Exploration of Mars".
- To implement the SEI, the concept of incremental programmatic milestones will be employed. These milestones are a series of major decision events affecting the emphasis and scope of the Initiative as time advances.
  - Permits more detailed planning and analysis of the initial capabilities based on
  - the more general definition of subsequent <u>potential</u> SEI programmatic milestones.

## **NASA** Phased Definition of Initial Programmatic Milestones and Follow-on Capabilities







Aggressively pursue development of concepts for early missions and flight hardware that:


- Are significant achievements
- Are phased to fit within available funding
- Contribute to the infrastructure necessary for support of follow-on waypoint capabilities
- Provide flexibility for downstream decisions and implementation choices based on:
  - Operational Experience
  - Test Data
  - Technology Developments
  - Engineering Analysis
  - Mission Discoveries
  - Available Budget
  - National Imperatives
- Encourage investment in additional infrastructure, technologies, and achievements
- Contribute to the goals of timely human and robotic exploration of the moon and Mars

S

## NV2V

#### SEI Reference Mission Scenario - Lunar Mission Timeline -






\* NOTE: Current HLLV planning (i.e. NLS) does not support this plan.

9

NASA

## **FLO Evolution Options**






 Resource extraction at demo level

J

## NV2V

#### SEI Reference Mission Scenario - Mars Mission Timeline -





00

1.




## Lunar Resource Mapper /

## Lunar Geodetic Scout

## **Program Status**

**3rd Space Exploration Initiative** 

**Technical Interchange** 



April 5, 1992

Ĺ.

## **NASA** Lunar Orbital Science & Engineering



- 1. Global elemental composition (much higher priority than all others)
- 2. Global gravity & topography
- 3. Global mineralogy
- 4. Global imaging
- 5. Global magnetics
- 6. Global atmospherics
- 7. Global heat flow

This ranking is based purely on science priorities, and may not reflect exploration architecture needs.

#### Space Exploration Initiative priorities

- 1. Global elemental and mineralogical composition (much higher priority than all others)
- 2. Global gravity & topography
- 3. Global imaging







## Why is a lunar orbiting mission attractive to SEI?



#### □ Science

• Provides a wealth of fundamental scientific knowledge of the Moon

#### Resource characterization and location

• Provides a detailed geochemical map of the Moon - Fundamental to utilizing the local resources to reduce the cost of exploration

#### Technology and Engineering

- Provides an improved gravity model A key element in precision landing and long-duration orbital missions
- Provides improved surface imaging Site selection
- Improved topographic knowledge for outpost design/emplacement

12

## LRM/LGS Program Office



- Lunar Orbiter Programs managed at JSC
- Two orbiter missions planned
  - Lunar Resource Mapper (LRM) launch, March 1995
  - Lunar Geodetic Scout (LGS) launch, early 1996
- Both vehicles small spacecrafts ~ 1000 kg
- Each mission collecting specific data sets to be used for landing site selection
  - Elemental and mineralogical (LRM)
  - Geodetic map, lunar gravity model and global stereo imaging (LGS)
- Experiment selection based on ability for the instrument provider to satisfy mission objectives defined in the LPI working group and Lunar



1

#### **SELECTION PROCESS**

Based	on	SEI	Information	Needs
-------	----	-----	-------------	-------

Criteria are Cost, Schedule, Performance

LPI Workshop Screened Potential Instruments

**Currently Reviewing Candidates** 

- -- Soft Xray, Gamma Ray & Neutron Spectrometers
- -- Imaging Spectrometers

First Series of Reviews Completed


Second Phase/Programmatic Reviews This Month


Instrument Selection Early June

Second Flight Screening to Start July

## **Major Milestones**







#### LRM/LGS Program Office NASA Organization Manager M. Conley (713) 283-5554 Business **Program Scientist** Management D. Morrison M. Nebrig (713) 483-5039 (713) 283-5536 Schedules Instrument Selection Mission Science Requirements Resources Science Lead for Operations Documentation Planetary Data System Launch Vehicle Engineering **Operations** Integration **B**. Drake B. Ward E. Švrcek (713) 283-5313 (713) 283-5758 (713) 283-5751 Delta II Spacecraft Com./Control (DSN) Instrument Integration **Payload Operations** Pallet Integration **Mission Operations** Ground Systems Data Reduction **Mission Planning** Instrument Development





ŝ



## Artemis Common Lunar Lander Project Status

## **SEI Technical Interchange**

May 5, 1992 Houston, Texas N92-33312

**NASA** Johnson Space Center


17

## Introduction



- Mike Griffin's plans are to start the SEI with lunar robotic missions that can demonstrate NASA culture change and provide a catalyst for human exploration of the Moon and Mars
- The Artemis Common Lunar Lander Concept developed by JSC has been accepted by Mike Griffin as the centerpiece of this lunar robotic exploration program, JSC proposes to develop the Lander in-house
- Aaron Cohen strongly supports the Artemis proposal
- Program new start (Phase C/D funding) is anticipated in FY '94
- First Launch as early as 4th quarter of 1996
- A JSC civil service design study is underway which will develop a Project Plan for the development of the Artemis Lander

New Initiatives Office



**NASA** Johnson Space Center

19

## Background Headquarters Perspective



"The Common Lunar Lander is exactly the kind of thinking we need to get the Exploration Initiative started and get some early missions going back to the moon."


Mike Griffin (Space News - Nov. 11-18)


"You can buy these by the yard and do that well into the next century ... It will be a long time before we can afford to send men everywhere on the Moon."

Mike Griffin (Aviation Week - Dec 2)

A principle goal of the Artemis Lander is to safely extend the reach of humans to areas of the lunar surface that would otherwise be inaccessible due to cost or risk.

New Initiatives Office






## Lander Value as a Function of Payload Mass



"Goodness" Relative Value to SE



NASA Johnson Space Center

## **Approach for JSC In-House Study**

- Used a small, in-house study team focusing on the lander
  - New Initiatives
  - Engineering
  - Administration
  - Safety, Reliability and Quality Assurance
  - Mission Operations
  - Center Operations
  - Human Resources
  - White Sands Test Facility
- Developed Baseline Concept Design which provides:
  - Mass and performance model
  - Baseline subsystem design and development models
  - Interface and requirements analysis model
  - Basis for preliminary cost estimates



• NASA Johnson Space Center

## **Approach (Cont)**

- Released a series of Commerce Business Daily announcements
  - Seeking an open dialog with industry on concepts & implementation
  - Seeking "off-the-shelf" components and assemblies which could support lander development
  - Building a database of potential vendors
- Primary objective was to develop the best possible estimates of cost, schedule and Center resources required for lander development
- Cost estimates generated from the bottoms-up
  - Tasks, level of effort, schedule relationships, equipment, materials, facilities and other costs generated from a series of interviews with all disciplines
  - All information captured for analysis and manipulation in the form
     of an Engineering Master Schedule (EMS)

**NASA** Johnson Space Center


## Technical Summary - Requirements -



Guidelines:	Priorities:	Derived Guidelines:
Small	Schedule	Use off-the-shelf hardware
<ul><li>Simple</li><li>Cheap</li></ul>	<ul> <li>Cost</li> <li>Risk</li> </ul>	<ul> <li>Avoid block redundancy where single string is adequate</li> </ul>
Quick	Performance	Challenge culture where required to achieve project goals

- Requirements
  - Land at any latitude and longitude
  - Capture into lunar orbit prior to descent
  - First launch by June 1996, assuming 1993 new start
  - Architecture:
    - Launch vehicle is McDonnell Douglas Delta II 7925
    - Lander is a single stage spacecraft
    - Employ pulse mode engines in order to avoid new engine development
  - Best possible payload given the above constraints

New Initiatives Office




## **Growth Option from Reference Design**



Delta II 7925 64 kg payload

- Single Stage
- Lander provides Trans Lunar Injection (TLI) attitude control
- Lander performs portion of TLI
- Lander performs Lunar Orbit Insertion (LOI)
- Lander performs
   descent from orbit





Atlas II


## **Atlas II Version**


- >150 kg payload
- Two Stage
- Same Lander w/ some scarring for LOI solid motor
- Centaur does an accurate TLI
- Lander is passive throughout TLI
- Solid Rocket motor performs LOI
- Lander trims LOI, and performs descent from orbit


Delta II

















NASA Johnson Space Center

## Delta II 7925 Launch



**Evaluation of single stage reference design** 

- Performance is acceptable ~ 64 kg
- Margins are trim but adequate ~ 56 kg
- A growth option to add an LOI strap-on solid motor exists
- Further avionics mass reduction may be possible through the integration or elimination of functions
- "Off the shelf" goal an implementation driver, significant level of development is required none the less
- Delta's third stage is a spin stabilized solid rocket motor (Star 48B)
- We decided to eliminate the spin table and nutation damping system and to provide attitude control during the TLI burn
  - Payloads have unknown properties
  - Our lander is a 3-axis spacecraft not a natural spinner
- Main engines used for TLI attitude control (similar to Magellan S/C)
  - Outboard engine mounting locations required for attitude control

Stephen Bailey/IE3/(713)283-5411

S

New Initiatives Office

# **Delta II 7925 Considerations (Cont)**

- However outboard engine valve and propellant line heaters are required - a major driver for power requirements (over 100 watts continuous)
  - Spin stabilization may allow better engine selection/location relative to thermal mass in tanks to reduce power consumption
  - Solid rocket dispersions would probably require that main engine lines be wet for significant post-TLI midcourse burn in any case
  - Therefore propellant lines for this architecture must be wet at TLI
- If heater power requirements are reduced, it is possible that primary batteries could replace the solar arrays completely
  - A significant cost and complexity reduction
  - Propellant lines must be kept dry until LOI
- The Atlas' Centaur upper stage is a highly accurate 3 axis stage
  - Post TLI midcourse budget may be low enough that it could be performed with ACS engines - keeping main propellant lines dry until LOI for any main engine selection

NASA Johnson Space Center -

### **Delta II 7925 Considerations (Cont)**


- A series of mass reduction activities are under way
  - High performance engine options
    - Acquisition of test engine (SDI heritage) underway
    - Test will focus on extending operational life to meet our reqts
  - Avionics options
    - Acquisition of evaluation avionics underway
    - Evaluation will focus on trying to consolidate as many avionics functions into a compact system as possible
    - Has strong secondary influence on power consumption and associated mass reduction
- These mass reduction options may yield a considerably lower parasitic mass fraction which would enable a payload in the 200 kg range to be flown on a one stage, Delta-launched spacecraft
  - Time and detailed engineering analysis will tell...

37

### **FLO Evolution Options**

NASA







- JSC as the lead center for exploration must pursue and implement the SEI, the central vision of the Agency
- Builds the talent, knowledge and capability of our people
  - "Perform selected in-house projects..."
  - "Perform selected precursor activities..."
  - Strengthens requirements and project management capabilities
  - Create experience wedge for future exploration missions
  - Emphasize the role of civil servants early in the project
- Helps to establish requirements for human exploration
- Will help prepare us for living and working on the moon

ယ စ

New Initiatives Office

	NASA Johnson Space Center
	Conclusions
•	We expect to produce a Project Plan which can be supported by Mike Griffin and the Johnson Space Center
•	We are proceeding with the expectation of a funding commitment at the beginning of FY '94, and are aiming for a 1996 launch
•	<ul> <li>Final architecture and launch vehicle decisions have yet to be made</li> <li>System trades will lead to final architecture and launch vehicle</li> </ul>
٠	selections are anticipated near the end of summer Component level make/buy decisions as well as procurement strategy will depend in part on the response of industry to an ongoing review of the design in progress - mailing now underway
	<ul> <li>We encourage proposals to supply items at all levels from single components to integrated assemblies, subsystems or systems</li> </ul>

 We welcome review from Industry, other NASA Centers, and other Government Agencies with spacecraft development experience — Lunar and Planetary Institute -

# Science Themes for Early Robotic Missions: LPI Workshops

Paul D. Spudis

Lunar and Planetary Institute

Presented to 3rd SEI Technical Interchange

8 N 9

ယ

හ යා

Houston, Texas

May 5, 1992

40

– Lunar and Planetary Institute -

# Office of Exploration Precursor Mission "Themes"

### **Lunar Resources**

global, regional, and site compositions and states

### Lunar Terrain

topography and morphology

**Lunar Gravity** 

location and magnitude of "anomalies"

Lunar surface lander

soft-landed exploration payloads

- Lunar and Planetary Institute -

# Workshop on Early Robotic Missions to the Moon

- Sought to evaluate technical readiness and scientific return from instruments to be flown in lunar orbit or operated on the lunar surface
- Held at the LPI on February 4-6, 1992
- 31 workshop members represented broad cross-section of science community likely to be active in SEI scientific program
- Workshop used "advocate" system to understand technical issues on equal basis
- 60 submissions; 30 orbital and 30 landed payloads or mission concepts
- Orbital concepts evaluated on basis of instrument maturity and degree to which they met LEXSWG orbital measurement requirements; landed payload science requirements still being defined

4/27/92

- Lunar and Planetary Institute -

# Workshop on Early Robotic Missions to the Moon

**Orbital Mission 2 - Theme: Lunar Terrain** 

- Laser altimeter

- Gravity experiment, with subsatellite for far side gravity
- Imaging system; global stereo coverage, 15 m/pixel resolution

Lander Mission 1 - Surface rover(s)

- Alpha particle backscatter for chemical analysis
- Mossbauer spectrometer for mineralogical data
- Stereo, high-resolution imaging
- Other instruments (e.g., evolved gas analyzer) as resources permit

4/27/92

43 ×

*— Lunar and Planetary Institute* 

# Lunar Geoscience Explorer

*Theme:* Explore the Moon, picking up where Apollo left off and capitalizing on its discoveries

Site: Hadley-Apennines, Apollo 15 site, 26 N, 3 E

Instruments: stereo, high-resolution color imaging, imaging spectrometer, XRF/XRD/Mossbauer spectrometers, gamma-ray/neutron spectrometer, laser breakdown spectrometer (if possible)

Operations: land at LM site for LDEF investigation. Traverses to North Complex, into and out of Rille (studying stratigraphy), up slope of Hadley Delta massif to Silver Spur

27/92



2

1.

. 92-333

6

# Artemis Program

Rover/Mobility Systems Workshop Results -

### NASA ExPO Technical Interchange Meeting

May 5, 1992



- Establish a set of viable rover capabilities and concepts as a function of delivered size.
  - Constrain to a 1997 launch
  - Artemis delivery capabilities of 65 kg and 200 kg

(Rough estimate is that the rover mechanisms will utilize ~60% of the landed mass and the rover science instruments and payloads comprise the remaining 40%.)

- Address science/payload support requirements.
- Define potential complete Artemis missions:.
  - 65 kg class (single/multiple rovers)
  - 200 kg class (single/multiple rovers)
- Develop cost boundaries and development critical paths.
- Educate ExPO and science community on rover capabilities and limitations.

#### Mission Theme: Outpost site survey and resource assessment

Landing site: Mare Tranquillitatis, highest Ti maria near 15 N, 22 E

- Survey and characterize a potential outpost site on the Moon.
- Large-scale topographic maps/high-resolution stereo imaging
- Surface soil properties, block distributions, and lateral variability will be mapped during rover traverses
- Characterize in situ hydrogen abundance and its variation over a 2 km square grid.
- Vertical distribution of hydrogen in the regolith will be inferred by measuring its concentration in the ejecta of fresh, small craters (20 - 50 m diameter).


Weaver/Artemis/Rover Conference 5/5/92

### NASA Lunar Rover/Mobility Systems Workshop - Workshop Results -

- Viable mobility systems appear to be capable of supporting a 1997 launch.
- Achieving the defined mission objectives within a 65 kg payload appears to be possible, although with limited capability.
- The two missions defined can potentially be accomplished within a lunar day, obviating the need for RTG-type power systems.
  - surviving a lunar night would be highly desirable and may be possible without extravagant systems
- Several strategies were advanced for involving educational institutions and the public in a first Artemis mission.



Weaver/Artemis/Rover Conference 5/5/92



NASA

EXPLORATION PROGRAMS OFFICE

é Ň

2

# First Lunar Outpost

### **Mission Overview**

Third Space Exploration Initiative Technical Interchange

> Kent Joosten Exploration Programs Office NASA/Johnson Space Center May 5, 1992

#### First Lunar Outpost Program Strategy



- Ensure high mission content
  - Provide lunar science and exploration capabilities exceeding those of Apollo
  - Allow evolution and growth along a number of potential paths as experience and knowledge are gained, and as resources allow
    - 1. Augustine Report "Go as you pay"
    - 2. Synthesis Group Report "Waypoint" Philosophy
- Reduce program costs
  - Reduce the number of elements and in-space operations required for space transportation
  - Limit number of surface elements required to establish initial lunar capabilities
  - Identify and employ improvements in management, procurement and operational practices
- Reduce development and deployment times
  - Mission-driven designs; not "technology for technology's sake"
  - Reduce number of flights and amount of surface operations required before establishing significant science and exploration capabilities




### First Lunar Outpost


**Mission Overview** 



- Each flight to the moon requires a single launch. This greatly simplifies the operations that would be required in a multiple launch scenario.
  - No parallel launch vehicle processing is required.
  - No requirement for long-term on-orbit cryogenic propellant storage.
  - Shorter on-orbit lifetime for transportation elements is required.
  - The need to synchronize multiple launch windows and the trans-lunar injection window is avoided.
- A one-way cargo mission precedes the arrival of the first crew.
  - It is assumed that one or more robotic precursor missions have characterized the landing site to a degree sufficient for certification.
  - A lander carrying the lunar habitat and consumables for the first mission lands autonomously.
  - The habitat is pre-integrated. No construction, emplacement or outfitting is required.
  - The habitat "self-deploys" (solar panels, radiators, etc.)
  - Confidence of habitability is established prior to the departure of the crew from Earth.











- The crew performs both EVA and IVA surface exploration and science activities.
- After the surface mission is complete, the crew returns to Earth.
  - The crew configures the habitat to an unmanned mode and returns to the piloted vehicle.
  - Lunar liftoff and trans-earth injection are performed by the return stage.
  - Crew module performs a direct entry at Earth, similar to Apollo.
  - The capability of landing on land is being pursued in anticipation of reducing recovery operations costs and enhancing crew module reusability.
- Plan to revisit the outpost at ~6 month intervals.
  - Revisit logistics are delivered with the new crew. These are transported to the habitat using the rover.

é e





# NASA

#### First Lunar Outpost Evolution Options



- 1) Transition to a continuously occupied outpost to increase the man-hours available on the moon.
  - Allows deployment and maintenance of observatory-class optical telescopes and radio telescope array elements
  - Allows for in-depth lunar science activities, such as drilling, trenching, etc.
  - Allows for longer-duration partial-g life-sciences investigations and operational experience applicable to Mars missions
  - This would most likely involve additional pressurized volume and power, enhanced radiation protection, and more extensive resupply capability.
- 2) Increase roving capability beyond the limits imposed by the EMU/rover.
  - Allows geophysical investigations over much larger areas
  - Allows support and maintenance of widely distributed instruments
- 3) Establish a second identical outpost at a remote site.
  - This may be more efficient than long-range roving.



PARE 67-13 INTERTIONALL BLANK

# Science and in situ resources utilization (ISRU): Design reference mission for the First Lunar Outpost

David S. McKay Solar System Exploration Division NASA Johnson Space Center May 5,1992


N92-33316

#### 1a. Disclaimer

- **1. Requirements and themes**
- 2. General approach
- **3. Science payloads**
- 4. Trade studies: past, present, and future
- 5. Science evolution
- 6. What are we doing now?
- 7. Where do we go from here?

#### **DISCLAIMER:**

- All science activities and payloads in this reference mission are to be considered strawmen only.
- Actual science activities and payloads as well as the FLO landing site will be chosen by appropriate committees, panels, and representatives from the respective science disciplines after due deliberation and agreement.
- However, the following activities are believed to be reasonably representative of a set which may finally be chosen.
- These activities provide necessary information on masses, dimensions, EVA activities, power, etc. as required for planning and designing other parts of the FLO reference mission.



- Science objectives of the first lunar outpost are derived from several top level goals of the SEI program as listed in the First Lunar Outpost Requirements and Guidelines (FLORG):
- The SEI shall expand knowledge of the solar system and the universe.
- The SEI shall establish continual human presence on the Moon.
- The SEI shall research the utilization of space resource.

#### Science Themes


- A series of science themes and first order scientific questions has been developed for each major science discipline
- These science themes and questions are mostly traceable to major reports of the scientific community and their representative bodies such as the National Academy of Science.
- The strawman science activities and payloads are designed to address these major science themes and questions

**Comparison to Apollo:** 

- An additional scientific objective is to provide more and better scientific data from FLO than from all Apollo missions combined
- It is judged that this is achievable in most disciplines
- FLO science is designed to provide much better geologic and geophysical coverage of a local area than any Apollo mission, both laterally and vertically
- FLO science will provide pioneering new science in astronomy
- FLO science will provide basic new information on planetary life support and human performance
- FLO science combined with robotic orbiter and Artemis science will provide a significantly better understanding of the moon as a planetary body and as detector and recorder for events in the solar system and the universe

### **FLO Science and Payloads Team**





General Approach:

Science activities consist of four components:

**1.EVA crew activities:** performing life science, geologic, geophysical, and geochemical investigations

2. EVA crew activities: deploying and activating experiments

- 3. IVA crew activities: performing life science investigations, and analyzing, sorting, and packaging geologic and life science samples for return to earth
- 4. Complementary robotic activities including operation of deployed payloads and additional experiment deployment and sample analysis, collection, and return done by the rover in robotic mode.

Strawman sites

- An initial strawman site (Mare Smythii near the equator on the eastern limb) has been chosen for specific science planning, including traverse layouts for EVAs
- An alternate strawman (Aristarchus Plateau at 23 N, 48 W) was chosen to determine if it made significant difference in the design reference mission
- It was found that the alternate site made no significant difference in the reference mission in terms of payloads and EVAs. Detailed differences in the timelines resulted from a different set of preplanned traverse stations

The overall conclusion is that, except for some specialized sites (lunar poles, crater bottoms, unusual features, etc.) the mission science payload and EVA activities will not change much from site to site.

84

Geoscience and Resource ExplorationTraverses

- For the Mare Smythii site, 9 looping traverses were laid out which ranged out to a maximum of about 25 km from the outpost
- The traverse were designed to visit all major features and to provide detailed geologic recon of an area about 50 km in diameter around the outpost
- Each traverse was divided into segments suitable for one 8-hr EVA on the rover
- Initial timelines indicate that about 5 to 6 of the traverses could be completed on one mission leaving the rest for future missions
- The number of traverses is flexible and can adapt to available EVA time

**Experiment Packages** 

- A number of experiment packages are deployed on the lunar surface
- Some experiment packages are "set and forget"
- Some experiment packages require interactive crew participation
- Four major scientific disciplines plus ISRU are represented by the experiment packages:
  - Astronomy
- Life sciences
- Geophysics
   Space and solar system physics

## **Science and Payloads Team**

Strawman Payload	Mass (kg)	Dimensions (folded)		
Geophysical Monitoring Package	200	1m x 1m x 1m 👘		
Solar System Physics Expt Package	200	0.25m x 0.25m x 0.25m		
Traverse Geophysical Package	400	0.5m x 0.5m x1m		
Lunar Geologic Tool Set	400	0.5m x 1m x 1m		
Lunar Transit Telescope	230	2.7m x 1.1m		
Small Research Telescope	200	2m x 1m x 1m		
Small Solar Telescope	100	0.5m x 0.5m x 1.5m		
ISRU Demo Package	700	1.4m x 1.4m x 1m		
Robotic Package for Rover	300	1m x 1m x 2m (initial est.)		
Life Science Package (EVA)	200	0.2m x 0.3m x 0.3m(initial est.		
Total	2930			

**Note:** Habitat laboratory equipment *not* included in this payload budget

**Geophysical Monitoring Package** 


- Measures values of a number of geophysical parameters
- Provides information on lunar heat flow, magnetic strength, seismic activity, micrometeorite and secondary ejecta flux, and precise distance measurements to earth
- Has ALSEP heritage and will contain very similar instruments
- Powered by central station, possible photovoltaic and batteries, or possibly RTG
- Must be deployed by crew and activated; robotically operated thereafter from earth

#### Solar System Physics Experiments Package

- Contains instruments to particles and fields
- Contains instruments to analyze the lunar atmosphere and its variations
- Also has ALSEP heritage and will contain some similar instruments
- Powered by central station, possible photovoltaic and batteries, or possibly RTG
- Must be deployed by crew and activated; robotically operated thereafter from earth
- FLO package may be identical to one designed for Artemis landing

Traverse Geophysical Package

- Contains instruments which can be operated from the rover
- Instrument package includes:
  - Electromagnetic sounder for subsurface data collection
  - Active Seismic Experiments for data on upper few kilometers
  - Traverse Gravimeter to track variations in lunar gravity from place to place
  - Electrical Properties Experiment to help determine subsurface structure
  - Profiling Magnetometer to measures local variations in magnetic field
- Instruments will be operated by crew and powered by rechargeable batteries




Lunar Geologic Tool Set

- Contains tools, cameras, and sample containers required for geologic investigations and exploration
  - Apollo-type 3-m drill
  - Hammers
  - Rake
  - Soil sampler
  - Scoops
  - Tongs
  - Drive tubes
  - Cameras/digital imaging
  - Sample containers
- Will be carried on traverses and used for collecting and documenting samples


Lunar Transit Telescope

- Will take advantage of minimal lunar atmosphere to survey the sky in the UV spectral range
- Will provide images of stars, galaxies, clusters, and the interstellar medium in the UV
- Deployed by crew at Telescope Farm and operated remotely from earth
- Can be powered by solar cells for lunar daytime operation only



Small Research Telescope

- Pointable telescope for various astronomy objectives
- To be deployed by crew at 10 km or more from habitat: Telescope Farm
- Will be operated and pointed from earth and will transmit data to earth
- Will provide valuable engineering and operating data for future telescopes



.

Small Solar Telescope

- Will provide high resolution images of sun to support solar flare tracking and other solar process investigations
- Will typically make on solar image every 30 seconds
- Operates only during lunar day
- Will be deployed by crew at Telescope Farm (10 km from outpost)



,

Life Science Packages (EVA):

- Monitoring equipment for human performance during EVA
- Will allow specialized testing for such attributes as vision, locomotion, balance, orientation, etc.
- Data will be collected for later analysis
- Exobiology experiment may consist of cosmic dust collector deployed on lunar surface to be returned on a later mission for analysis


ISRU Demo Package


- Enables early ISRU demonstration and validation
- Allows testing of basic processes
- Will provide operational experience for later production units
- Contain three basic subsystems:


1. Oxygen extraction unit which uses imported hydrogen and makes water from lunar oxygen testing various feedstocks and parameters

2. Brick making unit which investigates a number of variables for optimizing brick/block fabrication by sintering of lunar soil


3. Gas-solid flow unit which tests pneumatic transport and pneumatic size sorting methods







.



,

**IVA Science** 

- Will include basic analysis, sorting, and packaging of samples for return to earth, including lunar samples and biosamples
- Will include gravitational biology experiments
  - Mutagenicity of cosmic radiation
  - Chloroplast movement
- Will include physiological experiments
  - Central nervous system
  - Thermoregulation
  - Body fluid analysis

**Robotic Package for Rover Operations:** 

Current concept is an add-on package for manned rover which will allow robotic (mainly teleoperated) operation

• Provide capability for continuing robotic activity between missions

- Allows for teleoperation from outpost or earth
- Includes manipulator arm with ability to dig, scoop, and sample
- Contains set of basic analysis instruments
- Explore out to 100 km from outpost and return
  - Return samples to outpost for collection, analysis and return
  - Return samples from beyond human range for ISRU demo feedstock
  - Up to 4 round trips per year (outpost site to 100 km and return)

5

### Strawmen Science Payload Summary (kg)

3

<b>Discipline</b>	<u>EVA</u>	IVA	<u>Total</u>	<u>Percen</u> t
Geophysics	600		. 600	18
Space Physics	200		200	6
Lunar Geology	400	50	450	13
Astronomy	530		530	16
ISRU	700		700	21
Rover Robotic Package	300		300	9
Life Science	200	400	600	18
Total	2930	<b>450</b> <sup>′</sup>	3380	100

Some trade studies and issues which are being addressed:

- Appropriate mix of science among represented disciplines
- Use of EVA time and capability vs IVA time and capability
- Demo and validation of ISRU vs. use of products on FLO
- Initial evolution of science
- Initial evolution path for ISRU
- Rover range vs. assured crew walkback
- Frequency of EVA: every day using alternating crews vs every third day with all crew members staying in habitat every third day
- Radiation storm shelter using local materials vs transported materials
- Effect of site selection on science payloads and activities

Science on the second mission:

- 1. Continue original detailed reconnaissance traverses not completed on first mission.
  - Estimate that 5 or 6 of 9 planned traverses at Smythii would be completed on first mission leaving 3 to 4 for second mission.
  - •This would complete the mapping of the general geology and chemistry of an area about 20-25 km diameter around the outpost.

2. Begin a detailed drilling program with 10 meter drill (300 kg) using data from the traverses to determine optimum drilling locations within 20 km of outpost. Number of drill holes would be determined by EVA time available.

Science on the second mission (continued)

- 3. Bring and deploy initial elements of radio telescope array (300 kg).
- 4. Revisit optical telescope site and switch detectors as an operational test.
- 5. Analyze and sort samples returned by robotic science rover between missions.
- 6. Perform additional life science experiments with hardware on hand.

Science Evolution:

Over a series of missions to the same outpost, including the transition to permanent occupancy, science studies might be expected to evolve in the following ways:

#### Astronomy:

- Evolution will be toward bigger observatories, more observatories using different wavelengths (UV, IR, X-Ray, radio frequencies, and visible)
- Radiotelescopes will be added and array size can be increased

Space Physics and Geophysics:

- Evolution will be toward network emplacement to provide information on variations of many properties from place to place.
- Instruments may not change much or grow significantly larger

Life Sciences:

Additional and more elaborate experiments would be delivered

Geology and geochemistry:

**Evolution may be in two directions:** 

1. A need for broader coverage of the lunar surface may require *longer and longer traverses* which will in turn require a pressurized rover.

(An alternative approach is to use *Sorte* missions instead of very long traverses).

- 2. *Much more detailed studies* in close to the outpost may be undertaken.
  - May include trenching into the regolith as deep as possible and in several directions.
  - Very detailed study of local features such as large craters, rilles, or volcanic vents might also occupy considerable time.

ISRU Evolution:

Evolution will be toward producing larger amounts of oxygen, volatiles, ind construction materials which can be used to support the outpost and the ransportation system.

- Early production plant in 4-5 years with capacity of 10-15 MT oxygen/yr
- First real use of oxygen or water in infrastructure and outpost support
- Full production plant with capacity 100 MT/yr (8-10 years?)
- Transition to heavy use of lunar propellant and volatiles in infrastructure and transportation support

General: Evolution Philosophy:

- Allow payload room for new experiments
- Plan for new and different activities
- Stay flexible enough to take advantages of new discoveries

What are we doing now?

- Refining concept design and costing of strawmen payloads
- Iterating timeline planning and day to day activities
- Looking at synergy with robotic orbiter and Artemis program
- Working on design concepts and operations concepts for rover in robotic mode
- Planning science evolution
- Planning ISRU evolution
- Designing technology development plan for ISRU
- Preparing to plan for technology development for other science payloads

Where do we go from here?

- Startup of development programs for science and ISRU payloads
- Organize workshops and committees on science priorities and site selection
- Organize mapping and mission planning activity
- Write plan for payload command and control and data flow and analysis
- Write plan for science management
  - Payload selection and integration
  - Payload command and operation
  - Data flow and analysis
- Prepare detailed science and ISRU evolution trees with options, waypoints, and decision points leading to additional lunar-based science and to Mars science and ISRU activities



Z

92-3

ి: లా

200 200

Ron Kahl

# **Space Transportation**

# Presentation to

# **Technical Interchange**

5/5/92



### First Lunar Outpost Design Activity



- Design activity is an on-going requirements development process that will progress through numerous iterations before final selection of technical approach
- Current FLO concepts provide a framework for developing and testing requirements, the concepts are a "first cut" that will be refined considerably as analysis proceeds
- In Summary:
  - These approaches are not final and others have not been ruled out
  - Additional concepts, approaches, and issues will be identified and assessed
  - Input from the SEI community has been and continues to be valuable
  - Interim status reviews will continue as FLO products mature



Introduction

• Requirements

٠

٠

• Concepts

Issues


# NASA

## Introduction



- Space Transportation/Lander Scope
  - Launch Escape System
  - Crew Module
  - Return Stage
  - Lander for Piloted and Cargo Mission

- KEY Interfaces
  - Earth to Orbit Launch Vehicle and Trans Lunar Injection Stage
  - Surface Systems
  - Habitat
  - Operations
    - Launch
    - Flight
    - Communications and Navigation



# NVSV

### Driving Requirements, Guidelines and Assumptions



### Requirements

- First Flight in 1999 Schedule
- Anytime abort
- Crew size of 4
- 45 day stay on Moon
- Land landing at Earth
- Return Payload 200 Kg
- 5 tonne resupply on piloted mission

### **Design Guidelines and Assumptions**

- Use existing hardware where appropriate Cost/Risk
- Cryogenic Lander/Storable Return Stage

### **ETO Interface Assumption**


• Shroud 10m dia. x 18m length - Envelope



- Apollo Capsule Shape, upscaled 5% for larger Crew and EVA Suits
- Lunar Landing site redesignation capability (50 meters at 100 meters altitude)
- Lunar Landing accuracy 100 meters
- 8.5 days transit time, 2 days occupancy and 43 days dormant on surface
- Suits for EVA transfer of Crew
- 200 Kg. Return Cargo
- Thermal Protection System Ablative plus Tile
- RCS for return flight and earth entry
- Power for Earth Entry and Landing
- Parachute and Retrorocket Deceleration System
- Couches and Attenuation
- Land Landings at Earth

### Mass Summary (Kg.)

Dry	6,370
Non-Cargo	609
Residuals + FPR + Fluids	82
Propellants	199
Gross	7,260






15

- Storable Propellants in Four Main Propellant Tanks
- Gaseous Helium Pressurization system
- Three Delta 2nd stage engines (320 ISP)
- Air Tank
- Three Fuel Cell Cryogenic storage tanks
- Three Fuel Cells
- Three Water Storage Tanks
- Radiator

### Mass Summary (Kg.)

Dry	4,469
Residuals + FPR	543
Fluids	1,035
Propellants	18,077
Gross	24,124



# NASA



- Cryogenic Propellants in Eight Main Propellant Tanks
- Gaseous Helium Pressurization system
- Four RL-10 Derivative Engines (444 ISP) Modified for (4:1) throttling
- Monopropellant Hyrdazine RCS
- Four Deployable Legs and Landing attenuation
- Stair/Rails for Crew Access to surface
- Landing accuracy 2 km in Cargo Mode

### **Lander Operational Configurations**


- Cargo Mode
  - Habitat provides Power
  - Avionics, DMS & Comm. added
- **Piloted Mode** 
  - Return Stage Provides Power & Comm.
- Avionics in Crew Module

Mass Summary (Kg.)	Cargo	Piloted
Dry	10,868	10,660
Residuals + FPR + BO	1,732	1,732
Fluids & RCS	242	242
Propellants	43,954	43,954
Gross	56,796	56,588


# NASA


## **Piloted Lander Size**





<u>`</u>.







Mass Summary (Kg.)	Cargo Mission	<b>Piloted Mission</b>
Crew Module		6,370 🔎
Return Stage		4,469
Lander	10,868	10,660
Total Dry	10,868	21,499
Propellants	44,124	62,400
Residuals + FPR + BO + Fluid	ds 1,804	3,464
Non-Cargo	0	608
Cargo	36,175	5,000
TLI Stage Adapter	2,789	2,789
Gross Mass at TLI	95,760	95,760

# Design Issues




- System Mass
  - Lightweight Materials
  - Return Propulsion
- Land Landing at Earth (Reusability)
- Lunar Landing Accuracy/Hazard Avoidance
- Fire in the Hole
- Operations
  - · Ship and Shoot
  - Recovery
- Radiation Protection



## NV2V

### Surface Timeline



132





# NVZV

### EVA



- Exploration surface missions will be EVA-intensive in order to support the extensive science, exploration, and support activities planned.
- Zero-prebreathe EVA capability is considered mandatory.
  - This enables routine & contingency EVA operations from a pressurized enclosure (lander, habitats) without mission overhead impacts.
  - It is necessary to select appropriate EMU vs. cabin pressure for physiologically acceptable bends risk (Example: 5.85 psia EMU from 10.2 psia habitat)
- New suits will be required which must provide improved mobility and which will require low maintenance.
  - Walking, climbing, bending at waist, sitting on rover will be difficult with Apollo-era suits.
  - Current zero-gravity, orbital based suit lower torso mobility features are not adequate for partial-gravity activities.
- Suits must protect crew during powered flight phases of mission
- Support transfer of the crew from lander to habitat and return
- Hard torso surface suits may be too bulky for use or transport within the crew module. A flight suit derived from the STS launch/entry suits could be used for transfer from lander to habitat.
- Design desigion on quiting along antation is not not firm




NASA



## **Advanced EMU**









# NVSV


EVA (cont.)




- Contamination protective measures will be required for connectors, bearings, mechanical linkages, visor optical surfaces, and airlock/habitat environments.
  - Apollo experience indicates that the severe dust environment will be the single most limiting factor to extensive long-term EVA operations
- Surface exploration EMU design is based on highly mobile, lightweight systems and long-life, simple portable life support system technologies which require low maintenance by the mission crew on-site.
  - Minimize crewmember carry-weight in partial gravity
  - Reduce/eliminate need for resupply expendables by means of regenerable techniques or adequate available supply source (LOX)
  - Capable of routine recharge, service, and maintenance by the mission crew far removed from Earth-based facilities
- EVA/EMU servicing and recharge capabilities will be provided from:
  - Habitat airlock EVA accommodations
  - Rover add-on EVA accommodations











### UNPRESSURIZED ROVER

#### **Operating Modes**: Manned

Unmanned (Teleoperated)

#### Capacties:

4 crew 2 crew + 500 kg payload 0 crew + 1000 kg payload

Traverse Capabilities: Manned - 50 km Unmanned - 200 km

### Speed:

15 km/hr (max) - smooth 4 km/hr (max) - rough upland 7 5 km/hr (avg) Packaged Volume: (E) 1.5 m<sup>3</sup>

 Mass:
 0.5 mt

 20% Growth
 0 1

 15% ASE
 0.075

 Total
 0 675 mt

### Subsystem Mass: (E)

Chassis69 kgMobility127 kgCrew Station20 kgNavigation14 kgCommunications45 kgPayload Support10 kg

# Surface Systems Splinter Session

## **ExPO Technical Interchange Meeting**

An exchange of ideas on FLO Surface Systems

# Wednesday, May 6

# 11:00 a.m. - 1:00 p.m.


## **Bertolotti's Cuchina Italiana**

2555 Bay Area Blvd. (just west of UH-CL, seating may be limited)

Luncheon meeting No formal presentations

Each table will have a PSS facilitator

- Surface Systems
- Surface Systems Integration
- Topics
- EVARovers
- Logistics
- Programmatics





# **First Lunar Outpost**

### Lunar Habitat Concepts and Issues

Third Space Exploration Initiative Technical Interchange


> Molly Elrod Program Development NASA/Marshall Space Flight Center May 5, 1992

59-12 11558; A. M





- Flight Elements Shall Provide for a First Launch as Early as 1999
- Initial Design for a Mission Capability is a Crew of Four and a Lunar Surface Stay of 45 Days (lunar day-night-day)
- Initial Mass Requirement is 25 mt. (Current Assessment is 31 mt.)
- Existing Hardware is Utilized where Practical (As determined by cost, schedule, risk, and performance impacts and savings)
- Specific Design Goals are:
  - Reuse every six months
  - Provide solar flare protection
  - Enables manned EVA activities
  - Capable of operation anywhere on the lunar surface
  - System test occurs before crew launch
  - Crew surface operations begin within 24 hours of crew arrival
  - Access to all hardware to provide for infinite life
  - Design for growth capabilities

## **SSF Habitat Module as Lunar Campsite?**




### Lunar Habitat Stowed Configuration





## Lunar Habitat Space Station Derived

## **Habitation Module Layout**




.

### First Lunar Outpost Surface Habitat Mass



	(kg)
Structure and Subsystems	
Module	7302
External Structure	1614
ECLSS	2656
Medical Support/Life Science	445
Crew Systems	1294
Storm Shelter	1000
CDMS	863
Power System	3461
Thermal Control System	1990
Airlock System	4236
Subtotal (Habitat)	24,861
Contingency	2,486
Total (Habitat)	27,347 kg
Consumables	1506
Fuel Cell Reactants	1811
EVA Suits	635
Science Equipment	62
Total (Mass to the Surface)	31.361 kg

### Blood Forming Organ and Skin Dose Equivalent Comparison for Shelter Concepts A and B



Dose equivalent rates determined using the Computerized Anatomical Man Model (CAM)

### First Lunar Outpost Initial Study Conclusions



- A Feasible Habitat Has Been Defined That Can Be Emplaced In One Launch
- Habitat and Crew Module Utilize A Common Lander
- Habitat Is Derived From SSF Hardware (70% By Weight)
  - Module
  - Crew Systems
  - ECLSS
  - Data Management System
  - Internal Thermal Control System
  - Airlock
- Major Development Item Is the Power System (PV/RFC)
  - Lifetime
  - Reliability
  - High Pressure Tankage





- Configuration Options
  - Space Station Freedom Module
  - Clean Sheet
  - Inflatables

### • Design Definition and Assessments

- Detailed Structural Assessment
- Systems Definition
- Radiation Shielding Definition
- Internal Configuration Layouts
- Consumables Stowage/Transfer Logistics
- Growth Scenarios
  - Joining of Multiple Habitats
  - Offloading and Burying of Habitats
- Operational Issues (maintenance/dust mitigation)
- Airlock Options/Definition
- Integration of Lander and Habitat

# NASA

### First Lunar Outpost Definition Process




- FLO activity is an on-going requirements development process that will progress through numerous iterations before final selection of technical approach
- Current FLO concepts provide a framework for developing and testing requirements, the concepts are a "first cut" that will be refined considerably as analysis proceeds
- In summary:
  - These approaches are not final and others have not been ruled out
  - Additional concepts, approaches, and issues will be identified and assessed
  - Input from the SEI community has been and continues to be valuable
  - Interim status reviews will continue as FLO products mature

NAtional Aeronal Stand Space Administration

42-282 - 1

Lundon B. Johnson Space Lunty: Houston Texas 11058



149<sup>A.</sup>

# First Lunar Outpost Earth To Orbit Concepts And Issues

### Third Space Exploration Initiative Technical Interchange

At The

University Of Houston - Clear Lake

// 67/8 8 8 - 2 6 N

Gene Austin May 5, 1992


### Mission Design Choices: Implications to HLLV


- Lunar Direct Vs. Lunar Orbit Rendezvous
  - Lunar Orbit Rendezvous Mode; Provides Earth Return Opportunities Every 14 Days; Introducing Risk For Contingencies
  - $\sqrt{}$  Lunar Direct Mode: Carrying Earth Entry Heat Shield To Lunar Surface
- Earth Orbit Rendezvous Vs. Single Launch
  - Earth Orbit Rendezvous: Dual Launch Costs And Operational Complexity With A One Day Lunar Launch Window For Assembled Vehicle On Orbit.
  - $\sqrt{}$  Single Launch: One Flight For Cargo And One Flight For Piloted Missions Permits Mission Design Flexibility And Reduced Operations Cost/Risks.


### Requirements ExPO

- The Earth to Moon Transportation System (HLLV, TLI Stage, Lander) Shall Provide the Capability to Emplace 27.5 t (Including A 10% Manager's Reserve) on the Lunar Surface in a Single Flight. (Current Assessment Is 34t Resulting In A 93t Requirement To TLI)
- A Single HLLV Shall be Utilized for Each Flight to the Moon
- Flight Elements Shall Provide the Capability for a First Launch as Early as 1999
- The Capability Shall be Provided to Support Up To Four HLLV Flights per year

#### **SEI Reference Launch Vehicles**








Nominal

#### Saturn V Derived HLLV w/ 2 LOX/RP Boosters


#### **Single Launch - Piloted**



156

• ~ ~


#### NLS Derived HLLV w/ 4 LOX/RP Boosters Single Launch - Piloted



Notes: • F-1A & STME are 75% Step Throttlable

#### **First Lunar Outpost Mission Performance**

. ...



158

#### **Future Trade Studies**

- System Design, Performance, Operations And Cost Comparison Of Alternate Concepts
  - Clean Sheet Concepts
  - Minimize Hardware Elements
  - No Strap On Boosters
- Finalize Common Shroud Study
  - Piloted Mission
  - Cargo Mission
- Use Of Electro Mechanical Actuators For TVC On Large Engine Systems
  - Power Budget, Duty Cycle, Power Supply, Etc
  - System Weight And Cost Comparisons With Hydraulics
- Alternative Propulsion Concepts
  - Expendable SSME On NLS Core
  - New Or AlternateLOX/RP Engines



- FLO activity is an on-going requirements development process that will progress through numerous iterations before final selection of technical approach
- Current FLO concepts provide a framework for developing and testing requirements, the concepts are a "first cut" that will be refined considerably as analysis proceeds
- In summary:
  - These approaches are not final and others have not been ruled out
  - Additional concepts, approaches, and issues will be identified and assessed
  - Input from the SEI community has been and continues to be valuable
  - Interim status reviews will continue as FLO products mature

## Organizational Change Incentives and Resistance

### Dr. Peter C. Bishop, Chair Studies of the Future University of Houston-Clear Lake

N92-3332(


## **Models of Change**


## Momentum





## Discontinuity






## What we know about change

### $\checkmark$ Rates of change vary over time

## √ Outcomes are unpredictable

## $\checkmark$ We rarely get the change we want

## **Elements of the Current Period**




## The Signs of Change



## Strain

### Contradictions



## **Leader's Contribution**

Values What is important to us?

Vision What can we become?

*Direction* Which way should we go?

**Boundaries** What are the rules of the road?

Adjustments When and how do we obando?

## **Paradigms -- Our Worldview**

Rules that filter

- What we see
  - What we say
    - What we do

- Powerful and necessary in stable times
- Dangerously outmoded in times of change

## Paradigm Change Examples

Tradition → Flexibility "We've always done it this way."

Authority Motivation *"Because I said so."* 

## The Effects of Revealing Paradigms

## Making assumptions and skills explicit

## Considering their utility

## Changing them to suit the situation

## **Checklist for Change**

- 1. Understand the current period
  - when did it start?

ł

- what is the paradigm?
- why was that paradigm adopted?
- 2. Understand the sources of change
  - what has changed?
  - how soon before the system goes critical?
- 3. Understand the stakeholders
  - who is invested in the current paradigm?
  - who is ready for change?
  - who is confused?
- 4. Identify leaders and champions
- 5. Propose an alternative paradigm
  - new vision
  - new values
  - new rules
  - new rationale

#### Gertiting ไฟทราร ไดย ไลมาร์ Technology to overcome the limits of organizational control

Devid VV. Peserson Vencene Systems, Inc. Flar verd, Hasseshasesa

#### Technology to Overcome the Limits of Organizational Control Online

Flumin sonsrol limits

. Organizational control limits


Fachnology to overcome the limits

#### Technology

#### Technology Demaion of recinology:

- . Whys to Increme Flummin Effectiveness
  - , inhichlaise
  - , irleshoda

riodels



#### Control

1 !

#### Getting What You Want

Technology to Overcome the

Limits of Organizational Control

.

}	Control
	Four steps to achieve control:
	Understand
	. Predice
	. Choose
	. ALSS

#### Technology to Overcome the Limits of Organizational Control

#### Human control limits

- . Organizational concrol limica
- . Technology to overcome the limits

#### human control limits in unfamiliar environments argensition but

- . Required concrol mispercelved
- . Side effects unundstpaced
  - Concrol efforcs instead

#### Technology to Overcome the Limits of Organizational Control

#### climit teenee numuli

#### Organizational control limits

. Technology to overcome the limito

S . 10


#### Control


#### Technology to Overcome the Limits of Organizational Contr

.

#### Human control limits in unfamiliar environments

Technology to Overcome the Limits of Organizational Contr





## 

#### Organizational control limits

Target is clear, but:

Problems misdlegnosed

- . System reastion unantisipated
- . Resources wasced

#### GM Productivity

#### Toyota Productivity

,


•


#### Nissan Productivity

#### Organizational control limits

.


#### ORIGINAL PAGE IS OF POOR QUALITY





#### Technology for Aucomocive Organizational Control


- . Filgh standards
- . Employee Involvement / Teamwork
- . Studistical process control




#### Technology for Automotive Organizational Control

•

Big-Project / Low-Volume Organizational Control





#### Big-Project / Low- /olume Organizations Additional limits

- cexic elgnum llumic .
- . Long lead times
- . Expensive experiments
- . Expendive duta

#### Big-Project / Low-Yolume Organization: Impensives for controls

- and to two nottermobili fir exceeps .
- . Optimize for high-leverage decisions

#### Big-Project / Low-Volume Organizational Control

#### Big-Project / Low-Volume Organizational Control

•

.

Big-Project / Low-Volume Organizations

#### Big-Project / Low-Volume Organizations

#### Technology for Big-Project / Low-Volume Organizations

- . Filgh Scandards
- , Employee Involvement / Teamvork

Lessons Learned Models must be:

Complete (people, project, imrdivare)

. Dynamic (copredict change)

. Robust (realistic under all inputs)

- Model-based Scudsdos
- . Hodebbesed Optimization

#### Technology for Big-Project / Low-Volume Organizations

.

.

#### Lessons Learned

#### Lessons Learned Statistics must be: riodel-based Opdimal Compute-Intensive

#### future Planagement

. Technology we now apply to hardware will be routinely applied to organizations

#### Lessons Learned

#### Future Management

.

## **ACQUISITION STREAMLINING**





### Jesse Stewart

## DEFENSE SYSTEMS MANAGEMENT COLLEGE

May 6,1992





## DEFENSE SYSTEMS MANAGEMENT COLLEGE

## **STREAMLINING INITIATIVES**

**CULTURAL CHANGE** 



## DEFENSE SYSTEMS MANAGEMENT COLLEGE

# EDUCATIONAL INSTITUTION - GRADUATE COLLEGE(PMC) - PROFESSIONAL DEVELOPMENT --SHORT COURSES

## GOVERNMENT AND INDUSTRY

175 FACULTY



## DEFENSE SYSTEMS MANAGEMENT COLLEGE

### RESEARCHERS

## **CONSULTANTS**

## INFORMATION SOURCES

## ACQUISITION MANAGEMENT POLICY EXPERTS





EDUCATIONAL PHILOSOPHY

## COURSES FROM PROGRAM MANAGER'S PERSPECTIVE

## THINK FIRST, REGULATIONS SECOND

REALISM AND CURRENCY





EXECUTIVE

BRANCH

.

DEFENSE

INDUSTRY

## DEFENSE ACQUISITION ENVIRONMENT

## INCREASING EMPHASIS ON ACQUISITION EDUCATION

## DECLINING FORCE STRUCTURE AND RESOURCES

## LEGISLATIVE DEMANDS AND REQUIREMENTS



186

STREAMLINING INITIATIVES

## ORGANIZATIONAL OVERSIGHT RELIEF

## **LEGISLATIVE STATUE CHANGE**

DEFENSE ACQUISITION PILOT PROGRAMS



## ORGANIZATIONAL STREAMLINING TYPES

## **WITHIN PROGRAM OR COMMAND**

## SPECIFICATION and REGULATION ORIENTED

## PERSONNEL REASSIGNMENT



## **DEFENSE LAW REVIEW**

## IPPLICATION ACT

## STREAMLINE AND CODIFY ACQUISITION LAW



## LAW REVIEW PURPOSE

## REVIEW ACQUISITION LAWS

- STREAMLINE ACQUISITION PROCESS
- ELIMINATE UNNECESSARY LAWS
- ENSURE FINANCIAL and

## ETHICAL INTEGRITY

- PROTECT BEST INTERESTS OF DoD

## PREPARE RECOMMENDED CODE



LAW REVIEW OBJECTIVES

# FACILITATE GOVERNMENT ACCESS -COMMERCIAL TECHNOLOGIES -SKILLS IN COMMERCIAL MARKETPLACE

COMMERCIAL ACCESS TO GOVERNMENT DEVELOPED TECHNOLOGIES




LAW REVIEW OBJECTIVES


## COMMERCIAL PRODUCTS/SERVICES PURCHASE BASED ON MARKET PRICE


## INTEGRATE COMMERCIAL/DEFENSE PRODUCTION WITHOUT ALTERING ACCOUNTING OR MANAGEMENT PROCEDURES

MINIMIZE ADDITIONAL REPORTING


## MODEL








1.



ACQUISITION RELATED LAWS ONLY





## PROGRAM ANALYSIS

## **EFFECTS OF LAW**

## **EFFECTIVENESS OF NEW PROCESS**

## EFFICIENCIES OR SAVINGS



861

## PROCEDURES

## PROGRAMS ANALYZE LAWS AND REGULATIONS -PROVIDE RECOMMENDATIONS

## DEPARTMENT OF DEFENSE-- REVIEW and FORWARD TO CONGRESS

## CONGRESS AUTHORIZES and DESIGNATES IN APPROPRIATIONS



## POTENTIAL EXAMPLES

## MODIFY

- STATUTORY REPORTING
- OBLIGATION TIME FRAMES
- REPROGRAMMING AUTHORITY
- TEST REVIEW REQUIREMENTS
- MULTIYEAR CONTRACTING

### WAIVE PROGRAM CATEGORY DESIGNATION




STREAMLINING STATUS

## SPECIFICATIONS--ONGOING

## LAW ADVISORY PANEL -REPORTS JANUARY, 1993

# PILOT PROGRAM -PREPARING CONGRESSIONAL PROPOSAL






## -CHANGE-A CULTURAL PERSPECTIVE

## LEADERSHIP - TOP DOWN VERSUS BOTTOMS UP

# MAJOR CHANGE ISSUES - COMPARATIVE DATA - RESOURCES






## SUMMARY

## THREE TYPES OF STREAMLINING - SPECIFICATION

- LAW REVIEW
- PILOT PROGRAM

## MAJOR OPPORTUNITY FOR ACQUISITION IMPROVEMENT

**ORGANIZATIONAL CHALLENGE** 



NASA



1.12

- The ingredients of successful low-cost, high technology programs are well known and universally recommended by successful program managers interviewed
  - Use government only to define and verify requirements
  - Keep requirements fixed: once requirements are stated, only relax them; never add new ones
  - Place product responsibility in a competitive private sector
  - Specify end results (performance) of products, not how to achieve the results
  - Minimize government involvement (small program offices)
  - Insure that all technologies are proven prior to the end of competition
  - Utilize the private sector reporting system: reduce or eliminate specific government reports
  - Don't start a program until cost estimates and budget availability match
  - Minimize or eliminate government imposed changes
  - Reduce development time: any program development can be accomplished in 3 to 4 years once uncertainties are resolved
  - Force people off of development programs when development is complete
  - Incentivize the contractor to keep costs low (as opposed to CPAF, CPFF of NASA)
  - Use geographic proximity of contractor organizations when possible
  - To reduce the number of interfaces and keep responsibilities clean, use the major prime contractor as the integrating contractor

#### R.L. GRANT REMARKS CQI: CULTURE CHANGE WITHIN BOEING DEFENSE & SPACE GROUP

Space Exploration Initiative Third Technical Interchange Meeting Houston, TX May 6, 1992

- Boeing's approach to Continuous Quality Improvement (CQI) is an evolutionary one
- While consistently stressing the importance and inevitability of fundamentally changing the way we do business, and characterizing CQI as the "cornerstone" of our business management approach, the Corporation left it to individual organizations to adopt and implement CQI as they saw fit
- The ultimate aim of any CQI activity is the delivery of quality products and services. We are in the business of satisfying our customer.
- Fundamental to the culture change around the delivery of a quality product are several key points:
  - Quality is ultimately defined by the customer
  - · Redefining "customer" as internal as well as external.
  - Understanding the part suppliers play in the quality of our products, internally as well as externally.
- The shape of CQI in any organization around Boeing has been based on the workplace culture, products, customers and leadership personalities of that organization
- Our early approach focused on Quality Circles and Process Improvement Teams where we began to apply principles of problem-solving, process analysis, SPC and other tools
- However, in 1989, Boeing Aerospace began an organization-wide focus on planning getting everyone's arrows pointed in the same direction.
- A Large-Scale System Change process brought management together for 2-3 days for strategic planning and goal-setting sessions, a process that under normal circumstances would take months to accomplish.
- The single threading of the Company vision, mission, goals, objectives and actions through every level, organization and individual is known as Policy Deployment. Performance Management, the vehicle to communicate and involve everyone in the process, will be accomplished within the Group by the end of this year

- Our CQI approach follows three principle pathways for achieving quality products the first time every time:
  - **Policy Deployment**, mentioned earlier, is the system by which goals are determined, plans to achieve the goals are established, and measures are created to assure progress toward the goals
  - **Partnership** paying attention to the way we work together with our customers, suppliers, both internal and external; the way we work together cross-functionally, between paycodes; and the way we use teams to get work done. Through partnering, we recognize the importance of making organizational boundaries permeable at all stages of a product or process, thereby empowering everyone to have an opportunity to influence what goes on and be satisfied with with the outcome and how it was attained.
  - **Process Improvement** shifting the focus away from examining the quality of the end product to the quality of the process which creates the end product, thus preventing problems or poor quality from occuring and enabling true improvement and innovation
- Continuing with the spirit of evolution, the Defense & Space Group senior managers participated in a Japanese Study Mission late last year which involved a "Ground School"in Seattle followed by a visit to 10 world class Japanese companies
- Some basic observations of the Japanese management culture include:
  - Setting up an effective management system to assure the long-term viability and continuous adaptation/evolution of the enterprise is management's job (Nippon Steel: "Each day a new dawn for steel.")
  - Well-structured, documented, disciplined process for conducting all phases of business activity. System driven by facts and data and founded on the Plan-Do-Check-Act continuous learning cycle.
  - Entire organization maintains a consistent and persistent focus on full customer satisfaction (Quality, Cost, Delivery, Safety and Morale).
     Customer In as a way of life in contrast to old paradigm of Product Out
  - Design engineering must stay close to the field where the products are used and close to the shop floor where the products are made.
     ("Armchair engineers" who never visit the factory floor must go)
  - Manufacturing is a strategic weapon that can be used to continuously meet the changing needs of the customer and beat the competition. Manufacturing systems designed with a resiliency to assure a rapid and flexible response to changing market needs

- Everyone is involved in improving everything all the time. People seen as an asset; information on goals and performance is shared openly; team environment founded on mutual respect
- They are globally ambitious and playing for keeps

• •

- This lead us to go beyond seeing CQI as a program. While we did not radically change our current course, we are applying these lessons and are committed to institutionalizing CQI, making it the way of life in D&SG
- We will implement CQI as The Management System for D&SG and are working to develop a common approach
- Using the Malcolm Baldrige criteria to measure our progress, we will undertake the following initiatives:
  - 1. Train all managers to lead and teach CQI
  - 2. Establish a CQI information-gathering and analysis process
  - 3. Improve the planning process to produce an integrated plan that encompasses product, technical, business and CQI efforts
  - 4. Continue toward a participative work place for all employees and prepare the work force to function effectively in a CQI environment
  - 5. Identify, document and improve our product and business processes
  - 6. Measure our performance levels and improvement trends, and identify need for change
  - 7. Improve satisfaction of our external customers.
- So, we learn, we implement and we evolve. Japanese as well as US companies have their ups and downs as they embrace CQI as The Management System. Often we must regroup and restart.
- But the point is they stay with it, they persevere, and so shall we.
- We don't know what the future holds in this time of tremendous change.
- And while we may currently be in the middle of the journey as we perform the transition to a CQI culture, I believe we will figure it out, we will land on our feet, and we will compete successfully as a world class organization with all comers!

#### **Policy Deployment**

Policy deployment aligns the work of our people to meet consensus-developed mission statements, goals and objectives. This is reinforced by performance management contracts with all managers.

#### **Process Management**

Processes are managed effectively and efficiently by creating process-focused teams to accomplish continuous improvements that reduce defect rates and process flow time.

#### **Product Variability Reduction**

Product variability is minimized by product development teams that create robust designs. These teams iterate the design of a product while simultaneously developing manufacturing, support and training processes.

#### **Supplier Excellence**

We develop cooperative relationships with suppliers to help them improve their processes and products. Tracking costs of working with individual suppliers will enable us to select future suppliers on the basis of highest quality and lowest total cost.

#### **Customer Focus**

Maintaining a strong customer focus is the cornerstone of our continuous quality improvement process. This involves fulfilling the requirements and expectations of both internal and external customers.

#### **People Involvement**

Empowering our people creates ownership of and individual commitment to the continuous improvement process. This provides the energy to achieve our Quality goals.

#### Metrics

Metrics provide the data needed for measuring trends and making fact-based decisions. CQI metrics primarily focus on defect rates and flow times.

210

Dep/ou Process of Management , Product V Variability Reduction

5 mg

MARIE

٩U

t

1.22 Customer

Supplier (cellence

Focus

Î

€ **■** 

े. द्व

OBEN

•

SUPERIÉURE

Ę



Lockheed ع

### Technical Interchange Meeting for NASA Space Exploration Initiative


**Cooperation in Space** 

by

A. Guastaferro

May 6, 1992

Houston, Texas





#### Outline

Lockheed

- Personal background
- Objective
- Today's culture
  - Environment
  - Monopsony relationship
  - NASA decision maker
  - Industry participation
- Let's try a new approach
  - 14 rules of Skunk Works
  - Analysis of rules
- Congressional oversight
- Programmatic impact
- Recommendations



#### **Personal Background**

Lockheed

38 years of aerospace experience

- 8 Air Force
- 22 NASA
- 8 industry

Significant project management experience

- QB-47 (aeronautics)
- Scout (launch vehicle)
- Viking (planetary)
- Rotor systems research aircraft (helicopter)
- Large space structures (technology)
- Space Station Freedom (large program)

Other Government experience

- Project management
- General management
- Tech rep of contracting officer
- SEB chair
- SEB member
- Launch conductor

Served on a number of NASA, National Academy, and AIAA committees



Objective

lockheed ج

To share a perspective of a costeffective cooperative management structure of NASA and industry as we move towards the 21st century and the national commitment to continue our Exploration in Space with Humans



#### Today's Culture

The sector states and the sector states and

#### Environment

- Space exploration has been a very focused R&D activity
- Uncertainty leads to cost reimbursible contracts and change as the standard
- Developments take a major part of a decade
- Estimated costs are traditionally underscoped
- Award fee became fashionable over fixed fee (contractors become more responsive to change)



#### **Today's Culture**

*Lockheed* 

Monopsony relationship

- Many suppliers  $\rightarrow$  one customer
- Demand driven
- High contractor investment
- Aggressive pricing
- Optimistic proposal
- Raised technological and programmatic expectations
- Atmosphere of "more for less"
- Contractors accept lower fees
- Leads to overcommitment of programs (advocacy is optimistic)
- Congressional funding shifts programs to the right

Above leads to public and congressional criticism of both NASA and industry



#### **Today's Culture**



#### NASA GROUD MAKEN

- Too many Phase A's
- Phase A's demand contractor investment - \$\$\$
  - 222
  - People
- Phase B's are started with inadequate funding
  - Competition will yield adequate design
  - Extended activities level playing field
- Scientific community (users) brought in late to process
- Phase C/D decision making is at top
  - Vertical assessment for approval drives NASA centers to become aggressive
- Non-advocacy review has been a remedy for aggressiveness
- For every 10 Phase A/B programs, only one will be approved
- Process wastes resources and creates false advocacy



**Industry Participation** 

₩ Lockheed

- Industry understands the technical and fiscal value of participation in civil space
- Military and national security programs have contributed significantly to industry's technical base and professional staff development
- Strong relationship with NASA centers during advocacy
- Industry becomes advocacy agents for NASA (selling the program through heavy investment and optimistic planning)
- Industry understands that a delayed program costs more investment dollars and has lower probability of a win



#### Let's Try a New Approach

Jlockheed

#### Sell's Connecon (a **9.50**) -

- Empowered program management in industry
- Small, effective project team
- Limited access to "reviewers"
- Simple documentation system
- Minimum reports (critical work will be documented)
- Cost reviews with performance measurement
- Empowered contractor (do not micromanage)
- Inspect at lowest level (do it right the first time)
- Contractor will test for flight (need for continued competency)
- Specifications established early (prior to contract)
- Timely funding
- Trust
- High security (keep outsiders outside)
- Pay for performance



#### Let's Try a New Approach



#### Analysis

#### Industry management (rules 1, 2, and 3)

- TQM was started by Kelly Johnson
- Resources with program manager
- Complete control on people selection
- Shift from quantity to quality
- Stay "lean and mean"
- Must be customer driven

#### Documentation system (rules 4, 5; and 6)

- Our paperless programs must drive to be paperless
- MIS can be electronically controlled
- Most have more analysis and less paper
- There is "gold in the mounds of paper"
- Documentation reduction is our greatest challenge but it is also our greatest reward



#### Let's Try a New Approach (Cont)

#### Analysis

Subcontract management (rule 7)

- Buy "off the shelf"
- Use of commercial practices
- Must take prudent risk by selection of the best with the least oversight
- Empower the subs to beat cost and schedule reward if successful

Inspection (rule 8)

- Inspect at lowest level
- Avoid duplication
- Look for value added processes
- Reduce Government participation

Testing (rule 9)

- Try to do at contractor's facility
- Hold contractor responsible
- Eliminate Government testing

## חבקא Let's Try a New Approach (Cont) כגעליבע Lockheed

Analysis

Specifications (rule 10)

- Firm-up early
- Make play not better
- Time is the enemy of good
- Be flexible to meet performance
- Use the best people up front

Funding (rule 11)

- Plan the funds
- Fund the plan
- Try to get congressional support

Trust (rule 12)

- Award fee process must create a trust atmosphere
- Government/industry working together towards a common goal
- Must improve in this area



#### Let's Try a New Approach (Cont)

#### Analysis

#### Steurine (alle 13) mains stands on

- A psuedo system may yield positive results
- No "bad verbs"

#### Paysion performance (rule 14)

- Pay the best to get the best
- NASA must recognize and reward and penalize
- Cost analyst should not decide that cost per hour will give you the best
- More emphasis on skills
- NASA should not negotiate to lower the cost for fee determination
- Emphasis should be on getting the best at the lowest number of hours



**Congressional Oversight** 

Jockheed

- Responsibility for appropriation of resources should be rewarded with "shared accountability"
- NASA must treat their customer as a trusted and valued participant in the process
- Oversight by Congress should be reasonable and limited to major problems
- Micromanagement should be eliminated



**Programmatic Impact** 

₹ZZLockheed

- Must improve Government/industry relationship
- Need major overhaul of existing contracting methods
- Insufficient budget to match program
- Must change incentives to industry
  - Higher reward opportunities
  - Lower fees for marginal performance
- Government/industry must become equally accountable for successes and failures



## **Recommendations**

JLockheed

- NASA should assume a greater share of predevelopment funding
- NASA should reduce the number of underfunded programs and studies in Phase A/B to provide adequate funding for approved programs
- NASA should continue the nonadvocacy review process
- NASA should consider some elements of the Lockheed Skunk Works
- Congress should authorize multiyear funding for large programs
- Congressional staffers should provide better understanding of the risk associated with space exploration and get involved in the technical as well as political aspects of a program. Become an informed critic
- Industry, working with NASA, should find a way to leverage B/P and IRAD resources against underfunded predevelopment programs
- Industry must work harder to put the best and brightest on programs to achieve superior performance
- Industry must demonstrate that they are willing to provide their best people and facilities towards the civil space program for the benefit of:
  - The nation
  - The public
  - NASA

- The user communityTheir employees
- The stockholders

- Congress

## **SKUNK WORKS TYPE APPROACH FOR F-SAT**

NASA EXPLORATION PROGRAMS OFFICE JOHNSON SPACE CENTER MAY 6, 1992



### **F-SAT PROGRAM**

### **PROBLEM:** MULTIPLE TOUGH COMPETITIONS COMING - LOW EARTH ORBIT ATLAS/DELTA CLASS MISSIONS

• DMSP, NOAA, SBR, SDI EXPERIMENTS, EOS, CLASSIFIED PGMS • LOTS OF COMPETITION, COST INTENSIVE


**NEED:** DEMONSTRATED LOW COST "STANDARD" SPACECRAFT BUS

- CUSTOMERS CAN'T AFFORD TO REINVENT BUS FOR EVERY PGM.
- MUST ESTABLISH COST CREDIBILITY THROUGH PERFORMANCE.

**APPROACH: DEVELOP AND PRODUCE A "STANDARD" SPACECRAFT BUS** 


- DEMONSTRATE LOW COST, VERSATILE DESIGN
- GOAL FACTOR OF 4/5 COST REDUCTION
  - MAJOR IMPROVEMENT REQUIRES MAJOR CHANGES
    - IN OPERATING METHODS
    - IN PROGRAM CULTURE

### THE CLASSIC PROGRAM ORGANIZATION



- Separation of Engineering, Manufacturing, Test responsibility
- Overlapping hardware and software responsibilities
- No total product responsibility, no ownership

230



### **DESIGN/CONFIGURATION MANAGEMENT**

TOOLS

- MECHANICAL COMBINED CIEM (ANALYSIS) AND CADAM (DRAFTING). CROSS-COMMUNICATION
- ELECTRONICS MENTOR GRAPHICS SUPPORTED BY SELECTIVE BREADBOARDING
- DRAWING FORMATS
  - DESIGNER PHONE NUMBERS ON DRAWINGS
  - ISOMETRIC VIEW ON DRAWINGS
  - CRITICAL INSPECTION DIMENSIONS MARKED ON DRAWING
- DRAWING RELEASE/CHANGE CONTROL
  - LIMITED CONTROLLED COPIES (3)
  - CHANGE AUTHORITY FOR EACH PART SOLE AUTHORITY TO MAKE CHANGES
    - **RESPONSIBLE FOR ASSESSING, REPORTING COST IMPACT (ONE MAN CCB)**
    - HIS CALL AMOUNT AND TYPE OF FUNCTIONAL SUPPORT
    - RESPONSIBLE FOR MARKING CHANGES ON ALL 3 CONTROLLED DRAWINGS
  - MANUFACTURING APPROVAL PRIOR TO RELEASE
  - RED LINE CHANGES ONLY. NO EO'S ALLOWED. MUST INCORPORATE AFTER 1 MONTH.
  - SAME REV LETTER PARTS LIST AND DRAWING
  - QA AUDIT OF SYSTEM
- DESIGN/DEVELOPMENT PHILOSOPHY
  - "READY, FIRE, AIM, RELOAD," NOT "READY, AIM, AIM, AIM....."
  - DON'T "CONTROL" NUMBER OF CHANGES. ENCOURAGE <u>EARLY</u> SURFACING, CORRECTION OF PROBLEMS
  - ENCOURAGE HARDWARE/SOFTWARE/TEST MIX OF ASSIGNMENTS

### **PROCUREMENT/MATERIEL**

- **SUPPLIER INTERFACE** LISTEN!
  - SUPPLIER COMMENTS ON DRAFT SPECS, RFPS, REVIEW OF FINAL VERSIONS
    - USE THEIR SPECS WHEN WE CAN
  - UNLIMITED PRE-RFP ENGINEERING CONTACTS
  - DON'T JUST ASK BEG FOR BENEFICIAL EXCEPTIONS, CHANGES
  - MAXIMUM ACCEPTANCE TEST BY SUPPLIER
- SPECS/DOCUMENTATION
  - NO INTERNAL LOCKHEED SPECS/PROCESSES/STANDARDS USE MIL SPECS OR GENERAL ACCEPTED STANDARDS
  - USE SUPPLIER'S INTERNAL FORMATS
- **OPERATING METHODS** 
  - TREAT SUBS AS PARTNERS
  - DELAYS ARE MUCH MORE COSTLY THAN WASTED MATERIAL
    - ORDER MATERIAL BY AMR BEFORE DRAWING RELEASE IF POSSIBLE
    - IF YOU'RE NOT SURE WHICH MATERIAL YOU WANT, ORDER BOTH
    - PROVIDE EXTRA RAW MATERIAL TO THE SHOP. RETURN UNUSED MATERIAL.
    - USE OF PETTY CASH WHEN NECESSARY TO SAVE SCHEDULE
  - REJECT THE PROPOSITION THAT NON-PROCUREMENT PEOPLE ARE INCAPABLE OF SUBCONTRACTOR INTERFACING

### MANUFACTURING

### ALL NEW PAPERWORK SYSTEM

- BASIC MINIMUM DOCUMENTATION OF WHAT WE'RE GOING TO DO MAXIMUM DOCUMENTATION OF WHAT WE DID
- SIMPLIFIED TRAVELER "BUILD TO PRINT" PLUS BRIEF INSTRUCTIONS, ROOM FOR S/Ns, ETC.
- PHOTO RECORDS OF 1ST BUILD BY ENGR/TECHNICIAN SCAN INTO COMPTR FOR 2ND BUILD
- INSPECTION SHEET WITH TRAVELER. 100% 1ST BUILD, THEN CRITICAL DIMENSIONS ONLY.
- NC MACHINE DATA RETAINED WITH 1ST BUILD DATA PACKAGE
- MANHOUR ESTIMATES, UPDATES, ACTUALS BY DOERS

SHOP OPERATION - EMPHASIS ON SPEED, FACE-TO-FACE COMMUNICATION

- F-SAT MARKER ON ALL TOTES EASY TO SPOT IN SHOP
- BRIEFING OF ALL 1ST TIME F-SAT MANUFACTURING TECHNICIANS
  - WHAT DOES PART/ASSEMBLY DO?
  - PROGRAM DESCRIPTION, POSTER TO TAKE HOME
  - DISCUSSION ON BEST FAB APPROACH
  - TECHNICIAN CREATES AND/OR APPROVES PROCESS TRAVELER INSTRUCTIONS
- **FAST RESPONSE** 
  - DEDICATED STATION WAGON FOR FAST MATERIAL RETRIEVAL
  - IMMEDIATE ENGINEERING RESPONSE TO QUESTIONS/PROBLEMS DAY OR NIGHT
    - **NO LIAISON ENGINEERING**
- FULL SCALE FOAM BOARD MOCKUP BY SAME TECHNICIANS WHO WILL BUILD
- TOOLING IN CONTROL OF USERS
  - NEED FOR TOOL, DESIGN CONCEPT APPROVAL BY USING TECHNICIANS
  - TOOLS BUILT BY USERS

### **QUALITY ASSURANCE**

### **BASICS**


- F-SAT QA MANAGER IN COMPLETE CHARGE OF ALL QA FUNCTIONS
  - INCLUDES INSPECTION, PROCUREMENT, SUPPLIER PRODUCT CONTROL, RECEIVING
- MAXIMIZE ACCEPTANCE TEST BY SUPPLIER. DON'T REPEAT.
- EMPHASIS ON AUDIT OF CONFIGURATION CONTROL, OTHER PROCEDURES NOT SERIAL
   APPROVAL OF EACH ACTION


#### INSPECTION

- HEAVY EMPHASIS ON SELF INSPECT WITH QA AUDIT
- LATEST POSSIBLE INSPECT POINTS
  - EXAMPLE PC BOARDS. 1ST INSPECTION AFTER BOX TEST FOR OK TO COAT.
- RECEIVING INSPECTION IN BLDG. 159. WE KNOW WHAT WE WANTED WHEN WE ORDERED IT. OTHERS DON'T.

#### MRB

- ON LOW-COST PARTS, DELEGATE "SCRAP" MRB DECISION TO MFG TECHNICIAN
  - LOG EVENT, HOURS SPENT, REPLACEMENT NEEDS ON BACK OF TRAVELER
  - MRB ACTION APPROVAL PA AND CHANGE AUTHORITY ONLY. NO LIAISON.





• <u>TRUST</u> - A MUST. IF PEOPLE LET US DOWN, DON'T USE THERAPY (LAYERS OF REVIEWS), USE SURGERY (GET THE HELL OUT OF B/159).

### THE PILL

\*\*\*

Here's an excellent plan to increase organizational efficiency. Issue each employee a small pill box with a lethal pill inside. At the end of each work day, employing a lie detector to preclude cheating, each employee must honestly answer the question "Have I accomplished more work than I have caused?"

If the answer is no ---- take the pill!

## Project Management Lessons Learned on SDIO's Delta Star and Single Stage Rocket Technology Programs

6 May 1992

Paul L. Klevatt Deputy Program Manager, SSRT McDonnell Douglas Space Systems Co. (714) 896-4618

2 9

ろ

165/PLK2/]c

## Agenda

McDonnell Douglas

□ Delta Star (Delta 183) Program Overview

Lessons Learned

- Imperatives
- Proven Rapid Prototyping Groundrules and Axioms
  - Management, Design, and Control
  - Cost and Schedule
- Rapid Prototyping and the Single Stage Rocket Technology (SSRT) Program
- Concluding Remarks

## Acknowledgement

The author is indebted to the following individuals whose experiences, ideas, writings, advice and can-do management approach have been a key factor in the successes achieved on important SDIO/MDSSC programs. The "lessons-learned" contained herein, gleaned from program achievements and setbacks, provide valuable guidelines for present and future Rapid Prototyping programs.

### **DELTA STAR**

- Dr. Michael Griffin NASA (formerly SDIO)
- Col. Michael Rendine (SDIO/USAF(Ret.))

#### 


- Lt. Col. H. "Pat" Ladner SDIO
- Major Jess Sponable SDIO

## "The Difference Between a Dream and a Goal is a Time Limit"

💻 McDonnell Douglas 💻

□ Basic Objective of SDI Space Experiment Programs:

- <u>Quickly</u> reduce key uncertainties to a manageable range of parameters & solutions
  - Yield results applicable to focusing subsequent research dollars on high payoff areas.
- Success is achieved via a partnership relationship amongst all participants conducted in a Rapid Prototyping environment






### DELTA STAR PROGRAM SCHEDULE OVERVIEW

DS-VDD18953:1/M300



MER MCDONNELL DOUGLAS



246

## The Path To Program Success Begins With An Endorsement of Fundamental Needs & Priorities

- □ <u>IMPERATIVES</u>
  - A. Customer
    - <u>Short</u>, concise SOW and contract defining mission objectives, functional goals, schedule
    - Agreement on funding profiles and funding timeliness
    - Agreement on specifications at contract negotiation/award
    - Clearly established guidelines for on-site government agency roles/participation
    - Assurance of timely approvals re. test/qualification requirements and results
    - Rapid access to Program Director for on-the-spot problem solving
  - **B.** Contractor
    - Company President's commitment to Rapid Prototyping operations within the "system" to ensure:
      - Resources availability
      - Program priority
      - Team Program Manager's responsibility, authority and accountability

## Proven Rapid Prototyping Groundrules and Axioms

McDonnell Douglas

### A. Management, Design, and Control

- 1. Risk Management:
  - Recognize differences between space <u>research</u> experiment programs and <u>operational</u> space programs.

Space Research Experiment High Probability of Success	Operational Space Program Minimize/Eliminate Probability of Failure
--	---

Make decisions early on need for incorporating independent experiments to ensure high probability of success

## Proven Rapid Prototyping Groundrules and Axioms

- A. Management, Design, and Control (Cont'd)
- 2. Requirements/Goals
  - Establish optimistic & challenging technical and schedule requirements and goals
    - Allow for flexibility depending on hardware/software availability
  - □ Select only those Mil-Specs & Mil-Standards that match the intent of the program.
    - Allow flexibility & tailoring
      - The experiment just has to work
  - **Do not allow ICD's to drive the program be flexible** 
    - Change the interfaces to allow the most suitable teammate to solve the problem

- A. Management, Design, and Control (Cont'd)
- 3. Decision Making:
  - Delegate responsibility to those closest to the problem
    - Working groups (government & industry) produce timely "can-do's"
      - Reduces external monitoring & oversight
      - Replaces/augments the ICD
      - Tracks action items/documents with minutes
    - TQMS's Concurrent Engineering principles a must
    - All applicable functions/disciplines committed to first time quality
  - **Use real-time problem solving (at team and management levels)** 
    - Come to closure rapidly
    - Have meetings only when decision makers are present
      - Reinforces responsibilities

- A. Management, Design, and Control (Cont'd)
- 4. Design:
  - □ Work with the concept go rapidly to the Initial Design Review
    - Conduct timely focused systems engineering analyses & trades keep documentation at a minimum, but thorough
    - Surface problems and resolve quickly
    - Maximize use of off-the-shelf hardware & software items
      - "Imagineer" their original use/intention vs. program's performance goals (performance goals are flexible!)
      - Insist on "touching" the H/W & S/W before commiting schedules
    - Quickly establish hardware quantity and usage list
    - Maximize use of existing embedded facilities and launch operations resources & procedures

- A. Management, Design, and Control (Cont'd)
- 5. Design Reviews:
  - Replace MIL-Spec. type PDR & CDR with participative Initial Design Review (IDR) and Final Design Review (FDR) approach
    - IDR demonstrates design and development testing appropriateness
    - FDR freezes overall mission/experiment design; establishes basis for configuration management/control
    - Fosters teamwork & commitment to schedule; enables reviewers to be part of the solution, reinforces the benefits of cultural change
  - □ Encourage executive level participation
    - Reinforces their commitment

McDonnell Douglas

- A. Management, Design, and Control (Cont'd)
- 6. <u>Qualification / Acceptance Testing</u>:
  - □ Emphasize testing, especially at the subsystem and system levels
    - Conduct timely reviews and move on; document findings
  - □ Integrate subcontractor / supplier testing to reduce cost and schedule
  - □ Use proto-flight approach (vs. full Mil-Spec style qualification)
    - Reduces schedule risks, provides hardware use flexibility
  - □ Do not subject <u>available</u> H/W to multiple +6dB test cycles
    - Only flight safety, ascent, housekeeping functions and selected purpose-designed H/W need to meet a 3 sigma case

1

- Use tailored test procedures / hardware insulator / isolator systems to avoid over testing
- □ Use contractor procedures; Q.A. audits ensure adherence

- A. Management, Design, and Control (Cont'd)
- 7. Team Co-Location
  - □ Co-locate all team functions, technologies, & disciplines
    - Organize into concurrent engineering teams to develop a sense of "ownership"
    - Make Liberal use of E-Mail, FAX, telecommunication with customer & teammates
    - Include teammate/supplier representatives
  - Minimize team size
    - Promote team spirit/reward performance
- 8. Control
  - Short, daily actions and status-oriented staff meetings with functional heads/decision makers
  - Weekly meetings with customer to review progess issues, actions, and expenditures

💻 McDonnell Douglas 🗖

- B. Cost and Schedule
- 1. Requirements
  - □ Use contractor cost reporting and control processes
    - If over key thresholds, use CSSR not full C-Spec
      - Cost accountability to WBS Level II
  - □ <u>Reduce</u> the number of CDRLs
    - Provide visibility via government / industry working groups
    - Limit submittals to only those needed to control basic requirements, cost, schedule, and system / personnel safety

2

- □ Make liberal but judicial use of commercial parts and processes
- Baseline "redlined" drawings / procedures; cleanup/ incorporation of changes not required
- Quickly baseline and freeze program master schedule/major milestones
  - Use "work-arounds" in lieu of schedule slips
- Put heavy reliance on subcontractor's inspections and final buyoffs; strive to reduce contractor's receiving inspection to only parts I.D. and quantities checks


- B. Cost and Schedule (Cont'd)
- 2. Implementation
  - **Perform all critical functions within Rapid Prototyping Dept.** 
    - Contract Management
    - Subcontractor/supplier negotiators/administrators
    - Requirements, H/W, S/W and schedule configuration control
    - Computer aided analysis, design, drawings, autocoding
    - Drawing check, release & control
    - Procurement
    - Receiving/shipping authority
    - Control booths/stockrooms
    - Production control/follow-up
    - Material reviews/dispositions
    - Fabrication/tool orders
    - Facility planning and design
    - GFE acquisition



The "lessons learned" from prior SDIO/MDSSC Rapid Prototyping programs are an integral part of the Single Stage Rocket Technology program. We continue to learn by "doing" and to apply new knowledge gained to a <u>continuous</u> process of improving our management approach techniques and processes

"Hardware Flying Fulfills the Promise of our Vision"

## Specific Guidelines Have BeenApproved For The SSRT Rapid Prototyping Department



MDSSC-GUIDELINES for SINGLE-STAGE-TO-ORBIT RAPID PROTOTYPING DEPARTMENT ы Submitted by Sadbalz Director, SSTO Programs September 1991 Paul L. Klevatt **Director, Deputy Program Manager DC-X** SSTO Programs Approved by: Approved by: Approved by: Charles A. Ordahl William Gendron Vice President, PSD Vice President, QSD Vice President, APD&T




## DC-X Objectives Support Substantiation of Single Stage Rocket Technologies

- □ System operability supportability
  - Airline type operation
  - Support systems and procedures development
- □ Rapid system turnaround
  - Mobile flight operation and ground support functions
  - Small operations crew
- □ Software rapid prototyping/modularization
  - Reduced development costs with increased reliability
  - Flexible mission planning
- Controllable vertical take-off and landing
  - Blended control
- Controllable rotation maneuver
  - Typical of operational system



## **OPERATION PROVIDE LEARNING FOR SINGLE STAGE ROCKET TECHNOLOGY**

VED2628.3 M9CV



## **Concluding Remarks**

- Lessons learned from quick, productive, cost efficient past and present SDIO/MDSSC Rapid Prototyping programs provide a basis for achieving technical & programmatic goals and objectives
  - Key principles are fundamentally identical to basic TQM tenets:
    - Build in quality, empower the work force, build teams & commitment
- Transferring lessons learned from one organization or program to another requires:
  - A total team (management & work force) paradigm shift to a new way of doing business
    - Expect some early "cultural" shocks, but also expect some near-in, rewarding successes!



AIAA 92-1706 The Impact of New Business Approaches Derived from the Manned Transportation System Study B. M©Candless II Civil Space & Communications Company Martin Marietta Astronautics Group Denver, CO and F. F. Baillif Martin Marietta Manned Space Systems New Orleans, LA et. al.

Opr: -

- A 3875 -

P-12

12 1 1 1022

## AIAA Space Programs and Technologies Conference March 24-27, 1992 / Huntsville, AL

For permission to copy or republish, contact the American Institute of Aeronautics and Astronautics 370 L'Enfant Promenade, S.W., Washington, D.C. 20024

## THE IMPACT OF NEW BUSINESS APPROACHES DERIVED FROM THE MANNED TRANSPORTATION SYSTEM STUDY

<sup>a</sup> B. McCandless II<sup>1</sup>, F. F. Baillif<sup>2</sup>, N. Lance<sup>3</sup>, B. C. Clark<sup>4</sup>, M. S. Geyer<sup>5</sup>, M. Gaunce<sup>5</sup>, H. W. Anson<sup>6</sup>, D. G. Bienhof<sup>7</sup>, D. A. Carey<sup>8</sup>, B. R. Emmet<sup>9</sup>, and E. D. Wetzel<sup>10</sup>.

### Abstract

A survey of senior contractor and NASA management was conducted to determine those factors perceived as having the greatest impact on the aerospace industry's ability to do business with the Government, specifically NASA. The results, both critical and laudatory, are categorized and discussed herein. It is anticipated that a follow-on paper will address specific means of and agencies for alleviation of the greatest impediments.

### Background

The Manned Transportation System (MTS) study contracts are being conducted by the New Initiatives Office of the NASA Johnson Space Center. The objective is to use past work and current data to provide a framework for determining the right path to follow for an integrated manned transportation system using a logical, measurable, and repeatable process. A NASA-Industry Team (NIT) was formed to obtain consensus on the needs, attributes, and top-level requirements for manned transportation and to provide technical data to aid NASA in determining the right path to follow. The NIT consists of the following NASA participants -Johnson Space Center, Headquarters, Marshall Space Flight Center, Langley Research Center, and Kennedy Space Center; and the following industry participants - Lockheed, Boeing,

Martin Marietta, Rockwell, General Dynamics, and McDonnell Douglas.

One of the Study objectives is to identify "better" ways of doing business with the Government that would aid in developing and operating a more affordable, reliable, safe, and routine manned transportation system. The business areas identified to meet the Manned Transportation System objectives were: procurement, management, organization, policy/procedures, budget, personnel, and operations.

A survey was conducted among senior managers within the government and participating companies to obtain information in these selected business areas (see Appendix A). The main goal of the survey was the identification of items that could improve industry's way of doing business with the Government. Over one hundred suggestions were received; the categorized responses of the survey are depicted in figure 1. Each suggestion was assigned to one of the selected business areas (categories) so that those with the most concern could be easily determined. The summary of the responses are presented by category in the following sections. Most responses pertain to what is wrong with the current way of doing business, rather than But where improvements to the system. suggested improvements or solutions to specific problems were identified, they wereincluded in

Copyright © 1992 by Martin Marietta Corporation. Published by the American Institute of Aeronautics and Astronautics, Inc., with permission.

<sup>1.</sup> Martin Marietta, Civil Space & Communications Co.; Denver, CO; AIAA Senior Member.

<sup>&</sup>lt;sup>2</sup>. Martin Marietta Manned Space Systems, New Orleans, LA.

<sup>3.</sup> NASA JSC, New Initiatives Office - MTS Project Manager, Houston, TX; AIAA Senior Member.

<sup>4.</sup> Martin Marietta, Civil Space & Communications Co., Denver, CO; AIAA Associate Fellow.

<sup>5.</sup> NASA Johnson Space Center, New Initiatives Office, Houston, TX; AIAA Member.

<sup>6.</sup> Lockheed Missiles and Space Company, Sunnyvale, CA.

<sup>7.</sup> Rockwell International, Space Systems Division, Downey, CA; AIAA Member.

<sup>&</sup>lt;sup>8</sup>. McDonnell Douglas Space Systems Company, Huntington Beach, CA; AIAA Member.

<sup>9.</sup> General Dynamics, Space Systems Division, San Diego, CA; AIAA Member.

<sup>&</sup>lt;sup>10</sup>. Boeing Defense & Space Group, Seattle, WA; AIAA Senior Member.

the summation. The NIT did not necessarily agree with all of the responses received, but the summation reflects the unchanged context thereof. This has also resulted in the occasional occurrence of somewhat stilled language herein, for which the reader's understanding is requested. Before the study is finished, the NIT will develop and promulgate a strategy for the attempted removal of the impediments.




Figure 1 - % of categorized survey responses on better ways of doing business with the Government

### **Budget**

Program funding constraints can cause several things to happen. For example, test hardware may be forced to be deleted and designs may be changed resulting in much higher operational costs. Emphasis on low cost is perceived to be at the expense of on-time schedules and technology advancement. Cost and budget estimates have a significant influence on program stability and outcome. The lack of multi-year funding inhibits planning for orderly and efficient development of operational capability. Annualized funding is so variable that contractors expect to cost share in order to get around the uncertainties of the Government. Programs become longer and longer due to such

constraints, which makes them more costly overall. The detailed involvement of Congress in the budgeting process (*e.g.*, redesigning Space Station Freedom {SSF}) and the resultant contractor response to reduced budget levels cause early program inefficiencies. Political constraints affect the budget of NASA acquisitions and cause many restructuring problems.

Timely funding of fiscal year options is hindered because of tendencies within the appropriation and authorization processes to transfer NASA-budgeted funds to other agencies. This often results in work stoppages, delays of scheduled launches, and increased overall costs.

There is enormous pressure at the onset

## ORIGINAL PAGE OF POOR QUAL

of a program to assume high levels of cost risk without adequate reserves to cover contingencies or growth. One recommendation is to delay the start of a program until cost estimates and budget availability match. Program budgeting should recognize program dynamics from the outset and reflect "looking back" costs. Reserves should be budgeted after the originally predicted peak cost point.

#### Management

New management practices must be introduced. To reduce costs and meet tighter enditem delivery schedules, oversight and review of projects must be sharply reduced, and authority must be delegated to those closest to the problems to allow them to effect the solutions. There is a need to streamline and reduce the number of customer reviews and meetings. Top management time is consumed by lack of delegation and excessively broad program reviews which do not concentrate on key issues. Meetings for information only that do not address any specific problems should be When meetings are held, the minimized: decision makers should maintain open lines of communications, and maximize productive time. To save costs, telecommunications should be used to reduce travel and facilitate participation by those closest to the technical problems.

Management needs to assign clear responsibility, goals, and commensurate authority to each job assignment so that the responsible person(s) can see that the job gets done. Clear goals will focus the efforts to adhere to schedule and avoid lost time. Government management needs to specify the deliverables of the program, rather than how to achieve those deliverables. Mission objectives should be defined and the technical solutions should evolve as technical problems arise. This allows people the creative flexibility in their approach to problems which leads to the most cost-effective solutions.

The lines of communication should be open between Government and the contractor. Contractors should be treated as team members in open discussions. If continuity can be maintained within the program team (NASA and contractor) the following will happen: the team will be well-informed; time will be saved on training new team members; increased cooperation and enthusiasm for the progra will be generated; and team members will hav recognition for their individual efforts. A sense of trust among Government, industry, and tea members must be established to allow th members to push ahead decisively and to reduce barriers. Each member must be able to rely of support from the others. The high degree interaction between NASA and its contractor while technically productive, also tends to place upward pressure on the cost outcomes.

Government management should sele the contractor and then let it perform desig development. The contractor should have more up-front responsibility, using clearly define requirements and goals set by management. perform its assigned role of design developmer Program direction should emphasize the proje accomplishment rather than reporting, doci mentation, justification, etc. Abortive procure ments that continue to the point where the Request for Proposal (RFP) is expected any day and are then dropped, should be avoided reduce the wastage of contractor resource which ultimately are paid for by the Gover ment. A level of risk should be established enable the Government to communicate th likelihood that funding will be available t consummate any given procurement.

### **Operations**

There are outdated design/integratio processes used today that concurrent design systems engineering, and integrated produ development teams should improve. Establish ment of concurrent engineering teams t evaluate candidate designs and system archited tures should reduce the complexity of interface during the design phase. These teams need to b established early in the program. A "skun works" activity may be one way to effective formulate the concepts and system definition on which the overall program developmer effort relies: production (logical manufactur ing processes), operations (reduced manpowe and documentation), specialty engineerin (safety, quality, reliability, maintainability etc.), and design.

Having a "Design-for-Operations philosophy in the front end of a program ca reduce overall acquisition and support costs This is substantiated by quantitative modeling techniques and by experience. The F-117A has shown a reduction of over 25% in operations costs based on this concept. The F-117A Program also used commonality of hardware and saved over \$60M in DDT&E costs for avionic systems.

The Japanese approach to reliable product development is to engineer, in the product definition phase, both the design and the manufacturing process to provide a stable production approach and a product that is highly This "concurrent engineering" proreliable. cess produces a basic product design that will accommodate the normal statistical variance that can be expected from the manufacturing process. If the design and manufacturing process are properly developed together, a quality product can be built and statistical process control utilized rather than 100% inspection.

If design, fabrication, and operational processes for space hardware are put together using the following suggestion (e.g., launch vehicle), the results could possibly be a system with lower costs and greater reliability than any existing element of space hardware. The development team must establish an approach for the concurrent engineering of the element that will assure, to the maximum extent possible, a producible and reliable design. Before the hardware design of the element is started, an extensive analysis should be conducted of the functional operation of the total system to determine the design limits that must be placed upon all the critical subsystems/ components to assure acceptable system functionality.

This effort first requires a functional flow analysis of all the subsystems that make up the total system. This analysis should flow the operational requirements down to the major component or Line Replaceable Unit (LRU) level. Next a consistent computerized systems simulation model should be developed and utilized to apply Taguchi's techniques to establish acceptable operational limits on the subsystems down to the same LRU level.

When these limits are known and an assessment of the operational environment has been made, concurrent engineering design studies for the LRU's can begin. These studies

must include considerations for all elements of the launch system's life cycle. The product and process designs must result in LRU's that can be repeatedly built and operated reliably within the specification limits and with the only inspection being to assure that there is no human error in putting them together. The Mean Time Between Failure (MTBF) of the LRU's must be high enough that operational testing is not required to assure systems reliability.

A suggestion to minimize long term operating costs was to consider the impact and influence of logistics requirements on the system design early in the design phase of a The "blind spot" associated with program. inadequate front end analysis of logistics requirements results in an incomplete concurrent engineering process. The Department of Defense (DOD) major systems managers demand logistics assessments as a part of the concurrent engineering process, knowing the impact on long term operating costs. One obstacle encountered in implementing this suggestion was that funding constraints continued to reduce or cancel the logistics engineering analysis tasks.

It would greatly improve the implementation of the NASA management information data system if there was compatibility of computer hardware and software between NASA Centers. There could be an imposed standard of hardware/software requirements so that NASA computer systems can be compatible. The computers would be better utilized if there were more commonality.

### Organization

An understanding of the division of authority between NASA Centers is often not clear. Multiple Center roles and responsibilities need to be complementary rather than overlapping. Standardization of business practices between Centers would greatly improve the efficiciency of doing business. Paperwork is sometimes required by one Center for another Center that, in turn, actually demands something different.

Another area for improvement is when Level II wants all changes coordinated with the element for feasibility of concept approval before a Level II Program Change Identification Number (PCIN) is processed. The Level III projects do not appear to want to listen to improvements or changes that are not within their current funding structure. After the PCINs were processed, Level II had to direct Level III to assess the changes, which took over a year to complete. Time is costly. To reduce the time, one suggestion might be for Level III to consider sponsoring the change if they become involved. It would also allow an independent evaluation of the element data.

Use the major prime contractor as the integrating contractor. Contract design through launch with no second or third parties involved (*e.g.*, Shuttle Processing Contractor).

Within an organization, establish separate work centers focusing on one function or product with all supporting elements under the direction of the work center. There may be obstacles to overcome when co-locating some of the functional elements in the work centers due to the perception of where their traditional place is in the organization.

### Procurement

The procurement processes are fundamental to how a program succeeds. A procurement approach is needed that; 1) is applicable even with "international partners," (2) can get work going within a few months, (3) expends only a small percentage of the resources on the effort of the procurement process itself, and (4) has a way to continue to utilize the capability that has been built-up during a competition. The process needs to find the best combination of capability, motivation, and low cost, and also to leave the losing competitors with somewhere to go and something to do.

The procurement system needs to be simplified and kept honest. One suggestion on how to keep it honest was to establish a type of referee system whereby all procurement decisions are made by people who are precluded from subsequent involvement with the companies involved. The policy should be made simpler with no contractor involvement in the development of the statements of work. This includes support contractors -- competitive procurements should be fair to all. The procurement "boilerplate" needs to be streamlined. A large amount of effort is spent answering untailored specifications. It takes too long to get through all the steps to receive approval on procurements, both initial and modifications. Reduction in reporting requirements would simplify and keep costs down within the program. The Government could take advantage of the contractors' reporting systems to reduce or eliminate specific government reports.

The NASA Research Announcement (NRA) is a good approach for small studies and is a step in the right direction for larger contracts. The use of the NRA has resulted in less than a 30-day turnaround of award from proposal receipt from the contractor and streamlined the process of getting the contractor on board earlier. Level of Effort (LOE) contract types are good for increased flexibility. In all contracts, there needs to be an easier change mechanism because it takes too long and involves too many people.

<u>Development of new</u> systems should not be competitively priced. In fixed priced developments, the contractor is forced to throw out things that can be significant (*e.g.*, testing).

The imposition of a Performance Measurement System (PMS) on a one-of-akind type of DDT&E program (*e.g.*, SSF) is not wise. PMS does well with a production program and products that are well defined.

The cost of complicated procurement regulations unnecessarily raises the costs of Standardizing the planning launch services. system to reduce acquisition complexity may help keep the costs down. The current acquisition process forces unrealistic cost schedule submission. Suggested solutions to improve the acquisition processes are to: (1) develop new cost estimation methodologies, (2) establish requirements early and conservatively, then avoid changes; (3) utilize multiyear authorizations and appropriations, (4) allow more flexible/realistic contract type selection, and (5) promote total quality management (TQM) at all levels.

Incentives for the contractors to meet or exceed the program objectives would help keep

costs low. For example, Rockwell International earned 20% of every collar it saved NASA on building the Endeavor. Incentives could include: direct grants to develop new technology for systems specifically directed toward saving costs rather than increasing performance; cash incentives to firms for reducing the manufacturing costs of specific items procured by the Government; and encouragement of industrial teaming arrangements in focused technology areas such as the National Aerospace Plane Materials Consortium. In addition, the U.S. Government could stimulate the private sector's innovative creativity by issuing a request for proposal for space transportation services, and having industry bid on the end product (e.g., 4 seats to/from SSF every 90 days). Such an approach assumes minimum Government oversight over the design and manufacturing processes. It would also require the aerospace community to assume much greater financial risk than it has taken on in the past. In order to offset that risk, the Government would likely have to agree to a minimum purchase that would allow the companies involved to earn a profit on their investments.

Financial incentives passed through to the individuals working on a program would increase enthusiasm and motivation for working on the program. The individuals would be more personally responsible for the quality of their own efforts, and there would be less peertolerance of poor performers, who would otherwise dilute the financial incentives.

### Personnel

The only suggestion that was received explicitly regarding personnel was to off-load people supporting development programs when the development is complete. This is an ingredient of a successful low-cost, high technology program, but should be coupled with a plan to retain or otherwise utilize the people within the company so that their expertise is available "on-call" as required.

## Policy/Procedures

Lack of programmatic stability results in the wastage of resources to replan and in the loss of credibility of current schedules (caused by funding constraints, new requirements, *etc.*). The program planning process, in

particular the cost and budget estimation processes, have a significant influence on the program's stability, and hence its outcome. The essential problem is that there is currently no process which formally connects policy and the budget. At the top level, there is a space program policy. That policy should be broken down into particular pieces of the space program, and then further broken down into Level 1 requirements. Eventually, the Level 1 requirements would get decomposed into lower level derived or implementing requirements. The policy and top level requirements would tell NASA what it has to do. On the other side, there is the budget, which reflects the monetary constraints on the job NASA has to do, as defined by the policy and top level requirements.

The solution is to develop and implement a process which links the budgets and the requirements. The link is <u>especially important</u> very early in the life of a program, but is required throughout.

NASA should start at the top: identify and prioritize what it wants to accomplish; what the "mission need" is; and what it would cost. These must be in harmony before proceeding further. Just as the generation activity of the technical requirements is recognized as being iterative, with the product improving with the number of iterations, the policy/requirements *versus* budget process should also be iterated until the desired quality of product and agreements are achieved.

The risk of not doing this is a vicious cycle of undesirable events: (1) people in control of the budgets don't trust us; (2) those who don't trust us tend to micro-manage us; (3) as they get into micro-management, they squeeze the resources or add their technical requirements to replace those we didn't have or didn't clearly enunciate; (4) as we get squeezed, we tend to take what we can get, since we find it difficult to stand fast to requirements which weren't clearly enunciated or which had poorlyor un-defined mission needs; (5) taking what we can get, instead of what we should have written down, further damages our credibility.

NASA needs to prove to the administration and to Congress that it can run multi-year programs in a cost-effective manner, particularly such programs as the Space Shuttle which presently operate at levels of more than four billion dollars per year. Once NASA has reduced these costs and demonstrated this management capability and before it inaugurates new programs, it must make sure that it understands the top level needs, and that backers are available to support them with cash. Otherwise, these programs will be prey to multiple analyses and external micro-management.

While concept definition is fun for the participants, usually not enough work is done on accurate program planning and costing which should include supportability and even phaseout. Structured, recognizable, processes should be established which are consistent across the NASA and engineering contractor community.

It is felt that any program development can be accomplished in 3 to 4 years once uncertainties are resolved. The government should allow for more flexible contractual arrangements (less rigorous procedures and documentation). It was also recommended that the quantity of pre-phase A and B contractors be minimized.

Contractors complain that the cost of continued excessive government oversight and complicated procurement regulations unnecessarily raises the costs of launch services and/or programs. In the commercial sector, products or services are procured by the customer. The oversight in the production of those products or services is held to a minimum. In government contracting, the contractor engineering force is unnecessarily duplicated by the Government.

Purchasing launch services competitively from private firms, rather than managing launches from within NASA or the armed services, might well save money. The intent of purchasing launch services is to remove the Government as much as possible from setting detailed engineering specifications for that launch system and to reduce the burden of excessive oversight by Government managers. NASA could adopt the way the Federal Aviation Agency (FAA) does business in that they set the "airworthiness standards" and then let the industry design, develop, and qualify products to meet those standards while filling a need.

In streamlining the policy/procedure processes, a commitment to total quality management needs to be made. Some of the suggestions for the policy to incorporate are: (1) use statistical design and manufacturing process development to produce parts within the specification limits and to establish expected failure rates/modes; (2) have a "Design for Operations" philosophy in the front end of a program that would reduce overall acquisition and support costs; (3) minimize the levels of approval required for simple changes; (4) minimize formal contract deliverables; (5) decrease the time of the evaluation/definitization cycles for change orders; (6) confine review item discrepancies (RIDs) at preliminary and critical design reviews to design topics -not requirements -- and do not change them between reviews; (7) automate the flight and mission planning systems and standardize vehicle loads to specific weights and centers-ofmass, which would save large amounts of manpower intensive planning; (8) establish documentation structures which accommodate the total program requirements definition.

NASA is perceived to hold too much work in-house. It appears that they prefer to do the conceptual and preliminary design work themselves, competing with the contractors for business. In this process, they change system requirements, the program objectives become cloudy, and the program frequently loses support. If the NASA Center's mission is to be the design center, then it should perform the design function and contract only for manufacturing, assembly, and testing where there is no in-house capability to accomplish these functions. The alternative is for NASA to hand the contractor a set of requirements and to allow it to design and provide a system that satisfies those requirements.

Low cost innovation can be encouraged by providing contractors with an incentive and giving them the autonomy to implement changes without a lot of red tape. By providing incentives to change, a culture of constant improvement can be created. The Government should consider technology transfer to the ones developing the product and providing more of the technology work effort. They should also insure that the technology is proven prior to the end of the program. As manpower reductions on the contractor side take place as a result of implementing new ways of doing business, it is imperative that the Government reduce personnel proportionally. This would maximize the savings that result from such changes and also help the contractors to see that their efforts are matched and appreciated by their partner, the Government, in pursuing space goals. Positive accomplishments should be the primary determinants of new business and continued employment. If an area is cut, then the government employment should go down at least in proportion with the contractor's.

Government should consider entering into longer-term commitments with suppliers to purchase larger lot sizes. That could reduce the component unit cost substantially, which would directly benefit the competitive position and increase sales and profitability for the supplier. It would require some risk on either the prime contractor or the government. The Government would have to commit future budget funds which would reduce their budget flexibility. The contractor would have to take title to unsold goods with the expectation of adding value and reselling at a profit.

### **Requirements**

NASA programs need to have a multitiered requirement system in order to unfold successfully. Starting with an objective from the President or upper management, each tier needs to come up with appropriate requirements, working on down to the smallest elements of the program. For example, a broad brush objective may be a permanent base on the moon, a goal set by upper management. This implies requirements for a transportation system, habitat, and other support elements. In turn, these elements must be defined for the number of people they transport or support on the surface, resulting in further requirements for lower tiers.

Such a functional decomposition has long been employed by military programs, and could be adopted more widely and consistently by NASA. With the broad top-level requirements determined, configuration control could be employed early to make sure that concepts for program elements address upper level requirements Specifications must not drift off. once program elements start to drift away from the requirements, "You've lost the game." In the case of the military, a new system User Command will require a weapon system to counter a threat: the weapon system might be a fighter aircraft to counter ground-based weapons. The user group goes to the Systems Command to establish the definition and requirements for the weapon system, determining how it has to perform within a certain envelope. Specifications are then based on trades.

In the case of NASA development programs, in the Phase A portion of a program, contractors for one reason or another provide upper level designs instead of requirements. In the case of SSF, the requirements were set in Phase A studies, but they were set too broadly, or else disregarded to such a great degree that the Phase A contributed little substance to subsequent development of the project. When requirements for micro-"g" laboratory operations were imposed on the program, it was after the Phase A studies were complete, and without the needed configuration control. On the other hand, in the case of Apollo, the successful system engineering procedure was performed intuitively rather than formally.

It has been difficult to integrate payload or scientific requirements into the NASA engineering process, often because a multipurpose vehicle attempts to integrate mutually exclusive requirements and because managers are not ready to say "no" to what users want.

Since requirements are the first products in any potential program, and since they are very important to the life of that program, NASA should spend more quality effort on this product. Ways to accomplish this are to include certifying requirement writers before they are allowed to write any and requirements "stamping" for certification -- much akin to the SR&QA stamps of approval -- to insure they are true requirements and not "desirements". There should be at least a center-wide, if not agency-wide requirements tracking and control "tool," and perhaps even a requirements organization to insure uniformity of the requirements within a program and across programs. The technical organization within a program should develop the parameters that need to be controlled, and rationale for why they need to be controlled, so that discussions can be held involving all parties before actually discussing any quantified parameters.

The Government should define what it wants in a mission statement and establish the All requirements must be requirements. identified so that efforts are not wasted trying to satisfy unidentified requirements. It should let the contractor formulate the concepts and designs that meet the requirements, while providing the technology support required. The Government should review the concepts and designs (validating them against the requirements), advise, approve, and let the contractor implement the program. Once established, requirements should be changed only when All parties must stay absolutely necessary. focused on the mission statement instead of trying to meet excessive, sometimes conflicting, utopian requirements.

#### Summary

There is still much to be done on this topic. By the close of the study, the survey responses will have been prioritized by the manner in which they affect the way the new manned transportation system will be initiated, developed, and operated. Elements that have the authority to make improvements in the way we do business (*e.g.*, NASA centers, NASA Headquarters, Congress, *etc.*) will be identified and correlated with the required actions. A strategy will be developed to attack the major barriers to improvement and to implement the new ways of doing business into the next manned transportation system.

### Solicitation

The survey form used for the solicitation of inputs in conjunction with this study is attached as Appendix A. Readers are encouraged to submit additional inputs for consideration by the team as it prepares the final study report. "White space" within the form proper has been somewhat compressed in order to stay within the page limits for reproduction in this format, so feel free to use additional sheets if required. Responses may be mailed to:

> Bruce McCandless II Mail Stop DC8001 Martin Marietta Astronautics Group P. O. Box 179 Denver, CO 80201-0179

or FAX-ed to: (303) 971-5021. All inputs must be received prior to June 1st, 1992, for consideration.

Appendix A

## "THE IMPACT OF NEW BUSINESS APPROACHES" Task #4 of the MANNED TRANSPORTATION SYSTEM STUDY

Contracts NAS-9-185xx {Point of Contact} ...70: Boeing {E. Wetzei: (206) 773-1048} ...71: General Dynamics {B. Emmet: (619) 547-3865} ...72: Lockheed {J. Kerwin: (713) 282-6204} ...73: Martin Marletta {B. McCandless: (303) 971-6308} ...74: McDonnell Douglas {D. Carey: (714) 896-3186} ...75: Rockwell {D. Bienhof: (310) 922-4918} Sponsor: NASA Johnson Space Center {N. Lance: (713) 283-5508}

The MTS Study contract is being conducted by the New Initiatives Office of the NASA Johnson Space Center with the six industry participants indicated above. We are looking for a list of key impediments or new ways of doing business that you have encountered or are currently encountering in your experiences with Government contracts. Your input(s) will be combined with similar comments from other programs and functional areas across several contractors to focus efforts on how to improve our collective programmatic efficiency. A final NASA-Industry Team report, embodying the results of this survey, will be prepared, presented at appropriate levels within the NASA, and placed in the public domain.

Areas of interest include, but are not limited to, Organization, Management, Operations, Procurement, Personnel, Policy/Procedures, and Funding/Budgetary topics. Specific examples are useful for improving the readability of the report, but we are looking for broadly applicable material. Negative examples are acceptable, but the emphasis is on how to do more with what we have in the context of NASA-related business. Anonymity of organizations will be maintained in the final report(s) if such a desire is indicated above, but any information supplied will be available at the working level to all MTS Study contractors and participating Government elements. Additional pages may be added to this questionnaire at your discretion.

1. Please identify the top three to five things that would (have) result(ed) in the greatest improvements in your way of doing business with the Government.

- 2. Your Company/Organization:
- 3. Program/Project/Functional Area:
- 4. Point(s) of Contact for further info:

Tei: ( )

5a. Is it O.K. to identify your Company? Yes/No 5b. - - your Program? Yes/No 6. Were you able to actually implement the above improvement(s)? What obstacles were encountered? How were these overcome? 7. What risks are involved in the foregoing? Do you have any suggestions for mitigation?

8. Can you quantify the savings/level of improvement?

9. Approximately how large (dollars, man-months, or peak number of personnel) is/was your area of responsibility?

10. Was this a prime contract or a subcontracted effort? Were you teamed with any other serospace contractor?

11. How would you assess the PLANNED schedule duration vs. the magnitude of the task and the length of time ACTUALLY required?

12. Can you compare or contrast your way of doing business with the Government with practices in the U.S. commercial or international sectors?

INTERVIEW/DISCUSSION POINTS

- \* What gives you the most "heartburn" in dealing with NASA?
- \* Are documentation requirements: Excessive? Conflicting? Duplicative? Restricting innovation?

è

- \* What can you say about procurement policies/regulations?
- \* How is the interface with your customer(s)?

 Is your test program: About right? Duplicative as hardware progresses towards launch? Still addressing obsolete requirements? A great burden to your program?

\* Are there any personnel/human resources policies/practices that are causing you difficulties?

# FIRST LUNAR OUTPOST CONSTRUCTION ANALYSIS


Team:

Chris Grasso (EE) John Happel (CE) Brent Helleckson (Aero) \* Steve Jolly (Aero) (303-482-0559) Dr. Martin Mikulas (Prof., Aero) Jane Pavlich (EE) Dr. Renjeng Su (Prof., EE) Rob Taylor (Aero)


1 SDJ\_5-13-92


Z

0 20




Some Studies Suggest  $\frac{*785 \text{ g/ cm}^2}{1.66 \text{ g/ cm}^3} = 473 \text{ cm of Regolith}$ 






# Feasibility Analysis: A SMALL LUNAR TRACTOR-SCRAPER (LTSV)




cSc

Gross Mass	1300 kg
Empty Mass	925 kg
Payload	.25 m**3
Velocity	.305 m/s
Time-To-Fill	58.97 s
Cutting Depth 1.4 cm	
Apollo LRV Wheels	
Power: 27	5 kg NiH2
Duty: 12 hours	


- Estimate Power Requirements
- Perform Reliability Analysis
- Try Dragline Crane, Bulldozer, Front-End Loader






280

C





## A SINGLE LAUNCH BASE POSSIBLE MANIFEST?

20 MT SSF Derived Habitat Module with Airlock


06 MT Lunar Excursion Vehicle (LEV) - Dry, e.g. 90-Day

01 MT (est) Lunar Self-Offloading Lander Crane

04 MT (est) 3 Lunar Tractor-Scraper Vehicles

cSc

02 MT (est) Fully-Below Superstructure Arch (composite)





Engineers and Builders of the Future

112517 N92-33326

(505) 455-3484

Route 1, Box 92 LL - Santa Fe, New Mexico 87501, U S A

## Dome Cities for Extreme Environments

Raymond S. Leonard<sup>1</sup> and Milton Schwartz<sup>2</sup>

## Abstract

Extreme environments whether they be the frigid nights of the poles, the burning sands of the desert or the harsh environment of space pose interesting challenges to the Architect, the Engineer and the Constructor in their efforts to create habitats for mankind. Current or modern approaches seem almost primitive in that they seek minimums which confine and stifle the spirit rather than draw on technology and heritage to create environments for the human spirit which will allow it to grow. This paper is a discussion of the potential of separating some or all of the environmental protection functions from the structures providing privacy. The result is a graded environment for human habitation.

On Earth the major issue is thermal management. For arctic like environments the issue is to minimize the heat loss while providing an environment that not only maintains or merely sustains life but enriches. In the desert regions of the world the issue to minimize heat gain while preserving water. In both cases the goal is to create an oasis for human life. On Earth large domes offer a different approach. Large domes allow us to provide a buffer between the offices, living areas and recreational areas of small communities and the extreme environments in which they are located.

In space the goals are to protect from radiation while providing an aesthetic living environment for long duration missions. The need to provide both radiation protection and options for expansion of base facilities led the authors to create an unique structural system which separates the radiation protection systems from the pressure envelope of the habitats. The system uses cable networks in a tensioned structural system, which supports the lunar regolith used for shielding above the facilities. The system is modular, easily expandable and simple to construct. Additional innovations include the use of rock melting perpetrators for piles and anchoring deadmen and various sized craters to provide side shielding. The reflective properties of the fabric used in the membrane is utilized to provide diffuse illumination. The use of craters along with the suspended shielding allows dome to be utilized in fashions similar to those proposed by various designers unaware of the Moon's hostile radiation environment.

Additional topics addressed deal with construction techniques for large domes, i.e. on the order of 100's to 1000's of meters, thermal control, the integration of tertiary water treatment schemes with architectural design, human factors and its implications for the design of habitats for long term use in extreme environments

 President, Ad Astra, Ltd., Rt. 1, Box 92 LL, Santa Fe, NM 87501, Tel (505) 455-3484
 Fax (505) 662-0099

C-4

Principal, Milton Schwartz Architects, 236-A Tano Trail, Santa Fe, NM 87501, Tel (505) 989-8250, Fax (505) 988-1681

Engineers and Builders of the Future

Route 1, Box 92 LL - Santa Fe, New Mexico 87501, U S A

(505) 455-3484

## Dome Cities for Extreme Environments

Raymond S. Leonard, PE<sup>1</sup> and Milton Schwartz, AIA, PE<sup>2</sup>

Note that the concepts of using tensioned structures for creating a suspensed radiation shield and the use of rock melting technology and microwaving regolith into structural columns are consider innovative and have been disclosed to Los Alamos National Laboratory per consulting agreements for evaluation as to patentability.

## Introduction

Extreme environments whether they be the frigid nights of the poles, the burning sands of the desert or the harsh environment of space pose interesting challenges to the Architect, the Engineer and the Constructor in their efforts to create habitats for mankind. On Earth the major issue is thermal management. and the current approach is to confine mankind in boxes. Proposals for habitats in space range from tubes and spheres to fanciful artist concepts of large domes.

The challenge is to create or construct habitable environments which speak to the human spirit as well as to the minimums needed for survival. In the desert regions of the world the issue to minimize heat gain while preserving water. In both cases the goal is to create an oasis for human life. Malls, air bridges, and underground shopping areas in northern cities point to potential design solutions for Earth based habitats. Construction technology and economics have to develop hand in hand in order for domed habitats to become a cost effective solution as well as aesthetic solution.

<sup>&</sup>lt;sup>1</sup> President, Ad Astra, Ltd., Rt. 1, Box 92 LL, Santa Fe, NM 87501, Tel (505) 455-3484 Fax (505) 662-0099

Principal, Milton Schwartz Architects, 236-A Tano Trail, Santa Fe, NM 87501, Tel (505) 989-8250, Fax (505) 988-1681

For long duration missions or assignments to other planets the minimum goals are to protect from radiation and provide a habitable environment. If only minimums are to be meet and there will be no permanent settlements then tubes and boxes are the most cost effective. The Navy has shown that it is possible to keep over a hundred and thirty men working effectively in a confined and isolated tube, i.e. submarine, for up to ninety days. On the other hand experience in the arctic oil fields has shown that for assignments which approach being permanent more space and amenities are needed.

For arctic commercial operations the current approach consists of building large modules in the lower 48, shipping them to North Slope Oil Fields and installing them. The environmental hazards are cold and wind. Each structure wears a covering of thick insulation and requires considerable energy to counter both the cold. An alternative approach would be to erect large domes with a double skin for both strength and thermal insulation. The dome creates a volume of still air which is slightly heated by heat escaping from the structures enclosed within the volume of the dome. The inner surface of the transparent panes are coated to reflect back the infrared radiation being radiated by the buildings. Within the dome there would be the normal structures and landscaping. Waste heat from refrigerators, cooking, and normal activities would be rejected to the dome's interior atmosphere. The advantages are the creation of open space where people can walk without fear of the arctic winter winds and the energy savings which comes from not having to heat the buildings inside the dome against the wind.

While domed cities in the arctic attempt to keep the heat in, the equivalent of the lunar night, the desert environment imposes the design requirement is to minimize thermal gain, the equivalent of the lunar day, and water loss. In this case the outer layer of transparent panels are coated to reflect both UV and IR radiation thus minimizing the heat gain. On the north side of the dome the shaded radiators reject the heat load from the human activities inside the dome. Part of the tertiary water treatment system would be to run the water through irrigation channels or artificial stream beds inside the dome. This would help humidify the air and provide a pleasing background. This approach would emulate traditional practices of people living in oasis in the Sahara.

In the Sahara water is collected from the aquifers by long tunnels known as foggaras. The collected water runs through irrigation channels to the date palms. Close to the source the people draw their drinking water and in the village they add sewage or nutrients to the stream. Although the water is put to multiple uses it is in the end still lost.

Biosphere 2 is an experiment to see if a natural closed loop system can be created. It is ambitious and may or may succeed. Domed villages in the desert don't have to be as ambitious. They can allow for air exchange and if they minimize water lost they have gained a significant economic advantage.

Tertiary water treatment developed by civil engineers and filtration systems being developed for space exploration will allow use to create gardens in the desert complete with water falls and gardens. In the case of the semi-closed environment of the dome the water would be re-cycled. Some treated and some captured from the air after it had been transpired by the plants inside the dome.

Ignoring the question of economics of large domes, which is not unreasonable given the reasoning city governments use to justify domed sports stadiums, the next major question is constructibility. The proposed approach is to use a series of tower cranes, which after construction form the cores of high rise buildings and communication towers which penetrate the skin of the dome. The towers can also be used to support helipads, viewing rooms and other functions. Figure 1 shows a spherical type dome. The type of dome chosen will depend in part on whether the desire is to cover acreage or to provide vertical space for aesthetic purposes.

Milton Schwartz Architect

Ad Astra, Ltd.

## Design Considerations for Terrestrial Domes

The large spans and the need for thermal management lead the authors to a double skin or a layered approach. For the desert habitat the outer skin would be composed of a combination of opaque panels of solar cells and transparent panels treated with films to reject infrared radiation. The secondary skin would be composed of transparent panels coated with films to filter more of the thermal radiation. Consequently the amount of thermal gain or lost experience by the atmosphere and structures inside the dome would be controlled.

## Design Considerations for Lunar Systems

Having looked at two extreme environments on Earth we considered the problem of creating livable space on the Moon. The basic or major factors in the design environment are: vacuum, thermal cycling and radiation. The basic concepts, which have been suggested for lunar structures, are shown in the next set of figures. They range from tubes on the ground to sand bagged spheres.

Our first thought was to incorporate the required radiation protection into the envelope of each structure within the dome. In this case the residents would have windows three feet think for radiation shielding and could look out on gardens and open spaces. In some cases they might even be able to walk around outside if the solar radiation levels were low.

We considered putting the necessary shielding on the dome itself but this greatly increased both the strength needed in the structural system and the construction complexity. Constructibility is a concept often overlooked by many designers who extrapolate designs that are workable in a highly industrialized society to either developing countries or the lunar surface.

At this point one of the authors, Milton Schwartz, combined our layered approach with both cable roofing systems and the use of small craters. The resulting concept is one where a cable network roofing system is used to create a suspend radiation - shield. Underneath the shield the construction camp can gradually be expanded until the construction expertise and resources are available to enclose the individual habitats in a dome.

.-

revision: 2/9/92

288

The system is adaptable to both the lunar plain and to covering craters. In the latter case the crater walls provide the necessary side shielding. The approach is feasible because while weight changes with gravity the strength of materials doesn't. In addition we don't have wind loads to worry about on the moon. This sort of structure, tensioned cables, has been used around the world in applications as varied as sports arenas and in Saudi Arabia.

Milton Schwartz Architect 10

Ad Astra, Ltd.

## Tension Structures

Tensioned structures are load adaptive in that the structural system changes shape to accommodate changes in load rather than increase stress levels (Leonard, 1988). They transmit their loads to the support system though tensile stresses. Quoting further from Leonard, 1988, tension systems can be comprised of membranes, cables or combinations of both.

Tensioned structures can be grouped into two broad categories: uniaxially stressed cable systems and biaxially stressed systems such as membranes and nets. Suspension bridges such as the Golden Gate Bridge are an example of the first type.

There are four major categories of cable structures, Leonard, 1988:

- 1. Single cable systems such as guy lines for towers or tents.
  - 2. Cable trusses, e.g. cable stayed bridges and double layer cable supported roofs.
  - 3. Cable nets which are multiply connected in a curved surface and loaded normal to the surface, e.g. hanging roofs
  - 4. Cable networks forming a three-dimensional framework.

There are also four major categories of membrane structures, Leonard, 1988:

- 1. Air-supported structures where an enclosing membrane is supported by a small differential pressure..
- 2. Inflated structures which use highly pressurized tubes or dual walled mats as structural members.
- 3. Prestressed membranes where fabric is stretched over rigid frameworks to form diaphragms such as tents, masted roofs.
- 4. Hybird systems in which membrane panels span between primary load carrying members such as prestressed cables.

•

revision: 2/9/92 290

• .

S. Gov t

Why consider tension structures? The following reasons where given the 1979 ASCE special publication on Air-Supported Structures:

- 1. They are lightweight, collapsible and easy to transport.
- 2. They can be prefabricated in a factory.
- 3. They have low installation costs (low labor component)
- 4. The environmental loads are carried by direct stress without bending.
- 5. For air supported structures the primary load carrying mechanism is the habitable environment itself.

Hybird tension structures could be used as initial shelters in hostile environments, Leonard, 1988. A double wall system could first be inflated with air and later the wall foamed with a hydrated boron compound which would absorb the secondary thermal neutrons produced from the collision, i.e. stopping, of high energy particles with the primary radiation shield.

## Dead Loads and Radiation

The radiation environment drives the loading condition. Discussions with radiation transport specialists (MacFarlane, 1991) indicated the need for a shielding thickness of between two and three meters. One meter is often sufficient to stop the primary radiation. However the stopping of the primary radiation results in the production of secondary neutrons which require the extra thickness in order to attenuate them. Otherwise the thin shield actually becomes a radiation generator radiating neutrons at an energy level which is fairly harmful to humans.

Discussions with George Augenpaugh of SST-8, Space Physics, indicates that an astronaut on the surface of the Moon would be in a radiation field equivalent to that of free space due to the production of secondary neutrons and their refelction or bouncing upward from the luanr surface. These findings are preliminary and based on 3-D radiation transport codes as opposed to the standard one dimensional codes used in most studies to date. Once the calculations are checked a peer reviewed publication will be issued which can be cited.

revision: 2/9/92

## Description of Concept

The basic system is simply a network of cables with a membrane laid over the interconnected cables. If the system is to be erected on a plain a series of pylons have to placed along with deadmen for anchoring the cable ends.. If the system is to br placed over a crater which is deep enough then only the anchors for the cable ends have to be placed. Depending on the spans a three-dimensional system may be needed. The tension structural system proposed can take on a number of different shapes. The system can be rectangular and expandable or it can be designed to take advantage of a small crater. The advantages besides those listed above are:

- 1. An attenuated radiation field under the structure, which can be handled by light weight, high hydrogen content insulating materials.
- 2. Controlled thermal environment, i.e. a constant, known environment as opposed to the large thermal swings between the lunar day and night.
- 3. Large open spaces for base expansion without the need to move shielding material around whenever an expansion or facility repair is needed.

•

IS. Gov't

Milton Schwartz Architect

Ad Astra, Ltd.

## Materials of Construction

The basic materials used are cables, membranes, columns or poles and lunar regolith.

Weight considerations rule out steel cables. That leaves kevlar and some sort of fiberglass. For terrestrial applications there are many other choices. One long range possibility is to fabricate ultra high strength glass fibers from lunar resources. Jim Blacic of Los Alamos has been working on producing and testing glass fibers in an anhydrous environment. Steve Howe, also of Los Alamos, suggested coating the fibers with titanium obtained from processing lunar soils.

Membrane materials will probably be limited to kelvar, fiberglass or beta cloth. The fabric should have a fairly high resistance to accidental damage. It should be easily seamed or jointed.


For the pylons and deadmen we propose to adopt rock melting technology developed at Los Alamos. This is the expensive part of the system since because you leave the tip in place it is a consumable. Most of the pylon would be aluminum with only the tip made out of more exotic materials. An alternative would be to use a thin wall fiberglass cylinder which after it was placed could be filled with regolith. The regolith would be sintered into a solid mass using a variable frequency microwave generator. This would minimize the amount of mass that had to be landed.

The tip of the pile (pylon) would contain a melting system which could be either electrically driven or heated through the use of heat pipes driven by concentrated sunlight.


revision: 2/9/92


1 105 .

/




SURFACE STRUCTURE 3METER REGOLITH SHIELD (BETACLOTH COVER) SHETER BERM and it she with the state ADVANCED DOME HABITATS MODULOR-EXPANDABLE CABLE MEMBRANE RADIATION : SHIELD & MICRO-METEORITE SHIELD COLUMN SUPPORT Rock. MELTER HoLE SURFACE - GRADER / LOADER GABLE - TENSION UNIT INTIML PHASE SHIELD STRUCTURES HIGHENERGY POWER SOURCE -COLUMN ( TRI-POD LEGS ROTATE TO BASE PLATE DOFT DUST LAYER, A Lock POSITIONS NSE SOIL LAYER BASE PLATE - BEARNG NITIAL PHASE SHIELD STRUCTURES - LOW ENERGY POWER SOURCE LUNAR CONCEPTS ! MILTON Schwartz - AIA. PE 296 RAYMOND. S. LEONARD PE 1 VOD .2.U NOULNER IGOI





U.S. Gov 867




MILTON SCHWARTZ - AIA - PE RAYMOND S. LEONARD - PE OCTOBER 1991

LUNAR SURFACE STRUCTURE.

CABLE /MEMBRANE RADIATION SHIELD TOPCABLE VARIABLE ANGLE DISTRIBUTION HEAD ± 10 METER RANGE SUPPORT Extending Conveyor APPROX TO HETER RANGE BATCH FEED 2 CM /SCREEN Soil DEPOSIT CONVEYOR MOVES FROM SECTOR TO SECTOR

LUNAR CONCEPTS: MILTON SCHWARTZ AIA PE RAYMOND S. LEONARD PE 1009 501



ROBOTIC SOLAR COLLECTOR - CONCENTRATOR

Milton Schwartz Architect

Ad Astra, Ltd.

#### Rock Melting Technology

There are uncertainties associated with how well mechanical systems will hold up under the combination of heavy useage and hostile environment of lunar construction work. In looking for alternatives we re-evaluated the work done at Los Alamos National Laboratory in the area of rock melting penetrators for geological work. The next set of figures, taken from Los Alamos publications, describe some of the designs that were developed in the early 70's The work was conceptually scaled up for use in creating subway tunnels.

For our work we would look at modifying an extruding penetrator such that a solid core was left. This would be similar to the coring with consolidation penetrator shown in the figures. Our initial thoughts are to abandon the tip in place in order to simplify construction operations. However a trade off study of weight vs complexity of operations needs to be made since the penetrators are very heavy.

For anchoring the cables we envision using the penetrators to melt a chamber or cavity into which the anchorage could be placed. Then using a solar concentrator lunar fines could be quickly melted and casted around the baseplates. An alternative woud be to use sulfur concrete made for lunar resources. a la fa fa fa fa fa ca la fa

518-31 115518

N92-33327

A

CENTER FOR EXTRATERRESTRIAL ENGINEERING AND CONSTRUCTION

CETEC

#### GERALD G. LEIGH, PHD

New Mexico Engineering Research Institute University of New Mexico Albuquerque, New Mexico

As the Lead Agency for

The CETEC Development Team

#### CENTER FOR EXTRATERRESTRIAL ENGINEERING AND CONSTRUCTION (CETEC)


The urge for humans to return to and explore beyond the moon appears to be increasing, both throughout our country and around the world. On 20 July 1989, the twentieth anniversary of man's first visit to the moon, President Bush announced the national Space Exploration Initiative (SEI), which calls for the construction of a manned orbital space station, the establishment of a lunar base of operations, and the manned exploration of Mars (by 2019). Japan has placed a satellite in orbit around the moon and declared its intention to be involved in efforts to colonize the moon. National defense has diminished as the primary national priority and the manned exploration of space is emerging as a new national imperative.


The establishment of an extended manned presence on the moon will require the development and application of many new enabling technologies that are not available today. Instead of predominantly aeronautical related technologies used in orbital space, great emphasis must be placed on the research, development, testing, and evaluation of technologies for construction, mining, and chemical processing of lunar materials to form habitats and provide resources for sustaining human life. As needed processes are identified and associated equipment and procedures are developed, it will be necessary to operate and test both equipment and procedures here on earth in a realistically simulated lunar environment. A large test facility where prototype equipment can be subjected to the harsh environments of vacuum, lunar soil, dust, extreme heating and cooling, and partial gravity is needed within the next five years, if currently projected schedules for space exploration are to be achieved.

A group of knowledgeable scientists and engineers in New Mexico has recognized the need for such a testing capability and has proposed a project to develop an extraterrestrial surface simulation facility. A group of universities, national laboratories, and private industrial firms is proposing to establish a Center for Extraterrestrial Engineering and Construction (CETEC) and to develop large extraterrestrial surface simulation facilities in which this needed testing can be realistically performed.

The Center for Extraterrestrial Engineering and Construction is envisioned to be both a center of knowledge and data regarding engineering, construction, mining, and material process operations on extraterrestrial bodies and a set of extraterrestrial surface simulation facilities. The primary CETEC facility is proposed to be a large domed building made of steel reinforced concrete with more than one acre of test floor area covered with several feet of simulated lunar soil and dust. The entire building would be pumped down to partial vacuum (10<sup>-4</sup> to 10<sup>-6</sup> Torr) to provide a realistic simulation environment. Extreme heating, cryogenic cooling, and partial gravity suspension systems would be included in the facility to further enhance simulation fidelity. Large steel cylindrical tanks could be placed inside the vacuum facility and repressurized to atmospheric pressure to simulate habitat, workshop, and laboratory modules transported to the moon. Life support systems and elaborate safety procedures would be employed to permit researchers and test operations personnel to work safely inside the simulation facility. A lobby around the perimeter of the facility would permit tourists and other observers to look in through view-ports and observe test operations in the simulated extraterrestrial environment.

The development team proposing the CETEC includes the University of New Mexico (UNM), Los Alamos National Laboratory (LANL), the BDM Corporation, Ad Astra Corporation, and several large private engineering and construction firms. The CETEC is planned to be located in Albuquerque, New Mexico, on land provided by the University of New Mexico. The large simulation test facility is expected to cost between \$35M and \$50M to construct. The entire CETEC development project could be completed in five years, once funding is approved.





# WHY CETEC ?

- SIGNIFICANT CHANGE IN ENABLING TECHNOLOGIES FROM AERONAUTICAL ORIENTATION TO CONSTRUCTION, ENGINEERING, MINING, AND CHEMICAL PROCESSES AND EQUIPMENT
- SUCCESSFUL DEVELOPMENT OF A LUNAR OR MARTIAN BASE WILL REQUIRE SIMULATION OF EXTRATERRESTRIAL OPERATIONS ON EARTH
- A NEED EXISTS FOR A CENTER OF KNOWLEDGE AND FOR LARGE SIZED, REALISTIC SIMULATION OF EXTRATERRESTRIAL ENGINEERING, CONSTRUCTION, AND OPERATIONS
  - TO SUPPORT A WIDE RANGE OF CUSTOMERS
  - NO SUCH FACILITY CURRENTLY EXISTS

# WHAT IS CETEC ?

• A CENTER OF KNOWLEDGE AND EXPERTISE


1


- ENGINEERING, CONSTRUCTION, MINING, CHEMICAL PROCESSING
- ON EXTRATERRESTRIAL SURFACES
- A SET OF EXPERIMENTAL TEST FACILITIES
  - RESEARCH ON EXTRATERRESTRIAL ENGINEERING AND CONSTRUCTION
  - TEST LARGE PIECES OF EQUIPMENT
  - REALISTICALLY SIMULATED EXTRATERRESTRIAL ENVIRONMENT


THE UNIVERSITY OF NEW MEXICO ----- INDUSTRY SMALL BUSINESS OTHER UNIVERSITIES ----

LOS ALAMOS — NATIONAL LABORATORY

3








# SIMULATED ENVIRONMENT GOALS

- VACUUM (10<sup>-4</sup> to 10<sup>-6</sup> TORR)
- REDUCED GRAVITY (1/6 FOR LUNAR)
- HIGH TEMPERATURE
- LOW TEMPERATURE
- LUNAR SOIL SIMULANT
- ILMENITE MINERAL
- DUST
- MARTIAN SURFACE AND ATMOSPHERE (7 - 10 MILLIBARS)
  - CO 2 ATMOSPHERE
  - ICE
  - CRYOGENIC TEMPERATURES


INDUSTRY SMALL BUSINESS - OTHER UNIVERSITIES -

LOS ALAMOS – NATIONAL LABORATORY -



#### "SMART TETHER" PARTIAL GRAVITY SUSPENSION SYSTEM





## POTENTIAL CETEC PROJECTS AND EXPERIMENTS

## **CONSTRUCTION**

SOIL EXCAVATION FOUNDATION CONSTRUCTION STRUCTURAL ASSEMBLY/JOINING MASONRY BLOCK CONSTRUCTION EQUIPMENT OPERATION/HEAT REJECTION MACHINERY LUBRICATION WELDING DUST STABILIZATION DUST ABRASION

## **MINING & EXCAVATION**

DRILLING TRENCHING & EXCAVATION AGGREGATE PRODUCTION MATERIAL HANDLING

## **CONSTRUCTION AUTOMATION**

ROBOTIC LAYOUT OF LONG BASELINE INTERFEROMETER PRECISION STRUCTURAL ASSEMBLY & CONTROL

## **MATERIALS PROCESSING**


RECOVERY OF ELEMENTS (O2, S, Ti, He3,) PRODUCTION OF ULTRA-HIGH STRENGTH GLASS PRODUCTION OF CONCRETE-LIKE MATERIALS FABRICATION OF PRODUCTS & COMPONENTS PLASMA SPRAYED STRUCTURAL COATINGS MICROWAVE SINTERING

## LIFE SCIENCES

IMPROVED EVA WORK-SUITS IMPROVED MAN-OPERATED TOOLS

## **ACCIDENT CONTROL**

RAPID DE-PRESSURIZATION SPACE SUIT DAMAGE & REPAIR TESTING OF EMERGENCY EQUIPMENT



1155

## CRYOGENIC STORAGE TECHNOLOGY READINESS FOR FIRST LUNAR OUTPOST

(1)

John R. Schuster

### 3rd Space Exploration Initiative Technical Interchange May 5-6, 1992 Houston, Texas

GENERAL DYNAMICS Space Systems Division P.O. Box 85990 San Diego, California 92186-5990

# CRYOGENIC STORAGE TECHNOLOGY IS READY FOR FIRST LUNAR OUTPOST MISSION

- Storable propellant currently baselined for lunar ascent and Earth return
- Cryogen boiloff estimates for lunar surface indicate modest insulation requirements
- Cryogenic propulsion for lunar ascent and Earth return will reduce IMLEO by 20% to 30%
- The required cryogenic storage technology is developed and ready for mission application
  - Foam insulation to limit Earth launch boiloff
  - Thick multilayer insulation for low space and lunar boiloff
  - Thermodynamic vent system for tank pressure control in zero-g and gravity environments


1.1.1.1.

/


Lunar Transportation

 $\overline{\mathbf{S}}$ 

# **Cryogen Boiloff Predictions**



# CRYOGENIC FLUIDS TECHNOLOGY OFFICE




**Lewis Research Center** 

# SHUTTLE/CENTAUR THERMODYNAMIC VENT SYSTEM

- Compact, active type TVS concept well-suited for upper stages and space transfer vehicles
- Developed to enable Centaur hydrogen tank venting from within Orbiter cargo bay
- Eliminated the need for settled venting
- Fully ground tested and demonstrated to be insensitive to gravity
- Capable of venting up to 25 lb/hr
- Had nearly completed flight qualification when Shuttle/Centaur program was canceled in 1986

# **ZERO-G THERMODYNAMIC VENT SYSTEM**

Requirement: Vent to Control Tank Pressure Rises Caused by Propellant Tank Heating



**Component Design Requirements** 

Mixer

• To Provide: (a) Thermal Equilibrium Mixing of Bulk Propellants, and (b) Heat Exchange Mechanism Between Tank Fluid and Vent Fluid

Heat Exchanger

- Lowers Bulk Energy Level
- Assures Pure Vapor Venting Regardless of Fluid Quality at System Inlet


**Pressure Regulator** 

• Controls Vent Şide Fluid Pressure

GENERAL DYNAMICS Space Systems Division


4

# SHUTTLE/CENTAUR THERMODYNAMIC VENT SYSTEM ASSEMBLY



U

# **HEAT EXCHANGER / MIXER PUMP MODULE**



ŝ,

Space Systems Division

# THICK MULTILAYER INSULATION DEVELOPMENT PROGRAM

- Completed by General Dynamics in 1969 under contract to MSFC
- Four-inch thick Superfloc MLI
- Design of system for full-scale tank
- Fabrication and testing of system on 1/4-scale tank
  - Utilized same attachment methods
  - Scaled to achieve same blanket stresses
  - Combined vibration, acceleration and rapid pumpdown testing to simulate launch
  - No degradation in thermal performance
- Technology ready for full-scale application

BUINANYO JARABO

Space Systems Division

# **BLANKET GEOMETRY CONCEPT EVALUATIONS** (4 BLANKET LAYERS, EACH 1.0 IN. THICK)

Configuration	agore ∢	βconic ≰	Wrinkling Coefficient	Seam Length (1n.)	No. of Fasteners	No. of Blankets	Blanket Shapes
	20 deg (18 gores)	17 deg (2 caps)	1.05	12,390	2,052	80	ą
	24 deg (15 gores)	20 deg (2 caps)	1.52	10,305	1,775	68	Ň,
	30 deg (12 gores)	25 deg (2 caps)	2.35	8,256	1,349	56	8
	(3 cyl. segments)	24 deg (2 caps) (10 domes)	2.25	7,806	1,296	60	16
	(3 cyl. segment	18 deg (2 caps) (16 domes)	1.26	9, 610	1,600	84	20
6	30 deg (12 gores)	24 deg (2 caps) (4 domes)	2.35	8, 524	1,418	72	12
	20 deg (18 gores) (3 cyl. segments)	17 deg (2 caps)	1.05	12,410	2,060	164	12
	24 deg (15 gores) (3 cyl. segments)	20 deg (2 caps)	1.52	10,857	1,810	140	12
	30 deg (12 gores) (3 cyl. segments)	25 deg (2 caps)	2.35	9, 348	1,560	116	12
Rating:	1 = Configu	ration No. 4					

2 = Configuration No. 33 = Configuration No. 6




Space Systems Division

# FOUR-INCH THICK MLI SYSTEM ON 1/4-SCALE TEST TANK

; 1




## FOUR-INCH THICK MLI SYSTEM ON 1/4-SCALE TEST TANK



ORIGINAL PAGE IS OF POOR QUALITY

# COMBINED ENVIRONMEMTS OF VIBRATION, ACCELERATION, AND TEMPERATURE TESTING (CEVAT)

1:11



## 25-INCH TANK Predicted & Actual Thermal Performance

ITEM	SPACE ENVIRONMENT THERMAL ANALYSIS 1st THERMAL TEST 2nd THERMAL TES			GROUND HOLD St thermal test	
Cryogen	LH <sub>2</sub>	LH <sub>2</sub>	LH <sub>2</sub>	LH <sub>2</sub>	
Chamber Pressure	1×10 <sup>-6</sup> torr	2.7×10 <sup>-6</sup> torr	2.8×10 <sup>-6</sup> torr	14.7 psia	
Tank Pressure	14.7 psia	14.7 psia	15.3 psia	14.7 psia	
Tank Percent Ullage	10	10	10	40	
Sink Temperature	40° R	37° R	37° R	37° R	
Source Temperature	535°R	523°R	520°R	390° R	
Heat Flux, Total	0.19 B/hr. ft. <sup>2</sup>	0.19 B/hr. ft. <sup>2</sup>	0.18 B/hr. ft. <sup>2</sup>	50 B/hr. ft. <sup>2</sup>	
Insulation	17%	-	-	-	
Seams	24%	-	-		
Pins	59%				
Penetration	0%	—	. —	-	
Heat Flow Rate	<b>4.4</b> B/hr.	4.6 B/hr.	4.3 B/hr.	1160 B/hr.	
Mass Flow Rate	0.023 lb./hr.	0.024 lb./hr.	0.023 lb./hr.	6.2 lb./hr.	

\*.· ·

. .

٠

# **CENTAUR FIXED FOAM INSULATION**


- Insulates tank against atmospheric heating on pad and during ascent
- Controllable and well-characterized
- Tailorable, and well-suited as a substrate for multilayer insulation
- Operational on Atlas II vehicles

· • . . .

## SYSTEM REQUIREMENTS

- Stainless steel tank
- Semi-flexible foam and adhesive
- Maintain structural integrity
  - Aerodynamic heating during atmospheric ascent
  - Prevention of spallation due to cryopumping
  - Adhesive bond for multiple tankings
- Available safe/nontoxic materials
- Low cost
- Low weight

## INSULATION SYSTEM DESIGN Material Selection



## **PVC** foam characteristics


- Heat formed to tank contour
- Smooth surface finish
- Closed-cell/no sealant
- Nontoxic/noncorrosive

## **Adhesive characteristics**

- Mixed with solvent/sprayable
- Good working pot life
- Room temperature cure

### Space Systems Division FIXED FOAM ON OPERATIONAL ATLAS II

GENERAL DYNAMICS



Space Systems Division

## **CLOSING COMMENTS**

- Cryo propulsion for First Lunar Outpost ascent and return shows
   a 20% to 30% reduction in IMLEO over storable propulsion
- Cryo storage technology requirements are modest, compared to a Mars mission or an orbital depot
  - Combined Earth/space insulation providing low boiloff
  - Zero-gravity venting for tank pressure control
- Cryo technology to perform the lunar mission is available, has been adequately demonstrated, and is ready for full-scale application
  - Shuttle/Centaur compact thermodynamic vent system
  - Atlas II fixed foam insulation
  - Fully-tested thick MLI

P. C. F.D.

OMIT



AIAA 92-1031 INFLATABLE STRUCTURES FOR A LUNAR BASE HABITAT PAUL S. Nowak, Willy Z. Sadeh, and Jeffrey Janakus Center for Engineering Infrastructure and Sciences in Space Colorado State University Fort Collins, CO

# 1992 Aerospace Design Conference

February 3-6, 1992 /Irvine, CA

#### INFLATABLE STRUCTURES FOR A LUNAR BASE HABITAT

Paul S. Nowak, Willy Z. Sadeh and Jeffrey Janakus<sup>†</sup> Center for Engineering Infrastructure and Science in Space (CEISS) Colorado State University Fort Collins, Colorado 80523

#### ABSTRACT

Design and construction of а the Moon requires structure on a host of issues not addressing encountered on Earth. A modular inflatable auilted structure consisting of thin membranes of composite material integrated with supporting columns and arches is proposed. An initial linear analysis of the proposed structure is briefly reviewed. The actual response of an inflatable membrane is nonlinear and, hence, a nonlinear numerical analysis for the stresses and displacements undertaken. Initial results was clearly indicate that an inflatable structure is a feasible concept and ideally suited for a lunar is structure.

#### INTRODUCTION

A human-tended outpost on the Moon that will evolve into a functional base is a crucial stepping stone in the expansion of humanity into space. A lunar base is one of the prime missions of the Space Program and has been proposed in numerous studies in

- ...

recent years. The establishment of human-tended base on the Moon wa recommended by Nationa the Commission on Space report<sup>1</sup> as national mission, by the Ride repor as one of the four initiatives need to ensure U.S. leadership in space the 21st century, and in the studie of the NASA Office of Exploration<sup>3</sup> the case study for human exploration of space. On July 20, 1989, the 20th anniversary of the first hum. landing on the Moon (Apollo 11 President Bush called for a permanent human return to the Moon before 20 to be followed by a manned mission ' Mars. The long-term plan for huma expansion space into and t establishment of a lunar base was studied by the NASA 90-Day Report recommended by tl and further The Staffor Augustine Report. Report<sup>6</sup> recommends four spa architectures, all of which include different levels of lunar ba development.

The establishment, construction and existence of a lunar base and contingent upon the development of structure capable of accommodating lunar habitat, i.e., a Luna Engineered Closed/Controlled Eco System (L-ECCES).<sup>7</sup> An L-ECCE consists of human, plant and animal modules and associated scientific manufacturing and mining modules.

The design of a lunar structur requires addressing a host of issue

<sup>\*</sup>Assistant Professor of Structural Engineering and Assistant Director for Engineering, CEISS, Department of Civil Engineering; Member AIAA.

<sup>\*\*</sup>Professor of Space Engineering and Director,

CEISS, ibid. 1; Associate Fellow AIAA. †NASA Graduate Student Fellow and GRA, ibid. 1.

Copyright  $\bullet$  1992 by the American Institute of Aeronautics and Astronautics, Inc. All rights reserved.

that are not encountered on Farth. A structure on the Moon must meet both harsh and benian lunar the environmental conditions, and as a result, unconventional structural concepts must be explored. The lunar environmental primary conditions to be considered for a structure include: (1) an atmosphere that is essentially a vacuum; (2) no weather conditions; (3) gravity of (4) surface temperature 1/6 q; variations that range from a minimum of -173 deg C (-279 deg F) during the lunar night to a maximum of 127 deg C (261 deg F) during lunar day<sup>8</sup> which results in a 300 deg C (540 deg F) temperature variation; (5) harmful solar flare protons and galactic cosmic radiation such as HZE particles (high charge-Z and high energy-E particles); (6) meteorite and micrometeorite impact; (7) minimal seismic activity; and (8) specific regolith (lunar soil) properties at the selected structure site.

.

loads applied the The on structure inflatable. membrane consists of: (1) the internal pressure, selected to be 69 kPa (10 which corresponds psi) to an elevation of about 3050 m (10000 ft) on Earth; (2) the dead load (gravity load) induced by the structure's material weight; (3) the gravity load of a layer of regolith of about 3.3 m (10 ft) for radiation and shielding which micrometeorites amounts to a load of 7.9 kPa (1.15 psi); and (4) the thermal stresses caused by the lunar temperature variations.

Light transportation weight, expandability, small stowage volume, flexibility, low volume to usable floor area ratio, modularity, durability, safety, reliability, and

short construction time with minimal extravehicular activity are issues to be considered in the design and construction of a lunar structure. Constraints on the cost of transportation, materials. construction time. construction equipment, and architectural requirements must be incorporated in design and the construction processes.

Inflatable structures are ideally suited for a L-ECCES in view of their features. The primary loading on the membranes of an inflatable structure in the lunar environment is the internal pressure which, if designed correctly, will induce only tensile stresses. These stresses make the most efficient use of material strength since there are no stability problems associated with tension. Membrane materials typically are of low density and flexible, and transportation therefore. costs. construction time and the amount of equipment required are reduced compared with traditional Earth-bound construction materials (e.g., concrete, metals and wood). In addition, the structure can be tested for constructability and pressure containment on Earth prior to the actual construction on the Moon.

#### LINEAR ANALYSIS

concept for inflatable A structures in a lunar habitat was initially proposed by Vanderbilt, Criswell and  $Sadeh^{10}$  and was further by Nowak, Criswell refined and Sadeh.<sup>11</sup> This concept is based on a structure comprised of identical inflatable modules. Each module consists of the following structural components: (1) four external wall membranes; (2) a roof and a floor membrane; (3) four inflatable columns ar en

with footings; and (4) four rigid arches. A sketch of this inflatable structure is shown in Fig. 1, and a photograph of a model, built to a scale of 1:80, is given in Fig. 2. A 3.3 m (10.0 ft) thick layer cover of regolith primarily for radiation shielding, and also for meteorite and thermal protection,<sup>9</sup> is shown in both figures.

The size of the basic module was determined based on the size of a typical office and or living room in terrestrial structures. A spacing of 6.1 x 6.1 x 3.0 m (20 x 20 x 10 ft; 1 x w x h), was selected. A radius of curvature of the roof membrane of 6.1 m (20.0 ft) was chosen based on a compromise between reducing wasted internal volume (a low radius) and lowering the induced stresses (a higher radius). Attributes of this modular approach include modularity, of structural a minimal number components to facilitate manufacturing, expandability through any of the exterior wall membranes, the ability to isolate a pressure loss with interior pressure resistant partitions, and a low volume to usable floor space ratio.

Rigid arches are integrated with the roof membranes to stabilize the structure, limit the roof deformations, and support the gravity loads when there is a loss of internal pressure. This is necessary since the internal pressure supports the inflated structure. One concept for rigidizing the arches is to fill them with a structural foam that remains flexible until the foam is vented to a vacuum. Once the foam is subjected to the vacuum it becomes rigid. This concept was developed by the Goodyear Aerospace Corporation in the 1970's with promising results.

The membrane material in the columns holds the roof down and acts in tension when the structure is pressurized. If there is a pressure loss, the columns would support the rigid arches and act in compression. The compressive capacity of the columns is provided by pressurizing them.

Kevlar 49, a material widely used in space applications, which can be woven into a membrane with a tensile strength of 690 MPa (100 ksi), was chosen as the membrane material for the case study. Calculations for the stresses in the roof and column membranes were conducted based upon the linear elastic response of a pressurized sphere and cylinder, respectively.<sup>11</sup> Thicknesses of 0.3 mm (0.012 in) for the roof membrane and 1.94 mm (0.076 in) for the column membrane, based on a 61 cm (24 in) diameter, were found to be structurally adequate. Closed form solutions for the stresses in the wall membranes and rigid arches from linear analysis have not been а developed yet.

Based upon the results of the linear analysis, inflatable structures offer efficient. an practical and economic solution for a lunar structure. The next step is to conduct a nonlinear analysis of the entire module in order to check, verify and refine the linear results the if and modify structure necessary.

#### NONLINEAR ANALYSIS

Membranes are made from thin sheets of materials that are formed into the desired geometry of the structure. They can only transmit loads through the plane of the material. Any strength through transverse bending and shear is negligible. The structural behavior of membranes is governed by a set of coupled fourth order homoaeneous partial differential nonlinear with equations constant coefficients.<sup>13</sup> In order to perform a structural analysis for the actual stresses and deformations induced by the loads, these equations must be Very few closed solved. form solutions exist for the response of membrane structures due to their nonlinear behavior. Numerical solution techniques are employed to overcome this difficulty. It is important to note that the solutions for the deformations and stresses are even if the nonlinear material remains linear and elastic under the applied loads.

To perform a numerical nonlinear analysis of membrane structures, two approaches that involve specifying the geometry of the structure are possible. The first approach is to describe the initial or unstressed geometry and then to proceed with the analysis. A second approach is to define the final or stressed geometry before conducting the analysis. The first approach requires incremental or iterative nonlinear solution techniques to solve for the deformations and stresses, and is desirable from a fabrication view point. In the second approach, the initial shape for fabrication is found from the analysis, but may be fabricate. impractical to Consequently, the first approach is applied since the fabrication of the module is simplified.

#### SOLUTION TECHNIQUE

The Finite Element Method (FEM) was chosen as the numerical technique to perform the nonlinear structural

analysis. This method was selected since it is widely utilized in most of the recent advances in nonlinear structural analysis. This method requires the geometry of the discretized structure to be input. A finite element software package that has the capability of analyzing nonlinear membrane structures was used.

• \_

Results from a structural analysis are only accurate as as the description of the initial membrane shape since errors accumulate during the incremental solution techniques. In order to obtain accurate results, a computer program was written to generate the geometries of the This program (GEOMM) structure. computes the locations of specified points on the surface of the structure that are required in the FEM. The code was written so that a wide variety of structural shapes and element meshes finite can be generated for immediate input into the software package.

An analysis was performed on a module that is located at an external corner of the structure. This selection was made since there would be no "balancing" of the stresses and deformations by an adjacent module, as occurs in an internal module. One fourth of a module was analyzed due to its symmetry. The rigid arch was modeled with the structural properties of balsa wood since this material is lightweight yet strong, the properties required of the actual structural foam. The finite element mesh of the module is shown as dashed lines in Fig. 3.

#### <u>Results</u>

Input for the nonlinear structural analysis consisted of the same loadings, geometries. material properties and strengths used in the linear analysis. The same material found to be adequate for the roof membrane from the linear analysis was used as a starting point for the roof, floor and wall membranes. Data for all of the component geometries were generated using the GEOMM code.

initial nonlinear analysis The resulted in maximum tensile stresses in the roof membrane within 20% of those in the linear analysis. Variations of stresses throughout the entire roof membrane were obtained. These stresses can not be found from analysis. linear Areas of compressive stresses occurred at two locations within the roof membrane. Since membranes cannot resist "wrinkles" compressive stresses. developed at these sites. To eliminate this problem, the initial geometry of the roof membrane was varied so that the material is stiffened and more tensile stresses are developed at these locations. The results of the nonlinear analysis revealed that the thickness of the roof membranes was adequate.

Contour plots of the von Mises stresses in the roof membrane are shown in Fig. 4. Stresses in the roof membrane reached a maximum value of 580 MPa (84 ksi; 84% of the yield the center. At the stress) at corners of the roof membrane the material is isolated by the intersecting arches and the stresses This situation is are reduced. advantageous since the connection detailing there is complicated if high stresses exist.

Other problems were revealed with the original structural concept. One of the was at. the location intersection of the floor and Results membranes. external indicated that there are large stress concentration there. To alleviate this problem, another rigid arch was placed between the columns at the floor level. This change aids in the connection detailing at the intersection of different membranes.

The rigid arches were modeled with a diameter of 46 cm (18 in) with solid finite elements. Results indicates no stress concentrations and a maximum tensile stress of 10.4 MPa (1.5 ksi). This stress is less than the strength of balsa wood of 21 MPa (4.0 ksi). Compressive stresses were 9.5 MPa (1.4 ksi) also withir the strength limitations.

Results of the analysis for the which were modeled columns, as pressurized tubes, revealed localized deformations. The stresses and concentrations are caused by the membrane forces induced by the two external wall membranes acting on the column material. This problem was anticipated but can not be found from the linear analysis. Based on these results, the columns were modeled with the same properties as the arches since the solid arches reveal localized stresses or no deformations. The nonlinear analysis of the columns revealed that a diameter of 46 cm (18 in) was maximum adequate and yielded a tensile stress of 1.1 MPa (0.2 ksi) and a maximum compressive stress of 4.4 MPa (0.7 ksi). These stresses were caused by bending in the columns from the wall membrane loadings. It is important to note that these compressive stresses are higher than those that would occur in an interior column and that stability is not an issue.

· • .\_

The results for the stresses in the wall membrane revealed that the material was overstressed by 70%. This resulted because the stresses are not evenly distributed throughout the wall membrane since it is not a segment of a sphere. To eliminate this overstressing, the material thickness of the wall membrane was increased to 0.6 mm (0.022 in). Stress contours for the wall membrane are shown in Fig. 5. These results show in a maximum von Mises stress of 621 MPa (90 ksi; 90% of the yield stress).

Displacement contours of the entire module under the loadings of the internal pressure and regolith are shown as solid lines in Fig. 3. These displacements are magnified by a factor of 4 for clarity. The maximum displacement occurs at the center of the external wall membrane of 12.7 cm (5.0 in) outward. A displacement of 4.3 cm (1.7 in) upward occurred at the center of the roof arch. The displacement at the center of the roof arch is 1.8 cm (0.7 in) downward. This was caused by the external wall membrane pulling it down.

The results from the nonlinear analysis reveal a different pattern for the stresses and displacements in the roof membrane than the linear analysis. The magnitudes of the maximum stresses are within 20%. The resulting stresses and deformations within tolerable limits for are serviceability and strength Results from this requirements. nonlinear structural analysis reveal inflatable that the proposed structure is very feasible for a lunar base.

#### CONCLUSIONS

The use of an inflatable membrane structure for a lunar base is addressed. Initial calculations from a linear analysis demonstrated that the structure is feasible for a lunar The actual base. behavior of membrane structures is inherently nonlinear. Results from a nonlinear analysis reveal that the proposed structure is feasible with some modifications. Revisions from the nonlinear analysis include: a thicker wall membrane (0.6 mm; 0.022 in); the use of a solid column with a reduced diameter of 46 cm (18 in); and, a 46 (18 in) diameter arch. The induced stresses and deformations from the internal pressure load of 69 kPa (10 psi) and the gravity load of a 3.3 m (10 ft) layer of regolith shielding within acceptable are limits. Results from the nonlinear analysis reinforce the initial results of the linear analysis. Thus, inflatable structures are ideally suited for use in a lunar base habitat.

#### ACKNOWLEDGEMENT

The support of NASA Office of Aeronautics and Space Technology of this project is gratefully acknowledged.

#### REFERENCES

<sup>1</sup>National Commission on Space Report, <u>Pioneering the Space</u> <u>Frontier</u>, Bantam Books, New York, NY, 1986, p. 140.

<sup>2</sup>Ride, S. K., "Leadership and America's Future in Space," A Report to the Administrator." NASA, Washington, DC, August 1987. 1.1 1.4

<sup>3</sup>NASA OEXP, <u>Exploration Studies</u> <u>Technical Report FY 1988 Status</u>, Vol. I, II, NASA TM 4075, Office of Exploration, NASA, Washington, DC, December 1988.

<sup>4</sup>NASA, "Report of the 90-Day Study on Human Exploration of the Moon and Mars," NASA, Washington, DC, Washington, DC, November 1989.

<sup>5</sup>Augustine Report, "Report of the Advisory Committee on the Future of the U.S. Space Program," Superintendent of Documents, U.S. Government Printing Office, Washington, DC, December 1990.

<sup>5</sup>Stafford Report, "America at the Threshold-Report of the Synthesis Group on America's Space Exploration Initiative," Superintendent of Documents, U.S. Government Printing Office, Washington DC, May 1991.

<sup>7</sup>Condran, M. J., Sadeh, W. Z., Hendricks, D. W. and Brezeczek, M. E., "A Model of Human Metabolic Massflow Rates for an Engineered Closed Ecosystem," Paper 891486, 19th Intersociety Conference on Environmental Systems, San Diego, CA. July 24-26, 1989.

<sup>8</sup>Heiken, G. H., Vaniman, D. T. and French, B. M., <u>Lunar Sourcebook, A</u> <u>User's Guide to the Moon</u>, Cambridge University Press, London, 1991.

<sup>9</sup>Silberberg, R., Tsao, C. H., Adams, J. H. Jr., and Letaw, J. R., "Radiation Transport of Cosmic Ray Nuclei in Lunar Material and Radiation Doses," Proc., Lunar Bases and Space Activities of the 21st Century Symposium, Washington, DC, October 20-31, 1984, W. W. Mendell, Ed., Lunar and Planetary Institute, Houston, TX, 1985, pp. 663-669. <sup>10</sup>Vanderbilt, M. D., Criswell, M. E. and Sadeh, W. Z., "Structures for a Lunar Base, Proc., SPACE 88 The First Intl. Conf. on Engineering, Constructions and Operations in Space, Albuquerque, NM, August 29-31, 1988, Johnson S. W. and Wetzel J. P., Eds., ASCE, New York, NY, 1988, pp. 352-361.

<sup>11</sup>Nowak P. S., Criswell, M. E. and Sadeh, W. Z., "Inflatable Structures for a Lunar Base," Proc., SPACE 90 The Second Intl. Conf. on Engineering, Constructions and Operations in Space, Albuquerque, NM, April 22-26, 1990, Johnson S. W. and Wetzel J. P., Eds., ASCE, New York, NY, 1990, pp. 510-519.

<sup>12</sup>SISCA Outreach, "Inflatable Space Structures," University of Houston, Sasakawa International Center for Space Architecture, Vol. 1, No. 7, May-June 1988.

<sup>13</sup>Leonard, J.W., <u>Tension</u> <u>Structures, Behavior and Analysis</u>, McGraw-Hill, 1988.




Fig. 1 Overall view of the inflatable structure including a cutaway.





Fig. 2 A physical model of the inflatable structure including a cutaway (scale 1:80).


1.1

i



Solid line — displaced shape Dashed line — original shape Magnification factor = 4


Fig. 3 Displaced shape of one-fourth of the module.



Contour	von Mises stre
	(% of yield)
1	0.20
2	0.27
3	0.34
4	0.41
5	0.48
6	0.55
7	0.62
8	0.69
9	0.76
10	0.83
11	0.90

è

Fig. 4 Stress contours of the roof membrane.



Contour	von Mises stress
	(% of yield)
1	0.10
2	0.18
3	0.26
4	0.34
5	0.42
6	0.50
7	0.58
8	0.66
9	0.74
10	0.82
11	0.90

Fig. 5 Stress contours of external wall membrane.

520-31 115520 P-11

N92-33329

#### PRESENTATION #7 SEI TECHNICAL INTERCHANGE: 5 MAY 1992 UNIVERSITY OF HOUSTON AT CLEAR LAKE

#### **PRESENTATION #7**

RELATON OF THE LUNAR POWER SYSTEM TO THE SEI PROGRAM AND TO LANDERS

presentation by

Dr. David R. Criswell

Director - Institute of Space Systems Operations University of Houston and 16419 Havenpark Dr. Houston, TX 77059 713-486-5019 phone and fax

presentation based on the following paper

IAA-91-699: INTERNATIONAL LUNAR BASE AND LUNAR-BASED POWER SYSTEM TO SUPPLY EARTH WITH ELECTRIC POWER

by

Dr. David R. Criswell

and

Dr. Robert D. Waldron

15339 Regalado St. Hacienda Heights, CA 91745 818-333-6991

· · · ·

presented in 5th Symposium on International Space Plans and Policies Session on Lunar Base Study Follow-On 7 October 1991

A-7

IAA-91-699

#### TERNATIONAL LUNAR BASE AND LUNAR-BASED POWER SYSTEM TO SUPPLY EARTH WITH ELECTRIC POWER

Dr. David R. Criswell (1) and Dr. Robert D. Waldron (2)

(1) Director - Inst. of Space Systems Operations, Un. Houston and

16419 Havenpark Dr., Houston, TX 77059 (713-486-5019 phone and fax)

(2) 15339 Regalado St., Ilacienda Ileights, CA 91745 (818-333-6991)

<u>ABSTRACT</u>

The people of Earth will need more than 20,000 billion watts (GWe) of electric power by 2050 for high level of prosperity. Power needs in the 22nd Century could exceed 100,000<sup>-</sup>GWe. By 2100 the al quantity of thermal energy used could fully deplete the known inventory (10<sup>7</sup> GWt-Y) of all nonnewable sources on Earth except for deuterium and hydrogen for use in proposed fusion reactors. e Table summarizes the labor, capital, and mass of power plants required to produce 1 GWe-Y of ergy from present-day power plants. Fossil and nuclear plants respectively consume 80 to 190 M\$ d 12 to 48 M\$ of fuel per GWe-Y.

Labor	<u>Capital</u>	<u>Plant</u>	Net
Work-Y	106\$	<u>Mass</u>	Energy
		tons	
260	200	10,000	3 to 4
800	250	41,000	3.3
1,500	470	314,000	11.5
3,100	760	434,000	1.4
<20(Earth)	20	5,200	90 rectn
<1 (moon)			200 moon
	Labor Work-Y 260 800 1,500 3,100 <20(Earth)	Labor Work-YCapital 106\$2602008002501,5004703,100760<20(Earth)	Labor Work-YCapital 106\$Plant Mass tons26020010,00080025041,0001,500470314,0003,100760434,000<20(Earth)

ble: Generation of 1 GWe-Y of Energy

A manned International Lunar Base (ILB) can celerate the development of LPS by providing the itial transportation and habitation facilities and base erations. ILB can greatly reduce up front costs and ks by emplacing a moderate scale LPS (1-100 GWe).


LPS can accelerate the development of the ILB providing greater funding than is reasonable to pect for purely scientific research. An ternational ILB/LPS program can foster world trust d prosperity.

#### <u>eferences</u>

- iswell, D. R. and Waldron, R. D. (1990) Lunar System to Supply Power to Earth (paper #900279) Proc. of the 25th Ann. Intersociety Energy Conversion Engineering Conf., Vol. 1 (Aerospace Power Systems), p. 61-71, August 12-17, Reno, Nv.
- iswell, D.R. and Waldron, R.D. (1991a) Power Collection and Transmission System and Method, U.S. Patent 5,019,768. May 28.
- iswell, D. R. and Waldron, R. D. (1991b) Results of Analyses of a Lunar-based Power System to Supply Earth with 20,000 GW of Electric Power, Proc. SPS 91 Power from Space: the Second International Symposium, paper a3.6, 11 pp., Paris, France. Aug. & Net Energy Analysis (DRC) paper a1.2, 9pp.

afford, T. P. (1991) America at the Threshold: *America's Space Exploration Initiative, Synthesis Group*, 144pp. and 64pp appendix. U.S. GPO, Washington, D.C. 20402

The Lunar Power System (LPS) uses solar power bases on the moon to beam electric power to Earth (Criswell and Waldron 1990, 1991a, b). The LPS in the figure supplies load-following power to rectennas on Earth. Additional solar power conversion units are located across the lunar limb from their respective Earthward transmitting stations. LPS can be augmented by mirrors in polar orbit about the moon. The construction of rectennas on Earth determines the base cost (0.001s \$/kWe-H) of LPS power. Stafford (1991)



#### IAA-91-699

#### INTERNATIONAL LUNAR BASE AND LUNAR-BASED POWER SYSTEM TO SUPPLY EARTH WITH ELECTRIC POWER

Dr. David R. Criswell <sup>(1)</sup> and Dr. Robert D. Waldron <sup>(2)</sup> <sup>(1)</sup> Director - Inst. of Space Systems Operations, Un. Houston and 16419 Havenpark Dr., Houston, TX 77059 (713-486-5019 phone and fax) <sup>(2)</sup> 15339 Regalado St., Hacienda Heights, CA 91745 (818-333-6991)

#### <u>Abstract</u>

The people of Earth will need more than 20,000 billion watts (GWe) of electric power by 2050 for a high level of prosperity. Power needs in the 22nd Century could exceed 100,000 GWe. The Lunar Power System (LPS) can provide solar electric power to Earth at less cost than conventional terrestrial systems and with far less environmental impact.

A manned International Lunar Base (ILB) can accelerate development of LPS by: • providing the initial transportation and habitation facilities that will greatly reduce up front costs and risks;

demonstrating the emplacement over a 5 to 10 year period of a moderate scale LPS (1-100 GWe);
enabling early exploration of alternative LPS designs, emplacement methods, maintenance, and in-situ manufacturing of implementation equipment.

LPS can support the establishment of an ILB by:

substantially increasing the net wealth of the world and enabling general prosperity;
providing wider support and greater funding of operations beyond Earth than for purely scientific research;

• accelerating the development of resources in cis-lunar space and on the moon.

An international LPS program can foster world trust that lunar resources are being developed for the greatest good of mankind. The costs of SPS and LPS are compared. The organization of an international program for LPS is outlined.

#### Need for Solar Electric Power From Space

Figure 1 displays the two extreme power options for the world. The top curve depicts our world as it is presently dependent on thermal sources of power derived from the resources of Earth (Edmonds and Reilly 1985, DoE 1991, Holdren 1990). Notice that the world has really just started to make intensive use of its non-renewable resources for thermal energy.

Copyright © 1991 by Dr. D. R. Criswell. Published by the International Astronautical Federation, with permission.




Figure 1. Growth of Global Power System

Since the start of the industrial revolutio total world use of industrial energy, primari thermal, has grown at approximately 3.6 %/ In Figure 1 this rate of growth is assumed to continue until the world per capita productic power equals 10 kWt/person at the middle of 21st century. The 4 billion people of the developing countries now use less than 0.7 kWt/person. Increasing per capita use of  $\epsilon$ is the driving function. Population growth i secondary factor. The world population was assumed to grow at 0.9%/Yr from 1900 to 195

L)

#### 4%/Yr afterwards.

By 2100 the total quantity of thermal energy in this model will fully deplete the known tory  $(10^7 \text{ GWt-Y})$  of all non-renewable es on Earth except for deuterium and ogen for use in proposed fusion reactors.

'able 1 summarizes the labor, capital, and mass ower plants required to produce 1 GWe-Y of gy from present-day power plants (DeLaquill . 1988; DoE 1980a; DoE 1980b; DoE 1988; Martin 'etta 1984). The terrestrial thermal solar er (TTSP) and terrestrial photovoltaic solar er (TPSP) systems are scaled up by a factor of

This simulates their use as providers of base power rather than for power in only the -noon and early evening.

In addition, to produce 1 GWe-Y of energy a il fuel plant must burn approximately 0,000 tons of coal. This costs 80 to 190 M\$. The on plant must consume approximately 200 of yellow-cake at a cost of 12 to 48 M\$. tment of wastes from fossil and nuclear ems adds significantly to the fuel and capital enses.

ver	Labor	<u>Capital</u>	Plant Mass	Net
nts	Work-Y	106\$	tons	Energy
sil	260	200	10,000	3 to 4
sion	800	250	41,000	3.3
SP	1,500	470	314,000	11.5
SP	3,100	760	434,000	1.4
\$	<20(Earth)	20	5,200	90(rect)
	<1 (moon)			200(moon)

Table 1. Generation of 1 GWe-Y of Energy

It is unlikely that a terrestrial solar power em (TPS) can be designed to be the major olier of power to Earth. On average a ldwide TPS incorporating advanced nology will provide to end users less than 20 per m<sup>2</sup> of collector area. In addition, ensive secondary facilities require storage of eterminately immense quantities of energy 0 - 1,000s GWe-Y) and the worldwide stribution of that power. Table 1 does not ude the costs of these major elements of a hetary power system based on TTSP or TPSP iswell 1991).

The <u>Net Energy</u> column refers to the lifetime of or the respective power plants. This is the gral, over the life of the plant, of the annual energy output divided by the sum of the ual external energy inputs. The energy of fossil or nuclear fuels is not included. The

2

inputs include externally provided operating energy such as the oil to power a coal train or the energy to refine uranium ore into yellow-cake. It includes the energy tapped from the primary fuel to operate the plant and the energy inputs to build the plant and its fuel supply systems. TTSP, TPSP, and LPS bring net new quality energy to Earth. The larger the net energy ratio the more energy one gets out of the system for the energy necessary to build and maintain it. Fossil and nuclear fission plants decrease the nonrenewable energy stores of Earth.

The bottom curve in Figure 1 provides the functionally equivalent level of electric power to the thermal energy of the top curve. If the assumed population and energy utilization scenarios continue as expected a transition from terrestrial to space solar power must occur between 2000 and 2050.

#### Lunar Power System

In 1989 a NASA sponsored task force concluded that the moon has a vital role to play in supplying electric power to Earth in the 21st century. A

commission of the Office of the President of the United States has recommended study of the use of lunar resources to provide power to Earth (Stafford 1991). One of the options presented in both reports is the establishment of solar power bases on the moon to beam electric power to Earth. Criswell and Waldron (1990, 1991a) originated the LPS concept. These recent studies indicate that LPS can supply all the electric power needs of Earth by the year 2050


(>20,000 GWe) and grow to meet greater demands.


After a demonstration-LPS is built, all the costs of expanding LPS can be borne by profits from the sale of power from the moon. The LPS row in Table 1 indicates that the mature system will have low capital and labor costs. LPS can provide an internal rate of return that exceeds 30% per year. This can occur within 10 years of Net profits the start of construction on the moon. the order of 15,000 B\$/Yr are reasonable to expect if 20,000 GWe is sold at 0.1 \$/kWe-H. Preliminary economic models indicate that LPS will have a positive impact on the world economy. LPS can provide a stable growth of power and stablize the cost of energy (Thompson and Criswell 1991).

Several options for LPS architecture minimize deep space operations and orbital components.

The basic LPS includes pairs of solar power stations that beam power directly to rectennas on Earth during the time those rectennas can view the moon. Power storage on the Earth or on the moon can provide continuous power output on Earth when the moon is not in view (<16 hours/day) or when the moon is in eclipse (<3 hours).

Figure 2 illustrates a more advanced system that includes microwave mirrors in orbit about This system would continuously supply Earth. load-following power to rectennas on Earth except during the three day period around new The microwave reflectors, at a given moon. intensity of the microwave beams, would allow a factor of three reduction in the size of rectennas required to power a region on Earth. However, approximately three days of power storage would be required on Earth or on the moon during the period of new moon when bases on both limbs are in lunar night.





It is preferable to minimize the use of costly power storage. Microwave mirrors in orbit about Earth can minimize power storage. The duration of power storage is also reduced by increasing the fraction of the lunar month that each power station is sunlit. Additional solar power conversion units could be constructed across the lunar limb from their respective Earthward transmitting stations. Each set of cross-limb

3

ILB AND LPS (IAA-91-699)

arrays provides electric power during new and for three-quarters of the lunar month (Waldron and Criswell 1991).

LPS can be augmented by placing solar reflecting mirrors (i.e., solar sails) in polar about the moon. These mirrors illuminate to lunar bases during new moon, during an exand when a base is deep in its night cycle. sails would also augment the solar flux to the power stations during surface daytime. The sails operate as "light-buckets" that simply all of their sunlight into a section of the clo lunar power base. They do not have to imag sun or be continuously boresighted. The m LPS would likely include all the above elem-


Figure 3 is a schematic representation of of the LPS limb bases indicated in Figure 2. #1 is the 10 to 100 km diameter aperture as from the Earth. That aperture is composed of many stand -alone power plots. The power p occupy an elliptic area on the moon that is located Earthward of the terminator as seen Earth. View 2 shows a string of the power p This string extends from just Earthward of t lunar limb (top) along a line directed toward Earth. This string includes the "black" plot view #1.

View #3 shows the primary components of typical power plot. Sunlight collected by so converters (a) is changed to electricity. The electric power is collected by subsurface wi and provided to many solid state microwave integrated circuit converters (MICCs). Each (b) sends an individually controlled signal to microwave reflector grid (c) at the opposite of the power plot. That signal is reflected to Earth as the sub-beam (d) contributed by the power plot. A set of MICCs, one MICC per por plot, in the thousands of power plots in view acts to form a beam. The 100s to 1,000s of MIC positioned before each microwave reflector can form 100s to 1,000s of individual beams. the beams radiate out from the same segmen antenna shown in view #1, but each of the can be directed to a different rectenna on E Each LPS beam from a 40 to 100 km diams base is fully controlled in intensity, to a scale

few 100 meters, across its cross-sectional area Earth. Control of the phase and amplitude of each of the subtransmitters that contributes energy to a given beam produces the desired amplitude distribution at Earth.

Figure 4 depicts the operations needed to construct a lunar power plot (De Generes an Criswell 1983). Several tractors smooth the surface, extract fine-grained iron, and bury

7/28/91



NASA (1980, 1979) SPS studies. The extensive advances in the technology of power conversion and power beaming will be taken into account (Battelle 1991). One to two years of these studies and the laboratory studies that are done in parallel can provide adequate options for field demonstrations.

#### Early Steps in LPS Development

At this stage LPS faces three primary challenges. The first is to demonstrate on Earth the engineering and economic feasibility of the

\*\*\*\*\*\*

#### Figure 3. LPS Antenna, Power Plots & Components

power collection. They also lay down glass ets under which are layered thin films of ar converters. Thin films of moderate iversion efficiency, 5 - 10%, are adequate. In foreground is a mobile glass processor that Its lunar soil to produce foamed glass supports, erglass, and glass sheets. The supports and erglass are used to make the microwave lectors. One reflector is being erected. Solar ctric power is provided to sets of microwave y-transmitters that are buried under the mound the Earthward end of each power plot. Note it the Earth remains in the same general sition in the sky at a given base. The fleet of atively small and independent machines move m one construction area to another. The rate installation of new power is proportional to the mber of machines and their productivity. The conceptual design studies for LPS should done as part of an engineering systems aluation and accompanied by life-cycle sts/benefits analyses. These studies should ke maximum use of the DoE (1980c, 1981) and

critical components and systems of production. The second is to reduce the up-front costs. The third is to show that LPS is acceptable to billions of potential users on Earth. The International Lunar Base is relevant to all three challenges.

#### Systems Studies

There is an immediate need for more extensive conceptual design studies of LPS and alternatives to the LPS-reference system described in this paper. LPS is different from all other major aerospace and power systems. The primary systems integration that forms the beams occurs in free space between the moon and the Earth. The electromagnetic fields from the thousands of power plots of a given power base sum up to produce the various synthetic beams. Each of the contributing microwave sources must be accurately phased and controlled in amplitude. This is primarily a time-base and ephemeris problem and is well within the capabilities of modern electronics.

352




Figure 4Artist's Concept of the Construction of a Demonstration Lunar Power BarILB AND LPS (IAA-91-699)57/28/91

he moon provides the platform that rates the physical systems. The minimum for integration of large-scale physical ms has profound implications for the neering and economics of LPS. The power and the machines that build them do, not a to be extensively matched, as do for example, tiles of the space shuttle. Many different ins can be explored, many different sets of components tried, and many different ods of production employed.

#### ratory & Field Manufacturing

column 5 of Table 3, which will be discussed provides R&D priorities for the lunar First, extensive laboratory work is ms. ed on thin-film solar cells that can be readily iced on the moon using local resources. lext, the microwave sub-reflectors (Figure 3) to be formed and the wire to collect power The design of these systems is coupled iced. the design and demonstration of prototype rials handling and the manufacture of The objective is to use equipment that ment. a relatively low mass per unit of output [Tonsment/ (Tons-output/Hour)]. The equipment d require little make-up mass or components Earth, be highly automated, and be rable on the moon.

to the moon with equipment that can immediately begin to emplace a demonstration level LPS. In the early to mid-1960s, extensive testing of lunar equipment was done in simulation facilities on Earth. This was prior to landing on the moon. Since then a vast accumulation of knowledge of lunar materials and lunar conditions has been accumulated.

Adequate simulations of a lunar construction site can be done on Earth. The most promising laboratory and bench studies will be incorporated into sets of autonomous, mobile production machinery for demonstrations on Earth. The production equipment can be rover units of the general nature depicted in Figures 4 and 5.


Figure 5 illustrates three emplacer units traveling past several power plots to another emplacement area (Mortenson and Saul 1991). Α set of emplacer units should be be transportable by a class of aircraft with the cargo capacity of the U.S. STS or the Soviet Shuttle (< 30 tons payload). A C-130 is a good analog.


The set of prototype production equipment is air-lifted to a high desert area. The plane lands and the prototype units are driven out under automatic or remote control. The production units then go to a succession of sites to build power plots. Each site represents a different lunar terrain and soil type.

The sites are created in a set of five inflatable

buildings established in the high-desert area. Four of the buildings are located along the perimeter of an elliptical area 10 to 100 km in diameter, and the fifth is located near the center. The roof of each building is transparent to sunlight and 10 cm microwaves. The floor of each building is covered to a depth of one to two meters with simulated lunar soil and rocks. Highland (aluminum-rich) and mare (iron-rich) areas are simulated. The buildings are pressurized with an inert gas, and entry ways are provided for the robotic construction equipment.

The production equipment is designed for autonomous operation in





operations. Machine and human repair of unusual maintenance is allowed.

Each building houses a fully operational power plot. During the day time the power from one plot is beamed to nearby ground and airborne receivers. The plots are phased together to demonstrate beaming of very low-level power to satellites, to distant receivers on Earth via orbital reflectors, or to a set of lunar landers (next section).

This exercise requires compromises; for example, solar cell production may take place in a mobile vacuum chamber temporarily placed on the demonstration plot. Designs must accommodate the operation of equipment in an inert atmosphere and air, when traveling between plots, versus the vacuum of the moon.

#### Power Beaming

There are no basic technical mysteries about the beaming of power by way of microwaves. The basic theory is understood and the practice is well within the state of the art of electronics. Consider for example, that all radar sets use power beaming, either fixed by their physical optics or controlled through phasing of their individual sub-radiators. Routine, long-term phasing of very large microwave power systems has been demonstrated at the thee kilometer long Stanford Linear Accelerator since 1968 (NRC 1981, p. 21). Microwave technology is well developed. However, the application of the technology to beam at realistic power levels for reasonable periods of time must be demonstrated to the satisfaction of both the general population and the scientific community.

Demonstrations of beam control and beam power can be done separately. The demonstration of control of moon-to-Earth beaming can be done at very low power levels. High power level beaming can be done from the Earth to orbit and from Earth to the moon. These demonstrations serve several purposes. The moon will be confirmed as an adequate platform for a large synthetic array, and several different methods of phasing the lunar array will be exercised. The effects of the atmosphere and ionosphere on high power density beams can be examined.

The lunar demonstrations can be done by soft landing a set of unmanned vehicles on the moon. The lander array will operate for several years. The landers would be simple and could easily be on the moon within five years. Three to four of the landers are evenly placed along the perimeter of the site of a potential lunar power

The last lander is placed near the c base. Each lander carries a microwave transmi system, solar arrays, and battery storage th adequate for overnight operation of the transmitter. The microwave transmitters phased to send very low power but very collimated test signals to Earth. The signal normally be received and continuously n at deep space stations. However, short-du higher-power signals could be directed to expensive receivers at any point on Earth. example, the beam could be scanned over the campus of large universities to demor beam control and localization.

The landers can also contribute to othe engineering and scientific studies. Lander be equipped with diggers to bury the tran under 10 to 30 centimeters of lunar soil. T would simulate the placement of transmitte the very constant subsurface environmen Engineering packages such as solar cell te articles and metal-coated glass fibers can a attached. Perhaps self-contained robotic (few kilograms) can be included to conduct surveys for several hundred meters about lander.

The set of landers can also receive ver power test signals from Earth. The atmos and ionosphere of Earth create the greates disturbances of microwave beams. Beams primarily absorbed (few percent or less). secondary effect is to sporadically self-focu fraction of the beam energy into a new d The deflection effects will be much larger signals sent from the Earth to the moon the the reverse situation. Large radar systems as those associated with the early warning and ICBM tracking can be adapted to this function. These radars can provide beams wide range of power and frequency to es the full response of the atmosphere and ionosphere.

LPS provides continuous, load-followin power to a rectenna on Earth by reflectin. power beam from a succession of microwa mirrors in orbit about Earth (Figure 2). T mirrors of >100 meter diameter can be place LEO from the Space Shuttle or unmanned The Earth-based radar systems can direct power test beams to these microwave mir The beams can then be reflected and redir local test receivers or to receivers thousan miles away. The mirrors are low-mass bu area devices that can be readily derived f existing NASA work on large space struct Given adequate pric high-gain antennas.

) meter reflectors could be in orbit within be to five years. Ground-based transmitters of O and NSF (e.g., Arecibo) and the microwave rors can completely test microwave beaming full power levels. Such tests could be rapidly reloped and initiated.

Space Station Freedom can support R&D relopment of the larger orbital reflectors. portant tasks include verification of surface erances, demonstration of assembly and intenance procedures, and accelerated aging key components.

#### oduction and Resources

The percentage distribution of costs in column of Table 3 suggests additional activities at an 3 to reduce the costs of LPS. ILB can provide justrial laboratories for the development and monstration of better means of production. ose laboratories can also make all or large rtions of future production systems out of lunar Both advances will significantly scale terials. wn the transportation system (HLLV, other) d space construction. These will decrease the tor of 0.0025 for this part of the model. On the her hand there may be an increase in the mber of research personnel and habitats. Lunar resources can be developed for direct e in space transportation ("other"), logistics, d habitat construction. The factor of 0.0025 ould be sharply reduced.

SSF can provide the manned components for PS logistics facilities in LEO and LLO and celerate the testing of lunar base facilities for bitation and repair activities.

#### Demonstration LPS & the ILB

An ILB can greatly advance the development LPS by emplacing the demonstration system AA 1990). An ILB program can significantly duce the up-front cost of the demonstration LPS ad the full-scale program by providing most of e initial transportation, habitation, and frastructure.

Table 2 provides estimates of the total costs (\$(90)) of lunar bases scaled to permanent pulations of 30 (Case 1: 60 B\$), 85 (Case 2: 91 B\$), d 300 (case 3: 243 B\$) people. These estimates sume the base is operated for 10 years. The timates include R&D for facilities and uipment (line 1.c) and transportation (line 1.d). tablishment and operation of the flight systems ne 2) are also included.

The purpose of these bases is to demonstrate

the emplacement of 1, 10, or 100 GWe of power at the end of the ten-year period. The incremental cost of creating the production machinery for emplacing the LPS components is given in lines la and b. The additional R&D cost for the LPS production machinery increases from 12 B\$ (Case 1: 1 GWe) to 22 B\$ (Case 3: 100 GWe).

Several costs, such as transportation, do not scale linearly to lower rates of power emplacement. Case #3 is closest to the SPS production modeled by General Dynamics. The estimates are extrapolated from a study of using lunar materials to emplace one 10 GWe SPS every year (Bock 1979). Thus, the cost estimates of the smaller bases should be treated as preliminary. Consider these values primarily as encouragement to deeper analysis. NASA (1991) is studying this size of vehicle but for considerably lower launch rates. Those studies could be immediately extended to the launch rates implied by Table 2 and to the use of lunar materials to provide propellants.

Cases	# 1	# 2	# 3
GWe installed over			
10 Years	1	10	100
GWe-Yrs of energy	5	50	500
Gross Revenue (B\$)			
(@0.1\$/kWe-H)	4.4	44	438
Net Revenue (B\$)	-56	-47	195
Total Costs (B\$)	60	91	243
(sum 1+2+3)			
1. R&D (B\$)	42	51	86
(sum a+b+c+d)			
a. LPS Hrdw	11	11	11
b. CNSRT. SYST	1	3	11
c. FACILITIES & EQ	5	10	30
d. TRANSPORT	26	27	35
2. Space & Ops (B\$)	17	34	103
3. Rectenna (B\$)	0.6	6	55
\$/kWe-H	1.4	0.2	0.06
Moon (tons)	2,300	6,200	22,000
Space (tons)	970	2,700	9,700
People (moon, LLO,	30	85	300
& LEO)			

Table 2 Parameters of Smaller Bases

Costs of Space Equipment and Operations increase sharply between 10 and 100 GWe of final installed capacity. The cost of power drops

7/28/91




Figure 6. Lunar Lander with Eight Emplacement Rovers

sharply as the installed power increases. Power from the demonstration base is sold to Earth. The sale price is assumed to be 0.1 \$/kWe-H. At some time between the installation of 10 and 100 GWe, the integral of the net cash flow from the sale of power goes positive. In this model the net expenditures for all aspects of the lunar base and the LPS will be less than 100 B\$ by the time positive cash flow begins. Power could sell for much greater prices to customers off Earth.

Figure 6 illustrates a lunar vehicle that is scaled to land 30 tons of equipment on the moon (Mortensen and Saul 1991). The vehicle carries eight emplacement vehicles. Assumming the base described in Case 1 is emplaced over a period of three years then approximately 10 landing operations would be required per year. This tonnage and flight rate are consistent with with studies of larger-scale lunar bases considered by NASA (1989b) in the 90-day report.

#### Costs and Payoff

The cost of power from the mature LPS can be very low, the order of  $0.001s \(1990)/kWe-H$ , assuming a beam intensity at the rectenna of 23 milliwatts per cm<sup>2</sup>. Rectennas on Earth are the major cost elements (Tables 2 and 3). The cost of power will decrease as the cost of rectenna construction decreases or beam intensity increases. LPS enables the profitable operation of

small rectennas of on few hundred meters diameter with 10s MW output. Rectenna enlargement can be financed from profits finished portions. LPS economically robust major increases in construction and maintenance costs. L appears to be competi costs and environme considerations agains conventional power

#### NASA, DoE, NRC, and L Models

The early studies of were scaled to buildin 10 GWe or two 5 GWe satellites and company rectennas per year ow thirty year period (G

1977, NRC 1981). The fleet of 60 satellites, w peak capacity of 300 GWe, would feed approximately 9,000 GWe-Y of energy to Ea over 60 years. The order of 2,100,000 tons of satellites and supplies would be transported space over the period of construction and operation. This assumes each satellite has a of 35,000 tons and that 1% of its mass is rep over the period of operation.

The costs of major components and ope per GWe-Y are in the top part of column #1 "Solar array" refers primarily to t Table 3. solar cells. SPS structure, microwave gene and rotary joints constitute the "Other port Crew habitats, construction facilities in LEO GEO, and maintenance equipment are include "Other (habs, etc.)." The heavy-lift launch "Other" transport vehicles are the HLLVs. elements include E-LEO and LEO-GEO person vehicles and ion-drive engines to transport components from LEO to GEO. The nominal the electricity to emplace the fleet is predic be 88.1 M\$/GWe-Y or 0.01 \$/kWe-H. The distribution of these costs as percentage of Capital Total cost is in column #1a.

These engineering costs do not count the value of money required to establish the fu system. The bottom section of column 1 sho that the cost of financing the SPS dominates cost of power. NASA and the National Rese Council (1981, p. 37) adapted the "compound

9

an annuity" to evaluate cost recovery of the ney required to finance SPS (Copeland and esson 1979). The "Capital Recovery Factor" RF) in Eq. 1 is modified for the GWe-Y basis of sting used in Table 3.

1. CRF = Years\*R/[1-(1/(1+R))Years]

Equation 1, R is the Rate of Return (= 15% in SPS example) and Years is the operating life an SPS-rectenna set.

Multiplying CRF = 4.57 times the Capital Total (= 1 M/GWe-Y) yields the Capital Recovery = 447 //GWe-Y. The time value of money to build the S fleet dominates the cost of power from the SPS et. Note that the product of "Capital tal#Yaars" in Eq. 1 is the "Present Value of an

tal\*Years" in Eq. 1 is the "Present Value of an nuity." Capital Recovery in Table 3 is the ount of the periodic annual payment of the nuity. The Capital Total in Table 3 is slightly ther than the NASA and NRC estimate because includes the RDT&E.

To obtain the full cost of SPS power, NASA ied an estimated cost of 5.2 mills per kWe-H or M\$(77)/GWe-Y for maintaining the SPS fleet 1 rectennas. The sum of Capital Recovery and intenance yields 493 M\$(77)/GWe-Y or proximately 0.056 \$(77)/kWe-H. Current cost of S energy, 0.102 \$(90)/kWe-H, is obtained by This cost is approximately the ltiplying by 1.7. ce of wall-plug electricity in the United States. The National Research Council (1981) intained that almost all the SPS costs would be ther than the NASA estimates in column 1. lumn 2 contains the multipliers. They project t high efficiency, single crystal silicon solar Is will be 50 times more expensive and refore will be the dominant cost factor (82.5% column 3a). Transportation from Earth to orbit a factor of three higher. However, rectenna oduction and operation are unchanged. Notice at rectennas dropped to 2.1% of the costs, lumn 3a, from 16.7% in the NASA estimate, lumn 1a. The Capital Total in column 3 creased by a factor of 7.8 to 687 M (77)/GWe-Y.

The NRC made no changes in the financial sumptions of NASA but did indicate that the certainties were larger than indicated by ASA. The Capital Recovery Factor of 4.57 was ained. The Total Energy Cost thus rose to 3,550 \$(77)/GWe-Y. This is the same as 0.4 \$(77)/kWeor 0.7 \$(90)/kWe-H. This cost is approximately 7 tes the price of wall plug-electric power in the nited States.

#### Qualitative Costing of LPS

The NASA and NRC estimates of SPS cost can be used to provide a better understanding of the fundamental differences between deploying SPS from the Earth and sending equipment to the moon to make the components of the LPS system from local materials. These differences include maximum potential power, manufacturing versus deploying, efficiency of rectenna illumination, and financing the growth of SPS versus LPS.

First, consider RDT&E and the energy yield. The reference-SPS is scaled to provide 300 GWe. Each satellite would operate for 30 years. Thus. the reference-SPS fleet would yield 9,000 GWe-Y of energy. LPS has been modeled for growth to 20,000 GWe. Averaging over 40 years of build-up and 30 years of full operation, the LPS would yield 1,000,000 GWe-Y (= 20,000 GWe \* 50 Y). To a first approximation, the cost of RDT&E per unit of energy can be scaled to the respective total energy output of each system. This LPS/SPS ratio is 0.009 (=9,000/1,000,000). This ratio, in column 4, is multiplied against the NRC costs for RDT&E per unit of energy output in column 3. Multiplication yields the RTD&E cost of 100,000 \$/GWe-Y for LPS that is shown in column 5. Rescaling SPS to a greater energy output would similarly reduce the RDT&E for SPS. However, it is doubtful that even 300 GWe of SPS could be deployed from Earth because of environmental restrictions on launch operations.

Next, consider SPS deployment from Earth versus manufacturing LPS on the moon. The figure of merit is tonnage shipped from Earth per GWe-Y of energy returned to Earth. The 5 GWe SPS is estimated to weight 35,000 tons. Sixty would be deployed. We arbitrarily estimate that 1% of the mass of the SPS fleet is added for components, fluids for station keeping and orientation, and transportation propellant. The projected SPS mass-to-energy ratio is 230 tons/GWe-Y (= 2,100,000 tons/9,000 GWe-Y).

Detailed estimates are available for the 592,000 tons of equipment, facilities, and components that must be taken from Earth to emplace a 20,000 GWe LPS (Criswell and Waldron 1990). Thus, the LPS mass-to-energy ratio is 0.59. The combined LPS/SPS ratio is 0.0025.

Note the seven items in column 4 that are scaled by the LPS/SPS mass to the energy ratio. This ratio will not change greatly with total energy. However, it will vary with the level of technology used to implement SPS and to do manufacturing on the moon. It seems likely that SPS and LPS components, as opposed to the LPS

7/29/91

production system, can converge to similar massto-energy ratios. Thus, LPS will always have a relative advantage in terms of increasing efficiency of machines that make the LPS components on the moon.

The dominant effect of solar cell cost is reduced from 82.5% in column 3a, to 18.7% column 5a. The relative cost of solar cells in column 5a may be estimated too high. LPS does not need the high-efficiency solar cells that the NRC assumed could only be obtained from relatively thick, single-crystal silicon cells. Rather, LPS is compatible with thin-film cells, 5% - 10% conversion efficiency, that use very small quantities of photoconverter. Thin-film cells based on amorphous silicon, polycrystalline silicon, GaAlAs, and several other active lay can achieve this level of efficiency. If nec the active layers can be brought from Earth little effect on costs.

LPS costs for emplacing a unit of power continuously drop. This is because of the accumulation of industrial learning in the construction of LPS components, the increa use of production machinery made from lur materials, and the use of lunar materials and power in logistics. None of these positive fa are considered in Table 3. In large-scale production, the LPS should have a unit cost of power that is primarily dominated by the cost

								<u> </u>
	(1)	(1a)	(2)	(3)	(3a)	(4)	(5)	(5a)
	NASA	NASA	NRC	NRC	NRC		LPS	LPS
TYPE OF SYSTEM	M\$(77)	Į į	1 1	M\$(77)	1	Ratios	M\$(77)	
(across)	per	% of	Cost	per	% of	f .	per	% of
CAPITAL ITEMS	GWe-Y	Total	Multi-	GWe-Y	Total	LPS/SPS	GWe-Yper	Total
(below)		Costs	liers	I	Costs		$(3)^{\cdot}(4)$	Costs
RDT&E(& 1st 5 GWe	11.39	12.9%	1.4	15.9	2.3%	0.009	0.1	1.
set)		L	نـــــا	L	L	L	L	L
SPS portions		·			·	<u></u>	<b></b>	
Solar array	11.3			566.7	82.5%	0.0025	the second s	18.
Other portions	15.3		1.4	21.5	3.1%	0.0025		0.
Other (habs, etc)	2.0	2.3%	1.4	2.8	0.4%	0.0025	0.01	0.
Space Construction	6.7	7.6%	1.4	9.3	1.4%	0.0025	0.02	0.
Space Transportation								
HLLV (Earth to	13.0	14.8%	3	39.0	5.7%	0.0025	0.1	1.
orbit)		11	11	'I			·	۰. ا
Other (LEO-out)	5.7	6.4%	1	5.7	0.8%	0.0025	0.01	0.
Management &	8.0	9.1%	1.4	11.2	1.6%	0.0025	0.03	0.4
Integration			۱ <u> </u>			<u> </u>	·	
Rectenna (Earth)	14.7		1	14.7	2.1%	0.4	5.9	76.4
Capital Total	88.1	100.0%	1	686.7	100.0%		7.7	100.0
(M\$/GWe-Y)		<u> </u>	·	' <u> </u>	<u>ا</u> ا		<u> </u>	·
· · ·								
- 4	Rate		Cpt			LPS Rate		LPS C
	return=	15.0%	Fac.=	90.0%		Return=	15.0%	Fac.=
(Financing	Plant			<b>]</b>		LPS Plant	]	90.0
	Life(Yrs)=		·			Life(Yr)=		·
Capital Recovery Factor*Yrs	4.57			4.57			4.57	
Capital Recovery (M\$(77)/GWe-Y)	447			3,486			39	
Maintenance	46	1	1.4	64			19.55	
(M\$(77)/GWe-Y)		۰ <u>ا</u>	·			0.31		
		· -		- •	•		-	
Total Energy Cost (M\$(77)/GWeY) \$(77)/kWe-H	493			3,550 0.4050		(Wt. avg)	59	

Table 3. Summary of Cost Studies: NASA and DoE, NRC, and LPS

ructing and operating the rectennas on h.

he NRC (1981) considered rectennas to be understood technology. No adjustments were in column 2 to the projected costs of nna construction and operation.

.PS has a considerable advantage over the ence SPS, because rectennas are the nant engineering cost for LPS (5.9

77)/GWe-Y and 76.4%). LPS uses an oversized mission aperture at each power base on the n. This allows rectennas larger than several red meters in diameter to be illuminated evenly than in the reference SPS and, fore, increases the power production per area of rectenna. A rectenna receiving an power beam outputs approximately 2 to 2.5 more power than when receiving a power of the same peak intensity from a reference

This greater output level produces the stion factor of 0.4 in column 4 and the lower sy costs in column 5.

he factor of 0.4 assumes those microwave ctors in orbit about Earth are used to provide following power to the rectenna. It also nes that the life of the rectenna field is rned by environmental factors such as wind, and corrosion rather than being

ortional to the total energy received. The Capital Recovery Factor (CRF) increases projected cost of LPS power to 0.0067 )/kWe-H or 0.011 (90)/kWe-H. This cost is below present-day electric costs. Note in nn 4 that the Maintenance Factor = 0.31 [= 76.4% + 0.0025\*(100%-76.4%-1.9%)]. This ely adjusts for the fractions of the intenance going into the space and terrestrial

ems. The Constant Total of **7.7 M**\$(1077)/CWo Y

The Capital Total of 7.7 M\$(1977)/GWe-Y ed from the NRC estimates in column 4 ies a total LPS-program cost of 7,700 B\$(1077) 3,000 B\$(1990). The cost adjustments in mn 4 are derived from far more detailed els of LPS construction and operations swell and Waldron 1990). The detailed model, ming a 1990s level of technology, projects the cost of a 20,000 GWe LPS to be approximately 00 B\$(1990) with 16,000 B\$(1990) for rectenna truction on Earth. Advances in the nologies of components and production hinery, use of lunar resources in logistics, building portions of the systems of uction from lunar resources can ficantly reduce the mass that must be sent Earth (tons/GWe-Y).

#### Questions Concerning Financial Analyses

Future work on power from space must challenge the NRC (1981) cost model. The 15%/Y Rate of Return requirement, while representing the 1970s experience with high interest rates, is not typical of major public-related programs. Α much sounder approach is to use the real rate of RRR is the difference between the return (RRR). yield on long term, high value securities and the rate of inflation. Over the years, RRR = 2 to 3%/Yis typical (R. Thompson personal Table 4 applies a 3%/Y rate to communication). engineering costs in Table 3. Notice that the Total Energy Cost of the NASA estimate in column 1 falls to a reasonable value, <0.04 \$(1990)/kWe-H. The NRC estimate is higher, > 0.2 (1990)/ kWe-H, than most electricity today. The Capacity Factor is increased from the 90% in Table 3 to 95%.

Direct application of the annuity formula to the LPS, as shown in Table 4, is inappropriate. Most of the long-term investment is in the system of production and transportation, in space and on the moon, that emplace power units on the moon. The lunar and space investments constitute less than 17% of the total. Thus, the Capital Total in column 5 decreases to 1.81 M\$(77)/GWe-Y for the lunar operations. For a 3%/Y rate and a 30 investment horizon, CRF = 1.53 and the Capital Recovery = 2.8 M\$(77)/GWe-Y. Maintenance is already included in the lunar operations. With these adjustments, the cost of the lunar portion is approximately 0.0003 \$(77)/kWe-H.

A rectenna serviced by LPS has a much shorter payback period than when serviced by the reference SPS. In the latter case a complete SPS and 10 km by 20 km field of rectennas must be installed before power is produced. In contrast, the oversize transmitting apertures on the moon can send power efficiently to a rectenna only a few hundred meters across. The small rectenna is built in a fraction of one year and will immediately return a positive cash flow. Further expansion of the rectenna comes from current Using Equation 1 it is reasonable, to a revenue. first approximation, to take the investment period as one year, the Capital Total for the rectenna as 5.87 M(77)/GWe-Y, and RRR = 3%/Y. Thus, CRF = 1.03 and the Capital Recovery is 6 M\$(77)/GWe-Y or 0.0007 \$(77)/kWe-H.

Once a field of sub-reflectors is constructed on the moon, the installation of new capacity can proceed incrementally. This expansion of power on the moon is paid for by the sale of power from existing rectennas. We have assumed in Table 4 that the Capacity Factor of LPS is approximately 99%. LPS is a fully distributed, highly redundant system that more closely resembles a telephone network than a conventional central power station. In addition, LPS can average its power feed over the entire globe and is also decoupled from terrestrial feedbacks and the electromagnetic effects of solar storms.

Construction of conventional power stations (Table 1) will cost 10 to 30 times more than LPS. Terrestrial power plants will have additional, and increasing, costs for labor, fuel, compliance with environmental standards, and power storage and distribution. These costs can equal or exceed the costs of building and maintaining the power plants.

#### Organizing and Developing LPS

To develop LPS, three types of investors are anticipated: governments, consortia, and local organizations. Between now and 2001, government programs will likely pay for the development and initiation of the transportation elements and the lunar base. In that period, expenditures can be comparable to present United States government expenditures in aerospace products for the U. S. Department of Defense and NASA. LPS can provide a peaceful focus for the present defense- and technology-related organizations of the space-faring nations.

A national or international consortium formed to develop, procure, and implemen elements for LPS production and do the RD rectennas. After the year 2001, this conso can conduct all off-Earth operations. Bety 2001 and 2005, the consortium would begin receiving a net positive revenue from the power on Earth. More than one consortiur be formed. Many lunar bases are needed.

Rectenna R&D, both for rectennas and means of production, can involve all the of Earth. Rectennas can, as appropriate, b constructed, operated, and paid for by priv groups, cooperatives, and countries. Virtus the costs of rectenna production will be co by current cash flow. The major challenge startup costs and public confidence in LPS.

#### <u>Conclusion</u>

A vigorous Apollo-like program could the construction of the ILB and the demo LPS on the moon within ten years. LPS we firmly establish a permanent dual-planet economy, growing commerce between the and the moon, and world wide prosperity.

	(1)	(1a)	(2)	(3)	(3a)	(4)	(5)	(5 a
TYPE OF SYSTEM	NASA	NASA	NRC	NRC	NRC		LPS	LPS
(across)	M\$(77)			M\$(77)	ľ	Ratios	M\$(77)	
•	per	% of	Cost	per	% of	1	per	% 0
CAPITAL ITEMS	GWe-Y	Total	Multi-	GWe-Y	Total	LPS/SPS	GWe-Yper	Tota
(below)		Costs	liers		Costs		(3)*(4)	Cost
Capital Total (M\$/GWe-Y)	88.1	100.0%		686.7	100.0%			100

Cost of	Real Rate		Cpt		LPS Real		LPS
electricity:	Return=	3.0%	Fac.=	95.0%	Rate Return=	3.0%	Fac
(Financing Impact)	Plant Life(Yrs)=				Payback Time(Y)=	30.0	99
Capital Recovery Factor*Yrs	1.53			1.53		2.55	
Capital Recovery (M\$(77)/GWe-Y)	142			1,106		20	
Maintenance (M\$(77)/GWe-Y)	46		1.4	64	0.31	19.55	
Total Energy Cost (M\$(77)/GWeY)	187			1,170	(Wt. avg.)	39	
\$(77)/kWe-H	0.0214		[	0.1335		0.0045	I

Table 4. Alternative Financial Assumptions: NASA and DoE, NRC, and LPS

ILB AND LPS (IAA-91-699)

13

#### Acknowledgment

It is a pleasure to acknowledge the iments on draft versions of this paper by Dr. e Duke and Mr. Clarke Covington of the NASAnson Space Center, and Prof. Russell mpson of the College of Business at the versity of Houston. Special thanks are also to Mr. Mike Mortenson and Paul Saul for the work provided for Figures 5 and 6. These were e in the course of their master's thesis in hitecture at the University of Houston in the awaka International Center for Space hitecture (Prof. Larry Bell, Director). Mr. ry Tups of Lockheed provided references to ent work on lunar landers and scaling of the istics for lunar bases. As always, we thank la Criswell for editorial assistance.

#### References

- telle (1991) Power Beaming Workshop: Proceedings and Supplementary Information (Export Controlled), 36pp. and 300pp.(appx.), Pacific Northwest Laboratory, Pasco,
- Washington. Off. Scientific & Tech. Info., P.O. 30x 62, Oak Ridge, TN 37831. (May)
- ck, E. (1979) Lunar Resources Utilization for Space Construction, Contract NAS9-15560, DRL Number T-1451, General Dynamics - Convair Div., San Diego, CA.
- peland, T. F. and Weston J. F. (1979) Financial Theory and Corporate Policy, Addison-Wesley Pub. Co.
- swell, D.R. (1991) Terrestrial and space power systems: life-cycle energy considerations. Proceedings of SPS 91 Power from Space: the
- Second International Symposium, paper al.2, 9 pp., Paris, France. August.
- iswell, D. R. and Waldron, R. D. (1990) Lunar
- System to Supply Power to Earth (paper #900279) Proceedings of the 25th Annual
- Intersociety Energy Conversion Engineering
- Conference, Vol. 1 (Aerospace Power Systems), p. 61-71, August 12-17, Reno, Nevada
- iswell, D.R. and Waldron, R.D. (1991a) Power
- Collection and Transmission System and
- Method, U.S. Patent 5,019,768. May 28.
- iswell, D. R. and Waldron, R. D. (1991b) Results of Analyses of a Lunar-based Power System to Supply Earth with 20,000 GW of Electric Power, *Proceedings of SPS 91 Power from Space: the*
- Second International Symposium, paper a3.6, 11 pp., Paris, France. August.
- Generes, W. and Criswell, D. R. (1983) By

permission of Unisys Corporation.

- DeLaquill, P., Kelly, B.D., and Egan, J.C. (1988) RD and D: Solar Central Receiver Technology Advancement for Electric Utility Applications: Phase 1 - Topical Report, Vol. 1, Pacific Gas and Electric Company Contract GM 6343022-9, Bechtel National, Inc., Report 007.2-88.,2, August.
- DoE (1991) National Energy Strategy, First Edition-1991/1992, 217pp. and appendices, U.S. Dept. of Energy, Washington, D.C.
- DoE (1988) Nuclear Energy Cost Data Base: A reference data base for Nuclear and coal-fired power plant generation cost analysis, U.S. Department of Energy, DoE/NE-0095, pp161, Washington, D.C., September.
- DoE (1981) A Bibliography for the Satellite Power System (SPS) Concept Development and Evaluation Program. U.S. Dept. of Energy, DoE/ER-0098, 271pp., Cont. No. 31-109-ENG-38, Washington, D.C. (April).
- DoE (1980a) Cirillo, R.R., Cho, B.S., Monarch, M.R., and Levine, E.P., Comparative Analysis of Net Energy Balance of Satellite Power Systems (SPS) and Other Energy Systems, U.S. Dept. of Energy, DoE/ER-0056, pp.136, Washington D.C., April.
- DoE (1980b) Prototype Environmental Assessment of the Impacts of Siting and Constructing a Satellite Power System (SPS) Ground Receiving Station (GRS), U.S. Dept. of Energy, DoE/ER-0072 Contract #31-109-38-5251, 219pp. and appendices, Washington, D.C., August.
- DoE (1980c) The Final Proceedings of the Solar Power Satellite Program Review, Lincoln, Nebraska (April 22-25, 1980), U.S. Dept. of Energy, Conf-800491, Cont. No. FG05-79ER10116, 678pp., Washington, D.C. (June)
- Edmonds, J. and Reilly, J.M.(1985) Global Energy: Assessing the Future, 317pp., Oxford University Press.
- Glaser, P. (1977) Solar power from satellites, *Physics Today*, p. 30-38: Feb.
- Holdren, J. P.(1990) Energy in Transition, Scientific American, p. 157-163, September.
- IAA (1990) The Case for An International Lunar Base: 1st COSMIC STUDY OF THE IAA. Compiled by the Lunar Development Subcommittee of the Committee on International Space Plans and Policies, 55p. International Academy of Astronautics, BP 1268-16, 75766 Paris Cedix 16, France.
- Martin Marietta (1984) Design of a Photovoltaic Central Power Station, 69pp., Contract Report SAND82-7149, DoE Contract DE-AC04-76DP00789, February.

- Mortenson, M. and Saul, P. (1991-in press) Mobile lunar production system to emplace a demonstration LPS. 4pp. (School of Architecture, SICA). Quarterly Report of the Energy Lab, Un. of Houston. (August).
- NASA (1991) Space Transfer Vehicle: Concepts and requirements study. Contract NAS8-37856.
  Martin Marietta (P. Mitchell and J. Hodge) 38pp. Interim Rev. 5. Configuration Splinter Session, Marshall Space Flight Center, Space Transportation Week. 14-18 January.
- NASA (1989) Lunar Power System: Summary of Studies for the Lunar Energy Enterprise Task Force NASA - Office of Exploration, Appendix B-4, see Criswell (p. 84 - 96) in Report of NASA Lunar Energy Enterprise Case Study Task Force, NASA Tech. Memorandum 101652, 178 pp, July
- NASA (1989b) Report of the 90-Day Study on Human Exploration of the Moon and Mars, 145pp., Washington, D.C.: November.
- NASA (1980) Satellite Power System Concept Development and Evaluation Program: Vol. 1 -Technical Assessment Summary Report., Technical Memorandum 58232, 113pp., NTIS, Springfield, VI, 22161. (November).
- NASA (1979) The Solar Power Satellite Concept. 20pp. NASA Johnson Space Center Paper JSC-14898.
- NRC (1981) Electric Power from Orbit: A Critique of a Satellite Solar Power System, 332 pp., National Research Council, National Academy Press, Washington, D.C.
- Stafford, T. P. (1991) America at the Threshold: America's Space Exploration Initiative, Synthesis Group (T. P. Stafford - Chairman), 144pp. and 64pp appendix. U.S. GPO, Washington, D.C. 20402
- Thompson, R. and Criswell, D. R. (1991-in preparation) Solar Power Economic Potential, Un. Houston.

Waldron, R. D. and Criswell, D. R. (1991) System Requirements /Constraints and Design Options for a Global Lunar Power System, Proceedings of the 26th Intersociety Energy Conversion Engineering Conference, Vol.1 "Aerospace Space Power Systems.". (Boston, MA). 7pp. Paper #91-0277. August.

## DYNAMIC ISOTOPE POWER SYSTEMS FOR FLO

## M. E. HUNT ROCKWELL INTERNATIONAL ROCKETDYNE DIVISION

N92-33355-21 1555-21 192-33355 192-14

MAY 5 & 6 1992

## CANDIDATE SYSTEMS

## CONTINUOUS MOBILE/REMOTE POWER


**\***•

SYSTEM	< 1 ĸ₩e	> 1 кWe
RADIOISOTOPE THERMOELECTRIC GENERATORS	X	
ISOTOPE - BRAYTON	X	. X
ISOTOPE - STIRLING	X	X
PHOTOVOLTAIC/REGENERATIVE FUEL CELLS	X	X
ISOTOPE - ALKALI METAL THERMOELECTRIC CONVERTER (AMTEC)	X	X

FREE SPACE MISSIONS WITHIN APPROXIMATELY 1.5 AU WILL BE PHOTOVOLTAIC/BATTERY OR SOLAR DYNAMIC AND ARE NOT CONSIDERED WITHIN THIS STUDY. ISOTOPE SYSTEMS ARE NOT CONSIDERED CANDIDATE SYSTEMS FOR THESE APPLICATIONS.

•

## COMPLEMENTARY DIPS AND RFC UNITS - Roles Dependent on Time Between Recharge Opportunities-



366

# SUMMARY OF FIRST LUNAR OUTPOST POWER SYSTEM OPTIONS NASA-LeRC


ELEMENT	POWER (kW) (Day/Night)	BASELINE	ISOTOPE OPTION	NON-NUCLEAR OPTION
HABITAT	10/9	Array + RFC	DIPS + Array	PV + RFC
ISRU	2/.2	Habitat	Habitat	Habitat
ROVER				
Tele Manned	1.0 2.2	Batt or RFC RFC	DIPS DIPS	RFC RFC
LANDER	.5/2	PFC	DIPS + PFC	PFC
<u>SCIENCE</u>				
Geophysical Solar Physics	.25	RTG	Sm DIPS	RFC
Telescope Suite	.65	RTG	Sm DIPS	RFC
Geologic Toolset + Traverse Package	.60	Rover	Rover	Rover
	***			

NV2V

FLO DIPS IMPLEMENTATION

#### LUNAR DAYLIGHT







NV2V

# FLO DIPS IMPLEMENTATION





The second second





(四)





ASTRONOMY

### DIPS vs RTG ESTIMATED COSTS

\$3000/g x 450 g Pu/ BRICK = \$1.3 M/ BRICK FOR Pu


\$1.3 M/ BRICK (Pu) + \$700 K/ BRICK (FABRICATION) = \$2.0 M / BRICK

1 kWe DIPS = 17 BRICKS x 2 M BRICK = 34 M


1 kWe RTG = 60 BRICKS x 2 M BRICK = 120 M

TOTAL COST DIPS = \$34 M FUEL + \$4 M UNIT = \$38 M/kWe TOTAL COST RTGS = \$120 M FUEL + \$30 M CONVERTERS = \$150 M/kWe

## 2.5 kWe DIPS POWER CART



### TWO-2.5 kWe DIPS MODULES (5 kWe TOTAL)





### Near-Term Thermoelectric Nuclear Power Options For SEI Missions

### Jerry R. Peterson General Electric Company

Presented to The 3rd SEI Technical Exchange Meeting University of Houston May 5 - 6, 1992


1/SELWORKSHOP 5/5>EF Å٩




### Near-Term Options Thermoelectric Nuclear Space Power

- General Purpose Heat Source RTG
  - Qualified and Flown for Galileo/Ulysses
  - Fabrication Underway for Cassini
- Modular RTG
  - Life Verification Underway
  - Available for 1996 MESUR Launch
- SP-100 Early Flight Options
  - Current Technology 6 kW<sub>e</sub> System for 1996 Launch
  - Baseline Technology 15 kW<sub>e</sub> System for 1999 Launch








DOMESTIC: STORE



**GPHS**-RTG



•.

#### **Evolution of RTG Technology** 1990s +1970 1980 1960s ł, T MOD-RTG **GPHS-RTG** MHW-RTG Early RTGs (SNAP 3, 9A, 19, 27) - MARS-ROVER - GALILEO - LES 8/9 - TRANSIT 4, 5 Missions - ULYSSES - VOYAGER 1/2 - TRIAD - CRAF - VIKING - CASSINI - PIONEER - NIMBUS - APOLLO 7.7 5.3 4.0 ≤ 2.2 Specific Power (Watts/KG) Improved Silicon Silicon Germanium Silicon Germanium Lead Tellurides Thermoelectric Germanium Material **Muitiple Couples**

Single Couples

Single Container

(Unicouple)

Single Couples

Single Container

Thermoelectric

Component Configuration


**Single Couples** 

Multiple Containers

(Unicouple)

(Multicouple)

Multiple Containers



, ,

379




### SP-100 Progress

### Design

Design Refinements Based On Extensions Of Present Technology Results In Significant Improvements

### Survivability

Concepts Defined To Achieve Hardness To Current Spec And Super Threat Levels



### Flexibility/Scalability Technology Scales Over Large Power Page And

Development Significant Accomplishments Made In




### SP-100 Early Flight Options – Design Objectives

- Based On Using Proven RTG Unicouple Thermoelectric Converters That Provide a Logical Evolution to Higher Performance GFS Thermoelectric Converters
- Will Demonstrate The Safety Features and Facilitate Safety Approval for Subsequent Missions Through the INSRP Process
- Flight Demonstration Mission Will Provide the Catalyst Needed to Enable Subsequent Operational Missions Based on Technology That is Adaptable to a Variety of Orbital, Interplanetary and Lunar/Mars Surface Power Applications
- SP-100 Early Flight Design Concepts Have Been Developed That are Compatible with Atlas and Delta Launch Vehicles

. .




### SP-100 Thermoelectric Technology Evolution






### **Option G Key Features**





### **Concept G – Radiator Segments**





### Characteristics and Status Near-Term Nuclear Space Power Options

و المعر

Option	Power	Life	Specific Mass	Conversion Type		Earliest Launch Date	Status
GPHS-RTG	285 W <sub>e</sub>	>15 Yrs.	190 Kg/Kw <sub>e</sub>	Unicouple	Titon - IV	Flying	Qualified for Flight In Production
Modular RTG	15 - 340 W <sub>e</sub>	>2 Yrs.	140 Kg/Kw <sub>e</sub>	Radiant Multicouple	Thor/Delta	1996	Life Verification in Progress MESUR Launch Date
SP-100 Baseline Technology	15 Kw <sub>e</sub>	2 Yrs.	175 Kg/Kw <sub>e</sub>	Conduction Multicouple	Atlas IIAS	1999	Technology Under Development. Two Year Fuel Load.
SP-100 Current Technology	6 Kw <sub>e</sub>	2 Yrs.	250 Kg/Kw <sub>e</sub>	Unicouple	Delta II	1996	Existing Technology. Two Year Fuel Load.

- All Near-Term Options Under Existing Contract
- Current SP-100 Contract Has Flight Option
- Mod RTG Flight Would Require New Contract

## RF FEL For Power Beaming

Flockeiclyne Briefing Eloneterni levitetini netteroloxE ever

02

548 est

C.O

333


่ Lyndon ฮ. Johnson Spars Center ฟิลy อี & ฮิ, J992


Cockwell International

### **Rocketdyne RF FEL For Power Beaming**

Rocketdyne Division of Rockwell International has designed and tested all of the laser device components associated with operating an RF FEL for beaming power from Earth. Analysis of the power beaming system requirements reveals that the FEL, identified by NASA as the laser of choice, is the major subsystem requiring demonstration before proceeding further in proving the efficacy of laser power beaming. Rocketdyne has identified a series of low cost, low risk demonstrations which proceed sequentially from a 1kW proof-of-principle demonstration through a 150kW demonstration of beaming power to a satellite to a MW class demonstration of Earth to lunar surface power transmission. This sequence of events can be completed in 5.5 years at a cost of \$188M, with key milestones each year. In coordination with the High Energy Laser System Test Facility (HELSTF) directorate at WSMR, Rocketdyne has identified available HELSTF facilities which support implementation of this tightly scheduled, economical program. POC: Dr Robert Burke, (818) 700-3917










### **Rocketdyne Approach to Power Beaming**

### • RF FEL is the right choice

- Chosen by SDIO for Ground Based FEL Experiment
- Demonstrated high photo cell conversion efficiency in JPL, MSFC, LeRC illumination demo at Rocketdyne
- Easily tunable to maximum response point of whatever P-V cell material is selected
- Rocketdyne RF FEL components are all proven, highly capable designs




### Rocketdyne 1 kW FEL




### Rocketdyne is Ready to Start RF FEL Power Beaming Demo Program


- Currently working with USASDC to install components at HELSTF Test Cell 4
  - Coordinated requirements for 1 kW demonstration with HELSTF director and staff
  - Developed layout for 1 kW FEL
  - Coordinating with Navy for use of HELSTF SKYLITE beam director for power beaming demo
  - Growth to MW power levels on 5 year program
  - Can provide low cost demonstration of GEO satellite illumination within 4 years of funding
- Milestones and cost of sequential scaling of RF FEL to higher power demonstrations have been developed



393


í







٦,


395












### FEL's 3rd Harmonic Output Provides UV Light To Drive High Power Photocathode



1 kW FEL		2 MW FEL
LaB <sub>6</sub>	Cathode Material	LaB <sub>6</sub>
352 nm	Light Wavelength	280 nm
5 x 10 <sup>-4</sup>	Quantum Efficiency	1 x 10 <sup>-3</sup>
1.0 nC	Electron charge/ μ-pulse	2.8 nC
7 μ <b>J</b>	Photon Energy/µ-Pulse	<b>13</b> μ <b>J</b>
N/A	FEL 3ra Harmonic Output/µ-Pulse	<b>40</b> μ <b>J</b>
13 Watts	Average Power on Cathode	670 Watts
6 Watts	Average Power Absorbed	330 Watts
7°C	Cathode Temperature	350 °C
3.4 A/cm <sup>2</sup>	Thermionic Emission @ 1800 °K	3.4 A/cm <sup>2</sup>
2210 °C	Cathode Melting Point	2210 °C
3 mm	Cathode Diameter	6 mm
20 A/cm <sup>2</sup>	Macropulse Current Density	14.2 A/cm <sup>2</sup>
0.026 A/cm <sup>2</sup>	Average Current Density	0.51 A/cm <sup>2</sup>



1561-17

#### 2 MW FEL Wiggler Performance Scales Directly From 1 kW FEL ROC Relative sizes to scale **1 kW FEL Parameter** 2 MW FEL (Nominal) (Max) (Nominal) (Max) 78 MeV **Electron Energy** 100 MeV 120 MeV 500 A 1000 A **Electron Current** 500 A 1700 A 4 m Wiggler Length 12 m 2.4 cm Wiggler Wavelength 3 cm 6.3 % 10% **Extraction Efficiency** 15% 25% 2.7 GW 6.5 GW **Peak Optical Power** 9.5 GW 30 GW

Rockwell International

### 2 MW FEL Optics Based on Components Rocketdyne Built for HAPFEL and GBFEL


	Relative sizes to scale	Rochenar
1 kW FEL	2	MW FEL
<b>0.84</b> μ <b>m</b>	Optical Wavelength	0.84 μm
300 MW	Optical Seed Power	500 MW
70%	Outcoupling Fraction	90%
6.3 %	Extraction Efficiency	15%
0.33 kW	Circulating Power	200 kW
0.7 J/cm <sup>2</sup>	Macropulse Fluence on 1st Optic	100 J/cm <sup>2</sup>
N/A	Damage Threshold	500 J/cm <sup>2</sup>
Sapphire Flat	Outcoupler	Grating
Ring	Resonator Type	Grazing Incidence Ring
8 m	Mirror Spacing	37 m
<b>15</b> °	Incidence Angle on 1st Optic	<b>3</b> °



401


### Power Beaming FEL Program

# Funding requirements (\$M) year from start




Rockwell International

### Laser Power Beaming Proof-of-Principle




12

### Laser Power Beaming Demonstration and Satellite Power Mission



### **Laser Power Beaming for Lunar Mission**



•

OPTICAL ENERGY TECHNOLOGIES INC. 472 WESTOVER ROAD, STAMFORD, CT 06902 203-357-0626

THE MOON AS A SOLAR POWER SATELLITE BY 115-5-24 J-15 GERALD FALBEL

N92-33333

At the last Space Exploration Initiative meeting I attended here, a lot of the papers discussed "Waypoints" in various space exploration programs. It is the purpose of this paper to present approaches which are "off the screen to the right", indicating what goal these waypoints should be on the way to. This is important, because, as we all realize, the day of the blank check for space exploration is over, and the taxpayers and Congress are asking more and more: What do we get out of this"?

I firmly believe that in this climate, the only space exploration project that Congress and the people will support is one which <u>directly</u> improves their economic position or their life style.

I therefore hereby propose a modified version of the Satellite Solar Power System, (SPS), using the moon as the "satellite". I believe this is the only space project that can show a direct cash return on investment, and thus meets the above criterion.

The original SPS was conceived by Dr. Peter Glaser of MIT in 1968, as a series of large, photovoltaic solar collectors orbiting at geosynchronous altitude, and converting and beaming the collected solar power to the earth surface using microwave energy (which can pass through cloud cover). This system was studied extensively under the joint sponsorship of the Department of Energy and NASA between 1977 and 1980.

These studies concluded positively as to this concept's feasibility in hardware, legal, environmental, health, and societal acceptance areas. Unfortunately, in the 1980's President Reagan, proclaimed "Morning in America" but didn't see the sun.

The overall advantages of a Solar Power Satellite are summarized in Table I.

Figure 1, shows the reference system configuration defined by these studies, consisting of a 55 km<sup>2</sup> photovoltaic orbiting collector and a 1 km<sup>2</sup> transmitting microwave antenna. Figure 2 shows a 10 x 13 km elliptical microwave rectenna below the geostationary satellite. Figure 3 shows the breakdown of the collected solar energy and the conversion efficiencies up to the output to the electrical power grid on the earth.

I will first discuss a direct transfer of this highly defined system to a lunar platform, and will then discuss what I believe should be the ultimate lunar SPS configuration.

Figure 4 shows the reference system broken into an array of five, 100 meter high, by 55 km long, 2/1 concentrating, Ga As collectors. Notice that the aluminized polyester concentrating mirror uses the lunar gravity and lack of wind to effectively save half the cost of the collector.

These collectors are located 6° from the lunar pole to account for the sun's  $\pm$  5° elevation angle variation caused by the lunar orbit's inclination to the ecliptic plane.





FIGURE 1 SPS REFERENCE SYSTEM - SATELLITE CONFIGURATION





÷


1

.

FIGURE 2 BASIC SPS REFERENCE SYSTEMS CHARACTERISTICS







OVERALL EFFICIENCY = 6.97% Ge MPTS EFFICIENCY = 63.0% 7.06% SI


FIGURE 3 SPS EFFICIENCY CHAIN (GaAlAs CR2 and Si CR1)

.

409

1

----



ROLLERS FOR ALUMINIZED POLYESTER TO EXPOSE NEW SURFACE, REPLACING MICROMETEORITEDAMAGEDREFLECTOR

FIGURE 4 LUNAR PHOTOVOLTAIC CONCENTRATING COLLECTOR (5 COLLECTORS PER SITE)

#### TABLE I

#### OVERALL ADVANTAGES OF A SATELLITE POWER SYSTEM

- 1. SIGNIFICANT REDUCTION IN THE "GREENHOUSE EFFECT" CAUSED BY BURNING FOSSIL FUELS
- 2. A TOTALLY "CLEAN" GENERATION OF ELECTRIC POWER WITH NO NUCLEAR OR TOXIC WASTE
- 3. THE APPLICABLE TECHNOLOGY IS AVAILABLE TODAY AND REQUIRES NO SCIENTIFIC BREAKTHROUGH, AS DOES HYDROGEN FUSION.
- 4. RESUMPTION OF U.S. TECHNICAL LEADERSHIP IN SPACE, WHICH HAS BEEN LOST SINCE THE APOLLO PROGRAM.
- 5. APPLICATION OF U.S. ENGINEERING TALENT TO USEFUL AND CONSTRUCTIVE ENDS.
- 6. A DEFUSING OF THE OIL-DEPENDENT POWDER KEG OF THE MIDDLE EAST.

- 7. UNLIMITED AVAILABILITY OF CLEAN ELECTRIC POWER WORLDWIDE WILL BENEFIT DEVELOPING COUNTRIES, WILL SAVE THE RAIN FORESTS, AND WILL ELIMINATE ACID RAIN.
- 8. THIS PROGRAM WILL ACCELERATE THE DEVELOPMENT OF LOWER COST EARTH-MOUNTED PHOTOVOLTAIC SOLAR CELLS DUE TO QUANTITY PRODUCTION.
- 9. THE RECTENNAS RECEIVING THE MICROWAVE ENERGY TRANSMIT > 80% OF IMPINGING SUNLIGHT. IF THEY ARE MOUNTED ON FLOATING ISLANDS IN THE OCEANS, AND SYPHON OFF SOME OF THE RECEIVED MICROWAVE ENERGY, AND USE IT FOR DESALINIZATON OF OCEAN WATER, FOOD CAN BE GROWN IN ABUNDANCE TO FEED THE WORLD.
- 10. THIS PROGRAM IS IDEAL FOR INTERNATIONAL COOPERATIVE EFFORT WHERE EVERYONE BENEFITS, THUS MAKING WARS MORE UNLIKELY.

Table II lists the technical advantages of the lunar-based SPS compared to the geosy chronous SPS. Table III lists its disadvantages, and the means of dealing with them

As is shown in Table III, the moon does not face the same surface on the earth as do a geosynchronous satellite in Dr. Glaser's original proposal, but the entire earth c benefit from this electrical energy, and, as shown in Figure 5, three or more rectennas would be located 120° or 90° apart in longitude on the earth surface, and the U.S. would once again become an energy exporting nation. In order to eliminate the possibility of accidentally scanning a high power microwave beam across the eart! surface while switching between ground rectennas, I propose two transmitting antenna on the moon, one aimed at one rectenna, and the second aimed at the next rectenna to which power would be switched as it comes over the earth's horizon. While it is transmitting power, each transmitting antenna, (whose diameter may have to be as lar as 10 Rm to achieve the required diffraction-limited microwave beam size) will be scanned relative to the moon's polar axis by approximately 1° in a 6 or 8 hour period. This can be practically accomplished by achieving the effective 10 KM diameter with an array of smaller antennas ganged together, using the same principle: as is used in large baseline radio astronomy antennas, or preferably, by increasing the ground rectenna area, or increasing the 2.45 GHz transmitting frequency, or both

Of course, the moon rotates relative to the sun also, so at least three such solar collectors will be required, located 120° apart in longitude around the lunar pole. At any time, the combined output of two collectors will be equal to or greater than the peak output of one collector directly facing the sun. The distance between the collectors is about 250 KM, a distance amenable to standard high voltage conductive transmission, microwave beamed power transmission, or superconductor transmission.

The minimum 5 Gwatt input of this system at the power grid represents 46 Billion kilowatt hours per year, which, at the current average price of ten cents/kwhr., represents a yearly revenue of \$4.6 Billion per year. If we complete the "necklace" around the lunar pole, the collection area increases to 355 km<sup>2</sup>, and the net revenue increases to to \$29.7 billion per year. If we use both the north and south poles of the moon the net revenue increases further to \$59.4 Billion per year. Of course, one the solar cell fabrication facilities on the moon are in operation, the collection area can increase indefinitely.

However, I believe that the system shown in Figures 6 and 7 represents a more efficient and lower-cost-per-kilowatt design than the reference system defined by the DOF and NASA studies, which more efficiently uses the attributes of the lunar platform.

Studies of Stirling cycle solar energy conversion systems, conducted at Sandia and at NASA Lewis Research Center have shown that end-to-end solar-to-electricity efficiencies of higher than 30%, or twice the efficiency of the photovoltaic reference approach are feasible with high gain solar concentrators. The system shown in Figure 6, which girds the lunar equator, uses the lunar gravity and windless environment to achieve a very low cost cylindrical concentrator composed entirely of aluminized polyester hanging in a catenary, (which closely approximates a parabola) focusses the sum on a linear series of pipes containing the Stirling cycle gas. This gas is heate to increase its pressure, thus driving the Stirling engines distributed along this linear concentrator, which generate the electricity. No solar tracking is required because it is an optical characteristic of a cylindrical mirror that its line focus i maintained independent of the incident angle of the incoming rays in the plane of the cylindrical axis, and the maximum + 5° angular variation of the sum in the orthogonal plane is accommodated by the width of the black pipe collector. The availability of an unlimited heat sink less than 100°K on the dark side of the moon, allows even

· · · · ·

#### TABLE II

#### **TECHNICAL ADVANTAGES OF A LUNAR-BASED SPS**

- 1. THE MOON IS A MUCH MORE RELIABLE AND STABLE PLATFORM THAN A GEOSYNCHRONOUS SPACECRAFT.
- 2. THE MOON HAS UNLIMITED EXPANSION SPACE FOR ADDITIONAL SOLAR POWER CAPACITY.
- 3. THERE IS NO INTERFERENCE WITH VISIBLE ASTRONOMY DUE TO SPECULAR SUNGLINTS OFF THE SOLAR COLLECTORS, AS THERE IS WITH THE GEOSYNCHRONOUS SYSTEM.
- 4. RAW MATERIALS FOR INCREASED SOLAR COLLECTION CAPACITY ARE AVAILABLE DIRECTLY FROM THE MOON AND DO NOT HAVE TO BE LIFTED FROM THE EARTH.
- 5. COLLECTOR AND TRANSMITTING ANTENNA ASSEMBLY IS MUCH SIMPLER AND CHEAPER UNDER LUNAR GRAVITY THAN IN AZERO G ENVIRONMENT.
- 6. LOCATION OF THE COLLECTORS NEAR THE LUNAR POLE(S) PROVIDES:
  - THE NATURAL ARRANGEMENT FOR A CATENARY (PARABOLIC) MIRROR OPTICAL CONCENTRATOR BELOW A NEAR VERTICAL COLLECTOR.
  - THE COLD AVERAGE LUNAR SURFACE TEMPERATURE NEAR THE POLES MAKES AN EXCELLENT HEAT SINK FOR THE PHOTOVOLTAIC SOLAR ARRAYS, THUS MAKING THEM MORE EFFICIENT.

÷.

#### TABLE III

#### TECHNICAL DISADVANTAGES OF LUNAR SPS VS. GEOSYNCHRONOUS SPS

- 1. EARTH ROTATES UNDERNEATH TRANSMITTING ANTENNA
- 2. MOON IS APPROXIMATELY TEN TIMES FARTHER THAN GEOSYNCHRONOUS ALTITUDE, THUS REQUIRING TEN KM DIAMETER TRANSMITTING ANTENNA TO ACHIEVE THE SAME EARTH RECEIVING RECTENNA DIFFRACTION-LIMITED DIMENSIONS.
- 3. WITHOUT TRANSPONDING TRANSMITTING SATELLITES, THERE IS A DISCONTINUOUS POWER INPUT TO THE GRID AT ANY ONE EARTH LOCATION.

#### PROPOSED SOLUTIONS

- 1. LOCATE RECTENNAS AT THREE OR FOUR LONGITUDES ON THE EARTH, PROVIDING INTERNATIONAL POWER INPUT CONTINUOUSLY TO THE EARTH. (U.S. AGAIN BECOMES ENERGY EXPORTING NATION.)
- 2. DESIGN A LARGE BASELINE GANGED ARRAY OF SMALLER TRANSMITTING ANTENNAS, OR INCREASE THE RECTENNA DIMENSIONS, OR INCREASE THE TRANSMITTING FREQUENCY TO > 2.45 GHZ., OR ALL OF THE ABOVE.
- 3. ADD TWO TRANSPONDER SATELLITES, OPERATING 120 · APART IN THE LUNAR ORBIT, AND ADD TWO MORE TRANSMITTING ANTEMARS ON THE MOON. (THESE TRANSPONDING SATELLITES WOULD BE FABRICATED ON THE MOON AND LAUCHED INTO ORBIT FROM THE MOON.)




FIGURE 5 POWER TRANSMISSION FROM THE MOON TO EARTH (HALF MOON CONDITION)




FIGURE 6 OPTIMUM LUNAR SOLAR COLLECTOR FOR EQUATORIAL MOUNTING

nigher efficiencies for the Stirling cycle than have heretofore been achieved. The use of heat pipes to conduct the low temperature gases in the Stirling cycle to this unlimited heat sink should be able to achieve these high efficiencies. The equatorial location results in 10,000 km. of collector length, with 3,330 km<sup>2</sup> of net collecting area at any one time. As is shown in Figure 7, since the Stirling cycle efficiency is approximately twice that of the photovoltaic cell configuration, this system produces 5.31 Trillion kwhrs per year, generating a revenue of \$558 billion.

In this ultimate system, the power distribution to the earth should be maintained 24 hours a day. This is accomplished through the use of two "transponder" satellites operating at libration points 120" apart in the lunar orbit, as shown in Figure 8. These transponder satellites would consist of rectennas receiving microwave energy from the moon, and two transmitting antennas performing the same function as the transmitting antennas to the earth from the lunar surface described above. These transponder satellites would be fabricated on the lunar surface, assembled in lunar orbit, and located and maintained in their orbital positions using electrically driven ion engines driven from electricity received by their rectennas.

Upon completion and expansion of this ultimate system, the revenues could be used to retire the national debt and ultimately replace the income tax with an electric bill equal to what they are already paying.

Therefore, this ultimate system can be said to give the American electorate what in recent years they have shown that they want, namely, a free lunch!

Now I will discuss how I propose to obtain the seed money to pay for this project. (Once the revenues from the electric power begin, these revenues can be fed back into the system to expand it, without further tax based input).

I propose to fund these intial phases of this project with, read my lips: No new taxes!

In order to accomplish this seeming feat of magic, we must first acknowledge that the "Emperor has no clothes"! By this I mean that we must finally acknowledge that for forty years the U.S. defense budget, having a cumulative total of over \$4 trillion, has incorporated a large percentage of "make work" WPA programs for the Military Industrial Complex.

For those of you not familiar with "WPA", it stands for Works Progress Administration, a New Deal program initiated during the Great Depression to get the unemployed back to work on government sponsored programs. WPA paid artists to paint murals, laborers to replant forests, and contractors to build highways, such as the Merritt Parkway in Connecticut on which I drive every day. This parkway includes beautiful, artistic overpass bridges incorporating different and original artistic freecoes, which were the S level components of the thirties.

In fact, this useful version of WPA is alive and well today and residing in Japan. We call it "Japan Incorporated". If you harbor any remaining doubts relative to this WPA thesis, I will now dispel them with these two recent news items:

- 1. That Superhawk, Senator Edward Kennedy, is reported to be in favor of continuing to build the unneeded Sea Wolf Submarines.
- 2. The House and Senate Democrats have now passed a budget allocation continuing the fabrication of the second Sea Wolf Submarine over the objection of that Superdove, President Bush.

### COLLECTOR AREA X NET KWATTS COLLECTED BY REFERENCE SYSTEM X STIRLING EFFICIENCY REFERENCE AREA PHOTOVOLTAIC EFFICIENCY

 $\frac{3,330 \text{ KM}^2}{55 \text{ KM}^2} X \qquad 5 \text{ BILLION} \qquad X \qquad \underline{2} = 606 \text{ BILLION KW}$ 

YEARLY ENERGY VALUE = 606 BILLION KW X 8760 HOURS/YEAR X \$.10/KWHR


= <u>\$531 BILLION</u>

•

•

۹.

FIGURE 7 ENERGY CALCULATION FOR THE ULTIMATE LUNAR SPS



## FIGURE 8 CONTINUOUS WORLD WIDE POWER TRANSMISSION

How would we transfer the funds presently going to useless defense programs to a luna Solar Power Satellite? We would simply convert the defense contracts covering technical disciplines similar to those in the Solar Power Satellite, with the management of these contracts being retained by the present military responsible personnel. Therefore, no-one from the Defense Establishment would lose his or her job.

If you think this is impractical, I can recall for you two precedents:

- 1. General Leslie Groves, successfully managed the Manhattan Project for the development of the Atomic Bomb.
- 2. Rockwell International stipulated that its subcontractors for the B-1 bomber must come from all 50 states.

For over 12 years I have written letters expounding this misappropriation of U.S. engineering talent to U.S. Presidents, Senators, Congressmen, journalists, Presidential candidates, and Presidents Gorbachev and Yeltsin. I have never received a single direct response to any of these letters, nor any refutation of my arguments. This indicates to me the cataclysmic lack of the "Vision Thing" or in both the Executive and Legislative branches of our government.

In closing, I would like to read two quotations from these letters:

From a letter to President Gorbachev:

"When you address the "Military Industrial Complex", your attitude is that it is the incarnation of evil, intent only upon destroying the Soviet Union by military threats or application of military advantage. Since I am a member of the "Military Industria Complex", I assure you that for me, or any one I know, this is not the case.


However, when it comes to putting bread on the table, most people (including me) will justify their work in the Detense Establishment as assigned tasks that must be done properly and whose parochial justifications may even be advocated so that work accomplished on an ongoing project is not "wasted" by its cancellation. I submit to you that this insidious "work ethic" is the underlying cause of the Arms Race, to a much greater extent than any military or political necessities."


From a letter to President Reagan:

"It might be of interest for you to know that I am, by profession, an electro-optical engineer, whose hey-day would come with the widespread implementation of the systems in "Star Wars". However, I consider such work a prostitution of my art, which, unfortunately, I, and a majority of my professional associates, do as a matter of economic survival."

This leads me to my final manifesto:

Engineers of the world, unite! You have nothing to lose but your net stockings and your hot pants!





# Fast Track NTR Assessment Team

- LeRC
  - \* Nuclear Propulsion Office
  - \* Advanced Space Analysis Office
    - Procurement Division
    - Instrumentation and Controls Division
- MSFC
  - Program Development
  - Research and Technology Office
- DOE
  - Idaho National Engineering Lab (INEL)
  - \*- Los Alamos National Lab (LANL)
    - Sandia National Lab (SNL)

## Industry

- \* Rocketdyne
  - Analytical Engineering Corporation
- \*- General Dynamics

- Space Propulsion Technology Division
- Resources Analysis and Management Ofc.
- \*• Cryogenic Fluid Technology Office
- Safety Assurance Office
- Propulsion Laboratory

\* Indicates Organizations involved in Engine/System Analysis & Design

- Aerojet
- Sverdrup
- \*- Westinghouse
- NUCLEAR PROPULSION OFFICE


## **NERVA-Derivative Engine Parameters**


LEWIS RESEARCH CENTER


·-----


<b>Parameters</b>	<b>Graphite</b>	<u>Composite</u>
Т <sub>ех</sub> (°К)	2550	2700
p <sub>c</sub> (psia)	785	785
ε(-)	200:1	200:1
lsp (s)	870	915
M <sub>engine</sub> (kg)*		
- 25 klbf	3830	3966
- 50 klbf	5601	6009
- 75 klbf	6863	7361


\* Includes internal dome shield and dual turbopumps











LEWIS RESEARCH CENTER


## **Benefits of Modular, NTR-Based Lunar/Mars Space** <u>Transportation System</u>

- Past/On-going studies\* conducted by the NPO indicate that NTR propulsion is also enabling for lunar applications when demanding mission scenarios and/or significant payload delivery capability is being contemplated.
- Study results also indicate the attractiveness of evolving a "proven" lunar NTR transportation system for Mars application through the addition of a "modular propellant tank" for use either as a structural and/or drop tank.
- By using this "building block" approach, a variety of lunar/Mars vehicles can be configured to meet specific mission requirements.
- Analysis is proceeding aimed at quantifying vehicle building block and "best compromise" engine characteristics based on current ExPO mission requirements and a range of HLLV assumptions.

\*References


NVSV

- (1) S. K. Borowski, "The Rationale/Benefits of Nuclear Thermal Rocket Propulsion for NASA's Lunar Space Transportation System," AIAA paper 91-2052, 27th Joint Propulsion Conference, Sacramento, CA, June 24-26, 1991.
- (2) S. K. Borowski, "An Evolutionary Lunar-to-Mars Space Transportation System Using Modular NTR/Stage Components," AIAA paper 91-3573, Conf. on Advanced SEI Technologies, Cleveland, OH, Sept. 3-6, 1991.




## **Comparison of Lunar NTR Vehicles**

"90 Day Study" Fully Reusable Vehicle



LEWIS RESEARCH CENTER



LEWIS RESEARCH CENTER

# NASA

## NTR Vehicle "Building Block" Assumptions

- Modular components are sized to match boost capability of planned HLLV's (233t to 220 nmi w/ 14m x 30m payload volume) to reduce launch cost/maximize performance
- Main "Core" Propulsion Module
  - Includes:
- NTR Cluster Interstage/Docking Structure External Shields
- Tank Structure Thermal/micro Protection
- RCS
- Contingency (engine/shields: 15%; remainder: 10%)
- Dimensions: 14m x 17.25m length (cylindrical tank w/  $\sqrt{2/2}$  ellipsoidal bulkheads) - Total Mass: 233t (41.32 t hardware; 148.7t LH<sub>2</sub>; 15t NTO/MMH)
- "Modular" Tanks
  - Includes: Tank Structure - Interstage/Attachment Structure
    - Thermal/micro Protection
- Contingency (10%)
- Dimensions: 14m x 12.5m length (cylindrical tank w/  $\sqrt{2/2}$  ellipsoidal bulkheads)
- Total Mass:
  - Drop Tanks: 18.8t (w/ 2" MLI) and 98t LH2
  - "In-Line" Tank: 21.9t (w/ 4" MLI & VCS) and 98t LH2

## **Comparison of NTR Vehicles**

(lsp = 915 s)-10 m — 2007 MARS PILOTED ("No MEN" SPLIT MODE) IHLED = 622 t  $\Omega$ ECC1 REUSABLE LUNAR OR EXPENDABLE 2005 MARS CARGO MODULAR LH, TANKS LUNAR VEHICLE ``CORE " 14 m STAGE 

2 X 50 klbf Engines

#### LEWIS RESEARCH CENTER

<sup>3</sup> X 50 klbf Engines

LEWIS RESEARCH CENTER

## Summary/Conclusions

- NTP enables 93 t to TLI (cryo/storable lander option) for the "First Lunar Outpost" within original HLLV limits (200-210 t)
- LeRC has performed an initial assessment of the performance capability for single and multi-engine NTP concepts over a wide range of thrust levels, HLLV configurations (10 and 14 m diameter), and mission profiles.
- Mission Profiles examined to date:

NNSN

- Expendable TLI (One Burn) Mission
- Reusable Lunar (Four Burn) Mission
- 2005 Mars Cargo Mission
- 2007 Mars Piloted Mission
- Preliminary results indicate that the 50 klbf engine is the "best compromise" engine based upon IMLEO and burn time considerations.
- Initial analysis indicates both the attractiveness and feasibility of developing a "single, modular, NTR-Based" Space Transportation System (STS) for Lunar/Mars missions.
- The implementation of a NTR-Based Lunar STS will position NASA favorably for Mars missions in the 2005-2010 time frame. An <u>accelerated schedule</u> and <u>reduced</u> <u>cost</u> is anticipated for the Lunar/Mars STS because of a single development effort.

# Nuclear Thermal Rocket by 2000: A DOE Perspective

By

Steven D. Howe Los Alamos National Laboratory

and

Marland Stanley Idaho National Engineering Laboratory

For the

## **3rd SEI Technical Interchange Meeting**


May 5, 1992

Space Nuclear Propulsion Technology


92-33335

Z


A-14



## **FUEL DEVELOPMENT PATH \***



## SYSTEM TESTING PATH



#### \*Potential refurbishable sites exist

## **SUMMARY**

- NASA AND DOE TEAMS HAVE RECENTLY INVESTIGATED AN "NTR FAST TRACK" PROGRAM PLAN TO DEVELOP A FLIGHT- READY ENGINE BY THE 2000-2002 TIMEFRAME.
- BASELINE ASSUMPTION OF THE STUDY RELIED ON UPGRADING THE ROVER/NERVA FUEL FORM AND USING TESTED TECHNOLOGIES TO PRODUCE AN ENGINE WITH POTENTIAL FOR Isp BETWEEN 900-925s.
- IMPROVED FUEL RECOVERY AND CHARACTERIZATION CAN BE ACHIEVED WITH A COMBINATION OF ELECTRICAL TESTS AND REACTIVITY MEASUREMENTS. (MAJORITY OF FACILITIES CURRENTLY EXIST.)
- COMPLETE FUEL VALIDATION COULD BE ACCOMPLISHED IN A GENERIC FUEL ELEMENT TEST REACTOR TO SIMULATE ENGINE OPERTIONAL CONDITIONS. (CURRENTLY INVESTIGATING APPLICABILITY OF LOFT AT INEL.)
- FULL-POWER, GROUND TESTING APPROACHES ARE BEING EXPLORED - LANL AND INEL ARE CURRENTLY INVESTIGATING THE REFURBISHMENT AND UPGRADE OF THE PREVIOUS ROVER/NERVA FACILITIES-EMAD AND ETS-1.

LOS ALAMOS NATIONAL LABORATORY

Space Nuclear Propulsion Technology

## **SEI FACILITY ACTIVITIES - INEL**

- DOE Construction Short Form Data Sheets submitted for SEI Facilities with FY-94 Budget Request
  - Formal submittal for Test Reactor Hydrogen Loop (HFIR and ATR) to DOE-NE
  - Informal submittal of Fuel Element Test Facility, Reactor Test Stand, and Engine Test Stand at undetermined site made to DOE-NE
- LOFT Containment Building re-activation study completed (using INEL internal funds)
- Prepared draft environmental compliance plan for DOE's SEI ground test facility
- Supporting NASA-LERC non-nuclear test facility evaluations
- Supporting NASA-LeRC "Fast-Track" proposal
- Top Level Scoping Evaluation of use of SNTP PIPET for SEI NTP fuels testing
- Limited Evaluation of use of ETS-1 and E-MAD at NTS for SEI engine testing (internal LANL and INEL funds)
- Supporting review of EIS for SNTP
- Developing overall nuclear test selection strategies and plans

LOS ALAMOS NATIONAL LABORATORY

Space Nuclear Propulsion Technology

#### Engine Maintenance and Disassembly Facility Jackass Flats, Nevada Preliminary Status Report 4/15/92

#### • <u>General Description:</u>

Designed for the assembly, disassembly, and maintenance of a NERVA-type engine. A T-plan, multi-story structure, 280ft by 350ft divided into 7 separated sections based on specific functions and material traffic flow

• •

- Cold Assembly Area
- Hot Maintenance and Disassembly Area
- Post Mortem Cells
- High and Low Level Cells
- Operating Galleries
- Shop and Service Areas
- Office Area
- Preliminary Inspection Results;
  - Building generally in excellent shape
  - All major equipment items from hot-cell windows and manipulators to machine tools present and in good shape.
  - Overhead cranes in good shape and functional.
  - Electrical system grounding and labeling in compliance and functional.
  - No PCB electrical equipment on site.
  - Plumbing system in place and functional.
  - HVAC major components in good shape and functional.
  - Large shielding doors in place and in good shape.
  - RR system in place complete with engines, load cars, and turntables.
  - New cooling tower needed.
  - Sprinkler system needed.
  - Covering of asbestos flooring needed.
  - Roof leaks need patching.
  - Water tank leak needs patching.
  - Seismic assessment needed but no obvious problems.

## Engine Test Stand No. 1 Complex Jackass Flats, Nevada Preliminary Status Report, 4/15/92

•	<ul> <li>General Description:</li> <li>Designed for ground developmental testing of a downward firing NERVA-type engine in a flight simulated environment. The ETS-1 complex includes:</li> <li>A 160ft, 100t aluminum structure supporting a 77,000 gal LH2, vacuum jacketed run tank with associated below grade pipe chase and process piping, exhaust duct vault, and a 3ft wide by 40ft high by 100ft long concrete shadow shield.</li> <li>A below grade control point building supporting 2000 channels of diagnostics</li> <li>A cryogenic dewar and high pressure gas vessel tank farm with interconnecting process piping</li> <li>An engine compartment radiation shield.</li> <li>A diffuser/ejector exhaust duct.</li> <li>A 2.5 Mgal water storage tank.</li> <li>Required I&amp;C, electrical and water systems, HVAC and other support systems.</li> </ul>
•	Preliminary Inspection Results;         - Complex facilities generally in good shape.         - Aluminum superstructure in good shape.         - 250,000 gal LH2 tank in good shape.         - 77,000 gal LH2 run tank in good shape.         - 77,000 gal LH2 run tank in good shape.         - Process piping in place.         - Engine compartment radiation shields in good shape.         - RR track in place.         - Electrical switch-gear in good shape.         - Significant scavenging of HP gas tanks one remaining.         - Above ground buildings need significant repairs.         - Below grade control point building needs significant upgrading.         - Some flame-proof electrical boxes missing at test stand.         - Some stairway sections missing.         - Shadow shield bracing for seismic shock needs upgrading.         - Seismic assessment needed.         - Move LH2 dewar from Test Cell C for longer run times.

Los Alamos

# GENCORP AEROJET

# Propulsion Division

# Space Defense Initiative Technologies and Hardware Can Help Resolve Certain Space Exploration Initiative Weight and Performance Issues

N92-3333

#### **Propulsion Division**

# GENCORP AEROJET

۰.

# Many Aerojet Programs Have Contributed to Advanced Technologies and Hardware

Program and POP	Objective
Advanced Liquid Axial Stage (89-92)	Space Based Interceptor - Advanced Liquid Propulsion and Structures Technologies
Missile Integrated Stage (90-94)	Low Cost Booster/Interceptor
Liquid Propellant Sustainer (90-94)	Gelled Technology for Interceptor
High Endoatmospheric Def. Int. (87-93)	Ground Based Interceptor
SCIT-DACS (87-92)	Kill Vehicle Propulsion
THAADS (92- )	Theatre Missile Defense Propulsion
GBI (90- )	Ground Based Interceptor
Brilliant Pebbles (90-95)	Advanced Booster and Kill Vehicle Propulsion Systems and Structures
Endo LEAP (90- )	Endoatmospheric Interceptor Controls & Cooling

## **Propulsion Division**

# GENCORP AEROJET SDI Programs' Technical Focus


Lightweight	-	<ul> <li>High Mass Fraction Stages</li> <li>Heavy Use of Composites</li> <li>Advanced Propellants</li> </ul>
Low Cost	_	<ul> <li>Highly Producible Designs</li> <li>Integrated Propulsion Modules</li> </ul>
High Performance	; —	<ul> <li>Ultrafast Engine Responses</li> <li>Front-End Cooling for In Atmospheric Flight</li> <li>Advanced Propellants</li> </ul>

',

# **GENEORP** SDI Technology Provides Order **AEROJET** of Magnitude Savings on Weight

#### **Propulsion Division**

**Current State of the Art** 



Wt = 38.3 lbm (17.4 kg)

93.9 cm

# GENCORP AEROJET

# **Benefits are Realized in Several Areas**

- New Engines
- Structures
- Tanks
- Advanced Propellant

#### **Propulsion Division**

# GENCORP AEROJET

# Emerging Composites Technologies Result in Numerous Propulsion Benefits

Subsystem	Conventional Technology	ALAS Technology	Benefit
ALAS Axial Engine	<ul> <li>Refractory Nozzle</li> <li>Low Density Graphite Chambers</li> <li>Metal Structural Shell</li> </ul>	<ul> <li>Braided Carbon Axial Nozzle</li> <li>Carbon Structural Shell</li> </ul>	Nozzle Weight Reduced 90%
Propellant Tanks	<ul> <li>All Metal Designs Usually Titanium</li> <li>Glass – Overwrapped Thick-Wall Metal Liners (Pressure Load is Shared Between Liner and Overwrap</li> </ul>	<ul> <li>Carbon Fiber Overwrapped with Very Thin Wall Liners (Pressure Load Is Not Shared Between Liner and Overwrap)</li> </ul>	<ul> <li>~60% Weight Savings from</li> <li>1 lbm to .45 lbm</li> <li>Order of</li> <li>Magnitude</li> <li>Savings in Cost</li> <li>\$10,000 vs</li> <li>\$1000</li> </ul>
ACS Engine	Refractory     Nozzie	<ul> <li>Free Standing Graphite Nozzle</li> </ul>	<ul> <li>Nozzle/Chamber Weight Reduced from 2 lbm to &lt; 2 lbm</li> </ul>
A	All Aluminum Bolted/Welded Configuration	<ul> <li>Injection Molded Carbon Rings</li> <li>Braided Rings</li> <li>Stamped Struts</li> <li>Plastic Welding</li> </ul>	Weight Savings     - from 2 lbm to     5 lbm
Composite Structure			




# **Advanced Liquid Axial Stage**



- 111 × 1 • • . . . ,

> - in a min Car + was ,




#### GENCORP AEROJET TechSystems

# Propellant and Pressurant Tank Accomplishments

#### Features

- 10<sup>6</sup> psi (7000 MPA) Carbon Fiber
- Yielding .006 in (.015 cm) Al Liner
- No Liner Welds
- Passive Propellant Management Device



Status	
<ul> <li>Fiber/Resin System</li> <li>Demonstrated</li> </ul>	
• .006 in (.015 cm) Liners Made	
<ul> <li>Long Term CIF</li> <li>Material Storage</li> <li>Demonstrated</li> </ul>	
<ul> <li>He Containment Demonstrated With 0.010 in (.025 cm) Liner/@ 10,000 psi</li> </ul>	
<ul> <li>Prototype PMD Made</li> </ul>	
<ul> <li>First Burst Tests at 14,100 and 16,860 psia</li> </ul>	

١


` -

# GENCORP AEROJET

**Propulsion Division** 

# New Family of Lightweight Engines Has Been Developed

<u>Program</u>	Engine Type	Pc	Tests
ALAS	Axial	775	150 Tests 1989-91
ALAS	ACS	500	110 Tests 1989-91
SCIT	Divert	500	20 Tests 1989-92
LDI	Axial/Divert	300-600	23 Tests 1992 (On-going)
GBI	ACS	500	To Be Tested July 1992
BP	Divert	500	To Be Tested Early 1993
BP	ACS	300	To Be Tested Mid 1993



## **ALAS Has Demonstrated High Performing Helium Tanks**

20

Use or Disclosure of This Data is Subject to the Restrictions on the Title Page of This Presentation

454



# Propellant Hoop And Helical Fibers Have Been Selected



Fiber	Tank Application	Modulus (MSI)	Tank Weight Comparison, % Fu Ox		Delivered Fiber Stress (KSI) Avg	
T-400 (3K Tow)	Helical	36.4	+8	+4	367 368 370	368
T-650(1) (3K Tow)	Helical	35.0			591 605 591	596
T-650 (6K Tow)	Helical	42.0	+10	+5	596 609 603	603
Apollo 53-750 (12K Tow)	Helicat	53.0	+3	-1	615 666 660	647
Т-1000Н	Ноор	42.0	+6	+5	919 901 791*	910
T-1000GB(3)	Hoop	42.0			909 901 981	(2) 924

\*Not Included in Average

ALAS0228




#### **Selection Criteria**

- (1) Minimum Weight Design
- (2) Higher Strength
- (3) Cheaper and Available




## **ALAS Developed An Advanced Carbon Composite Structure**



KKV Deflection Test 0.018 in. Deflection at Flight Load






Compression Test

Ultimate Failure at 5000 lbf

SLOSH Tensile Test • Strut Demonstrated at 2X Load



Forward Ring Component Test Set-Up ALAS Aft Ring Component Test Set-Up



Use or Disclosure of Proposal Data Is Subject to the Restriction on the Title Page of This Proposal

Main Strut Component Test Set-Up

**Propulsion Division** 

#### GENCORP AEROJET TechSystems

# ALAS Structure Estimated Weight Summary

<mark>، 1</mark>

1

<ul> <li>Forward Ring, Ibs</li> </ul>	.147
Aft Ring, Ibs	.230
ACS Supports, Ibs	.0178
Tank Support Inserts, lbs	.0086
<ul> <li>Struts, Structure, Ibs</li> </ul>	.328
<ul> <li>Struts, Engine, Ibs</li> </ul>	.041
<ul> <li>Tank Retaining Pins, Ibs</li> </ul>	.011
·	Total, lbs .757

Note: Change in Tank Mounting Method Provides .0195 lbs Total Tank Weight Saving

# Optimum Material for Each Component

Component	Material	. Rationale
Helium Tank Mount	High Strength Graphite Fiber/High Elongation Resin [±45°] Layup	Best Balance of Stiffness/Strength
Longeron	High Modulus Graphite Fiber/BMI Resin [±45°/0°/±45°] Layup	Stiffness Driven Producible BMI for Thermal Capability
Aft Ring*	High Strength Graphite Fiber/High Elongation Resin	Best Strength/Weight Ratio for Launch Looks
Forward Flange*	Beryllium	Stiff Isotropic Machined Part Ribs/Bosses

\*Detailed Structural Analysis and Dynamics Must Be Done

458

#### **Propulsion Division**

# GENCORP AEROJET

# CLF<sub>5</sub> Offers Improved Performance Without Undue Safety/Toxicity Issues

- Performance
  - High specific impulse 340-360 sec delivered
  - High specific gravity 1.8 vs.  $N_2H_4 = 1.04$
- Safety
  - No untoward incidents in 5 years of recent testing
    - Over 300 rocket engine tests
    - Over 25 different engines
    - Stage test (loading and firing)
  - Handles like N2O4 and tested with same precautions (Amines are more trouble)
  - Strong reaction with hydrocarbons must be clean
    - Lox cleanliness level is appropriate
- Toxicity
  - Only about two-four times as toxic as N<sub>2</sub>H<sub>4</sub>
  - About 4-8 times safer than Titan III launch
    - Titan III fuel load = 105,000 lb of  $N_2H_4/UDMH$
    - $CLF_5$  on Atlas ~ 6,500 lb
    - Equivalent N<sub>2</sub>H<sub>2</sub> = 13.000-26.000 lb



# LOW PRESSURE - HIGH PERFORMANCE BOOSTER ENGINE TECHNOLOGY FOR ULTRA-LOW COST LAUNCH VEHICLES

PRESENTED TO THE THIRD SPACE EXPLORATION INITIATIVE TECHNICAL INTERCHANGE MEETING UNIVERSITY OF HOUSTON, CLEAR LAKE PARK


co

MAY 5 & 6, 1992 R. L. SACKHEIM DEPUTY DIRECTOR PROPULSION TECHNOLOGY AND FLUID MECHANICS CENTER, APPLIED TECH. DIVISION TRW SPACE & TECHNOLOGY GRP.

## Liquid Propellant Booster Engine Technology

# Approach Low-cost booster engine

2-



- Strategic advantages
  - Reduced booster engine cost with enhanced reliability and safety
    - Enabling technology for low-cost assured access to space Reduced launch costs are needed to achieve national space program goals
    - Would enhance competitive position of U.S. commercial space industry
- TRW development activities
  - TRW is a leader in pioneering low-cost booster engine technology
  - Current work builds on TRW technology work started in late 1960s
  - A cooperative program is in place to demonstrate low-cost booster technology at small scale (16.4 Klbs thrust)
    - LOX/LH<sub>2</sub> propellants
    - TRW (IR&D)
    - NASA Lewis Research Center (National Space Act)





## Background

- TRW pioneered a minimum-cost booster engine concept in mid 1960s
  - Low pressure, pressure fed
    - Pc ~ 300 psia
  - Ablative cooled
  - Commercial manufacturing processes
  - Pintle injector
    - Produces inherently stable combustion

50 C

•

- Relaxed margins
- · Several minimum cost engines were fabricated and tested
  - 250 K
    - NTO/UDMH
  - 50 K
    - IRFNA/UDMH
    - LOX/Propane
    - LOX/RP-1
  - 35 K
    - IRFNA/UDMH
  - All were stable
- Efforts terminated in early 1970s



## TRW PINTLE INJECTOR BACKGROUND

- TRW PINTLE INJECTOR WAS ORIGINALLY DEVELOPED UNDER NASA APOLLO PROGRAM AS THE LUNAR MODULE DESCENT ENGINE (LEMDE)
  - $P_C = 100 PSIA$
  - NTO/A-50
  - DEEP THROTTLING (10:1)
  - 10,500 LBS FULL THRUST
  - ABLATIVE COOLED
  - PRESSURE FED
- A FIXED THRUST VARIANT OF LEMDE (TR 201) FLEW 75 SUCCESSFUL FLIGHTS AS THE LOW COST, PRESSURE FED SECOND STAGE ENGINE OF DELTA
- TRW LOW COST BOOSTER ENGINE WORK IS BASED ON THE LEMDE CONCEPT
  - SIMPLIFIED PINTLE INJECTOR DESIGN
  - COMMERCIAL MANUFACTURING PROCESSES
  - LOW COST ABLATIVE


# 7**R**₩

## **TRW PINTLE INJECTOR BACKGROUND (Cont.)**


- PINTLE INJECTOR ADVANTAGES INCLUDE:
  - INHERENT COMBUSTION STABILITY ON A WIDE RANGE OF PROPELLANTS WITH GOOD TO EXCELLENT COMBUSTION PERFORMANCE HAS BEEN DEMONSTRATED
    - NTO/UDMH
       NTO/A-50
       LOX/LH<sub>2</sub>
       HDA/USO
    - LOX/PROPANE
       LOX/RP-1
       IRFNA/MMH (GELS)
    - NTO/MMH
       NTO/N2H4
       LOX/N2H4
       IRFNA/UDMH
  - MULTI-PROPELLANT CAPABILITY WITH THE SAME ENGINE DESIGN
    - IRFNA/UDMH, LOX/RP-1 AND LOX/LH<sub>2</sub> INJECTORS CAN BE A COMMON DESIGN
    - INJECTOR CAN BE DESIGNED FOR EASY RECONFIGURATION TO ACCOMMODATE PROPELLANT CHANGES
  - DIAL-A-THRUST CAPABILITY
    - INJECTOR CAN BE DESIGNED FOR EASY RECONFIGURATION TO ACCOMMODATE DIFFERENT THRUST LEVELS
  - DEEP THROTTLING CAPABILITY
    - MOVING SLEEVE MAINTAINS PROPELLANT VELOCITIES FOR EFFICIENT THROTTLING
    - 19:1 THROTTLING HAS BEEN DEMONSTRATED WITH LOW COST TECHNOLOGY

.





#### BOK HEAT SINK ENGINE RUN ON LOX/RP-1



466



#### **COMPARISON OF BOOSTER ENGINE PERFORMANCE**

,

	ENGINE DESIGNATION							
	F-1	H-1	RS-27		TRW CONCEP	PTS*		SSME
PROPELLANTS	LOX/RP-1	LOX/RP-1	LOX/RP-1	LOX/RP-1	LOX/RP-1	LOX/LH2	LOX/LH2	LOX/LH2
P <sub>C</sub> (PSIA)	982	700	700	300	660	300	660	3270
ε	16.0	8.0	8.0	7.0	10	7.0	10.0	77.5
0/F	2.27	2.23	2.25	2.67	2.24	6.6	6.6	6.0
I <sub>SPSL</sub> (SEC)	265.4	263.4	263.3	233.9	263.4	304.2	339.5	370.8
I <sub>SPVAC</sub> (SEC)	304.1	295.8	294.7	291.5	301.6	379.2	388.6	455.3


\*  $\eta_{I_{SP}}$  = 93.1% FOR LOX/RP-1

2

 $\eta_{I_{\text{SP}}}$  = 96.0% FOR LOX/LH<sub>2</sub>



## LAYOUT OF 16.4 K LOX/LH2 HEAT SINK ENGINE





۰,

## BOMB TEST SUMMARY

• .

- FIVE BOMB TESTS
  - 20 GRAINS, TANGENTIAL
  - 20 GRAINS, RADIAL
  - 40 GRAINS, RADIAL
  - 40 GRAINS, TANGENTIAL/20 GRAINS, RADIAL
    - SIMULTANEOUS FIRING
- LARGEST OVERPRESSURE ~ 200 PSI
- Pc RECOVERY WITHIN 40 m sec
- ABSOLUTELY STABLE



#### STATUS OF 16.4 K LOX/LH<sub>2</sub> TESTS AT LeRC (5 MARCH 1992)

- 67 HEAT SINK CHAMBER TESTS COMPLETED (UP TO 2.5 SEC DURATION)
  - INJECTOR PARAMETRIC OPTIMIZATION
  - OFF-DESIGN OPERATION
- ONE 20-SEC ABLATIVE CHAMBER FIRING PERFORMED
- HAVE DEMONSTRATED
  - OPERATION AT EXTREME OFF-DESIGN POINTS
    - O/F FROM 4.9 TO 11.8 (DESIGN IS 6.6)
    - 100% DOWN TO 60% RATED FLOWS
  - OPERATION ON SATURATED LOX
  - OPERATION WITHOUT LHe INJECTOR PRECHILL
  - ABLATIVE PERFORMANCE
  - HIGH COMBUSTION PERFORMANCE
    - > 98% C\* FOR HIGHEST PERFORMING PROPELLANT RING COMBINATION
      - BLOCKAGE RATIO = 48%,  $\Delta P$  = 150 PSIA LOX RING
      - $\Delta P = 50 PSI LH_2 RING$
    - THIS RING IS EXPECTED TO ACHIEVE 95% C\* ON LOX/RP-1
  - ABSOLUTELY NO INDICATION OF SPONTANEOUS COMBUSTION INSTABILITIES
    - $P_{rms}/P_c < 1\%$  (LEMDE QUAL. DATA 1.2% <  $P_{rms}/P_c < 2.0\%$ )
    - CONTRIBUTION TO Prms AT FREQUENCIES > 300 HZ IS NEGLIGIBLE
      - VIRTUALLY NO COMBUSTION TURBULENCE EVIDENT
  - NO HARD STARTS OR SHUT DOWNS
  - FIVE BOMB TESTS WITH NO INDUCED COMBUSTION INSTABILITIES

529-32 11552/ N92-333380 12

#### FEASIBILITY OF LUNAR COMMUNICATIONS USING THE TDRS II

Michael A. Jordan The MITRE Corporation 409 3rd ST., SW, Suite 300 Washington, DC 20024

#### ABSTRACT

The Space Network's Tracking and Data Relay Satellite (TDRS) II geostationary satellite constellation may be capable of providing lunar communiocations for the Space Exploration Initiative. This paper summarizes geometrical coverage constraints, link budgets, TDRS II delivery schedules and life cycle costs for various Space Network architecture options.

#### **1 INTRODUCTION AND BACKGROUND**

The Space Network is a constellation of equatorial geosynchronous Tracking and Data Relay Satellites (TDRSs) which relay the communications from low earth orbiting user spacecraft to the White Sands Complex (WSC) - a ground station and processing facility at the NASA complex in White Sands, NM. The nominal Space Network constellation [1,2] in the Space Station era consists of four spacecraft located at 41° W, 46° W, 171° W and 174° W longitudes (see Figure 1). A TDRS spacecraft has two independently steerable 4.9 meter dishes, each of which supports Single Access Sband and Ku-band services (see Figure 2). Single Access services are circularly polarized with a user-selected polarity.

In the later half of this decade, the Space Network will begin a transition from the TDRS to the TDRS II. The TDRS II will extend communications service support to users with orbital altitudes up to Geostationary Earth Orbit (GEO) while remaining backward compatible with existing TDRS services. In addition, TDRS II will introduce a new Single Access service at Ka-band.

Space Exploration Initiative lunar missions require communications support for bases and rovers on the lunar surface, as well as spacecraft in-transit between the earth and the moon. A communications architecture based on existing Space Network concepts can provide much of the basic communications needs of the lunar initiative. Modification of the Space Network satellite design or constellation architecture, possibly including the addition of a terrestrial terminal, can allow the Space Network to provide lunar communications.

This paper summarizes previous estimates of geometrical coverage constraints, link budgets, TDRS II delivery schedules and life cycle costs for various Space Network architecture options [3,4,5]. Geometrical coverage constraints are determined by comparing the coverage provided by constellation architecture options with possible lunar user locations. Link budgets are based on existing Space Network service requirements, projected lunar user requirements, and estimates of lunar user characteristics. Projected TDRS II availability is compared to estimated need dates. Life cycle costs for comparing ground costs in the architecture options are based on WSC upgrade costs. Satellite costs are based on NASA estimates. .. ..




Figure 1. Space Network Architecture




Figure 2. The Tracking and Data Relay Satellite

2

#### **2 SUMMARY OF RESULTS**

#### 2.1 General Field of View Considerations

The Field Of View (FOV) of a constellation and/or ground stations is constrained by the limits on the maximum antenna scan angles and the placement of the satellites or earth terminals. Satellite antenna scan angle limits in elevation or azimuth result in areas behind the satellite which are outside of the FOV (See Figure 3A). Earth terminal FOV is limited at low elevation angles due to terrain masking and absorption and scintillation due to increased atmospheric transit ranges (see Figure 3B). Earth intrusion effects a satellites FOV just as terrain masking effects a ground terminals FOV

The impact of the FOV constraints on lunar support depends on the orbital ephemeris - orbital parameters - of the lunar user's trajectory. Elevation angle requirements are determined by the declination extrema of the TDRS II and the user in-transit or on the lunar surface. The maximum declination of a user in an orbit is the inclination angle of the orbit. TDRS II orbital inclination is assumed to be no greater than 7°. Lunar users may be on the surface of the moon or in a transfer orbit between a low earth parking orbit and the moon. The extrema in declination of a user on the lunar surface is determined by the ephemeridies of the moons orbit, while the in-transit user's declination extrema is determined by the cis-lunar transfer orbit. The moon's orbit is nearly circular and has an inclination of up to 28.5° north and south. The apparent angular extent of the moon as viewed from the earth is about 0.5°.

The selection of a cis-lunar transfer orbit is governed by mission constraints. Circumlunar trajectories with retrograde lunar orbits and direct return trajectories were often used during Project Apollo. Injection into these orbits occurred from low earth parking orbits after near due east launches from Kennedy Space Center. Inclinations of these orbits are typically below 34.3°. Communications support for unconstrained lunar and in-transit longitudes requires full circle azimuth coverage. The maximum in-transit user declination drives the TDRS II elevation angle requirement.

Earth intrusion outages occurred in groups of two to seven clustered around the time the moon crosses the equatorial plane. The onsets of the outages within a group are separated by between 24 and 26 hours. Outage durations are up to 82 minutes. The frequency of onsets increases with TDRS II inclination, decreases with lunar inclination, and decreases as the relative geocentric azimuth of the ascending nodes of TDRS II and the moon increases.

#### 2.1.1 Near Baseline Architecture

The baseline architecture is the nominal Space Network constellation. Three Zones Of Exclusion (ZOEs, i.e., areas outside of the line-of-sight due to FOV restrictions or intrusion of the earth into the FOV) occur in the baseline architecture at altitudes beyond GEO; one ZOE is located "behind" the constellation (i.e., in the region above the western hemisphere), and the other two are due to earth-intrusion into the line-of-sight from the TDRS II to the user (see Figure 4). A fourth ZOE occurs at low altitudes (below 1200 km), but does not uniquely impact lunar communications support.




Figure 3A. Satellite Field of View Constraints




Figure 3B. Earth Terminal Field of View Constraints




Figure 4. Baseline Space Network Constellation Field Of View Constraints

The connectivity provided by the baseline Space Network architecture may be characterized by the mean communications link availability. The baseline architecture provides 80% mean link availability for users on the lunar surface. For in-transit users, the outage due to earth intrusion (which accounts for two to three percent of the lost communications link availability at lunar ranges) will increase until it approximately doubles at GEO altitudes. This will be counteracted by the decrease in the communications link availability lost "behind" the constellation, which disappears at GEO altitudes. This availability assumes an increase in the TDRS II elevation angle scan limits to 39°. The nominal TDRS II maximum elevation scan angle is sufficient except when the TDRS declination and the user declinations are at their extrema.

#### 2.1.2 Augmented Architecture

In the "augmented" architecture, the ZOEs are closed by augmenting the near-baseline architecture with a ground station on the earth and an operational satellite in a central location (see Figure 5).

The near-baseline TDRS II architecture of four operational satellites can provide a communications link availability of 80% for lunar users. The communications link availability is increased to 97-98% by the addition of a ground station at the WSC. The ground station provides coverage when the user is "behind " the constellation. The WSC ground terminal and the baseline TDRS II constellation can cover the ZOE "behind" the constellation with minimum elevation angles above 16.2° for lunar surface users and 11.4° for cis-lunar transit users. (The use of the same frequencies for both space-to-space and space-to-ground links may result in regulatory conflicts.)

The addition of a TDRS II satellite at a central location (i.e., an orbital slot between 102.5° W and 112.5° W longitude) increases the link availability to 100%. The additional satellite covers lunar users when line-of-sight to all baseline Space Network TDRS IIs is blocked by earth-intrusion. The central satellite would also prevent traffic overload caused by the addition of the lunar users. The WSC ground terminal and the central satellite can, by themselves, provide 84% availability for a single user and 51% for two independent users. (The reduced coverage for two users is due to limits on the overlap of the two TDRS II antennas.)




Figure 5. Augmented Space Network Constellation Field Of View Constraints

#### 2.1.3 New Configuration

In the "new configuration" architecture, one or more satellites are placed at remote locations, i.e., below the horizon as viewed from the Space Network ground terminals in White Sands, NM. These remote satellites provide coverage of ZOEs which occur in the baseline architecture (see Figure 6). The placement of one satellite in an orbital slot between 36.8° E and 106.2° E longitude will provide coverage of the ZOE "behind" the baseline constellation -including about six degrees of operational overlap - except for the earth-intrusion into the line-of-sight of the remote satellite. This assumes an increase in the TDRS II elevation angle scan limits to 38°. The nominal TDRS II maximum elevation scan angle is sufficient except when the TDRS declination and the user declinations are at their extrema.

The earth-intrusion into the remote satellite's line-of-sight and one of the two earth-intrusion ZOEs in the baseline architecture may be eliminated by the proper placement of the remote satellite. If the satellites in the baseline architecture used for lunar support are those in the 41° W and 174° W longitude orbital slots and the operational overlap is relaxed from six to one degree., then a remote satellite placed between  $28.8^{\circ} - 29.5^{\circ}$  E longitude or between  $115.5^{\circ} - 116.2^{\circ}$  E longitude will satisfy these conditions. An increase in the azimuth antenna scan angles of the satellite may be used to increase the operational overlap and/or increase the orbital slots which satisfy these conditions. Two remote satellites can provide complete coverage and operational overlap.

The new configuration architecture presumes the use of direct inter-satellites links for relaying high volume user data from the remote TDRS IIs (those not within the line-of-sight of the WSC) to a relay TDRS II which is within line-of-sight of the WSC. (The inter-satellite link is an option for the future system growth reserve in the TDRS II Phase B program, and has been suggested if closure of the low altitude ZOE is required.). The new configuration architecture also results in the introduction of ground stations outside the continental United States to support the telemetry, tracking and control of the remote satellites.




Figure 6. New Space Network Constellation Field Of View Constraints

#### 2.2 Services

Projections of the data rates for lunar surface support have shown maximum forward rates of 25 Mb/s and return data rates of 350 Mb/s. The rates required for the first lunar outpost may be significantly less [5]. Link analyses show that the TDRS II can support S-band, Ku-band, and Ka-

.....

band single access services at lunar distances (see Table 1). Rate 1/2 coded QPSK modulation, which is not specified for the present forward link, is suggested to increase the forward data rate supportable by TDRS II for lunar users. One coded Ka-band return service can provide a return data rate of 150 Mb/s. The 350 Mb/s maximum data rate projected for a lunar user is not one of the Phase B TDRS II options. Coded return services are not presently specified for TDRS II Ka-band return signal access services at data rates above 150 Mb/s although there may be sufficient bandwidth in the channel to support rate 1/2 coded 350 Mb/s return signals.

In S-band, a  $1.7^{\circ}$  Half-Power Beam Width (HPBW) antenna pattern from a 5 meter antenna would produce a beam diameter of over 10,000 km at lunar ranges. This would provide coverage of the entire lunar surface. At Ku-band, a  $0.2^{\circ}$  HPBW produced by a 5 meter antenna would produce a spot beam with a radius in excess of 700 km on the lunar surface. Similarly, at Ka-band, a  $0.1^{\circ}$  HPBW produced by a 5 meter antenna would produce a spot beam with a radius in excess of 350 km on the lunar surface. Efficient use of the nominally single access services by multiple lunar users may require the use of some multiplexing or multiple access technique.

#### 2.3 Schedule -

The first TDRS II satellite's availability date is assumed to be in 1997, and the following satellites are assumed to be available for launch every twelve to eighteen months The projected date for the first robotic precursor mission is in the late 1990's, the first test flight of the manned portion of the lunar exploration initiative is in the early 2000's. Support from the robotic precursor could be provided by a WSC ground station and/or the first TDRS II. The manned lunar mission could be supported by three TDRS IIs (see Figure 7).

Space Network replenishment is based on a launch strategy in which on-orbit replacement satellites are available when needed (as spares) with a probability of 80%. If operational use is made of the planned on-orbit spare, then no additional TDRS IIs are required in the augmented architecture. In the event of a failure of an on-orbit TDRS II in one of the eastern or western slots, either the central satellite would need to be moved to replace the failed TDRS II, resulting in a decrease in lunar communications coverage to 97-98%, or there would be decreased services in the eastern or western slots until another TDRS II is launched. If an augmented architecture of one operational satellite in the central location in addition to the baseline architecture of four operational satellites plus one spare is implemented, at least 2 additional satellites would likely be required by the end of the TDRS II era (2013) in order to ensure an 80% availability.

#### 2.4 Cost

The augmented architecture requires the addition to the WSC of three direct lunar downlink antennas (two operational plus one spare) and a TDRS II equipment chain (which normally supports two independent links, each with a primary and hot spare). Commonality of design was assumed in order to eliminate non-recurring development costs, and collocation to minimize operational costs. The resulting projected ten-year life-cycle cost for this architecture is less than \$125 million. This does not include the additional costs of the communications links between the WSC and the terrestrial end-users.

#### User Characteristics

Band	S-low	S-high	Ku	Ka-low	Ka-med	Ka-high
Antenna Diameter, m	1.0	2.0	4.9	1.0	2.0	4.9
Antenna Efficiency, %	55	55	55	<b>5</b> 5	55	55
System Noise Figure, dB	5.5	5.5	5.5	5	5	5
Transmitter Power, dBW	13	13	16	13	13	16

v S-high	Ku	Ka-low	Ka-med	Ka-high
e None	1/2	1/2	1/2	1/2
2 0.08	1	1	5	25
0 15.0	2.2	1.3	1.3	1.3
5 45.5	45.5	56.0	56.0	56.0
5 -211.5	-228.2	-232.5	-232.5	-232.5
9 1.2	25.7	16.9	22.9	30.7
3 12.3	10.2	8.2	7.4	8.1
2 0.2	3.3	1.3	0.5	1.2
	e None 2 0.08 0 15.0 5 45.5 5 -211.5 9 1.2 3 12.3	e         None         1/2           2         0.08         1           0         15.0         2.2           5         45.5         45.5           5         -211.5         -228.2           9         1.2         25.7           3         12.3         10.2	e         None         1/2         1/2           2         0.08         1         1           0         15.0         2.2         1.3           5         45.5         45.5         56.0           5         -211.5         -228.2         -232.5           9         1.2         25.7         16.9           3         12.3         10.2         8.2	e         None         1/2         1/2         1/2           2         0.08         1         1         5           0         15.0         2.2         1.3         1.3           5         45.5         45.5         56.0         56.0           5         -211.5         -228.2         -232.5         -232.5           9         1.2         25.7         16.9         22.9           3         12.3         10.2         8.2         7.4

(\*Based on a 10^-5 BER, SGL S/N = 16 dB, and a 2.5 dB implementation loss;

S- and Ku-band includes 3 dB of pointing loss)

#### TDRS II Return Link

.

.

Band	S-low	S-high	Ku	Ka-low	Ka-med	Ka-high
Coding Rate	1/2	1/2	1/2	1/2	1/2	1/2
Data Rate, Mb/s	0.1	· 0.4	75	20	80	350
RF Wavelength, cm	13.6	13.6	2.0	1.2	1.2	1.2
User EIRP, dBW	37.7	43.7	71.1	58.8	64.9	75.7
Space Loss, dB	-212.3	-212.3	-229.0	-233.5	-233.5	-233.5
User Prec, dBWi	-174.6	-168.6	-157.8	-174.6	-168.6	-157.8
Min. Req. Prec, dBWi 🕶	-174.9	-168.9	-161.2	-175.0	-169.0	-162.6
Margin, dB	0.3	0.3	3.4	0.4	0.4	4.7

(\*\*Based on TDRS DG2 QPSK BER 10^-5;

S- and Ku-bands include 3 dB of pointing loss)

WSC Forward Link						
Band	S-low	S-high	Ku	Ka-low	Ka-med	Ka-high
Coding Rate	None	None	1/2	1/2	1/2	1/2
Data Rate, Mb/s	0.02	0.08	1	1	5	25
RF Wavelength, cm	15.0	15.0	2.2	1.3	1.3	1.3
WSC EIRP, dBW	45.5	45.5	45.5	66.0	66.0	66.0
Atmospheric Loss, dB	0.0	0.0	-2.8	-7.4	-7.4	-7.4
Space Loss, dB	-210.7	-210.7	-227.4	-231.7	-231.7	-231.7
User G/T. dB-K	-4.9	1.2	25.7	16.9	22.9	30.7
Eb/No, dB	15.6	15.6	9.6	12.4	11.4	12.2
Margin, dB***	3.5	3.5	2.7	5.5	4.5	5.3

;

э

WSC Return Link						
Band	S-low	S-high	Ku	Ka-low	Ka-med	Ka-high
Coding Rate	1/2	1/2	1/2	1/2	1/2	1/2
Data Rate, Mb/s	0.1	0.4	75	20	80	350
RF Wavelength, cm	13.6	13.6	2.0	1.2	1.2	1.2
User EIRP, dBW	37.7	43.7	71.1	58.8	64.9	75.7
Space Loss, dB	-211.5	-211.5	-228.2	-232.7	-232.7	-232.7
Atmospheric Degrad., dI	0.0	0.0	-2.8	-11.6	-11.6	-116
WSC G/T, dB-K	5.3	5.3	20.0	40.3	40.3	40.3
Eb/No, dB	10.1	10.1	10.0	10.5	10.5	14.8
Margin, dB***	3.2	3.2	3.1	3.6	3.6	7.9

•

(\*\*\*Based on QPSK BER 10^5 and 2.5 dB implementation loss;

S- and Ku-bands include 3 dB of pointing loss)

Table 1: Sample Link Budgets for Lunar Users




Figure 7. Schedule

In an augmented architecture with one operational satellite in the central location in addition to the baseline architecture of four operational satellites plus one spare the additional ground segment acquisition and ten-year operations and maintenance costs of two antennas (prime and backup) and a redundant equipment chain are about \$100 million. The additional space segment costs are approximately \$400 million to \$600 million for two additional satellites and launches.

The new configuration architecture requires two additional remote ground terminals in order to provide TT&C support for the two TDRS II satellites which are relocated in order to close the ZOEs. Data is relayed to the WSC either by inter-satellite links between the TDRS II, a ground hop using the TDRS II, and leased commercial lines. Based on the incremental changes to the baseline TDRS II Phase A designs, the cost of this architecture is estimated to fall in the range of \$150 to \$250 million.

#### **3 CONCLUSIONS**

Several options for using the Space Network in support of lunar communications are available (see Table 2). The use of the Space Network as a basis for the lunar exploration initiative offers a low risk, evolutionary approach with maximum use of existing ground-based processing facilities developed in support of the Space Station Freedom program. In addition, the use of a single location for the ground terminal (i.e., the NASA facility at White Sands, NM) offers low operational costs.

The TDRS II mechanical design is well-suited for the lunar support if the augmented architecture is used. Maximum antenna elevation scan angles should be increased from 31° to 39° to ensure no drop-outs occur. The nominal TDRS II scan angle is sufficient except when the TDRS declination and the user declinations are at their extrema.

The addition of error correcting codes on the forward links and the highest data rate on the return links may be required.

The impact of the additional loading associated with the lunar initiative on the capacity of the TDRS II constellation, and the ability of the constellation to support the navigation requirements for lunar in-transit and surface operations requires further investigation.

The availability of a GEO slot between 102.5° W and 112.5° W longitude for operational use of the central spare in the augmented architecture should be investigated.

Possible regulatory conflicts associated with the use of the same frequencies for both space-tospace and space-to-ground links in the augmented architecture should be investigated.

Efficient use of the bandwidth available from the TDRS II may require multiplexing multiple low-rate users onto a single TDRS II single access service. Further investigations of the options and their implications on Space Network design and operations is required.

The impact of an operational spare on WSC operations should be considered.

Expansion room in the WSC infrastructure (e.g., common communications, depot, training facilities) sufficient to support the addition of the direct downlinks and the operational spare should be considered as a portion of the TDRS II development.

#### Table 2. Comparison of Space Network Constellation Architecture Options

Parameter	Near-Baseline	Augmented	New Configuration
S/C Antenna Scan Angles ±Az(E-W)/±El(N-S),°	77/39	77/3 <del>9</del>	77/38
Ground Segment	Nom	1 Ground Terminal	Remote Ground Terminals
Link Availability	80	100	100

#### **4 LIST OF REFERENCES**

- 1. \_\_\_\_\_, 31 July 1989, Phase B Advanced Tracking and Data Relay Satellite System (ATDRSS) Service Requirements Specification, S-500-1, Goddard Space Flight Center, Greenbelt, MD
- 2. \_\_\_\_\_, 31 July 1989, Phase B Advanced Tracking and Data Relay Satellite System (ATDRSS) System Requirements Specification, S-500-2, Goddard Space Flight Center, Greenbelt, MD
- 3. Jordan, M., Using the Space Network in Support of Lunar Communications, MTR-91-W00098, in preparation, The MITRE Corporation, Mclean, VA
- 4. Jordan, M., "Space Network Support for Lunar Communications", AIAA 91-3531, American Institute of Aeronautics and Astronautics, Washington, DC
- 5. Brandel, D., and Jordan, M., Earth-Lunar Communications Using the Advanced TDRSS", IAF 439, International Astronautical Federation, Paris, France
- 6. Hei, D., and Stephens, E., "FLO TISN & Operations. Data Systems & Communications Architecture", April @, 1992, NASA GSFC, JSC ExPO

# NASA

483

B-4

### **SATWG QFD Objectives**

(1) Initiate a Cooperative Process for Continual Evolution of an Integrated, Time Phased Avionics Technology Plan

-Involve customers, technologists, developers, managers

(2) Demonstrate Application of QFD to SATWG Technology Planning Process

•"Customer-Focused" Effort

•Training & Forum for Teamwork

•Inputs to a "Total" Multi-Project, Multi-Year Plan Via QFD

(3) Demonstrate Computer Network Technology To Augment QFD Process

> •Reduce Travel Costs and Make More Convenient to a Geographically Dispersed Team

> > SATWG Networked Quality Function Deployment

Z 6 2

21

Don Brown

### NASA SATWG Networked Quality Function Deployment (QFD)

Applying state of the art concurrent engineering tools to NASA Strategic Avionics requirements for the space infrastructure.

> QFD - Involves the development and prioritization of requirements for space systems, followed by analysis of technology areas to address these requirements.

Voice and data networking are being used to facilitate the QFD process and involve technology users, developers, and program managers

General requirements have been defined for space systems, as well as program specific requirements.

These requirements are being correlated to system design characteristics that can be altered to meet requirements

This analysis is useful when considering how to most effectively expend resources for the most value added technology advancement.

SATWG Networked Quality Function Deployment

# NV2V

485

### **SATWG Networked QFD Participation**

**Facilitators:** 

-Martin Marietta, Denver

The QFD Team:


-Ames Research Center -Johnson Space Center -Kennedy Space Center -Langley Research Center -Lewis Research Center -Marshall Space Flight Center

Other Sources of Input:

-Project Offices (NLS, ACRV, Commercial ELV)

-SATWG Panels (C&T, VHM, SAAP, GN&C)

SATWG Networked Quality Function Deployment



Satwg technology plan	Le	ve		of	Im	por	tan	ce	(	Cu	st	ome	er#1)	)			A1
		Le	eve	1 0	f	Imp	ort	an	Ce	; (	Cı	isto	mer	#2)			A2
			Le	vel	0	of I	mp	or	lar	nce	) (	Cus	tom	er#3)	)		A3
			[	Lev	/el	of	In	ηp	ort	an	ice	; (C	usto	omer	ŧ4)		A4
				Γ	.ev	el	of	In	ιp	ort	an	cè	(Cu	stom	er#5)		A 5
A-1a Matrix					Ir	ndu	str	y	No	W							В
"What" Evaluation	1					19	94-	19	96	; F	Pla	n ((	CEL	V,	.)		C1
							_	_	-			Plan					C2
									_	_				(ACF		)	C3
						1								n (N			C4
														Plan			C5
	N	A									200	)4-2	006	Plar	ייין ר	.)	C6
3/26/92	L		E								- [1	Rati	0 0	f Imp	rove	ment	D
	S	R				i							Sal	es Po	oint		E
		V	V								İ			Abso		Weight	F
	*	*	•									-			Dem	anded Weight	G
Customer Demands ("What's"):		<b></b>						_			$\downarrow$						
1.1 Be Insensitive to Schedule Chgs		3			_	7			7		_	_		3.0			
1.2 Accommodate P/L Variability		1				3			7		_		_	1.0	<u></u>		
1.3 Improved Maintainability	-	4		$\perp$	-	7			9		_	_		4.0		Cust#1 Wt (W1)=	0.0%
1.4 Robust System Performance		5			_	7			7		_	_		5.0		• • •	100.0%
1.5 Launch & Perf Mission on Demand		5				5			7			9.0	1.0	5.0	6.1	Cust#3 Wt (W3)=	0.0%
2.1 Minimize Cost of P/L increases		1			_	8		1	_			1.0	1.0	1.0	1.2	Cust#4 Wt (W4)=	0.0%
2.2 Meet Recur Cost Goal	-	1			1			-	7			1.0	1.0	1.0	1.2	Cust#5 Wt (W5)=	0.0%
2.3 Meet Non-Recur Cost Goal		3			1	8		7	9			7.0	1.0	3.0	3.7		
2.4 Minimize Cost of Failure		4			1	_			7			9.0	1.0	4.0	4.9	A=A1*W1+A2*W2	+A3*W3+
2.5 Improve Design Process (PDT's)	-	1			1	6		_	7			8.0	1.0	1.0	1.2	A4'W4+A	.5*W5
2.6 Minimize Production Cost Risk		1			1	3	1	1	7			1.0	1.0	1.0	1.2	D=Plan/Now (user	selectable)
2.7 Minimize Ops Cost Risk		4			1	7	1	7	9	Τ		7.0	1.0	4.0		F=A'D'E	
3.1 Be Reliable	5	5	4		1	5		7	7			7.0	1.0	5.0	6.1	G=F/(FTotal)	

٠

•



. ' '

					Su	bs	titu	te	Q	ual	ity	Ch	ara	cteristics ("How's"):
satwg technology	3.1 Adaptive Guidance/Landing													
	D 3.2 Auto Nav, Rendezvous & Capture						pture							
	E		1		_		_		_	_	_			tors
	M			1	3.4	A	dv	and	ed	A	lao	rith	ms.	S/W
	A				1		5 (	_	_				,	
A-1b-2 Matrix	N		Į .				_	_	_		An	ten	na	Systems
"What" vs "How" Correlation	D													mit/Receive Systems
	E													ital Signal Processing
	D													clent Modulation/Coding
	]	İ												d RF/Op Tracking Sensors
	w	Ì												ower Source
	Т	ſ									}		_	Power Distr/Cond
Customer Demands ("What's"):		1								{		ł		
1.1 Be Insensitive to Schedule Chgs	3.7						1	3		<b>—</b>				
1.2 Accommodate P/L Variability	1.2													
1.3 Improved Maintainability	4.9											[		
1.4 Robust System Performance	6.1													
1.5 Launch & Perf Mission on Demand	6.1													
2.1 Minimize Cost of P/L Increases	1.2													
2.2 Meet Recur Cost Goal	1.2													
2.3 Meet Non-Recur Cost Goal	3.7													
2.4 Minimize Cost of Fallure	4.9													
2.5 Improve Design Process (PDT's)	1.2													
2.6 Minimize Production Cost Risk	1.2													
2.7 Minimize Ops Cost Risk	4.9													
3.1 Be Reliable	6.1													
3.2 Be Safe	6.1													
3.3 Improve Product Quality	6.1													
3.4 Achieve Program Dependability	6.1													
4.1 Improve System Modernization Cap	3.7													
4.2 Improve Visibility Into System Health	6.1													
4.3 Optimize P/L Accommodation	1.2													
4.4 Optimize Mission Accommodation	2.4								3	3	9			
4.5 Man-Rateable	3.7													
4.6 Provide Benign Environment	1.2								1				·	

· •.

4

\*\*


.

•



Advanced Avienics Johnson Space Center

# **Study Objectives**



# Will commercial avionics do the job?

Improvements needed?

N92-33340


#### Honeywell

0 /



Advanced Avionics Johnson Space Center

# **Program Objectives**



 $\mathbb{N} \, \mathbb{N} \,$ 



## Architecture Requirements Comparison

Advanced Avienics Johnson Space Center

	Advanced Avolnics	Nondevelopmental Item Design Requirements			
Requirements	System Requirements	Military	Commercial		
Cost	Low	High	Low		
Reliability	High	High	High		
Maintainability	Space	Ground/war	Ground		
Useful Life	90 days/20 years	20 years	20 years		
Safety	High	High	High		
Quality Assurance	High	High	High		
Transportability	High	High	High		
Health Monitoring	High Migh	Medium	Medium		
Commonality	High	High	High		
Environmental	TANAN UNA MUTANI MANANGKATA				
Acceleration	ETO	Maneuvers	Low		
Vibration	ETO	High	Low		
• Shock	Docking/landing/ETO	Hits	Landing		
Electromagnetic	Space 2	Electronics	Electronics		
• Thermal	2800W/m <sup>2</sup>	Medium	Medium		
Contamination (dust)	High	Medium	Low		
Meteorite	Yes	No	No		
Radiation	GCR/SPE	No	No		
Partial vacuum	Yes States	Some	No		
Performance	High	High	High		
Physical • Size		0	0		
	Small	Small	Small		
• Mass	Light	Light	Light		
Power     Materials	Low	Low Minimum	Low Minimum		
Autonomy	Outgassing High	Medium	Low		
Reusable/Expendable	Both	·	Reusable		
Manned/Man-Rated/Unmanned		Reusable	Manned		
Growth/Flexibility	Man-rated	Manned			
Growth/Flexibility	i se cultur	Medium	Medium		

Shaded areas Indicate significant differences between commercial requirements and space requirements of this study

### Honeywell

.



Advanced Avienics Johnson Space Contor

# **Architectural Approach**

- Flexible integration—from transitional COTS+ integration to COTS+ framework with a minority of space-qualified products
- Universal applications
  - All future manned/unmanned space missions/vehicles
  - Backward integration
  - Surface applications
- Universal architecture
  - Standard interfaces (multistandard)
  - Open architecture
  - Modular avionics
  - ARINC 651\*
  - LRU subsystems compatible
- Cost-effective
- \* Special acknowledgment and appreciation is given to the AEEC for permission to incorporate ARINC 651 concepts into this study.


Honeywell



Advanced Avienics Johnsen Space Center

~

## Architectural Framework



Flight-Critical Vehicle Management Network

- Scalable multinetwork/ bus architecture adapts to different missions/ vehicles and accommodates COTS interfaces
- Point-of-departure design is Boeing 777 architecture
  - Federated hierarchy
  - Distributed processing
  - Flight-critical, faulttolerant ARINC 629
     bus, ARINC 629
     system data bus, highthroughput FDDI
     optical avionics LAN
     network, TAXI and
     ARINC 429 bus LRM
     interfaces

No monoroll



# Ultra-Reliability Requirement Implementation

Advanced Avienics Johnson Space Center

#### **Problems**


- Ultra-reliable avionics are desirable for extended and deepspace missions. These missions will degrade avionic reliability due to increased galactic and solar radiation explosure.
- Ultra-reliability (fail-op, 10 failure probability) may not be practical to meet. This normally brings up fault tolerance, fault detection, fault isolation, and recovery (FDIR) design issues.
- Parallel redundancy and/or pooled sparing redundancy using multipurpose electronics modules will be required for longer duration missions. The cost to orbit and posit powered redundant avionics is undesirable.


#### Solution

- Define architecture to allow cold sparing and hot/cold insertions
- Define new deferred maintenance architecture (e.g., quad channel) and operations (e.g., <10-day deferral) for cold sparing. In this solution, maintenance is used for cold spare insertions. This eliminates the cold spare technology gap identified in other studies.
- Specify cold storage in areas other than user chassis (may be protected storage areas)

#### Benefit

- Ultra-reliable reliability
- No technology gap





### Honeywell



# **Summary of Results**

- A COTS<sup>+</sup> avionic system concept was defined and implemented within space avionic architectures
- System specifications, avionic architecture, and COTS+ qualification were modified as required to accommodate COTS+ integration; a relatively small set of COTS+ unique "needs" (or "changes" requiring further development) were identified
  - Distributed, physically partitioned avionics
  - Acceleration qualification as required
  - SEU recovery
  - Humidity and salt spray qualification
  - Acoustic qualification as required
  - Storm cell and safe for cold spares on extended-duration missions
  - Qualification by analysis for outgassing effects
  - Partial vacuum testing as required
  - Configuration and parts control



# Summary of Results (continued)

- One concern (a possibly unaccommodating need) was identified—radiation tolerance of commercial parts
  - Possibility of substituting radiation-tolerant parts
  - Using radiation-protected equipment bays or spot shielding
- No technology gaps (development requiring significant involvement, funding, time lapse and/or risk) were identified
- COTS+ reduces space avionic needs and technology gaps
  - COTS<sup>+</sup> is available by definition
  - Space avionics requirement study
    - --Red (technology gap) 13---7

    - --Green (current/near-term technology) 29---95



( )

# **Conclusions and Recommendations**

- COTS provides the space program many attractive benefits
  - Reducing technology gaps
  - Cost-effectiveness
  - Dependability
  - Delivery timelines
- The COTS+ concept for space avionic architectures appears workable in part or in totality. Radiation tolerance of COTS+ products is a concern requiring further assessment. It is recommended that the development needs identified within the study be addressed in ongoing studies.
   Sponsorship of standards, initiation of technical maturation programs, and further studies are recommended.
  - AHP willty assessments are suggested
  - Deferred maintenance concept should be validated
  - COTS demonstrations are encouraged
  - Transitional Integration is suggested
  - A comprehensive development plan is suggested as a next step

# Common Manned Module

Space Exploration Initiative Third Technical Interchange Meeting University of Houston - Clear Lake May 6, 1992




# **Combined Lunar Crew Module Studies**

Economic analyses say reusable single crew module reduces costs of Moon to stay exploration program by \$5B

- What does that module look like?
  - Aerodynamics?
  - Weights?
- Runway landing or prepared site recovery?
- Reusable or replaceable TPS?
- What technologies should be supported now?

Car a common module satisfy all manned reentry requirements?

### **STV** Lunar Return Trajectories MSFC- BOEING




Perigee Point Latitude varies with Epoch Date


Return to KSC can be initiated on any lunar orbit



### Ballistic Parachute Earth Landing System Reference LTS Crew Module Concept

MSFC - BOEING







BUEING

.


### Equilibrium Temperatures for Common Manned Module During Lunar Return Reentry




# L/D = 0.5 LCRV Reentry Accuracy



### **Midcourse Correction Accuracy**



# Three Future Manned Re-entry Systems Under Study



### Space Transfer Vehicle

Space Transfer Vehicle Concepts and Requirements Study (NAS8-37856)


### Third Space Exploration Initiative



### Multi Stage Lunar Lander Storable vs Cryo Propulsion

University of Houston 06 May 1992





N92-33342

John R. Hodge (303) 977 - 2792

MARTIN MARIETTA

### **Groundrules and Assumptions**



### **TLI Stage Interface**

- Post TLI Payload Capability Is 76 t
  - Current Baseline is 93 t

### **Element Design**

- The Return Stage Will Have the Capability of Bringing 200 kg of Cargo Back to Earth
- The Lander Will Have the Capability of Delivering at Least 27.5 t of Cargo or 5.0 t of Cargo and Crew of Four to the Lunar Surface
  - Current Cargo Baseline Is 31 t
- Crew Module Mass Is 9.2 t (including radiation shielding & consumables)
  - Current Baseline is 6 t

### 440 Descent & 444 Ascent System Isps

#### **Mission**

- 4 Day Trans-Lunar/Trans-Earth Transfer Time
- 45 Day Lunar Stay Time
- 4 RL10-A3 Engines (Thrust = 16,300 lbs)
- 15% (of Total) Trapped and Residual Propellants

#### MARTIN MARIETTA


002 SE920317-02B

, 7

### **Performance Parametrics**



Configuration	TLI Mass	Comments
• EXPO Reference	91 t	Cryo Descent/Storable Ascent
Cryo 2 Stage Lander	78 t (23% Savings)	<ul> <li>All Cryo</li> <li>Cost Benefits</li> <li>Propulsion Commonality</li> </ul>
Cryo 1-1/2 Stage Lander	75 t (26% Savings)	All Cryo     Cost Benefits     Propulsion Commonality     Fewer Program Elements



MARTIN MARIETTA

175

003

. 1

1/

. .

### **Comparison of the Lander Configurations**



Option	Advantages	Disadvantages		ISS Fraction
#1	<ul> <li>Close To Surface P/L Platform</li> <li>Packages in 33 ft Dia.</li> <li>Few Strct Mod's For Cargo Mission</li> <li>Conventional Tank Mounting</li> </ul>	<ul> <li>Large # of Tanks</li> <li>Large Surface Area / Volume Ratio</li> </ul>	0.0%	0.848
#2	<ul> <li>Close To Surface P/L Platform</li> <li>Packages in 33 ft Dia.</li> <li>Few Strct Mod's For Cargo Mission</li> <li>Fewer # of Tanks</li> </ul>	<ul> <li>Additional Baffles &amp; Acquisition Device Work for Tanks</li> <li>Non Conventional Tank Mounting</li> </ul>	7.7%	0.855
#3	<ul> <li>Lower Structural Mass</li> <li>Packages in 33 ft Dia.</li> <li>Fewer # of Tanks</li> </ul>	<ul> <li>Increased Thermal Leak From Tank Attach Structure</li> <li>No Infinite Plane Cargo Deck</li> <li>Complex Mechanisms</li> </ul>	1.6%	0.849
#4	<ul> <li>Moderately Lower Structural Mass</li> <li>Packages in 33 ft Dia.</li> <li>Fewer # of Tanks</li> </ul>	<ul> <li>High Thermal Leak From Tank Attach Structure</li> <li>Complex Ascent Adaptor</li> <li>Non-Conventional Tank Mounting</li> </ul>	6.9%	0.855

**Recommendation:** Option #1 as Baseline & Option #2 as Alternate

٧


MARTIN MARIETTA



s.


### **Recommended Configuration**

Piloted & Cargo Vehicles with a Common Lander



005


-MSFC





Concern -

Undesirable Effects from Debris Generated by Engine Exhaust Impingement



Obscuring of Landing Site, Making HazardAvoidance and Navigation More Difficult

**Throwing of Large Size Debris Significant** 

 Distances (Hundreds or Even Thousands of Feet). Concern over Major Damage from Debris, or Problems from Dust Contamination of Optics, Windows, or Mechanisms on Existing Lunar Installations.

Causing Damage to Critical Portions of a Lander,

• which May Interfere with a Safe Landing, or Preclude Reuse as an Ascent Vehicle.

Mitigation -

Prepare a Hard Surfaced Landing Site as Soon as • Possible

- Eventually, Routine Flight Operations Should Use Prepared Sites

**Place Engines in Close Proximity** 

- This Will Help Minimize the "Fountain" Effect, Which May Blast Lunar Debris at the Lower Side of the Lander

#### MARTIN MARIETTA



## **Concern**

Separation Impingement Due to Launch Anomalies





## **Mitigation:**

- Simultaneous Start-Up and Desired Thrust Level Achieved in All Engines Prior to Separation.
- Guide Rails Attached to Lander For Controlled Separation of Ascent Stage Eliminating Impingement of Engine Bells With Surrounding Structure
- Additional Shielding May Be Added To Act As a
   Plume Deflector Forcing The Lander Onto The
   Surface, During Separation

## Follow-on:

 Additional Analysis is Needed To Determined Effects of Timing Sequence During Engine Start-Up and Motion Realized By Lander

#### MARTIN MARIETTA






- Abort Scenarios and Options Were Developed for Each Phase of the Mission: Pre-TLI to Lunar Landing to Earth Reentry
- Abort During Lunar Descent Is a Major Discriminator Between the 1.5 Stage and 2 Stage Systems in Regards to a Main Propulsion Failure
  - The 1.5 Stage Vehicle Has No Abort Option Available
  - The 2 Stage Vehicle Can Abort to LLO with the Ascent Stage
  - This Can Be Mitigated with Single Engine Out Capability
- Both Lander Options Cannot Tolerate an Engine Failure during the Lunar Ascent Phase of the Mission without Incorporating an Engine Out Capability
  - Also Would Give the 1.5 Stage System Engine Out Capability During Descent on the Piloted and Cargo Missions

The Single Propulsion Approach, Consisting Of 3 - 4 Engines And Single Engine-out, Provides Both a Highly Reliable and Efficient System.

#### MARTIN MARIETTA

# **Propulsion System Reliability**



MARTIN MARIETTA

010 JH920428-05A

# System Risk Assessment



Cryogenic Propellant Management (Ascent)

Risk	Mitigation		
<ul> <li>Boiloff Of Critical Return Propellant         <ul> <li>Lunar Day/Night/Day (7% H2, 1.5% O2 per month)</li> </ul> </li> </ul>	<ul> <li>Reduce Tanks' View To Direct Radiation <ul> <li>Center of Vehicle</li> <li>Combination Vapor Cooled and Debris Shield</li> </ul> </li> <li>Separate Ascent and Descent Tanks <ul> <li>Heavier Insulation Possible on Ascent Tanks</li> </ul> </li> </ul>		
<ul> <li>Pressure Build Up In Tanks         <ul> <li>Frozen Vents</li> <li>Large Temperature Increases On Tank Surfaces</li> </ul> </li> </ul>	<ul> <li>Backup Cryo Management Systems <ul> <li>Redundant Pressure Relief</li> <li>Redundant Vapor Cooled Shield Tubing</li> </ul> </li> <li>Tankage Configuration Reduces Visibility to Heating Source</li> </ul>		
<ul> <li>Liquid Acquisition</li> <li>Problem Similar With Storable</li> <li>LH2 &amp; LO2 Difficult To Handle</li> </ul>	<ul> <li>Acquisition Devises Ensure Vapor-Free Liquid.</li> <li>Tank Head Idle</li> <li>Paramagnetic</li> </ul>		

MARTIN MARIETTA

011

# System Risk Assessment



Single Propulsion System

## Advantages

- Reduction In Engine Quantities
- Performance Gains with Higher Cryo Isp

## **Risks**

- Disconnects With Lander Tankage
   Vulnerable to Leakage
- Increased Plumbing Complexities
- Higher Potential For Engine Damage
   During Initial Ascent
- Potential Damage Or Contamination During Final Descent

Lander/Ascent Vehicle Clearance

Reduction In Overall System Height

Operational Confidence Due to LOI

- Engine Gimbaling

and Descent Burns.

- Lander Deformation At Landing
- Non-Vertical Ascent
- Release Failure of:
  - "Hold-Downs"
  - Fluid Disconnects
  - Electrical Disconnects



System Restart Following Extended
 Surface Stay

#### MARTIN MARIETTA



# System Risk Assessment



# RL-10A3 Cryogenic Engine


Risk	<b>Concerns/Mitigation</b>	
<ul> <li>System Restart Following Extended Surface Stay         <ul> <li>Lunar Day/Night/Day</li> <li>Up to Three Starts Prior to Ascent</li> <li>Temperature Differential Across Engines</li> </ul> </li> </ul>	<ul> <li>Longest Period Between RL-10 Burns Has Been 24 Hours (In-Space)         <ul> <li>Titan/Centaur Operations:</li> <li>Ten Minutes Between First and Second Burns</li> <li>Several Hours Between Second and Third Burns</li> <li>Tested To 290°R (-170°F) With Successful Restart</li> </ul> </li> </ul>	
	<ul> <li>Temperature Differentials Create Start Lags         <ul> <li>Centaur Specification = 700 ms ∆</li> <li>Colder Engine Slower To Start</li> <li>Controllability Impacted</li> <li>Thermal Control Proven (Passive/Active)</li> <li>Thermal Control Systems</li> <li>Centaur Roll Providing Uniform Heating (In-Flight Option Only)</li> </ul> </li> </ul>	

Single System Risks Are Mitigated By Design, Operation or Margin

MARTIN MARIETTA

013






たいたい

#### MARTIN MARIETTA

**014** JH920429-02A



MARTIN MARIETTA

015

#### NASA LeRC ASAO STUDY

MAY 6, 1992

#### **"BENEFITS AND TECHNOLOGY READINESS FOR USING CRYOGENIC INSTEAD OF STORABLE PROPELLANTS FOR RETURN MISSION FROM MOON"**

DAVID W. PLACHTA PHONE (216)433-6366

Z 9 2 Į ce CC co 5 O 1 È L

522

BS

# The FLO Mission is Different Than Previous SEI Mission, and Has Different Cryo Requirements

Launch Strategy: Single launch, no LEO assembly, 4 day trip to moon.

• Zero-G pressure control and thermal control cryo issues are greatly minimized


Lunar Stay Time: 45-day maximum stay, and longer stays for future missions.

- Analysis, using actual test data, shows 34 layers of MLI on  $O_2$  and  $H_2$  tanks is adequate.
- Cryo insulation systems are evolvable to longer missions.

Lunar Direct Strategy: No rendezvous with orbiting vehicle, like Apollo.

• More ascent stage propulsion is required.

FLO cryo requirements are less demanding than previous lunar missions, e.g., 90-day study.



524

;/

#### $N\Lambda S\Lambda =$ LEWIS RESEARCH CENTER -TWO CRYO THERMAL CONTROL SYSTEM'S STUDIED FOR FLO WEIGHTED BOIL-INSULATION SYSTEM **HEAT FLUX** DENSITY **OFF RATES** (%/mo) 0.36 Btu/hr/ft<sup>2</sup>, FROM K-SITE TEST DATA DURING SIMULATED LUNAR SUNRISE, 175 ft<sup>3</sup> TANK 34 LAYER MLI SYSTEM $0.3 \, 1b/ft^2$ 4.8% 0.12 Btu/hr/ft<sup>2</sup>, FROM EXTRAPOLATED $0.6 \, lb/ft^2$ , OPTIMIZED (TOTAL INS. WT. AND 1.3% **BOIL-OFF WT. MINIMIZED)** TEST DATA AND LOCKHEED EQN. FOR H<sub>2</sub> H, TANK TANK 2" MLI ON H<sub>2</sub> TANK 0.08 Btu/hr/ft<sup>2</sup>, FROM SAME EXTRAPOLATED DATA, FOR 0<sub>2</sub> TANK $0.9 \ 1b/ft^2$ , 3" MLI ON 0, TANK 0, TANK

HEAT FLUX ESTIMATES ARE BASED ON UNIFORM HEAT FLUX. PACKAGING OF TANKS WILL RESULT IN LOWER AVERAGE HEAT FLUX.

## ANALYSIS OF TANK BOIL-OFF RATES

- ALL CRYO MISSION ASCENT STAGE PROPELLANT LOAD IS 12.7 MT, OR 28,000 LBS. ASSUMING A 5.3:1 MIXTURE RATIO, THEN
  - 4435 LBS. OF HYDROGEN, 1025 FT<sup>3</sup>, AND 491 FT<sup>2</sup> SURFACE AREA
  - 23500 LBS. OF OXYGEN, 330 FT<sup>3</sup>, AND 230 FT<sup>2</sup> SURFACE AREA

BOIL-OFF RATE IS =  $q \times A / h$ 

q= HEAT FLUX A= SURFACE AREA OF TANK h= HEAT OF VAPORIZATION

HEAT FLUX, Btu/hr/ft <sup>2</sup>	H <sub>z</sub> , LB/MO	%/MONTH	0 <sub>2</sub> , LB/MO	0 <sub>2</sub> , %/MONTH	WEIGHT AVERAGED, %/MONTH
0.36	680	15.4%	660	2.8	4.8%
$H_2 0.12 0_2 0.08$	227	5.1%	141	0.6%	1.3%

#### **CRYOGENIC FLUID SYSTEMS**

## **MISSION ANALYSIS GROUND RULES**

PHASE	STAGE	Δ V (M/S)	INERT MASS (MT)	
TLI	1	3200	0	
LOI	II	892	12.2	
LD	II	1830	12.2	
LA	III	1810	5.22*	
TEI	III	848	5.22*	

- ISP 444
- NO LEO ASSEMBLY. 1 DAY LEO, 3 DAY COAST, 1 DAY IN LUNAR ORBIT
- 5 MT PAYLOAD DELIVERED TO LUNAR SURFACE
- 7.2 MT CREW CAB

 $N\Lambda S\Lambda ==$ 

- 2% PROPELLANT RESERVE ON EACH STAGE- LeRC INPUT
- 2% PER MONTH BOIL-OFF RATE FOR PHASES OTHER THAN LUNAR STAY- LeRC INPUT
- STORABLE ASCENT STAGE COMPARISON WAS BASED ON THE FOLLOWING:
  - **ISP** = 320
  - LD INERT MASS = 12.2 MT
  - LA INERT MASS = 5.22 MT
- ALL MASSES, DELTA V'S, AND Isp'S FROM JSC.
  - \* MASS OF OPTIMIZED MLI SYSTEM ASSUMED TO BE INCLUDED


# MLI FOR CRYOGENIC STORAGE

- THERMAL CONTROL OF CRYOGENIC TANKAGE FOR FLO WILL REQUIRE USE OF MLI
- MLI TECHNOLOGY IS IN PLACE FOR RELATIVELY SHORT MISSIONS ANTICIPATED FOR FLO (< FEW MONTHS). NO SHOW STOPPERS.
  - MEASURED PERFORMANCE IS ADEQUATE
  - EXTENSIVE EXPERIENCE EXISTS ON INSTALLING AND HANDLING MLI
  - METHODS OF APPLYING MLI TO WET-LAUNCHED LH<sub>2</sub> TANKS HAVE BEEN INVESTIGATED AND MLI CAN SURVIVE LAUNCH LOADS AND RAPID DECOMPRESSION DURING ASCENT
  - MLI SYSTEM SELECTED WILL ONLY REQUIRE SOME MINOR ENGINEERING DESIGN TO OPTIMIZE FOR GIVEN MISSION
- THERMAL CONTROL FOR LONGER MISSIONS (MONTHS TO YEARS) WILL REQUIRE:
  - EXTENSION OF MLI DATA BASE TO THICKER SYSTEMS FOR A RANGE OF BOUNDARY TEMPERATURES
  - THE ADDITIONAL USE OF OTHER THERMAL CONTROL TECHNIQUES SUCH AS VAPOR-COOLED SHIELDS, REFRIGERATION SYSTEMS, SHADOW SHIELDING, ETC.

## THERMAL PERFORMANCE OF MLI HAS BEEN DEMONSTRATED FOR LH<sub>2</sub> TANKAGE

MOST MLI DATA IS FOR A HOTSIDE BOUNDARY TEMPERATURE OF 530 R

#### LH<sub>2</sub> BOIL-OFF AS A , FUNCTION OF HEAT TRANSFER RATE & SEI TANK SIZES



HEAT TRANSFER RATE, BIU/HR F12

#### MLI HANDLING/INSTALLATION DEMONSTRATED FOR LH<sub>2</sub> TANKAGE (LIST NOT INCLUSIVE)

- LERC
  - ►  $175 \text{ FT}^3 \text{ TANK}$ 34 LAYERS (DAM & SILK NET SPACERS) REPLACEABLE SYSTEM ► 180 FT<sup>3</sup> TANK 30, 40, 50, 60 LAYERS (DAM & DEXIGLASS SPACERS) 11
  - 50 FT<sup>3</sup> TANK 34 LAYERS (DAM & SILK NET SPACERS) ►
  - 19 FT<sup>3</sup> TANK 18 LAYERS (SEMI-SYSTEM CO, FILLED)
- **MSFC** 
  - 34 FT<sup>3</sup> TANK
     450 FT<sup>3</sup> CALORIMETER
     15 LAYERS (DAM & DACRON NET) OVER FOAM SUBSTRATE
     70 LAYERS (DAM & DACRON NET) MACDAC SYSTEM
- GDC
  - 7.2  $FT^3$  TANK 128 LAYERS (~4" SUPERFLOC) ▶


  - 175 FT<sup>3</sup> TANK
     1266 FT<sup>3</sup> D1-T FLIGHT TANK
     1892 FT<sup>3</sup> SHUTTLE/G-PRIME TANK
     44 LAYERS (SUPERFLOC)
     3 TO 46 LAYERS (HE PURGED)
     3 LAYERS OVER 1.5" FOAM (HE PURGED)
- LOCKHEED
  - ▶ 180 F<sup>3</sup> TANK 30, 40, 50, 60 LAYERS (DAM & DEXIGLASS) FOR TESTS AT LERC
- OTHERS

MOST AEROSPACE COMPANIES HAVE DIRECT MLI EXPERIENCE THAT HAS BEEN OR COULD BE APPLIED TO LH, TANKAGE


> EXTENSIVE EXPERIENCE EXISTS IN HANDLING AND INSTALLING MLI SYSTEMS



Ņ



87 INCH DIAMETER MLI INSULATED LH2 TANK TESTED AT NASA LERC K-SITE FOR BOTH NEAR-EARTH, LUNAR SURFACE AND DEEP SPACE CONDITIONS



CENTAUR VEHICLES ARE ONLY FLIGHT APPLICATION OF MLI TO LIGHT-WEIGHT CRYOGENIC TANKAGE




Figure 3. - Ground-hold system and helium gas purge flow paths.





Figure 4. - Insulation blankets.

180 FT<sup>3</sup> LH<sub>2</sub> TANK TESTED AT LERC --30, 40, 50 AND 60 LAYER MLI SYSTEMS (DAM AND DEXIGLASS SPACERS)



**Space Flight Systems Directorate** 



### **GROUND PERFORMANCE AND ASCENT DEPRESSURIZATION EFFECTS** ON MLI HAVE BEEN DEMONSTRATED

LERC

- 50 FT<sup>3</sup> LH<sub>2</sub> TANK WITH 34 LAYERS MLI (FLIGHTWEIGHT SYSTEM)
  - SPACE TUG LAUNCH PRESSURE PROFILE
  - NO SIGNIFICANT THERMAL OR MECHANICAL DEGRATION AFTER 19 RAPID DEPRESSURIZATION CYCLES (12% DEGRADATION IN ON-ORBIT PERFORMANCE)
  - GROUND HOLD WITH HE PURGE < 200 BTU/HR  $FT^2$
- **30 INCH LH, CYLINDRICAL CALORIMETER** 
  - SIMULATED SATURN V PRESSURE PROFILE
  - TESTED 3 MLI CONCEPTS WITH NO DAMAGE NOTED
  - GROUND HOLD WITH HE PURGE GAVE:

    - 55 BTU/HR FT<sup>2</sup> WITH 30 LAYERS MLI AND 0.75" OF FOAM 115 BTU/HR FT<sup>2</sup> WITH 30 LAYERS MLI AND 0.75" FIBERGLASS SUBSTRATE
    - 170 BTU/HR FT<sup>2</sup> WITH 30 LAYERS MLI AND 0.5" FIBERGLASS SUBSTRATE
    - NO MEASURABLE DEGRADATION

**MSFC** 

- 450 FT<sup>3</sup> LH<sub>2</sub> CALORIMETER WITH 70 LAYERS (MLI)
  - SIMULATED SATURN V PRESSURE PROFILE
  - SOME THERMAL DEGRADATION SUBSEQUENT TO DEPRESSURIZATION
    - $(.13 \text{ TO } .195 \text{ BTU/HR FT}^2 \text{ SPACE PERFORMANCE})$

## GROUND PERFORMANCE AND ASCENT DEPRESSURIZATION EFFECTS ON MLI HAVE BEEN DEMONSTRATED

#### GDC

- 7.2  $FT^3 LH_2$  Tank (25" Dia.) With 128 Layers of MLI (~4")
  - INSULATION SYSTEM PUMPED TO 1 TORR IN 70 SECONDS (MORE SEVERE THAN SATURN V)
  - NO DISCERNABLE DAMAGE MECHANICALLY OR THERMALLY
  - GROUND HOLD WITH HE PURGE GAVE 50 BTU/HR FT<sup>2</sup>
- DEVELOPMENTAL TESTS FOR CENTAUR USING 9.5" DIA. LH<sub>2</sub> Cyl. Calorimeter
  - TESTED ALL MLI CONCEPTS USED UNDER SIMULATED LAUNCH-ASCENT
- FULL SCALE GROUND HOLD TESTS OF FLIGHT QUALIFIED SHUTTLE/CENTAUR G-PRIME
  - THREE LAYEERS MLI OVER 1.5 INCH FOAM
  - Ground Hold With He Purge < 100 Btu/hr  $Ft^2$  .
- 175 Ft<sup>3</sup> LH<sub>2</sub> Tank With 44 Layers MLI (Flightweight)
  - 100 FLIGHT CYCLES (RAPID DEPRESSURIZATION)
  - 26% Degradation After 50 Cycles



## GROUND PERFORMANCE AND ASCENT DEPRESSURIZATION EFFECTS ON MLI HAVE BEEN DEMONSTRATED

#### BALL AEROSPACE

- 150 LAYERS MLI (~3") MOUNTED ON 52 INCH DIA. TEST PLATE
  - SIMULATED STS CARGO BAY PRESSURE PROFILE
  - INSULATION SEALED ON 52" CIRCUMFERENCE TO FORCE EVACUATION THROUGH ONE LINEAR SEAM
  - NO DISCERNABLE DAMAGE TO INSULATION OR SEAM AREA
  - No THERMAL VERIFICATION
  - CONCLUSION: TESTING DEMONSTRATED EDGE PUMPING ADEQUATE

#### LOCKHEED

- RAPID EVACUATION TESTS ON 27" DIA. MLI SAMPLES TO VERIFY ANALYSIS
  - SATURN V PRESSURIZATION PROFILE
  - 20 TO 80 LAYER SAMPLES
  - Both He and  $N_2$  Purges
  - GOOD CORRELATION WITH ANALYSIS

#### CONSIDERABLE EXPERIENCE EXISTS IN DESIGNING WET-LAUNCHED MLI SYSTEMS FOR LH2 TANKS EXPOSED TO LAUNCH PRESSURE PROFILES

# Reasons for Changing Ascent Stage Propulsion Baseline

- Using a cryo ascent stage to perform FLO yields-
  - At least a 15% reduction in TLI mass--using identical weights for the storable return case and the cryogenic return study.
  - The IMLEO savings would be 25 to 30%, enabling a 200 mt class launch vehicle.
- We know how to do this how to insulate the tank and what the performance is.
  - The technical issues for FLO have been resolved by ground based testing.

# Reasons for Changing Ascent Stage Propulsion Baseline (cont.)

- An MLI system for the baselined cryo descent stage is needed for the 3-4 day trip to the moon-
  - Development work is needed for the descent stage MLI system, of perhaps 15 to 20 MLI layers.
  - The ascent stage MLI system will have more layers, but the design and manufacturing utilizes same technology.
- These MLI systems are evolvable to longer or more ambitious lunar missions and for Mars missions, with some technology development.
- LeRC and MSFC have planned test programs to test and study MLI systems for FLO and other SEI missions.

Is there any reason not to do this?




NASA/UA SERC


TELEROBOTICS LABORATORY

# NASA/UNIVERSITY OF ARIZONA SPACE ENGINEERING RESEARCH CENTER FOR UTILIZATION OF LOCAL PLANETARY RESOURCES

## **PROPOSED LUNAR MISSIONS**

- 65 kg Artemis payload: ISMU Pilot Plant
- 65 kg Artemis payload: Lunar Resource Prospector
- 200 kg Artemis payload: Integrated Oxygen Production Plant






# **ISMU PILOT PLANT FOR OXYGEN PRODUCTION**

NASA/UNIVERSITY OF ARIZONA SPACE ENGINEERING RESEARCH CENTER FOR UTILIZATION OF LOCAL PLANETARY RESOURCES (Contact: Ramohalli, 602-322-2304)

PRESENTATION ON FEBRUARY 4-6, 1992 TO: Workshop on Early Robotic Missions to the Moon Lunar and Planetary Institute, Houston, Texas





# TASK DECOMPOSITION INTEGRATED OXYGEN PRODUCTION

# • SOIL SAMPLE ACQUISITION

- move arm and gather soil
- deposit in crucible through sieve
- **REACTOR OPERATION** 
  - mix solid carbon powder with soil
  - insert crucible at the focus
  - control heating (mirror adjustment)
  - measure/identify gases
  - remove and store residue (tiles from slag)
- DATA MANAGEMENT
  - obtain measurements and store data
- TELEMETRY AND UPLOAD
  - adjust antenna/transmit data
  - upload code and data

# COMMON LUNAR LANDER





# A GENERAL-PURPOSE INTELLIGENT VEHICLE SYSTEM AS LUNAR RESOURCE PROSPECTOR

NASA/UNIVERSITY OF ARIZONA SPACE ENGINEERING RESEARCH CENTER FOR UTILIZATION OF LOCAL PLANETARY RESOURCES (Contact: Schooley, 602-621-2352)

## NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY UNITED STATES DEPARTMENT OF COMMERCE

PRESENTATION ON APRIL 29-30, 1992 TO: Lunar Rover/Mobility Workshop Lunar and Planetary Institute, Houston, Texas



# Goal:

•

To develop an Intelligent Robotic Vehicle System (IRVS) based on the NIST SPIDER Robot for general-purpose services of Lunar and/or Martian missions.


OT


ARIZONA

# Advantages of the SPIDER Structure:

- A powerful platform with large working volume to accommodate the execution of diversified tasks
- Exceptionally high force to mass ratio
- Compact packaging for transport
- Mobility, dexterity, versatility, flexibility of scale, and ease of reconfiguration

Robot Systems Division





National Institute of Standards and Technology

Robot Systems Division



**SPIDER AND HORSE represent a new approach to manipulation and locomotion** 

Structure is lightest and strongest possible

**Configuration is ideal for mobility, soil sampling,** & instrument deployment

**Concept is simple and control technology is ready** 



## Phase I IRVS Task

- I Geophysical Instrument Deployment
  - Collect visual information
  - Navigate to the inspection site
  - Arm deploys instrument (e.g., seismometer) on the ground
- II Sample Collection and Analysis
  - Arm attaches a sample collection tool (e.g., bucket)
  - Arm collects soil sample
  - Arm places the sample into the assay instrument (e.g., gamma ray spectrometer)
- **III Site Evaluation** 
  - Statistical analysis
  - Information fusion
  - Mineralogical site classification database and geological map generation



## **INTEGRATED OXYGEN PRODUCTION PLANT**

NASA/UNIVERSITY OF ARIZONA SPACE ENGINEERING RESEARCH CENTER FOR UTILIZATION OF LOCAL PLANETARY RESOURCES (Contact: Ramohalli, 602-322-2304)

#### NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY UNITED STATES DEPARTMENT OF COMMERCE

PRESENTATION ON APRIL 29-30, 1992 TO: Lunar Rover/Mobility Workshop Lunar and Planetary Institute, Houston, Texas



NASA/UA SERC

TELEROBOTICS LABORATORY

## **INTEGRATED OXYGEN PRODUCTION PLANT**

A mobile Stewart platform carrying an on-board ISMU plant with associated tools and instruments.

#### TASKS:

- Prospecting and Resource Assessment
- Mining and Beneficiation
- Plant Services and Oxygen Production
- Identification of Useful Byproducts


**EQUIPMENT:** 

- Analytical Instruments
- Assorted Tools
- Beneficiation Machines
- Production Plant
- Vehicle Infrastructure

## Phase II : Mining and Beneficiation

-----


.




#### Side View of NIST Task Platform

Phase III: General Services to ISMU Plants

\_\_\_\_\_



Top View of the NIST Work Platform



## FIRST LUNAR OUTPOST (FLO) CREW MODULE THERMAL PROTECTION DESIGN SENSITIVITY


#### **STUDY OBJECTIVES**

- ASSESS EFFECTS OF VEHICLE SIZE ON AEROTHERMODYNAMIC ENVIRONMENT AND THERMAL PROTECTION SYSTEM (TPS) WEIGHT
- ASSESS EFFECTS OF LUNAR-RETURN STRATEGIES ON AEROTHERMODYNAMIC ENVIRONMENT AND TPS WEIGHT
- ASSESS WEIGHT PENALTY FOR COMMON TPS DESIGN FOR ALL LUNAR-RETURN STRATEGIES


#### STUDY GUIDELINES

- APOLLO COMMAND MODULE VEHICLE CONFIGURATION FOR SCALES OF 1.0, 1.5, 2.5
- LUNAR-RETURN STRATEGIES
  - DIRECT-ENTRY (MODIFIED APOLLO GUIDANCE)
  - AERO-CAPTURE (AFE GUIDANCE) AND LOW-EARTH ORBIT ENTRY (SHUTTLE GUIDANCE)
- AEROTHERMODYNAMICS
   APOLLO RADIATIVE AND CONVECTIVE (LAMINAR) HEATING DISTRIBUTIONS
- TPS MATERIALS
  - FLIGHT CERTIFIED MATERIALS
  - MODIFIED APOLLO TPS SIZING METHOD

#### Sketch of TPS Weight Calculation Process





#### VEHICLE AND TRAJECTORY DESIGN ASSUMPTIONS





	TRA	AERODYNAMIC CRITERIA		
	MODE OF ENTRY	INERTIAL VELOCITY (KM/SEC)	FLIGHT PATH ANGLE (DEGS.)	ANGLE-OF-ATTACK = 20 DEGS.
	DIRECT-ENTRY	11.0	-6.6	C <sub>D</sub> = 1.2906
	AERO-CAPTURE	11.0	-5.2	$C_{L} = 0.3867$
_	LOW-EARTH ORBIT ENTRY	7.9	-1.5	L/D = 0.3
778	APOLLO 4 (Alpha=24 <sup>0</sup> )	11.2	-6.95	

ALTITUDE AS A FUNCTION OF TIME FOR 1.5-SCALE APOLLO VEHICLE FOR AEROCAPTURE, DIRECT ENTRY, AND A/C-LEO ENTRY LUNAR MISSIONS
















**AERO-CAPTURE TRAJECTORY** 

e · · · · · · · ·

#### PEAK HEATING RATES TO SCALE APOLLO VEHICLES




#### HEAT LOADS FOR SCALE APOLLO VEHICLE AT PEAK HEATING LOCATION




562

÷


PEAK HEATING RATES AS A FUNCTION OF VEHICLE DIAMETER FOR LUNAR RETURN DIRECT ENTRY









#### **Thermal Protection System**









Comparison of the TPS Unit Weights vs. Heat Load for the 1.5 Scale Apollo CM for the Aerocapture-5 Orbit-Entry



vs. Heat Load for the 1.5 Scale Apollo CM



TPS Weight Penalty as a Function of Ballistic Coefficient



TPS Weight Penalty as a Function of Vehicle Size

. : \*

#### CONCLUSIONS

#### • VEHICLE SIZE SENSITIVITY

ப

- PEAK HEATING RATES NOT STRONG FUNCTION OF VEHICLE SIZE BUT LARGER VEHICLES HAVE RELATIVELY LOWER HEAT LOADS.
- TPS WEIGHT PENALTY NOT STRONG FUNCTION OF VEHICLE SIZE.
- LUNAR-RETURN STRATEGY SENSITIVITY
  - DIRECT-ENTRY HAS SIGNIFICANTLY HIGHER HEATING RATES BUT AERO-CAPTURE LUNAR-RETURN HAS HIGHER HEAT LOADS.
  - DIRECT-ENTRY HAS LEAST TPS WEIGHT PENALTY.
  - AEROCAPTURE PLUS LOW-EARTH ORBIT ENTRY RESULTS IN AN 10- 30% (65-208 KGS) INCREASE IN TPS WEIGHT OVER THE DIRECT-ENTRY CASE FOR THE 1.5 SCALE VEHICLE.
- TPS WEIGHT PENALTY FOR A COMMON TPS DESIGN FOR ALL LUNAR-RETURN STRATEGIES IS APPROXIMATELY 7.5% FOR 1.5 SCALE VEHICLE.
- PRESENT TPS WEIGHT (SCALE=1.0) 50% LESS THAN ORIGINAL APOLLO DESIGN DUE TO FLIGHT EXPERIENCE AND TO IMPROVED MATERIALS.

#### FUTURE EFFORTS

- IMPROVE TRAJECTORY GUIDANCE ALGORITHMS.
- UTILIZE IMPROVED METHODS FOR PREDICTING HEATING ENVIRONMENTS.
- EVALUATE BENEFITS OF ADVANCED MATERIALS.

Presented to

#### Exploration Programs Office Technical Interchange Meeting

by


**Ralph Eberhardt** 

May 6, 1992




MARTIN MARIETTA


B-11





MARTIN MARIETTA



MARTIN MARIETTA







5


i

.

Martin Marietta Contacts for SHOM:

Ben Clark	(303)	971-9007
Carolyn Cooley	(303)	971-9375
Bob Boyd	(303)	971-9069
Rohan Žaveri	(303)	971-9369

MARTIN MARIETTA



۰,

## Earth Land Landing Alternatives

Lunar Transportation System

#### Presented to the 3rd Space Exploration Initiative Technical Interchange

6 May 1992

N92-33347

NASA JSC EG3 (713) 483-4629



#### What is the LSWG?

# The Landing Systems Working Group is a multi-disciplinary team made up of Engineering Directorate personnel organized to plan landing systems acitivity for future NASA missions.

#### **Objectives**

- Develop the land landing option so that it is a viable trade option for future NASA missions.
- Provide NASA programs with solid technical support in the landing systems area.
- Develop the technical staff.
- Advance the state of landing systems technology to apply to future NASA missions.


Johnson Space Center – Houston, Texas



Study ProcessNavigation, Control & Aeronautics Division<br/>Aeroscience BranchRobert MeyersonMay 1992

٠,

Two Phase Process





- Needs identified from interviews with Program, Engineering User representatives at NASA JSC.
  - Interviews performed in November 1991

Inhouse expertise and technology base Technology assessment of outside efforts Focal point for landing systems issues Perform entry through landing flight tests

> Simple, Affordable, Reliable, and Safe space vehicles Automatic/Autonomous Landing Capability Minimize crew input and training workload Assurance of vehicle readiness Reduce system cost

#### Focus on critical technical areas

Descent - Reduce footprint, gliding chutes Avionics - Automatic landing, DMS, Sensors Impact Attenuation - Retrorockets, no tumbling

> Plan Facility Development Take advantage of existing facilities

Johnson Space Center – Houston, Texas



Program Requirements

Navigation, Control & Aeronautics Division Aeroscience Branch

**Robert Meyerson** 


May 1992


## GOAL - "Develop reliable manned land landing capability"


- Use 8-crew SCRAM concept as baseline vehicle for concept evaluation
- Land landing at a pre-selected, unprepared landing zone (with water backup)
  - Immediate post-landing access
  - Landing site size = 5 mile diameter nominal (10 mile dia emergency)
  - No ground preparation
  - No navigation aids at the site
  - Weather limits from ACRV SEDB (90th percentile nominal, 99th percentile for emergency)
  - Service module jettisoned during entry
- No tumbling
- Physiological constraints = +/- 15 Gx, +/- 10 Gy, +8/-8.5 Gz Nominal

+40/-30 Gx, +/-20 Gy, +25,-20 Gz Emergency


- Night landing capability
- Single fault tolerance
- Fully automatic operations
- 15,000 lb landed weight
- Consider reusability in design








### **Option 4 - "Gemini Soft Lander/Apollo Land Lander"**





Johnson Space Center – Houston, Texas



<b>Development of Activities Plan</b>	Navigation, Control & Aeronautics Division Aeroscience Branch	
	Robert Meyerson	May 1992

- Evaluation of the 5 landing options will produce a list of technical and system integration "holes"
  - Does the system meet the requirements?
  - Can we design/analyze/test the system today?
- These "holes" will be prioritized based on a criteria to include the following:
  - Technology/Development risk and cost
  - Applicability to future NASA programs
  - Performance Improvement
- Ongoing programs will be identified which are addressing these "holes"
- A development plan will be produced to address remaining "holes" including the following:
  - Proposed activity
  - Performing organization
  - Requirement/Justification
  - Schedule
  - Cost estimate
  - Impact if not completed



# Parachute/Cluster Opening Loads - Major design issue on Apollo ELS

- **Orientation System Implementation** Where? How?
- **Reduce Landing Footprint** Improve guidance through entry. Vehicle based wind sensing would help.

,'

**Dynamics of Ground Contact and Energy Mitigation** - Soil modelling. Impact performance prediction. Effects of shape on impact.

Johnson Space Center – Houston, Texas



Issues with Gliding Systems	Navigation, Control & Aeronautics Division Aeroscience Branch	
	Robert Meyerson	May 1992

Inflation - Asymetry about one axis makes conventional loads management difficult.

**Reliability -** Large use database on personnel size systems. Never demonstrated in the 15,000 - 20,000 lb size. Not scalable. How do we deal with redundancy?

**High Horizontal Velocity at TD** - Higher wing loading required for weight efficiency.

Landing Flare Maneuver - Maneuver requires precise timing. Autonomous system never demonstrated at any scale.

**Reduced Knowledge Base** - Wealth of knowledge developed during Apollo program is no longer available.



- Low Altitude Retrorocket System (U.S. Army Natick/AAI Corp.)
  - Air Delivery system for unmanned Army payloads up to 60,000 lbs
  - Designed for deployment at 250 KEAS and 300 ft AGL
  - Includes riser mounted rocket, laser altitude sensor, processor
- F-111 Crew Escape Module (U.S. Air Force)
  - Recertification of parachutes and airbags
  - Impact testing performed at NASA Langley IDRF (Fall 1991)
  - Airdrop testing at NAWC China Lake (Summer 1992)
- Advanced Recovery Systems Program (NASA MSFC/U.S. Army)
  - Demonstrate the capability to soft land, in a precisely controlled manner, a large object selected to simulate a launch component, such as P/AM.
  - Several tests performed with W < 13,600 lbs and S = 3600 sq ft.
  - Phase II Complete with no current plans to fund Phase III
- Dryden Autoland Experiments (Joint NASA DFRF/JSC)
  - Develop and demonstrate an autonomous landing flare maneuver using a simulated spacecraft with a gliding parachute and GPS
  - Tests to begin in June 1992

Johnson Space Center – Houston, Texas




Summary & Recommendations	Navigation, Control & Aeronautics Division Aeroscience Branch	
	Robert Meyerson	May 1992

- Landing Systems knowledge base is being developed
- Issues with land landing systems are being identified for a variety of parachute system options
- There are few **technology** issues with a conventional parachute with retrorocket system
  - This may not meet the system requirements
- Gliding parachutes may provide the most operational flexiblity but also create large technology risks
  - Reliability will always be an issue with current gliding concepts
- Land landing CAN be done

# **RECOMMENDATION:** Address the following issues...


- Landing Footprint/Site Selection
- Ground impact dynamics
- Gliding parachute reliability/redundancy



The pneumatically erected rigid habitat concept consists of a structure based on an overexpanded metal bellows. The structure is reinforced with rings and stringers in typical airframe construction technique. The achievable expansion ratio is easily five to one thus allowing a small volume during launch. An integrated micrometeorite shield and MLI consists of an overexpanded titanium honeycomb. Each module consists of four sections each separated by pressure bulkheads and airlocks. The module also has a self contained life support system. The module is designed so that it can be chained to other modules to construct a full base station.

The basic concept of a pneumatically erected rigid habitat incorporates the advantages of both the inflatable and rigid structures. The inflatable approach allows the number of launches needed to orbit a mission to be greatly reduced. The heavy launch vehicles in use can orbit a full payload volume worth of collapsed hardware, thus reducing the number of launches needed by a factor of 6x, and the cost proportionately. The prime disadvantage to this approach is problems with high maintainability times and the need for frequent repairs of inflatable structures. The aluminum rigid structure is extremely durable and low maintenance but has an extremely large launch volume. The pneumatically erected rigid habitat thus addresses the launch volume and provides a durable low maintenance structure.

The pneumatically erected rigid habitat is built up of standard aluminum construction techniques using rings and stringers, incorporating normal rip stop safety protection, but provides a structure that can be erected from a compressed shape. The structure would be built in the collapsed form, much as a set of metal bellows. During the deployment the structure would be over pressurized internally, yielding the bellow structure radially into a standard tank or fuselage structure. Because of the yielding which takes place, the process is not reversible, and the same strength and other structural properties are achieved as if the structure was fabricated in the normal manner. Figure 1 shows the collapsed launch configuration, the non extended configuration on the lunar surface and erected structure.



### TRACOR

#### **Key Features**

The key features of the concept, shown in figure 1 are: The multiple sections separated by airlocks for redundant depressurization protection. The expanded transfer rooms, allowing easy, full suit transfer. The expanded floor joists with removable floor panels, allowing easy access below decks and allowing a rigid floor to be erected. The elliptical pressure bulkheads which isolate each section and provide stowage space and attachment for equipment and the floor panels during launch. The inner living wall, which gives a redundant pressure wall, and provides protection to the structural wall from inadvertent puncture from within. The expanded titanium honeycomb micrometeor shield and MLI which provides a light weight "bring from home" protection that deploys autonomously during the habitat erection. To provide radiation protection a smaller expandable section is shown which can be covered with lunar soil. This would provide protection for the crew during periods of high radiation, but would not require bringing a lunar bulldozer. The dry weight of the concept is 3450 pounds per module (four sections) with no equipment, life support systems or tankage included. A total of six sections could be put into low earth orbit using a Titan IV D, with weight capacity for the modules, life support systems, tankage, and some modest equipment.

#### **Erection Details**

The primary design driver in developing the Pneumatically Erected Rigid Habitat (PERH), is forming the collapsed structure in a smooth bellow like fashion with no sharp bends, and maintain this no sharp bend or kink configuration throughout the erection process. The other design driver is to limit the elongation of any portion of the structure in yield to 50% of the allowable for the materials being used.

By using a bellows type structure shown in Figure 2, with rings on the outside of alternate crests or fold and a triangular stringer arrangement, the erection process takes place in three distinct well controlled steps. In the first step, at low pressure, the inflated habitat section elongates axially. During this stage stresses in the rings are negligible, stresses in the skin are below yield, but the stringers are yielding into a near straight condition. During the second stage of inflation the skin begins to yield outward, allowing the stringers to carry almost all the axial load of inflation and yielding them into near final condition. The last stage of inflation the skin is yielded and continues to bulge outward between the rings and stringers in diaphragm loading until the diaphragm deflection lowers the skin stress below yield. This process is thus self regulating and fairly insensitive to either inflation pressure tolerances or variations in material properties from one lot to the next. After the final inflation stage the pressure is lowered back to normal inhabitation pressure. The excess gas is use to inflate the next section of the habitat.

#### **Erection Details, Pneumatically Erected Rigid Habitat** PATENT PENDING **STOWED BELLOW EXTENDED OUTER SKIN YIELDED ONE SECTION AT A TIME** (Micrometeorite Shield Not Shown) Stowage Space During (Micrometeorite Shield Not Shown) 24" Section Launch for Equipment and Floor Panels Pressure-Bulkhead Airlock and Collapsed **Transfer Room** Collapsed Floor Joists, Aluminum **Micrometeor Shields Skins Yielded** Extendable Vent and in Diaphram Loading **Utility Lines** Pressure Bulkhead Stowed 8.7 Fabric Backup or Living Wall Expanded Deployed 6.3 Material: .0007" Titanium Foil Skin and Stringers in/ 7.0" Load Rings **Bellow Configuration MICROMETEOROID SHIELD** .787 Typical DEPLOYMENT

RACOR

Figure 2.

. i ·

TRACOR

#### **Conclusions**

- -


The expanded metal structure of the pneumatically erected rigid habitat and its micrometeor shield allows a large inhabitable structure to be transported to the moon with a minimum launch cost. The structure draws upon the excellent flight experience with aluminum structures, without paying a large cost penalty or being forced to use excessively compact living quarters.

1426 C 14 Statistic 14

# PLUME INDUCED ENVIRONMENTS ON FUTURE LUNAR MISSION VEHICLES

Bill Rochelle and Ruston Hughes Lockheed Engineering & Sciences Co., Houston, TX

Steve Fitzgerald NASA/Johnson Space Center, Houston, TX



SEI 3RD TECHNICAL INTERCHANGE MEETING MAY 5-6, 1992 HOUSTON, TX Z

540-

## **OVERVIEW OF PRESENTATION**

- Objective: To identify potential plume heating/impingement problem areas on vehicles used for future lunar missions
- Basis of Comparison with Lunar Module plume investigations performed during 1968 1971
- New Vehicles
   Considered:
- Common Lunar Lander (Artemis)
  First Lunar Outpost (FLO)
  - Cargo Lander
     Crew Lander

- Engines Considered:
- Reaction Control System (RCS)
- Lunar Descent Stage
- Lunar Ascent Stage
- Plume Technology:
- Available Computer Codes
- Available Test Facilities

#### LUNAR MODULE PLUME INDUCED ENVIRONMENT EFFECTS

## A. <u>Vehicle Design Issues</u>

- RCS engine plume impingement on sides and base of LM (installation of plume deflector or "coal chute")
- Descent engine plume impingement to LM landing gear
- Descent engine plume soil erosion on lunar surface
- Descent engine high base pressure during touchdown
- Ascent engine plume impingement on Early Apollo Scientific Experiment Package (EASEP)
- Ascent engine plume impingement on Apollo Lunar Scientific Experiment Package (ALSEP)
- Ascent engine plume impingement on top of LM descent stage

#### B. Ground Testing Used for Vehicle Design


- Full scale ground tests of RCS engine plume in JSC TTA and Chamber A facilities
- Scale model ground tests of descent stage engine plume at Grumman detonation facility

ASIG-113-18334 FIG. 8 CLOSE-UP OF LM RCS PLUME DEFLECTOR FOR APOLLO 16






### s-投始。 FIG. 10 LM ASCENT PLUME IMPINGEMENT ON DESCENT STAGE FOR APOLLO 16



# TABLE I. SUMMARY OF CLL PLUME HEATING/IMPINGEMENT EFFECTS


<b>Engine</b>	<u>Vehicle</u>	Mission Phase	Plume Effect
RCS	Lander	TLI & Descent	Impingement on bottom of lander
			Impingement on landing gear
Descent	Lander	TLI	Impingement on casing of STAR 48B SRM
		TLI & Descent	Impingement on landing gear
			Radiation to base
		Descent	Soil erosion on base and landing gear
N N			High base pressure at touchdown

#### CLL STAR 48B SRM AND PAYLOAD SHROUD




#### RIGHT SIDE VIEW OF CLL VEHICLE

.



.

#### BOTTOM VIEW OF CLL VEHICLE




606

Ļ

## TABLE II. SUMMARY OF FLO PLUME HEATING/IMPINGEMENT EFFECTS

Engine	<u>Vehicle</u>	Mission Phase	Plume Effect
RCS	Cargo Lande Cargo Landei		Impingement on habitat module Impingement on sides and base
	Crew Lander	On-orbit	Impingement on sides and base
	Crew Lander	Descent	Impingement on sides and base
	Crew Lander	Ascent	Impingement on sides and base
Descent Stage	Cargo Lande	r Descent Descent Descent Descent	Radiation to base Impingement on landing gear Soil erosion on base & landing gear High base pressure at touchdown
	Crew Lander	Descent Descent Descent Descent	Radiation to base Impingement on landing gear Soil erosion on base & landing gear High base pressure at touchdown
Ascent Stage	Crew Lander	Ascent Ascent Ascent	Radiation to base Impingement to top of descent stage Soil erosion to componts left on lunar surface
		Ascent	High hase pressure at lift-off


Φ



;

•

#### SIDE VIEW OF FLO CREW LANDER ASCENT STAGE



#### **GENERIC PLUME TECHNOLOGY NEEDED FOR LUNAR MISSIONS**

### Technology

- Flow Fields
  - Nozzle
  - Plume
- Surface Loads (Pressures, Forces, Moments, etc.)
  - Heating
    - Radiation
    - Convection
- Soil Erosion
- Contamination
- Temperatures
- Ground Tests

**Available Computer Codes/Facilities** 

CEC, RPP RAMP, CHARM, VISMOC, SFPLIMP, DSMC

**RCSFORCE, PIM900, SFPLIMP, SFPDQ** 

SIRRM, CHARM VISMOC, BLIMP, PLIMP, CHENG, DSMC, Bridging Functions, etc.

**Roberts Theory** 

CONTAM, PROX, MOLFLUX

SINDA

Full Scale: JSC/TTA & Chamber A Scale Model: CALSPAN, Grumman

### **CONCLUSIONS AND RECOMMENDATIONS**

- CLL and FLO vehicles represent the first spacecraft to return to the moon in a generation
- Plume heating/impingement problems will exist on new lunar vehicles, similar to those of the LM 20-25 years ago
- Plume effects could result in potential damage to critical structures and components of the new lunar vehicles if these effects are not assessed prior to detailed design phase
- Current methodology exists to predict almost all plume effects
- For special cases, more extensive analyses (including CFD) may be required
- JSC/EG3 and LESC/Aerothermal Group have plume experience with numerous engines (ASRM, RSRM, SSME, PRCS, LM, SM, Saturn, etc.)
- Analytical tools are available to support design trade studies conducted by FLO and CLL system designers