

**OPERATIONS =**

**N 9 3 - 7 1 8 4 3**

**IN-SPACE ASSEMBLY AND CONSTRUCTION  
TECHNOLOGY PROJECT SUMMARY**

**INFRASTRUCTURE OPERATIONS AREA  
OF THE  
OPERATIONS TECHNOLOGY PROGRAM**

59-81  
157519  
P-12

June 26, 1991

Office of Aeronautics, Exploration and Technology  
National Aeronautics and Space Administration

Washington, D.C. 20546

**OPERATIONS TECHNOLOGY  
INFRASTRUCTURE OPERATIONS**

**In-Space Assmbly and Construction**

**OBJECTIVES**

- Programmatic

Develop and Demonstrate an In-Space  
Assembly and Construction Capability for  
Large and/or Massive Spacecraft

**SCHEDULE**

- 1993 Automated panel installation on truss  
Complete welding vacuum facility
- 1994 Demonstrate precise 2-D crane positioning
- 1995 Demonstrate automated "orbital" welding
- 1997 Controlled slewing of 3-D space crane
- 1998 Precise positioning of large component
- 1999 Automated construction of curved antenna

**RESOURCES**

- 1991 \$ 0.3M
- 1992 \$ 0.0M
- 1993 \$ 2.0M
- 1994 \$ 4.0M
- 1995 \$ 7.0M
- 1996 \$ 8.0M

**PARTICIPANTS**


Langley Research Center

Space crane  
Positioning control  
Passive damping  
Active damping  
Suspension systems  
Automated construction

Marshall Spaceflight Center

Automated welding

## IN-SPACE ASSEMBLY AND CONSTRUCTION ENHANCES FUTURE MISSIONS PLANNING FLEXIBILITY



OPERATIONS TECHNOLOGY: INFRASTRUCTURE OPERATIONS

## IN-SPACE ASSEMBLY AND CONSTRUCTION

### TECHNOLOGY NEEDS

THE IN-SPACE ASSEMBLY AND CONSTRUCTION TECHNOLOGY PROGRAM WILL SUPPORT THE NEED TO BUILD, ON ORBIT, THE FULL RANGE OF SPACECRAFT REQUIRED FOR THE MISSIONS TO AND FROM PLANET EARTH, INCLUDING:

#### EARTH-ORBITING PLATFORMS

- EARTH OBSERVATION SYSTEM (PLATFORMS)
- PRECISION RADIOMETER & ANTENNAE
- EVOLUTIONARY SPACE STATION

#### LUNAR TRANSFER VEHICLES

- AEROBRAKE CONSTRUCTION
- SPACECRAFT COMPONENT ASSEMBLY

#### MARS TRANSFER VEHICLES


- SPACECRAFT COMPONENT ASSEMBLY
- NTR: BACKBONE TRUSS & RADIATOR CONSTRUCTION, UTILITIES WELDING
- SEP: SOLAR ARRAY CONSTRUCTION

## IN-SPACE ASSEMBLY AND CONSTRUCTION

### TECHNOLOGY CHALLENGES/APPROACH

- **TECHNOLOGY DEVELOPMENT CHALLENGES:**
  - **REDUCE LIMITATIONS ON SPACE VEHICLE SIZES AND CONFIGURATIONS IMPOSED BY LIMITED ETO LAUNCH CAPABILITY AND/OR ON-ORBIT OPERATIONS REQUIREMENTS**
  - **SPECIFIC CHALLENGES INCLUDE:**
    - ACCURATELY POSITION LARGE SPACECRAFT COMPONENTS
    - ASSEMBLY TWO OR MORE LARGE COMPONENTS TO FORM SPACECRAFT
    - CONSTRUCT DISCRETE SINGLE-POINT JOINTS
    - CONSTRUCT DISCRETE MULTI-POINT JOINTS
    - CONSTRUCT CONTINUOUS "LINE" JOINTS
    - AUTOMATE ASSEMBLY AND CONSTRUCTION OPERATIONS
    - ANALYZE AND SIMULATE ALL ASSEMBLY AND CONSTRUCTION OPERATIONS
- **TECHNOLOGY DEVELOPMENT APPROACH**
  - SURVEY MISSIONS FOR ISAAC NEEDS AND REQUIREMENTS
  - DEFINE FUNDAMENTAL GENERIC CAPABILITIES NEEDED
  - DEFINE FOCUS PROBLEMS AND ASSOCIATED EXPERIMENTS
  - DEVELOPE METHODS AND HARDWARE FOR ACCOMPLISHING ISAAC PROCESSES
  - PERFORM EXPERIMENTS WHICH VALIDATE ISAAC METHODS

### IN-SPACE ASSEMBLY AND CONSTRUCTION FACILITY CONCEPT



## **IN-SPACE ASSEMBLY AND CONSTRUCTION**

---

---

### **STATE-OF-THE-ART ASSESSMENT**

- **GENERAL ASSESSMENT: EXTENSIVE NEUTRAL BUOYANCY EXPERIENCE IN SIMULATED ZERO-G CONSTRUCTION OF LARGE SPACE TRUSSES. VERY GOOD CORRELATION WITH FLIGHT DATA (ACCESS). NO EXPERIENCE IN THE AREAS OF ON-ORBIT ASSEMBLY (AUTOMATED) OR AUTOMATED (TELEROBOTIC) CONSTRUCTION**
- **DETAILED ASSESSMENT:**
  - **NO VALIDATED DESIGN-FOR-CONSTRUCTION METHODS**
  - **NO SYSTEM EXISTS FOR RAPIDLY & PRECISELY POSITIONING LARGE/MASSIVE SPACECRAFT COMPONENTS (FOR ASSEMBLY)**
  - **CONCEPTS EXIST FOR LIGHTLY MECHANICAL LOADED JOINTS (ACCESS, SSF), HOWEVER, NO CONCEPTS EXIST FOR HEAVILY LOADED JOINTS**
  - **LIMITED EXPERIENCE WITH ZERO-G WELDING (SKYLAB, SOVIET UNION), HOWEVER, NO EXPERIENCE WITH AUTOMATED ZERO-G VACUUM WELDING FOR CONSTRUCTION OR ASSEMBLY APPLICATIONS ON ORBIT**

## **IN-SPACE ASSEMBLY AND CONSTRUCTION**

---

---

### **STATE-OF-THE-ART ASSESSMENT**

#### **DETAILED ASSESSMENT (CONCLUDED):**

- **AUTOMATED CONSTRUCTION OF A LIGHTLY LOADED TRUSS IN A HIGHLY STRUCTURED ENVIRONMENT WITH NO ON-ORBIT EFFECTS INCLUDED (ASAL). NO EXPERIENCE WITH AUTOMATED ASSEMBLY OR CONSTRUCTION IN AN UNSTRUCTURED ENVIRONMENT INCLUDING PATH PLANNING, COLLISION AVOIDANCE, AND FACILITY INFRASTRUCTURE FLEXIBILITY.**

OPERATIONS TECHNOLOGY: INFRASTRUCTURE OPERATIONS  
**IN-SPACE ASSEMBLY AND CONSTRUCTION**

**POSITIONING AND CONSTRUCTION DEVICES PERFORMANCE OBJECTIVES**

PERFORMANCE REQUIREMENT	CURRENT S.O.A. (RMS)	LUNAR	MARS
Manipulator Reach	15 m	30 m	100 m
Component Mass	14,500 kg (ret.) 30,000 kg (dep.)	75,000 kg	150,000 kg
Placement Accuracy	± 2 inches	± 1 inch	± 1 inch
Tip Force	15 lbf	50 lbf	150 lbf
Damping	< .5%	> 5.0% (5 modes)	> 5.0% (5 modes)
Max. tip velocity (14,500 kg, 2 ft. stop)	0.2 ft/sec	0.4 ft/sec	0.6 ft/sec
Maintenance Interval	After each flight	> 1 year	> 1 year
Required environment	Highly structured taught points	Unstructured path planning	Unstructured path planning
Operation	Teleoperated	Telerobotic	Telerobotic

## SPACE CRANE


**The Capability to Position and Control Spacecraft Components Precisely and Safely During Assembly Will be Achieved by Developing a Structural Space Crane Type Arm, Having Multiple Articulating Joints for Dexterity, and that can Ultimately be Operated in an Automated Mode**

### **FEATURES**


- **Strength to Move and Control Large Spacecraft Components Safely**
- **Passive and Active "Stiffness" to Maintain a Stable and Secure Position**
- **Highly Controllable Large Angle Motion with Dynamic Control for Stable Trajectories**
- **Passive and Active Vibration Damping to Achieve Required Precision**
- **Reconfigurable/Adaptable Geometry to Reduce the Amount of Required On-Orbit Infrastructure**
- **Scaleability (Larger or Smaller Sizes) for a Variety of Applications**
- **Robustness and Reuseability for Long Life**







# SPACECRAFT COMPONENT POSITIONING AND ASSEMBLY TEST-BED



## SPACE CRANE ARTICULATING JOINT TEST BED FABRICATED





# ERECTABLE TRUSS HARDWARE PREDICTABILITY IS EXCELLENT





NASA Langley Research Center

Summary - 81187

# IMPROVED LINEAR ACTUATORS REDUCE TEST BED BACKLASH BY 57 PERCENT




ARTICULATING JOINT DETAIL




NASA Langley Research Center

Summary - 81187

# AUTOMATED STRUCTURES ASSEMBLY LABORATORY



## AUTOMATED CONSTRUCTION TECHNOLOGY DEVELOPMENT & DEMONSTRATION TEST-BED






OPERATIONS TECHNOLOGY: INFRASTRUCTURE OPERATIONS  
**IN-SPACE ASSEMBLY AND CONSTRUCTION**

**JOINING METHODS PERFORMANCE OBJECTIVES**

PERFORMANCE REQUIREMENT	CURRENT S.O.A.	LUNAR	MARS
Strength	2000 lbf (SSF)	Up to 50,000 lbf	Up to 150,000 lbf
Connection time	0.3 min/strut (ACCESS)	0.3 - 5.0 min/strut (mechanical) Welding: TBD	0.3 - 5.0 min/strut (mechanical) Welding: TBD
Durability	> 5years (SSF)	> 5 years	> 10 years
Connection method	Manned EVA (ACCESS, SSF)	Automated/EVA (mix)	Automated/EVA (mix)

**ERECTABLE JOINT FAMILY AVAILABLE FOR EFFICIENT AEROBRAKE TRUSS DESIGN**



## **WELDED JOINTS - CLASSIFICATION (Basic Advantages)**

- **TUBULAR STRUT**
  - High Strength, Low Mass
  - Low Dimensional Accuracy Requirements
  - Simple Welding Mechanism
  
- **PIPES/DUCTS**
  - Hermetic Seal
  - Simple Welding Mechanism
  
- **SKIN/TANK**
  - Hermetic Seal
  
- **SEMI-MONOCOQUE STRUCTURES**
  - High Strength, Low Mass
  - Low Dimensional Accuracy Requirements
  
- **REPAIR/CONTINGENCY (Manual)**
  - Flexibility

OPERATIONS TECHNOLOGY: INFRASTRUCTURE OPERATIONS

## **IN-SPACE ASSEMBLY AND CONSTRUCTION**

---

### **CURRENT PROGRAM: ACCOMPLISHMENTS**

#### **ACCOMPLISHMENTS**

- Load/displacement testing of 1st and 2nd generation space crane linear actuators completed
- Space crane maximum allowable tip velocity established using strut buckling loads
- 1st. generation heavily loaded 4-inch diameter erectable aerobrake joint developed
- Automated construction of the complete 102-member flat tetrahedral truss structure successfully completed
- Vacuum plasma welding experiments conducted
- Aerobrake hexagonal heatshield panel construction tests completed

OPERATIONS TECHNOLOGY: INFRASTRUCTURE OPERATIONS  
**IN-SPACE ASSEMBLY AND CONSTRUCTION**

---

---

CURRENT PROGRAM: FY 91/92 PLANS

FY 91/92 PLANS (FUNDING FOR FY 92 = \$0)

- Perform space crane kinematic and dynamic simulations
- Upgrade space crane articulating joint test hardware and perform dynamic tests
- Redesign heavily-loaded erectable joints and perform static tension failure tests
- Demonstrate automated installation of flat antenna panels onto flat truss
- Complete welding vacuum manipulation facility

OPERATIONS TECHNOLOGY: INFRASTRUCTURE OPERATIONS  
**IN-SPACE ASSEMBLY AND CONSTRUCTION**

---

---

OTHER DEVELOPMENT EFFORTS

- LaRC BASE R&T
  - EVA construction of precision curved truss with panels
  - Automated Structures Assembly Laboratory (ASAL)
- NO OTHERS

# IN-SPACE ASSEMBLY AND CONSTRUCTION

## ISAAC TECHNOLOGY ROADMAP/SCHEDULE

KEY ACTIVITIES	1991	1992	1993	1994	1995	1996	1997	1998	1999	
<b>ASSEMBLY</b>										
Articulating joint test-bed		Slewing	Passive damping	Precise positioning	Active damping					
Simulations		Kinematic/Dynamic	Assembly & Construction Test-bed operations					On-orbit facility		
3-D space crane		Reqs. (Lunar)	Design	Hardware fab.	Suspension system			Reqs. (Mars)	Design	
Assembly experiment		Concept selection	Reqs. & concept	Controls	End-effector reqs.	Hardware integration				
<b>CONSTRUCTION</b>							Controlled Telerbotic slewing positioning			
Flat truss/panels		Automated panel installation	Unstructured environment							
Antenna			Reqs. & concept	Hardware fab.	Carriage, arm and effector fab.		Auto. const. rigid base	Auto. const. flexible base		
Welding (utilities)		Complete vacuum facility	Utility concept	Hardware fab.	Automated orbital weld					

## CONCLUDING REMARKS

- Design-for-Construction/Assembly Must be Emphasized From the Very Beginning of the Spacecraft Design Process
- Having a Basic Generic Set of In-Space Assembly and Construction Capabilities Available Will
  - Give Mission Planners and Spacecraft Designers a Great Deal of Flexibility
  - Minimize the Amount of In-Space Infrastructure and Resources Required to Build Spacecraft on Orbit
- Spacecraft Design Costs can be Reduced by Using Available and Developed ISAAC Capabilities, Methods, and Hardware