# Test & Verification Approach for the NASA Constellation Program



CONSTELLATION



## Outline



- NASA's Vision for Exploration
- Constellation Program Overview
- Constellation Vision for Test & Verification
- Test & Verification Implementation





## The Vision for Space Exploration: Foundations for Exploration



- Complete the International Space Station
- Safely fly the Space Shuttle until 2010
- Develop & fly the Crew Exploration Vehicle no later than 2014
- Return to the Moon no later than 2020
- Extend human presence across the solar system & beyond
- Implement a sustained & affordable human & robotic program
- Promote international & commercial participation in Exploration

#### NASA Authorization Act of 2005










# Constellation Program Fleet of Vehicles









## **Exploration Roadmap**














## **Ares I Elements**







## **Orion Elements**



# Orion Crew Exploration vehicle (JSC)

- NASA Management and Integration
- Prime contract Lockheed Martin:design, development, and production

#### Crew Module (JSC)

- Crew and cargo transport
- Under Prime contract

#### Spacecraft Adapter (GRC)

- Structural transition to Ares launch vehicle
- Under Prime contract


#### Launch Abort System (LaRC)

- Emergency escape during launch
- Under Prime contract

#### Service Module (GRC)

propulsion, electrical power, fluids storage
Under Prime contract







## **Lunar Lander**





- Transports 4 crew to and from the surface
  - Seven days on the surface
  - Lunar outpost crew rotation
- Global access capability
- Anytime return to Earth
- Capability to land 20 metric tons of dedicated cargo
- Airlock for surface activities
- Descent stage:
  - Liquid oxygen / liquid hydrogen
     propulsion
- Ascent stage:
  - Storable Propellants



## Map of Constellation content across NASA









- Mission and Vision
- Organization
- Documentation
- Processes
- Integrated Testing
- Flight Testing







- Attrition of workforce experienced in human spaceflight development
  - Aging of existing human spaceflight programs as well as previous programs
- Application of lessons learned
  - Must ensure lessons learned are applicable to CxP
- Developing integrated approach among multiple organizations
  - Differing practices, documentation, vocabulary
- New Information technology environment
  - Requires shift in thinking from paper processes
- Extensive use of heritage hardware envisioned for CxP
  - Must be applied carefully when mission differs from original





## Reinvigorate T&V – thinking, experience, discipline, culture

T&V planners and practitioners get educated via OJT

### Incorporate lessons learned

- Plan a project & THEN plan T&V is a current norm
  - This practice has piles of lessons written on it
- Planning for T&V must MOVE LEFT
  - CONCURRENTLY with formulation of concepts and requirements
  - Enough work early enough
    - T&V effort INCLUDED in the plan, not added later

#### Rules, standards, practices aimed/set for FAR more reliable exploration systems

 Integrated T&V guiding policy, general requirements, standard practices, and cooperative implementation plans and processes






- The primary mission of the CxP T&V function is to ensure the following objectives are accomplished through the life of the CxP:
  - Verification that the Constellation Architecture satisfies the CARD and associated IRDs
  - <u>Verification</u> that each 'end item' meets its specified requirements
  - <u>Verification</u> that the 'end items' appropriately integrate with other end products and "systems", as required (e.g., CEV integration with ISS)
  - <u>Validation</u> that the Constellation Architecture satisfies its stakeholders' needs
- The vision of the CxP T&V function is that the following items be established, integrated, maintained, and be readily retrievable for all levels of the CxP Architecture throughout the life of the CxP:
  - A formalized verification process that ensures CxP HW/SW complies with applicable designto/performance/build-to specifications (e.g., CARD, SRD, ERD, IRDs/ICDs)
  - A complete and readily accessible "materiel history" for all CxP 'end items'
  - A complete "certification baseline" that encompasses all CxP flight HW/SW
  - Processes and tools to support the planning, execution, and assessment of effectiveness for verification activities performed throughout the mission integration lifecycles of each DRM
  - A formalized validation process that confirms that CxP HW/SW and processes fulfill their intended capability, functionality, and performance



## **Constellation Program Organization**








# **Test and Evaluation Organization**








## **CxP** Requirements Flowdown







## **CxP Model Based Systems Engineering Approach**




				REQ - CONST: I.CLV-GOE.1824 (01A)
Ī	CCODY	EQ - CONST 🛛 🗙	1	[] I.CLV-GOE.1824 (01A)
	WRK COPY I		-	Model: NOTE Identity: I.CLV-GOE.1824 Author: TWOOD
	Scope: Iter	n 🔻		Type: NOTE Name: CLV Accessibility Created: 05/10/06
	-Options			Subtype: REQ - CONST Security: UNCLASSIFIED  Modifier: TWOOD
				Key: CLV-GOE Group: 3.2.2.4  Modified: 05/10/06
	🗌 🗌 Overw	rite existing items		SIG: Integrated Loads, S Baseline: Status:
	Copied	items inherit cross-references		Draft: A Version: 01 Schedule Achieve:
				Owner: TWOOD PerfAchieve:
	🕞 🗖 Link co	py to original		CostAchieve:
				Text:
	Link Type	<u> </u>		The CLV to GS physical access locations shall be as shown in the CLV Physical Access Figure [TBS 1824].
	Reason		1111000 i 11000000	-
Cradl	Rationale	- <del> </del>		
e Edit	Reference			
۹.			1	Navigation Downwards 💌 🗙 📃
Intitled	Note		Þ	
🖹 IF R	Note Type:	REQ - CONST		
			-	NOTE : DOC SECTION : CX-NET_IF_1.3 : CONVENTION AND NOTATION : PSHAH
	New Item:	I.CLV-GOE.1824		NOTE : DOC SECTION : Cx-NET_IF_1.4 : CHANGE AUTHORITY : DRADE
	Name:	CLV Accessibility		NOTE : DOC SECTION : CX-NET_IF_2 : DOCUMENTS : PSHAH
	Key:	CLV-GOE		NOTE : DOC SECTION : Cx-NET_IF_2.1 : APPLICABLE DOCUMENTS : PSHAH
	Group:	3.2.2.4		NOTE : DOC SECTION :      Impet_if_2.2 : Reference documents : PSHAH      NOTE : DOC SECTION : Cx-NET_IF_3.2 : LOADS, STRUCTURES, AND MECHANISMS RE
	areap.			NOTE : DOC SECTION : CX-NET_IF_3.3 : POWER REQUIREMENTS : PSHAH
		OK Cancel Help		NOTE : DOC SECTION : CX-NET_IF_3.4 : ENVIRONMENTAL CONTROL AND LIFE SUPPO
+				NOTE : DOC SECTION : CX-NET_IF_3.5 : GASSES AND FLUIDS REQUIREMENTS : PSHAI
		ERENCE : 79 : Spacecrart Contaminants : BTEAG ERENCE : 79 : Specification for Percussion Primers : BTEAG		NOTE : DOC SECTION : CX-NET_IF_3.6 : COMMUNICATION REQUIREMENTS : PSHAH
	_	ERENCE : 81 : ASRS Handbook : BTEAG		NOTE : DOC SECTION : Cx-NET_IF_3.6.1 : RF Communications : PSHAH      NOTE : DOC SECTION : Cx-NET_IF_3.6.1.1 : Common RF Communication : PSHAH
	🔁 NOTE : REF	ERENCE : 108 : Fracture Control Requirements : BTEAG		Image: The second se
	_	ERENCE : 110 : Software Safety : BTEAG		Image: The second se
	🔁 NOTE : REF	ERENCE : 117 : Software Asssurance Standard : BTEAG	-	



## **CxP Verification Planning Documents**










- Developed CxP 70036 CxP Environmental Qualification and Acceptance Test Requirements
- Roughly equivalent to MIL-STD-1540, but many practices differ from DoD
- Utilizes Risk-based tailoring process
- Document addressed varying test practices within NASA community
- Resulted in formation of Environmental Testing Community of Practice (CoP)



## **Scope of CxP Verification**








## **CxP Verification - General Process Flow**






Compliance





- CxP will use distributed approach for avionics and software integration and verification
- Utilizes high speed networks to leverage existing test facilities rather than developing a standalone integrated test facility






## A-3 Test Stand



- Located at Stennis Space Center
- Will be used to test J-2X engine
- First large test stand built at the center since the 1960s
- 300-foot-tall, open-frame design will allow engineers to simulate conditions at different altitudes in order to test the J-2X's ability to function as a second stage engine for the Ares I and the Earth Departure Stage engine for the Ares V
- Test stand will generate approximately 4,620 pounds per second of steam to reduce the engine test cell pressure.






## **Space Power Facility**



- Glenn Research Center Plumbrook Facility
- Will provide Orion Environmental Correlation Test (ECT) for the Ground Test Article (GTA) (vibro-acoustic) and Integrated Environmental Orion Qualification Testing in a "test as you fly" configuration.
  - Acoustic Vibration
  - Mechanical Vibration
  - Thermal-Vacuum
  - EMI/EMC








- The MEIT and FEIT tests will confirm that the work done by the Projects to verify the interfaces are complete and the elements are ready to fly and support in flight operations.
- Plans for these tests will be outlined in the Integrated Test Plan (ITP)





 FEIT - An FEIT is an integration test between new or significantly modified systems, elements, and modules being assembled into an integrated launch vehicle for the first time (e.g., CEV and CLV; LSAM, Earth Departure Stage (EDS), and CaLV) for the purposes of operational testing (i.e., typically not development testing) or crewed flight.




28





 MEIT - An MEIT is an integration test between two or more flight systems which will be launched on separate launch vehicles and integrated together for the first time in space (e.g., CEV and ISS; CEV and LSAM/EDS).





## **Flight Test Driving Principles**



- Integrated flight test strategy encompasses development through operational validation
- Development tests inform design, models, adjustments
- Validation objectives:
  - Does the system 'do what we want'?
  - Does the system 'behave as expected'?
  - Do we understand how to operate the system?
- A mission's objectives (test, ops) are linked to manifested capability set
- Testing continues after transition into mission service





### Constellation's Integrated Flight Test Strategy Low Earth Orbit Servicing Capability



