

ENGINEERING DEPARTMENT TECHNICAL REPORT

TR-RE-CCSD-FO-1094-3

March 15, 1967

SATURN IB PROGRAM

TEST REPORT FOR

GATE VALVE, MANUALLY OPERATED

6-INCH, 150-POUND

Pacific Valve Company Part Number S8550F(8)-12T-ASA

NASA Drawing Number 75M12930 IGV-IB

| 602 | N67-361 | 21 |
|----------|-------------------------------|--------|
| FORM | (ACCESSION NUMBER) | (THRU) |
| FACILITY | (NASA CR OR TMX OR AD NUMBER) | (CODE) |



TEST REPORT

FOR

GATE VALVE, MANUALLY OPERATED

6-INCH, 150-POUND

Pacific Valve Company Part Number S8550F(8)-12T-ASA

NASA Drawing Number 75M12930 LGV-IB

ABSTRACT

This report presents the results of tests performed on one sample of manually operated Gate Valve 75M12930 IGV-IB. The following tests were performed:

- 1. Receiving Inspection
- 3. Functional
- 2. Proof Pressure

4. High Temperature

The results of the tests performed were satisfactory. The performance of the specimen was in accordance with specification requirements of NASA drawing 75M12930 LGV-IB.

Testing of manually operated Gate Valve 75M12930 IGV-IB was discontinued after high temperature test. Due to a material compatibility problem encountered at the John F. Kennedy Space Center on the subject valve, the manufacturer has recommended certain design modifications.

TEST REPORT

FOR

GATE VALVE, MANUALLY OPERATED

6-INCH, 150-POUND

Pacific Valve Company Part Number S8550F(8)-12T-ASA

NASA Drawing Number 75M12930 IGV-IB

March 15, 1967

FOREWORD


The tests reported herein were conducted for the John F. Kennedy Space Center by Chrysler Corporation Space Division (CCSD), New Orleans, Louisiana. This document was prepared by CCSD under contract NAS 8-4016, Part VII,

TABLE OF CONTENTS

| Section | e de la companya de | age |
|---------|---|-------------|
| 1. | INTRODUCTION | L -1 |
| п | RECEIVING INSPECTION | 2-1 |
| III | PROOF PRESSURE TEST | }-1 |
| IV | FUNCTIONAL TEST | -1 |
| V | HIGH TEMPERATURE | -1 |

LIST OF ILLUSTRATIONS

| - | TRUCE | | rage |
|---|--------------|--|------|
| Ĭ | FRONTISPIECE | • | v |
| | 3-1 | PROOF PRESSURE TEST SCHEMATIC | 3-3 |
| | 3-2 | PROOF PRESSURE TEST SETUP | 3-4 |
| | 4-1 | FUNCTIONAL TEST SCHEMATIC | 4-5 |
| | 4-2 | FUNCTIONAL TEST SETUP | 4-6 |
| | 5-1 | HIGH TEMPERATURE TEST SETUP | 5-3 |
| | | LIST OF TABLES | |
| | Table | | Page |
| | 2-1 | SPECIMEN SPECIFICS | 2-1 |
| | 3-1 | PROOF PRESSURE TEST EQUIPMENT LIST | 3-2 |
| | 3-2 | PROOF PRESSURE TEST DATA | 3-2 |
| | 4-1 | FUNCTIONAL TEST EQUIPMENT LIST | 4-3 |
| | 4-2 | FUNCTIONAL TEST DATA | 4–4 |
| | 5-1 | HIGH TEMPERATURE TEST EQUIPMENT LIST | 5-2 |
| | 5-2 | FUNCTIONAL TEST DATA OBTAINED DURING HIGH TEMPERATURE TEST | 5-2 |
| | 5-3 | FUNCTIONAL TEST DATA OBTAINED AFTER HIGH TEMPERATURE TEST | 5-2 |



Gate Valve, Manually Operated 75M12930 LGV-IB

CHECK SHEET

FOR

GATE VALVE, MANUALLY OPERATED

6-INCH, 150-POUND

MANUFACTURER: Pacific Valve Company

MANUFACTURER'S PART NUMBER: \$8550F(8)-12T-ASA NASA PART NUMBER: 75M12930 LGV-IB

TESTING AGENCY: Chrysler Corporation Space Division, New Orleans, Louisiana

LN₂

AUTHORIZING AGENCY: NASA KSC

I. FUNCTIONAL REQUIREMENTS

A. OPERATING MEDIUM :

150 psig В. OPERATING PRESSURE:

PROOF PRESSURE: 225 psig

II. CONSTRUCTION MATERIAL

BODY: **316** stainless steel A.

BONNET: 316 stainless steel В. 316 stainless steel C. VALVE TRIM:

YOKE: 316 stainless steel D.

316 stainless steel with Teflon inserts E. DISCS:

6-inch, 150-1b ASA flanges END CONNECTIONS:

III. ENVIRONMENTAL REQUIREMENTS

> OPERATING TEMPERATURE: -320 to +125°F

IV. LOCATION AND USE: Used as a shutoff valve in the LOX

fill system at John F. Kennedy Space Center Launch Complexes 34 and 37B.

TEST SUMMARY

GATE VALVE

75ML2930 LGV-IB

| | Environment | Units | Operational Boundary | Test Objective | Test Results | Remarks |
|----------|----------------------------|-------|--|---|-----------------|--|
| | Receiving Inspection | 1 | Visual examination > | To determine if specimen conforms with applicable drawings and specifications | Satisfactory | Length: 10-½ inches flange to flange Height: 37 inches |
| | .Proof Pressure Test | 1 | 225 psig for 5 minutes | Check for leakage and distortion | Satisfactory | Maintained 225 psig. No ex- ternal leakage |
| - | Functional Test | 1 | Maximum allowable leakage 10 sccm | To determine specimen internal and packing gland leakage | Satisfactory | Internal leak— age: none Packing gland leakage: none |
| | High Tempera- ture Test | 1 | Stabilize speci- men at 125°F for 72 hours; perform functional test both at high tem- perature and after return to ambient conditions | To determine operating ability at high temperature and after return to ambient conditions | Satisfactory | No change of operation ability. No increase in leakage during functional tests |
| | Surge Test | 0 | 50 to 150 psig within 100 milli- seconds for 20 cycles | To determine if specimen operation is impaired by surge | • | Test not conducted |
| | Cycle Test | 0 | Open and close the specimen while the specimen is pressurized to 300 psig. Perform 500 cycles | Perform a functional test after 100, 200, 300, 400, and 500 cycles. Check for leakage | | Test not conducted |
| <u> </u> | Burst Test | 0 | 600 psig for 5 minutes | Maintain 600 psig with no leakage for 5 minutes | | Test not conducted |

SECTION I

INTRODUCTION

1.1 SCOPE

This report describes the results of tests that were performed to determine if Gate Valve 75M12930 IGV-IB meets the operational and environmenta 1 requirements of the John F. Kennedy Space Center. A summary of the test results is presented on page vii.

1.2 ITEM DESCRIPTION

- 1.2.1 Gate valve 75M12930 LGV-IB is a manually operated, 6-inch, flanged end gate valve. The valve is manufactured by the Pacific Valve Company, Long Beach, California and serves as a shutoff valve in the LOX fill system.
- 1.2.2 The valve is of a one piece pattern and has an integral seat. The valve also has an extension bonnet, and an outside screw and yoke. The valve control handle is of the hand wheel type. The valve measures $10\frac{1}{2}$ inches face to face. Construction is of 316 stainless steel with a Teflon insert in the downstream valve disc. The upstream valve disc is pronze.

1.3 APPLICABLE DOCUMENTS

The following documents contain the test requirements for gate valve 75ML2930 ICV-IB.

- a. KSC-STD-164(D), Standard Environmental Test Methods
- b. Drawing 75ML2930 IGV-IB
- c. MSFC Cleaning Standard MSFC-STD-164
- d. Test Plan CCSD-F0-1094-1F. Rev. A
- e. Test Procedure TP-RE-CCSD-F0-1094-2F

SECTION II

RECEIVING INSPECTION

2.1 TEST REQUIREMENTS

The specimen shall be visually and dimensionally inspected for conformance with the applicable specifications prior to testing,

2.2 TEST PROCEDURE

A visual and dimensional inspection was performed to determine compliance with NASA drawing 75M12930 IGV-IB and the applicable vendor drawing to the extent possible without disassembly of the test specimen. At the same time the test specimen was inspected for poor workmanship and manufacturing defects.

2.3 TEST RESULTS

The specimen successfully complied with the requirements of NASA drawing 75M12930 IGV-IB and the vendor drawing. No evidence of poor workmanship or manufacturing defects was observed.

2.4 TEST DATA

The data presented in table 2-1 were recorded during receiving inspection.

Table 2-1. Specimen Specifies

| Name | Gate Valve, Manually Operated |
|----------------------|---|
| Size | 6-inch |
| Figure No. | S8550F (8)-12T-ASA |
| Material | Stainless steel |
| Height | 37-inches |
| Length | 10 $\frac{1}{2}$ -inches (flange to flange) |
| End Connec- tions | 6-inch, 150 pounds ASA flanges |

SECTION III

PROOF PRESSURE TEST


| 3.1 | TEST REQUIREMENTS |
|-------|---|
| 3.1.1 | With the test specimen in the open position, the inlet and outlet ports shall be simultaneously pressurized to 225 psig. This pressure shall be maintained for 5 minutes. |
| 3.1.2 | The test specimen shall be checked for leakage and distortion. |
| 3.1.3 | The test medium shall be H2O. |
| 3.2 | THE TIMOMENT |
| 3.2.1 | The test setup shown in figures 3-1 and 3-2 was assembled using the equipment listed in table 3-1. |
| 3.2.2 | It was determined that all connections were tight, the gage was installed and operating properly, and that all valves were closed. |
| 3.2.3 | The specimen was placed in the opened position and valves 4 and 6 were opened. The specimen and system were purged of air by operating hand pump 3. |
| 3.2.4 | Valve 6 was closed and hand pump 3 was operated until the specimen was pressurized to 225 psig. The pressure was monitored on gage 5. |
| 3.2.5 | Valve 4 was closed and the pressure was maintained for 5 minutes. |
| 3.2.6 | During the 5-minute pressurization period, the specimen was checkea for leakage by monitoring gage 5, and by v sual inspection. The initial and final pressures were recorded |
| 3.2.7 | Valves 4 and 6 were opened and the system was allowed to depressurize to zero psig, |
| 3.2.8 | The specimen was inspected for distortion and all data were recorded. |
| 3.3 | TEST RESULTS |
| 3.3.1 | The test specimen was successfully subjected to the proof pressure test, No leakage or distortion was noted, |
| 3.4 | TEST DATA |
| | Tie data recorded during the proof pressure test are presented |

Table 3-1. Proof Pressure Teat Equipment List

| Item No. | Item | Manufacturer | Model/ | Serial No. | Remarks |
|-------------|----------------------------|--------------------------------------|----------------------------------|-----------------------|---------------------------------------|
| 1 | Test Specimen | Pacific Valve Company | Part-No 58550F(8) -12T-ASA | MA | 6-inch gate valve |
| 2 | H ₂ 0 Reservoir | CCSD | NA | N A | |
| 3 | Hand Pump | Sprague Engineer- ing Corporation | NΑ | 300–16 – 64 | 5000-psig |
| 4 | Hand Valve | Robbins Aviation | SSKE 250-4T | NA NA | t-inch |
| 5 | Gage | Duragage | NA NA | 109-1001 | 0-to 500-psig +0.5% FS accuracy |
| 6 | Hand Valve | Robbins Aviation | SSKG- 250 - 4T | NA | Cal date 4-9-67 |
| | | | | | |

Table 3-2. Proof Pressure Test Data

| Test Media | H ₂ 0 | |
|------------|------------------|--|
| Pressure | 225 psig | |
| Duration | 5 minutes | |
| Leakage | None | |
| Distortion | None | |



Note: All lines are 1/4 inch.
Refer to table 3-1 for item identification.

Figure 3-1. Proof Pressure Test Schematic




Figure 3-2. Proof Pressure Test Setup

SECTION IV

FUNCTIONAL TEST

| 4.1 | TEST REQUIREMENTS |
|-------|---|
| 4.1.1 | The test specimen shall be opened and closed five times while pressurized to 150 psig with LN_2 . |
| 4.1.2 | The test specimen shall be checked for internal leakage while pressurized to 150 psig with IN2. The maximum allowable leakage shall be 10 sccm per inch of seat diameter. |
| 4.1.3 | The packing gland shall be checked for leakage for 30 minutes while the specimen is open and pressurized to 150 psig with ${\rm LN}_2$. |
| 4.2 | TEST PROCEDURE |
| 4.2.1 | The test setup was assembled as shown in figures 4-1 and 4-2 using the equipment listed in table 4-1. The test specimen was closed. |
| 4.2.2 | It was determined that all connections were tight, that gages were installed and operating properly, and that all valves were closed. |
| 4.2.3 | Hand valve 5 was opened and the, 3000-psig supply pressure was monitored on pressure gage 6, |
| 4.2.4 | LN_2 tank 10 was pressurized to 150 psig by adjusting regulator 7. The LN_2 tank pressure was monitored on pressure gages 8 and 11. |
| 4.2.5 | Hand valves 12 and 18 were opened and hand valve 16 was slightly opened. The test specimen was allowed to cool. The test specimen inlet pressure was maintained at 150 psig by adjusting regulator 7. The test specimen inlet pressure was monitored with pressure gage 13. |
| 4.2.6 | When thermometer 14 indicated the presence of LN2 in the test specimen, the test specimen was slowly opened. The test specimen was opened and closed five times. |
| 4.2.7 | Hand valves 12 and 18 were closed and hand valve 15 was opened. All the LN ₂ was drained from the specimen outlet, Flowmeter 17 was connected as shown in figure 4-1 (view A), |
| 4.2.8 | LN ₂ boiloff was monitored by observing flowmeter 17. The presence of boiloff was evidenced by a flowmeter indication when the specimen inlet pressure was zero psig. |
| | |

- 4.2.9 When the boiloff ceased, hand valve 12 was opened, The test specimen inlet pressure was maintained at 150 psig by adjusting regulator 7.
- 4.2.10 When thermometer 14 indicated the presence of LN₂ in the test specimen inlet, leakage fron the test specimen outlet was checked for 5 minutes. Leakage was indicated by flowmeter 17. The maximum allowable leakage was 10 sccm per inch of seat diameter.
- 4.2.11 Flowmeter 17 was disconnected from the outlet of hand valve 15. Hard valve 15 was closed and hand valve 18 was opened,
- 4.2.12 The test specimen was opened slowly. The entire specimen was allowed to fill with LN_2 . The specimen pressure was maintained at 150 psig.
- 4.2.13 While thermometer 14 indicated the presence of LN₂ in the test specimen, leakage from the packing gland of the specimen was checked for 30 minutes. A soap solution was used to check for leakage.
- 4.2.14 For the initial functional test, the procedures described in'
 4.2.1 through 4.2.13 were performed as necessary to obtain consistent data. For all subsequent functional tests, the procedures were performed once.

4.3 TEST RESULTS

The specimen successfully completed the functional test requirements. No leakage was recorded.

4.4 TEST DATA

Data recorded during the functional test are recorded in table 4-2.

Table 4-1. Functional Test Equipment List

| Item No | Item | Manufacturer | Model/ Part No. | Serial No. | Remarks |
|------------|------------------------|---------------------------|---------------------------|---------------------|--|
| 1 | 1:est Specimen | Pacific Valve Co. | S8550F (8)-12T- ASA | NA | Gate valve, 6-inch, 150-pound |
| `2 | GN ₂ Source | CCSD | INA | NA | 3000-psig |
| 3 | Pressure Gage | Ashcroft | 1057 | NA | 0-to 5000-psig |
| 4 | Filter | Bendix | 5-S- 13460- 16-B-0 | NA | 10-micron |
| 5 | Hard Valve | Vacco | NA | 5116-13 | l-inch |
| 6 | Pressure Gage | Duragage | NA | 109- 1001 | 0-to 5000-psig ±1.0% FS accuracy Cal date 10-13-66 |
| 7 | Regulator | Tescom | 26-1101- 162 | NA | O-to 500-psig outlet O-to 5000-psig inlet |
| 8 | Pressure Gage | Duragage | MA | 109- 1004 | 0-to 500-psig +0.1% FS accura cy Cal date 10-13-66 |
| 9 | Relief Valve | Anderson-Green- | 81-B- 66-0 | NA. | 220-psig |
| 10 | IN ₂ Tank | Convair-Astro- nautics | 27-29501 -803 | 104898 | |
| 11 | Pressure Gage | Marsh Instru- ments | NA . | 95-1145 | 0-to 500-psis +1.0% FS accuracy Cal date 10-23-66 |

Table 4-1. Functional Test Equipment List (Continued)

| item No. | Item | Manufacturer | Model/ Part No. | Serial No. | Remarks |
|-------------|---------------|-------------------|------------------------|----------------------|---|
| 12 | Hand Valve | Hydromatics | NA | NA | l-inch 400-psi, water or gas |
| 13 | Pressure Gage | Marsh Instruments | NA | 95 -1149 B | 0-to 500-psig ±0.1% FS accuracy Cal date 10-14-66 |
| 14 | Thermometer | Honeywell | NA . | 640710 99 | -300 to +400°F ±1°F accuracy |
| 15 | Hand Valve | Hydromatics | NA | NA | l-inch 400-psi, water or gas |
| 16 | Hard Valve | Flowmatics | MBL -715- 19 | NA | l-inch |
| 17 | Flowmeter | Fisher–Porter | NA | 200595-E | 0-to 100-sccm +5% accuracy |
| 18 | Hand Valve | Flowmatics | MBL-715- 19 | NA . | l-inch |

Table 4-2. Functional Test Data

| Test Media | LN ₂ |
|---------------|-----------------|
| Pressure | 150-psig |
| Leakage: | * |
| Internal | None |
| Packing Gland | None |





Figure 4-2. Functional Test Setup



SECTION V

HIGH TEMPERATURE TEST

| 5.1 | TEST REQUIREMENTS |
|-------|---|
| 5.1.1 | A high temperature test shall be performed on the specimen test to determine whether the environment causes degradation or deformation. |
| 5.1.2 | The rated high temperature is 125 (+4, -0)°F. |
| 5.1.3 | A functional test shall be performed during this test, using ${\rm LN}_2$ as the test medium. |
| 5.2 | TEST PROCEDURE |
| 5.2.1 | The test specimen was placed in a high temperature chamber and installed as shown in figure 4-1 (view A) using the equipment shown in tables 4-1 and 5-1. |
| 5.2.2 | The chamber was controlled to the specified test conditions of 125(+4,-0) F by maintaining a relative humidity of 20(-5) percent. |
| 5.2.3 | This temperature was maintained for a period of 72 (+2, -0) hours. |
| 5.2.4 | A functional test was conducted while the chamber temperature was maintained. |
| 5.2.5 | The chamber temperature was returned to ambient conditions upon completion of the functional test. |
| 5.2.6 | The test specimen was visually inspected and functionally tested within 1 hour following the establishment of ambient conditions. |
| 5.2.7 | The test data were recorded. |
| 5.3 | TEST RESULTS |
| | The test specimen successfully met the requirements of the high temperature test. No leakage was noted. |
| 5.4 | TEST DATA |
| | The data presented in tables 5-2 and 5-3 were recorded during the high temperature test. |

Table 5-1. High Temperature Test Equipment List .

| Item No. | Item | Manufacturer | Model/ Part No. | Serial No. | Remarks |
|-------------|--------------------------|------------------|--------------------|---------------|--------------------------------------|
| 1 | Temperature Power Supply | Thermotron Corp. | NA | 200507 | -100 to + 400°F al date 9-1-66 |
| 2 | Temperature Recorder | Honeywell | NA | 64071099 | -300 to + 400°F Gal date 10-21-66 |

Table 5-2. Functional **Test** Data Obtained During **Ḥigh** Temperature Test

| Temperature | | +125 "F |
|---------------|---|-----------------|
| Test Media | | IN ₂ |
| Pressure | - | 150 psig |
| Leakage: | | |
| Internal | | None |
| Packing Gland | | None |

Table 5-3. Functional Test Data Obtained After High Temperature Test

| Temperature | Ambient |
|-------------------|-----------------|
| Test Media | IN ₂ |
| Pressure | 150 psig |
| Leakage: | |
| Internal | None |
| Packing Gland | None |



Figure 5-1. High Temperature Test Setup

APPROVAL

TEST REPORT

FOH

GATE VALVE, MANUALLY OPERATED 6-INCH, 150-POUND

Pacific Valve Company Part Number S8550F(8)-12T-ASA

NASA Drawing number 75M12930 LGV-IB

SUBMITTED BY:

T.W. Sparks

Test and Evaluation Section

APPROVALS

R.W. Claunch

Program Supervisor

V.J. Velko

Director, Engineering Department

DISTRIBUTION

Chrysler Corporation Space Division

| C. | A. | Brakebill | Test and Evaluation Section | 2 | | |
|-------------------------------------|---|---|--|---|--|--|
| R. | W. | Claunch | Program Supervisor, CCSD-Michoud | 2 | | |
| W. | E. | Dempster | Program Manager, CCSDFO | 6 | | |
| E. | J. | Dofter | Chief Engineer , Reliability Engineering Branch | 1 | | |
| L. | L. | Gray | Test and Evaluation Section | 5 | | |
| P. | Pe | rani | Manager, Test and Evaluation Section | 2 | | |
| L. | T. | Scherer, Jr. | Manager, Data Center Section | 1 | | |
| V. | J. | Vehko | Director, Engineering Department | 1 | | |
| Technical Files | | | | | | |
| Technical Information Centre | | | | | | |
| Technical Writing and Editing Group | | | | | | |
| | | National . | Aeronautics and Space Administration | | | |
| Ma | MS | all Space Flight Cen 5-IP, Bldg, 4200 PIC | ter | 3 | | |
| Jol | John F. Kennedy Space Center MD MG MH ML, Mr Fedor RC-423 | | | | | |
| P. | 0. | Box 33 | Information Facility | _ | | |
| י ח | 100 | To Park Marriland 201 | 11.(3 | 2 | | |