


ENGINEERING DEPARTMENT
TECHNICAL REPORT

TR-RE-CCSD-FO-1020-3

April 3, 1967

SATURN IB PROGRAM



TEST REPORT
FOR

PRESSURE REGULATORS

Grove Valve and Regulator Company Part Numbers T-1538 and T-1541

NASA Drawing Numbers B75M50305-1 and B75M50305-4

N67-36615

FACILITY FORM 502

(ACCESSION NUMBER)

163

(PAGES)

CR-88213

(NASA CR OR TMX OR AD NUMBER)

(THRU)

0

(CODE)

15

(CATEGORY)

SPACE DIVISION



CHRYSLER
CORPORATION

TEST REPORT

FOR

PRESSURE REGULATORS

Grove Valve and Regulator Company Part Numbers T-1538 and T-1541

NASA Drawing Numbers B75M50305-1 and B75M50305-4

ABSTRACT

This report presents the results of tests performed on two **specimens each** of Pressure Regulators B75M50305-1 and B75M50305-4. The regulators differ only in orifice size. The B75M50305-1 has a 3/8-inch orifice, while the B75M50305-4 has a 1-inch orifice. The following tests were performed.

- | | |
|-------------------------|-----------------------|
| 1. Receiving Inspection | 4. Prolonged Pressure |
| 2. Proof Pressure | 5. Low Temperature |
| 3. Functional | 6. High Temperature |

The specimen performance was in accordance with the specification requirements of NASA drawing B75M50305 with the following exceptions:

1. The proof pressure of 9000 psig, applied to specimen 1 at all three ports simultaneously, resulted in permanent structural deformation of the regulator dome and body. The dome and outlet proof pressure requirement was reduced to 5250 psig. No permanent structural deformation resulted on samples 2, 3, and 4 after this revision. However, all three leaked excessively at the body plug at an inlet pressure above 8000 psig.
2. The low temperature test resulted in excessive external leakage at the dome and regulator body interface. It was determined that this external leakage occurred at specimen temperatures of +5°F and below. Some of the body bolt torque values were below the specified value when measured at low temperature.
3. The high temperature test resulted in excessive external leakage at the regulator body plug. The body plug torque values were below the specified value when measured at high temperature.

TEST REPORT

FOR

PRESSURE REGULATORS

Grove Valve and Regulator Company Part Numbers T-1538 and T-1541

NASA Drawing Numbers B75M50305-1 and B75M50305-4

April 3, 1967

CHRYSLER CORPORATION SPACE DIVISION - NEW ORLEANS, LOUISIANA

FOREWORD

The tests reported herein were conducted for the John F. Kennedy Space Center by Chrysler Corporation Space Division (CCSD), New Orleans, Louisiana. This document was prepared by CCSD under contract NAS 8-4016, Part VII, CWO 271620.

TABLE OF CONTENTS

| <u>Section</u> | | <u>Page</u> |
|----------------|-----------------------------------|-------------|
| I | INTRODUCTION | 1-1 |
| II | RECEIVING INSPECTION | 2-1 |
| III | PROOF PRESSURE TEST | 3-1 |
| IV | FUNCTIONAL TEST | 4-1 |
| V | PROLONGED PRESSURE TEST | 5-1 |
| VI | LOW TEMPERATURE TEST | 6-1 |
| VII | HIGH TEMPERATURE TEST | 7-1 |

LIST OF ILLUSTRATIONS


| <u>Figure</u> | | <u>Page</u> |
|---------------|--|-------------|
| FRONTISPIECE | | vi |
| 2-1 | DIMENSIONS FOR RECEIVING INSPECTION TEST | 2-3 |
| 2-2 | RECEIVING INSPECTION | 2-4 |
| 3-1 | PROOF PRESSURE TEST SCHEMATIC | 3-5 |
| 3-2 | DOMO O-RING SEAL FAILURE | 3-6 |
| 3-3 | DEFORMED REGULATOR BODY | 3-7 |
| 3-4 | DEFORMED DOME | 3-8 |
| 3-5 | PROOF PRESSURE TEST SETUP | 3-9 |
| 4-1 | FUNCTIONAL TEST SCHEMATIC | 4-12 |
| 4-2 | FUNCTIONAL TEST SETUP | 4-13 |
| 5-1 | PROLONGED PRESSURE TEST SCHEMATIC | 5-8 |
| 5-2 | PROLONGED PRESSURE TEST SETUP | 5-9 |
| 6-1 | LOW TEMPERATURE TEST SETUP | 6-11 |
| 7-1 | HIGH TEMPERATURE TEST SETUP | 7-6 |

LIST OF TABLES

| <u>Table</u> | | <u>Page</u> |
|--------------|--|-------------|
| 2-1 | RECEIVING INSPECTION EQUIPMENT LIST | 2-2 |
| 2-2 | DIMENSIONAL DATA | 2-2 |
| 3-1 | PROOF PRESSURE TEST EQUIPMENT LIST | 3-3 |
| 3-2 | PROOF PRESSURE TEST DATA | 3-4 |
| 4-1 | FUNCTIONAL TEST EQUIPMENT LIST | 4-5 |
| 4-2 | INITIAL FUNCTIONAL DATA FOR SPECIMEN 2 | 4-9 |
| 4-3 | INITIAL FUNCTIONAL DATA FOR SPECIMEN 3 | 4-10 |
| 4-4 | INITIAL FUNCTIONAL DATA FOR SPECIMEN 4 | 4-11 |

LIST OF TABLES (CONTINUED)

| <u>Table</u> | | <u>Page</u> |
|--------------|---|-------------|
| 5-1 | PROLONGED PRESSURE TEST EQUIPMENT LIST | 5-3 |
| 5-2 | SPECIMEN 4 FUNCTIONAL TEST DATA BEFORE PROLONGED PRESSURE TEST | 5-5 |
| 5-3 | SPECIMEN 4 FUNCTIONAL TEST DATA AFTER PROLONGED PRESSURE TEST | 5-6 |
| 5-4 | PRESSURE FLUCTUATION DATA DURING PROLONGED PRESSURE TEST . | 5-7 |
| 6-1 | SPECIMEN 2 FUNCTIONAL TEST DATA PRIOR TO LOW TEMPERATURE TEST | 6-3 |
| 6-2 | SPECIMEN 2 FUNCTIONAL TEST DATA AT -65°F LOW TEMPERATURE TEST | 6-4 |
| 6-3 | SPECIMEN 2 FUNCTIONAL TEST DATA AFTER -65°F LOW TEMPERATURE TEST | 6-5 |
| 6-4 | SPECIMEN 3 FUNCTIONAL TEST DATA PRIOR TO LOW TEMPERATURE TEST | 6-6 |
| 6-5 | SPECIMEN 3 FUNCTIONAL TEST DATA AT +5°F LOW TEMPERATURE TEST | 6-7 |
| 6-6 | SPECIMEN 3 FUNCTIONAL TEST DATA AFTER +5°F LOW TEMPERATURE TEST | 6-8 |
| 6-7 | SPECIMEN 3 FUNCTIONAL TEST DATA DURING -65°F LOW TEMPERATURE TEST | 6-9 |
| 6-8 | BODY BOLT TORQUE VALUES FOR SPECIMEN 3 AT AMBIENT AND LOW TEMPERATURE | 6-10 |
| 7-1 | SPECIMEN 2 FUNCTIONAL TEST DATA DURING HIGH TEMPERATURE TEST | 7-2 |
| 7-2 | SPECIMEN 2 FUNCTIONAL TEST DATA AFTER HIGH TEMPERATURE TEST | 7-3 |
| 7-3 | SPECIMEN 3 FUNCTIONAL TEST DATA DURING HIGH TEMPERATURE TEST | 7-4 |
| 7-4 | SPECIMEN 3 FUNCTIONAL TEST DATA AFTER HIGH TEMPERATURE TEST | 7-5 |



Pressure Regulator

CHECK SHEET

FOR

PRESSURE REGULATORS

MANUFACTURER: Grove Valve and Regulator Company

MANUFACTURER'S PART NUMBERS: T-1538 and T-1541

NASA DRAWING NUMBERS: B75M50305-1, Rev. K, B75M50305-4, Rev. K

TESTING AGENCY: Chrysler Corporation Space Division, New Orleans, Louisiana

AUTHORIZING AGENCY: NASA KSC

I. FUNCTIONAL REQUIREMENTS

- A. OPERATING PRESSURE:
 - 1. INLET PRESSURE: 6000 psig maximum
 - 2. OUTLET PRESSURE: 0 to 3500 psig
- B. PROOF PRESSURE: 9000 psig inlet, 5250 psig dome and outlet
- C. BURST PRESSURE: 24,000 psig
- D. OPERATING MEDIUM: Dry air, nitrogen, or helium
- E. LEAKAGE: Bubble tight
- F. FLOW: Monodirectional, orifice diameter -
P/N T-1538, 3/8-inch
P/N T-1541, 1-inch

II. CONSTRUCTION

- A. MATERIAL: Metal parts in flow stream are stainless steel. Nonmetallic parts in flow stream are nylon and Teflon.
 - 1. BODY: 18/8 CRES
 - 2. SEATS: Nylon
 - 3. DIAPHRAGM: Nitrite rubber
 - 4. O-RINGS: Rev MIL-G-5510, MIL-P-5315 or MIL-P-5516
- B. PNEUMATIC CONNECTIONS:
 - 1. INLET: 1 1/2 inch Grayloc, P/N GR14/XXS/316SS
 - 2. OUTLET: 1 1/2 inch Grayloc Flange, P/N GR14 160S 316SS
 - 3. DOME: Per MC240-4
- C. MOUNTING ATTITUDE: Dome flange in horizontal plane

III. ENVIRONMENTAL REQUIREMENTS

OPERATING TEMPERATURE: -65 to +160°F

IV. SPECIAL REQUIREMENTS

CLEANING SPECIFICATION: A10M01671, Level IV

V. LOCATION AND USE:

Pneumatic Distribution System to reduce storage vessel pressure to working pressure in pneumatic control distribution systems 1 and 2 for GN₂ and He.

TEST SUMMARY

PRESSURE REGULATORS

B75M50305-1 and B75M50305-4

| Environment | Units | Operational Boundary | Test Objective | Test Results | Remarks |
|----------------------|-------|--|---|----------------|------------------|
| Receiving Inspection | 4 | Specifications and drawings | Conformance with drawings and specifications | Satisfactory | |
| Proof Pressure | 4 | 9000 psig inlet 5250 psig outlet and dome | Check for leakage and distortion | Unsatisfactory | External leakage |
| Functional | 4 | 6000 psig inlet 0 to 3500 psig outlet | Check seat and external leakage, repeatability, and stability | Satisfactory | Test completed |
| Prolonged Pressure | 2 | 30 days | Determine if specimen operation is impaired by prolonged pressure | Satisfactory | Test completed |
| Low Temperature | 2 | -65 (+0, -4)°F | Determine if specimen operation is impaired by low temperature | Unsatisfactory | External leakage |
| High Temperature | 2 | 160 (+4, -0)°F | Determine if specimen operation is impaired by high temperature | Unsatisfactory | External leakage |

SECTION I

INTRODUCTION

1.1 SCOPE

1.1.1 This report presents the results of tests that were performed to determine if Pressure Regulators B75M50305-1, Rev K, and B75M50305-4, Rev K, meet the operational and environmental requirements for the John F. Kennedy Space Center Launch Complexes 34 and 37. A summary of the test results is presented on page viii.

1.1.2 Four pressure regulators (two B75M50305-1, Rev K, and two B75M50305-4, Rev K) were numbered specimens 1 through 4 for identification purposes; specimens 1 and 2 refer to B75M50305-1, Rev K, and 3 and 4 refer to B75M50305-4, Rev K. See table 2-2 for specimen serial numbers.

1.2 ITEM DESCRIPTION

1.2.1 Pressure Regulators B75M50305 are dome-loaded pneumatic regulators. They are designed for use with dry air, gaseous nitrogen, or helium. Orifices of 0.375 and 1.000 inch are in B75M50305-1 and B75M50305-4, respectively. The regulators are designed to reduce an inlet pressure of 6000 psig to an outlet pressure ranging from 0 to 3500 psig. The regulators are manufactured by Grove Valve and Regulator Company.

1.3 APPLICABLE DOCUMENTS

1.3.1 The documents used in this test report are as follows:

- a. 75M50305, Rev K, Component Specification
- b. KSC-STD-164(D), Environmental Test Methods
- c. A10M01671, Cleanliness Requirement
- d. Test Plan CCSD-FO-1020-1R, Test Requirements
- e. Test Procedure TP-RE-CCSD-FO-1020-2R

SECTION II

RECEIVING INSPECTION

2.1 REQUIREMENTS

- 2.1.1 Test specimens 1 and 2 shall be checked for conformance with NASA drawing B75M50305-1, Rev K, and applicable specifications. Test specimens 3 and 4 shall be checked for conformance with NASA drawing B75M50305-4, Rev K, and applicable specifications. Each specimen shall be checked to the extent possible without disassembly of the test specimen and shall also be inspected for poor workmanship and manufacturing defects. The specimens shall be checked for vendor certification of the presence of the dome plate with a spiraled groove.

2.2 PROCEDURE

Specimens 1 and 2 were checked for conformance with NASA drawing B75M50305-1, Rev K, and specimens 3 and 4 were checked for conformance with NASA drawing B75M50305-4, Rev K.

- 2.2.2 Checks were made for defective threads and welds.

- 2.2.3 Checks were made for damage to end fittings.

2.3 TEST RESULTS

The receiving inspection test results were satisfactory.

2.4 TEST DATA

The dimensional data are presented in table 2-2.

Table 2-1. Receiving Inspection Equipment List

| Item No. | Item | Manufacturer | Model/ Part No. | Serial No. | Remarks |
|----------|------------|------------------|--------------------|--------------------|--|
| 1 | Scale | Brown and Sharpe | 300-24" | NASA 101-1013 | 24 inches long Cal date 7-23-64 |
| 2 | Micrometer | Starrett | 239 3"-4" | NASA 49- 1611-A | 3 to 4 inch range Cal date 8-16-66 |
| 3 | Micrometer | Starrett | 436 13"- 14" | NASA 49- 1375-A | 13 to 14 inch range Cal date 9-6-66 |
| 4 | Calipers | Union Tool | NA | NA | Internal |

Table 2-2. Dimensional Data

| Dimension* | Allowable (Inches) | Specimen (Inches) | | | |
|----------------|--------------------------------|-------------------|-------------------|-------------------|-------------------|
| | | 1 S/N 106869-1 | 2 S/N 106869-2 | 3 S/N 106870-1 | 4 S/N 106870-2 |
| A | 10-1/4 ($\pm 1/32$) Dia. | 10-7/32 | 10-1/4 | 10-7/32 | 10-7/32 |
| B _O | 1.338 ($\pm 1/16$) I.D. Dia. | 1.340 | 1.350 | 1.360 | 1.350 |
| B _I | 1.100 ($\pm 1/16$) I.D. Dia. | 1.100 | 1.100 | 1.125 | 1.120 |
| C | 14 ($\pm 1/8$) | 13.981 | 13.953 | 13.988 | 14.105 |
| D | 13-1/2 ($\pm 1/16$) | 13.524 | 13.458 | 13.50 | 13.420 |
| E _O | 3.125 ($\pm 1/16$) O.D. Dia. | 3.1245 | 3.126 | 3.1270 | 3.126 |
| E _I | 3.125 ($\pm 1/16$) O.D. Dia. | 3.1245 | 3.1225 | 3.1270 | 3.123 |

* See figure 2-1 for dimensions identification.




Figure 2-1. Dimensions For Receiving Inspection Test




Figure 2-2. Receiving Inspection

SECTION III

PROOF PRESSURE TEST

3.1 TEST REQUIREMENTS

- 3.1.1 Each specimen shall be subjected to a proof pressure of 9000 psig at the inlet and 5250 psig at the dome and outlet.*
- 3.1.2 Proof pressure shall be maintained for 5 minutes.
- 3.1.3 Leakage shall be monitored during this test.

3.2 TEST PROCEDURE

- 3.2.1 The proof pressure test setup was assembled as shown in figures 3-1 and 3-5 using the equipment listed in table 3-1.
- 3.2.2 Regulator 4 was adjusted for zero outlet pressure. Hand valves 6 and 7 were closed.
- 3.2.3 Hand valve 9 was slowly opened. Gage 10 indicated 10,000 psig.
- 3.2.4 Regulator 4 was adjusted to provide an outlet pressure of 9000 psig as indicated on gage 5.* This pressurized the inlet port of the test specimen.
- 3.2.5 This proof pressure was maintained for 5 minutes. Leakage was monitored by checking for bubbles in the water tank. No leakage is allowed.
- 3.2.6 Hand valve 9 was closed.
- 3.2.7 Hand valve 6 was slowly opened to vent the system.
- 3.2.8 The specimen was examined for damage or deformation resulting from this test.
- 3.2.9 Regulator 4 was adjusted for zero outlet pressure. Hand valves 6 and 11 were closed. Hand valve 7 was opened.
- 3.2.10 Hand valve 9 was slowly opened. Gage 4 indicated 10,000 psig.
- 3.2.11 Regulator 4 was adjusted to provide an outlet pressure of 5250 psig as indicated on gage 5. This simultaneously pressurized the inlet, outlet, and dome parts of the specimen.
- 3.2.12 A proof pressure of 5250 psig was maintained for 5 minutes. Leakage was monitored by checking for bubbles in the water tank. No leakage is allowed.

* Note: The proof pressure requirement was originally 9000 psig on the outlet, inlet, and dome.

- 3.2.13 Hand valve 9 was closed.
- 3.2.14 Hand valve 3 was slowly opened to vent the system.
- 3.2.15 The specimen was examined for damage or distortion resulting from this test.

3.3 TEST RESULTS

- 3.3.1 Sample 1 was proof pressure tested to the original test requirement of 9000 psig on all ports. The dome O-ring seal ruptured at 8800 psig. The dome O-ring is shown in figure 3-2. Further investigation revealed that the valve body and the dome had permanently deformed. This is shown in figures 3-3 and 3-4 respectively.
- 3.3.2 Samples 2, 3, and 4 were proof pressure tested as per the present test requirement. No structural deformation occurred, although all three leaked excessively at the body plug before the required inlet proof pressure was reached.

3.4 TEST DATA


Proof pressure test data are presented in table 3-2.

Table 3-1. Proof Pressure Test Equipment List

| Item No. | Item | Manufacturer | Model/ Part No. | Serial No. | Remarks |
|----------|------------------------|---------------------------|--------------------|------------|---|
| 1 | Specimen 1 | Grove Valve and Regulator | T-1538 | 106869-1 | Dome regulator |
| | Specimen 2 | Grove Valve and Regulator | T-1538 | 106869-2 | Dome regulator |
| | Specimen 3 | Grove Valve and Regulator | T-1541 | 106870-1 | Dome regulator |
| | Specimen 4 | Grove Valve and Regulator | T-1541 | 107870-2 | Dome regulator |
| 2 | GN ₂ Source | CCSD | | | 10,000-psig |
| 3 | Filter | Microporous | 4813-2DM | | 2-micron |
| 4 | Regulator | Tescom Corp. | 26-1021-20 | 3024 | 10,000-psig inlet 0-to 10,000-psig outlet |
| 5 | Pressure Gage | Heise | H34955 | 014231 | 0-to 10,00-psig +0.25% FS Cal date 10/30/66 |
| 6 | Hand Valve | Grove | KA 2B | | 10,000-psig |
| 7 | Hand Valve | Grove | KA 2B | | 10,000-psig |
| 8 | Tank | Local Mfg. | | | Detonized water |
| 9 | Hand Valve | Grove | KA 2B | | 10,000-psig |
| 10 | Pressure Gage | Ashcroft | | 200613- | 0-to 20,000-psig +0.25% FS Cal date 10/30/66 |
| 11 | Hand Valve | Grove | KA 2B | | 10,000-psig |

Table 3-2. Proof Pressure Test Data

| Specimen | Proof Pressure (psig) | | Pressurization Time | Results |
|----------|-----------------------|-------------|------------------------|---|
| | Inlet | Outlet/Dome | | |
| 1 | 8800 | 8800 | NA | Dome seal ruptured at 8800 psig |
| 2 | 9000 | 5250 | 5 | Excessive body plug leakage above 8300 psig |
| 3 | 9000 | 5250 | 5 | Excessive body plug leakage above 8200 psig |
| 4 | 9000 | 5250 | 5 | Excessive body plug leakage above 7400 psig |



Note: All lines $\frac{1}{4}$ inch.
Refer to table 3-1 for item identification.

Figure 3-1. Proof Pressure Test Schematic




Figure 3-2. Dome O-Ring Seal Failure




Figure 3-3. Deformed Regulator Body




Figure 3-4. Deformed Dome




Figure 3-5. Proof Pressure Test Setup.

SECTION IV

FUNCTIONAL TEST

4.1 TEST REQUIREMENTS

- 4.1.1 With the specimen set for zero flow and its inlet port pressurized to 6000 psig, the specimen shall be checked for internal and external leakage.
- 4.1.2 With the outlet port of the specimen pressurized to 3000 (+40) psig, the specimen shall be checked for leakage into the dome. No leakage shall be allowed.
- 4.1.3 With the dome of the test specimen pressurized to 500 (+10) psig, the specimen shall be checked for leakage past the diaphragm. No leakage shall be allowed.
- 4.1.4 With the inlet port of the specimen pressurized to 6000 psig and the dome pressure set to yield an outlet pressure of 750 psig, determine that the dome pressure agrees with the following formula within ± 5 per cent:

$$\text{Specimens 1 and 2: } P_{\text{dome}} = 0.3 \frac{(P_{\text{inlet}} - P_{\text{outlet}})}{100} + P_{\text{outlet}}$$

$$\text{Specimens 3 and 4: } P_{\text{dome}} = 2.0 \frac{(P_{\text{inlet}} - P_{\text{outlet}})}{100} + P_{\text{outlet}}$$

Check for repeatability of the dome pressure by cycling the downstream shutoff valve five times. Outlet and dome pressure shall return to within ± 2 per cent when the downstream valve is closed.

- 4.1.5 With the inlet port of the specimen pressurized to 6000 psig, the dome pressure shall be cycled five times with outlet port vented from zero to the pressure determined in 4.1.4. After the fifth cycle, a leakage check shall be made between the inlet and outlet ports (10 sccm maximum leakage is allowable).
- 4.1.6 The procedures described in paragraphs 4.1.4 and 4.1.5 shall be repeated for outlet pressures of 1500 psig and 3000 psig.
- 4.1.7 The initial functional test shall be performed three times each with GN₂ and GHe as test media. All subsequent functional tests shall be performed three times with GN₂ as the only test medium, except where specified.

4.2 TEST PROCEDURE

- 4.2.1 The functional test setup was assembled as shown in figures 4-1 and 4-2 using the equipment listed in table 4-1.

- 4.2.2 All hand valves were closed and all regulators were adjusted for zero outlet pressure.
- 4.2.3 Hand valves 11, 17, 19, 29, 30 and 33 were opened.
- 4.2.4 Regulator 7 was adjusted as required to load regulator 7A to provide a specimen inlet pressure, as indicated on gage 9, of 6000 psig. This pressure was maintained for 5 minutes while monitoring flowmeter 18 for leakage. Maximum allowable leakage is 10 sccm.
- 4.2.5 During this period, a check was made for specimen external leakage by using soap solution. No external leakage is allowed.
- 4.2.6 Hand valve 17 was closed.
- 4.2.7 Hand valve 23 was opened. Regulator 7 was readjusted as required to load regulator 7A to provide 4500 psig as indicated by gage 9.
- 4.2.8 Hand valves 12 and 35 were slowly opened. Gages 9 and 13 indicated 4500 psig. This condition was maintained for five minutes while checking for leakage (utilizing water displacement method) into the dome. No bubble leakage is allowed.
- 4.2.9 Regulator 7 was adjusted to provide zero outlet pressure. Hand valve 36 was cracked to vent pressure until gages 9 and 13 indicated zero pressure. Hand valve 17 was opened. Hand valves 23 and 36 were closed.
- 4.2.10 Hand valves 10, 20, and 32 were opened. Regulator 6 was adjusted to provide a specimen dome pressure of 3000 psig as indicated by gages 8 and 37. This pressure was maintained for 5 minutes while checking for leakage past the diaphragm. No leakage is allowed.
- 4.2.11 Regulator 6 was adjusted for zero outlet pressure. Hand valve 27 was cracked to vent pressure until gage 37 indicated zero pressure. Hand valves 12, 17, and 27 were closed.
- 4.2.12 Regulator 7A was adjusted to provide a specimen inlet pressure, as indicated by gage 9, of 6000 psig.
- 4.2.13 Regulator 6 was adjusted to pressurize the specimen dome until a specimen outlet pressure of 750 psig, as indicated on gage 13, was obtained.
- 4.2.14 Specimen dome pressure was recorded as indicated on gage 8. This value was compared with the theoretical dome pressure as calculated using the formula in 4.1.4. The actual dome pressure must be within ± 5 per cent of the theoretical pressure.

- 4.2.15 Solenoid valve 14 was opened and closed for five cycles. Then, with solenoid valve 14 closed, the pressures indicated on gages 13 and 38 were within ± 2 per cent of the previous recorded pressures.
- 4.2.16 Regulator 6 was adjusted for zero outlet pressure. Hand valve 27 was cracked to vent pressure until gage 8 indicated zero pressure. Hand valve 27 was closed.
- 4.2.17 Hand valve 36 was cracked to vent specimen outlet pressure until gage 13 indicated zero pressure. Solenoid valve 14 was opened and hand valve 36 was closed.
- 4.2.18 Using regulator 6 and hand valve 27, the specimen dome was alternately pressurized to the actual pressure determined in 4.2.14 and vented to zero for five cycles. After the last cycle, gage 8 indicated zero pressure, and gage 9 indicated 6000 psig. While maintaining these conditions, hand valve 17 was opened and solenoid valve 14 was closed. Flowmeter 18 was monitored for indication of leakage. The maximum leakage allowable is 10 sccm.
- 4.2.19 Hand valves 17 and 27 were closed.
- 4.2.20 The procedures described in 4.2.13 through 4.2.19 were repeated using a specimen outlet pressure of 1500 psig.
- 4.2.21 The procedures described in 4.2.13 through 4.2.19 were repeated using a specimen outlet pressure of 3000 psig.
- 4.2.22 For the initial functional test, the steps in paragraphs 4.2.1 through 4.2.21 were repeated three times using GHe as test medium and three times using GN₂ as test medium. For all subsequent functionals, steps in paragraphs 4.2.1 through 4.2.21 were repeated three times using only GN₂ as test medium unless otherwise specified.
- 4.2.23 Upon completion of the last test, hand valves 19 and 20 were closed. Hand valve 34 was opened. Hand valve 12 was slowly opened. Hand valve 27 was opened and regulator 6 was adjusted for maximum outlet pressure. All gages indicated zero pressure.
- 4.2.24 The specimen was visually examined for evidence of damage or distortion.
- 4.2.25 All test data were recorded.

4.3 TEST RESULTS

Samples 2, 3 and 4 completed the initial functional test satisfactorily.

4.4

TEST DATA

4.4.1

Initial functional test data are shown in tables 4-2, 4-3 and 4-4.

Table 4-1. Functional Test Equipment List

| Item No. | Item | Manufacturer | Model/ Part No. | Serial No. | Remarks |
|----------|--|---------------------------|--------------------|------------|--|
| 1 | Specimen 1 | Grove Valve and Regulator | T-1538 | 106869-1 | Dome regulator |
| | Specimen 2 | Grove Valve and Regulator | T-1538 | 106869-2 | Dome regulator |
| | Specimen 3 | Grove Valve and Regulator | T-1541 | 106870-1 | Dome regulator |
| | Specimen 4 | Grove Valve and Regulator | T-1541 | 106870-2 | Dome regulator |
| 2 | GH ₂ & GN ₂ Source | CCSD | | | 10,000-psig |
| 3 | GH ₂ & GN ₂ Source | CCSD | | | 10,000-psig |
| 4 | Filter | Fluid Dynamics | FL-20-8 BB | | 2-micron |
| 5 | Filter | Fluid Dynamics | FL-20-8 BB | | 2-micron |
| 6 | Regulator | Tescom Corp | 26-1021- 20 | 3024 | 10,000-psig inlet 0-to 10,000-psig outlet |
| 7 | Regulator | Tescom | 26-1021- 10 | 1529 | 10,000-psig inlet 0-to 10,000- psig outlet |
| 7A | Dome Regulator | Grove | 201-B | RA-7049 | 10,000-psig inlet 0-to 10,000-psig outlet |
| 8 | Pressure Gage | Heise | H34955 | 014231 | 0-to 10,000-psig +0.1% FS Cal date 10/31/66 |
| 9 | Pressure Gage | Heise | H35838 | 200595-P | 0-to 10,000-psig +0.1 FS Cal date 10/31/66 |

Table 4-1. Functional Test Equipment List (Continued)

| Item No. | Item | Manufacturer | Model/ Part No. | Serial No. | Remarks |
|----------|----------------|-----------------|--------------------|---------------|--|
| 10 | Hand Valve | Aminco | 13126 | NA | 30,000-psig ±0.1% FS Cal date 10-3-66 |
| 11 | Hand Valve | Grove | KA2B | NA | 10,000-psig |
| 12 | Hand Valve | Robbins | SSKG-250 -4T | NA | 10,000-psig |
| 13 | Pressure Gage | Heise | H35840 | 200616E | 10,000-psig ±0.25% FS Cal date 12-1-66 |
| 14 | Solenoid Valve | Marotta | MV583 | 370 | 6000-psig |
| 15 | Switch | Ind. Lab., Inc. | NA | NA | SPST |
| 16 | Power Supply | Perkin | MRST-28- 300 | 63-293 | 28-vdc |
| 17 | Hand Valve | Robbins | SSKG-250 -4T | NA | 6000-psig |
| 18 | Flowmeter | Local Mfg. | NA | NA | Water dis- placement |
| 19 | Hand Valve | Grove | KA2B | NA | 10,000-psig |
| 20 | Hand Valve | Aminco | 13126 | NA | 30,000-psig |
| 21 | Pressure Gage | Ashcroft | NA | 200613- 3 | 0 to 20,000- psig |
| 22 | Pressure Gage | Ashcroft | NA | 95-1508 -B | 20,000-psig ±0.25% FS Cal date 10-11-66 |
| 23 | Hand Valve | Robbins | SSKG-250 -4T | NA | 6000-psig |
| 24 | Flowmeter | Local Mfg. | NA | NA | Water dis- placement |

Table 4-1. Functional Test Equipment List (Continued)

| Item No. | Item | Manufacturer | Model/ Part No. | Serial No. | Remarks |
|----------|----------------|--------------------|--------------------|------------|---|
| 25 | Temp. Chamber | Local Mfg. | NA | NA | NA |
| 26 | Thermocouple | Conax Corp. | Type T | NA | NA |
| 27 | Hand Valve | Aminco | 13126 | NA | 30,000-psig |
| 28 | Pressure Gage | Ashcroft | NA | 200613-10 | 0 to 10,000-psig $\pm 0.25\%$ FS Cal date 10-11-66 |
| 29 | Hand Valve | Grove | KA2B | NA | 10,000-psig |
| 30 | Hand Valve | Cardair | 3510-0077 | NA | 10,000-psig |
| 31 | Hand Valve | Hoke | 100 G | NA | 30,000-psig |
| 32 | Hand Valve | Aminco | 13126 | NA | 30,000-psig |
| 33 | Hand Valve | Robbins | SSKG-250-4T | NA | 6000-psig |
| 34 | Hand Valve | Robbins | SSKG-250-4T | NA | 6000-psig |
| 35 | Hand Valve | Robbins | SSKG-250-4T | NA | 6000-psig |
| 36 | Hand Valve | Robbins | SSKG-250-4T | NA | 6000-psig |
| 37 | Pressure Gage | Ashcroft | NA | 95-1509-B | 0 to 10,000-psig $\pm 0.25\%$ FS Cal date 10-11-66 |
| 38 | Relief Valve | Anderson-Greenwood | 83 JC | NA | 6000-psig |
| 39 | Temp. Recorder | Honeywell | Y1530 | 019417 | -110 to +525°F Cal date 11-23-66 |
| 40 | Thermatron | Thermatron | NA | 200895-13 | -130 to +430°F Cal date 8-29-66 |

Table 4-1. Functional Test Equipment List (Continued)

| Item No. | Item | Manufacturer | Model/ Part No. | Serial No. | Remarks |
|----------|------------------------|----------------|--------------------|------------|------------------------|
| 41 | Solenoid Valve | Marotta | MV583 | 380 | 6000-psig |
| 42 | Hand Valve | Grove | KA2B | NA | 6000-psig |
| 43 | GN ₂ Source | CCSD | NA | NA | 3000-psig |
| 44 | Thermocouple | Honeywell | NA | NA | -150 to +400°F |
| 45 | Filter | Fluid Dynamics | FL-20-8 BB | NA | 2-micron |
| 46 | LN ₂ Source | Airco | 150-5T | 251 | Portable 150-gallon |

Table 4-2. Initial Functional Test Data For Specimen 2


| Run | | 1 | 2 | 3 | 4 | 5 | 6 |
|--------------------------------------|-------------------------------|---------------------------------|----------------|----------------|------|------|------|
| Media | | N ₂ | N ₂ | N ₂ | He | He | He |
| Test | Procedure Reference Paragraph | Allowable Value | | | | | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 | 0 | 0 | 0 | 0 |
| External Leakage | 4.1.1 | No leakage | 0 | 0 | 0 | 0 | 0 |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 | 0 | 0 | 0 | 0 |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 | 0 | 0 | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 780 | 780 | 775 | 780 | 775 |
| Calculated Dome Pressure | 4.1.4 | +2% of dome and outlet pressure | 765 | 765 | 765 | 765 | 765 |
| Regulator Stability | 4.1.4 | | OK | OK | OK | OK | OK |
| Seat Leakage After Cycling 750-psig | 4.1.5 | 10 sccm | 0 | 0 | 0 | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 1530 | 1530 | 1525 | 1515 | 1520 |
| Calculated Dome Pressure | 4.1.4 | +2% of dome and outlet pressure | 1513 | 1513 | 1513 | 1513 | 1513 |
| Regulator Stability | 4.1.4 | | OK | OK | OK | OK | OK |
| Seat Leakage After Cycling 1500-psig | 4.1.5 | 10 sccm | 0 | 0 | 0 | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 3010 | 3010 | 3010 | 3010 | 3010 |
| Calculated Dome Pressure | 4.1.4 | +2% of dome and outlet pressure | 3009 | 3009 | 3009 | 3009 | 3009 |
| Regulator Stability | 4.1.4 | | OK | OK | OK | OK | OK |
| Seat Leakage After Cycling 3000-psig | 4.1.5 | 10 sccm | 0 | 0 | 0 | 0 | 0 |

Table 4-3. Initial Functional Test Data For Specimen 3

| Run | | 1 | 2 | 3 | 4 | 5 | 6 |
|--------------------------------------|-------------------------------|---------------------------------|----------------|----------------|------|------|------|
| Media | | N ₂ | N ₂ | N ₂ | He | He | He |
| Test | Procedure Reference Paragraph | Allowable Value | | | | | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 | 0 | 0 | 0 | 0 |
| External Leakage | 4.1.1 | No leakage | 0 | 0 | 0 | 0 | 0 |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 | 0 | 0 | 0 | 0 |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 | 0 | 0 | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 870 | 860 | 870 | 870 | 870 |
| Calculated Dome Pressure | 4.1.4 | +2% of dome and outlet pressure | 855 | 855 | 855 | 855 | 855 |
| Regulator Stability | 4.1.4 | | OK | OK | OK | OK | OK |
| Seat Leakage After Cycling 750-psig | 4.1.5 | 10 sccm | 0 | 0 | 0 | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 1600 | 1615 | --- | --- | --- |
| Calculated Dome Pressure | 4.1.4 | +2% of dome and outlet pressure | 1590 | 1590 | 1590 | 1590 | 1590 |
| Regulator Stability | 4.1.4 | | OK | OK | OK | OK | OK |
| Seat Leakage After Cycling 1500-psig | 4.1.5 | 10 sccm | 0 | 0 | 0 | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 3070 | 3070 | --- | --- | --- |
| Calculated Dome Pressure | 4.1.4 | +2% of dome and outlet pressure | 3060 | 3060 | 3060 | 3060 | 3060 |
| Regulator Stability | 4.1.4 | | OK | OK | OK | OK | OK |
| Seat Leakage After Cycling 3000-psig | 4.1.5 | 10 sccm | 0 | 0 | 0 | 0 | 0 |

Table 4-4. Initial Functional Test Data For Specimen 4

| Test | Procedure Reference Paragraph | Run | | | | | |
|--------------------------------------|-------------------------------|----------------|----------------|----------------|------|------|------|
| | | Media | | | | | |
| | | 1 | 2 | 3 | 4 | 5 | 6 |
| | | N ₂ | N ₂ | N ₂ | He | He | He |
| Seat Leakage | 4.1.1 | 0 | 0 | 0 | 0 | 0 | 0 |
| External Leakage | 4.1.1.1 | 0 | 0 | 0 | 0 | 0 | 0 |
| Reverse Dome Leakage | 4.1.1.2 | 0 | 0 | 0 | 0 | 0 | 0 |
| Forward Dome Leakage | 4.1.1.3 | 0 | 0 | 0 | 0 | 0 | 0 |
| Actual Dome Pressure | 4.1.1.4 | 870 | 875 | 870 | 865 | 860 | 865 |
| Calculated Dome Pressure | 4.1.1.4 | 855 | 855 | 855 | 855 | 855 | 855 |
| Regulator Stability | 4.1.1.4 | OK | OK | OK | OK | OK | OK |
| Seat Leakage After Cycling 750-psig | 4.1.5 | 0 | 0 | 0 | 0 | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | 1590 | 1600 | 1595 | 1605 | 1610 | 1590 |
| Calculated Dome Pressure | 4.1.4 | 1590 | 1590 | 1590 | 1590 | 1590 | 1590 |
| Regulator Stability | 4.1.4 | OK | OK | OK | OK | OK | OK |
| Seat Leakage After Cycling 1500-psig | 4.1.5 | 0 | 0 | 0 | 0 | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | 3070 | 3075 | 3070 | 3080 | 3070 | 3070 |
| Calculated Dome Pressure | 4.1.4 | 3060 | 3060 | 3060 | 3060 | 3060 | 3060 |
| Regulator Stability | 4.1.4 | OK | OK | OK | OK | OK | OK |
| Seat Leakage After Cycling 3000-psig | 4.1.5 | 0 | 0 | 0 | 0 | 0 | 0 |



Note: All lines 1/4-inch unless otherwise indicated.
Refer to table 4-1 for item identification.

Figure 4-1. Functional Test Schematic

SECTION V

PROLONGED PRESSURE TEST

5.1 TEST REQUIREMENTS

5.1.1 A prolonged pressure test will be performed on test specimens 2 and 4 while the specimens are pressurized with GHe to 6000 psig inlet port pressure and set to provide 3000 psig outlet port pressure to determine whether degradation or deformation occurs.

5.1.2 The prolonged pressure shall continue for 30 days.

5.1.3 External and internal leakage shall be monitored.

5.1.4 Monitor any fluctuation or variation in dome, inlet port, and outlet port pressure.

5.2 TEST PROCEDURE

5.2.1 The prolonged pressure test setup was assembled as shown in figures 5-1 and 5-2 using the equipment listed in table 5-1.

5.2.2 A functional test was performed because more than 72 hours had elapsed since the previous functional test.

5.2.3 All hand valves were closed and all regulators were adjusted for zero outlet pressure.

5.2.4 Hand valve 11 was opened. Regulator 7 was adjusted to provide a specimen inlet pressure, as indicated on gage 9, of 6000 psig, using GHe as the test medium.

5.2.5 Hand valve 15 was opened. Regulator 6 was adjusted to provide a specimen outlet pressure, as indicated on gage 19, of 3000 psig.

5.2.6 The conditions of 5.2.4 and 5.2.5 were maintained for 30 days. During this period, the specimen was examined for evidence of external or internal leakage and any variations in dome, inlet, and outlet pressure were noted.

5.2.7 Hand valves 11 and 15 were closed. Hand valves 13 and 14 were cracked until gages 9, 10, and 20 indicated zero pressure. Then, hand valve 17 was cracked until gages 8, 18 and 19 indicated zero pressure.

5.2.8 Immediately following this test, a functional test using GHe as the test medium was conducted.

5.2.9 Test data were recorded.

5.3

TEST RESULTS

Specimen 4 satisfactorily went through prolonged pressure test. The test was discontinued before specimen 2 was tested.

5.4

TEST DATA

5.4.1

The functional data prior to the prolonged pressure test are presented in table 5-2.

5.4.2

The functional data obtained immediately after the prolonged pressure test are presented in table 5-3.

5.4.3

The pressure fluctuation data recorded during the prolonged pressure test are presented in table 5-4.

Table 5-1. Prolonged Pressure Test Equipment List

| Item No. | Item | Manufacturer | Model/ Part No. | Serial No. | Remarks |
|----------|---------------|--------------------|--------------------|----------------|---|
| 1 | Regulator | Accessory Products | 140200-11/14 | 39, 40, 41, 42 | Test specimen |
| 2 | GHe Source | NA | NA | NA | 6000-psig |
| 3 | GHe Source | NA | NA | NA | 6000-psig |
| 4 | Filter | Microporous | 4813 F-2 DM | NA | 2-micron |
| 5 | Filter | Microporous | 4813 F-2 DM | NA | 2-micron |
| 6 | Regulator | Tescom Corp. | 26-1021-20 | 3024 | 10,000-psig inlet 0 to 10,000-psig outlet |
| 7 | Regulator | Tescom Corp. | 26-1021-20 | 1529 | 10,000-psig inlet 0 to 10,000-psig outlet |
| 8 | Pressure Gage | Heise | H34955 | 014231 | 0 to 10,000-psig $\pm 0.1\%$ FS Cal date 10-31-66 |
| 9 | Pressure Gage | Heise | H35838 | 200595-P | 0 to 10,000-psig ± 0.1 FS Cal date 10-31-66 |
| 10 | Pressure Gage | Ashcroft | NA | 200613-3 | 0 to 20,000-psig $\pm 0.25\%$ FS Cal date 10-11-66 |
| 11 | Hand Valve | Grove | KA 2B | NA | 10,000-psig |
| 12 | Hand Valve | Robbins | SSKG-250-4T | NA | 6000-psig |
| 13 | Hand Valve | Robbins | SSKG-250-4T | NA | 6000-psig |

Table 5-1. Prolonged Pressure Test Equipment List (Continued)

| Item No. | Item | Manufacturer | Model/ Part No. | Serial No. | Remarks |
|----------|---------------|---------------|--------------------|----------------|---|
| 14 | Hand Valve | Robbins | SSKG-250 -4T | NA | 6000-psig |
| 15 | Hand Valve | Aminco | 13126 | NA | 30,000-psig |
| 16 | Hand Valve | Robbins | SSKG-250 -4T | NA | 6000-psig |
| 17 | Hand Valve | Robbins | SSKG-250 -4T | NA | 6000-psig |
| 18 | Pressure Gage | Ashcroft | NA | 95-1509-B | 0 to 10,000-psig $\pm 0.25\%$ FS Cal date 10-11-66 |
| 19 | Pressure Gage | Seegers | 2122-9 | 200506-A | 6000-psig $\pm 0.25\%$ FS Cal date 12-9-66 |
| 20 | Pressure Gage | Martin-Decker | 8-760- 600 | 106-1016 -B | 6000-psig $\pm 0.25\%$ FS Cal date 12-30-66 |

Table 5-2. Specimen 4 Functional Test Data Before Prolonged Pressure Test


| Test | Media | | N ₂ |
|--------------------------------------|-------------------------------|---------------------------------|----------------|
| | Procedure Reference Paragraph | Allowable Value | Actual Value |
| Seat Leakage | 4.1.1 | 10 sccm | 0 |
| External Leakage | 4.1.1 | No leakage | 0 |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 |
| Actual Dome Pressure | 4.1.4 | ±5% of calculated | 860 |
| Calculated Dome Pressure | 4.1.4 | | 855 |
| Regulator Stability | 4.1.4 | ±2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | ±5% of calculated | 1600 |
| Calculated Dome Pressure | 4.1.4 | | 1590 |
| Regulator Stability | 4.1.4 | ±2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | ±5% of calculated | 3065 |
| Calculated Dome Pressure | 4.1.4 | | 3060 |
| Regulator Stability | 4.1.4 | ±2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | 0 |

Table 5-3. Specimen 4 Functional Test Data After Prolonged Pressure Test

| Test | Media | | N ₂ |
|--------------------------------------|-------------------------------|---------------------------------|----------------|
| | Procedure Reference Paragraph | Allowable Value | Actual Value |
| Seat Leakage | 4.1.1 | 10 sccm | 0 |
| External Leakage | 4.1.1 | No leakage | 0 |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 810 |
| Calculated Dome Pressure | 4.1.4 | | 855 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 1580 |
| Calculated Dome Pressure | 4.1.4 | | 1590 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 3045 |
| Calculated Dome Pressure | 4.1.4 | | 3060 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | 0 |

Table 5-4. Pressure Fluctuation Data During Prolonged Pressure Test

| Date | Inlet (psig) | Outlet (psig) | Dome (psig) | Date | Inlet (psig) | Outlet (psig) | Dome (psig) |
|----------|-----------------|------------------|----------------|----------|----------------------|------------------|----------------|
| 10-31-66 | 6000 | 3000 | 3050 | 11-15-66 | 6010 | 3015 | 3065 |
| 11-1-66 | 5980 | 2990 | 3050 | 11-16-66 | 6010 | 3015 | 3065 |
| 11-2-66 | 5920 | 2960 | 3015 | 11-17-66 | 6015 | 3020 | 3075 |
| 11-3-66 | 5925 | 2960 | 3025 | 11-18-66 | 6005 | 3010 | 3070 |
| 11-4-66 | 5978 | 2982 | 3040 | 11-19-66 | Saturday | | |
| 11-5-66 | Saturday | | | 11-20-66 | Sunday | | |
| 11-6-66 | Sunday | | | 11-21-66 | 6000 | 3005 | 3065 |
| 11-7-66 | 6010 | 3015 | 3065 | 11-22-66 | 5995 | 3000 | 3060 |
| 11-8-66 | 6010 | 3015 | 3065 | 11-23-66 | 5993 | 3000 | 3060 |
| 11-9-66 | 6010 | 3015 | 3070 | 11-24-66 | Thanksgiving Holiday | | |
| 11-10-66 | 6015 | 3020 | 3075 | 11-25-66 | Thanksgiving Holiday | | |
| 11-11-66 | 6020 | 3020 | 3078 | 11-26-66 | Saturday | | |
| 11-12-66 | Saturday | | | 11-27-66 | Sunday | | |
| 11-13-66 | Sunday | | | 11-28-66 | 5900 | 2950 | 3030 |
| 11-14-66 | 6000 | 3000 | 3055 | 11-29-66 | 5910 | 2960 | 3035 |



Note: All lines 1/4-inch.
Refer to table 5-1 for item identification.

Figure 5-1. Prolonged Pressure Test Schematic




Figure 5-2. Prolonged Pressure Test Setup

SECTION VI

LOW TEMPERATURE TEST

6.1 TEST REQUIREMENTS

- 6.1.1 A low temperature test will be performed on test specimens 2 and 3 to determine whether the environment causes degradation.
- 6.1.2 The body of the regulator shall be subjected to a temperature of -65°F and the dome of the regulator exposed to ambient temperature. A flow rate of approximately 1 scfm shall be established with the operating medium at -65°F and at least -65°F dewpoint.*
- 6.1.3 A functional test shall be performed during this test using GN₂ as the test medium. Leakage will be monitored by noting pressure drop.

6.2 TEST PROCEDURE

- 6.2.1 The low temperature test setup was assembled as shown in figures 4-1 and 6-1 utilizing the equipment listed in table 4-1.
- 6.2.2 A functional test was performed because 72 hours or more had elapsed since the previous functional test.
- 6.2.3 The chamber was controlled to the specified test conditions while maintaining a relative humidity between 60 and 90 per cent.
- 6.2.4 A functional test was performed when temperature stabilization was obtained. Temperature stabilization is defined as a maximum temperature change rate of 4°F per hour as determined from the instrumentation monitoring the test specimen.
- 6.2.5 The specimen was returned to ambient conditions. Within one hour following the return of the specimen to ambient conditions, the test specimen was visually inspected and functionally tested.
- 6.2.6 The test data were recorded.

6.3 TEST RESULTS

Specimens 2 and 3 were subjected to the low temperature test environment. Both specimens had excessive external leakage when the dome was pressurized. The leakage occurred between the dome and body approximately 90° from the flow axis. It was determined that the external leakage occurred at specimen temperatures of +5°F and below. Some of the body bolt torques were below the specified value.

* Note: The rated low temperature was originally +5°F.

6.4

TEST DATA

6.4.1

All low temperature test functional data are presented in tables 6-1 through 6-7.

6.4.2

Body bolt torque values for specimen 3 at ambient and low temperature are presented in table 6-8.

Table 6-1. Specimen 2 Functional Test Data Prior To Low Temperature Test

| Media | | | N ₂ | N ₂ |
|--------------------------------------|-------------------------------|---------------------------------|----------------|----------------|
| Test | Procedure Reference Paragraph | Allowable Value | | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 | 0 |
| External Leakage | 4.1.1 | No leakage | 0 | 0 |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 | 0 |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 765 | 760 |
| Calculated Dome Pressure | 4.1.4 | | 765 | 765 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | OK |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 1510 | 1520 |
| Calculated Dome Pressure | 4.1.4 | | 1513 | 1513 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | OK |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 3000 | 3005 |
| Calculated Dome Pressure | 4.1.4 | | 3009 | 3009 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | OK |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | 0 | 0 |

Table 6-2. Specimen 2 Functional Test Data At -65°F Low Temperature Test

| Media | | | N ₂ |
|--------------------------------------|-------------------------------|---------------------------------|----------------|
| Test | Procedure Reference Paragraph | Allowable Value | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 |
| External Leakage | 4.1.1 | No leakage | 0 |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 |
| Forward Dome Leakage | 4.1.3 | No leakage | 0* |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 760 |
| Calculated Dome Pressure | 4.1.4 | | 765 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 1500 |
| Calculated Dome Pressure | 4.1.4 | | 1513 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 3000 |
| Calculated Dome Pressure | 4.1.4 | | 3009 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | 0 |

* Note: External leakage excessive between dome and body.

Table 6-3. Specimen 2 Functional Test Data After -65°F Temperature Test

| Media | | | N ₂ |
|--------------------------------------|-------------------------------|---------------------------------|----------------|
| Test | Procedure Reference Paragraph | Allowable Value | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 |
| External Leakage | 4.1.1 | No leakage | 0 |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 760 |
| Calculated Dome Pressure | 4.1.4 | | 765 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 1510 |
| Calculated Dome Pressure | 4.1.4 | | 1513 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 3000 |
| Calculated Dome Pressure | 4.1.4 | | 3009 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | 0 |

Table 6-4. Specimen 3 Functional Test Data Prior To Low Temperature Test

| Media | | | N ₂ |
|--------------------------------------|-------------------------------|---------------------------------|----------------|
| Test | Procedure Reference Paragraph | Allowable Value | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 |
| External Leakage | 4.1.1 | No leakage | 0 |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 865 |
| Calculated Dome Pressure | 4.1.4 | | 855 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 1600 |
| Calculated Dome Pressure | 4.1.4 | | 1590 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 3060 |
| Calculated Dome Pressure | 4.1.4 | | 3060 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | 0 |

Table 6-5. Specimen 3 Functional Test Data At +5°F Low Temperature Test

| Test | Media | | N ₂ |
|--------------------------------------|-------------------------------|---------------------------------|------------------------|
| | Procedure Reference Paragraph | Allowable Value | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 |
| External Leakage | 4.1.1 | No leakage | 0 |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 900 |
| Calculated Dome Pressure | 4.1.4 | | 855 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK* |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 1570 |
| Calculated Dome Pressure | 4.1.4 | | 1590 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 3040 |
| Calculated Dome Pressure | 4.1.4 | | 3060 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | Large ** external leak |

* Note: Sample operated erratically while dome was being pressurized.

** Note: External leak developed between dome and body 90° from flow direction when seat leakage measurement was attempted.

Table 6-6. Specimen 3 Functional Test Data After +5°F Low Temperature Test


| Media: | | | N ₂ | N ₂ |
|--------------------------------------|-------------------------------|---------------------------------|----------------|----------------|
| Test | Procedure Reference Paragraph | Allowable Value | | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 | 0 |
| External Leakage | 4.1.1 | No leakage | 0 | 0 |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 | 0 |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 860 | 860 |
| Calculated Dome Pressure | 4.1.4 | | 855 | 855 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | OK |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 1570 | 1600 |
| Calculated Dome Pressure | 4.1.4 | | 1590 | 1590 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | OK |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | 0 | 0 |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 3070 | 3060 |
| Calculated Dome Pressure | 4.1.4 | | 3060 | 3060 |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | OK |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | 0 | 0 |

Table 6-7. Specimen 3 Functional Test Data During -65°F Low Temperature Test

| Media | | | N ₂ |
|--------------------------------------|-------------------------------|---------------------------------|--------------------|
| Test | Procedure Reference Paragraph | Allowable Value | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 |
| External Leakage | 4.1.1 | No leakage | 0 |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 |
| Forward Dome Leakage | 4.1.3 | No leakage | 0* |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | ----- Test Stopped |
| Calculated Dome Pressure | 4.1.4 | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | |
| Calculated Dome Pressure | 4.1.4 | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | |
| Calculated Dome Pressure | 4.1.4 | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | |

* Note: External leakage excessive between dome and body.

Table 6-8. Body Bolt Torque Values For Specimen 3 At Ambient And Low Temperature



Specified Torque - 1500 in./lbs

Torque values underlined are
at low temperature (5°F)




Figure 6-1. Low Temperature Test Setup

SECTION VII

HIGH TEMPERATURE TEST

7.1 TEST REQUIREMENTS

- 7.1.1 A high temperature test will be performed on test specimens 2 and 3 to determine whether the environment causes degradation.
- 7.1.2 The rated high temperature is 160 (+4, -0)°F.
- 7.1.3 A functional test shall be performed using GN₂ as the test medium during this test.

7.2 TEST PROCEDURE

- 7.2.1 The high temperature test setup was assembled as shown in figures 4-1 and 7-1 using the equipment listed in table 4-1.
- 7.2.2 The chamber was controlled to the specified test conditions while maintaining a relative humidity of 20 per cent (+5 per cent).
- 7.2.3 The temperature was maintained at 160 (+4, -0)°F for 72 (+2, -0) hours.
- 7.2.4 A functional test was conducted while the chamber temperature was maintained.
- 7.2.5 The chamber temperature was returned to ambient conditions upon completion of the functional test.
- 7.2.6 Within one hour following the return of the specimen to ambient conditions, the specimen was visually inspected and functionally tested.
- 7.2.7 Test data were recorded.

7.3 TEST RESULTS

- 7.3.1 Specimens 2 and 3 were subjected to the high temperature test environment. Both specimens had excessive external body plug leakage during and after the test.
- 7.3.2 The body bolt torque values dropped off considerably at high temperature. The torque value of specimen 2 was 75 ft-lbs at 160°F. The torque value of specimen 3 was 133 ft-lbs at 160°F.

7.4 TEST DATA

- 7.4.1 Functional data on specimens 2 and 3 are presented in tables 7-1 through 7-4.

Table 7-1. Specimen 2 Functional Test Data During High Temperature Test

| Run | | | 1 | 2 | 3 |
|--------------------------------------|-------------------------------|---------------------------------|--------------------|----------------|----------------|
| Media | | | N ₂ | N ₂ | N ₂ |
| Test | Procedure Reference Paragraph | Allowable Value | Actual Value | | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 | | |
| Internal Leakage | 4.1.1 | No leakage | Excessive leakage* | | |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 | | |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 | | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 765 | | |
| Calculated Dome Pressure | 4.1.4 | | 765 | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | | |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | 0 | | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 1520 | | |
| Calculated Dome Pressure | 4.1.4 | | 1513 | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | | |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | 0 | | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 3010 | | |
| Calculated Dome Pressure | 4.1.4 | | 3009 | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | | |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | 0 | | |

* Excessive external body plug leakage due to low torque value at high temperature (75 ft-lbs). The body plug was re-torqued to 180 ft-lbs.

Table 7-2. Specimen 2 Functional Test Data After High Temperature Test

| Run | | | 1 | 2 | 3 |
|--------------------------------------|-------------------------------|---------------------------------|----------------------|----------------|----------------|
| Media | | | N ₂ | N ₂ | N ₂ |
| Test | Procedure Reference Paragraph | Allowable Value | Actual Value | | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 | | |
| External Leakage | 4.1.1 | No leakage | Excessive leakage | | |
| Reverse Dome Leakage | 4.1.2 | No leakage | --- Test Stopped --- | | |
| Forward Dome Leakage | 4.1.3 | No leakage | | | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | | | |
| Calculated Dome Pressure | 4.1.4 | | | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | | | |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | | | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | | | |
| Calculated Dome Pressure | 4.1.4 | | | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | | | |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | | | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | | | |
| Calculated Dome Pressure | 4.1.4 | | | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | | | |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | | | |

Table 7-3. Specimen 3 Functional Test Data During High Temperature Test

| Run | | | 1 | 2 | 3 |
|--------------------------------------|-------------------------------|---------------------------------|--------------------|----------------|----------------|
| Media | | | N ₂ | N ₂ | N ₂ |
| Test | Procedure Reference Paragraph | Allowable Value | Actual Value | | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 | | |
| External Leakage | 4.1.1 | No leakage | Excessive leakage* | | |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 | | |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 | | |
| Actual Dome Pressure | 4.1.4. | +5% of calculated | 860 | | |
| Calculated Dome Pressure | 4.1.4 | | 855 | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | | |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | 0 | | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 1595 | | |
| Calculated Dome Pressure | 4.1.4 | | 1590 | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | | |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | 0 | | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | 3060 | | |
| Calculated Dome Pressure | 4.1.4 | | 3060 | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | OK | | |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | 0 | | |

* Excessive external body plug leakage due to low torque value at high temperature (133 ft-lbs). The body plug was re-torqued to 180 ft-lbs. The body plug leakage was still 20 scim.

Table 7-4. Specimen 3 Functional Test Data After High Temperature Test

| Run | | | 1 | 2 | 3 |
|--------------------------------------|-------------------------------|---------------------------------|----------------------|----------------|----------------|
| Media | | | N ₂ | N ₂ | N ₂ |
| Test | Procedure Reference Paragraph | Allowable Value | Actual Value | | |
| Seat Leakage | 4.1.1 | 10 sccm | 0 | | |
| External Leakage | 4.1.1 | No leakage | 0 | | |
| Reverse Dome Leakage | 4.1.2 | No leakage | 0 | | |
| Forward Dome Leakage | 4.1.3 | No leakage | 0 | | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | * | | |
| Calculated Dome Pressure | 4.1.4 | | --- Test Stopped --- | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | | | |
| Seat Leakage After Cycling 750 psig | 4.1.5 | 10 sccm | | | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | | | |
| Calculated Dome Pressure | 4.1.4 | | | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | | | |
| Seat Leakage After Cycling 1500 psig | 4.1.5 | 10 sccm | | | |
| Actual Dome Pressure | 4.1.4 | +5% of calculated | | | |
| Calculated Dome Pressure | 4.1.4 | | | | |
| Regulator Stability | 4.1.4 | +2% of dome and outlet pressure | | | |
| Seat Leakage After Cycling 3000 psig | 4.1.5 | 10 sccm | | | |

* As inlet pressure was increased the body plug began to leak excessively.




Figure 7-1. High Temperature Test Setup

APPROVAL
TEST REPORT


FOR

PRESSURE REGULATORS

Grove Valve and Regulator Company Part Numbers T-1538 and T-1541


NASA Drawing Numbers B75M50305-1 and B75M50305-4

SUBMITTED BY



R. Kolowith
Test and Evaluation Section

APPROVALS



R. W. Claunch
Program Supervisor



V. J. Venko, Director
Engineering Department

DISTRIBUTION

Chrysler Corporation Space Division

| | | |
|-------------------------------------|--|---|
| C. A. Brakebill | Test and Evaluation Section | 2 |
| R. W. Claunch | Program Supervisor, CCSD-Michoud | 2 |
| W. E. Dempster | Program Manager, CCSD-FO | 6 |
| E. J. Dofter | Chief Engineer, Reliability Engineering Branch | 1 |
| L. L. Gray | Test and Evaluation Section | 5 |
| P. Perani | Manager, Test and Evaluation Section | 2 |
| L. T. Scherer, Jr. | Manager, Data Center Section | 1 |
| V. J. Vehko | Director, Engineering Department | 1 |
| Technical Files | | 3 |
| Technical Information Centre | | 1 |
| Technical Writing and Editing Group | | 1 |

National Aeronautics and Space Administration

| | | |
|---|--|---|
| Marshall Space Flight Center | | |
| MS-IP, Bldg. 4200 | | 3 |
| APIC | | 1 |
| John F. Kennedy Space Center | | |
| MD | | 1 |
| MG | | 1 |
| MH | | 1 |
| ML, Mr. Fedor | | 1 |
| RC-423 | | 5 |
| Scientific and Technical Information Facility | | 2 |
| P. O. Box 33 | | |
| College Park, Maryland 20740 | | |