

202

SATURN S-IVB-209 STAGE ACCEPTANCE FIRING REPORT

Facility Form 602

N70-75908	(THRU)	
(ACCESSION NUMBER)		(CODE)
230		
(PAGES)		(CATEGORY)
CR-113301		
(NASA CR OR TMX OR AD NUMBER)		

DOUGLAS REPORT DAC-47475
AUGUST 1967

PREPARED BY:
DOUGLAS AIRCRAFT COMPANY
SATURN S-IVB TEST PLANNING
AND EVALUATION COMMITTEE

PREPARED FOR:
NATIONAL AERONAUTICS AND
SPACE ADMINISTRATION
UNDER NASA CONTRACT NAS7-101

A. P. O'Neal

APPROVED BY: A. P. O'NEAL
DIRECTOR, SATURN DEVELOPMENT ENGINEERING

ABSTRACT

This report presents an evaluation of the Saturn S-IVB-209 stage acceptance firing that was conducted at the Sacramento Test Center on 20 June 1967. Included in this report are stage and ground support equipment deviations associated with the acceptance firing configuration.

The acceptance firing test program was conducted under National Aeronautics and Space Administration Contract NAS7-101, and established the acceptance criteria for buyoff of the stage.

DESCRIPTORS

Saturn S-IVB-209 Stage

Saturn S-IVB-209 Stage
Test Evaluation

J-2 Engine

Complex Beta

Countdown Operations

Saturn S-IVB-209 Stage Acceptance
Firing

Saturn S-IVB-209 Stage Test
Configuration

Sacramento Test Center

Sequence of Events

PREFACE

The purpose of this report is to document the evaluation of the Saturn S-IVB-209 stage acceptance firing as performed by Douglas personnel at the Sacramento Test Center.

This report, prepared under National Aeronautics and Space Administration Contract NAS7-101, is issued in accordance with line item 129 of the *MSFC Data Requirements List 021*, dated 15 September 1966.

This report evaluates stage test objectives, instrumentation, and configuration deviations of the stage, test facility, and ground support equipment.

TABLE OF CONTENTS

<u>Section</u>		<u>Page</u>
1.	INTRODUCTION	1-1
1.1	General	1-1
1.2	Background	1-1
1.3	Objectives	1-1
2.	SUMMARY	2-1
2.1	Countdown Operations	2-2
2.2	J-2 Engine System	2-2
2.3	Oxidizer System	2-2
2.4	Fuel System	2-2
2.5	Pneumatic Control and Purge System	2-2
2.6	Propellant Utilization (PU) System	2-2
2.7	Data Acquisition System	2-2
2.8	Electrical Power and Control Systems	2-2
2.9	Hydraulic System	2-3
2.10	Flight Control System	2-3
2.11	Structural System	2-3
2.12	Thermoconditioning and Purge System	2-3
2.13	Reliability and Human Engineering	2-3
3.	TEST CONFIGURATION	3-1
3.1	Configuration Deviations	3-1
4.	COUNTDOWN OPERATIONS	4-1
4.1	Countdown 614084 (Run 1A, Run 1B)	4-1
4.2	Countdown 614085 (Run 2A)	4-1
4.3	Countdown 614086 (Special Tests)	4-2
4.4	Checkout	4-2
4.5	Cryogenic Loading	4-2
4.6	GSE Performance	4-3
4.7	Countdown Problem Summary	4-3
4.8	Atmospheric Conditions	4-5
5.	SEQUENCE OF EVENTS	5-1

TABLE OF CONTENTS (Continued)

<u>Section</u>		<u>Page</u>
6.	ENGINE SYSTEM	6-1
6.1	Engine Chillydown and Conditioning	6-1
6.2	J-2 Engine Performance Analysis Methods and Instrumentation	6-2
6.3	J-2 Engine Performance	6-2
6.4	Engine Sequencing	6-6
6.5	Component Operation	6-6
6.6	Engine Vibration	6-7
7.	OXIDIZER SYSTEM	7-1
7.1	Pressurization Control	7-1
7.2	Cold Helium Supply	7-3
7.3	J-2 Heat Exchanger	7-3
7.4	LOX Pump Chillydown	7-4
7.5	Engine LOX Supply	7-5
7.6	LOX Tank Vent and Relief Valve Performance	7-5
8.	FUEL SYSTEM	8-1
8.1	Pressurization Control	8-1
8.2	LH2 Pump Chillydown	8-1
8.3	Engine LH2 Supply	8-2
8.4	LH2 Vent and Relief Valve Performance	8-3
9.	PNEUMATIC CONTROL AND PURGE SYSTEM	9-1
9.1	Pneumatic Control	9-1
9.2	Ambient Helium Purges	9-1
10.	PROPELLANT UTILIZATION SYSTEM	10-1
10.1	PU System Calibration	10-1
10.2	Propellant Loading	10-2
10.3	Propellant Mass History	10-2
10.4	Propellant Residuals	10-3
10.5	PU System Response	10-4

TABLE OF CONTENTS (Continued)

<u>Section</u>		<u>Page</u>
11.	DATA ACQUISITION SYSTEM	11-1
	11.1 Instrumentation System Performance	11-1
	11.2 Telemetry System Performance	11-2
	11.3 RF System Performance	11-2
	11.4 Electromagnetic Compatibility	11-3
	11.5 Emergency Detection System Measurements	11-3
	11.6 Hardwire Data Acquisition System Performance	11-3
12.	ELECTRICAL POWER AND CONTROL SYSTEMS	12-1
	12.1 Electrical Control System	12-1
	12.2 APS Electrical Control System	12-4
	12.3 Electrical Power System	12-5
	12.4 Special Depletion Sensor Test	12-6
13.	HYDRAULIC SYSTEM	13-1
	13.1 Hydraulic System Operation	13-1
	13.2 System Pressure at Salient Times	13-1
	13.3 Reservoir Level at Salient Times	13-2
	13.4 Temperature History	13-2
	13.5 Engine Side Loads	13-3
	13.6 Hydraulic Fluid Flowrates	13-3
	13.7 Auxiliary Pump Motor Voltage and Current	13-3
	13.8 Thrust Offset	13-4
14.	FLIGHT CONTROL SYSTEM	14-1
	14.1 Actuator Dynamics	14-1
	14.2 Engine Slew Rates	14-1
	14.3 Differential Pressure Feedback Network	14-2
	14.4 Cross Axis Coupling	14-2
15.	STRUCTURAL SYSTEMS	15-1
	15.1 Common Bulkhead	15-1
	15.2 LH2 Tank Interior	15-1

TABLE OF CONTENTS (Continued)

<u>Section</u>		<u>Page</u>
	15.3 Exterior Structure	15-2
	15.4 Malfunction of LOX Tank Pressure Regulator	15-2
16.	THERMOCONDITIONING AND PURGE SYSTEMS	16-1
	16.1 Aft Skirt Thermoconditioning and Purge System	16-1
	16.2 Forward Skirt Environmental Control and Thermoconditioning System	16-1
17.	RELIABILITY AND HUMAN ENGINEERING	17-1
	17.1 Reliability Engineering	17-1
	17.2 Human Engineering	17-1

APPENDICES

<u>Appendix</u>		
1.	ENGINE PERFORMANCE PROGRAM (PA49)	AP 1-1
2.	ABBREVIATIONS	AP 2-1

LIST OF TABLES

<u>Table</u>		
1-1	Milestones, Saturn S-IVB-209 Stage	1-3
3-1	S-IVB-209 Stage Hardware List	3-5
3-2	S-IVB-209 Stage and GSE Acceptance Firing Orifices	3-8
3-3	S-IVB-209 Stage Pressure Switches	3-12
4-1	Terminal Countdown Sequence (CD 614085)	4-7
5-1	Sequence of Events	5-3
6-1	Thrust Chamber Chillover	6-7

LIST OF TABLES (Continued)

<u>Table</u>		<u>Page</u>
6-2	Engine Control Sphere Performance	6-7
6-3	Comparison of Computer Program Results	6-10
6-4	Data Inputs to Computer Programs	6-11
6-5	Engine Performance	6-13
6-6	Engine Thrust Variations	6-14
6-7	Engine Sequence	6-15
7-1	LOX Tank Prepressurization Data	7-7
7-2	LOX Tank Pressurization Data	7-8
7-3	J-2 Heat Exchanger Data	7-10
7-4	LOX Chillo down System Performance	7-11
7-5	LOX Pump Inlet Conditions	7-13
8-1	LH2 Tank Prepressurization Data	8-5
8-2	LH2 Tank Pressurization Data	8-6
8-3	LH2 Chillo down-System Performance	8-7
8-4	LH2 Pump Inlet Conditions	8-8
11-1	Instrumentation System Performance Summary	11-5
11-2	Inactive Measurements	11-6
11-3	Measurement Discrepancies	11-9
11-4	Telemetry to Hardwire Data Comparison (T ₀ +213 sec)	11-10
11-5	Hardwire Data Acquisition System	11-12
17-1	Flight Critical Components Malfunctions	17-3
AP 1-1	Program PA49 Printout Symbols	AP 1-3
AP 1-2	Engine Performance Program (PA49)	AP 1-4
AP 2-1	Abbreviations	AP 2-1

LIST OF ILLUSTRATIONS

<u>Figure</u>		<u>Page</u>
3-1	Propulsion System Configuration and Instrumentation	3-13
3-2	Facility Propellant and Pneumatic Loading Systems	3-14
4-1	LOX Tank Loading	4-9
4-2	LH2 Tank Loading	4-10
4-3	Cold Helium System Loading	4-11
4-4	GSE Performance During Engine Start Sphere Chillo down and Loading	4-12
4-5	GSE Performance During Engine Control Sphere Loading	4-13
4-6	GSE Performance During LOX and LH2 Tank Prepressurization	4-14
4-7	GSE Performance During Thrust Chamber Chillo down	4-15
6-1	J-2 Engine System and Instrumentation	6-21
6-2	Thrust Chamber Chillo down	6-22
6-3	LH2 Pump Performance During Engine Start	6-23
6-4	Engine Start and Control Sphere Performance	6-24
6-5	Engine Start Sphere Performance	6-25
6-6	J-2 Engine Chamber Pressure	6-26
6-7	J-2 Engine Injector Supply Conditions	6-27
6-8	LOX and LH2 Flowrate	6-28
6-9	J-2 Engine Pump Operating Characteristics	6-29
6-10	Turbine Inlet Operating Conditions	6-30
6-11	Gas Generator Performance	6-31
6-12	Engine Steady-State Performance	6-32
6-13	Specific Impulse versus Mixture Ratio	6-35
6-14	Total Accumulated Impulse After Engine Start Command	6-36
6-15	Engine Start Transient Characteristics	6-37
6-16	Thrust Variations	6-38
6-17	Total Accumulated Impulse After Engine Cutoff Command	6-41

LIST OF ILLUSTRATIONS (Continued)

<u>Figure</u>		<u>Page</u>
6-18	Engine Cutoff Transient Characteristics	6-42
6-19	Engine Start Sequence	6-44
6-20	Engine Vibration	6-45
7-1	LOX Tank Pressurization System	7-15
7-2	LOX Tank Prepressurization Simulated Boost	7-16
7-3	LOX Tank Pressurization System Performance	7-17
7-4	LOX Pressurization Module Start Transient Pressure . . .	7-18
7-5	Cold Helium Supply	7-19
7-6	J-2 Heat Exchanger Performance	7-20
7-7	LOX Pump Chillover System Operation	7-21
7-8	LOX Pump Chillover System Performance	7-22
7-9	LOX Supply System	7-23
7-10	LOX Pump Inlet Conditions	7-24
7-11	LOX Pump Inlet Conditions During Firing	7-25
7-12	Effect of LOX Mass Level on LOX Pump Inlet Temperature	7-26
8-1	LH2 Tank Pressurization System	8-11
8-2	LH2 Tank Prepressurization System Performance	8-12
8-3	LH2 Tank Pressurization System Performance	8-13
8-4	LH2 Pump Chillover	8-14
8-5	LH2 Pump Chillover Characteristics	8-15
8-6	LH2 Supply System	8-16
8-7	LH2 Pump Inlet Conditions	8-17
8-8	LH2 Pump Inlet Conditions During Firing	8-18
8-9	Effect of LH2 Mass Level on LH2 Pump Inlet Temperature	8-18
9-1	Pneumatic Control and Purge System	9-3
9-2	Pneumatic Control and Purge System Performance	9-4
10-1	LOX Tank-to-Sensor Mismatch Normalized to Sensor End Points	10-9
10-2	LH2 Tank-to-Sensor Mismatch Normalized to Sensor End Points	10-10

LIST OF ILLUSTRATIONS (Continued)

<u>Figure</u>		<u>Page</u>
10-3	PU Valve Position	10-11
10-4	PU Valve Position Reconstruction with PU System Gain Reduction	10-12
12-1	Secure Range Safety Command System Data	12-7
12-2	Battery Temperatures	12-8
12-3	Aft Battery Voltage and Current Profiles	12-9
12-4	Forward Battery Voltage and Current Profiles	12-10
14-1	Actuator Response (Gain)	14-3
14-2	Actuator Response (Phase Lag)	14-3
14-3	Actuator Differential Pressure (<u>+2</u> deg Transient Response)	14-4

1. INTRODUCTION

1.1 General

This report was prepared at the Douglas Huntington Beach Missile & Space Systems Division by the Saturn S-IVB Test Planning and Evaluation (TP&E) Committee for the National Aeronautics and Space Administration under Contract NAS7-101.

Activities connected with the Saturn S-IVB-209 stage included a prefiring checkout and the acceptance firing. Checkout started at the subsystem level and progressed to completion with the integrated systems test and the simulated acceptance firing. The information contained in the following sections documents and evaluates all events and test results of the acceptance firing which was completed on 20 June 1967. The tests were performed at the Complex Beta, Test Stand I, Sacramento Test Center (STC).

1.2 Background

The S-IVB-209 stage was assembled at the Huntington Beach Missile & Space Systems Division. A checkout was performed in the Vertical Checkout Laboratory (VCL) prior to shipping the stage to STC. The stage was delivered to STC on 10 March 1967 and installed on Test Stand I on 15 May 1967. The stage was ready for acceptance firing on 12 June 1967.

The APS modules were shipped to the Santa Monica checkout laboratory for leak and functional checks. The modules were then shipped to Sacramento for stage interface checks. No confidence firings of these modules were scheduled.

Table 1-1 lists the milestones of the Saturn S-IVB-209 stage events and dates of completion.

1.3 Objectives

All test objectives outlined in Douglas Report No. SM-47459A, *Saturn S-IVB-209 Stage Acceptance Firing Test Plan*, dated February 1967 and revised 29 May 1967 were successfully completed.

Stage acceptance objectives which provided maximum system performance evaluation were as follows:

- a. Countdown control and operational capability verification
- b. J-2 engine system performance verification
- c. Oxidizer system performance verification
- d. Fuel system performance verification
- e. Pneumatic control system performance verification
- f. Propellant utilization system performance verification
- g. Stage data acquisition system performance verification
- h. Stage electrical control and power system performance verification
- i. Hydraulic system performance and J-2 engine gimbal control performance verification
- j. Structural integrity verification
- k. Auxiliary propulsion system stage interface compatibility verification
- l. Ambient repressurization system performance verification.

TABLE 1-1
MILESTONES, SATURN S-IVB-209 STAGE

EVENT	COMPLETION DATE
Tank Assembly	8 July 1966
Proof Test	26 July 1966
Insulation and Bonding	6 Sept 1966
Stage Checkout and Join J-2 Engine	28 Nov 1966
Systems Checkout	7 Feb 1967
Ship to STC	10 March 1967
Stage Installed on Test Stand	15 May 1967
Ready for Acceptance Firing	12 June 1967
Acceptance Firing	20 June 1967
Propellant Loading for Special Tests	23 June 1967
Abbreviated Postfire Checkout on Stand	6 July 1967
Ready for Storage	11 July 1967

2. SUMMARY

The S-IVB-209 stage was acceptance fired on 20 June 1967 at Complex Beta, Test Stand I, Sacramento Test Center. The countdown was designated as CD 614085. The mainstage firing duration was 455.95 sec; engine cutoff was initiated through the PU processor when LOX was depleted below the 1 percent level.

2.1 Countdown Operations

2.1.1 CD 614084

CD 614084 (run 1A) was initiated on 13 June and proceeded smoothly with only one anomaly; LH2 depletion sensor No. 1 cycled dry for 28 ms during LH2 loading at the 30 percent level.

At 822.9 sec prior to simulated liftoff the "Engine Ready" scan received an ignition detection signal that was attributed to a temperature differential across the probe resulting from the thrust chamber chilldown. This halted the automatic program and the stage was secured automatically. A manual thrust chamber chilldown sequence was then conducted with no recurrence of the problem.

Run 1B was initiated and during the start sequence, a switch selector complement error was received halting the automatic program and the stage was secured manually. At this point, the countdown was scrubbed.

2.1.2 CD 614085

CD 614085 (run 2A) was initiated on 19 June 1967 and proceeded smoothly to a successful acceptance firing on 20 June 1967. The following anomalies were experienced during the countdown:

- a. Shortly after engine start, an abnormal decrease was noted in the LOX tank ullage pressure as a result of a temporary anomaly in the LOX tank pressurization module.
- b. ESC occurred 685 ms later than expected due to a slow opening of the LOX pre valve. This was attributed to the use of the new Sterer actuation control modules. The valve also exhibited an erratic talkback on the hardwire "CLOSED" indication during the postfiring special test. The pre valve was replaced.

2.2 J-2 Engine System

The J-2 engine (S/N 2083) exhibited operational characteristics compatible with stage design requirements and consistent with prior test data and with the Engine Model Specification R-2158b.

2.3 Oxidizer System

Due to a malfunction of the LOX tank pressurization control module, LOX NPSH fell below the minimum acceptable level for a 20-sec period shortly after Engine Start Command; however, there were no detrimental effects to the J-2 engine or to the remainder of the acceptance firing. With the exception of the above anomaly, the oxidizer system performance was acceptable.

2.4 Fuel System

The fuel system performed as designed and supplied LH2 to the engine LH2 pump inlet within the limits required for satisfactory engine performance.

2.5 Pneumatic Control and Purge System

The pneumatic control and purge system performed satisfactorily throughout the acceptance firing. The helium supply to the system was adequate for both pneumatic valve control and purging; the regulated pressure was maintained within acceptable limits and all components functioned normally.

2.6 Propellant Utilization (PU) System

The PU system performed satisfactorily and accomplished all the design objectives.

2.7 Data Acquisition System

The data acquisition system performed satisfactorily throughout the acceptance firing. One hundred and seventy five measurements were active of which 2 failed resulting in a measurement efficiency of 98.86 percent.

2.8 Electrical Power and Control Systems

The electrical power and control systems performed satisfactorily

throughout the acceptance firing. All firing objectives were satisfied and all system variables operated within design limits.

2.9 Hydraulic System

The hydraulic system operated properly supplying pressurized fluid to the servo-actuators. All specified test objectives were achieved and all system variables operated within design limits.

2.10 Flight Control System

The dynamic response of the hydraulic servo-thrust vector control system was measured while the J-2 engine was gimbaled during the acceptance firing. The performance of the pitch and yaw hydraulic servo control systems was satisfactory.

2.11 Structural Systems

Structural integrity of the stage was maintained for the vibration, temperature, and thrust load conditions of the acceptance firing. A postfiring visual inspection of the stage revealed no debonding or other structural defects resulting from cryogenic loading and firing.

2.12 Thermoconditioning and Purge System

The thermoconditioning and purge system functioned properly during the acceptance firing. All system temperatures and flowrates were maintained within design limits.

2.13 Reliability and Human Engineering

All malfunctions of Flight Critical Items were investigated and documented. A Human Engineering evaluation has been conducted in support of the acceptance firing.

3. TEST CONFIGURATION

This section describes the stage and ground support equipment (GSE) deviations and modifications from the flight configuration affecting the acceptance firing. Additional details of specific system modifications are discussed in appropriate sections of this report. Details of the S-IVB-209 stage configurations are presented in Douglas Report No. 1B66532, *S-IVB/IB Stage End-Item Test Plan*.

Figure 3-1 is a schematic of the S-IVB-209 stage propulsion system and shows the telemetry instrumentation transducer locations from which the test data were obtained. The functional components are listed in table 3-1. Hardwire measurements are noted in the appropriate subsystem schematics included in this report. The propulsion system orifice characteristics and pressure switch settings are presented in tables 3-2 and 3-3. J-2 engine S/N 2083 was installed.

The propulsion GSE (figure 3-2) consisted of pneumatic consoles "A" and "B," two propellant fill and replenishing control sleds, a vacuum system console, and a gas heat exchanger.

3.1 Configuration Deviations

Configuration deviations required for the acceptance firing are discussed in Douglas Report No. SM-47459A, *Saturn S-IVB-209 Stage Acceptance Firing Test Plan*. Significant configuration changes to the stage and GSE during the acceptance firing are discussed in the following paragraphs.

3.1.1 Propulsion System

- a. Stage propellant vent and bleed systems were connected to the facility vent system.
- b. The stage portions of the propellant and pneumatic quick-disconnects were replaced with hardlines.
- c. A converging water-cooled diffuser was installed in the engine thrust chamber exit to reduce the possibility of sideloads induced by jet stream separation.

- d. A reusable J-2 engine ignition detection probe was installed in place of the S-IB expendable probe.

3.1.2 Propellant Utilization System

- a. The propellant loading fast-fill sensors installed on the instrumentation probes were used in the indicating mode only.

3.1.3 Electrical Power System

- a. Model DSV-4B-170 battery simulators were used to supply stage internal power.
- b. Model DSV-4B-727 primary battery simulators were used in place of primary flight batteries.

3.1.4 Electrical Control System

- a. The instrument unit and S-IVB/IB stage electrical interfaces were simulated by GSE.
- b. Two Model DSV-4B-188B APS simulators were used to provide APS module electrical loads to the stage control signals.
- c. The electrical umbilicals remained connected throughout the acceptance firing.

3.1.5 Data Acquisition System

- a. The MSFC Basic Static Firing Measurement Program hardwire transducers were installed.
- b. All instrumentation parameters without transducers, and those disconnected for hardwire usage, were left as open channels.
- c. Measurement D0576 (LH2 Tank Ullage Press) - Strain gage flight transducer P/N 1B40242-509 was RF sensitive and was replaced by pot transducer P/N 1A72913-539.

3.1.6 Forward Environmental Control System

- a. Fluid for the forward thermoconditioning system was supplied by Model DSV-4B-359 Servicer.

3.1.7 Secure Range Safety Command System

- a. The engine cutoff command output from Range Safety Systems 1 and 2 was disconnected and stowed.
- b. Pulse sensors were attached to the output of the exploding bridgewire (EBW) firing units.

3.1.8 Structural Systems

- a. The main and auxiliary tunnel covers were not installed.
- b. The stage was mounted on the Model DSV-4B-540 Dummy Interstage.

3.1.9 GSE and Facilities

- a. Resistance wire fire detection system was installed for monitoring critical areas of the stage, GSE, and facilities.
- b. GH2 leak detection system was installed for monitoring critical areas of the stage, GSE, and facilities.
- c. Blast detectors were installed in the test area for monitoring ranges of 0 to 25 psi overpressure.
- d. Model 742 static firing hazardous gas shield, thrust cone water spray Firex, cryogenic spill pan, forward skirt support ring and vent port covers were installed.
- e. Model 601 flame resistant protective firing cover was installed to enclose the forward skirt area.
- f. An auxiliary propellant tank pressurization system was installed using a GSE ambient helium source.
- g. Model DSV-4B-618 Engine Unlatch Restrainer Links were installed to restrain the J-2 engine during start transient sideloads.
- h. Two O₂ content analyzers were installed in the thrust structure.

TABLE 3-1 (Sheet 1 of 4)
S-IVB-209 STAGE HARDWARE LIST

ITEM NO.*	PART NO.	NAME
1	7851861-1	Disconnect, LH2 tank pressurization
2	1B65673-1	Valve, check, LH2 tank prepressurization line
3	7851823-503	Disconnect, ambient helium fill
4	1B53817-505	Valve, hand, 3-way, LOX vent and relief valve purge line
5	1B53817-505	Valve, hand, 3-way, LH2 and LOX fill and drain valves, nonpropulsive vent and LH2 chilldown valve purge line
6	1B51361-1	Valve, check, LH2 fill and drain valve and nonpropulsive vent purge line
7	1B63206-1	Orifice, ambient helium fill, 65 scfm
8	1B51361-1	Valve, check, control helium fill
9	1A57350-507	Module, control helium fill
10	1A49963-1	Sphere, control helium, 4.5 std cu ft
11	1B68260-1	Disconnect, LH2 tank vent
12	1B66932-501	Disconnect, LH2 fill and drain
13	1B40622-505	Orifice, LH2 fill and drain valve purge line, 15 scfm
14	1B66692-501	Module, actuation control, LH2 fill and drain valve
14 A&B	1B67481-1	Valve, check, LH2 fill and drain valve actuation control module vent
15	1B41065-1	Disconnect, common bulkhead vacuum system
16	1A48240-505	Valve, LH2 fill and drain
17	1B66932-501	Disconnect, LOX fill and drain
18	1B51361-1	Valve, check, LOX fill and drain valve purge line
19	1B40622-505	Orifice, LOX fill and drain valve purge line, 15 scfm
20	1A48240-505	Valve, LOX fill and drain
21	1B66692-501	Module, actuation control, LOX fill and drain valve
21 A&B	1B67481-1	Valve, check, LOX fill and drain valve actuation control module vent
22	7851844-501	Disconnect, cold helium fill and LOX tank prepressurization
23	1B57781-505	Module, cold helium dump
24	1B40824-507	Valve, check, cold helium fill line
25	1B42290-505	Module, LOX tank pressure control
26	1B40824-503	Valve, check, cold helium fill and LOX prepressurization line
27	1A49991-1	Plenum, LOX tank pressurization, 250 std cu in.
28	7851830-517	Switch, pressure, LOX tank pressurization regulator backup, P/U 465 +20, -15 psia, D/O 350 +20, -15 psia

* Indicates location in figures 3-1 and 3-2.

P/U = Pickup

D/O = Dropout

TABLE 3-1 (Sheet 2 of 4)
S-IVB-209 STAGE HARDWARE LIST

ITEM NO.*	PART NO.	NAME
29	1B63046-513	Orifice, LOX tank pressurization, heat exchanger primary, 0.03218 in. ² effective area
30	1B63047-513	Orifice, LOX tank pressurization, heat exchanger bypass, 0.02291 in. ² effective area
31	DELETED	
32	1A49958-517	Disconnect, mainstage OK pressure switch checkout
33	1A49958-519	Disconnect, thrust chamber jacket purge and chilldown
34	1B43657-509	Module, pneumatic power control
35	1A48857-501	Plenum, control helium, 100 std cu in.
36	1B55200-505	Module, LH2 tank pressure control
	1B64443-505	Orifice, undercontrol mode, 0.0444 in. ² effective area
	1B64443-505	Orifice, overcontrol mode, 0.0777 in. ² effective area
	1B64443-505	Orifice, step flow, 0.1392 in. ² effective area
37	1B51361-1	Valve, check, LH2 nonpropulsive vent purge line
38	1B40622-501	Orifice, LH2 nonpropulsive vent purge line, 1 scfm
39	1B59265-1	Orifice, nonpropulsive vent, 2.180 in. dia
40	1B59265-1	Orifice, nonpropulsive vent, 2.180 in. dia
41	7851860-537	Switch, pressure, LH2 prepressurization and ground fill, P/U 34 psia, D/O 31 psia min
42	7851860-541	Switch, pressure, LH2 flight control, P/U 29.5 psia, D/O 26.5 psia
43	1A67005-507	Switch, pressure, LH2 tank orbital vent initiation, P/U 35.25 \pm 0.75 psia, D/O 31 psia min
44	1B53817-505	Valve, 3-way, LH2 tank pressure switch shutoff
45	1A49988-1	Valve, directional control, LH2 vent
46	1A49591-531	Valve, relief, LH2 tank, crack 40 psia max, reseal 37 psia min
47	1A48257-509	Valve, vent and relief, LH2 tank, crack 39 psia max, reseal 36 psia min
48	1A48858-1	Sphere, storage, cold helium (6 each)
49	1B58100-1	Probe, LH2 temperature sensor
50	1A48431-509	Probe, LH2 mass sensor
51	1A79603-509	Probe, LOX temperature sensor
52	1A48430-509	Probe, LOX mass sensor
53	1A49421-501	Pump, LH2 chilldown

* Indicates location in figures 3-1 and 3-2.

P/U = Pickup

D/O = Dropout

TABLE 3-1 (Sheet 3 of 4)
S-IVB-209 STAGE HARDWARE LIST

ITEM NO.*	PART NO.	NAME
54	1A58854-1	Orifice, LOX chilldown pump purge line, 600 sccm at 475 psid
55	1A58347-505	Module, LOX chilldown pump purge
55A	1B40622-511	Orifice, LOX chilldown pump purge module bypass, 10 scim at 475 psid
56	1A49423-507	Pump, LOX chilldown
57	1A49964-501	Valve, check, LOX chilldown return line
58	7851847-535	Switch, pressure, LOX chilldown pump purge regulator backup, P/U 53 psia max, D/O 49 psia min
59	114-109 (PESCO)	Valve, relief, LOX chilldown pump motor container, crack and reseal 65 to 85 psia
60	1A67913-1	Valve, vent, LOX chilldown pump motor container
61	1A49965-521	Valve, shutoff, LOX chilldown line
62	1A89104-509	Flowmeter, LOX chilldown line
63	1A87749-1	Strainer, LOX chilldown pump discharge
64	1A49968-509	Prevalve, LOX
65	1B66692-501	Module, actuation control, directional valve, LH2 vent
65 A&B	1B67481-1	Valve, check, directional valve actuation control module vent
66	1B66692-501	Module, actuation control, LH2 vent and relief valve
66 A&B	1B67481-1	Valve, check, LH2 tank vent and relief valve actuation control module vent
67	1A49964-501	Valve, check, LH2 chilldown return line
68	1B53817-505	Valve, 3-way, LOX tank pressure switch shutoff
69	7851847-533	Switch, LOX prepressurization, flight, and ground fill control, P/U 40 psia max, D/O 37 psia min
70	1B40622-501	Orifice, LOX tank pressure sensing line purge
71	1A49968-507	Prevalve, LH2
72	1B66692-501	Module, actuation control, prevalves and chilldown valves
72 A&B	1B67481-1	Valve, check, LOX vent and relief valve actuation control module vent
73	1B40622-507†	Orifice, LH2 chilldown shutoff valve purge line, 14 scfm
74	1A49965-523	Valve, shutoff, LH2 chilldown pump discharge
75	1A89104-509	Flowmeter, LH2 chilldown pump discharge

* Indicates location in figures 3-1 and 3-2.

P/U = Pickup

D/O = Dropout

† Flight orifice--for acceptance firing, purge function is supplied by facility orifice
65 scfm at 1,600 psia

TABLE 3-1 (Sheet 4 of 4)
S-IVB-209 STAGE HARDWARE LIST

ITEM NO.*	PART NO.	NAME
76	1B53920-503	Valve, check, LH2 chilldown pump discharge
77	1B52985-501	Strainer, LH2 chilldown pump discharge
78	1B51361-1	Valve, check, LOX vent and relief valve purge line
79	1B63206-1	Orifice, flow, LOX vent and relief valve purge line, 65 scfm
80	1A49590-517	Valve, relief, LOX tank, crack 45 psia, reseal 42 psia
81	1A48312-505	Valve, vent and relief, LOX tank, crack 44 psia, reseal 41 psia
82	1B66692-501	Module, actuation control, LOX vent and relief valve
83	1B56804-1	Module, engine purge control
84	1A67002-509	Switch, pressure, engine purge regulator backup, P/U 130 psia min, D/O 105 psia min
85	1A49958-521	Disconnect, engine start sphere vent and relief valve drain
86	1A49958-515	Disconnect, engine control helium sphere fill
87	1A49958-523	Disconnect, engine start sphere fill

* Indicates location in figures 3-1 and 3-2.

P/U = Pickup

D/O = Dropout

TABLE 3-2 (Sheet 1 of 3)
S-IVB-209 STAGE AND GSE ACCEPTANCE FIRING ORIFICES

ITEM*	DESCRIPTION	ORIFICE SIZE OR NOMINAL FLOWRATE	COEFFICIENT OF DISCHARGE	EFFECTIVE AREA (in. ²)
	<u>STAGE</u>			
7	Ambient helium fill	65 scfm	--	Sintered
13	LH2 fill and drain valve purge line	15 scim at 3,200 psid	--	Sintered
19	LOX fill and drain valve purge line	15 scim at 3,200 psig	--	Sintered
29	LOX tank pressurization system heat exchanger outlet	0.219 in. dia	0.85	0.03218
30	LOX tank pressurization system heat exchanger bypass	0.185 in. dia	0.85	0.02291
36	LH2 tank pressurization module			
	Undercontrol**	0.257 in. dia		0.0444
	Overcontrol**	0.223 in. dia		0.0777
	Step**	0.323 in. dia		0.1392
38	LH2 tank nonpropulsive vent purge line	1 scfm at 3,200 psid	--	Sintered
29-40	LH2 tank nonpropulsive vent (2)	2.180 in. dia	--	3.1726
54	LOX chilldown pump purge line	600 scim at 475 psid	--	Sintered
55	LOX chilldown pump purge module	0.00166 lb/sec at 475 psig IN and 85 psig OUT	†	
55A	LOX chilldown pump purge module bypass	10 scim at 475 psid	--	Sintered

* Indicates location in figures 3-1 and 3-2.

** Discharge coefficient and effective area are calculated for overcontrol and step orifices in successive combination with the undercontrol orifice.

† Flight orifice--for acceptance firing, purge function is supplied by facility orifice of 65 scfm at 1,600 psi.

TABLE 3-2 (Sheet 2 of 3)
S-IVB-209 STAGE AND GSE ACCEPTANCE FIRING ORIFICES

ITEM*	DESCRIPTION	ORIFICE SIZE OR NOMINAL FLOWRATE	COEFFICIENT OF DISCHARGE	EFFECTIVE AREA (in. ²)
70	LOX tank pressure sensing line purge	1 scfm at 3,200 psig	--	Sintered
73	LH2 chilldown valve purge line†	14 scfm at 3,000 psid	--	Sintered
79	LOX tank vent and relief valve purge line	65 scfm at 3,100 psid	†	0.00043
83	Engine pump purge module	0.00166 lb/sec at 475 psig IN and 85 psig OUT	--	0.00023
<u>CONSOLE A</u>				
--	All console A stage bleeds	Variable	--	--
A9515	Pressure actuated valve and mainstage pressure switch supply	1.2 scfm	--	Sintered
A9526	J-box inerting supply	0.013 in. dia	--	--
A9533	LH2 system checkout supply	1.2 scfm	--	Sintered
A9534	LOX system checkout supply	2.0 scfm	--	Sintered
A9535	LH2 tank and umbilical purge	0.260 in. dia	0.88	0.0467
A9536	Pressure switch checkout--low pressure	1.2 scfm	--	Sintered
A9537	Pressure switch checkout--high pressure	0.044 in. dia	--	--
A9538	LH2 tank repressurization supply (ambient helium supply)	Union	--	--
A9539	Console A GN2 inerting supply	0.013 in. dia	--	--

* Indicates location in figures 3-1 and 3-2.

† Flight orifice--for acceptance firing, purge function is supplied by
facility orifice of 65 scfm at 1,600 psi.

TABLE 3-2 (Sheet 3 of 3)
S-IVB-209 STAGE AND GSE ACCEPTANCE FIRING ORIFICES

ITEM*	DESCRIPTION	ORIFICE SIZE OR NOMINAL FLOWRATE	COEFFICIENT OF DISCHARGE	EFFECTIVE AREA (in. ²)
	<u>CONSOLE B</u>			
--	All console B stage bleeds	Variable	--	--
--	Turbine start sphere supply	--	--	--
--	LOX tank prepressurization supply	0.096 in. dia	0.94	0.00680
A9525	Engine control sphere supply	0.125 in. dia	0.84	0.01031
A9527	LH2 tank prepressurization	0.161 in. dia	0.94	0.0094
A9528	Thrust chamber jacket purge and chilldown system	0.072 in. dia	0.89	0.00362
A9529	LOX tank and umbilical purge system	0.305 in. dia	--	--
A9540	J-box inerting supply	0.013 in. dia	--	--
A9550	Engine control sphere supply vent	--	--	--
A9552	Turbine start sphere GH2 supply vent	0.081 in. dia	0.83	0.00479
OR395	LH2 tank auxiliary pressuriza- tion	0.395 in. dia	--	--
OR396	LOX tank auxiliary pressuriza- tion	0.395 in. dia	--	--

* Indicates location in figures 3-1 and 3-2.

TABLE 3-3
S-IVB-209 STAGE PRESSURE SWITCHES

PARAMETER	PART NO.	SPECIFIED (psia)		PRETEST (psia)	
		PICKUP	DROPOUT	PICKUP	DROPOUT
<u>LH2 Tank Pressurization System</u>					
Flight control	7851860-541	30.0 max	26.5 min	29.26	27.17
Prepressurization and ground fill valve control	7851860-537	34.5 max	30.8 min	33.49	31.03
Orbital vent	7851860-543	35.0 ± 1	30.5 min	35.24	31.92
<u>LOX Tank Pressurization System</u>					
LOX prepress, flight control, and ground fill valve control	7851847-533	41.0 max	36.5 min	40.02	37.57
LOX tank regulator backup	7851830-517	467.5 ± 23.5	352.5 ± 23.5	458.3	355.4
<u>Pneumatic Control System</u>					
Power control module	7851830-521	600 ± 21	490 ± 31	599.1	499.2
LOX chilldown pump motor container	7851847-535	54 max	49 min		
Engine pump purge	1A67002-509	130 max	105 min	125.0	114.2
<u>J-2 Engine</u>					
Mainstage OK No. 1	NA5-27453	515 ± 30	P/U minus 62.5 ± 31.5	526.70	458.30
Mainstage OK No. 2	NA5-27453	515 ± 30	P/U minus 62.5 ± 31.5	529.41	465.50

NOTES: All pressures listed are the average of three actuations.

P/U = Pickup




Figure 3-1. Propulsion System Configuration and Instrumentation




Figure 3-2. Facility Propellant and Pneumatic Loading Systems (Sheet 1 of 2)




Figure 3-2. Facility Propellant and Pneumatic Loading Systems (Sheet 2 of 2)

4. COUNTDOWN OPERATIONS

The S-IVB-209 stage acceptance firing was successfully accomplished during CD 614085 on 20 June 1967. All phases of the acceptance firing countdown are reviewed and evaluated in the following paragraphs, which include discussions of the prefiring checkout, propellant loading, and ground support and facility operations.

4.1 Countdown 614084 (Run 1A, Run 1B)

Countdown 614084 was initiated on 13 June and proceeded smoothly through propellant loading. Two firing attempts were made on 14 June. Run 1A proceeded to T_0 -822.9 sec when an erratic augmented spark igniter (ASI) ignition detection signal was received on the "Engine Ready" scan. The automatic count was halted and the stage was recycled automatically to T_0 -25 min. The problem was isolated to an overly sensitive ignition detection probe, and the system amplifier was adjusted slightly. The acceptance firing was also modified to avoid looking for ignition detection until after the probe had been chilled down.

Run 1B was picked up at the initiation of terminal count, T_0 -25 min, at 1550 PDT and proceeded smoothly to the engine start sequence. When the computer sent the Switch Selector LOX Chillydown Pump Reset Command, it did not receive the proper complementary answer which would permit the command to be executed, and the test was manually cut off and the countdown terminated.

4.2 Countdown 614085 (Run 2A)

Countdown 614085 was initiated on 19 June. Propellant loading proceeded smoothly, although LH2 depletion sensor No. 1 cycled three times. Terminal count was initiated at 1114 hr on 20 June, and the acceptance firing successfully completed. Cutoff was automatically initiated by the PU processor due to LOX depletion (1 percent residual) after 455.95 sec of mainstage operation. All systems operated properly with the exception of the LOX tank pressurization system, which is discussed in section 7. Specific countdown times are presented in table 4-1.

4.3 Countdown 614086 (Special Tests)

After the acceptance firing, the stage was reloaded with propellants on 23 June to conduct additional tests on the LH2 chilldown system and the LH2 depletion sensors. The purpose of these tests was to investigate the effect of the LH2 chilldown duct fairing purge media upon the LH2 pump chilldown. The data obtained from these tests should provide some insight into the abnormal chilldowns that occurred during the S-IVB-207 and 208 acceptance firings. These data are presently being analyzed.

4.4 Checkout

The modifications, procedures, and checkouts performed for the acceptance firing were initiated on 10 March 1967, when the stage was received at the Sacramento Test Center, and continued through 12 June when the stage was ready for the acceptance firing. The handling and checkout procedures that were used for the prefiring and post-firing checkouts are described in Douglas Report DAC 56501, *Narrative End Item Report on Saturn S-IVB-209, Volume 1, SSC*, dated March 1967.

After the prefire modifications and limited prefire checkout were performed at the Vertical Checkout Laboratory, the stage was installed on Complex Beta Test Stand I on 15 May. The prefire checkout of the stage was completed 4 weeks later; the "Ready for Acceptance Firing" milestone was met on 12 June 1967.

4.5 Cryogenic Loading

The S-IVB-209 stage was successfully loaded with LOX, LH2, and cold helium.

4.5.1 LOX Loading

The LOX loading procedures were conducted as specified in Task 41 of the Countdown Manual. Preparations were completed and computer controlled loading operations were initiated without incident. Loading data for CD 614085 are presented in figure 4-1.

4.5.2 LH2 Loading

The LH2 loadings were conducted as specified in Task 42 of the Countdown Manual and proceeded smoothly, although LH2 depletion sensor No. 1 cycled several times during CD 614085, run 2A. LH2 loading data for CD 614085 are presented in figure 4-2.

4.5.3 Cold Helium Loading

Cold helium was loaded after the completion of LH2 loading. Satisfactory temperatures and pressures were attained although, due to a short chill-down period, the temperature was slightly higher than normal. Data from CD 614085 are presented in figure 4-3.

4.6 GSE Performance

4.6.1 GH2 Supply System

The GH2 supply system performed adequately. Start sphere chilldown and loading were satisfactorily accomplished. At Engine Start Command, the engine start sphere conditions were within the required limits. Data are presented in figure 4-4.

4.6.2 Helium Supply System

The helium supply system functioned adequately. Propellant tank prepressurization, thrust chamber chilldown, cold helium spheres loading, and stage and engine control sphere loading were all satisfactorily accomplished. Following each prepressurization cycle the ambient helium supply pressure (D0778) shifted upward, due to a regulator shift. This has occurred on other firings and is not considered abnormal. Data are presented in figures 4-5 through 4-7.

4.7 Countdown Problem Summary

4.7.1 Countdown 614084

This countdown was aborted when no ignition was obtained at $T_0 + 150$ sec,

and manual cutoff was initiated when it was evident that a malfunction had occurred. The following problems were encountered:

- a. While the bonnet screws on the LOX main fill valve were being torqued during Task 7, Propellant Transfer Lines Preparation and Controls Check, the valve cycled closed. Investigation of the closing of the valve revealed that it was closed from an interlock command sent during Task 9, Redline Checks.
- b. During the terminal count, at $T_0 - 822.9$ sec, the engine control bus power was lost and no power was on the engine bus. Investigation revealed that when the computer scanned the engine for a readiness check, it found power on the engine ignition detection circuit. The computer automatically turned off the engine control bus power and returned the count to $T_0 - 25$ min, as programmed. A manual check of the situation could not duplicate the problem, so the countdown was restarted as run 1B.
- c. During the terminal count of run 1B at $T_0 + 150$ sec, or at the time of engine ignition, no ignition occurred and manual cutoff was initiated. Investigation revealed that when the computer program gave the command for LOX chilldown pump reset, it did not receive the complementary answer that would permit execution of the command. The test was manually cut off and the countdown was terminated.

After considerable troubleshooting, three relays within the computer control equipment were replaced. Although the precise cause of the problem was not pinpointed, it is felt that the probable cause was a single, random malfunction in the response conditioner.

4.7.2 Countdown 614085

Five problems were encountered during this countdown; however, none of the problems required a delay in countdown time.

- a. During Task 14, Abort Mode Checks, the forward bus No. 1 power supply malfunctioned because a defective fan system caused it to overheat. The unit was replaced.

- b. During Task 39, LOX loading, the digital events recorder malfunctioned and required reloading.
- c. The LH2 depletion sensor No. 1 cycled twice from wet to dry at the 31, 34, and 60 percent levels for durations of 7, 12, and 9 ms, respectively, then indicated normally.
- d. The main LH2 storage tank shutoff valve, ROV-408, was reported to be leaking externally during the firing.
- e. At approximately $T_0 - 1$ hr, the safety cutoff-gas generator exhaust temperature measurement began to indicate erratically.

4.8 Atmospheric Conditions

The atmospheric conditions at specific times during the countdowns are presented in the following paragraphs.

4.8.1 Countdown 614084

Time (PDT)	1000	1200	1400	1600
Wind speed (knots)	3	4	9	6
Wind direction (deg)	200	290	280	270
Barometric pressure (in. Hg)	29.85	29.84	29.82	29.78
Ambient temperature (deg F)	75	79	85	88
Dew point (deg F)	54	55	53	47

4.8.2 Countdown 614085

Time (PDT)	0800	0900	1000	1100	1200
Wind speed (knots)	3	4	4	3	4
Wind direction (deg)	170	200	200	260	210
Barometric pressure (in. Hg)	29.91	29.89	29.88	29.86	29.86
Ambient temperature (deg F)	61	65	70	75	79
Dew point (deg F)	33	54	56	57	56

TABLE 4-1
 TERMINAL COUNTDOWN SEQUENCE (CD 614085)

EVENT	TIME FROM T ₀ (sec)
Start sphere purge supply OPEN .	-1230.144
Thrust chamber purge CLOSED	-1200.097
Thrust chamber chilldown OPEN	-1199.966
Start sphere purge supply CLOSED	-873.332
Start sphere GH2 fill supply OPEN	-869.383
LOX chilldown pump ON	-598.228
LH2 chilldown pump ON	-595.057
LH2 prevalve CLOSED	-591.385
LOX prevalve CLOSED	-591.195
Start sphere GH2 fill CLOSED	-327.595
Start sphere supply vent OPEN	-327.458
LOX tank vent valve CLOSED	-160.672
LH2 tank vent valve CLOSED	-163.319
Cold helium regulator backup switch ENABLED	-92.493
LOX fill and drain valve CLOSED	-52.149
LH2 fill and drain valve CLOSED	-51.087
LH2 directional vent to flight position	-31.951
Cold helium sphere supply OFF	-3.444
Engine control sphere fill CLOSED	-3.360
Simulated Liftoff (11:39:34.000)	0
Engine pump purge OFF	90.824
LH2 prevalve OPEN	150.155
LOX prevalve OPEN	150.570
LH2 chilldown pump OFF	151.574
LOX chilldown pump OFF	151.663
Engine Start Command	151.847
LOX pressurization system ON	152.709
Step pressurization	452.057
Engine Cutoff Command	610.682




Figure 4-1. LOX Tank Loading




Figure 4-2. LH2 Tank Loading





Figure 4-3. Cold Helium System Loading





Figure 4-4. GSE Performance During Engine Start Sphere Chilldown and Loading




Figure 4-5. GSE Performance During Engine Control Sphere Loading





Figure 4-6. GSE Performance During LOX and LH2 Tank Prepressurization





Figure 4-7. GSE Performance During Thrust Chamber Chilldown

5. SEQUENCE OF EVENTS

The S-IVB-209 stage acceptance firing sequence of events is presented in table 5-1. Event times from three data sources are included in the table. These sources were Digital Events Recorder (DER/CAT 57), PCM/FM Sequence (CAT 42), and PCM/FM Digital Tabulation (PCM/TAB/CAT 45).

Accuracies of the listed events are as follows:

<u>DATA SOURCE</u>	<u>ACCURACIES</u>
Digital Events Recorder (DER/CAT 57)	+0, -1 ms
PCM/FM	
Discrete Bi-Level (CAT 42)	+0, -9 ms
Digital Tabulation (CAT 45)	
Prime	+0, -9 ms
Submultiplex	+0, -84 ms

TABLE 5-1 (Sheet 1 of 9)
SEQUENCE OF EVENTS

EVENT/RESULT OF COMMAND	SWITCH SELECTOR CHANNEL	DIGITAL EVENT RECORDER (CAT 57)		PCM/FM SEQUENCE (CAT 42)		PCM/FM DIGITAL TABULATION (CAT 45)	
		MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)
Launch Automatic Sequence Start							
Auxiliary Hydraulic Pump ON	28	K0513	-693.589				
Auxiliary Hydraulic Pump Coast Mode OFF	31	K3890	-694.332				
LOX Chilldown Pump ON	22	K0519	-598.228				
LH2 Chilldown Pump ON	58	K0512	-595.057				
Engine Pump Purge Control Valve Open Command	24	K3890	-92.493				
Internal Power Transfer							
Pwr Aft Bus 1 Int Transfer		K0622	-27.371				
Pwr Aft Bus 2 Int Transfer		K0623	-27.118				
Pwr Fwd Bus Int Transfer		K0639	-26.867				
Simulated Liftoff (T_0)*			0.000				
Inflight Cal ON		K3890	91.819				
Inflight Cal OFF		K3890	92.942				
Ullage Rocket Chg ON Cmd	54	K3890	142.600				

* T_0 = 1139:34.000 PDT

TABLE 5-1 (Sheet 2 of 9)
SEQUENCE OF EVENTS

EVENT/RESULT OF COMMAND	SWITCH SELECTOR CHANNEL	DIGITAL EVENT RECORDER (CAT 57)		PCM/FM SEQUENCE (CAT 42)		PCM/FM DIGITAL TABULATION (CAT 45)	
		MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)
EBW Charge 1-1	56	K3890	146.893			M0032	143.3
EBW Charge 1-2						M0033	143.4
EBW Charge 2-1						M0034	143.5
EBW Charge 2-2						M0035	143.3
EBW Charge 3-1						M0036	143.4
EBW Charge 3-2						M0037	143.3
Ullage Rocket Fire Cmd							
EBW Fire 1-1				K0143	146.929	M0032	146.9
EBW Fire 1-2				K0144	146.929	M0033	146.9
EBW Fire 2-1				K0145	146.937	M0034	146.9
EBW Fire 2-2				K0146	146.937	M0035	146.9
EBW Fire 3-1				K0147	146.937	M0036	146.9
EBW Fire 3-2				K0148	146.937	M0037	146.9
Pre-Valve Open Cmd		K0576	147.560				
LH2 Pre-Valve Open		K0540	150.155				
LOX Pre-Valve Open		K0541	150.570				

TABLE 5-1 (Sheet 3 of 9)
SEQUENCE OF EVENTS

EVENT/RESULT OF COMMAND	SWITCH SELECTOR CHANNEL	DIGITAL EVENT RECORDER (CAT 57)		PCM/FM SEQUENCE (CAT 42)		PCM/FM DIGITAL TABULATION (CAT 45)	
		MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)
LH2 Chilldown Pump OFF Cmd	59	K0512	151-574				
Engine Cutoff OFF Cmd	13	K3890	151.372				
Engine Cutoff Command ON (Dropout)		K0522	151.381	K0140	151.387		
Chilldown Pump Discharge Valve Closed Cmd		K0577					
LH2 Chilldown Pump OFF		K0512	151.574				
LOX Chilldown Pump OFF Cmd	23	K3890	151.656				
LOX Chilldown Pump OFF		K0519	151.663				
LOX Chilldown Valve Closed		K0552	151.844				
LH2 Chilldown Valve Closed		K0551	151.556				
Engine Start ON Cmd (ESC)*	9	K3890	151.847				
Thrust Chamber Spark Sys ON		K0454	151.850	K0010	151.851		
Gas Generator Spark ON		K0455	151.850	K0011	151.851		
Helium Control Solenoid Energized		K0531	151.850	K0007	151.851		
Engine Ready Signal OFF		K0530	151.854	K0012	151.920		
Engine Start ON		K0556	151.847				

*ESC = $T_0 + 151.847$ sec

TABLE 5-1 (Sheet 4 of 9)
SEQUENCE OF EVENTS

EVENT/RESULT OF COMMAND	SWITCH SELECTOR CHANNEL	DIGITAL EVENT RECORDER (CAT 57)		PCM/FM SEQUENCE (CAT 42)		PCM/FM DIGITAL TABULATION (CAT 45)	
		MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)
Ignition Phase Control Solenoid Energ	27	K0535	151.849	K0006	151.851		
Main Fuel Valve Closed (Dropout)		K0632	151.902	K0119			
Main Fuel Valve Open		K0118		K0118	152.003		
Ignition Detected		K0537	152.044	K0008	152.043		
Engine Start OFF Cmd		K3890	152.398				
Engine Start OFF	103	K0556	152.401				
Start Tank Discharge Valve Close (Dropout)		K0695	153.084	K0123			
Start Tank Discharge Valve Open		K0536	153.379	K0122	153.253		
LOX Tank Flight Pressure System ON Cmd		K3890	152.709				
Mainstage Control Solenoid Energized		K0538	153.382	K0005	153.385		
Main Oxidizer Valve Closed (Dropout)		K0633	153.468	K0121			
Gas Generator Valve Closed (Dropout)		K0631	153.482	K0116			
Start Tank Discharge Valve Closed		K0695	153.702	K0122	153.503		

TABLE 5-1 (Sheet 5 of 9)
SEQUENCE OF EVENTS

EVENT/RESULT OF COMMAND	SWITCH SELECTOR CHANNEL	DIGITAL EVENT RECORDER (CAT 57)		PCM/FM SEQUENCE (CAT 42)		PCM/FM DIGITAL TABULATION (CAT 45)	
		MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)
Gas Generator Valve Open	68	K0457	153.617	K0117	153.670		
Oxidizer Turbine Bypass Valve Open (Dropout)		K0461	153.631	K0124	153.678		
Oxidizer Turbine Bypass Valve Closed		K0463	153.828	K0125	153.845		
Mainstage Pressure Switch Depress B (Dropout)		K0573		K0159	154.945		
Mainstage Pressure Switch Depress A (Dropout)		K0572		K0158	154.945		
Mainstage OK		K0610	154.907	K0014	154.920		
Engine Burn No. 1 ON Cmd		K3890	154.858				
Engine Burn No. 1 ON (LH2 Tnk Step Press Cont Sol)		K0523	154.866				
Main Oxidizer Valve Open		K0459	155.522	K0120	155.586		
Gas Generator Spark System ON (Dropout)		K0455	156.679	K0011	156.684		
Thrust Chamber Spark System ON (Dropout)	5	K0454	156.680	K0010	156.684		
PU Activate Cmd		K3890	158.047				

TABLE 5-1 (Sheet 6 of 9)
SEQUENCE OF EVENTS

EVENT/RESULT OF COMMAND	SWITCH SELECTOR CHANNEL	DIGITAL EVENT RECORDER (CAT 57)		PCM/FM SEQUENCE (CAT 42)		PCM/FM DIGITAL TABULATION (CAT 45)	
		MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)
PU Activate		K0507	158.052				
Ullage Rocket Jettison Charge ON Cmd	55	K3890	176.078				
EBW Charge 1						M0038	176.8
EBW Charge 2						M0039	176.8
Ullage Rocket Jettison Fire ON Cmd	57	K3890	179.209				
Ullage Jettison Charge Cmd Reset	88	K3890	179.297				
EBW Fire 1				K0149	179.269	M0038	179.3
EBW Fire 2				K0150	179.269	M0039	179.3
Ullage Jettison Fire Cmd Reset	73	K3890	179.384				
Range Safety OFF Enable ON Cmd	85	K3890					
Auxiliary Hydraulic Pump OFF Cmd	29	K3890	337.489				
Auxiliary Hydraulic Pump ON (Dropout)		K0513	337.755				
Auxiliary Hydraulic Pump ON Cmd	28	K3890	384.355				
Auxiliary Hydraulic Pump ON		K0513	384.439				
First Burn Relay OFF Cmd	69	K3890	452.050				

TABLE 5-1 (Sheet 7 of 9)
SEQUENCE OF EVENTS

EVENT/RESULT OF COMMAND	SWITCH SELECTOR CHANNEL	DIGITAL EVENT RECORDER (CAT 57)		PCM/FM SEQUENCE (CAT 42)		PCM/FM DIGITAL TABULATION (CAT 45)	
		MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)
First Burn Relay OFF	97	K0523	452.057				
Point Level Sensor ON Cmd		K3890					
Non Programmed Engine Cutoff Cmd		K0419	610.688				
Cutoff Signal Energized							
Ignition Phase Control Solenoid Energized (Dropout)		K0535	610.685	K0006	610.687		
Mainstage Control Solenoid Energized (Dropout)	12	K0538	610.687	K0005	610.687		
Engine Cutoff ON Cmd		K3890					
Engine Cutoff Command ON (ECC)*		K4797.	610.682	K0140	610.698		
Main Oxidizer Valve Open (Dropout)		K0633	610.882	K0120	610.814		
Gas Generator Valve Open (Dropout)		K0631	610.867	K0117	610.731		
Main Fuel Valve Open (Dropout)	24	K0632	610.992	K0118	610.814		
Engine Pump Purge Control Valve Open Cmd		K3890	611.332				
Gas Generator Valve Closed		K0631	610.849	K0116			
Mainstage Pressure Switch B Depress		K0573	610.852	K0159	610.923		

*ECC = T_0 + 610.682 sec

TABLE 5-1 (Sheet 8 of 9)
SEQUENCE OF EVENTS

EVENT/RESULT OF COMMAND	SWITCH SELECTOR CHANNEL	DIGITAL EVENT RECORDER (CAT 57)		PCM/FM SEQUENCE (CAT 42)		PCM/FM DIGITAL TABULATION (CAT 45)	
		MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)
Mainstage Pressure Switch A Depress		K0572	610.857	K0158	610.923		
Main Oxidizer Valve Closed		K0633	610.882	K0121			
Main Fuel Valve Closed		K0632	610.992	K0019			
Fuel Pre-Valve Open (Dropout)		K0540	612.089	K0111	612.139		
Oxidizer Pre-Valve Open (Dropout)		K0541	612.091	K0109	612.139		
Fuel Pre-Valve Closed		K0549	612.421	K0112	612.473		
Oxidizer Pre-Valve Closed		K0550	612.616	K0110	612.639		
Helium Control Solenoid De-energized		K0531		K0007			
Coast Period ON Cmd	79	K3890					
Engine Start OFF Command	27	K3890	612.175				
LH2 Chilldown Pump OFF Command	59	K3890	612.412				
LOX Chilldown Pump OFF Command	23	K3890	612.313				
PU Activate OFF Cmd	6	K3890	613.817				
PU Activate OFF		K0507	613.820				
PU Inverter and DC Power OFF Cmd	8	K3890					

TABLE 5-1 (Sheet 9 of 9)
SEQUENCE OF EVENTS

EVENT/RESULT OF COMMAND	SWITCH SELECTOR CHANNEL	DIGITAL EVENT RECORDER (CAT 57)		PCM/FM SEQUENCE (CAT 42)		PCM/FM DIGITAL TABULATION (CAT 45)	
		MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)	MEAS NO.	TIME (sec)
Point Level Sensors Disarm Cmd	98	K3890	613.965				
Ullage Jettison Charge Command Reset	88	K3890	615.445				
First Burn Relay OFF Command	69	K3890	615.533				
Ullage Jettison Fire Command Reset	73	K3890	615.620				

6. ENGINE SYSTEM

The S-IVB-209 stage acceptance firing was performed with an uprated (230,000-lbf-thrust) Rocketdyne engine S/N 2083 (figure 6-1) mounted on the stage. The engine was manufactured in the designated configuration baseline for J-2 engines S/N 2077 and subs as described in the Rocketdyne configuration report (R-5788) and contained orifice diameters of 0.276 in. LOX and 0.481 in. LH2 in the gas generator feed system. The engine had a 1-sec start tank discharge valve timer in the engine control circuit and prior to the acceptance firing blank orifices were installed in the start tank refill system to prevent start tank refill. There were no other significant engine modifications affecting engine performance.

6.1 Engine Chillover and Conditioning

6.1.1 Turbopump Chillover

Chillover of the engine LOX and LH2 turbopumps was adequate to provide the conditions required for proper engine start. An analysis of the chillover operations is presented in paragraphs 7.3 and 8.2.

6.1.2 Thrust Chamber Chillover

The thrust chamber skin temperature (figure 6-2) was 230 deg R at Engine Start Command (ESC), well within the engine start requirement of 260 \pm 50 deg R; this resulted in satisfactory start transient buildup characteristics for the LH2 pump (figure 6-3). Data are presented in table 6-1. Further information on the chillover operation and ground support equipment supply system is presented in section 4.

6.1.3 Engine Control Sphere Chillover and Loading

Engine control sphere conditioning was adequate (figure 6-4), and all objectives were satisfactorily accomplished. The engine start requirement of 2,000 to 3,450 psia was met. Significant control sphere performance data are presented in table 6-2.

6.1.4 Engine Start Sphere Chillover and Loading

Chillover and loading of the engine GH2 start sphere met the requirements

for engine start. Start sphere performance data are presented in figure 6-5. The GH2 supply system performance during start sphere chill-down and loading is described in section 4. The sphere warmup rate from sphere pressurization to blowdown was 2.87 deg R/min. Since the S-IVB-209 stage may be utilized in the orbital workshop program, and thus may have to be passivated in orbit, the start sphere was not repressurized during engine operation.

6.2 J-2 Engine Performance Analysis Methods and Instrumentation

Engine performance for the acceptance firing was calculated by use of computer programs AA89, G105-1, and F823-1. Computer program PA49 presents the average performance results. Computer program PA53 was used to compute start and cutoff transient engine performance. A description of the operation and a comparison of the results of each program is presented in table 6-3. Data inputs to the computer programs with the applicable biases are shown in table 6-4.

6.3 J-2 Engine Performance

The engine performance was satisfactory. Plots of selected data showing engine characteristics are presented in figures 6-6 through 6-11. The engine propellant inlet conditions are presented in sections 7 and 8.

The engine performance levels were comparable, within the run-to-run deviations, to the levels established during the Rocketdyne stage acceptance firing series and the stage acceptance firing prediction. The performance profiles determined by the programs discussed in paragraph 6.2 are shown in figure 6-12; the composite values which constitute the final engine performance values are shown in table 6-5.

Flow integral mass analysis indicates that 189,949 lbm of LOX and 36,856 lbm of LH2 were consumed between Engine Start Command and Engine Cutoff Command (ECC). This value of propellant consumption will be further refined and presented in the flow integral cryogenic calibration report on the S-IVB-209 stage propellant utilization system. The analysis also indicates that the overall stage average thrust from the 90 percent performance level (ESC +3.799 sec) to engine cutoff (ESC +458.836 sec)

was 212,412 lbf. The average mixture ratio and specific impulse were 5.192 and 426.8 sec, respectively, for the same time period. The variation of specific impulse with mixture ratio is shown in figure 6-13. The total impulse generated from Engine Start Command to Engine Cutoff Command was 97.67×10^6 lbf-sec. Extrapolation of the propellant residuals as indicated by the point level sensors (2,311 lbm of LOX, 1,366 lbm of LH2) indicates that a LOX depletion cutoff would have occurred at ECC +5.148 sec. In that time, an additional 937,591 lbf-sec impulse would have been generated, making the total stage potential impulse from Engine Start Command to depletion cutoff 98.61×10^6 lbf-sec, as compared to the predicted value of 98.53×10^6 lbf-sec. The 0.08 percent deviation is within the predicted accuracy of approximately 1 percent. The 4.228 sec difference between the actual and predicted times is also within the prediction accuracy.

6.3.1 Start Transient

The J-2 engine start transient was satisfactory. A summary of engine performance is presented in the following table:

	<u>Acceptance Firing</u>	<u>Log Book</u>
Time to 90 percent performance level (sec)	3.799	3.48
Start Tank Discharge Valve Command (sec)	ESC +1.083	ESC +1.0
Thrust rise time (sec)	2.439	2.00
Total impulse (lbf-sec)	186,220	159,926*
Maximum rate of thrust increase (lbf/sec)	6,370	40,000**

* Based on stabilized thrust at null PU and standard altitude conditions (test No. 313-082)

** Maximum allowable

Thrust buildup to the 90 percent performance level (627 psia thrust chamber pressure for the uprated engine) was within the maximum and

minimum thrust bands. The deviation in total impulse (log book) is due to longer thrust rise time (time from first indication of thrust to the 90 percent performance level) during the acceptance firing. The total impulse accumulated during the start transient is shown in figure 6-14. Figure 6-15 shows the thrust chamber pressure during start transient and the thrust buildup to the 90 percent performance level for the acceptance firing as determined by computer program PA53. As expected, thrust overshoot during the start transient did not occur. No correction was made on acceptance firing data for main LOX valve skin temperature, as these data are not available.

6.3.2 Steady-State Performance

Satisfactory performance of the J-2 engine was demonstrated throughout the steady-state portion of the engine burn. No evidence of an engine performance shift was found in any of the engine instrumentation.

Table 6-5 compares the overall average performance values during steady-state operation with the predicted performance values. The S-IVB-209 stage utilized an uprated (230,000 lbf thrust) J-2 engine which explains the high performance values. The deviation between the PU valve cutback time prediction and the actual PU valve cutback time is discussed in section 10.

Engine thrust variations occurring during the acceptance firing are presented in table 6-6. These thrust variations are compared to the predicted acceptance firing thrust history and the Contract End Item (CEI) thrust variation limits for flight. The CEI limits do not apply to acceptance firing performance and are presented for reference only. The thrust variations will be modified by flight effects on stage operation.

Figure 6-16 presents expanded thrust plots illustrating thrust variations noted during the following phases of engine operations:

a. Hardover, or maximum engine mixture ratio operation (EMR = 5.5)

The thrust variations during hardover operation were within the CEI limits for normal engine operation. Normal operating thrust

variations during this period of engine burn are caused by stabilization of the engine and by stage perturbations, including the effects of variations in propellant supply environmental condition, and propellant tank pressurization requirements.

b. Transient from PU valve cutback +65 sec to ECC -70 sec

Thrust variations during the transient period from PU valve cutback +65 sec to ECC -70 sec were within the CEI limits for normal engine operation. The thrust variations during this period were caused by stabilization of the engine after cutback and can be directly linked to movements of the PU valve.

c. Final 70 sec of burn

Thrust variations during the final 70 sec of engine burntime were within the CEI limits for normal engine operation. These thrust variations were mainly due to movements of the PU valve. These movements will be modified somewhat by flight effects on stage performance and by improved flight calibration of the PU system.

6.3.3 Cutoff Transient

The time between engine cutoff, as received at the J-2 engine and monitored by event measurement K0539 (time of cutoff = $T_0 + 610.683$ sec), and thrust decrease to 11,500 lbf was within the maximum allowable time of 800 ms for the acceptance firing as shown in the following table:

	<u>Acceptance Firing</u>	<u>Log Book</u>	<u>Allowable</u>
Thrust decrease to 11,500 lbf (ms)	370	359	340 \pm 30
Total impulse (lbf-sec)	34,636*	35,411**	34,100 \pm 1,300

* PU valve at -13.5 deg

** PU valve at null position, standard altitude conditions, includes -2,400 lbf-sec correction for time bias due to inherent electronic circuitry system delays

The performance values presented are in satisfactory agreement with the log book and the Rocketdyne J-2 Engine Manual No. K-3825-1. The stage acceptance firing does not include a correction for main LOX valve skin temperature deviation from 0 deg F or PU valve deviation from null position. Figures 6-17 and 6-18 present the data for the accumulated cutoff impulse, thrust chamber pressure cutoff transient, and the cutoff thrust to the 11,500 lbf level, as calculated by computer program PA53.

6.4 Engine Sequencing

The engine sequencing was satisfactory throughout the acceptance firing and compatible with the engine logic and the acceptance firing test plan. Table 6-7 and figure 6-19 illustrate the event times recorded during the acceptance firing. The measured values are compared with nominal or log book values. Most of the disagreements between measured and log book values are insignificant and may be ascribed to sampling rate errors or effects of the liquids that are present during the acceptance firing but absent during log book testing. The opening time of the gas generator valve was slower than nominal, but this caused no ill effects to the firing.

6.5 Component Operation

All components on the J-2 engine (S/N 2083) performed satisfactorily during the S-IVB-209 acceptance firing. The main LOX valve opened satisfactorily. The opening time data were as follows:

<u>Item</u>	<u>Specification</u>	<u>Actual</u>
First stage travel (ms)	50 \pm 25	55
First plateau (ms)	510 \pm 70	533
Second stage travel (ms)	1,825 \pm 75	1,804
Total time (ms)	2,385 \pm 170	2,392

All times were within specifications, indicating nominal main LOX valve performance during valve opening. The valve closing time was 170 ms which was approximately 35 ms longer than the maximum specified; however, this did not contribute to any significant increase in cutoff transient impulse.

The performance of the pumps, turbines, and gas generator were satisfactory. Data indicative of the performance of these components are shown in figures 6-9, 6-10, and 6-11, respectively. PU valve performance was also satisfactory and is discussed in section 10.

The engine-driven hydraulic pump performed satisfactorily during the acceptance firing. The gimbal program was conducted between approximately ESC +69 and ESC +125 sec. Calculation made during the gimbal program showed the following hydraulic pump performance.

<u>Time from ESC (sec)</u>	<u>Horsepower Required (hp)</u>
80	6.4
101	6.2

This is point function data only and no extrapolations are to be made between the time points given. For times prior to ESC +69 sec and after ESC +125 sec, the required horsepower was 4.8.

6.6 Engine Vibration

Five vibration measurements were monitored on the engine which included one at the LOX turbopump, one at the LH2 turbopump, and three on the combustion chamber dome. All measurements provided usable data and are shown as power spectral density plots (figure 6-20). The vibration levels at these locations were comparable to those measured on past acceptance firings.

TABLE 6-1
THRUST CHAMBER CHILLDOWN

PARAMETER	S-IVB-209	S-IVB-208	S-IVB-207
Engine Start Requirement (°R)	260 \pm 50	260 \pm 50	260 \pm 50
Thrust Chamber Chilldown Initiated (sec)*	-1,200	-1,201	-1,200
Thrust Chamber Chilldown Terminated (sec)*	128	127	127
Thrust Chamber Skin Temperature at End of Chilldown (°R)	223	227	240
Thrust Chamber Temperature at Engine Start (°R)	230	230	250

*Time from simulated liftoff (T_0)

TABLE 6-2
ENGINE CONTROL SPHERE PERFORMANCE

PARAMETER	TEMPERATURE (°R)			PRESSURE (psia)			MASS (lbm)		
	S-IVB 209	S-IVB 208	S-IVB 207	S-IVB 209	S-IVB 208	S-IVB 207	S-IVB 209	S-IVB 208	S-IVB 207
Engine Start Requirement	None	290 \pm 30'	290 \pm 30'	2,000 to 3,450	2,800 to 3,450	---	---	---	---
Engine Start Command	289	270	296	2,877	3,144	3,264	1.90	2.08	1.98
Engine Cutoff	*271	229	252	2,243	2,139	2,187	1.56	1.73	1.61
Total Helium Usage	---	---	---	---	---	---	0.34	0.35	0.37

*The start sphere was not recharged.

TABLE 6-3
COMPARISON OF COMPUTER PROGRAM RESULTS

PROGRAM	INPUT	METHOD	RESULTS
AA89	LOX and LH2 pump inlet pressures and temperatures, PU valve position, and engine tag values	Influence equations relate nominal inlet conditions to nominal performance. Using actual inlet conditions, PU valve position and engine tag values, the actual performance is simulated.	$F = 213,739 \text{ lbf}$ $\dot{W}_T = 501.22 \text{ lbm/sec}$ $I_{sp} = 426.59 \text{ sec}$ $MR = 5.203$
G105 Mode 3	LOX and LH2 flowmeters, pump discharge pressures and temperatures, chamber pressures, chamber thrust area	Flowrates are computed from flowmeter data and propellant densities. The C_F is determined from equation $C_F = f(P_C, MR)$ and thrust is calculated from equation $F = C_F A_t P_C$.	$F = 211,812 \text{ lbf}$ $\dot{W}_T = 498.05 \text{ lbm/sec}$ $I_{sp} = 425.39 \text{ sec}$ $MR = 5.206$
F823 Mode 1	Thrust chamber pressure, gas generator pressure, fuel injection temperature, fuel pump discharge temperature, fuel turbine inlet temperature	Total flows of the thrust chamber and gas generator are calculated as a function of respective chamber pressures. Mixture ratio of the chamber is calculated as a function of temperature rise of the fuel in the cooling jacket, and mixture ratio of the GG is calculated as a function of turbine inlet temperature. Thrust is calculated from the equation $F = C_F A_t P_C$.	$F = 211,686 \text{ lbf}$ $\dot{W}_T = 494.48 \text{ lbm/sec}$ $I_{sp} = 428.30 \text{ sec}$ $MR = 5.166$
PA53	Thrust chamber pressure, chamber throat area	The C_F is computed from equation $C_F = f(P_C)$ and thrust is computed from equation $F = C_F A_t P_C$. The impulse is determined from integrated thrust.	Refer to paragraphs 6.3.1 and 6.3.3.

TABLE 6-4 (Sheet 1 of 2)
DATA INPUTS TO COMPUTER PROGRAMS

PARAMETER	PROGRAM	SELECTION	REASON	BIAS	REASON
Chamber Pressure	G105-1, F823-1	D0524 (H/W)	Appeared to be in better agreement with engine log book data	-0.28	Psig +14.72 = psia P_{Cmeas} -15 = P_{Cact} (Rocketdyne estimation of P_C purge effect)
	PA53	D0001 (T/M)	High sampling rate produced more realistic transient	98.11 Percent	Adjusts P_C so that at ESC, P_C Prog = P_{Cinput} ; at ESC +60 sec, P_C Prog = P_{Cinput} -15 psi
LH2 Injection Temp	F823-1	C0646 (H/W)	Only one available	0	
LH2 Pump Disch Press	G105-1	D0008 (T/M)	Agreed with engine log book data	0	
LH2 Pump Disch Temp	G105-1 F823-1	C0134 (T/M)	T/M & H/W essentially the same. Used T/M	0	
LOX Pump Disch Press	G105-1	D0009 (T/M)	Less noisy	0	
LOX Pump Disch Temp	G105-1	C0648 (H/W)	Less noisy	0	
LH2 Flowrate	G105-1	F0002 (T/M)	Less noisy	-41.82 gpm	Agree with actual pip count
LOX Flowrate	G105-1	F0001 (T/M)	T/M & H/W essentially the same. Used T/M	+1.94 gpm	Agree with actual pip count

H/W - Hardwire

T/M - Telemetry

TABLE 6-4 (Sheet 2 of 2)
DATA INPUTS TO COMPUTER PROGRAMS

PARAMETER	PROGRAM	SELECTION	REASON	BIAS	REASON
LH2 Pump Inlet Press	AA89	D0536 (H/W)	T/M transducer affected by pump chilldown	+15.917	Psig +14.72 = psia. Add 1.197 for dynamic head
LH2 Pump Inlet Temp	AA89	C0003 (T/M)	T/M & H/W essentially the same. Used T/M	-0.3	0 adjustment
LOX Pump Inlet Press	AA89	D0537 (H/W)	Less noisy	+17.20	Psig +14.72 = psig. Add 2.48 for dynamic head
LOX Pump Inlet Temp	AA89	C0004 (T/M)	T/M & H/W essentially the same. Used T/M	0	
Gas Generator P _c	F823	D0010 (T/M)	Less Noisy	0	
LH2 Turbine Inlet Temp	F823	C0001 (T/M)	H/W not available	0	
PU Valve Position	AA89	G0010 (T/M)	T/M & H/W essentially the same. Used T/M	0	

H/W - Hardwire

T/M - Telemetry

TABLE 6-5
ENGINE PERFORMANCE

PARAMETER	CLOSED PU VALVE OPERATION			REFERENCE MIXTURE RATIO OPERATION			OVERALL PERFORMANCE		
	ACTUAL	PREDICTED	PERCENT DEVIATION	ACTUAL	PREDICTED	PERCENT DEVIATION	ACTUAL	PREDICTED	PERCENT DEVIATION
Thrust (lbf)	229,885	230,756	0.4	186,683	186,988	0.2	212,412	214,300	0.9
Total flowrate (lbf/sec)	540.43	542.70	0.4	435.33	435.77	0.1	497.92	502.46	0.9
LOX flowrate (lbm/sec)	457.76	460.06	0.5	358.88	359.70	0.2	417.69	422.28	1.1
LH2 flowrate (lbm/sec)	82.67	82.64	0.04	76.45	76.03	0.6	80.23	80.18	0.1
Engine mixture ratio	5.537	5.567	0.5	4.694	4.731	0.8	5.192	5.251	1.1
Specific impulse (sec)	425.37	425.20	0.04	428.84	429.13	0.1	426.76	426.68	0.02

TABLE 6-6
ENGINE THRUST VARIATIONS

TIME PERIOD	LIMITS	HARDOVER	TRANSIENT FROM PU VALVE CUTBACK +65 sec TO ECC -70 sec	FINAL 70 sec OF BURN
Variation in mean thrust level (lbf) or thrust band centerline variation at ECC -70 sec (lbf)	Allowable*	± 4000	$+6000$ -5000	± 6000
	Actual	830	790	500
	Predicted	--	--	--
Oscillations about mean thrust level (lbf) or thrust variation band (lbf)	Allowable	± 2500	± 7500	± 3000
	Actual	± 1090	± 1710	± 490
	Predicted	± 740	± 325	± 390
Rate of change of thrust (lbf/sec)	Allowable	± 500	± 500	± 500
	Actual	+435	-370	+87
	Predicted	+35	+29	+40
Thrust acceleration (lbf/sec)	Allowable	± 125	± 350	± 350
	Actual	+108	+32.1	-16.8
	Predicted	+6	+2.7	4.5
Thrust band slope (lbf/sec)	Allowable	--	--	+115 -60
	Actual	--	--	+1.0
	Predicted	--	--	+6.5
Variation of thrust band slope about nominal (lbf/sec)	Allowable	--	--	± 35
	Actual	--	--	5.5
	Predicted	--	--	--

* Allowable limits are quoted from Specification Change Notice No. 7, dated 1 June 1967,
and assume a nominal PU cutback at ESC +250 sec.

TABLE 6-7 (Sheet 1 of 6)
ENGINE SEQUENCE

CONTROL EVENTS		CONTINGENT EVENTS		NOMINAL TIME FROM SPECIFIED REFERENCE	ACTUAL TIME (ms)	
MEAS NO.	EVENT AND COMMENT	MEAS NO.	EVENT AND COMMENT		FROM ESC	FROM SPECIFIED REFERENCE
K0021 (K0021)	*Engine Start Command P/U			0	0	0
		K0007 (K0531)	Helium Control Solenoid Engr P/U	Within 10 ms of K0021	3	3
		K0010 (K0454)	Thrust Chamber Spark on P/U	Within 10 ms of K0021	3	3
		K0011 (K0455)	Gas Generator Spark on P/U	Within 10 ms of K0021	3	3
		K0006 (K0535)	Ignition Phase Control Solenoid Engr P/U	Within 20 ms of K0021	2	2
		K0012 (K0530)	Engine Ready D/O	Within 20 ms of K0006	7	5
		K0126 (K0558)	LOX Bleed Valve Closed P/U	Within 130 ms of K0007	62	59
		K0127 (K0557)	LH2 Bleed Valve Closed P/U	Within 130 ms of K0007	49	46
		K0020 (K0627)	ASI LOX Valve Open P/U	Within 20 ms of K0006	39	37

(K0XXX) Actual number from acceptance firing event recorder.

*Engine ready and stage separation signals (or simulation) are required before this command will be executed. This command also actuates a 640 \pm 30 ms timer which controls energizing of the start tank discharge solenoid valve (K0096).

TABLE 6-7 (Sheet 2 of 6)
ENGINE SEQUENCE

CONTROL EVENTS		CONTINGENT EVENTS		NOMINAL TIME FROM SPECIFIED REFERENCE	ACTUAL TIME (ms)	
MEAS NO.	EVENT AND COMMENT	MEAS NO.	EVENT AND COMMENT		FROM ESC	FROM SPECIFIED REFERENCE
K0008 (K0537)	*Ignition Detected	K0119 (G0506)	Main Fuel Valve Closed	60 \pm 30 ms from K0006	39	37
		K0118 (G0506)	Main Fuel Valve Open P/U	80 \pm 50 ms from K0119	121	82
				Within 250 ms of K0021 P/U	197	197
				Approx 200 ms from K0021 P/U	219	219
				1,000 \pm 40 ms from K0021	1,083	1,083
K0021 (K0021)	**Engine Start Command D/O					
K0096 (K0536)	***Start Tank Disc Control Solenoid Engr	K0123 (G0508)	Start Tank Disc Valve Closed D/O	100 \pm 20 ms from K0096	1,216	133
		K0122 (G0508)	Start Tank Disc Valve Open P/U	105 \pm 20 ms from K0123	1,353	137
K0005 (K0538)	Mainstage Control Solenoid Engr			450 \pm 30 ms from K0096	1,535	452

*This signal must be received within 1,110 \pm 60 ms of K0021 P/U or cutoff will be initiated.

**This signal drops out after a time sufficient to lock in the engine electrical.

***An indication of fuel injection temperature of -150 \pm 40 deg F (or simulation) is required before this command will be executed. This command also actuates a 450 \pm 30 ms timer which controls the start of mainstage.

(K0XXX) Actual number from acceptance firing event recorder.

TABLE 6-7 (Sheet 3 of 6)
ENGINE SEQUENCE

CONTROL EVENTS		CONTINGENT EVENTS		NOMINAL TIME FROM SPECIFIED REFERENCE	ACTUAL TIME (ms)	
MEAS NO.	EVENT AND COMMENT	MEAS NO.	EVENT AND COMMENT		FROM ESC	FROM SPECIFIED REFERENCE
		K0096 (K0536)	Start Tank Disc Control Solenoid Engr D/O	450 \pm 30 ms from K0096	1,532	449
		K0121 (G0507)	Main LOX Valve Closed D/O	60 \pm 30 ms from K0005	1,580	45
		K0116 (G0509)	Gas Generator Valve LOX side first motion	140 \pm 10 ms from K0005	1,710	5
		K0122 (G0508)	Start Tank Disc Valve Open D/O	95 \pm 20 ms from K0096 D/O	1,617	534
		K0117 (G0509)	Gas Generator Valve Open P/U	50 \pm 30 ms from K0116	1,811	151
		K0124 (G0510)	LOX Turbine Bypass Valve Open D/O		1,720	
			LOX Turbine Bypass Valve 80% Closed	400 $\begin{smallmatrix} +150 \\ -50 \end{smallmatrix}$ ms from K0122	1,977	360
		K0123 (G0508)	Start Tank Disc Valve Closed P/U	250 \pm 40 ms from K0122	1,884	267
		K0125 (G0510)	*LOX Turbine Bypass Valve Closed P/U		2,028	
K0158 (K0572)	Mainstage Press Switch No. 1 Depress D/O				3,061	

*Within 5,000 ms of K0005 (Normally = 500 ms)

(K0XXX) Actual number from acceptance firing event recorder.

TA. 6-7 (Sheet 4 of 6)
ENGINE SEQUENCE

CONTROL EVENTS		CONTINGENT EVENTS		NOMINAL TIME FROM SPECIFIED REFERENCE	ACTUAL TIME (ms)	
MEAS NO.	EVENT AND COMMENT	MEAS NO.	EVENT AND COMMENT		FROM ESC	FROM SPECIFIED REFERENCE
K0159 (K0573)	Mainstage Press Switch No. 2 Depress D/O				3,069	
K0191 (K0610)	*Mainstage OK				3,060	
		K0120 (G0507)	Main LOX Valve Open P/U	2,435 ± 35 ms from K0005	3,965	2,430
		K0010 (K0454)	Thrust Chamber Spark on D/O	3,300 ± 200 ms from K0005 P/U	4,833	3,298
		K0011 (K0455)	Gas Generator Spark On D/O	3,300 ± 200 ms from K0005 P/U	4,832	3,297
K0507 CSS-22	PU Activate Switch P/U				6,205	
K0013 (K0539)	Engine Cutoff P/U (New Time Reference)			0	0	0
		K0005 (K0538)	Mainstage Control Solenoid Engr D/O	Within 10 ms of K0013	4	4
		K0006 (K0535)	Ignition Phase Control Solenoid Engr D/O	Within 10 ms of K0013	2	2
		K0020 (K0627)	ASI LOX Valve Open D/O		22	
		K0120 (G0507)	Main Oxidizer Valve Open D/O	50 ± 15 ms from K0005	75	71
		K0117 (G0509)	Gas Generator Valve Open D/O	75 $\begin{smallmatrix} +25 \\ -35 \end{smallmatrix}$ ms from K0006	23	21

*One of these signals must be received within 4,410 ± 260 ms from K0021 P/U, or cutoff will be initiated.
Signal occurs when LOX injection pressure is 500 ± 30 psig.

(K0XXX) Actual number from acceptance firing event recorder.

TABLE 6-7 (Sheet 5 of 6)
ENGINE SEQUENCE

CONTROL EVENTS		CONTINGENT EVENTS		NOMINAL TIME FROM SPECIFIED REFERENCE	ACTUAL TIME (ms)	
MEAS NO.	EVENT AND COMMENT	MEAS NO.	EVENT AND COMMENT		FROM ESC	FROM SPECIFIED REFERENCE
		K0118 (G0506)	Main Fuel Valve Open D/O	90 \pm 25 ms from K0006	100	98
		K0121 (G0507)	Main Oxidizer Valve Closed P/U	120 \pm 15 ms from K0120	240	165
		K0116 (G0509)	Gas Generator Valve Closed P/U	500 ms from K0006	385	383
		K0119 (G0506)	Main Fuel Valve Closed	225 \pm 25 ms from K0118	377	277
K0158 (K0572)	*Mainstage Press Switch A Depress P/U				174	
K0159 (K0573)	Mainstage Press Switch B Depress P/U				169	
K0191 (K0610)	Mainstage OK D/O				174	
K0007 (K0531)	Helium Control Solenoid Enrg D/O			1,000 \pm 110 ms from K0013	1,008	1,008

*Signal drops out when pressure reaches 425 \pm 25 psig
(K0XXX) Actual number from acceptance firing event recorder.

TABLE 6-7 (Sheet 6 of 6)
ENGINE SEQUENCE

CONTROL EVENT		CONTINGENT EVENTS		NOMINAL TIME FROM SPECIFIED REFERENCE	ACTUAL TIME (ms)	
MEAS NO.	EVENT AND COMMENT	MEAS NO.	EVENT AND COMMENT		FROM ESC	FROM SPECIFIED REFERENCE
SS-22 (K0507)	PU Activate Switch D/O			N/A	3,137	
		K0125 (G0510)	Oxidizer Turbine Bypass Valve Closed D/O		220	
		K0124 (G0510)	Oxidizer Turbine Bypass Valve Open P/U	10,000 ms from K0005	847	843
K0126 (K0558)	LOX Bleed Valve Closed D/O			30,000 ms from K0005	7,210	7,206
K0127 (K0557)	LH2 Bleed Valve Closed D/O			30,000 ms from K0005	9,111	9,107

(K0XXX) Actual number from acceptance firing event recorder.




Figure 6-2. Thrust Chamber Chillardown




Figure 6-3. LH2 Pump Performance During Engine Start





Figure 6-4. Engine Start and Control Sphere Performance

PARAMETER	TEMPERATURE (°R)			PRESSURE (PSIA)			MASS (LBM)		
	209	208	207	209	208	207	209	208	207
ENGINE START REQUIREMENT	SEE START REGION			SEE START REGION			3.53	3.83	3.32
ENGINE START COMMAND									
AFTER START SPHERE BLOWDOWN	194	168	200	152	160	169	0.64	0.72	0.66
ENGINE CUTOFF	281**	225	205	330**	1362	1300	0.92**	4.48	3.85
TOTAL GH2 USAGE DURING START							2.89	3.11	2.66

** FOR S-IVB-209 ACCEPTANCE THE START SPHERE WAS NOT RECHARGED. SEE PARAGRAPH 6.1.4.




Figure 6-5. Engine Start Sphere Performance




Figure 6-6. J-2 Engine Chamber Pressure




Figure 6-7. J-2 Engine Injector Supply Conditions




Figure 6-8. LOX and LH2 Flowrate




Figure 6-9. J-2 Engine Pump Operating Characteristics




Figure 6-10. Turbine Inlet Operating Conditions




Figure 6-11. Gas Generator Performance




Figure 6-12. Engine Steady-State Performance (Sheet 1 of 3)




Figure 6-12. Engine Steady-State Performance (Sheet 2 of 3)




Figure 6-12. Engine Steady-State Performance (Sheet 3 of 3)




Figure 6-13. Specific Impulse versus Mixture Ratio




Figure 6-14. Total Accumulated Impulse After Engine Start Command




Figure 6-15. Engine Start Transient Characteristics




Figure 6-16. Thrust Variations (Sheet 1 of 3)




Figure 6-16. Thrust Variations (Sheet 2 of 3)




Figure 6-16. Thrust Variations (Sheet 3 of 3)




Figure 6-17. Total Accumulated Impulse After Engine Cutoff Command




Figure 6-18. Engine Cutoff Transient Characteristics (Sheet 1 of 2)




Figure 6-18. Engine Cutoff Transient Characteristics (Sheet 2 of 2)




Figure 6-19. Engine Start Sequence




Figure 6-20. Engine Vibration.

7. OXIDIZER SYSTEM

Due to a malfunction of the LOX tank pressurization control module, LOX NPSH fell below the minimum acceptable level for a 20-sec period shortly after Engine Start Command; however, there were no detrimental effects to the J-2 engine or to the remainder of the acceptance firing. With the exception of the above anomaly, the oxidizer system performance was acceptable.

7.1 Pressurization Control

The LOX tank pressurization system (figure 7-1) provided ullage pressure in the tank sufficient to satisfactorily complete the acceptance firing; however, a severe, though temporary, anomaly within the LOX tank pressurization control module caused the ullage pressure to drop to a low of 29.1 psia at ESC +27 sec. As a result, the engine pump NPSH dropped to 18.1 psi, 2.8 psi below the required minimum. The low ullage pressure also caused a common bulkhead negative differential pressure (refer to paragraph 15.4). In spite of these conditions, no detrimental effects were noted, the ullage pressure recovered, and the firing continued to a normal cutoff.

7.1.1 Prepressurization

The LOX tank prepressurization and pressure makeup cycles before simulated liftoff were accomplished from ground support equipment console "B" cold helium supply (figure 7-2). Helium purges of the vent valve and the LOX tank ullage pressure sensing line increased the ullage pressure to the vent relief setting twice, just prior to simulated liftoff and immediately after simulated liftoff. In order to protect the reusable ignition detection probe, the LOX tank was vented to 38.3 psia prior to Engine Start Command. Table 7-1 compares significant LOX tank prepressurization data from two previous acceptance firings.

7.1.2 Pressurization

The LOX tank pressurization system performance in maintaining the ullage pressure at the proper level was inadequate. During the start transient,

the ullage pressure dropped to 29.1 psia (as compared to the predicted minimum of 34.8 psia) before recovering to a value within the normal band by ESC +60 sec; however, pressure after this time was as anticipated. As predicted, an overcontrol cycle was required five times to maintain the ullage pressure within the range of 39.6 to 37.6 psia during the firing.

Except for the period during the noted malfunction, the LOX tank pressurization system operation was nominal (figure 7-3) and compared well with that of the S-IVB-207 and 208 stage systems. Table 7-2 compares the S-IVB-209 stage pressurization system data with that from previous acceptance firings.

The cause of the dip in ullage pressure was an anomaly in the LOX tank pressurization control module during the initial chilldown of the system. The plenum discharge pressure (D0105) dropped to a low of 218 psia during this period as opposed to a nominal minimum of 300 psia.

(Figure 7-4 presents a comparison of S-IVB-209 data with that from five previous stages for the first 100 sec of firing.) The pressure then recovered but remained below specification until the final overcontrol cycle started. At this time the regulator outlet pressure increased and stayed within the specification range until near cutoff, when the supply pressure caused it to fall below specification. The plenum discharge pressure has remained below specification levels through most of previous acceptance firings. This occurs because the regulator, which is flow-sensitive, is calibrated at a flowrate lower than that used during the acceptance firing. This will be corrected on subsequent stages.

The data indicated that the temporary drop in plenum pressure might have been caused by one of the following problems:

- a. Leakage between the regulator and the plenum caused by differential contraction rates during chilldown.
- b. Failure of the regulator to regulate properly during system chilldown.
- c. Internal blockage in the system between the regulator and the plenum.

The possibility of leakage was discounted after initial calculation showed that a leakage rate in the order of 600 scfm would have been required. This rate is entirely too high to be reasonable.

After the firing, the module was removed from the stage, inspected, and tested. The testing indicated that the regulator would function normally when thoroughly chilled but tended to regulate to low plenum pressures while being chilled. The low plenum pressure during chilldown is presumed to be due to choking in the regulator metering system, causing the regulator poppet to respond to metering system anomalies rather than the pressures downstream of the poppet; however, even though there is a strong indication that this explains the low plenum pressure, this is not the total explanation of the problem.

When the module was inspected, the No. 1 shutoff valve, the shutoff pilot seat, the module outlet filter, and some parts in the regulator dome were rusted, indicating that moisture had been present in the system. Also, three of the separators in the regulator were fractured. The exact point in time when the moisture was introduced into the regulator has not been determined. If the moisture had been present during the acceptance firing, there could have been an added pressure drop due to moisture freezing on the outlet filter.

At the present time the anomaly of the pressurization module seems to have a double cause: the regulator thermal choking and the moisture collecting on the outlet filter. Additional testing is presently being conducted to substantiate these presumptions.

7.2 Cold Helium Supply

At Engine Start Command, the six cold helium spheres contained a total of 246 lbm of helium at 3,043 psia and 42.25 deg R. The conditions of the cold helium spheres at significant times are presented in table 7-2. The temperature and pressure profiles were normal and are shown in figure 7-5.

7.3 J-2 Heat Exchanger

The J-2 heat exchanger functioned satisfactorily and compared well with previous tests (figure 7-6). A comparison of significant S-IVB-209

stage heat exchanger data with that from two previous acceptance firings is presented in table 7-3.

7.4 LOX Pump Chillover

The LOX pump chillover system performed adequately. At Engine Start Command, the NPSH at the LOX pump inlet was above the minimum required at that time. The chillover system data and the results of the performance calculations are presented in figures 7-7 and 7-8 and compared with previous test data in table 7-4.

The chillover pump was started 598 sec prior to simulated liftoff in an attempt to simulate the KSC launch countdown sequence. Subsequent to the establishment of this sequence, it was determined that, at KSC, chillover starts at approximately liftoff minus 300 sec. This sequence will be reflected in future STC testing. The chillover shutoff valve was left open until $T_0 + 602.8$ sec (approximately ECC -10 sec), also in simulation of the flight sequence.

The heat input rates for the three sections of the chillover system were computed using flowrate and temperature data. The three sections are defined as follows:

- a. Tank to turbopump inlet
- b. Pump inlet to bleed valve
- c. Blead valve to tank inlet.

These heat input rates decreased rapidly as heat was removed from the hardware during the first minute of chillover, then remained relatively constant during the subsequent chillover process (figure 7-8). During steady-state pressurized chillover, the heat input rates were within the range of those obtained for previous acceptance firings (table 7-4).

The chillover pump flowrate and differential pressure at 46.5 gpm and 11.5 psid were both somewhat higher than they were on previous firings. This higher flowrate and consequently increased differential pressure is attributed to a change in LOX chillover pump design. This stage is the first to utilize a pump with an improved inducer. The high level of differential pressure measured by D0219, however, is not supported by the remainder of the system data; it appears to be approximately 20 percent high. This discrepancy has been noted during previous firings;

however, no definite explanation is presently available. The subject is under investigation.

7.5 Engine LOX Supply

The LOX supply system (figure 7-9) delivered the necessary quantity of LOX to the engine pump inlet throughout the engine firing and maintained the pressure and temperature conditions within the specified range except for a 20-sec period after engine start. During this time, NPSH decreased to 18.1 psi, as opposed to the required 20.9 psi; however, no detrimental effects were attributed to this occurrence.

The cause of the problem originated in the LOX tank pressurization system and is discussed in paragraph 7.1.2. The data and calculated performance are presented in figure 7-10. Table 7-5 compares S-IVB-209 stage data and calculated performance with that from two previous acceptance firings.

The LOX pump inlet pressure and temperature were plotted in the engine LOX pump operating region (figure 7-11) and showed that the engine LOX pump inlet conditions were met satisfactorily during most of the engine operation. In figure 7-12, the pump inlet temperature is plotted against the mass remaining in the LOX tank during engine operation and is compared to the S-IVB-208 and 503N acceptance firing data. These data have been biased to an identical initial condition to correct for instrumentation error, different heating rates during prepressurization, and other test-to-test variations. It is apparent that the heat transfer to the LOX was very similar to that noted on previous stages.

7.6 LOX Tank Vent and Relief Valve Performance

The LOX tank vent and relief valve was tested during CD 614084. The valves relieved at 43.6, 43.5, and 43.4 psia; however, when the tank was allowed to self-pressurize, ullage pressure stabilized at 42.0 psia and, after several minutes at this level, the vent valve talkback was received. In addition, the valve relieved twice at 42.1 psia, following prepressurization. The different pressure ranges are attributable to the rate of ullage pressure rise; auxiliary ground pressurization with a very rapid pressure rise rate is used during the vent and relief valve test versus the slow rise caused by self-pressurization.

TABLE 7-1
LOX TANK PREPRESSURIZATION DATA

PARAMETER	S-IVB-207	S-IVB-208	S-IVB-209
Prepressurization duration (sec)	16	19	17.1
Number of makeup cycles	1	2	2
Prepressurization flowrate (lbm/sec)	0.22 to 0.32	0.22 to 0.30	0.22 to 0.29
Helium added to LOX tank			
During main prepressurization (lbm)	4.00	3.87	3.4
During makeup cycles (lbm)	0.66	0.65	0.63
Ullage pressure			
At prepressurization initiation (psia)	15.2	15.0	15.0
At prepressurization termination (psia)	40.5	39.2	39.9
At Engine Start Command (psia)	41.9	41.4	38.3
Events (sec from ESC)			
Prepressurization initiation	-311	-315	-312.5
Prepressurization termination	-295	-296	-295.4

TABLE 7-2 (Sheet 1 of 2)
LOX TANK PRESSURIZATION DATA

PARAMETER	S-IVB-207	S-IVB-208	S-IVB-209
Number of secondary flow intervals	7	6	5
Control pressure switch range (psia)	37.43 to 39.45	37.5 to 39.5	37.6 to 39.6
Ullage pressure			
At Engine Start Command (psia)	41.9	41.4	38.3
Minumum during start transient (psia)	36.3	34.25	29.1
LOX tank pressurization total flowrate			
During overcontrol (lbm/sec)	0.35 to 0.47	0.36 to 0.44	0.39 to 0.47
Predicted (lbm/sec)	0.42 to 0.46	0.39 to 0.47	0.41 to 0.45
During undercontrol (lbm/sec)	0.265 to 0.34	0.26 to 0.32	0.28 to 0.37
Predicted (lbm/sec)	0.29 to 0.33	0.27 to 0.32	0.29 to 0.32
Cold helium sphere conditions			
Mass in spheres at engine start (lbm)	254	254	246.4
Pressure at engine start (psia)	2,990	3,046	3,043
Average temperature at engine start (deg R)	39.7	40.0	42.2
Mass in spheres at engine cutoff (lbm)	97	100	82.5
Helium consumed during firing as calculated from sphere conditions (lbm)	157	154	163.9

TABLE 7-2 (Sheet 2 of 2)
LOX TANK PRESSURIZATION DATA

PARAMETER	S-IVB-207	S-IVB-208	S-IVB-209
Cold helium sphere conditions (Continued)			
Helium consumption calculated by integration of flowrate (lbm)	155	142	154
Pressure at engine cutoff (psia)	640	648	550
Average temperature at engine cutoff (deg R)	44.8	42.2	43.0
Estimated temperature loss in 10 feet of insulated line			
During overcontrol (deg R)	7	11	9
During undercontrol (deg R)	17	28	23
Maximum LOX tank vent inlet temperature (deg R)	496	506	500

TABLE 7-3
J-2 HEAT EXCHANGER DATA

PARAMETER	S-IVB-207	S-IVB-208	S-IVB-209
Flowrate through heat exchanger			
During overcontrol (lbm/sec)	0.215	0.20	0.20 to 0.215
During undercontrol (lbm/sec)	0.085	0.080	0.085
Heat exchanger inlet temperature			
During overcontrol (deg R)	60	60	55
During undercontrol (deg R)	73	70	68
Heat exchanger outlet temperature*			
During overcontrol (deg R)	957	980	959
During undercontrol (deg R)	1,002	1,000	1,006
Heat exchanger outlet pressure			
During overcontrol (psia)	335 to 360	315 to 345	325 to 350
During undercontrol (psia)	385 to 407	380 to 400	355 to 410
Heat exchanger outlet temperature at Engine Cutoff Command (deg R)	902	906	898
Average LOX vent inlet pressure			
During overcontrol (psia)	72	69	70
During undercontrol (psia)	51	51	50

*Estimated from measurement C0009 and uninsulated line temperature loss.

TABLE 7-4 (Sheet 1 of 2)
LOX CHILLDOWN SYSTEM PERFORMANCE

PARAMETER	S-IVB-207	S-IVB-208	S-IVB-209
NPSH (psi)			
At Engine Start Command	33.2	32.0	29.7
Minimum required at engine start (psi)	16.5	16.5	16.5
Average flow coefficient (sec ² /in ² ft ³)	15.3	15.6	15.0
Pump inlet conditions at engine start			
Pressure (psia)	50.0	49.5	46.3
Temperature (deg R)	164.6	165.6	164.4
Heat absorption rate (Btu/hr)			
Section 1 (tank to turbopump inlet)	2,000	4,000	3,000
Section 2 (pump inlet to bleed valve)	14,200	14,000	17,100
Section 3 (bleed valve to tank inlet)	2,800	2,000	4,300
Total	19,000	20,000	24,400
Chilldown flowrate (gpm)			
Unpressurized	36.7	37.7	40.6
Pressurized	41.0	43.0	46.5
Pressure drop (psi)			
Unpressurized	8.7	8.0	9.0
Pressurized	10.0	10.0	11.5
Events (sec from T ₀)			
Chilldown start	-302	-602	-598.2
Prevalve Open Command	146.88	146.39	147.56

TABLE 7-4 (Sheet 2 of 2)
LOX CHILLDOWN SYSTEM PERFORMANCE

PARAMETER	S-IVB-207	S-IVB-208	S-IVB-209
Events (sec from T_0) (Continued)			
Prevalve closed signal dropout	147.50	147.16	149.03
Prevalve open signal pickup	149.08	148.69	150.57
Delay between prevalve open signal and pickup of signal	2.26	2.30	3.01
Chilldown shutoff valve closed	150	566.57	602.8
Prepressurization	-161	-165	-160.7
Engine Start Command	150.86	150.27	151.847
Engine Cutoff Command	598.94	576.87	610.682

TABLE 7-5
LOX PUMP INLET CONDITIONS

PARAMETER	S-IVB-207	S-IVB-208	S-IVB-209
Pump inlet conditions at engine start			
Static pressure (psia)	50.0	49.5	46.3
Temperature (deg R)	165.2	165.6	164.4
NPSH requirements			
At high EMR (psi)	21.0	20.2	20.9
After EMR cutback (psi)	14.9	14.25	15.8
NPSH available			
At Engine Start Command (psi)	33.2	32.0	29.7
Minimum during start transient (psi)	26.0	22.8	18.1
Time of occurrence (sec from ESC)	20	21	27
At Engine Cutoff Command (psi)	21.8	20.7	23.7
Minimum during firing (psi)	21.8	20.7	18.1
Time of occurrence (sec from ESC)	ECC	ECC	27
Feed duct during high EMR			
Pressure drop (psi)	1.4	1.8	2.3
Flowrate (lbm/sec)	450	468	457
Feed duct after EMR cutback			
Pressure drop (psi)	0.4	1.3	1.3
Flowrate (lbm/sec)	368	379	359

NOTE:
 (X) ITEM NUMBERS FROM
 PARTS LIST TABLE 3-1
 SEE FIGURE 3-1 FOR
 LEGEND




Figure 7-1. LOX Tank Pressurization System




Figure 7-2. LOX Tank Prepressurization




Figure 7-3. LOX Tank Pressurization System Performance




Figure 7-4. LOX Pressurization Module Start Transient Pressure




Figure 7-5. Cold Helium Supply





Figure 7-6. J-2 Heat Exchanger Performance





Figure 7-7. LOX Pump Chilldown System Operation




Figure 7-8. LOX Pump Chilldown System Performance




Figure 7-9. LOX Supply System






Figure 7-10. LOX Pump Inlet Conditions




Figure 7-11. LOX Pump Inlet Conditions During Firing




Figure 7-12. Effect of LOX Mass Level on LOX Pump Inlet Temperature

8. FUEL SYSTEM

The fuel system performed as designed and supplied LH2 to the engine within the limits defined in the engine specification.

8.1 Pressurization Control

The LH2 tank pressurization system (figure 8-1) performed adequately and satisfactorily controlled LH2 tank ullage pressure throughout the firing.

8.1.1 Prepressurization

The LH2 tank was satisfactorily prepressurized with helium from ground support equipment console "B." Data are presented in figure 8-2 and compared with S-IVB-207 and S-IVB-208 data in table 8-1. Between the end of prepressurization and Engine Start Command (ESC), the ullage temperature increased because of ambient heat input, causing the ullage pressure increase shown in figure 8-2.

8.1.2 Pressurization

During engine operation, LH2 tank pressurization was satisfactorily accomplished by the GH2 tapoff system (figure 8-1). The data are presented in table 8-2 and figure 8-3 and show that all measured parameters were within the normal dispersion range observed in previous tests. Two complete overcontrol cycles were accomplished before step pressurization. The LH2 tank relief valve cracked open at ESC +442.7 sec, during step pressurization, and continued relieving until Engine Cutoff Command (ECC).

8.2 LH2 Pump Chillover

The LH2 pump chillover system performed satisfactorily; the NPSH at Engine Start Command was well above the required level. The chillover system data and the results of the performance calculations are presented in figures 8-4 and 8-5 and compared with previous test data in table 8-3. Examination of the data during the quiescent period before recirculation was initiated revealed that the liquid in the system was saturated at

that time. LH2 chilldown flowrate (F0005), LH2 chilldown pump differential pressure (D0218), LH2 pump inlet pressure (D0536), LH2 pump inlet temperature (C0003), LH2 bleed valve temperature (C0650), and LH2 return line temperature (C0161) were biased based on known conditions at that time.

The test utilized the anticipated flight sequence, with chilldown initiated at approximately $T_0 - 595$ sec (paragraph 7.4) and the chilldown shutoff valve open after chilldown termination. The valve was closed at approximately $T_0 + 602.8$ sec. Chilldown system performance was nominal and compared well with that of previous stages, as indicated in table 8-3. System flowrates and temperatures were at the levels anticipated. During unpressurized chilldown, the liquid was subcooled through the system to a point between the engine pump inlet and the bleed valve; the system became entirely subcooled during prepressurization. The high heat leak condition that occurred on the S-IVB-207 and S-IVB-208 stages did not recur.

It should be noted that during the post-acceptance firing tests, the LH2 chilldown duct vacuum and the LH2 upper low pressure duct vacuum exceeded 1,000 microns. No detrimental effect was noted in the chilldown system performance; both of these ducts were subsequently replaced.

Because of the problems during the S-IVB-207 and S-IVB-208 stage acceptance firings and because available data were inadequate for developing a satisfactory explanation, additional instrumentation was installed on the S-IVB-209 stage and two special chilldown tests were performed. During the prefiring period of CD 614084, the chilldown operation was performed repeatedly while the flowrate of the chilldown fairing helium purge was varied. After the acceptance firing had been completed, CD 614086 was initiated on 23 June. During this test, the environment inside the chilldown fairing was varied between helium and GN2 and controlled within known limits.

8.3 Engine LH2 Supply

The engine LH2 supply system (figure 8-6) satisfactorily supplied LH2 to

the engine pump inlet throughout engine operation and maintained the pressure and temperature within a range that provided an NPSH above the minimum requirement. The data and the results of the performance calculations are presented in figure 8-7 and compared with data from two previous acceptance firings in table 8-4.

The LH2 pump inlet pressure and temperature were plotted in the engine operating region (figure 8-8) and showed that the LH2 pump inlet conditions were met satisfactorily throughout the firing. Figure 8-9 is a plot of the pump inlet temperature versus the mass remaining in the LH2 tank during burn. It includes data from S-IVB-208 and S-IVB-503N acceptance firings biased to an identical initial condition to correct for instrumentation error, different heating rates during prepressurization, and other test-to-test variations. The data from all three firings agree closely.

8.4 LH2 Vent and Relief Valve Performance

During the vent and relief valve check during CD 614084, the LH2 vent and relief valve relieved at 38.0, 37.9, and 37.9 psia. During the acceptance firing (CD 614085), the valve feathered open at 37.7 psia.

TABLE 8-1
LH2 TANK PREPRESSURIZATION DATA

PARAMETER	S-IVB-207	S-IVB-208	S-IVB-209
Prepressurization duration (sec)	71.6	77.5	49.0
Helium mass used during prepressurization (lbm)	38.72	33.76	24.6
Ullage pressure			
At prepressurization termination (psia)	34.1	33.4	33.5
At simulated liftoff (psia)	34.7	33.9	34.1
At Engine Start Command (psia)	37.4	36.4	36.5
Rise rate after prepressurization (psi/min)	1.04	0.99	0.84
Events (sec from T_0)			
Prepressurization initiation	-110.7	-109.6	-110.7
Prepressurization termination	-39.1	-32.1	-61.7

TABLE 8-2
LH₂ TANK PRESSURIZATION DATA

PARAMETER	S-IVB-207	S-IVB-208	S-IVB-209
Number of control cycles	2	2	2
Control pressure switch range (psia)	27.1 to 29.3	27.3 to 29.0	27.3 to 29.3
Ullage pressure			
At Engine Start Command (psia)	37.4	36.4	36.5
At step pressurization (psia)	28.5	28.2	28.0
At Engine Cutoff Command (psia)	38.9	37.3	37.8
At relief valve operation (psia)	38.35	N/A	37.7
GH ₂ pressurant flowrate			
Undercontrol (lbm/sec)	0.36	0.40	0.36
Overcontrol (lbm/sec)	0.65	0.68	0.63
Step before cutback (lbm/sec)	1.10	1.18	N/A
Step after cutback (lbm/sec)	0.99	1.08	0.98
Total GH ₂ pressurant mass (lbm)	281.2	285.1	280.3
LH ₂ boiloff during engine operation (lbm)	0	0	0
Events (sec from ESC)			
Step pressurization	301.3	300.2	300.2
Relief valve opening	408	N/A	442.7

N/A = Not applicable

TABLE 8-3 (Sheet 1 of 2)
LH2 CHILLDOWN SYSTEM PERFORMANCE

PARAMETER	S-IVB-206	S-IVB-209
NPSH (psi)		
Maximum	25.5	21.9
At Engine Start Command	18.0	14.2
Minimum required at Engine Start Command	6.4	6.5
Average flow coefficient ($\text{sec}^2/\text{in.}^2\text{ft}^3$)	18.2	17.5
Fuel quality (sections 2 and 3--unpressurized)		
Maximum (lb gas/lb mixture)	0.033	0.045
At prepressurization (lb gas/lb mixture)	0.025	0.034
Pump inlet conditions at engine start		
Static pressure (psia)	38.5	37.3
Temperature (deg R)	38.6	39.4
Amount of subcooling (deg R)	4.6	3.5
Heat absorption rate--unpressurized (Btu/hr)		
Section 1 (tank to pump inlet)	21,000	20,000
Sections 2 (pump inlet to bleed valve) and 3 (bleed valve to tank)	18,000	23,000
Total	39,000	43,000
Heat absorption rate--pressurized (Btu/hr)		
Section 1	17,500	21,000
Section 2	22,000	23,300
Section 3	21,500	15,000
Total	61,000	59,300
Chilldown flowrate (gpm)		
Unpressurized	108	102
Pressurized	143	142.6

TABLE 8-3 (Sheet 2 of 2)
LH2 CHILLDOWN SYSTEM PERFORMANCE

PARAMETER	S-IVB-206	S-IVB-209
Pressure drop (psi)		
Unpressurized	9.4	9.4
Pressurized	8.0	8.0
Events (sec from T ₀)		
Chilldown start	-305.1	-595.1
Prevalve closed	-301.8	-591.1
Prepressurization	-110.1	-110.7
Prevalve Open Command	147.22	147.6
Chilldown pump off	150.2	151.6
Chilldown shutoff valve closed	150.34	602.8
Engine Start Command	150.77	151.847

TABLE 8-4
LH2 PUMP INLET CONDITIONS

PARAMETER	S-IVB-207	S-IVB-208	S-IVB-209
Pump inlet conditions at engine start			
Static pressure (psia)	38.2	38.1	37.3
Temperature (deg R)	41.6	41.4	39.4
NPSH requirements			
At high EMR (psi)	5.8	6.5	6.6
After EMR cutback (psi)	5.6	5.9	6.05
NPSH available			
At Engine Start Command (psi)	6.8	7.6	19.5
At Engine Cutoff Command (psi)	16	16	15.8
Minimum (psi)	9.5	9.5	8.25
Time of minimum (sec from ESC)	270	215	300
Feed duct at high EMR			
Pressure drop (psi)	0.5	0.5	1.1
Flowrate (lbm/sec)	80.5	85.5	82.8
Feed duct after EMR cutback			
Pressure drop (psi)	0.3	0.5	0.9
Flowrate (lbm/sec)	74.2	79.4	76.1




Figure 8-1. LH2 Tank Pressurization System




Figure 8-2. LH2 Tank Prepressurization System Performance





Figure 8-3. LH2 Tank Pressurization System Performance




Figure 8-4. LH2 Pump Chillo down




Figure 8-5. LH2 Pump Chilldown Characteristics





Figure 8-7. LH2 Pump Inlet Conditions




Figure 8-8. LH2 Pump Inlet Conditions During Firing




Figure 8-9. Effect of LH2 Mass Level on LH2 Pump Inlet Temperature

9. PNEUMATIC CONTROL AND PURGE SYSTEM

The pneumatic control and purge system (figure 9-1) performed satisfactorily throughout the acceptance firing. The helium supply to the system was adequate for both pneumatic valve control and purging; the regulated pressure was maintained within the acceptable limits and all components functioned normally. Because the pneumatic sphere temperature transducer is not installed on operational stages such as S-IVB-209, mass and temperature data cannot be presented. The data that were obtained are presented in figure 9-2.

9.1 Pneumatic Control

With the exception of the LOX pre valve, all engine and stage pneumatically controlled valves responded properly throughout the countdown and acceptance firing. The LOX pre valve opening time was 3.01 sec, 0.01 sec longer than the 3 sec SIM-interrupt time used on previous acceptance firings. During CD 614084 the pre valve opening time was observed to be 2.85 sec; therefore, for CD 614085 the SIM-interrupt time was changed to 4 sec. Part of this increase over the normal 2.2 to 2.5 sec opening time is attributed to a new configuration of the actuation control module. The precise causes of the problem, as well as remedial action, are presently under investigation.

9.2 Ambient Helium Purges

During the acceptance firing, all stage purge functions that utilize stage pneumatics were satisfactorily accomplished. The pneumatic system was isolated from the ground support equipment at $T_0 - 3$ sec, thus discontinuing those purges that were facility supplied. The flowrates of the various purge orifices are listed in table 3-2.

The LOX chilldown motor container purge pressure was maintained within the design range throughout the acceptance firing. The engine pump purge regulator pressure was initially thought to be abnormal; however, the cause was determined to be a faulty transducer (D0050).




Figure 9-1. Pneumatic Control and Purge System




Figure 9-2. Pneumatic Control and Purge System Performance

10. PROPELLANT UTILIZATION SYSTEM

The propellant utilization (PU) system performed as expected during the acceptance firing and all test objectives were satisfactorily accomplished. This was the first S-IVB/IB stage to be acceptance fired with the common propellant load of 38,000 lbm LH2 and 193,273 lbm LOX. This was also the first acceptance firing of the reshaped LH2 mass sensor. The final indicated LOX and LH2 masses loaded were 0.49 percent higher and 0.42 lower, respectively, than the actual masses based on the flow integral analysis. The PU system operated in the closed-loop mode throughout the firing with a reference mixture ratio (RMR) of 4.7:1. PU valve cutback occurred at Engine Start Command (ESC) +233 sec as compared to the predicted cutback time of ESC +265 sec. Based on extrapolation from the conditions at cutoff, depletion would have occurred with 215 lbm of usable LH2 on board as compared to a guaranteed maximum flight residual of 575 lbm.

The engine thrust variations were well within the thrust variation limits derived for the CEI specification. No engine performance shifts occurred during RMR control at 4.7:1.0. Use of both reshaped LOX and LH2 sensors significantly reduced sensor-induced thrust variations. The mean thrust slope during the last 70 sec of burn was one lbf/sec and the thrust variation band was ± 490 lbf.

The actual PU valve history exhibited a more gradual slope following cutback than the predicted. This slope deviation, which also occurred in the S-IVB-503N acceptance firing data, is indicative of a gain difference between the actual PU system and the simulation model. The actual PU system gain was approximately 3 db lower than the postfiring simulation. Investigation of test data obtained during checkout of the PU electronics assembly for the S-IVB-209 acceptance firing revealed 1.7 db of the difference.

10.1 PU System Calibration

The nominal pre-acceptance mass sensor calibration was determined from previous test results. The propellant masses at the upper and lower calibration point were determined from calculated unique tank volume data

and predicted propellant densities. The capacitance at the lower point was determined from vendor's sensor calibration data and fast drain data from previous acceptance firings. The LOX sensor capacitance at the upper calibration point was determined from the S-IVB-209 vendor's air capacitance test and immersed LOX sensor data from the S-IVB-207 stage. The LH2 sensor capacitance at the upper calibration point was determined from the S-IVB-503N immersion test and S-IVB-209 vendor's air capacitance. The LOX and LH2 PU mass sensor calibrations are listed in the following table:

<u>PU Mass Sensor</u>	<u>Cap (pf)</u>	<u>Mass (lbm)</u>	<u>Location</u>
LOX	281.70	1,284	Bottom of Inner Element
	413.05	196,224	Top of Inner Element
LH2	970.18	214	Bottom of Inner Element
	1,186.24	44,777	Top of Inner Element

10.2 Propellant Loading

Propellant loading was accomplished automatically by the loading computer. The following is a tabulation of the desired, indicated, and actual full propellant loads at ESC:

<u>Propellant Load</u>	<u>LOX (lbm)</u>	<u>LH2 (lbm)</u>
Desired full load (predicted)	193,273	38,000
Indicated full load (PU reading)	193,203	38,061
Actual full load (flow integral)	192,260	38,222
Difference (indicated less desired)	-70	61
Difference (actual less desired)	-1,013	222
Difference (indicated less actual)	943	-161

10.3 Propellant Mass History

The flow integral method was used to determine the actual propellant full load and mass history. The results of the flow integral method of mass determination will be used to recalibrate the PU system for flight.

The flow integral method consists of determining the mass flowrates of LOX and LH2 and integrating as a function of time to obtain total consumed

mass during firing. Flow integral mass values are based on the analysis of engine flowmeter data, thrust chamber pressure and temperature differentials, engine influence equations, and engine tag values.

The initial full load mass is determined by adding the propellant residuals at engine cutoff, the fuel pressurant added to the ullage and the propellant lost to boiloff, to the total mass consumed. Residual mass values at engine cutoff are based on the best estimate method (paragraph 10.4). The following tabulation presents the propellant mass history for salient times during the acceptance firing:

TIME	FLOW INTEGRAL MASS (lbm)		CORRECTED PU SYSTEM ⁽¹⁾ MASS (lbm)		DEVIATION ⁽²⁾ (lbm)	
	LOX	LH2	LOX	LH2	LOX	LH2
Simulated Liftoff (T_0) and Engine Start Command	192,260	38,222	193,188	38,419	928	197
PU Valve Cutback ESC +233 sec	87,262	19,154	87,813	19,131	489	-23
Engine Cutoff Command ESC +458.841 sec	2,311	1,366	2,324	1,391	13	25

NOTES: (1) Total mass in tank as determined by the PU system corrected for nonlinearities.

(2) Deviation of the corrected PU system mass from the flow integral mass.

10.4 Propellant Residuals

Propellant residuals were computed at Engine Cutoff Command using both the PU mass sensor and the residual point level sensors. Two level sensors (L0005 and L0004) in the LOX tank and one level sensor (L0002) in the LH2 tank were activated during the firing and were used for the residual computations.

The residuals derived from the point level sensors were generated using engine consumption data to extrapolate from level sensor activation

to engine cutoff. A statistical average residual was computed for the point level sensors for each propellant tank. The final residual masses at engine cutoff are the best estimate residuals generated by weighted averaging the level sensor and PU mass residuals.

The following table presents the propellant residuals determined by the PU mass sensor and the residual point level sensors at engine cutoff:

LEVEL SENSOR (ACTIVATION TIME)	LOX (lbm)			LH2 (lbm)		
	PU SYSTEM VALUE	LEVEL SENSOR	LEVEL SENSOR RESIDUAL (EXTRAPOLATED TO ECC)	PU SYSTEM VALUE	LEVEL SENSOR	LEVEL SENSOR RESIDUAL (EXTRAPOLATED TO ECC)
L0005 (ESC +437.58 sec)	9,930	9,864	2,249			
L0004* (ESC +459.50 sec)	2,220	2,199	2,323			
L0002 (ESC +446.42 sec)				2,253	2,308	1,350
Engine Cutoff (ESC +458.84 sec)	2,324 ± 320		2,305** ± 226	-1,391 ± 75		1,350** ± 59
Best Estimate Residuals***	2,311 ± 185			1,366 ± 46		

* Level sensor L0004 activated immediately after engine cutoff. Residual for this sensor was computed by adding the engine propellant consumption during the cutoff transient to the level sensor computed mass.

** Statistical average of level sensor residuals.

*** Statistically weighted average of level sensor and PU system residuals.

10.5 PU System Response

The tank-to-sensor mismatch for the LOX and LH2 mass sensor normalized to the sensor end points are presented in figures 10-1 and 10-2. Mismatch values are presented including and excluding manufacturing nonlinearities for comparison. The maximum LOX mass sensor error was 475 lbm at

52,000 lbm total LOX load or approximately 0.25 percent error at the 27 percent level of the tank. The maximum LH2 mass sensor error was +80 lbm at the 14,000 lbm level and -80 lbm at the 27,000 lbm level of total LH2 load or approximately 0.19 percent error at the 32 and 63 percent levels of the tank, respectively.

PU system valve cutback occurred at ESC +233 sec, 32 sec earlier than the predicted cutback time of ESC +265 sec (figure 10-3). The PU valve position trace exhibited a more gradual slope following cutback than predicted and reached a steady-state position with a mean value approximately 2.5 deg lower than predicted. The difference between the actual and predicted PU valve response following cutback was caused mainly by a PU system calibration deviation and by PU system gain deviation. The following table summarizes the deviations between the actual and predicted PU valve position histories and their sources.

<u>Description</u>	<u>Cutback Time Deviation (sec)</u>	<u>Valve Position Shift (deg)</u>
Loading computer deviations	-5.5	0
Mass/capacitance calibration deviations	-14.5	-3.3
Difference between predicted and actual tank-to-sensor mismatch nonlinearities	+3.0	-1.7
PU system gain deviation -3 db	-10	+1.0
Total	-27.0	-4.0

Considering the above factors, the predicted cutback time would decrease by 27 sec and the mean level of valve position after the cutback transient would be decreased by 4.0 deg. This provides satisfactory agreement between the actual valve response and the postfiring reconstruction as shown in figure 10-4.

10.5.1 Loading Computer Deviations

Loading computer deviations are the difference between the PU system indicated loads at ESC and the desired PU system indicated loads at ESC.

The loading deviations were -70 lbm LOX (-0.036 percent) and +61 lbm LH2 (0.016 percent). The combined effect of these loading computer deviations decreased cutback time by 5.5 sec. The mean level of the valve position after cutback is not affected by these loading computer deviations.

10.5.2 Mass/Capacitance Calibration Deviations

Calibration deviations at ESC were +0.490 percent LOX and -0.421 percent LH2 thus causing the initial LOX mass to be under-loaded and the initial LH2 mass to be over-loaded by the above percentages. Calibration deviations at ECC were -0.078 percent LOX and -0.097 percent LH2. The slope deviations between ESC and ECC were +0.568 percent LOX and -0.324 percent LH2. The desired reference mixture ratio (RMR) for the S-IVB-209 acceptance firing was 4.7:1.0. The bridge-gain-ratio (BGR) was therefore calibrated at 4.7:1.0. Since PU sensor calibration deviations also affect the BGR, the actual ratio was 4.65:1.0. The calibration deviations decreased cutback time by 14.5 sec and shifted the mean value of valve position by -3.3 deg.

The total loading deviations including calibration and loading computer deviations were -0.53 percent LOX and -0.581 percent LH2.

10.5.3 Difference Between Predicted and Actual Tank-to-Sensor Mismatch

The effect of the differences between the average of previous acceptance firing flow integral tank-to-sensor mismatch results used for the S-IVB-209 stage prediction and the actual flow integral tank-to-sensor mismatch increased cutback time by 3 sec and shifted the mean valve position by 1.7 deg.

Figures 10-1 and 10-2 present the predicted and actual LOX and LH2 mismatch curves normalized to the sensor extremities. Actual mismatch values are plotted including and excluding sensor manufacturing nonlinearities. Two predictions are provided, one is for the measured tank-to-sensor mismatch based on internal tank measurements including manufacturing nonlinearities and the other is an average of previous test data excluding manufacturing nonlinearities. The actual mismatch curves are based on the combined flow integral computer program.

10.5.4 PU System Gain Difference

The postfiring reconstruction of the PU valve history was obtained from actual acceptance firing data and is compared to the actual valve profile in figure 10-3. This resulted in a reasonably close comparison between actual and reconstructed data; however, the actual cutback occurred 15 sec earlier, the PU valve cutback response was slower, and the mean valve position was shifted -2.0 deg. The lag between valve cutback and thrust cutback was also larger than predicted (22 sec vs 16 sec). This time lag was caused by the increased time experienced for the PU valve to travel through the nonlinearity gain phase (+32 to +15 deg). During cutback, thrust cutback is normally observed at a valve position of approximately +15 deg. The above factors indicate that the S-IVB-209 stage PU system gain was lower than the PU system simulated gain. The PU system simulation gain reduction required to reconstruct the actual valve cutback transient was 3 db. A reconstruction with the gain reduction is compared to the actual in figure 10-4. This gain difference accounts for the decreased slope of the valve cutback profile, the increased lag between valve and thrust cutback, 10 sec of the early cutback, and a mean valve position shift of +1.0 deg.

Investigation of test data obtained during checkout of the PU electronics assembly for the S-IVB-209 acceptance firing has isolated 1.7 db of the difference. Other possible sources of gain reduction are presently being investigated and the flight PU model for S-IVB-209 will reflect the results of this study.

10.5.5 PU Efficiency

The closed-loop PU efficiency is determined by expressing the usable residual propellant at depletion cutoff as a percentage of the total propellant load. LOX depletion cutoff would have occurred 5.148 sec after the actual ECC. Total stage propellant consumption rates at ECC were 353.89 lbm/sec for LOX and 74.966 lbm/sec for LH2. Extrapolating these flowrates to the theoretical depletion cutoff results in a usable LH2 residual of 215 lbm and a PU efficiency of 99.907.

10.5.6 Thrust Variations

The thrust variations after cutback were reduced due to the reshaping of the LH2 propellant sensor. This was the first test of the reshaped LH2 propellant sensor combined with the previously acceptance fired reshaped LOX sensor. The complete thrust profile is presented in figure 6-12 and figure 6-16 shows expanded thrust plots of the three significant phases of flight defined for the Contract End Item (CEI) Specification. A tabulation of the actual thrust variations compared to the CEI Specification limits for flight are presented in table 6-6.

The thrust variations after cutback were within the CEI thrust limits recently established for the S-IVB-209 CEI Specification. The thrust cutback transient was slower than predicted due to the lower PU system gain (paragraph 10.5.4). The mean slope during the last 70 sec of burn was 1 lbf/sec and the maximum thrust variations about the mean slope was ± 490 lbf. The maximum rate during this period was 87 lbf/sec.

There was a thrust tailup of 1,000 lbf during the last 15 sec of burn corresponding to a PU valve tailup of 1.5 deg. The S-IVB-209 stage employing the reshaped LH2 mass sensor exhibited a significant reduction in thrust tailup from the values experienced on previous stages.




Figure 10-1. LOX Tank-to-Sensor Mismatch Normalized to Sensor End Points




Figure 10-2. LH2 Tank-to-Sensor Mismatch Normalized to Sensor End Points




Figure 10-3. PU Valve Position




Figure 10-4. PU Valve Position Reconstruction with PU System Gain Reduction

11. DATA ACQUISITION SYSTEM

The data acquisition system performed as designed by demonstrating the competency of acquiring stage information, conditioning the data signals, translating these signals into proper telemetry format, and transmitting the telemetry information to a ground station. The measurements which comprise this system are specified in Douglas Drawing No. 1B43562S, *Instrumentation Program and Components List (IP&CL)*. A measurement summary is presented in the following table:

Measurement efficiency	98.86%
Total number of measurements designed	232
Total number of measurements deleted	57
Total number of active measurements	157
Measurement failures	<u>2</u>
Total successful measurements	173

The data acquisition system satisfactorily accomplished its acceptance firing criterion as specified by the *S-IVB-209 Stage Acceptance Firing Test Plan* (DAC 47459A, as amended). The system performed as expected; no system malfunction was observed and the system was free of radio frequency interference and was electromagnetically compatible with other stage systems.

11.1 Instrumentation System Performance

The instrumentation system performance was excellent during the acceptance firing with the exception of two (2) pressure measurement discrepancies. The system performance is tabulated in table 11-1; status of the inactive measurements is shown in table 11-2.

Two measurements failed to exhibit valid data (table 11-3): D0050 - Engine Pump Purge Regulator Pressure data were invalid at $T_0 + 604$ sec and at $T_0 + 612$ sec; D0054 - Fuel Tank Inlet Pressure was known to have a bad transducer before the firing. No replacement was made.

Measurements D0183 and D0184, LH2 Tank Non-Prop Vent 1 and 2, are known RFI susceptible parameters and gave trend data only.

An evaluation of acceptance firing data revealed that M0069, T/M Aft 5 Volt reference exhibited approximately 2 to 4 percent interference amplitude during chilldown inverter operation. The interference amplitude is not existent on this measurement during the time the 5 volt references will be used for inflight calibrations.

11.2 Telemetry System Performance

The telemetry system performance was good. There was no loss of system synchronization and good data were received from all channels. DDAS hardware (600 kc) to DDAS open-loop (RF) comparison did not reveal any data discrepancies (table 11-4).

Inflight T/M calibration was observed at $T_0 - 3,569$, $T_0 + 92$, and $T_0 + 1,298$ sec. The T/M calibration during the operation of the chilldown inverters at $T_0 + 31$ sec indicated data point dispersions of ± 10 bits with periodic dropouts of 16 bits; however, the T/M calibration, observed when the chilldown inverters were off at $T_0 + 1,298$ sec, showed maximum data point dispersions of only ± 5 bits, which is well within the required tolerance.

11.3 RF System Performance

No difficulties were encountered in the performance of the RF system. The RF power output after correcting for signal conditioning anomaly was 19.5 W. The correction is to compensate for the 115 ohm series resistor on the output of the voltage generator which is used to calibrate the low gain amplifier following the power detector. The VSWR was calculated to be 1.43:1. RF system performance data are presented in the following table:

RF Power Amplifier Output (minimum acceptable is 12 W)	19.5 W
Deviation	32 kc
Ground Station Signal Strength (UV)	10 k
Reflected Power	0.6 W
VSWR (maximum acceptable is 1.8:1)	1.43:1

11.4 Electromagnetic Compatibility

The data acquisition system did not interfere with other stage systems in the areas of electromagnetic compatibility; however, the strain gage pressure transducer for measurements D0183-409 and D0184-409 exhibited RFI susceptibility giving trend data only and measurement M0069-404 showed noise during chilldown inverter operation. This interference will not exist during the time the 5 V reference will be used for inflight calibrations.

11.5 Emergency Detection System Measurements

The LH2 and LOX tank ullage emergency detection system (EDS) pressure measurements performed satisfactorily. The variation between the LOX EDS measurements, which is within instrumentation tolerance, was introduced in the data reduction process.

11.6 Hardwire Data Acquisition System Performance

The ground instrumentation system (GIS) provides a backup and data comparison for certain stage telemetry system parameters in addition to recording measurements from the ground support and facility equipment. The GIS also provides strip charts for redline and cutoff parameter monitoring. The GIS performance during the acceptance firing was satisfactory.

The following table presents the type of recording equipment and the number of channels used during the acceptance firing.

<u>Ground Recorder</u>	<u>Channels Assigned</u>
Beckman 210 Digital Data System	152
Constant Bandwidth FM	67
Wideband FM	7
Strip Charts	37
Total	<u>263</u>

Table 11-5 presents a list of the various types of measurement data recorded and the performance of the system.

11.6.1 Hardwire Measurement Discrepancies

There were three measurement failures, yielding an overall hardwire measurement efficiency of 98.25 percent. The following measurements were classified as failures:

<u>Measurement No.</u>	<u>Parameter</u>	<u>Remarks</u>
D0516	Press LH2 Pump Discharge Press	Ambient shifted. Transducer was replaced.
D0521	Press LOX Pump Primary Seal Cavity	5 to 7 percent ambient high; pin in signal conditioning unit pushed out. Connec- tion was repaired postfire.
F0507	Flow Eng LH2 AC Output	Off scale high. Static test uncovered no prob- lems - dual element pick- up. F-2 - T/M measurement was OK.

TABLE 11-1
INSTRUMENTATION SYSTEM PERFORMANCE SUMMARY

FUNCTION	NUMBER ASSIGNED PER IP&CL	DELETED	INACTIVE	ACTIVE	FAILED
Temperature	45	11	3	31	0
Pressure	58	22	2	34	0
Flow	4	0	0	4	0
Position	8	0	0	8	0
Events	68	5	9	54	2
Liquid Level	5	1	0	4	0
Volt, Current, Freq.	29	0	0	29	0
Miscellaneous	13	4	0	9	0
Speed	2	0	0	2	0
Totals	232	43	14	175	2

TABLE 11-2 (Sheet 1 of 3)
INACTIVE MEASUREMENTS

MEASUREMENT NO.	PARAMETER	REMARKS
C0007-401	Temp - Engine Control Helium	Open - Hardwire reqm't - T/M disconnected
C0050-401	Temp - Hydr Pump Inlet Oil	Open - Hardwire reqm't - T/M disconnected
C0102-411	Temp - Fwd Battery 1	*Simulated - Primary battery not installed
C0103-411	Temp - Fwd Battery 2	*Simulated - Primary battery not installed
C0104-404	Temp - Aft Battery 1	*Simulated - Primary battery not installed
C0105-404	Temp - Aft Battery 2	*Simulated - Primary battery not installed
C0166-414	Temp - He Sphere Gas, Mod 1 (APS)	Simulated - APS not installed
C0167-415	Temp - He Sphere Gas, Mod 2 (APS)	Simulated - APS not installed
C0168-414	Temp - Oxid Tank Outlet, Mod 1 (APS)	Simulated - APS not installed
C0169-415	Temp - Oxid Tank Outlet, Mod 2 (APS)	Simulated - APS not installed
C0170-414	Temp - Fuel Tank Outlet, Mod 1 (APS)	Simulated - APS not installed
C0171-415	Temp - Fuel Tank Outlet, Mod 2 (APS)	Simulated - APS not installed
C0200-401	Temp - Fuel Injection	Open - Hardwire reqm't - T/M disconnected
C0211-411	Temp - Fwd Batt No. 1 Unit No. 2	*Simulated - Primary battery not installed
D0041-403	Press - Hydraulic System	No data - Hardwire reqm't - T/M disconnected
D0042-403	Press - Reservoir Oil	No data - Hardwire reqm't - T/M disconnected
D0063-414	Press - Fuel Sply Man, Mod 1 (APS)	Simulated - APS not installed
D0064-414	Press - He Reg Inlet, Mod 1 (APS)	Simulated - APS not installed
D0065-414	Press - He Reg Outlet, Mod 1 (APS)	Simulated - APS not installed
D0066-415	Press - Oxid Sply Man, Mod 2 (APS)	Simulated - APS not installed
D0067-415	Press - Fuel Sply Man, Mod 2 (APS)	Simulated - APS not installed

* Battery simulator heaters have been deleted; therefore, only Battery SIM Ambient was recorded.

TABLE 11-2 (Sheet 2 of 3)
INACTIVE MEASUREMENTS

MEASUREMENT No.	PARAMETER	REMARKS
D0068-415	Press - He Reg Inlet, Mod 2 (APS)	Simulated - APS not installed
D0069-415	Press - He Reg Outlet, Mod 2	Simulated - APS not installed
D0078-414	Press - Attitude Contr Chamber, 1-1	Simulated - APS not installed
D0079-414	Press - Attitude Contr Chamber, 1-2	Simulated - APS not installed
D0080-414	Press - Attitude Contr Chamber, 1-3	Simulated - APS not installed
D0081-415	Press - Attitude Contr Chamber, 2-1	Simulated - APS not installed
D0082-415	Press - Attitude Contr Chamber, 2-2	Simulated - APS not installed
D0083-414	Press - Attitude Contr Chamber, 2-3	Simulated - APS not installed
D0084-414	Press - Oxid Sply Man, Mod 1 (APS)	Simulated - APS not installed
D0089-414	Press - Fuel Tank Ullage, Mod 1 (APS)	Simulated - APS not installed
D0090-415	Press - Oxid Tank Ullage, Mod 2 (APS)	Simulated - APS not installed
D0091-415	Press - Fuel Tank Ullage, Mod 2 (APS)	Simulated - APS not installed
D0092-415	Press - Oxid Tank Ullage, Mod 2 (APS)	Simulated - APS not installed
D0093-414	Press - Fuel Tank Outlet, Mod 1 (APS)	Simulated - APS not installed
D0094-414	Press - Oxid Tank Outlet, Mod 1 (APS)	Simulated - APS not installed
D0095-415	Press - Oxid Tank Outlet, Mod 2 (APS)	Simulated - APS not installed
D0096-415	Press - Fuel Tank Outlet, Mod 2 (APS)	Simulated - APS not installed
G0003-401	Posit - Main LOX Valve	Simulated - Hardwire reqm't
G0004-401	Posit - Main LH2 Valve	Simulated - Hardwire reqm't
G0005-401	Posit - Gas Generator Valve	Simulated - Hardwire reqm't
G0008-401	Posit - LOX Turbine Bypass Valve	Simulated - Hardwire reqm't
G0009-401	Posit - GH2 Start Tank Valve	Simulated - Hardwire reqm't

TABLE 11-2 (Sheet 3 of 3)
INACTIVE MEASUREMENTS

MEASUREMENT NO.	PARAMETER	REMARKS
K0020-401	Event - ASI LOX Valves, OPEN	No data - Computer reqm't
K0095-401	Event - T/C LH2 Inj Temp OK	No data - J-2 Engine Modification
K0116-401	Event - Gas Gen Valve, CLOSED	No data - Computer reqm't
K0119-401	Event - Main LH2 Valve, CLOSED	No data - Computer reqm't
K0121-401	Event - Main LOX Valve, CLOSED	No data - Computer reqm't
K0123-401	Event - Start Tank Disch Valve, CLOSED	No data - Computer reqm't
K0126-401	Event - LOX Bleed Valve, CLOSED	No data - Computer reqm't
K0127-401	Event - LH2 Bleed Valve, CLOSED	No data - Computer reqm't
K0128-404	Event - Switch Selector	No data - Computer reqm't
L0007-403	Level - Reservoir Oil	Simulated - Hardwire reqm't
N0037-414	Misc - Qty Oxid Tank, Mod 1 (APS)	Simulated - APS not installed
N0038-415	Misc - Qty Oxid Tank, Mod 2 (APS)	Simulated - APS not installed
N0039-414	Misc - Qty Oxid Tank, Mod 1 (APS)	Simulated - APS not installed
N0040-415	Misc - Qty Fuel Tank, Mod 1 (APS)	Simulated - APS not installed

TABLE 11-3
MEASUREMENT DISCREPANCIES

MEASUREMENT NO.	PARAMETER	REMARKS
D0054-410	Press - Fuel Tank Inlet	This transducer malfunctioned prior to static firing. Dispositioned to remove and replace during postfiring checkout. The RAC Cals read -0.123vdc and the ambient value read 104 psia, which is full scale. The transducer has been rejected per FARR A251588 (V) and A251589 (Detail).
D0050-403	Press - Eng Pump Purge Regulator	Data became erratic at T ₀ +604 sec and at T ₀ +612 sec data read -9.0 psia off scale low. Postfiring checkout determined the transducer wiper was open circuited. The transducer has been rejected per FARR A255206.

TABLE 11-4 (Sheet 1 of 2)
TELEMETRY TO HARDWARE DATA COMPARISON (T₀ +213 SEC)

PARAMETER	TELEMETRY			HARDWARE				
	UNITS	MEAS NO.	PCM	UNITS	MEAS NO.	GIS	S/C	F/M
Temp - Fuel Turbine Inlet	°R	C0001	1,704	°R	C0755	1,658	--	1,692
Temp - LH2 Pump Inlet	°R	C0003	37.7	°R	C0658	37.6	37.5	37.8
Temp - LOX Pump Inlet	°R	C0004	164.1	°R	C0659	163.9	164.4	164.0
Temp - GN2 Start Bottle	°R	C0006	221	°R	C0649	231	240	--
Temp - Elect Control Assy.	°R	C0011	530	°R	C0657	528	--	--
Temp - LOX Tank He Inlet	°R	C0016	496	°R	C0662	492	--	--
Temp - LOX Pump Discharge	°R	C0133	169.8	°R	C0648	169.6	--	169.8
Temp - LH2 Pump Discharge	°R	C0134	52.4	°R	C0644	52.3	52.6	--
Temp - Thrust Chamb Jacket	°R	C0199	135	°R	C0645	141	129	--
Temp - Cold He Sphere No. 4	°R	C0210	36	°R	C0661	36.1	34.1	--
Press - Thrust Chamber	psia	D0001	789	psig	D0524	774	780	--
Press - LH2 Pump Inlet	psia	D0002	27.6	psig	D0536	15	15.0	12
Press - LOX Pump Inlet	psia	D0003	40.7	psig	D0537	25	28	--
Press - Main LH2 Injector	psia	D0004	882	psig	D0518	822	--	875
Press - LH2 Pump Discharge	psia	D0008	1,229	psig	D0516	1,336	--	1,350
Press - LOX Pump Discharge	psia	D0009	1,060	psig	D0522	1,103	--	1,080
Press - GG Chamber	psia	D0010	719	psig	D0530	709	--	680
Press - Cont He Reg Discharge	psia	D0014	538	psig	D0581	537	536	545
Press - Cold He Sphere	psia	D0016	2,104	psig	D0542	2,049	2,100	--
Press - GH2 Start Bottle	psia	D0017	298	psig	D0525	286	300	290
Press - Eng Reg Outlet	psia	D0018	411	psig	D0535	395	394	--
Press - Cont He Supply	psia	D0019	2,486	psig	D0534	2,479	2,502	--

TABLE 11-4 (Sheet 2 of 2)
TELEMETRY TO HARDWARE DATA COMPARISON (T₀ +213 SEC)

PARAMETER	TELEMETRY			HARDWARE				
	UNITS	MEAS NO.	PCM	UNITS	MEAS NO.	GIS	S/C	F/M
Press - He Amb Sphere	psia	D0160	2,899	psig	D0541	2,904	2,905	--
Press - LOX Tank U11 EDS-1	psia	D0177	29.7	psig	D0539	15.1	15.5	--
Press - LOX Tank U11 EDS-2	psia	D0178	29.4	psig	D0539	15.1	15.5	--
Press - LH2 Tank U11 EDS-1	psia	D0179	37.7	psig	D0540	23.5	23.5	--
Press - LH2 Tank U11 EDS-2	psia	D0180	37.6	psig	D0540	23.5	23.5	--
Press - Common Blkhd	psia	D0237	-0.2	psia	D0545	0.1	0.1	--
Flowrate LOX	gpm	F0001	2,907	gpm	F0506	2,902	--	2,917
Flowrate LH2	gpm	F0002	8,017	gpm	F0507	9,186	--	7,978
Position - Pitch Act	deg	G0001	-0.1	deg	G0504	-0.1	0.0	-0.1
Position - Yaw Act	deg	G0002	0.0	deg	G0505	-0.1	0.07	-0.1
Voltage - Eng Control Bus	vdc	M0006	28.5	vdc	M0514	28.4	28.4	29
Voltage - Eng Ignition Bus	vdc	M0007	28.8	vdc	M0515	28.6	28.7	29
Voltage - Aft Battery - 1	vdc	M0014	28.7	vdc	M0541	28.7	--	29
Voltage - Aft Battery - 2	vdc	M0015	59.3	vdc	M0540	59.1	58.9	59.5
Voltage - Fwd Battery - 1	vdc	M0016	28.1	vdc	M0543	28.5	--	28.0
Voltage - Fwd Battery - 2	vdc	M0018	26.7	vdc	M0542	27.0	--	27.2
Current - Fwd Battery - 1	amp	M0019	11	amp	M0536	11.6	11.8	11.5
Current - Fwd Battery - 2	amp	M0020	5.1	amp	M0537	4.3	4.9	5.0
Current - Aft Battery - 1	amp	M0021	10	amp	M0534	11.5	11.25	11.5
Current - Aft Battery - 2	amp	M0022	20	amp	M0535	21	21	22.5
Speed - LOX Pump	rpm	T0001	8,565	rpm	T0502	8,682	--	8,688
Speed - LH2 Pump	rpm	T0002	27,260	rpm	T0503	27,458	--	27,408
Position - PU Valve	deg	G0010	30.5	deg	G0503	30.5	32.8	32.5

TABLE 11-5
HARDWIRE DATA ACQUISITION SYSTEM

MEASUREMENT TYPE	RECORDED	FAILED	PARTIALLY SUCCESSFUL	SUCCESSFUL (PERCENT)
Pressure	86	2	0	97.7
Temperature	41	0	0	100
Flow	2	1	0	50.0
Position	10	0	0	100
Voltage/Current	33	0	0	100
Events/Switches	97	0	0	100
Speed	2	0	0	100
Level	3	0	0	100
Vibration	12	0	0	100
Miscellaneous	0	0	0	100
Totals	286	3	0	98.25

12. ELECTRICAL POWER AND CONTROL SYSTEMS

12.1 Electrical Control System

The electrical control system performed satisfactorily as verified in the sequence of events (section 5). All incremental response times to switch selector commands were within the design tolerances.

12.1.1 J-2 Engine Control System

All event measurements verified that the engine control system had responded properly to the engine start and cutoff commands. The Engine Start Command was given by the switch selector 151.844 sec after simulated liftoff. Engine cutoff was initiated at 610.862 sec. Total engine burn time was 459.018 sec.

The ignition detection signal was intermittent during engine burn and was due to flame pattern and probe location. The engine cutoff signal was non-programmed. The main LOX and LH2 valves closed at 0.200 and 0.310 sec respectively after engine cutoff. The LOX and LH2 prevalues closed 1.934 and 1.739 sec respectively after engine cutoff, as verified by the digital events recorder.

12.1.2 Secure Range Safety Command System

The secure range safety command system was tested during the engine burn phase to verify the capability of engine cutoff and propellant dispersion. Evaluation of the data showed that the arm and engine cutoff and propellant dispersion commands were received and that the EBW firing units discharged into their respective pulse sensors. The following measurements were evaluated:

<u>Measurement No.</u>	<u>Parameter</u>
M0030	R/S EBW Firing Unit No. 1
M0031	R/S EBW Firing Unit No. 2
K0141	EBW No. 1 Pulse Sensor Indication
K0142	EBW No. 2 Pulse Sensor Indication
*(K0659)	R/S No. 2 Arm and Engine Cutoff Indication
(K0660)	R/S No. 1 Arm and Engine Cutoff Indication

* Hardwire measurements are in parenthesis.

<u>Measurement No.</u>	<u>Parameter</u>
*(K0692)	R/S No. 2 EBW Arm and Engine Cutoff Indication
(K0693)	R/S No. 1 EBW Arm and Engine Cutoff Indication
N0057	R/S No. 1 Low Level Signal Strength
N0062	R/S No. 2 Low Level Signal Strength

The secure range safety commands, receipt of signals and firing unit performance are shown in figure 12-1.

12.1.3 Control Pressure Switches

A review of the event and pressure measurements verified that each control item functioned properly. Each pressure switch and its associated measurements were evaluated. Listed below are those measurements and a description of their performance.

K0105 Engine Pump Purge Control Regulator Backup Pressure Switch - De-energized

(K0566) Engine Pump Purge Control Module Solenoid Valve - Energized

K0050 Engine Pump Purge Regulator Pressure

The Engine Pump Purge Control Valve Enable ON and OFF Commands were given prior to engine start. The purge orifice size and low back pressure resulted in a purge pressure buildup of 96 psia which was below the actuation of the pressure switch (105 - 130 psia).

K0131 LOX Chilledown Pump Purge Pressure Switch - De-energized

D0103 He Pressure to LOX Pump Motor Control

(K0565) LOX Chilledown Pump Purge Control Valve - Energized

The LOX chilledown pump helium purge regulator backup pressure switch controlled the LOX pump purge control valve during the LOX Chilledown Purge Control Valve Command to maintain a regulated 49 to 53 psia purge pressure.

K0156 LOX Tank Regulator Backup Press Switch - Energized

(K0571) Cold Helium Shutoff Valves - Energized

D0225 Cold Helium Control Inlet Pressure

* Hardwire measurements are in parenthesis.

The measurements indicated that the cold helium regulator backup pressure switch was de-energized during the test and that the actuation pressure of 465 psia was never attained.

D0177, D0178 Fuel Tank Ullage EDS 1 and 2 Pressures

The LH2 tank flight control pressure switch enabled the LH2 pressurization control module to maintain a 26.5 - 29.5 psia pressure in the LH2 tank during the period that the LH2 Tank Pressure Control Switch Enable Command was on. The ullage pressure never dropped below 26.5 psia as verified by measurements D0177 and D0178. At engine start, the pressure was 30.4 psia.

K0102 LOX Prepress Flight Switch - Energized

D0179, D0180 LOX Tank Ullage EDS 1 and 2 Pressures

The LOX prepressurization flight control pressure switch controlled the heat exchanger bypass valve during the LOX Tank Flight Pressurization Command to maintain 37 to 40.8 psia regulated pressure in the LOX tank.

12.1.4 Vent Valves

The LOX and LH2 vent valves are commanded OPEN and CLOSE by GSE, bypassing the switch selector. The vent valves responded to these commands and operated properly. The GSE commands and their corresponding measurements are listed below:

*(K0576) Fuel Tank Vent Valve Open - Energized

K0001 (K0532) Fuel Tank Vent Valve Closed

K0017 (K0542) Fuel Tank Vent Valve Open

(K0575) Oxidizer Tank Vent Valve Open - Energized

K0002 (K0533) Oxidizer Tank Vent Valve Closed

K0016 (K0543) Oxidizer Tank Vent Valve Open

K0113 LH2 Tank Directional Vent Valve C - Closed

K0114 LH2 Tank Directional Vent Valve D - Closed

(K0561) LH2 Tank Directional Vent Valve - Ground Position

(K0562) LH2 Tank Directional Vent Valve - In-flight Position

* Hardwire measurements are in parenthesis.

12.1.5 Childdown Shutoff Valves

These valves were not operated during the acceptance firing.

12.1.6 Fill and Drain Valves (LH2 and LOX)

The fill and drain valves were commanded CLOSED through the umbilical prior to simulated liftoff, and remained closed through the acceptance firing. A review of the following measurements verified that the valves performed satisfactorily:

K0003 *(K0554) Fuel Fill and Drain Valve Closed

K0004 (K0553) LOX Fill and Drain Valve Closed

12.1.7 Depletion Sensors

(K0597) LH2 Depletion Sensor No. 1 - Wet

(K0598) LH2 Depletion Sensor No. 2 - Wet

(K0599) LH2 Depletion Sensor No. 3 - Wet

(K0676) LH2 Depletion Sensor No. 4 - Wet

(K0601) LOX Depletion Sensor No. 1 - Wet

(K0602) LOX Depletion Sensor No. 2 - Wet

(K0603) LOX Depletion Sensor No. 3 - Wet

(K0604) LOX Depletion Sensor No. 4 - Wet

The measurements indicated that all depletion sensors performed as expected during the acceptance firing and no malfunctions were observed. During LH2 loading, LH2 sensor No. 1 indicated dry three times at approximately 31, 34 and once at approximately 60 percent mass. Refer to paragraph 12.4 for the special test on the depletion sensor.

12.2 APS Electrical Control System

The APS Simulator No. 188B was utilized to verify the engine control functions of APS No. 1 and APS No. 2 during the acceptance firing.

Exhibits of the engine feed valves verified that the electrical control system operated within its prescribed limitations.

* Hardwire measurements are in parenthesis.

Listed are the monitored results:

<u>Measurement No.</u>	<u>Function</u>	<u>Specified Minimum Value</u>	<u>Actual Value</u>
K0132	APS Eng 1-1/1-3 Feed Valves Open	3.2 vdc	4.2 vdc
K0133	APS Eng 1-2 Feed Valves Open	3.2 vdc	4.2 vdc
K0134	APS Eng 2-1/2-3 Feed Valves Open	3.2 vdc	4.0 vdc
K0135	APS Eng 2-2 Feed Valves Open	3.2 vdc	4.0 vdc

The specified minimum value of 3.2 vdc indicated that all of the feed valves were operating.

12.3 Electrical Power System

The electrical power system performed satisfactorily throughout the acceptance firing.

The battery voltage, current, and battery simulator temperature profiles are shown in figures 12-2 through 12-4.

12.3.1 Static Inverter-Converter

The static inverter-converter operated within its required limits during the firing. Its actual values are shown in the following table:

<u>Characteristics</u>	<u>Maximum</u>	<u>Minimum</u>	<u>Acceptable Limits</u>
Voltage (vrms)	114.50	114.30	115.0 \pm 3.45
Voltage (vdc)	5.0	5.0	5.0 \pm 0.5
Voltage (vdc)	21.8	21.7	21.0 \pm 1.5 -1.0
Frequency (cps)	400.5	400.7	400.0 \pm 6.0

12.3.2 5-Volt Excitation Modules

The performance of the forward No. 1 and No. 2, and aft 5-volt excitation

modules was satisfactory during the acceptance firing. The actual values are listed below:

<u>Characteristics</u>	<u>Maximum</u>	<u>Minimum</u>	<u>Acceptable Limits</u>
Aft Voltage (vdc)	5.03	5.02	5.0 \pm 0.03
Forward 1 Voltage (vdc)	5.00	4.99	5.0 \pm 0.03
Forward 2 Voltage (vdc)	4.99	4.98	5.0 \pm 0.03

12.3.3 Chilldown Inverters

The chilldown inverters performed satisfactorily during the acceptance firing.

12.4 Special Depletion Sensor Test

During the first LH2 loading, LH2 depletion sensor No. 1 cycled one time for 28 ms at the 30 percent loading level.

On the second LH2 loading, the same sensor cycled three times for 7, 12, and 9 ms at 31, 34 and the 60 percent levels, respectively. No other abnormal cycles were noted during the remainder of the test. The cycles were of such short duration that the special test, prepared for use in case of depletion sensor cycling, could not be implemented.

A Simulated Wet Command was sent to sensor No. 1 at the 5 percent level on the third loading. This would define an open system between sensor and control unit if cycling should occur. No abnormal cycles occurred for the remainder of the test.

During the third loading, a helium bubble test was performed at approximately 86 and 40 percent LH2 level during detanking. Helium was bubbled at a rate of 30 scfm for 2 min. The helium was injected in the low pressure duct by way of the engine purge system. No abnormal depletion sensor activity was noted.




Figure 12-1. Secure Range Safety Command System Data




Figure 12-2. Battery Temperatures




Figure 12-3. Aft Battery Voltage and Current Profiles




Figure 12-4. Forward Battery Voltage and Current Profiles

13. HYDRAULIC SYSTEM

13.1 Hydraulic System Operation

The hydraulic system test program was conducted during countdown 614085, during which the engine was successfully positioned and gimbaled. System running time for this test, from auxiliary pump ON prior to simulated liftoff to auxiliary pump OFF following cutoff, was 1,316.5 sec.

The gimbal program was initiated after the engine start side loads subsided and the support links dropped. The auxiliary hydraulic pump was turned off after the gimbaling program for approximately 47 sec during the firing to verify satisfactory engine-driven pump operation.

Significant event times are presented in the following table:

<u>Event</u>	<u>Approximate Time (sec)</u>
Auxiliary pump ON	$T_0 - 693.5$
Simulated Liftoff	$T_0 + 0$
Engine-driven Pump Start	$T_0 + 153.2$
Support Links Dropped	$T_0 + 187.2$
Gimbal Program Start	$T_0 + 221.0$
Gimbal Program Stop	$T_0 + 277.7$
Auxiliary Pump OFF	$T_0 + 337.0$
Auxiliary Pump ON	$T_0 + 384.0$
Engine-driven Pump Stop	$T_0 + 610.7$
Auxiliary pump OFF	$T_0 + 623.0$

13.2 System Pressure at Salient Times

The GN2 accumulator precharge pressure was 2,309 psia at 53 deg F during prefire checkout and approximately 2,210 psia at 35 deg F after the acceptance firing. The pressure observed after the firing is equivalent to the acceptable precharge pressure limits of 2,300 to 2,400 psia at 68 deg F. Test data indicated that the auxiliary pump discharge pressure increased to 3,600 psia in 14.3 sec after energizing the pump motor. Acceptable pump pressure was maintained from $T_0 - 679.2$ sec through $T_0 - 0$. The simulated launch requirements were met.

During the brief period that the auxiliary pump was off, the engine-driven pump pressure was observed to be 3,650 psia. The engine-driven pump supplied the system leakage flow throughout the firing since its pressure compensator setting was sufficiently higher (3,650 versus 3,600 psia) than that of the auxiliary pump. The auxiliary pump however, shared some of the gimbal flow requirements as seen from fluctuation of the motor current demand.

GN2 pressure was similar to hydraulic system pressure with the pump(s) operating. The significant system pressures are shown in the following table:

<u>TIME (sec)</u>	<u>SYSTEM PRESSURE (psia)</u>	<u>RESERVOIR PRESSURE (psia)</u>
T ₀ -679.2	3,600	161
T ₀ +0 (simulated start)	3,600	180
T ₀ +203 (after engine start transient)	3,650	178
T ₀ +221 to (gimbal)	3,700	192
T ₀ +277	3,590	160
T ₀ +623 (prior to auxiliary pump OFF)	3,630	180

13.3 Reservoir Level at Salient Times

The reservoir level prior to system operation was 90 percent at an approximate average system oil temperature of 61 deg F (equivalent to 91.2 percent at 70 deg F). Minimum level during operation was 33 percent.

13.4 Temperature History

Hydraulic fluid and accumulator gas temperatures experienced during the hydraulic system test program were as follows:

<u>TIME</u> (sec)	<u>ENGINE-DRIVEN PUMP INLET</u> (deg F)	<u>RESERVOIR</u> (deg F)	<u>ACCUMULATOR GN2</u> (deg F)
T ₀ -693.5 (auxiliary pump ON)	50	33	73
T ₀ +153.2 (ignition)	92	60	58
T ₀ +221 (start gimbal)	110	62	61
T ₀ +227.7 (stop gimbal)	97	67	
T ₀ +610.7 (cutoff)	136	75	
T ₀ +623 (auxiliary pump OFF)	137	84	61

13.5 Engine Side Loads

Peak loads in the support links during engine start transients were as follows:

<u>ITEM</u>	<u>PEAK LOAD (lbf)</u>
Pitch Link	+12,000, -20,000
Yaw Link	+17,000, -32,000

13.6 Hydraulic Fluid Flowrates

Approximations from the reservoir fill and emptying rates are presented in the following table:

<u>ITEM</u>	<u>FLOW (gpm)</u>	<u>ALLOWABLE (gpm)</u>
System Internal Leakage	0.51	0.4 to 0.8
Auxiliary Pump Maximum Flowrate	1.77	1.5 min

13.7 Auxiliary Pump Motor Voltage and Current

Auxiliary pump motor electrical data were monitored only after the stage power source had switched to internal power (batteries) and after the chilldown pumps had shut down. The design requirements are as follows:

Voltage	51 to 61 vac
Maximum Starting Current	300 amp
Maximum Operating Current	85 amp

<u>TIME (sec)</u>	<u>VOLTAGE SUPPLY (V)</u>	<u>CURRENT DEMAND (amp)</u>
T ₀ +153 (prior to ignition)	57.5	32.2
T ₀ +160 (after ignition)	59	21
T ₀ +221 to (gimbal)	59 maximum	37.5 maximum
T ₀ +277.2	57.5 minimum	21 minimum (52 maximum during 7 deg ramp)
T ₀ +384 (turn auxiliary pump ON after brief shutdown)	52 min	155 peak
T ₀ +610 (prior to cutoff)	59	21
T ₀ +623 (prior to auxiliary pump OFF)	56.3	39

13.8 Thrust Offset

Approximate thrust offset was calculated from actuator differential pressures obtained prior to and following engine cutoff, using 164,000 lbf net thrust. The thrust offset was 0.273 in. from the stage longitudinal axis and 38.7 deg from fin plane 2 toward fin plane 1.

14. FLIGHT CONTROL SYSTEM

The dynamic response of the hydraulic servo thrust vector control system was measured while the J-2 engine was gimbaling during the acceptance firing of the S-IVB-209 stage. The performance of the pitch and yaw hydraulic servo control system was found to be acceptable.

14.1 Actuator Dynamics

The frequency response test of the pitch and yaw hydraulic servo control system for a $\pm 1/2$ -deg sinusoidal signal between 0.6 and 9 cps, and for a $\pm 1/4$ -deg sinusoidal signal between 0.6 and 2 cps verified the acceptability of the actuator responses. The acceptable limits and the gain and phase plots within these limits are presented in figures 14-1 and 14-2.

14.2 Engine Slew Rates

A nominal two-deg step command was applied to the pitch and yaw actuators from which the engine slew rates were determined. The minimum acceptable engine slew rate is 8 deg/sec, which corresponds to an actuator piston travel rate of 1.66 ips. A nominal slew rate for a 2-deg step without the effects of gimbal friction is 13.6 deg/sec. The measured values were found to be acceptable and are presented in the following table:

<u>Actuator</u>	<u>Condition</u>	<u>Engine Travel (deg)</u>	<u>Engine Slew Rate deg/sec</u>
Pitch	Retract	0.0 to +2.0	10.8
	Extend	+2.0 to 0.0	10.8
	Extend	0.0 to -2.0	10.9
	Retract	-2.0 to 0.0	10.7
Yaw	Extend	0.0 to +2.0	11.9
	Retract	+2.0 to 0.0	11.3
	Retract	0.0 to -2.0	11.4
	Extend	-2.0 to 0.0	11.8

The minimum engine slew rate obtained is 10.7 deg/sec. This corresponds to an actuator piston travel of 2.22 ips when using a conversion of 4.83 deg of engine movement per in. of actuator travel. Thus, in all cases, each actuator exceeded the minimum acceptable piston travel rate of 1.66 ips, or corresponding engine travel rate of 8 deg/sec.

14.3 Differential Pressure Feedback Network

The differential pressure feedback network in the pitch and yaw hydraulic servo-valves was operating properly since adequate system damping was demonstrated by observing the actuator differential pressure measurements during the 2-deg step response tests. The differential pressures decreased in amplitude as a function of time without sustained ringing. The recorded data are presented in figure 14-3.

14.4 Cross Axis Coupling

A minimum amount of cross axis coupling occurred as noted by the generated actuator differential pressure in the non-gimbaled plane.




Figure 14-1. Actuator Response (Gain)




Figure 14-2. Actuator Response (Phase Lag)




Figure 14-3. Actuator Differential Pressure (± 2 Deg Transient Response)

15. STRUCTURAL SYSTEMS

Structural integrity of the S-IVB-209 stage was maintained for the vibration, temperature, and thrust load conditions of the acceptance firing. No structural irregularities were detected during the postfiring inspection, static firing, and cryogenic loading.

15.1 Common Bulkhead

The results of the gas sample surveys, combined with satisfactory common bulkhead pressure decay checks, indicate the bulkhead is sound and leak tight. An additional vacuum port location for common bulkhead internal pressure measurements was used for the second time, having been previously used with the S-IVB-503N stage. This port, located approximately 180 deg from the vacuum pump port, was located so the readings would be more indicative of general pressure conditions within the honeycomb filled bulkhead. It was found that during pumpdown of the common bulkhead, the pressure readings from the vacuum pump port dropped immediately to less than 1 psia; however, at the pressure port located 180 deg from the vacuum pump port the pressure gradually dropped to 10.5 psia in 6 hrs and to less than 1 psia in 9 days of pumpdown. Thus, it is evident that the newly added pressure measurement (D0237) is more accurate than the original vacuum pump port measurement (D0545) in indicating general pressure conditions within the bulkhead. During the actual acceptance firing, the bulkhead internal pressure readings from both transducers was less than 1 psia. Gas sample analyses consistently indicated negligible quantities of hydrogen and helium gases within the common bulkhead. The results of the pressure checks and gas surveys are presented in Douglas Report No. SM-37550, *S-IVB-209 Stage Acceptance Firing (15 Day) Report*, dated July 1967.

15.2 LH2 Tank Interior

LH2 tank internal inspections during buyoff have been discontinued in view of a series of recent S-IVB stages having virtually no tank non-conformities requiring repair; however, as a matter of routine verification, the tank interior will be visually inspected from the manhold when the S-IVB-209 stage is erected in the VCL after storage.

15.3 Exterior Structure

A visual inspection of the stage thrust structure, LOX tank aft dome, aft skirt, LH2 tank cylindrical section, LH2 tank forward dome, and forward skirt revealed no structural damage after the full duration acceptance firing. The inspection revealed no debonding of stand-offs, tunnel clips, or the aft skirt purge membrane.

15.4 Malfunction of LOX Tank Pressure Regulator

As a result of a malfunction of the LOX tank pressure regulator, the LOX tank ullage pressure was abnormally low for a duration of 60 sec immediately following J-2 engine start. During this time a minimum LOX tank ullage pressure of 29.1 psia was obtained (refer to paragraph 7.1). Simultaneously, the LH2 tank ullage pressure was 33.7 psia. The corresponding LH2 and LOX pressure heads at the critical common bulkhead to aft dome joint were 0.8 and 2.7 psia respectively. The net differential pressure at the joint was -2.7 psid (negative pressures occur when LH2 tank pressure exceeds LOX tank pressure). The design pressure at the critical joint is -21.9 psid limit or -30.7 psid ultimate (reference page 386 of Douglas Report No. SM-46987, *Saturn S-IVB-202 Stage Flight Evaluation Report*); therefore, the critical common bulkhead to aft dome joint has adequate strength to resist the imposed negative pressure differential without detrimental effects.

16. THERMOCONDITIONING AND PURGE SYSTEMS

16.1 Aft Skirt Thermoconditioning and Purge System

The aft skirt GN2 purge was initiated prior to LOX loading and continued throughout the acceptance firing until the completion of tank purge. The purge system operated satisfactorily and was within the design limits.

16.1.1 Aft Skirt GN2 Flowrate

The GN2 purge flowrate of 3,400 scfm was maintained throughout the acceptance firing.

16.1.2 Aft Skirt GN2 Temperature

The GN2 temperature at the APS module thermoconditioning system outlet sensor (C0663) held constant at 90 deg F. The aft skirt umbilical inlet temperature (C0715) varied between 105 and 110 deg F throughout the acceptance firing.

16.1.3 Aft Skirt Umbilical Inlet Pressure

The umbilical inlet pressure (D0767) was approximately 1/2 psi (13.8 in. H₂O) throughout the firing.

16.1.4 Nonflight Hardware

a. APS Module

Model DSV-4B-188B APS simulators were used in place of the flight modules at APS positions 1 and 2. These substitutes functionally represent the flight module thermoconditioning system.

b. Aft Interstage

The model DSV-4B-540 dummy interstage was used to support the stage on the test stand.

16.2 Forward Skirt Environmental Control and Thermoconditioning System

The forward skirt GN2 purge was initiated prior to LOX loading and continued throughout the firing until the completion of the tank purges.

The model DSV-4B-359, thermoconditioning system servicer, supplied the methanol/water coolant fluid to the thermoconditioning system throughout the firing.

16.2.1 Forward Skirt GN2 Purge Flowrate

A flowrate of 500 scfm was maintained during the acceptance firing which was within the design requirement of 500-600 scfm.

16.2.2 Forward Skirt GN2 Temperature

The forward skirt GN2 internal temperature (C0768) was within 43 to 58 deg F which was above the minimum design requirement of 40 deg F.

16.2.3 Forward Skirt Internal Pressure

The forward skirt internal pressure was approximately 0.69 in. H₂O which is well below the relief valve setting of 2 in. of H₂O.

16.2.4 Forward Skirt Thermoconditioning System Temperature

The thermoconditioning system fluid inlet temperature (C0753) was maintained between 56 to 61 deg F which is within the design temperature range of 57 \pm 7 deg F.

16.2.5 Nonflight Hardware

Model DSV-4B-359, Thermoconditioning System Servicer

The servicer supplies thermally conditioned fluid to the forward skirt cold plates during all field station operations requiring power to the forward skirt electronic equipment. When the S-IVB is staged, the cold plates will receive fluid from the NASA instrument unit thermoconditioning system.

17. RELIABILITY AND HUMAN ENGINEERING

17.1 Reliability Engineering

All functional failures of Flight Critical Items (FCI) and Ground Support Equipment/Special Attention Items were investigated by Reliability Engineering. Significant malfunctions of FCI's documented are noted in table 17-1.

17.2 Human Engineering

A Human Engineering evaluation was conducted in support of the S-IVB-209 stage acceptance firing. No significant man-machine problems were identified.

TABLE 17-1 (Sheet 1 of 6)
FLIGHT CRITICAL COMPONENTS MALFUNCTIONS

P/N AND S/N	NAME	TROUBLE	CAUSE	ACTION TAKEN
1A48431-505 S/N D-1	Probe, Fuel Mass	<p>The following discrepancies were discovered while performing assembly outline modification on LH2 mass probe, lower mount:</p> <ol style="list-style-type: none"> 1. Retaining plug was installed in such a manner as to preclude removal without damage to plug. Peelings of plug around plug port indicated maximum force had been exerted to install the plug. 2. Kel-F plug was forced into split-sleeve. Should be loose fit. 3. Lock pin P/N 973491-1 appeared to be sawed off and rough filed on end. 4. Foreign material, rubber like, found on hollow end of lock pin. 	To be determined.	The probe was removed and shipped to location A3 for further evaluation and disposition. The discrepant probe was replaced with a like configuration probe, S/N D-6.
1A49968-509 S/N 101	Valve, Propellant Tank Shutoff	During C/D 614086 (TR1046, Run 3A) with propellants loaded, no hardwire talkback was received from the valve when prevalues were commanded closed. The valve also exhibited a slow opening time (3.010 sec).	To be determined.	The valve was removed and sent to location A-MRCC for additional test and evaluation. The discrepant valve was replaced with a like configuration valve, S/N 109.

TABLE 17-1 (Sheet 2 of 6)
FLIGHT CRITICAL COMPONENTS MALFUNCTIONS

P/N AND S/N	NAME	TROUBLE	CAUSE	ACTION TAKEN
1A66212-505 S/N 015	Electronics Assembly, Inverter- Converter, Static	During prefiring system checkout, unit was found to be inoperative. No output was obtained with an input of 28 vdc.	To be determined.	The unit cover was removed at location A45 and the internal components inspected for signs of wire and module damage from heat or electrical shorting. No visible damage was noted. The unit was removed and routed to location A-MRCC for additional disposition, test, and possible SFA. The discrepant unit was replaced with a like configuration unit, S/N 00011.
1A66248-507 S/N 68	Actuator Assembly, Hydraulic	Nicks and scratch marks were found around the rod end of hydraulic actuator.	Caused by installation and removal of the mid- stroke locks. Due to the close tolerance between the lock and rod end, technicians must gently rock J-2 engine in order to install or remove locks. Using this method, the locking halves tend to pene- trate the softer metal at the rod ends.	The nicks and scratches were removed with crocus cloth and hand stone. At the completion of rework and inspection, actuator was found acceptable by engineering for use.

TABLE 17-1 (Sheet 3 of 6)
FLIGHT CRITICAL COMPONENTS MALFUNCTIONS

P/N AND S/N	NAME	TROUBLE	CAUSE	ACTION TAKEN
1B42290-503 S/N 0025	Module, Control, LOX Tank Pressurization	During prefiring system checkout per procedure 1B71877, leakage of 2,500 scim was measured through the cold helium shutoff valve segment of the module. Maximum allowable leakage is 375 scim.	Not determined at location A45. Believed to be the shutoff valve main poppet seat (3 ply .010 mylar).	EW0 32607 revises Drawing 1B42290 and creates -505 configuration identical to the -503 except for the shutoff valve main poppet seats (Vespel, SP-1) and the addition of a circle-seal check valve in the top vent of the regulator. The module was routed to location A3-MRCC for further disposition. The discrepant module was replaced by a -505 configuration module, S/N 0037.
1B42290-503 S/N 0037	Module, Control, LOX Tank Pressurization	During C/D 614085 (TR1046, Run 2A) the output of the module regulator was 222 to 230 psia after mainstage ignition. The output should not exceed 410 \pm 25 psig.	To be determined.	The module was sent to location A-MRCC for further investigation and test. The discrepant module was replaced with a like configuration module, S/N 0028.

TABLE 17-1 (Sheet 4 of 6)
FLIGHT CRITICAL COMPONENTS MALFUNCTIONS

P/N AND S/N	NAME	TROUBLE	CAUSE	ACTION TAKEN
1B43657-509 S/N 016	Module Assembly Pneumatic Power Control	During propulsion systems checkout at location A3-VCL, this module malfunctioned twice. The regulator discharge pressure went to approximately 600 psig. The regulator output should be 475 \pm 25 psig. The regulator operated satisfactorily during seven tests that followed. Because the malfunction did not repeat, no FARR was written at A3 and the module was not replaced; however, the malfunction was recorded in location A3-SPB ROD #165 which is a description of the propulsion systems checkout at location A3.	During prefire checkout at location A45, FARR A245444 was written removing the module from the vehicle and FARR A245479 was written against the module. Engineering requested this action because of the malfunction noted on ROD #165 and because there was no information available at location A45 pertaining to this assembly. There was no malfunction of the module at location A45.	The module was removed and shipped back to location A3. It was dispositioned at A3 as "acceptable to engineering for use" due to the known history of the module (Ref. ROD #165). No further action will be taken regarding this case. The module was replaced with a like configuration module, S/N 022.
1B53920-501 S/N 51	Valve, Check, Chill System	The valve failed during the leak check per procedure 1B70773. The reverse leakage was 8,400 scim. The leakage should not exceed 6,000 scim.	To be determined.	The valve was removed and shipped to location A3-MRCC for evaluation and final disposition. The discrepant valve was replaced with a like configuration valve, S/N 040.

TABLE 17-1 (Sheet 5 of 6)
FLIGHT CRITICAL COMPONENTS MALFUNCTIONS

P/N AND S/N	NAME	TROUBLE	CAUSE	ACTION TAKEN
1B57781-501 S/N 0011	Module, Cold Helium Fill	During the checkout per procedure 1B57781, the reseal pressure was found to be 3,195 psig. The procedure calls for a reseal pressure between 3,200 and 3,500 psig.	Suspected improper adjustment of the relief valve.	The module was removed and shipped to the vendor for rework to -503 configuration. The discrepant module was replaced with a -503 configuration module, S/N 31. WRO S-IVB-3171 R2 1B58006 calls for replacing the 1B57781-501 module with a -503 configuration.
1B57781-503 S/N 0031	Module, Cold Helium Fill	The module failed during the test per procedure 1B57781 when removed from the stage and sent to A45 LOX Lab for test in compliance with 1B70773. The recorded cracking pressure was found to be 3,180 psig. The procedure calls for a cracking pressure between 3,200 and 3,500 psig.	Not determined at location A45.	The module was sent to location A-MRCC for evaluation and test. The failure mode could not be duplicated (cracking pressure was 3,280 psig) and the module was found to be acceptable to engineering for use. The module was returned to location A45 for installation on the stage.

TABLE 17-1 (Sheet 6 of 6)
FLIGHT CRITICAL COMPONENTS MALFUNCTIONS

P/N AND S/N	NAME	TROUBLE	CAUSE	ACTION TAKEN
1B57781-503 S/N 0031	Module, Cold Helium Fill	During C/D 614085 (Task 51) post-test securing, the cold helium fill valve was frozen in the "open" position. The valve could not be cycled at ambient temperature.	To be determined.	The module was removed and sent to the vendor for investigation and rework. The discrepant module was replaced with a like configuration module, S/N 0034.
103826 S/N J-2083	J-2 Engine	During engine field inspection prior to acceptance firing, the actuation time of the gas generator control valve was 128 ms instead of 140 ms.	To be determined.	Unit control pneumatics line was re-orificed to correct valve timing. The .047 dia orifice was replaced by Rocketdyne with a .043 dia orifice. This is a GFE item.

AP 1

ENGINE PERFORMANCE
PROGRAM (PA49)

1. ENGINE PERFORMANCE PROGRAM (PA49)

This appendix contains the digital printout of computer program PA49 which is a compilation of computer programs AA89, G105, and F823. These computer programs are the methods employed in the propulsion system performance reconstruction of the S-IVB-209 stage acceptance firing. The performance analysis and associated plots are presented in section 6. Printout symbols are presented in table AP 1-1 and the digital printout is contained in table AP 1-2.

TABLE AP 1-1
PROGRAM PA49 PRINTOUT SYMBOLS

FSUB1	Stage thrust from AA89 (lbf)	EMR 3	Engine mixture from F823
WDOTT1	Total flowrate from AA89 (lbm/sec)	ISP 3	Specific impulse from F823 (sec)
WDOTO1	LOX flowrate from AA89 (lbm/sec)	MSUBO3	LOX mass onboard from F823 (lbm)
WDOTF1	LH2 flowrate from AA89 (lbm/sec)	MSUBF3	LH2 mass onboard from F823 (lbm)
EMR 1	Engine mixture ratio from AA89	FSUB4	Predicted stage thrust (lbf)
ISP 1	Specific Impulse from AA89 (sec)	WDOTT4	Predicted total flowrate (lbm/sec)
MSUBO1	LOX mass onboard from AA89 (lbm)	WDOTO4	Predicted LOX flowrate (lbm/sec)
MSUBF1	LH2 mass onboard from AA89 (lbm)	WDOTF4	Predicted LH2 flowrate (lbm/sec)
FSUB2	Stage thrust from G105 (lbf)	EMR 4	Predicted engine mixture ratio
WDOTT2	Total flowrate from G105 (lbm/sec)	ISP 4	Predicted specific impulse (sec)
WDOTO2	LOX flowrate from G105 (lbm/sec)	MSUBO4	Predicted LOX mass onboard (lbm)
WDOTF2	LH2 flowrate from G105 (lbm/sec)	MSUBF4	Predicted LH2 mass onboard (lbm)
EMR 2	Engine mixture ratio from G105	THRUST	Composite stage thrust (lbf)
ISP 2	Specific impulse from G105 (sec)	T FLOW	Composite total flowrate (lbm/sec)
MSUBO2	LOX mass onboard from G105	O FLOW	Composite LOX flowrate (lbm/sec)
MSUBF2	LH2 mass onboard from G105 (lbm)	F FLOW	Composite LH2 flowrate (lbm/sec)
FSUB 3.	Stage thrust from F823 (lbf)	*EMR*	Composite engine mixture ratio
WDOTT3	Total flowrate from F823 (lbm/sec)	*ISP*	Composite specific impulse (sec)
WDOTO3	LOX flowrate from F823 (lbm/sec)	O MASS	Composite LOX mass onboard (lbm)
ODOTF3	LH2 flowrate from F823 (lbm/sec)	F MASS	Composite LH2 mass onboard (lbm)

TABLE AP 1-2 (Sheet 1 of 6)
ENGINE PERFORMANCE PROGRAM (PA49)

TIME	FSUB 2	FSUB 3	FSUB 4	THRUST	6.100	193504.428	193350.928	231468.832	186345.672
FSUB 1	FSUB 2	FSUB 3	FSUB 4	THRUST	172141.652	193504.428	193350.928	231468.832	186345.672
WONTT1	WONTT2	WONTT3	WONTT4	T FLOW	199.454	453.117	450.387	543.905	434.320
WONTT1	WONTT2	WONTT3	WONTT4	O FLOW	123.314	374.454	371.602	460.613	355.457
WONTT1	WONTT2	WONTT3	WONTT4	F FLOW	76.143	78.663	78.785	83.291	77.864
EMR 1	EMR 2	EMR 3	EMR 4	*EMR*	4.266	4.760	4.717	5.530	4.574
ISP 1	ISP 2	ISP 3	ISP 4	*ISP*	431.040	427.351	429.299	425.569	429.130
MSURD1	MSURD2	MSURD3	MSURD4	O MASS	192187.805	192078.850	192046.215	191788.803	192106.289
MSURF1	MSURF2	MSURF3	MSURF4	F MASS	37756.678	37747.492	37774.847	37667.007	37759.672
0.000	0.000	0.000	0.000	0.000	6.200	193702.537	193710.355	231463.910	186764.980
0.000	0.000	0.000	0.000	0.000	172676.055	193702.537	193710.355	231463.910	186764.980
0.000	3.475	1.479	0.000	1.651	399.991	453.562	451.308	543.892	434.953
0.000	3.416	0.260	0.000	1.225	323.796	374.496	372.422	460.601	357.162
0.000	0.059	1.219	0.000	0.426	76.194	78.566	76.886	83.291	77.864
0.000	57.810	0.214	0.000	19.341	4.250	4.773	4.722	5.530	4.581
0.000	0.000	0.000	0.000	0.000	431.700	427.351	429.233	425.570	429.461
193215.000	193215.000	193215.000	193273.000	193215.000	192155.435	192041.332	192006.978	191742.899	192068.555
38047.000	38047.000	38047.000	38000.000	38047.000	37749.030	37739.603	37766.931	37658.637	37751.454
1.000	0.000	0.000	447.604	72.731	6.200	193741.078	193754.781	231463.664	186803.930
218.192	0.000	0.000	4.852	15.454	172715.932	193741.078	193754.781	231463.664	186803.930
32.366	12.525	1.471	0.000	8.406	400.113	453.629	451.403	543.891	435.949
22.566	2.393	0.259	0.000	7.048	323.918	375.060	372.509	460.601	357.162
9.801	10.132	1.212	4.852	0.917	76.194	78.569	78.694	83.291	77.864
2.302	0.236	0.214	0.000	2.247	4.251	4.774	4.722	5.530	4.582
0.761	0.000	0.000	92.249	0.000	431.669	427.532	429.228	425.570	429.475
193190.209	193211.963	193214.703	193272.564	193205.484	192153.779	192039.451	192007.057	191740.395	192068.760
38041.037	38041.021	38045.757	37995.167	38042.604	37748.647	37739.203	37766.535	37658.218	37751.453
2.000	17136.404	16486.111	43407.979	16862.966	7.000	213107.453	213299.707	231424.533	212386.637
16566.382	17136.404	16486.111	43407.979	16862.966	210552.759	213107.453	213299.707	231424.533	212386.637
86.672	95.674	13.238	113.200	65.202	481.549	487.773	499.087	543.790	489.470
48.763	56.464	0.331	65.825	37.179	400.850	408.351	417.740	460.505	408.940
37.929	39.230	0.908	47.375	28.022	80.709	79.422	81.347	83.291	80.499
1.285	1.439	0.917	1.389	1.214	4.967	5.142	5.135	5.529	5.031
191.138	177.075	1279.514	383.462	548.593	437.263	437.309	427.038	425.577	433.976
193155.154	193196.154	193211.979	193236.223	193187.760	191868.760	191731.275	191693.078	191373.903	191764.349
38020.645	38020.166	38042.367	37965.003	38027.725	37686.180	37676.229	37702.544	37591.677	37688.317
3.000	112398.611	115683.021	165017.518	109475.517	8.000	227214.785	227104.746	231375.309	222747.516
100344.920	112398.611	115683.021	165017.518	109475.517	223923.020	227214.785	227104.746	231375.309	222747.516
188.671	211.030	249.568	355.977	216.473	522.651	520.343	520.476	543.663	521.157
135.475	156.303	199.878	271.929	163.859	440.217	438.667	438.238	460.384	439.040
53.196	54.729	64.891	64.048	52.538	82.435	81.676	82.238	83.279	82.116
2.567	4.725	4.404	4.558	3.142	5.340	5.371	5.329	5.528	5.347
531.853	534.619	463.533	463.533	509.334	426.437	427.054	426.734	425.585	427.448
193076.320	193107.203	193115.152	193077.646	193099.557	191440.304	191303.113	191260.377	190913.023	191334.797
37974.264	37972.428	38011.133	37910.944	37985.941	37604.362	37595.173	37620.375	37507.983	37606.643
4.000	187939.219	181765.442	216093.441	175750.609	9.000	225024.471	223689.355	231564.840	224243.333
162647.127	187939.219	181765.442	216093.441	175750.609	225024.471	223689.355	223438.328	231564.840	224243.333
361.517	409.682	424.531	494.556	397.910	529.275	527.300	523.940	544.148	526.848
292.199	338.117	344.338	416.029	324.815	446.314	444.764	441.115	460.845	444.138
69.318	71.564	76.193	78.527	73.075	82.941	82.336	82.425	83.303	82.701
4.215	4.725	4.404	5.298	4.448	5.381	5.404	5.326	5.532	5.370
449.901	446.296	430.183	436.939	442.127	426.248	424.217	426.458	425.555	425.641
192850.523	192845.170	192810.863	192701.844	192835.518	190971.102	190860.604	190819.510	190451.971	190492.472
37913.138	37909.301	37934.550	37839.064	37920.330	37521.230	37512.617	37537.421	37424.280	37523.756
4.100	184480.361	183206.680	217300.160	177351.479	10.000	226359.841	224919.771	231546.784	225346.719
164367.402	184480.361	183206.680	217300.160	177351.479	226359.841	224919.771	224880.496	231546.784	225346.719
367.832	417.095	426.703	496.897	403.877	531.733	530.236	526.731	544.101	529.722
297.719	344.341	347.107	417.984	329.772	448.791	447.409	444.079	460.800	447.074
70.114	72.753	74.597	78.914	74.154	81.207	80.630	80.256	83.301	82.608
4.240	4.733	4.361	5.297	4.447	5.394	5.417	5.340	5.532	5.466
446.854	442.299	429.154	437.114	439.502	425.490	424.188	426.774	425.559	425.434
192820.977	192811.002	192776.109	192662.098	192805.695	190549.111	190413.920	190379.674	189990.680	190446.234
37906.140	37902.067	37930.573	37831.150	37912.926	37437.817	37429.826	37454.944	37340.566	37440.729
4.110	184020.842	183359.926	217421.119	177473.416	15.000	227153.350	227015.986	231347.494	227752.153
164439.406	184020.842	183359.926	217421.119	177473.416	227153.350	227015.986	226881.143	231347.494	227752.153
368.472	417.769	427.051	497.131	404.431	534.973	536.958	534.825	543.584	535.252
298.240	344.928	347.478	418.179	330.279	452.181	454.589	451.380	460.317	452.717
70.122	72.841	74.573	78.952	74.202	82.701	82.368	82.445	83.272	82.535
4.249	4.735	4.367	5.297	4.451	5.462	5.519	5.475	5.528	5.465
446.283	441.927	429.363	437.351	439.191	425.729	424.272	426.521	425.593	425.567
192817.969	192807.523	192774.631	192657.904	192790.371	188294.310	188154.970	188129.004	187685.773	188192.445
37905.432	37901.333	37924.775	37830.355	37912.140	37021.073	37016.006	37042.137	36922.073	37026.475
5.000	190324.592	190325.650	224680.352	183342.245	20.000	229172.553	228629.662	231124.498	228873.664
169376.621	190324.592	190325.650	224680.352	183342.245	229172.553	228629.662	228668.777	231124.498	228873.664
393.050	444.489	444.030	513.151	426.523	538.082	538.836	535.451	543.047	517.456
318.078	367.127	367.074	431.440	350.093	455.762	456.544	453.946	459.824	455.384
74.973	77.361	76.956	81.711	76.440	82.320	82.272	81.025	83.273	81.272
4.243	4.746	4.744	5.280	4.577	5.576	5.548	5.561	5.525	5.549
430.929	428.188	430.572	437.845	429.896	425.907	424.303	427.058	425.615	425.750
192561.100	192487.582	192452.145	192279.053	192493.615	186022.105	185673.205	185562.846	185383.082	185919.383
37840.153	37833.765	37861.228	37758.293	37845.048	36006.350	36003.427	36036.377	36003.739	36014.051
6.000	173236.453	193126.275	231478.818	184022.176	25.000	229444.350	228708.771	231015.701	228394.943
171703.911	173236.453	193126.275	231478.818	184022.176	229444.350	228708.771	228631.775	231015.701	228394.943
398.970	452.683	449.890	543.930	433.848	538.924	540.143	535.588	542.816	538.216
322.844	373.421	371.144	460.637	355.943	456.441	457.962	453.778	456.562	456.774
76.087	78.762	78.762	83.293	77.865	82.353	82.181	81.410	83.154	82.164
4.244	4.748	4.713	5.330	4.548	5.542	5.573	5.547	5.528	5.544
430.167	426.869	429.274	425.567	428.837	425.960	423.423	426.480	425.587	425.238
192720.160	192716.314	192703.418	191874.910	192139.043	183759.289	183593.334	183590.334	183082.484	183637.716
37764.319	37755.390	37744.752	37675.376	37767.447	36192.600	36190.876	36222.163	36085.745	36271.840

TABLE AP 1-2 (Sheet 2 of 6)
ENGINE PERFORMANCE PROGRAM (PA49)

30.000	229598.783	229710.984	231048.240	229437.675	80.000	229497.680	229524.725	230852.713	230043.508
230203.372	541.958	537.834	542.969	540.453	231228.173	539.661	539.216	542.797	540.565
541.566	459.052	459.531	459.872	458.412	543.797	456.550	455.454	460.012	457.617
459.052	82.513	82.307	83.097	82.041	460.460	83.111	82.782	82.745	82.948
82.513	5.563	5.585	5.615	5.534	82.951	5.550	5.502	5.557	5.517
5.563	425.070	423.647	427.104	425.527	5.550	425.211	425.203	425.302	425.617
425.070	181448.459	181287.650	181311.668	180781.502	425.211	158711.453	158475.752	157735.133	158158.688
181448.459	35778.570	35778.290	35812.830	35668.061	31619.527	31622.187	31675.512	31499.955	31637.740
35778.570									
35.000	230174.469	230224.816	231093.746	230429.077	85.000	228621.932	228719.797	230773.119	229476.576
230882.803	543.048	539.211	543.143	541.606	230938.313	538.829	536.023	542.614	539.317
542.553	460.692	457.614	460.089	459.600	543.003	455.837	453.823	459.851	456.619
459.893	82.356	81.598	83.054	82.205	460.176	82.992	82.200	82.759	82.698
82.690	5.574	5.508	5.540	5.549	82.903	5.541	5.571	5.557	5.522
5.564	425.454	426.975	425.475	425.460	5.551	424.294	420.697	425.302	425.405
425.454	179148.827	179071.056	178477.318	179054.440	425.117	155991.756	156149.447	154933.260	156069.332
179148.827	35364.049	35403.040	35250.641	35177.438	156066.801	31194.543	31205.596	31044.046	31221.327
35364.049									
40.000	230455.939	230553.217	231134.127	230794.322	90.000	230093.227	229997.137	230695.768	230446.874
231373.814	542.691	540.062	543.282	541.989	231370.115	542.615	539.492	542.425	542.111
543.213	460.158	458.282	460.254	459.660	544.275	459.608	456.570	459.691	459.142
460.554	82.533	81.779	83.028	82.322	461.247	82.978	82.722	82.735	82.949
82.654	5.572	5.604	5.543	5.544	82.978	5.559	5.537	5.534	5.534
5.572	425.730	426.654	425.440	425.830	5.559	425.117	424.345	425.304	425.168
425.730	176845.154	176684.328	176176.236	176756.457	425.117	153099.836	153868.121	153132.195	153775.723
176845.154	34948.917	34951.314	34991.317	34963.449	153759.213	30781.597	30788.622	30843.787	30668.257
34948.917									
45.000	230716.520	230759.201	231188.123	231063.051	95.000	229945.049	229704.270	231023.041	230374.541
231134.439	543.661	540.766	543.456	542.749	231534.311	542.616	539.675	543.279	541.901
543.878	461.016	458.827	460.452	460.244	544.812	458.981	456.591	460.516	458.705
461.149	82.645	82.080	83.005	82.445	461.544	83.064	82.736	82.763	83.106
82.730	5.574	5.588	5.547	5.580	82.978	5.555	5.528	5.564	5.514
5.574	426.039	426.726	425.403	425.714	5.555	424.240	420.108	425.238	425.161
426.039	174538.254	174381.756	174450.393	174456.799	425.136	151449.777	15102.387	150874.698	151478.297
174538.254	34533.378	34536.708	34574.249	34549.795	151449.777	30364.455	30371.839	30426.583	30347.659
34533.378									
50.000	230733.049	230755.412	231264.244	231141.926	100.000	229369.447	229174.240	231107.541	229926.314
231937.372	542.951	540.915	543.688	542.679	231235.262	541.855	537.645	543.513	541.137
544.170	460.134	458.492	460.704	459.950	543.910	458.871	456.548	460.752	458.107
461.315	82.855	82.422	82.984	82.678	460.902	82.985	82.707	82.761	83.030
82.855	5.566	5.556	5.552	5.552	83.064	5.530	5.510	5.567	5.517
5.566	426.222	426.961	425.362	425.925	5.552	423.304	420.259	425.211	424.838
426.222	172230.164	172078.539	172160.664	172156.455	425.135	149139.277	149104.492	148523.495	149150.104
172230.164	34117.418	34121.288	34154.800	34134.532	149139.277	29947.330	29955.156	29836.561	29970.557
34117.418									
55.000	230510.623	230554.230	231343.498	230457.699	105.000	229155.977	229176.834	231189.301	229798.309
231804.240	542.685	540.363	543.924	542.507	231062.121	540.147	537.127	543.742	540.277
544.474	459.953	458.127	460.457	459.872	543.556	457.288	454.815	460.987	457.582
461.531	82.732	82.236	82.967	82.635	460.644	82.959	82.712	82.755	82.695
82.938	5.560	5.571	5.556	5.545	82.914	5.519	5.525	5.570	5.533
5.560	425.747	426.760	425.324	425.724	5.555	424.247	420.672	425.182	425.137
425.747	169920.830	169776.295	169871.709	169856.109	425.097	146832.596	146813.813	146216.918	146888.402
169920.830	33700.944	33705.727	33744.794	33718.878	425.097	29530.441	29539.221	29420.715	29554.372
33700.944									
60.000	230249.908	230225.508	231426.367	230724.674	110.000	229079.936	229017.400	230901.168	229688.041
231698.607	542.690	539.717	544.164	542.397	230766.792	539.913	536.625	543.024	539.959
544.784	459.847	457.727	461.210	459.599	543.374	457.285	454.325	460.323	457.352
461.721	82.843	82.409	82.954	82.708	460.447	82.914	82.628	82.701	82.608
82.866	5.559	5.551	5.550	5.551	82.891	5.534	5.520	5.566	5.536
5.559	425.304	426.275	425.367	425.362	5.555	424.290	420.774	425.213	425.134
425.304	167610.426	167472.896	167574.441	167554.244	425.097	144575.027	144774.805	143910.412	144597.938
167610.426	33283.974	33289.486	33335.927	33303.128	425.097	29113.667	29123.708	29004.023	29116.878
33283.974									
65.000	230505.027	230558.361	231110.682	230443.649	115.000	228604.182	228504.764	230834.988	229345.943
231725.797	542.788	540.283	543.383	542.671	230778.954	540.153	537.160	542.672	539.641
544.943	459.868	458.144	460.494	459.977	543.060	457.632	454.402	460.196	457.128
461.919	82.920	82.139	82.987	82.644	460.350	82.710	82.322	82.676	82.533
83.024	5.564	5.578	5.556	5.542	82.710	5.566	5.566	5.566	5.539
5.564	425.227	426.669	425.318	425.570	5.555	424.260	420.672	425.210	424.946
425.227	165299.385	165170.318	165284.911	165252.504	425.097	142222.357	142235.402	141806.898	142328.395
165299.385	32866.670	32873.003	32921.397	32887.630	425.097	28097.047	28106.170	28089.465	28123.068
32866.670									
70.000	230433.721	230365.652	231374.195	230867.970	120.000	227896.627	227704.072	230768.875	228300.250
231804.416	542.764	540.191	543.187	542.718	230602.054	538.441	535.617	542.720	539.376
545.199	459.761	457.353	460.332	459.763	543.070	456.229	453.172	460.069	457.970
462.175	82.802	82.339	82.955	82.655	460.301	82.212	82.220	82.651	82.400
82.823	5.567	5.539	5.556	5.542	82.770	5.561	5.549	5.566	5.534
5.567	425.174	426.556	425.313	425.354	5.561	423.252	420.715	425.208	424.947
425.174	162987.262	162868.586	162955.559	162950.449	423.252	13950.173	140195.066	139304.023	140021.377
162987.262	32449.465	32456.199	32507.010	32470.891	423.252	28292.965	28348.357	28174.093	28307.137
32449.465									
75.000	230024.672	230056.430	230934.418	230460.557	125.000	228667.521	228511.282	230703.789	229407.770
231300.570	541.138	539.393	542.992	541.490	230604.573	538.764	535.700	542.571	539.404
543.941	458.060	456.720	460.172	458.586	543.744	456.364	453.172	459.945	456.838
460.979	82.962	82.672	82.820	82.904	460.979	82.406	82.527	82.626	82.566
82.962	5.557	5.514	5.556	5.532	82.745	5.530	5.532	5.567	5.533
5.557	425.211	426.076	425.307	425.606	5.557	424.214	420.646	425.205	424.942
425.211	160677.844	160570.750	160707.918	160652.172	425.097	137612.044	137932.430	137001.773	137736.266
160677.844	32032.470	32039.148	32091.074	32054.230	425.097	27863.127	27878.176	27933.138	27878.847
32032.470									

TABLE AP 1-2 (Sheet 3 of 6)
ENGINE PERFORMANCE PROGRAM (PA49)

130.000					180.000				
231193.363	229158.818	229113.889	230640.801	229822.070	231392.582	229397.423	229433.320	230546.867	230074.441
544.009	541.855	530.715	542.424	540.847	544.426	540.945	537.723	542.305	541.031
461.258	459.240	454.736	459.821	458.411	461.170	458.232	455.569	459.823	458.374
82.832	82.615	81.979	82.504	82.475	83.256	82.713	82.154	82.482	82.708
5.569	5.559	5.547	5.567	5.558	5.539	5.540	5.545	5.575	5.552
424.918	422.915	420.881	425.204	424.905	425.021	424.068	420.676	425.124	425.255
135303.799	135374.078	135652.580	134700.146	135443.518	112753.884	112465.622	112880.761	111677.738	112533.415
27445.171	27462.554	27517.966	27343.723	27475.431	23272.402	23307.525	23372.597	23195.369	23317.578
135.000					185.000				
231302.555	229899.008	229853.121	230581.230	230351.559	231108.519	230178.932	230076.506	230498.135	230454.648
544.287	542.008	530.788	542.281	541.874	543.942	540.384	539.634	542.193	541.320
461.353	459.373	450.437	459.695	459.054	460.912	457.470	456.041	459.729	458.408
82.933	82.635	82.351	82.586	82.640	83.030	82.714	82.793	82.464	82.912
5.563	5.559	5.543	5.566	5.555	5.551	5.533	5.502	5.575	5.529
424.965	424.162	426.612	425.206	425.246	424.877	425.955	420.356	425.122	425.729
132994.521	133076.582	133370.617	132399.143	133147.278	109446.636	110171.932	110600.309	109376.671	110239.675
27028.289	27046.608	27104.355	26928.695	27059.417	22854.406	22871.932	22757.398	22786.948	22901.378
140.000					190.000				
231063.334	229191.158	229048.811	230521.662	229767.766	231138.355	229423.014	229553.527	230449.402	230081.797
543.704	540.789	530.822	542.138	540.438	544.286	541.379	537.665	542.080	541.110
460.814	458.340	454.453	459.570	457.869	461.210	458.596	456.032	459.634	458.613
82.890	82.449	82.368	82.569	82.576	83.076	82.782	81.533	82.446	82.947
5.559	5.559	5.517	5.566	5.545	5.552	5.546	5.586	5.575	5.559
424.980	423.809	426.676	425.208	425.155	424.848	423.776	421.001	425.120	425.208
130687.336	130778.176	131009.584	130094.782	130851.607	107336.847	107876.855	108316.113	107076.073	107944.074
26610.730	26630.620	26686.657	26513.751	26643.335	22437.157	22776.278	22543.244	22366.618	22485.560
145.000					195.000				
231095.174	229506.881	229336.443	230462.694	229979.500	231009.039	228992.658	228325.387	230173.985	229509.025
543.627	541.069	537.867	541.995	540.848	543.541	540.123	535.892	541.716	539.852
460.599	458.264	454.902	459.442	457.922	460.912	457.381	454.253	459.596	457.311
83.030	82.805	82.964	82.551	82.677	83.271	82.762	81.639	82.126	82.540
5.547	5.534	5.484	5.566	5.572	5.531	5.526	5.564	5.590	5.541
425.097	424.173	426.397	425.210	425.222	425.004	423.409	420.799	424.898	425.139
128381.762	128485.414	128812.481	127799.060	128559.885	105333.590	105584.228	106037.791	104775.874	105651.888
26193.278	26214.873	26272.787	26098.895	26226.979	22619.749	22600.822	22124.766	21952.328	22070.043
150.000					200.000				
231234.345	229603.664	229502.066	230768.443	230114.375	230551.647	228768.250	228641.367	230144.672	229553.555
543.731	539.780	538.154	542.790	540.545	543.855	540.052	536.698	541.626	540.035
460.442	457.114	450.373	460.209	457.643	460.317	457.294	453.918	459.491	457.177
83.249	82.666	82.781	82.581	82.912	83.037	82.759	82.730	82.134	82.858
5.574	5.530	5.501	5.573	5.570	5.544	5.526	5.483	5.594	5.518
425.274	425.365	426.467	425.152	425.702	424.863	423.374	420.347	424.914	425.075
126077.045	126194.485	126535.103	125496.724	126269.239	103029.166	103295.668	103761.566	102475.980	103362.134
25776.021	25799.479	25857.905	25884.061	25811.155	21602.366	21645.258	21719.750	21537.922	21654.458
155.000					205.000				
231088.311	228834.617	228913.041	230834.613	229605.320	230795.479	228586.463	228596.844	230114.650	229322.476
543.593	539.074	536.455	542.973	539.707	543.241	539.954	535.671	541.535	539.622
460.546	456.320	454.351	460.394	457.073	460.198	457.291	453.606	459.392	457.032
83.044	82.754	82.103	82.579	82.634	83.042	82.663	82.065	82.142	82.590
5.546	5.514	5.534	5.575	5.511	5.542	5.532	5.527	5.593	5.534
425.076	424.406	426.716	425.131	425.429	424.862	423.344	420.730	424.931	424.974
123772.859	123905.771	124258.478	123195.016	123979.035	100725.704	101009.271	101484.730	100176.581	101074.900
25358.835	25383.896	25443.600	25249.102	25395.444	21184.892	21230.025	21300.543	21123.473	21238.487
160.000					210.000				
230954.521	229090.502	229144.635	230900.051	229731.219	230874.032	228755.828	228450.945	230084.615	229794.169
543.329	539.845	536.770	543.156	539.441	543.143	539.485	535.991	541.444	539.561
460.291	457.221	454.856	460.380	457.454	460.262	457.009	452.853	459.293	456.708
83.037	82.624	81.920	82.576	82.527	82.886	82.476	83.138	82.150	82.833
5.543	5.534	5.552	5.578	5.543	5.553	5.541	5.447	5.591	5.514
425.073	424.363	426.903	425.103	425.447	424.002	424.027	420.221	424.947	424.983
121469.287	121617.765	121981.846	120890.373	121689.631	98422.320	98723.271	99214.932	97877.677	98788.508
24941.601	24968.459	25029.514	24854.159	24979.858	20167.330	20614.707	20884.644	20708.984	20822.279
165.000					215.000				
230989.846	229343.541	229330.332	230965.398	229887.906	230631.277	228707.297	228610.787	230054.590	229316.453
543.392	539.985	537.607	543.333	540.248	542.974	539.392	535.940	541.353	539.455
460.291	457.143	455.156	460.766	457.510	460.003	456.766	453.457	459.194	456.742
83.101	82.722	82.451	82.572	82.758	82.772	82.627	82.483	82.158	82.694
5.539	5.526	5.520	5.580	5.529	5.544	5.526	5.498	5.589	5.573
425.039	424.817	426.576	425.086	425.494	424.756	424.009	420.501	424.963	425.108
119166.410	119330.369	119700.839	11834.804	119401.207	96119.513	96437.315	96944.517	95579.271	96502.114
24524.561	24553.376	24610.323	24439.234	24564.753	20349.644	20399.341	20469.758	20294.455	20406.248
170.000					220.000				
230860.594	229466.367	229460.584	230844.340	229929.162	230510.975	228443.651	228364.658	230026.316	229107.893
543.143	539.130	536.006	542.330	540.073	542.725	539.122	535.191	541.263	539.679
460.099	456.576	453.337	460.011	457.404	459.785	455.839	453.043	459.095	456.229
83.043	82.555	82.469	82.519	82.649	82.940	82.283	82.147	82.169	82.457
5.540	5.531	5.524	5.575	5.532	5.545	5.540	5.515	5.587	5.533
425.046	425.623	426.502	425.127	425.724	424.727	424.519	420.707	424.980	425.318
116864.027	117044.691	117435.060	116281.288	117114.592	9717.505	94153.677	94681.165	93281.357	94217.248
24107.313	24138.471	24201.125	24024.485	24148.969	19931.752	19983.855	20055.758	19879.383	19990.455
175.000					225.000				
231170.816	229298.293	229230.768	230595.604	229979.957	230582.990	228663.945	228650.045	230375.488	229298.992
543.993	540.415	537.425	542.418	540.611	542.827	538.629	535.481	542.138	539.112
460.925	457.665	454.853	460.917	457.815	459.745	456.012	453.613	459.906	456.463
83.068	82.749	82.572	82.501	82.796	83.063	82.617	82.267	82.232	82.649
5.549	5.531	5.509	5.575	5.529	5.533	5.520	5.514	5.593	5.523
424.952	424.300	426.535	425.126	425.293	424.702	424.530	420.681	424.939	425.331
114560.072	114758.298	115160.104	113979.278	114626.157	91816.091	91870.002	92413.381	91982.659	91933.324
23690.156	23723.172	23787.213	23609.881	23733.313	19113.794	19268.706	19640.604	19465.177	19574.369

TABLE AP 1-2 (Sheet 4 of 6)
ENGINE PERFORMANCE PROGRAM (PA49)

230.000 230503.969 542.771 459.452 82.059 5.543 424.680 89214.264 19095.469	228702.451 538.175 455.857 82.318 5.538 424.959 89286.639 19153.368	228408.264 535.716 452.680 82.036 5.452 424.361 90146.851 19227.176	230433.051 542.776 460.009 82.257 5.592 424.944 88680.671 19050.197	229204.893 538.887 456.116 82.771 5.511 425.333 89649.457 19156.671	280.000 197673.564 461.695 382.803 78.892 4.852 428.144 67307.204 14664.506	195816.006 459.894 381.518 74.375 4.868 425.785 67742.255 15048.131	195479.963 457.636 378.232 71.404 4.886 429.904 68473.479 15140.815	212172.150 456.822 416.263 80.419 5.175 427.230 65864.005 14908.052	196456.510 459.075 380.851 78.224 4.869 427.946 67840.979 15051.181
235.000 230600.584 542.875 459.733 83.142 5.529 424.777 86914.289 18677.114	229006.896 538.612 456.255 82.357 5.540 425.179 87304.259 18738.299	228763.252 535.413 453.683 82.919 5.471 426.356 87879.477 18814.375	230490.613 542.395 460.113 82.282 5.592 424.950 86378.165 18635.091	229443.707 519.363 456.557 82.806 5.514 425.437 87366.021 18742.929	285.000 195417.080 456.205 377.873 78.422 4.818 428.269 65403.444 14569.508	192695.625 452.095 374.304 77.791 4.812 426.228 65852.586 14655.661	192680.266 448.044 370.756 77.288 4.797 430.003 66579.133 14751.920	202899.924 473.966 395.058 78.928 5.005 428.071 63837.795 14507.793	193590.922 452.145 374.311 77.834 4.899 428.166 65951.721 14659.030
240.000 230424.545 542.549 459.499 83.046 5.534 424.711 84614.110 18258.824	228194.469 538.222 455.887 82.335 5.537 423.987 85023.039 18323.190	228024.301 535.413 452.611 82.402 5.485 426.078 85612.649 19399.684	230773.107 542.774 460.167 82.607 5.571 425.174 84075.267 18219.939	228892.104 516.393 455.799 82.594 5.519 425.120 85083.266 18327.232	290.000 193680.838 451.917 373.674 78.284 4.773 428.575 63522.610 14176.039	190606.422 447.172 369.456 77.116 4.756 426.249 63992.492 14265.815	190544.420 443.047 365.763 77.284 4.733 430.086 64755.215 14364.452	196688.055 454.938 381.030 77.901 4.891 428.572 61894.172 14113.855	191611.891 447.379 369.618 77.901 4.753 428.303 64090.272 14268.749
245.000 230887.357 543.644 460.420 83.274 5.532 424.703 82313.562 17840.345	228670.785 538.728 456.218 82.510 5.529 424.464 82743.814 17908.275	228514.117 535.852 453.154 82.698 5.480 426.450 83348.206 17986.666	230805.287 542.672 460.273 82.598 5.514 425.156 81771.967 17804.870	229357.416 539.408 456.598 82.811 5.514 425.216 82401.859 17411.742	295.000 192787.408 448.692 370.708 77.894 4.739 428.551 61660.320 13783.991	189353.791 443.420 366.154 77.665 4.739 427.031 62152.583 13877.192	189121.779 439.109 362.174 77.534 4.671 430.107 62930.924 13977.902	193030.309 450.000 372.667 77.333 4.723 428.956 60013.188 13723.793	190254.324 443.940 368.375 77.565 4.723 428.563 62247.944 13879.692
250.000 230747.621 543.445 460.345 83.190 5.530 424.601 80004.043 17421.688	228071.473 539.806 457.468 82.138 5.536 423.989 80456.938 17492.625	228686.881 536.122 453.217 82.305 5.498 426.557 81076.898 17573.886	230837.447 542.969 460.381 82.589 5.531 425.139 79468.133 17389.846	229435.322 539.791 457.163 82.640 5.514 425.049 80516.306 17496.066	300.000 191050.074 446.193 368.954 77.234 4.721 428.174 59809.045 13392.747	188645.484 442.036 364.767 77.268 4.721 426.765 60322.533 13389.381	188364.674 438.106 360.371 77.137 4.696 429.904 61114.355 13390.129	190125.143 443.736 367.571 76.165 4.826 428.464 58161.987 13335.994	189353.408 442.112 364.679 77.413 4.711 428.298 60416.993 13490.752
255.000 229794.588 540.678 457.140 83.538 5.472 425.012 77710.004 17002.383	227836.068 537.280 454.600 82.680 5.498 424.055 78172.430 17076.724	227719.613 533.799 451.315 82.683 5.454 426.435 78806.871 17156.162	230494.393 542.108 459.578 82.530 5.569 425.182 77167.354 16975.074	228446.754 537.319 454.362 82.967 5.476 425.167 78279.768 17079.089	305.000 190542.953 444.829 367.517 77.301 4.754 428.360 57966.091 13001.737	187396.508 439.516 363.327 76.489 4.746 426.370 58501.229 13102.252	187264.490 434.834 358.427 76.207 4.703 430.860 59323.294 13201.529	188652.568 440.120 364.142 75.978 4.793 428.639 56311.313 12949.262	189401.944 439.657 362.971 76.666 4.735 428.530 58596.871 13101.840
260.000 223924.535 525.802 462.744 83.058 5.331 425.873 75451.570 16582.956	222631.795 525.765 463.464 82.301 5.388 423.444 75924.387 16662.443	222534.674 521.162 459.245 81.917 5.362 426.997 76575.120 16746.202	230445.689 542.000 459.492 82.508 5.569 425.177 74867.687 16560.425	223030.332 524.243 441.818 82.429 5.360 425.438 75483.691 16663.847	310.000 190120.262 443.888 360.747 77.140 4.754 428.307 56126.870 12611.180	187199.436 434.783 357.324 76.296 4.746 425.888 56685.719 12715.257	186832.533 433.859 357.324 76.535 4.669 430.752 57530.357 12813.708	187737.891 437.860 361.984 75.876 4.771 428.763 54514.366 12763.288	188068.574 439.177 362.520 76.657 4.771 428.241 56781.637 12713.491
265.000 214601.408 502.927 421.301 81.627 5.151 426.705 73295.073 16189.490	214324.076 506.028 424.442 81.586 5.202 423.542 73754.913 16251.125	214136.553 501.393 419.773 81.620 5.143 427.068 7427.699 16335.835	230396.750 541.891 459.404 82.486 5.569 425.172 72568.257 16145.685	214354.676 503.449 421.838 81.611 5.169 425.778 73425.961 16252.317	315.000 189786.642 442.879 367.767 77.057 4.747 428.334 54995.222 12220.547	186948.998 438.214 362.024 76.184 4.752 426.616 54874.120 12329.335	186595.847 434.346 358.567 76.781 4.644 430.590 55441.103 12426.804	187257.164 436.653 360.808 75.345 4.757 428.547 52705.692 12177.696	187741.012 438.129 361.453 76.676 4.714 428.515 56970.147 12325.609
270.000 206709.791 483.810 403.523 80.287 5.026 427.254 71231.202 15763.117	206840.014 486.081 407.631 80.450 5.067 423.782 71648.431 15643.949	206796.783 482.947 403.134 79.813 5.051 424.198 72363.411 15930.039	230051.418 540.959 458.395 82.564 5.552 425.266 70270.120 15731.363	206782.195 484.946 404.762 80.144 5.068 426.411 71754.348 15445.702	320.000 199812.657 442.907 365.580 77.322 4.724 428.363 52464.004 11830.277	186597.502 438.510 362.286 76.223 4.753 426.188 53085.015 11943.393	186832.641 434.180 357.631 76.549 4.734 431.309 53957.123 12038.656	187985.795 436.197 360.332 75.865 4.758 428.902 50400.462 11792.147	187445.277 438.199 361.834 76.395 4.758 428.573 51154.344 11649.924
275.000 201370.197 470.785 391.409 79.377 4.931 427.733 69243.956 15362.013	200034.133 470.108 390.790 79.318 4.927 425.507 69073.234 15441.803	200055.172 466.212 387.025 78.588 4.932 424.108 70389.574 15534.526	223479.461 542.267 452.686 82.181 5.379 426.270 68007.832 15316.178	206486.500 469.035 389.941 79.074 4.930 427.449 69768.428 15446.114	325.000 189650.822 442.672 365.333 77.138 4.739 428.423 50613.571 11439.747	187242.840 438.181 361.898 76.283 4.744 427.318 51254.553 11557.303	186920.406 434.169 357.277 76.069 4.647 428.945 52168.051 11652.495	187655.888 435.084 360.184 75.900 4.746 428.945 49097.494 11406.503	187938.020 438.340 361.570 76.770 4.710 428.756 51454.344 11649.924

TABLE AP 1-2 (Sheet 5 of 6)
ENGINE PERFORMANCE PROGRAM (PA49)

330.000					380.000				
18971.525	187024.760	186636.914	187097.633	187813.054	188297.887	185733.650	185437.215	187227.805	186789.5-2
442.498	437.548	433.690	436.151	437.912	439.810	434.963	430.990	436.293	435.257
365.402	361.280	357.113	360.214	361.331	362.570	358.669	355.172	360.192	358.870
77.000	76.267	76.378	75.936	76.580	77.247	76.095	75.818	76.100	76.377
4.740	4.737	4.678	4.744	4.718	4.694	4.716	4.685	4.733	4.698
428.412	427.448	430.812	424.975	428.871	428.809	427.470	431.187	429.134	429.153
4802.497	4944.703	50374.363	47294.370	49562.320	30559.229	31389.184	32562.533	29233.153	31503.648
11049.193	11171.256	11267.342	11020.715	11162.593	7143.366	7314.122	7402.244	7157.318	7286.558
335.000					385.000				
189691.801	185864.348	186663.916	187175.697	187740.020	188356.709	186001.182	185705.520	187099.086	186647.801
442.759	437.706	433.215	436.215	437.893	439.360	435.553	431.073	435.974	435.399
365.602	361.291	358.800	360.348	361.231	362.284	359.441	354.543	359.884	358.756
77.157	76.415	76.415	75.967	76.662	77.076	76.112	76.530	76.090	76.573
4.734	4.728	4.669	4.743	4.712	4.700	4.723	4.633	4.730	4.685
428.431	426.917	430.881	428.992	428.743	428.707	427.046	430.199	429.152	428.381
46972.062	47634.567	48591.166	45490.807	47732.708	28745.203	29591.804	30789.677	27430.808	29718.835
10658.549	10785.201	10831.603	10634.813	10775.118	6753.030	6924.092	7012.638	6770.888	6899.255
340.000					390.000				
189772.334	186971.557	186784.201	187278.559	187842.695	188278.563	185552.203	185270.357	186974.541	186345.675
442.847	436.818	436.509	436.540	437.725	439.169	434.811	429.888	434.667	434.623
365.583	360.685	357.187	360.539	361.152	362.107	358.825	353.361	359.588	358.096
77.204	76.133	76.321	76.001	76.573	77.062	75.986	76.527	76.079	76.525
4.732	4.738	4.680	4.744	4.719	4.699	4.722	4.617	4.726	4.670
428.528	428.030	430.866	429.007	429.141	428.715	426.742	430.824	429.169	428.761
45141.814	45824.765	46804.269	43686.416	45923.615	26931.912	27494.101	29017.378	25679.964	27914.444
10267.606	10399.213	10490.539	10248.795	10387.786	6362.910	6544.031	6628.331	6384.514	6511.757
345.000					395.000				
189613.117	186656.818	186378.834	187340.668	187549.588	188502.061	185496.555	185167.201	186433.523	186388.604
442.539	437.235	434.078	436.780	437.434	439.713	434.706	429.762	435.320	434.776
365.371	361.067	358.169	360.751	360.849	362.610	358.724	354.302	359.253	358.212
77.164	76.168	76.309	76.035	76.615	77.109	75.982	76.460	76.066	76.514
4.735	4.740	4.655	4.745	4.710	4.703	4.721	4.621	4.723	4.652
428.460	426.903	430.757	429.022	428.709	428.676	426.717	430.360	429.187	428.750
43313.141	44014.617	45014.105	41881.005	44115.247	25118.364	25957.892	27240.113	23830.677	26120.759
9876.907	10013.106	10104.595	9862.652	9999.536	5972.670	6159.165	6241.860	5996.198	6124.573
350.000					400.000				
189324.566	186419.148	186124.307	187523.387	187289.018	188379.467	186030.227	185692.932	186681.000	186701.057
441.832	437.639	431.987	437.082	437.153	439.419	435.376	431.145	434.945	435.313
364.701	361.406	352.552	361.007	360.553	362.445	359.318	354.449	358.892	358.704
77.131	76.233	76.435	76.076	76.600	77.073	76.058	76.609	76.052	76.639
4.728	4.741	4.652	4.745	4.707	4.701	4.724	4.621	4.719	4.632
428.479	425.986	430.854	429.034	428.639	428.703	427.287	430.697	429.206	428.856
41485.209	4204.965	43231.894	40074.454	42307.351	23303.967	24199.777	25474.050	22033.169	24325.911
9486.184	9627.040	9722.229	9476.374	9611.919	5582.427	5774.529	5852.279	5611.951	5737.412
355.000					405.000				
189420.098	186525.699	186215.744	187645.537	187387.130	188110.334	185664.869	185404.527	186547.805	186393.242
441.894	437.237	432.237	437.360	437.123	439.747	434.386	430.198	434.623	434.510
364.542	361.131	358.170	361.250	360.505	362.610	358.289	353.496	358.595	357.971
77.302	76.086	76.467	76.110	76.618	77.032	76.077	76.490	76.030	76.519
4.710	4.747	4.653	4.745	4.705	4.690	4.708	4.627	4.717	4.677
428.655	426.601	430.818	429.041	428.671	428.744	427.419	430.775	429.216	428.940
39659.408	40397.737	41444.476	38266.571	40502.207	21491.564	22404.256	23703.761	20237.330	22533.194
9095.514	9241.367	9332.565	9089.936	9224.149	5192.184	5389.211	5468.583	5224.797	5349.993
360.000					410.000				
189241.742	186744.771	186545.891	187674.531	187510.807	188084.877	185621.607	185335.625	186462.818	186313.703
441.571	436.374	432.993	437.420	436.979	438.087	434.082	429.366	434.422	433.778
364.607	360.114	356.531	361.296	360.351	361.650	358.070	351.965	358.410	357.230
77.165	76.259	76.452	76.124	76.629	77.031	76.011	76.602	76.012	76.546
4.722	4.722	4.663	4.746	4.703	4.693	4.711	4.595	4.715	4.667
428.564	427.947	430.829	429.049	429.113	428.743	426.237	430.827	429.221	428.600
37633.830	38591.336	39687.066	36457.922	38697.410	19581.695	20610.137	21938.462	18442.699	20742.755
8704.784	8655.628	8946.715	8703.390	8836.375	4802.218	5004.152	5079.321	4839.743	4961.944
365.000					415.000				
189138.736	185983.166	185682.760	187609.213	186934.885	187771.224	185309.430	185084.342	186434.758	186055.154
441.255	436.597	430.925	437.250	436.259	437.943	434.037	429.399	434.356	433.771
364.040	360.531	356.609	361.128	359.777	360.948	358.035	353.280	358.355	357.433
77.215	76.066	76.314	76.123	76.572	76.943	76.049	76.119	76.001	76.338
4.715	4.740	4.647	4.744	4.700	4.691	4.711	4.641	4.715	4.681
428.638	425.984	430.894	429.066	428.505	428.757	426.949	431.032	429.221	428.915
36010.757	36785.949	37887.222	34649.619	36494.643	17873.490	18816.670	20169.595	16648.688	18453.242
8314.173	8470.150	8561.534	8316.815	8448.619	4412.259	4619.359	4692.996	4453.763	4574.868
370.000					420.000				
188785.002	185936.451	185783.574	187485.500	186835.008	18758.899	185702.703	184952.703	186456.375	185871.432
440.484	436.152	430.842	436.940	435.826	437.143	434.016	429.151	434.411	433.437
363.415	360.044	352.025	360.827	357.475	360.182	358.023	352.962	358.416	357.058
77.069	76.108	75.817	76.113	76.331	76.950	75.993	76.189	75.994	76.379
4.715	4.731	4.683	4.741	4.710	4.690	4.711	4.633	4.716	4.675
428.595	426.311	431.210	429.088	428.742	428.820	426.718	430.973	429.217	428.839
34190.088	34985.175	36109.337	32842.526	35094.460	16866.324	17023.711	18402.750	14854.680	17164.328
7923.622	8084.650	8175.094	7930.272	8061.122	4922.407	4234.658	4309.435	4067.627	4183.580
375.000					425.000				
188443.539	185750.744	185592.955	187354.248	186595.742	187483.922	185101.361	184876.553	186505.992	185821.344
439.642	434.697	430.442	436.610	434.927	437.175	432.701	428.475	434.526	432.917
362.611	358.517	354.404	360.505	358.511	360.170	356.746	352.705	358.529	356.548
77.031	76.180	76.037	76.105	76.416	76.940	75.955	76.171	75.997	76.359
4.707	4.706	4.651	4.737	4.691	4.691	4.711	4.607	4.714	4.669
428.627	427.311	431.160	429.111	429.076	428.853	427.782	431.378	429.218	428.928
32373.448	33186.371	34330.714	31037.059	33294.844	14261.753	15233.848	16637.177	13060.077	15177.572
7533.424	7699.394	7788.234	7543.782	7673.654	3632.681	3850.281	3924.878	3681.902	3852.347

TABLE AP 1-2 (Sheet 6 of 6)
ENGINE PERFORMANCE PROGRAM (PA49)

430.000	187408.301	185623.924	184991.344	186566.523	185807.855	458.200	188348.803	185913.154	185630.242	186966.145	186664.044
437.014	433.769	433.769	428.624	434.664	433.136	429.798	429.798	435.384	430.471	435.618	435.218
360.076	357.810	357.810	353.407	358.601	357.098	362.754	362.754	359.352	354.578	359.641	358.895
76.933	75.959	75.959	75.217	76.003	76.038	77.044	77.044	76.032	75.893	75.977	76.373
4.680	4.711	4.711	4.599	4.719	4.676	4.708	4.708	4.726	4.672	4.734	4.702
428.838	426.549	426.549	431.594	429.220	428.994	428.717	428.717	426.780	431.225	429.197	428.908
12457.882	13443.493	13443.493	14871.502	11266.915	13590.959	2260.456	2260.456	3327.597	4874.136	1129.492	3494.063
3242.995	3465.816	3465.816	3539.675	3295.950	3416.142	1044.664	1044.664	1297.932	1376.206	1120.004	1239.601
435.000	187472.184	185444.176	185336.107	186627.877	186084.354	458.300	188558.512	185893.768	185678.336	184970.137	186710.203
437.174	433.809	433.809	429.619	434.803	433.534	439.857	439.857	435.397	430.677	435.628	435.298
360.240	357.803	357.803	353.945	358.795	357.329	362.774	362.774	359.374	354.628	359.650	358.925
76.933	76.006	76.006	75.674	76.008	76.204	77.047	77.047	76.024	76.048	75.977	76.373
4.682	4.708	4.708	4.677	4.721	4.689	4.704	4.704	4.727	4.663	4.734	4.700
428.828	427.479	427.479	431.398	429.224	429.235	428.715	428.715	426.952	431.132	429.197	428.933
10654.196	11652.856	11652.856	13104.408	9469.089	11803.820	2224.136	2224.136	3291.617	4858.033	1093.483	3458.129
2853.316	3081.270	3081.270	3156.430	2909.972	3030.339	1036.862	1036.862	1290.233	1368.505	1112.287	1231.867
440.000	187581.803	185418.488	185218.307	186641.225	186072.843	458.400	188575.732	185939.191	185575.145	184974.016	186663.354
437.456	433.999	433.999	429.528	434.844	433.658	439.857	439.857	435.440	430.496	435.637	435.446
360.528	358.126	358.126	353.639	358.861	357.431	362.799	362.799	359.929	354.339	359.659	359.022
76.928	75.864	75.864	75.890	75.983	76.227	77.057	77.057	76.066	76.148	75.978	76.424
4.687	4.721	4.721	4.660	4.723	4.689	4.708	4.708	4.732	4.653	4.734	4.698
428.802	427.241	427.241	431.213	429.214	429.085	428.721	428.721	426.242	431.083	429.197	428.682
8850.356	9861.949	9861.949	11339.103	7672.734	10017.136	2187.814	2187.814	3259.608	4823.156	1057.474	3422.193
2463.718	2696.725	2696.725	2771.665	2524.041	2644.036	1029.061	1029.061	1282.533	1360.794	1104.570	1224.129
445.000	187802.580	185119.037	184945.852	186638.914	185975.822	458.500	188586.113	185826.998	185576.756	184977.908	186663.363
438.117	433.986	433.986	428.774	434.845	433.632	439.881	439.881	436.073	430.555	435.646	435.514
361.180	358.157	358.157	353.135	358.889	357.491	362.825	362.825	359.980	354.417	359.667	359.074
76.957	75.829	75.829	75.638	75.956	76.141	77.059	77.059	76.093	76.168	75.979	76.440
4.693	4.723	4.723	4.669	4.725	4.695	4.708	4.708	4.731	4.653	4.734	4.697
428.776	426.555	426.555	431.337	429.208	428.899	428.718	428.718	426.137	430.988	429.197	428.615
7043.943	8070.009	8070.009	9573.382	5876.193	8229.112	2151.492	2151.492	3219.567	4787.672	1021.646	3386.244
2074.037	2312.540	2312.540	2386.687	2134.243	2257.755	1021.258	1021.258	1274.828	1353.082	1096.854	1216.399
450.000	187958.227	185350.158	185357.434	186674.307	186221.938	458.600	188563.381	185883.830	185697.453	184981.807	186714.887
438.375	434.658	434.658	429.348	434.937	434.194	439.894	439.894	436.440	430.870	435.655	435.388
361.420	358.656	358.656	354.304	359.004	358.176	362.829	362.829	359.369	354.792	359.675	358.995
76.955	75.992	75.992	75.045	75.933	75.997	77.030	77.030	76.071	76.078	75.979	76.393
4.697	4.720	4.720	4.672	4.728	4.712	4.708	4.708	4.724	4.664	4.734	4.699
428.762	426.437	426.437	431.118	429.199	428.972	428.699	428.699	426.888	430.983	429.197	428.855
5234.786	6275.701	6275.701	7803.062	4079.339	6437.850	2115.163	2115.163	3183.559	4752.150	985.453	3350.291
1684.192	1928.349	1928.349	2003.028	1752.575	1871.846	1013.455	1013.455	1267.125	1345.378	1089.137	1200.653
455.000	188496.361	185491.863	185484.139	186838.508	186490.745	458.700	188559.684	185819.295	185670.135	184985.717	186683.035
439.660	435.381	435.381	429.574	435.320	434.872	439.841	439.841	435.378	430.661	435.664	435.293
362.600	359.521	359.521	354.675	359.363	358.934	362.808	362.808	359.336	354.796	359.684	358.990
77.054	75.860	75.860	74.899	75.957	75.938	77.032	77.032	76.041	75.865	75.980	76.313
4.706	4.739	4.739	4.735	4.731	4.727	4.710	4.710	4.726	4.677	4.734	4.704
428.732	426.045	426.045	431.786	429.198	428.855	428.700	428.700	426.800	431.128	429.197	428.876
3422.230	4479.113	4479.113	6030.416	2281.305	4443.970	2078.838	2078.838	3147.580	4710.627	949.441	3314.348
1294.309	1544.091	1544.091	1620.668	1366.908	1486.356	1005.657	1005.657	1259.423	1337.695	1081.420	1200.925
458.000	188465.852	185884.654	185693.461	186958.158	186707.986	458.800	188558.703	185809.777	185783.365	184989.635	186750.613
439.816	435.444	435.444	430.696	435.600	435.319	439.854	439.854	436.440	430.479	435.673	435.250
362.795	359.376	359.376	354.696	359.624	358.955	362.868	362.868	359.324	354.193	359.692	359.128
77.021	76.068	76.068	76.090	75.976	76.343	77.132	77.132	76.036	75.286	75.980	76.151
4.710	4.724	4.724	4.667	4.733	4.701	4.705	4.705	4.726	4.718	4.734	4.716
428.693	426.885	426.885	431.148	429.197	428.909	428.770	428.770	426.795	431.574	429.197	429.046
2333.097	3399.554	3399.554	4965.138	1201.508	3565.930	2042.513	2042.513	3111.603	4681.066	913.428	3278.394
1060.265	1313.335	1313.335	1391.577	1135.434	1255.049	997.853	997.853	1251.723	1330.071	1073.703	1193.216
458.100	188537.475	185816.938	185635.137	186962.146	186663.142	458.833	188559.133	185819.035	185745.318	184990.990	186717.160
439.784	435.424	435.424	430.478	435.609	435.229	440.154	440.154	436.709	411.706	435.676	428.856
362.754	359.366	359.366	354.573	359.633	358.898	362.905	362.905	359.280	354.485	359.695	358.890
77.027	76.059	76.059	75.904	75.976	76.331	77.144	77.144	75.428	74.221	75.981	74.966
4.709	4.725	4.725	4.671	4.733	4.702	4.698	4.698	4.716	4.701	4.734	4.721
428.765	426.749	426.749	431.231	429.197	428.895	428.861	428.861	426.430	431.178	429.197	428.873
2296.774	3363.576	3363.576	4929.638	1165.499	3529.996	2029.797	2029.797	3099.019	4669.263	900.823	3266.026
1052.465	1305.633	1305.633	1383.891	1127.721	1247.329	995.119	995.119	1249.369	1327.332	1071.002	1190.573

TABLE AP 2-1 (Sheet 1 of 2)
ABBREVIATIONS

<u>ITEM</u>	<u>TERM</u>	<u>ITEM</u>	<u>TERM</u>
ac	Alternating current	F	Fahrenheit, thrust
Act	Actuator	FCI	Flight Critical Items
APS	Auxiliary Propulsion System	Flt	Flight
ASI	Augmented Spark Igniter	ft	Feet
attach	Attach	FM	Frequency modulation
Aux	Auxiliary	FTC	Florida Test Center
Btu	British thermal unit	Fwd	Forward
Bgr	Bridge gain ratio	GG	Gas generator
Cfm	Cubic feet per minute	GH2	Gaseous hydrogen
Contr	Control	GIS	Ground Instrumentation System
cps	Cycles per second	GN2	Gaseous nitrogen
db	Decibel	gpm	Gallons per minute
dc	Direct current	GSE	Ground support equipment
DDAS	Digital Data Acquisition System	He	Helium
deg	Degree	Hg	Mercury
DER	Digital Events Recorder	H ₂ O	Water
Disch	Discharge	hr	Hour
DNA	Data not available	hp	Horsepower
D/O	Dropout	Hyd	Hydraulic
DPF	Differential Pressure Feedback	Hz	Hertz
EBW	Exploding bridgewire	in.	Inch.
ECC	Engine Cutoff Command	IP&CL	Instrumentation Program and Component List
ECO	Engine Cutoff	I _{sp}	Specific Impulse
EDS	Emergency Detection System	IU	Instrument Unit
E/I	External/Internal	K	Kilo = 1,000 or 10 ³
EMI	Electromagnetic Interference	Kc	Kilocycle
EMR	Engine Mixture Ratio	KSC	Kennedy Space Center
ESC	Engine Start Command	lbf	Pounds force
		lbm	Pounds mass

TABLE AP 2-1 (Sheet 2 of 2)
ABBREVIATIONS

<u>ITEM</u>	<u>TERM</u>	<u>ITEM</u>	<u>TERM</u>
LH2	Liquid Hydrogen	Refl	Reflected
Loc	Location	Reg	Regulator
LOX	Liquid oxygen	RF	Radio Frequency
M&A	Manufacturing and Assembly	RMR	Reference Mixture Ratio
ms	Millisecond	RPM	Revolutions per minute
MSFC	Marshall Space Flight Center	RSS	Root sum square
NASA	National Aeronautics and Space Administration	SAI	Special Attention Items
N/A	Not applicable	SCC	Standard cubic centimeter
NPSH	Net positive suction head	SCI	Standard cubic inch
PCM	Pulse code modulation	scim	Standard cubic inch per minute
PDT	Pacific Daylight Time	scfm	Standard cubic foot per minute
pf	Picofarad	sec	Second
Posit	Position	sps	Samples per second
pps	Pulses per second	STC	Sacramento Test Center
Press	Pressure	sw	Switch
psi	Pounds per square inch	Syst	System
psia	Pounds per square inch, absolute	T ₀	Simulated liftoff
psid	Pounds per square inch, differential	TAN	Tangential
psig	Pounds per square inch, gauge	Temp	Temperature
PST	Pacific Standard Time	T/M	Telemetry
Pt	Point	TP&E	Test Planning and Evaluation
P/U	Pickup	Vac	Volts alternating current (100 vac)
PU	Propellant Utilization	V	Volts
Pwr	Power	VCL	Vertical Checkout Laboratory
R	Rankine	vdc	Volts direct current
RACS	Remote Analog Checkout System	Vib	Vibration
RAD	Radial	vswr	Voltage standing wave ratio
		W _T	Total flowrate

Distribution List

DISTRIBUTION LIST

HUNTINGTON BEACH (A3)

K010 Senior Director - Saturn/Apollo Programs
KW00 Director - Saturn System Development
K100 Director - Saturn Development Engineering
KYC0 Manager - Saturn Program Production
HAAA Manager - Vehicle Flight Readiness
KWA0 Supervisor - Saturn System Development
(Rocketdyne) via J. Boyde (KCDE)
KN00 Deputy Chief Design Engineer - Saturn Development
KA00 Chief Engineer - Mechanics & Reliability
KAB0 Branch Chief - Structural Mechanics
KAC0 Branch Chief - Flight Mechanics
KC00 Chief Engineer - Propulsion
KCB0 Branch Chief - Propulsion Analysis
KCBC Propulsion Performance and TP&E - Analysis
KCC0 Deputy Branch Chief - Propulsion Design
KCD0 Branch Chief - Propulsion Test
KCDE Chief Engineer - Saturn Electronics
KDBA Section Chief - Electronics TP&E
KDCA Branch Chief - Electronic-Stage Design
L110 Chief - Engine Data Reduction Engineering
KEC0 Branch Chief - Computing Engineering
KADO Branch Chief - Reliability Engineering (2)
KF00 Chief Engineer - Vehicle Checkout Laboratory
KKB0 Project Engineer - Test
KKBA Assistant Project Engineer - Test Special Products
KKBJ Assistant Project Engineer - Test
5284 Library
KEBG Records

S-IVB TP&E COMMITTEE MEMBERS (A3)

AFD3 Materials Research/Production Methods
KBDB Structural Mechanical
KCBC Propulsion Performance and TP&E
KDBA Electronics
KKBJ TP&E - Static Test

PROPELLANT UTILIZATION PANEL (A3)

KKBH PU Panel Chairman - TP&E

FLORIDA TEST CENTER (A41)

HE00 M. F. Cooper
KOCO H. T. Gardner (2)
KKG0 R. S. Spain
KKG0 H. H. Nichols

DISTRIBUTION LIST (Continued)

SACRAMENTO TEST CENTER (A45)

KKHO R. J. Mohr (2)
KKHO C. E. Ausley

MANNED SPACE CENTER (A57)

K010 R. A. Ammons

MARSHALL SPACE FLIGHT CENTER (A61)

KBDB W. E. Naymola (3)

NASA/MARSHALL SPACE FLIGHT CENTER

H. S. Garrett (17)
TP&E - Files (5)