CONTRACT REQUIREMENTS	CONTRACT ITEM	MODEL	CONTRACT NO.	DATE
Exhibit E, Par. 5.1	55	LEM	NAS 9-1100	1/15/63

TYPE II DATA

Primary Code 910

REPORT

LED-2-4'B'

Rev. 15 January 1964

LEM REQUIREMENTS FOR THE STATIC TEST STOR AT AME

CODE 26512

AMR Facilities Committee

PREPARED BY: ETS E. T. Barron, Chairman

T. H. Moorman

M. H. Dandridge

J. Walsh

REVISIONS

DATE	REV. BY	REVISIONS & ADDED PAGES	REMARKS
1/15/64	E	COMPLETE REVISION	
		·	
	-		

This document contain

The facilities planned in reference (a) for the Static Test Site at AMR for acceptance firing the IEM propulsion subsystem are adequate, with the exception of the Static Test Site control building; which is marginally adequate for housing the control equipment. The equipment required for the checkout operation at this site is included in this report, with layouts of the equipment in the planned buildings for the site.

Code 26512

Eng-23A

ABSTRACT

The facilities planned for the Static Test Site at AMR for acceptance firing the LEM propulsion subsystem are adequate, with the exception of the Static Test Site Control Building; which is marginally adequate for housing the control equipment. The equipment required for the checkout operation at this site is included in this report, with layouts of the equipment in the planned buildings for the site.

REFERENCES

- a. MSC-AMR Operations Criteria for Design MSC Static Test Facility Preliminary. 11 Dec 1963
- b. GAEC Report No. LED-2-2 Technical Criteria for Altitude Simulation System for Apollo LEM Test Facility, NASA, MSC Test Area, WSMR 17 June 1963.
- c. U.S. Army Engineer District, Albequerque Corps of Engineers Albequerque, New Mexico Specifications for Construction of LEM Test Facilities, NASA/MSC WSMR, New Mexico Specfication #ENG (NASA) 29-005-64-3 Amendment #4 "Altitude Simulation System" 12/27/63.
- d. U.S. Army Engineer District, Albequerque Corps of Engineers, Albequerque, New Mexico. "Specifications for Altitude Simulation Chamber LEM Test Facilities, NASA, MSC-WEMR, New Mexico" 11/1/63.

Eng-23A

REFERENCES

- a. MSC-AMR Operations Criteria for Design MSC Static Test Facility Preliminary 11 Dec 1963
- b. GAEC Report No. LED-2-2 Technical Criteria for Altitude Simulation System for Apollo LEM Test Facility, NASA, MSC Test Area, WSMR -17 June 1963.

Code 26512

Eng-23A

Code 26512

Eng-23A

CONTENTS

Sect	<u>ion</u>	Page
1.0	INTRODUCTION	1
2.0	DISCUSSION	1
2	.1 General Requirements	1
2	.2 Equipment Required at the Static Test Site	2
2	.3 Special Requirements	3
3.0	TABLES OF REQUIRED EQUIPMENT	
3	.1 Fluid Systems GSE	4
3	.2 Handling and Transportation GSE	5
3	.3 Electrical GSE	6
4.0	SITE BUILDING LAYOUTS	
4	.1 Concept Drawing-Test Stand	7
4	.2 Concept Drawing - Test Stand	8
4	.3 GSE and Transfer Building	9
4	.4 Control Room	10
APPE	NDIX'A' - Technical Criteria for the Atlantic Missile R Altitude Simulation System.	lange
1.0	SCOPE	Al.
2.0	DESCRIPTION OF EQUIPMENT	Al
3.0	DIFFUSER-EJECTOR PERFORMANCE REQUIREMENTS	АЗ
4.0	ALTITUDE REQUIREMENTS	A 6
5.0	SYSTEM REQUIREMENTS	A 6

CONTENTS - continued

	rage
Section	
APPENDIX'B' - Reaction Control Subsystem Engine Parameters	
1.0 INTRODUCTION	Bl
2.0 REACTION CONTROL SUBSYSTEM	B1

1.0 INTRODUCTION

Static firing of the LEM engines utilizing each complete LEM will be performed as part of the prelaunch acceptance tests at AMR to insure proper operation of the LEM system and the propulsion subsystem. LEM requirements for the Static Test Site to perform these tests have been summarized and are presented herein. The technical criteria for the required altitude simulation system and engine parameters for the ascent and descent engines are presented in Appendix 'A'. Engine parameters and data which affect the design of a separate exhauster or collector system for the reaction control subsystem are presented in Appendix 'B', in the event that the RCS engines are acceptance fired at the Static Test Site.

It appears most desirable that the equipment, facilities, and methods developed for use at WSMR in the development program be duplicated where possible and used at AMR for the acceptance tests of the propulsion and reaction control subsystems. This is the philosophy which has been used in determining the facilities and equipment required at the Static Firing Site at AMR.

2.0 DISCUSSION

2.1 General: The requirements for the LEM at the Static Test Site at AMR are comprised of the equipment required to perform the acceptance tests of the propulsion subsystem, the services required for the equipment and tests, and the facilities required at the site for performance of the tests. The acceptance tests currently planned to be conducted at the LEM Static Test Site include tests on the ascent and descent engines with all subsystems operating which are in the ascent or descent engine firing loop. For example, the N & G and S & C subsystems will be operating during the descent engine firing since signals from these subsystems control the thrust and gimballing of the descent engine. The reaction control subsystem may be acceptance tested at the Static Firing Site. The need for hot firing tests of the RCS at the Static Firing Site has not been completely defined at this time. possibility does exist, however, that the RCS flight nozzles cannot be adequately acceptance fired at sea level. There is also the possibility of a conflict in scheduling the use of the hypergolics building between the currently planned space programs at AMR. For these reasons, this report makes provisions for firing the RCS at the Static Test Site. The equipment required for the RCS has been included in the equipment lists and on the layouts.

> There is a potential need for a collector system or a separate exhauster system for each RCS quad if the RCS is fired in the altitude chamber of the Static Test Site. One of these systems

2.0 DISCUSSION

2.1 General - continued

would be required to prevent the corrosive unburned gases from damaging the ascent stage of the LEM vehicle during firing. An exhauster system would be required if the RCS was fired at altitude. Firing the RCS at sea level would not require an exhauster system, but would require a collecter system for the unburned corrosive gases.

The site plan presented in reference (a) has been reviewed to compare the facilities planned with those required for the planned acceptance tests. The facilities described in reference (a) are sufficient for the tests planned at the Static Test Site. A conceptual layout of the site appears on figure 1.2, with the servicing equipment located in the vicinity of the altitude chamber.

2.2 Equipment Required at the Static Firing Site

Fluid Systems GSE

The fluid system equipment listed in table 3.1 is required for servicing the propulsion and reaction control subsystems, and for checkout prior to actual engine firing. This equipment will be located on the pad adjacent to the altitude chamber as shown on figure 4.2.

Handling and Transportation GSE

The equipment listed in table 3.2 is required for transporting and handling the ascent stage, descent stage, and mated LEM at the Static Test Site. A crane or gantry with a 10-ton capacity will be required for handling the mated LEM vehicle.

Within the altitude chamber there need be only two positions for supporting the LEM; these are: (1) Support of the mated ascent and descent stages for descent engine firing; (2) Support of the ascent stage alone for ascent engine and/or reaction control subsystem operation. A smaller crane with a 3 ton capacity will be required for installing and removing equipment and the LEM support mounts. This crane must have access to the inner periphery of the altitude chamber.

Electrical GSE

The equipment listed in table 3.3 will be required for the control of the engine firing. Most of this equipment is similar to that required at WSMR for controlling engine firing during propulsion development tests. The IFM's at AMR, however, will contain complete subsystems which will not be used in the early development tests at WSMR. The

2.2

Equipment Required at the Static Firing Site

Electrical GSE - continued

GSE listed in table 3.3 has been laid out in the control room of the Static Test Site (figure 4.4) and will operate by utilizing as much as possible the actual LEM engine controls and related subsystems.

The facility control equipment (TV control station, altitude simulation control station, etc.) has also been laid out in the area allotted for the LEM control room (Figure 4.4). It should be noted that the area has been completely utilized and does not provide for any growth of planned equipment. An additional 300 square feet is desirable to allow for additional equipment or possible growth of currently planned equipment.

PACE downlink will be used for data acquisition. A certain number of critical parameters will, however, be hardlined to the control building for monitoring during firing. The instrumentation readout equipment for this purpose has been laid out in Figure 4.4. The PACE carry-on equipment will be located either inside the LEM vehicle or adjacent to the LEM within the altitude chamber. The data interleaver will be located in the transfer building, as shown in figure 4.3.

2.3

Special Requirements: Altitude simulation is required for acceptance tests of the LEM propulsion subsystem. The technical criteria for this required altitude simulation system are described in Appendix A of this report and are very similar to that required for WSMR (presented in reference (b)). Also, see (c) and (d).

It is necessary that the lower end of the ascent engine skirt fit into the diffuser at the bottom of the altitude chamber. This may require an extension to the altitude chamber diffuser since the ascent stage will sit above the diffuser (due to the fixed supports). This extension should bridge the gap between the lower end of the ascent engine and the diffuser.

Within the altitude chamber external power will be used to power the LEM system. Power requirements will include 28 volt DC and 105/125 volts AC,60 cps, 10.

Code 26512

2.0 DISCUSSION

2.2 Equipment Required at the Static Firing Site

Electrical GSE - continued

GSE listed in table 3,3 has been laid out in the control room of the Static Test Site (figure 4.4) and will operate by utilizing, as much as possible, the actual LEM engine controls and related subsystems.

The facility control equipment (TV control station, altitude simulation control station, etc.) has also been laid out in the area allotted for the LEM control room (Figure 4.4). It should be noted that the area has been completely utilized and does not provide for any growth of planned equipment. An additional 300 square feet is desirable to allow for additional equipment or possible growth of currently planned equipment.

PACE downlink will be used for data acquisition. A certain number of critical parameters will, however, be hardlined to the control building for monitoring during firing. The instrumentation readout equipment for this purpose has been laid out in Figure 4.4. The PACE carry-on equipment will be located either inside the LEM vehicle or adjacent to the LEM within the altitude chamber. The data interleaver will be located in the transfer building, as shown in figure 4.3.

2.3 Special Requirements: Altitude simulation is required for acceptance tests of the LEM propulsion subsystem. The technical criteria for this required altitude simulation system are described in Appendix A of this report and are very similar to that required for WSMR (presented in reference (b)).

It is necessary that the lower end of the ascent engine skirt fit into the diffuser at the bottom of the altitude chamber. This may require an extension to the altitude chamber diffuser since the ascent stage will sit above the diffuser (due to the fixed supports). This extension should bridge the gap between the lower end of the ascent engine and the diffuser.

Within the altitude chamber external power will be used to power the LEM system. Power requirements will include 28 volt DC and 105/125 volts AC,60 cps, 10.

				TAN BOUTPART	,	STATEC FIXING PACILITY - AME			•	
	e e	AREA: GSE & TRANSFER BUILDING	2	TYPE	PLUEDO	POSSESS PROCESSES	몺	SIZE	5	A. A
	MARKE	mABT.R 3.1	BEG.D	DESTALL.	0 0 0		#	2	<u> </u>	
		- 1	1	West 19	1, 1, 1, 1	120/208 V AC. 36, 4 Wire	9	6, 10,	3000	6000 pai Helium Source
	430-62160	Checkout Unit - Propulsion	1		Holina Holina		. 17	. †		
	430-62180	RCS, Checkout Chart	4			115 V AC, 28 V DC	36	181	_	
	1,30-621,60	I GE	1	Mobile	No Hydrox	W. Hvdrow 115 V AC, 28 V DC	9	10.01	2500	
	430-94063	RCS Fuel Servicing Unit	1		vacetic			- 1		
<u>.</u> į	1,000,000	Bos Orddizer Service Unit	1	Mobile	Triethano	115 V AC, 60 Cycle	وَ	2	2,700	
	430-94021	NCD CALLESCE CO.			Lamine, F2		7		250	
	430-62500	RCS Oxidizer, Transfer	٦	Mobile			ر ال	4		
	1,30-94060	Vapor Disposal Unit, Fuel	1	Mobile		480 V, 60 Cycle 30, 60 Amps			L	0 2000 pg1
_	430-94058	Fuel Ready Storage Unit	1	Mobile	, E	120/206 V AC, 30, 4 WATE	ي و		Ľ.	_
	430-94059	Oxidizer Ready Storage Unit	1.	Mobile	10 Car	Toolong V AC 60 Cycle. 36	1 0			
	430-64420	Control Unit, Fuel Ascent & Descent		MODILE	24	Ι.	72"	1 ₄₀ " 80"	2000	0
	430-94019	Service Unit Water Glycol	7	TOOL		208/220 V AC				-
		The Holling		Mohtle	Helium	115 V. 60 Cycle, 30 Amps	8 0	42" 34"		550 Reight with Bell Jar
	430-94003	Mass Spectrometer, L.D. nellum	-	Mobile	CE S	120/208 V AC, 36, 4 Wire.	9	18" 72"	5000	
	430-94009	Transier & Committeer, Lerran				28 v DC		+		1-4 OWN -4 0000
	ocorlo oc (Helim Booster Unit	7	Mobile	Water	221/480, 36, 4 Wire, 120/208	ঙ	001,09	800	O Boost hellum from cast but to that the
.	130-21055					30, 4 Wire	ŀ	à	5	
	79040-054	Helium Ready Storage Unit	-	Mob11e	Helium	0.16 Po	o y	00 00	- Boo	O (PONO Pully Loaded)
1	430-94002	Oxidizer Transfer & Condit. Unit	-	Mobile	Mtrogen	ABO V AC, 50 CYCLE, 30, 120		1	1	
						Ample	5	6, 10,	2000	0
	430-94008	Fuel Transfer & Condit. Unit	4	Mobile	Aerozine E	150/500 V AV.		_		
L			-		2	180 V AC. 60 Cycle. 36, 60 Amp	8	168"120"	000† "(_
	130-94061	Oxidizer Toxic Vapor Disposal		Mob 11e	٤	120/208 V AC. 36. 4 Wire	9	8, 1		O Flushing Fluids 2000 psi
	430-94070	Engine Decontamination Unit	-	Moh 1 a	Witrogen	120/208 V AC, 60 Cycle, 30	<u>œ</u>	18		150
	09449-064	Oxidizer Propulsion Fanel		Mobile	+ 6	115 V.AC, 60 Cycle	9.	<u>.</u>	7.	0
	430-62520	Cart, Oxtaires frame a see,			Frieth.		7		1.1	S
	130-621180	Cart. Fuel Flush & Purge, RGS	ы	Mobile	No + Hydo	No + Hydr- 115 V AC & 28 V DC	٥		┸	2
L	200				oxyacetic		1	+	+	Data Not Available
	430-64220	Helium Pressure Distribution Unit	_					H	$\left\{ \cdot \right\}$	
								\dagger	+	
			_					+	+	
			_				1	\dagger	+	
							\downarrow	+	+	
Ţ							T	+	+	
L			_					+	-	
L			1				Ţ	-	-	
<u>_</u>				-	-		Ŀ		-	
										meder LED-2-4'B'

ENCIS

PARC MUMBER			LIEN BOUT	HOGET -	STATES FIRTHS PACTLLTY - AME				
PARE	AREA: STATIC FIRING STAND								
		0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	TTPE OF TREDITE.	FLUTO G. 9	POWER ERQUINED	is		(Bg.)	
	Rocat Of cond Prome	-	Pfynd			* 101 91	191	15000	15000 Summerta Vehinies (LIM) durisa static Seine bank
	(Inside charber)		TYCA			1	+		
	Platform Set	1	Fixed			71 71	1751175"	1500	1500 Allows personnel to reach lest access areas abilities
	(workstand, inside chamber)								. 1
	D/S Hard Mount Adapter	4	Removable			,0†	#O. 36"	001	400 Connects D/S to thermo expension & Missilgenest's
	(inside chamber)								- 1
	A/S Hard Mount Adapter	-	Removeble			20.	250 250"	88	Connects A/S to thermo expansion & Missilgument
	(inside chamber)					- i			Joint.
	Expansion & Misalignment Adapter	-	Removable			36.	18" 10"	8	Compensates for thermo expansion of test
	(inside chamber)					4	1		vehicle and test stand
420-13450	Door Access - Docking Hatch	-	Removable			35.4"Dia	7	R	Substitute hatch for checkout lines when in
	(inside chamber)						1		static firing chamber,
420-13250	A/S Transporter		Mobile.			134 1		3200	ransports A/S to site.
420-13500	D/S Transporter	1	Mobile			10,012,8	8, 18	3000	Transports D/S to site
420-13100	A/S Hoist Sling		Moveble				3,108	500	Lifts A/S into static firing stand
420-13600	D/S Hoist Sling	1	foveble			Ι.,	.96.1	100	Lifts D/S into static firing stand
420-13260	Hoist Sling Transporter Cover	1	Mobile			13	1925 191	09	Afts transporter cover off transporter when
									loading or unleading lak.
				٠		_			
							1		
			Î			-	1		
						+	+	1	
		1				4	1		
						_			
						-	ŀ		
								l	
						-	+	T	
						-	1		
								T	
			T			1	‡	T	


--- 1/15/63

			LLZ: EQUITMENT		- STATIC PINING NACILITY - AMR		1		
PARE	AREA: CONTROL BUILDING	30 REC 10	TYPE	TUTE TEQ.D	POTER REQUIRED	l į		Wr. (1bs.)	REMARKS
Figure 4.4	NOMENCLATURE TABLE 3.3				115 V. 60 Cycles. 28 V DC	:: 'S	W D 6' 2.5'		
4 410-64520 5 410-64560	Oxidizer Control Station	4-1				50"	24" 30"		
9 410-62840	Pressurization Control Station		pag LJ						
15 410-62800	RCS Progremmer	1	Fixed		115 V, 60 Cycles 5KVA, 28 V Dd	9	6.2.5	3000	
000003_01.1 8	Engline Firing Control Station	F	Fixed	1	- International Control				
	Engine Programmer	1	Fired			18	24" 30"		
	Test Conductor Control Station	-	Fixed	±			Q.		
1 410-12040	Instrumentation Monitor Panel	7							
						+			
		1							
						+-			
						-	-		
		+				-			
						+	+		
						-	+		
		1							
		-				-			
					•	+			
						+	+		
		-	1				+-		
		+		4					
							-		negation of the state of the st
						1	+		
				-		+			
		-		+-			 		
				\		-			
									aeroer LED-2-4'B'
						1 6			DATE 1/15/64

GRUSSAN AIRCRAFT ENGINEERING CORPORATION

ENCUS

GRUMMAN AIRCRAFT ENGINEERING CORPORATION



QB 728


21-04

Report LED-2-4¹E Date 1/15/64

<u>6</u> **3** AMR STATIC TEST SITE CONTROL BLDG <u>জ</u> **®** F16.4.4 09549-014 410-64520 S-OVIDIZER CONTROL STATION
S-ALT SIMULATION CONTR STA
T-ENGINE PROGRAMMER
S-VEHICLE CONTROL STATION
T-PRESSURIZATION CONTR STA
TO-RC S-CONTR-STA * FACILITY EQUIPMENT

GRUMMAN AIRCRAFT ENGINEERING CORPOBATION

01 201



TYPE II DATA

REPORT

LED-2-4'B'

DATE: 15 January 1964

APPENDIX A

TECHNICAL CRITERIA FOR THE

ATLANTIC MISSILE RANGE

ALTITUDE SIMULATION SYSTEM

CODE 26512

Propulsion System @


PREPARED BY:


CHECKED BY:
M. H. Dandridge
E. Scicchitano

R. M. Carbee

REVISIONS

DATE	REV. BY	REVISIONS & ADDED PAGES	REMARKS
	·		






٠	SCOPE
1.	SCOPE

- 1.1 Scope: These criteria establish the requirements for the design and fabrication of the altitude simulation system at the Atlantic Missile Range (AMR), Cocoa Beach, Florida.
- 1.2 The altitude simulation system shall be designed in modular fashion for the Ascent and Descent Propulsion stages at AMR. The system shall consist of four major subsystems:
 - (a) The exhaust system, including altitude chamber, diffuser, subsonic elbow section, and ejector stages.
 - (b) The steam generator, to provide drive media for the ejector stages.
 - (c) The propellant system, consisting of propellant tankage, fill and feed control equipment for the system propellants and water, gas storage and regulation equipment.
 - (d) The control system, which controls, monitors and indicates the performance of the overall simulation system equipment.
- 1.3 There shall be a Vertical Test Stand at AMR capable of accommodating the LEM vehicle. The test stand altitude chamber shall be sized to accommodate the entire LEM system.


2. DESCRIPTION OF EQUIPMENT

- Altitude Chamber for AMR: The altitude chamber for the LEM vehicle shall be sized to accommodate the entire configuration less the lunar landing gear. Two GSE fixtures shall be provided. One fixture will be required for the Descent engine firing in the mated LEM configuration. The second fixture will be required to mount the ascent stage demated for the ascent engine firing test. The AMR altitude chamber should be interchangeable and compatible with the WSMR altitude chamber.
- Diffuser for MR: The basic diffuser design shall be of the center body type and shall be installed between the altitude chamber and subsonic elbow section and shall be concentric with the engine exit cone. The diffuser must perform two distinct functions. The first is to provide minimum pressure in the altitude chamber and the second is to accomplish a maximum pressure rise so as to minimize the pumping requirements of the steam ejector system through, out the operating range requirements of the rocket engines. The diffuser inlet flange shall be attached directly to the altitude chambers.



- 2.2.1 Diffuser Interchangeability Requirements: The diffuser shall be interchangeable with engine vendor static facilities and the WSMR static facility.
- Sub-Sonic Elbow Section for AMR: The sub-sonic elbow section shall be installed downstream of the diffuser. This section shall have a bend or a long radius elbow to turn the gases from the vertical to the horizontal plane into the steam operated ejectors. The sub-sonic elbow section shall be protected by a water cooling jacket. The sub-sonic elbow section inlet flange shall mate with the descent and ascent stage diffuser.
- 2.4 Steam Ejectors for AMR: The Steam Ejector shall be compatible and interchangeable with the engine manufacturers facilities and the WSMR facility.
- Steam Generation for AMR: A LOX-Alcohol steam generator shall be provided to drive the steam ejectors. It shall be rated to supply the steam quantity and quality required to operate the altitude simulation system. The steam generation system selected should be interchangeable with the WSMR facility.
- Steam Generator Propellant Run and Storage Tanks for AMR: The propellant run tanks shall have sufficient capacity to perform two (2) descent stage acceptance tests. Considerations in tankage capacity shall include boil-off, decomposition and other losses. The propellant storage tanks shall have sufficient storage capacity for two (2) descent stage acceptance firings of 45 seconds duration. Provisions for filling the propellant run and storage tanks by truck delivery shall be included.
- Water Run and Storage Tanks for AMR: The water run tanks shall have sufficient capacity to supply all the water required (cooling water for diffuser, injection water, etc.) to perform two (2) descent stage acceptance test firings. The water storage tanks shall have sufficient capacity to supply all the water required to perform two (2) acceptance test firings.
- 2.8 Pressurization System: The propellant and water transfer shall be made with a suitable nitrogen pressurization system. System pressure and line sizing will be a function of steam generator requirements.
- 2.9 Control Systems for AMR: Remote manual and automatic starting and stopping of the steam generation system shall be provided. The controls and instrumentation shall be located at one panel in the

PEPORT



operation. The control system shall include all necessary safety monitoring provisions so that vehicle and system are protected upon steam or power failure. The control system shall be simple, with minimum number of manual operations required. Provisions for the replacement of components, adjustments, and other required "trouble-shooting" shall be incorporated into the design so that they may be readily accomplished.

3. DIFFUSER-EJECTOR PERFORMANCE REQUIREMENTS

3.1 Descent Engine Parameters

3.1.1 The Diffuser-Ejector System shall operate, to the conditions prescribed in these specifications with the following engine parameters:

Thrust (Maximum)	10,500 pounds +10% - 3%
Thrust (Minimum)	1,050 pounds +10%
I at Minimum Thrust	-285 sec.
I at Maximum Thrust	305 sec.
Gimbaling	<u>+</u> 6°
Gimbal Point Location	Nozzle Throat
Chamber Pressure at Maximum Thrust	113 psia
Chamber Pressure at Minimum Thrust	11.3 psia
Nozzle Exit to Throat Area Ratio	*50
<pre>% Bell (Based on Equivalent of 15° Half Angle Conical Nozzle)</pre>	73
Exit I.D.	58 inches
Exit O.D.	60 inches
Length (Gimbal Point to Nozzle Exit)	69.32 inches

3.1.2 The composition and flow rates of the engine exhaust gases cover the following ranges:

COMPOSITION	MASS FLOW	/ #/SEC
	Max.	Min.
H ₂	. 668	0.0690
CO	1.190	0.1236
co2	7.859	0.8110
н ₂ о	9.318	0.9749
N ₂	15.366	1.586 0.0356
Total	34.400	3.6000

3.1.2.1 The following physical and thermodynamic properties of the exhaust gas shall be used in the analysis of this Diffuser-Ejector System.


> Ratio of specific heats (Frozen Gamma at £ = 2) 1.245 Specific heat -----39 BTU/lb/°F Total Temperature _____5125 °F

- 3.1.3 The descent engine will have capabilities to throttle from the maximum flow rate of 34.40#/sec. to the minimum flow rate of 3.60#/sec. in a period of one second. Minimum flow rate to maximum flow rate throttling is also accomplished in a period of one second. Intermediate throttling conditions will be accomplished in proportional amounts of time.
- 3.1.4 The exhaust nozzle exit static pressure will vary from a maximum of 0.163 psia to a minimum of 0.016 psia, the lower pressure occurring with the lower chamber pressure in the design of the system.
- 3.1.5 The descent engine nozzle has a collapsing pressure limitation of 0.05 psi imposed as a differential pressure across the radiation cooled skirt.
- 3.1.6 Duration of Test Firing: The total duration of test firing the descent propulsion system at AMR shall be 45 seconds.
- 3.2 Ascent Engine: The ascent engine operates within the following design parameters:
 - a) Expansion ratio = 40:1; Exit diameter of nozzle = 31.27 inches; Total length of ascent rocket engine = 51 inches.

DATE

- b) Chamber pressure; steady state at nominal thrust = 100 psia.
- c) Thrust after 5 sec at nominal engine inlet pressure and propellant temperature = 3,500 ± 2.5%.
- d) Thrust; end of duty cycle operating time = 3500 + 7% 2.5%.
- Mixture Ratio (Wo/Wf); 1.6 + 1.7%.
- f) Isp minimum, max. thrust end of duty cycle operating time = 306.34 sec. (36 value) 1b.f sec
- g) Oxidizer Nitrogen Tetroxide (Nooh) conforming to specification MIL-P-26539.
- h) Fuel Specification MIL-P-26539. An actual mixture by weight of Hydrazine and unsymmetrical dimethylhydrazine (UDMH) conforming to Specification MIL-P-27402.
- i) Start Characteristics: The rocket engine will develop 90% rated thrust within 0.200 seconds after onset of electric signal.
- j) Shutdown Characteristics: The rocket engine will accomplish thrust decay to 10% rated thrust within 0.200 seconds after receipt of command signal.
- k) Impulse Repeatability: The rocket engine start and shutdown. characteristic shall be repeatable to provide a predictable total impulse accuracy of ± 35 lb. sec.
- 1) Stability: The transient starting combustion chamber pressure will not be greater than 110% of the nominal rated combustion chamber pressure. There will be no cyclic or periodic chamber pressure oscillations which exceed ± 2%, after start and during the period of effective steady-state operation.
- m) Starting: Normal starting shall be accomplished at the nominal thrust level.
- Thrust Vector Alignment: The thrust vector shall pass within a cylinder of 0.125 in radius about the engine reference line.
 - NOTE: 1) The thrust vector location is defined as the spatial position of the resultant reactive force of the rocket engine during operation.
 - 2) The engine reference line is defined as a line perpendicular to a plane established by the thrust mount surface and passing through the centroid of a circle defined by the thrust mount locations.

DATE



- a) The total duration of test firing the Ascent propulsion system. at AMR shall not exceed 20 seconds.
- 3.2.2 The Ascent engine nozzle has a collapsing pressure limitation of 0.1 psi imposed as a differential pressure across the engine skirt.
- 4.0 ALTITUDE REQUIREMENTS

These requirements are applicable to both the descent and ascent propulsion stages.

- a) Starting at Pc (max.) 105,000 feet (minimum).
- b) Running at Pc (max.) 105,000 feet (minimum).
- c) Running between Pc (max.) and Pc (min.) Nozzle full (minimum).
- d) Restarting at max. Pc: 105,000 feet (minimum)
- e) Non-operative periods (vacuum soak) 105,000 feet (minimum).


5.0 SYSTEM REQUIREMENTS

- a) The system shall be of the type or one similar that has been in successful operation for a minimum of one year and which will require no development.
- b) The system shall be designed to have a usable life of five (5) years except for those portions that are exposed to excessive corrosion or erosion in which case minor periodic maintenance shall be required.
- c) The exhaust system shall provide means to prohibit recirculation of rocket exhaust gases over the test vehicle during start, normal operation, shut down and restarts.
- d) The system shall be capable of being placed in operation and attaining the desired altitude in 30 seconds maximum using the steam ejector.
- e) The system shall be designed to minimize the effect of exhaust gas toxicity. The atmospheric exhaust point shall be located to maximize natural dispersement of toxic fumes.
- f) The system shall not operate in vibration frequency ranges that will generate adverse noise problems or cause malfunction of the test vehicle other than those normally encountered in test vehicle operation.
- g) The system shall be designed to provide for safe shutdown in event of a test vehicle malfunction or electrical power failure without damage to test vehicle.

Code 26512



- h) The system shall be designed for minimum maintenance.
- i) The system shall be designed to be self-contained and independent of external facilities except for supporting utilities such as water, power, gas (inert) and a control center.
- j) The system shall be capable of performing two (2) descent stage acceptance test firings in a twelve (12) hour period.
- k) Manual control of the injection water used to cool the hot gases shall be provided to override the automatic system.
- 1) All materials shall be compatible with Nitric Acid for limited periods of time.
- m) The system shall be designed to an ambient pressure of 14.7 psia.
- n) The procurement of the Altitude Simulation System for AMR shall be from one Vendor who shall have the complete system responsibility for fabrication, installation, checkout and training of personnel to operate facilities.
- o) Diffuser, Ejector and Steam Generation system should be compatible and interchangeable with the Engine Manufacturers and the WSMR facilities.
- p) The Diffuser-Ejector system should be one unit sized for the descent engine. Such a diffuser will also accommodate the ascent engine.



CONTRACT REQUIREMENTS	CONTRACT ITEM	MODEL	CONTRACT NO.	DATE
Exhibit E, Par. 5.1	55	LEM	NAS 9-1100	1/15/63

REPORT

NO. APPENDIX B

DATE: 15 January 1964

REACTION CONTROL SUBSYSTEM ENGINE PARAMETERS

CODE 26512

Reaction Control Subsystem

PREPARED BY:

CHECKED BY:

S. Portegal

APPROVED BY:

O. S. Williams

REVISIONS

DATE	REV. BY	REVISIONS & ADDED PAGES	REMARKS	
	<u> </u>			
	<u> </u>			
-				

This document contains information affecting the national defense of the United States, within the meaning of the Espionage Laws, Title 18, U.S.C., Sections 793 and 794, the transmission or revelation of which in any manner to an unauthorized person is prohibited by law.



chambers each).

Thrust Chamber Characteristics

Steady State

1.0

2.0

2.1

2.2

INTRODUCTION

REACTION CONTROL SUBSYSTEM

Chamber Wall Temperature (Radiation

Engine Parameters

The RCS engine parameters and operating information required for the design of the Static Test Facility, including a

collector or separate exhauster system, are presented herein.

Thurst Chambers ----- 16 (4 clusters of 4

Fuel ----- 50/50 Mix N₂ H₄/(CH₃)₂

Cooled) ----- 2800°F
Chamber Material ----- Molybdenum

Oxidizer ---- No O4

Expansion Ratio (each chamber) ----- 40:1

Throat Diameter ----- .865 inches
Throat Area ----- .59 sq. inches

Exit Diameter ---- 5.47 inches

Exit Area ----- 23.6 sq. inches

Thrust ----- 100 lbs ±5%

Chamber Pressure ----- 90 psia

2.4

2.3

2.0	REACTION CONTROL SUBSYSTEM

2.2 Thrust Chamber Characteristics

Pulse Mode - continued

Average Chamber Pressure for a Minimum Pulse ----- 50 psia Average Flow Rate for a Minimum Pulse - .55 lb/sec Minimum Impulse Bit ----- .5 lb/sec ± .1 lb/sec

Exhaust Gases and Flow Rates: The composition and flow rates of the exhaust gases from one individual thrust chamber in a steady-state mode cover the following ranges:

Pulse Mode Duration ---- 500 seconds

Composition	Mass Flow Rate (#/sec)
N ₂	.1426
H ₂ 0	.1052
ОН	.00968
H ₂	.00201
œ	.0291
002	.0367
02	.0073
Н	.0003
	.33298 #/sec Total

The following are the physical and thermodynamics properties of the RCS exhaust gases.

Ration of Specific Heats ----- 1.30 Modecular Weight ----- 21.991 Specific Heat ----- .386 BTU/lb/°F Total Temperature ----- 5629°R

Tests Planned: Acceptance tests at AMR will consist of steady-state running and pulse mode operation simultaneously. The total firing time required for these planned tests will be 240 seconds. During the planned firing the maximum exhaust efflux will be 1.98 lbs/sec, based on four chambers steady-state and four chambers pulsing.