

(NASA-TM-78562) NASA/ARMY XV-15 TILT ROTOR  
RESEARCH AIRCRAFT WIND-TUNNEL TEST PROGRAM  
PLAN (NASA) 73 p CSCL 01C

N80-15067

00/05 46668  
Unclas

---

# NASA/Army XV-15 Tilt Rotor Research Aircraft Wind-Tunnel Test Program Plan

---

James A. Weiberg and Martin D. Maisel

---

March 1979

(NASA-TM-78562) NASA/ARMY XV-15 TILT ROTOR  
RESEARCH AIRCRAFT WIND-TUNNEL TEST PROGRAM  
PLAN (NASA) 73 p LIMIT NASA

X79-90154

00/98 17262  
Unclas

**NASA**  
National Aeronautics and  
Space Administration

United States Army  
Aviation Research  
and Development  
Command



---

# **NASA/Army XV-15 Tilt Rotor Research Aircraft Wind-Tunnel Test Program Plan**

---

James A. Weilberg, Ames Research Center, Moffett Field, California

Martin D. Maisel, Aeromechanics Laboratory, AVRADCOM Research and Technology Laboratories



National Aeronautics and  
Space Administration


**Ames Research Center**  
Moffett Field, California 94035


United States Army  
Aviation Research and  
Development Command  
St. Louis, Missouri 63166



NASA/ARMY XV-15 TILT ROTOR RESEARCH AIRCRAFT  
WIND-TUNNEL TEST PROGRAM PLAN


Prepared by:


  
James A. Weiberg  
Tilt Rotor Research Project Office



Martin D. Maisel  
Tilt Rotor Research Project Office

Approved by:

  
John P. Magee  
Deputy Manager, Tilt Rotor Research Project Office

  
LTC James H. Brown, Jr.  
Manager, Tilt Rotor Research Project Office

## TABLE OF CONTENTS

	<u>Page</u>
LIST OF TABLES . . . . .	vii
LIST OF FIGURES . . . . .	viii
1.0 PROGRAM SCOPE . . . . .	1
2.0 APPLICABLE DOCUMENTS . . . . .	1
3.0 MANAGEMENT AND TEST DIRECTION . . . . .	2
3.1 Project Manager . . . . .	2
3.2 Deputy Manager (Technical) . . . . .	3
3.3 Deputy Manager (Test and Operations) . . . . .	3
3.4 Test Director . . . . .	3
3.5 Test Engineers . . . . .	4
3.6 Project Control Officer . . . . .	4
4.0 OPERATIONS . . . . .	4
4.1 Schedule . . . . .	4
4.1.1 Ground tiedown tests . . . . .	4
4.1.2 Disassembly, inspection and shipment . . . . .	5
4.1.3 Reassembly and checkout . . . . .	5
4.1.4 Wind-tunnel test . . . . .	5
4.1.4.1 Installation and pre-test checkout . . . . .	5
4.1.4.2 Shake tests . . . . .	6
4.1.4.3 Test operations . . . . .	6
4.1.5 Post-test refurbishment . . . . .	7
4.2 Aircraft Preparation and Remote Systems . . . . .	7
4.2.1 Support system . . . . .	7
4.2.2 Remote control system . . . . .	8
4.2.3 Fuel system . . . . .	8
4.2.4 Hydraulic systems . . . . .	8
4.2.5 Electrical system . . . . .	9
4.2.6 Research instrumentation and data acquisition . . . . .	9
4.2.7 Computation and data reduction . . . . .	10
4.2.8 Configuration control . . . . .	10

	<u>Page</u>
5.0 PROGRAM SAFETY . . . . .	10
5.1 Systems Safety Analysis . . . . .	11
5.1.1 Pre-test analysis . . . . .	11
5.1.1.1 Loads and strength evaluation . . . . .	11
5.1.1.2 Dynamic stability . . . . .	11
5.1.2 Simulation and crew training . . . . .	11
5.1.3 Operation and monitoring procedures . . . . .	12
5.1.4 Fire protection . . . . .	12
5.1.5 Emergency egress system . . . . .	12
5.2 Viewing System . . . . .	13
5.3 Test Readiness Review . . . . .	13
6.0 SUPPORT REQUIREMENTS . . . . .	13
7.0 REPORTING AND DOCUMENTATION . . . . .	14
7.1 Test Plan . . . . .	14
7.2 Instrumentation Plan . . . . .	15
7.3 Systems Safety Analysis Report . . . . .	15
7.4 Wind-Tunnel Operating Hazard Analysis . . . . .	15
7.5 Failure Reporting . . . . .	16
7.6 Incident/Accident Reports . . . . .	16
7.7 Test Readiness Report . . . . .	16
7.8 Test Emergency Procedures . . . . .	16
7.9 Engine/Rotor Operations Checklist . . . . .	16
7.10 Test Report . . . . .	16
8.0 REFERENCES . . . . .	17
APPENDIX A — FUEL PURGING PROCEDURES . . . . .	18

## LIST OF TABLES

		<u>Page</u>
I	Available wind-tunnel strut arrangements . . . . .	20
II	Hydraulic power distribution . . . . .	21
III	Aircraft instrumentation . . . . .	22
IV	Wind-tunnel data requirements . . . . .	41
V	Wind-tunnel test responsibility . . . . .	46

## LIST OF FIGURES

		Page
3-1	Wind-tunnel test program management . . . . .	47
4-1	Wind-tunnel test schedule . . . . .	48
4-2	Aircraft schedule . . . . .	49
4-3	Ames facilities for assembly and test . . . . .	50
4-4	Wind-tunnel installation . . . . .	51
4-5	Rotor-wall clearance . . . . .	53
4-6	Hoisting arrangement . . . . .	54
4-7	Flight controls schematic . . . . .	55
4-8	Remote control console . . . . .	56
4-9	Wind-tunnel control room . . . . .	58
4-10	Aircraft fuel system schematic . . . . .	59
4-11	Aircraft/wind-tunnel interface, hydraulic/fuel systems . . . .	60
4-12	Aircraft hydraulic system schematic . . . . .	61
4-13	Aircraft electrical system schematic . . . . .	62
4-14	Data system block diagram . . . . .	63
6-1	Organizational structure of support elements . . . . .	64
6-2	Wind-tunnel staff organization . . . . .	65

NASA/ARMY XV-15 TILT ROTOR RESEARCH AIRCRAFT  
WIND-TUNNEL TEST PROGRAM PLAN

James A. Weiberg  
~~Ames~~ Research Center

and

Martin D. Maisel  
~~Ames~~ Research Center  
and  
Aeromechanics Laboratory  
AVRADCOM Research and Technology Laboratories

## 1. PROGRAM SCOPE

The joint NASA/Army XV-15 Tilt Rotor Research Aircraft Project involves design, fabrication, and flight test of two essentially identical aircraft. The overall plan to implement this program is documented in references 1 and 2. A Test and Evaluation Plan (ref. 3) outlines the tests to ensure that the XV-15 Tilt Rotor Research Aircraft will meet the requirements of the Program Plan and the Contract Model Specification and Statement of Work. As part of this plan, one of the aircraft will be tested in the ~~Ames~~ 40 x 80 Foot Wind Tunnel. These tests are to provide an initial assessment of the aerodynamic characteristics, structural loads, and rotor/pylon/wing dynamics in a simulated flight environment for correlation with estimated values. The results will be used for evaluation of the adequacy of production methods prior to flight tests. The tunnel speed capability includes all critical conversion and high blade load areas. The tests will also serve to verify the functional operation of the aircraft systems and on-board instrumentation in a flight environment.

Additionally, if problem areas are later encountered during the subsequent flight tests, or if it is desirable to investigate areas that can be more safely accomplished in the wind tunnel, the aircraft can again be put into the wind tunnel.

The purpose of this document is to define the management structure, operational plan, support requirements and responsibilities, safety provisions and reporting requirements for conduct of the wind tunnel tests and to relate the tests to other phases of the program.

## 2. APPLICABLE DOCUMENTS

The following documents, to the extent applicable, are made a part of this plan. Latest revisions of the reference documents will apply.



1. ~~Ames~~ Research Center, Guide for Planning Investigations in the ~~Ames~~ 40 × 80 Foot Wind Tunnel.
2. Planning Rotor Tests for the 40 × 80 Foot Wind Tunnel.
3. AHB 1750-1, ~~Ames~~ Research Center, Operations Safety, 40 × 80 Foot Wind Tunnel.
4. NHB 1700.1(VI), NASA Safety Manual, Volume 1, Basic Safety Requirements.
5. Appendix V, XV-15 System Safety and R&QA Plan, Contract NAS2-7800 Statement of Work.
6. AHB-6540-1, NASA-Ames Aircraft Maintenance and Inspection Manual.
7. XV-15 Maintenance and Inspection Manual.
8. BHT Report No. 301-099-003, Preliminary Interface Control Document for GFE/CFE Research Instrumentation.
9. BHT Report No. 301-959-001, XV-15 Aircraft Fuel Cells, Draining, Purging and Pressurizing Procedures.
10. XV-15 Flight Operators Manual.
11. BHT Report No. 301-993-001, Ground Tiedown Aircraft Test Plan for XV-15 (Model 301) Aircraft No. 1, Part 1.
12. Assembly Inspection Logs (AIL) (Aircraft Status Book).
13. Flight Test Workbook (Aircraft Service Workbook).

### 3. MANAGEMENT AND TEST DIRECTION

The Tilt Rotor Research Aircraft Projects Office will have primary management responsibility for the XV-15 Wind-Tunnel Test Program. This program will be supported by the Contractor and personnel of the 40 × 80 Foot Wind Tunnel, with assistance from elements of the Aircraft Operations Division and the Research Facilities and Instrumentation Division of ~~Ames~~. Coordination of this effort will be the responsibility of the Project Office. The management structure for the Wind Tunnel Test Program is shown in figure 3-1. The principle elements of this structure are described in the following paragraphs.

#### 3.1 Project Manager

The Project Manager is responsible for the overall operation of the Project Office and coordination with the Contractor and supporting elements within NASA and from other government agencies.

### 3.2 Deputy Manager (Technical)

This Deputy Manager is responsible for planning and coordinating the Wind-Tunnel Test Program, including organization of technical support and supporting research efforts. This includes the effort provided by the Project Office, the Contractor, the wind-tunnel staff, and other ARC supporting personnel.

### 3.3 Deputy Manager (Test and Operations)

This Deputy Manager has primary responsibility for project coordination, management control systems, aircraft configuration control, research instrumentation, Government Furnished Equipment (GFE), Aircraft Ground Equipment (AGE), Project Office effort related to reliability and quality assurance, and test safety.

### 3.4 Test Director

The Test Director is responsible for the Project Office support and coordination of the preparation for and conduct of the wind-tunnel tests. This includes:

- Preparation of a Test Plan and Schedule.
- Preparation of the Instrumentation List with priority requirements for data collection, reduction, analysis, and reporting.
- Completion or reviewing of the Systems Safety Analysis, test limits, and emergency procedures.
- Conduct of pre-test simulations for test crew and operator training in operating and emergency procedures.
- Support the Wind-Tunnel Test Readiness Review and Report with necessary documentation relating to elimination of hazards or minimizing risks disclosed by the Systems Safety Analysis.
- Monitoring preparation of the aircraft to ascertain that the provisions for testing will meet the requirements of the test objectives and that the aircraft is ready for test.
- With the test engineers, provide support for each shift during conduct of the test to monitor instrumentation displays to determine that the test is being conducted within established limits and ascertain any required modifications to the Test Plan and Schedule as dictated by test results or hardware/instrumentation problems.
- Assist in preparation and review of the report presenting the results of the wind-tunnel test.

### 3.5 Test Engineers

Test Engineers in support of the Test Director are responsible for the effort in their area of discipline including:

- Dynamics and stability and control
- Aerodynamics and performance
- Aircraft structure, structural dynamics, and aeroelastics
- Aircraft systems
- Instrumentation, data acquisition, reduction, and analysis

### 3.6 Project Control Officer

The Project Control Officer is responsible for arranging for procurement, transportation, shipping, and storage of project hardware and spares and maintains distribution control of the Wind-Tunnel Test Documentation.

## 4. OPERATIONS

The Wind-Tunnel Test Program includes preparation and checkout of the aircraft and systems, including special instrumentation, remote controls and other special hardware requirements for the conduct of the tests, data acquisition and analysis, reporting, and post-test refurbishment. Preparation for these tests will follow the requirements of references 4 and 5.

### 4.1 Schedule

The detail schedule for accomplishment of this effort is shown in figure 4-1. The relation to the overall program schedule is shown in figure 4-2. The various phases of the program leading to the Wind-Tunnel Test are described in the following paragraphs.

**4.1.1 *Ground tiedown tests***- Following completion of the aircraft final assembly, the installed systems will be tested by the Contractor for interface compatibility and functional operation, including proof loading and calibration prior to ground testing of the complete aircraft. The tiedown tests will be conducted at the Contractor's facility. The purpose is to ensure proper functioning of all the aircraft systems during helicopter, conversion and airplane modes to ensure that the aircraft is safe for wind tunnel testing and exploratory flight testing. For the majority of the ground tiedown tests, operational control of the aircraft will be by a pilot in the cockpit.

For a portion of the tiedown tests of the wind-tunnel test aircraft, the remote control system and instrumentation for operation of the engines and flight controls during the wind-tunnel tests will be installed and functionally checked for proper operation. This checkout will duplicate wind-tunnel

operation except that the ground tiedown tests will utilize the on-board fuel and hydraulic systems. Operation under remote control will be conducted to demonstrate hardware reliability and to train personnel that will operate the aircraft in the wind tunnel.

4.1.2 *Disassembly, Inspection and Shipment*- Upon completion of the ground tiedown development tests, the aircraft will be disassembled by the Contractor and a complete teardown and inspection will be made of the rotors, transmissions, drive system, and rotating control components. The inspected components will be refurbished or replaced as deemed necessary. Engine inspection will be conducted appropriate to the accumulated operating time or the severity of the operation. The aircraft will then be broken down into components and shipped to NASA/Ames by transportation suitable to the Government. An MTAR for disassembly, crating, packaging, tiedown, shipment, and reassembly will be provided by the Contractor. These tasks will be witnessed and approved by the Contractor's QA Inspector. Packaging and shipment will also be witnessed and approved by the Army Bell Plant Activity QA.

4.1.3 *Reassembly and Checkout*- After shipment and arrival at Ames, the aircraft will be reassembled by the Contractor. After assembly, a ground checkout will be conducted using the remote controls and control console to functionally verify proper operation of all systems. Although the actual tests will be conducted in the Ames 40 x 80 Foot Wind Tunnel, other facilities at Ames will be utilized during the buildup, pre-test operational checkout and the post-test refurbishment. These include the static or tiedown test facilities is shown in figure 4-3. The majority of the assembly effort will be in the vehicle assembly building. This site is equipped with fuel, power and portable hydraulics so that preliminary checkout of the aircraft and systems for functional operation and calibration also can be conducted. The extent of this checkout and the facilities used will be determined by mutual agreement between the Tilt Rotor Project Office and the wind-tunnel staff. If it is more expeditious, part of this checkout may be conducted in the wind tunnel, such as final instrumentation checkout and calibration.

4.1.4 *Wind-tunnel tests*- Following completion of the reassembly and initial checkout, a Test Readiness Review will be conducted. This review will be initiated by the Large-Scale Aerodynamics Branch Test Operations Group Project Engineer and will be conducted in accordance with reference 4. The review serves to assure that all aspects of test operation safety have been properly considered. Ames, Contractor, and Project Office personnel will review, initial and date all items on the Test Readiness Review Form pertinent to the test. Ames management approval must be received before tests will be permitted to start.

4.1.4.1 *Installation and pre-test checkout*: The aircraft will be moved from the assembly building to the tunnel and installed. Control and instrumentation leads will be routed from the aircraft down the support struts to the control room. They then will be connected to the control console or the appropriate wind-tunnel instrumentation for data reduction, analysis, monitoring and recording. The instrumentation is described in more detail in section 4.2.6. Again the systems will be checked for continuity,

functional operation and calibration. Following this, a shake test will be conducted.

**4.1.4.2 Shake tests:** A dynamic shake test of the combined aircraft, tunnel support system and balance system will be made after the aircraft is installed in the wind tunnel and prior to wind on testing to verify predicted mode shapes, frequencies and damping values of the aircraft as mounted in the wind tunnel. These tests will be conducted with the rotors off and with weights attached to the rotor hub spindles to simulate the rotor mass. The shake tests will be conducted by the wind-tunnel staff using the wind-tunnel shake test procedures and data analysis system as described in reference 6.

Excitation will be applied to the rotor hub and/or selected air-plane points with electro-hydraulic actuators. Accelerometers and/or strain gages will be used to measure the applied force and structural response. Structural damping will be determined using the wind-tunnel Dynamic Analysis System (DAS, ref. 4). The data will be used for comparison with pre-test analysis and identification of frequency placements with respect to rotor rotational speeds to ensure that resonant vibration levels will not occur for operational rotor speeds. If resonance problems at operating conditions are identified, they will be corrected if feasible or the test plan will be modified.

**4.1.4.3 Test operations:** After the shake tests, the blades will be installed and runs made, wind-off, to check rotor track and balance. A functional check of the instrumentation in the rotating system will also be made.

Testing will follow the Test Plan (ref. 7). This includes rotors off runs to obtain baseline airframe characteristics. The tests with rotors on will consist of various phases of simulated tilt rotor flight at air-speeds from 0 to 200 knots. Blade angle, conversion angle (rotor tilt) and control setting will be varied to explore the performance, dynamics, stability, control, loads and noise characteristics in near hover, conversion and cruise configurations. The results of the wind-tunnel investigation will be compared to predicted values to be certain all critical mode analyses are valid and that the methods properly assess the dynamic characteristics, capabilities and operating behavior of the tilt rotor flight research aircraft. Wind-tunnel demonstrations of operational safety and of technical feasibility are required before initiating the subsequent task leading to flight research.

The Wind-Tunnel Test Operations Group (section 6.0 and ref. 8) has primary responsibility for management and safe conduct of the test in accordance with the Test Plan (ref. 7), and the safety procedures of references 8, 9, 10, and 11. Prior to each operating shift, a pre-shift meeting will be held between the 40 x 80 Shift Engineer and Project Engineer, Tilt Rotor Office Test Director and Contractor Project Engineer and rotor operators to detail the portion of the Test Plan to be implemented during that shift based on data results from completed portions of the test and to assure that the

required aircraft systems, instrumentation and the wind tunnel and data acquisition system are operational. Limitations to test operation will be identified and any possible hazards with emergency procedures reviewed with the rotor and tunnel operators. During test operations, the assessment of the safety of a particular test condition due to structural loads or an instrumentation, electrical or mechanical failure and the authority to terminate or interrupt the test because of the hazardous condition, are the mutual responsibility of the 40 x 80 Shift Engineer and Project Engineer, Tilt Rotor Office Test Director and Contractor Project Engineer. Procedures and contingency plans to counteract emergencies will have previously been defined and approved (section 5 and ref. 4). If, in the judgment of any one of these individuals, a hazardous test condition exists, the test must be terminated until the condition is remedied or the test procedure modified.

4.1.5 *Post-test refurbishment*- Upon completion of the wind-tunnel testing, the aircraft will be removed from the wind tunnel and a detailed inspection made of the aircraft and dynamic components. The aircraft will be refurbished by the Contractor as required to bring the aircraft to flight status. The refurbishment will include removal of all instrumentation and hardware peculiar to the wind-tunnel testing, installation of all instrumentation, ballast and other hardware necessary for conduct of the flight test program. If any modifications to the aircraft are made as a result of a review of the wind-tunnel test results, qualification tests will be conducted as required for new, repackaged, or modified components and assemblies. A ground run will then be performed by the Contractor to complete the pre-flight and functional ground test requirements prior to releasing the aircraft for flight.

## 4.2 Aircraft Preparation and Remote Systems

A general description of the wind tunnel, the aircraft support system, and installation requirements are given in reference 4. In order that the XV-15 aircraft may be mounted and operated in the tunnel, certain provisions or modifications to the ship's structure and hydraulic, fuel, electrical, and control systems are required. These provisions and modifications are described in the following paragraphs.

4.2.1 *Support system*- The aircraft is supported in the wind tunnel on a system of three struts as described in reference 4. To accept the loads imposed by attachment to the support struts, additional structure has been added to the wing and fuselage in the attachment area. Consideration was given to dynamic requirements in selection of the location of the attach points. Mounted on these attach points are removable adaptor fittings (BHT dwg 301-099-017 and -018) to which are attached the support strut ball socket tip fittings (ARC dwg A5005-D200). The adaptor fittings are contractor designed and fabricated. The ball socket fittings are supplied by Ames. Structural integrity of the strut attach points and fittings was verified by proof load tests.

The installation of the aircraft in the wind tunnel is shown in figure 4-4. Various strut and tip arrangements are available (table I). Consideration was given to dynamic characteristics and clearances (fig. 4-5)

in selecting the strut arrangement. Because of an interference between the landing gear doors (gear down) and the support struts, it is planned to conduct all tests with gear up and the gear doors on and closed.

Clearances for hoisting the aircraft in the tunnel are shown in figure 4-6. Although this figure indicates rotors on, it is planned to remove the rotors prior to lift in.

4.2.2 *Remote control system*- Tests of aircraft in the ~~Ames~~ 40 × 80 Foot Wind Tunnel which require operation of gas turbine engines utilize remote operation of engine and flight control systems because of safety considerations necessitated by the particular tunnel design (closed return and minimal air exchange). For the XV-15, remote operation of the controls will be through actuators installed in the aircraft systems as shown in figure 4-7. The controls for operation of these actuators, along with the instrumentation for monitoring the conditions of the various system for the remote operation, will be located and displayed on a control console. The layout of this console is shown in figure 4-8. The console will be located in and operated from the wind tunnel control room (ref. 4 and fig. 4-9). The remote control system will be designed and built by BHT and installed in the aircraft and checked for functional operation during the latter portion of the Ground Tiedown Test of the aircraft (ref. 12).

4.2.3 *Fuel system*- Normal 40 × 80 Foot Wind Tunnel procedures for safe operation of engines in the wind tunnel require external supply of fuel. Therefore, the ship's fuel tanks will be purged and inerted as described in appendix A. The fuel lines to the engines will be connected to the wind tunnel supply system and the ship's crossfeed valve opened (fig. 4-10). Fuel lines to the ship's tanks will be disconnected and capped to prevent fuel from entering the ship's tanks. A fuel shutoff valve operated from the console will be installed in the wind tunnel supply line where it enters the wing which will shut off fuel to both engines. In addition, a fuel shutoff valve is located in the aircraft at each pylon and is controlled from a switch in the fuel control panel that will be removed from the aircraft and installed in the console. This valve also closes when the fire extinguisher handle is pulled.

It will be the responsibility of the contractor to inert the fuel tanks and provide for connections to the ship's system. ~~Ames~~ will have the responsibility for providing fuel to the connection of the ship's system with a shutoff valve and filter (fig. 4-11). Prior to the test, the cleanliness of the wind tunnel supplied fuel will be ascertained to determine that it is satisfactory for connection to the ship's system.

4.2.4 *Hydraulic systems*- The ship's hydraulic system for operation of control actuators and motors consists of three independent systems which provide redundancy (ref. 13 and table 11). The systems are supplied from transmission driven hydraulic pumps. For the tests with engines operating, the ship's system will be operating. To provide capability for operation of the aerodynamic controls (flaps, flaperons, rudders, and elevators) with rotors and power off when the ship's system would not be operating, one of the ship's

hydraulic systems (PC-2) will have provision for external connections to the wind tunnel hydraulic system through an interface system as shown in figure 4-11. The contractor will provide the fittings in the PC-2 system hydraulic line within the wing structure at the support strut location for connection to the interface system (fig. 4-12). The design of the interface will be provided by the contractor. ~~Ams~~ will provide the wind-tunnel hydraulic system and the interface with the ship's system. ~~Ams~~ will have the responsibility to determine the cleanliness of the tunnel system to determine that it is satisfactory for connection to the aircraft system. For pre-run (power off) checkout of the systems, calibration and troubleshooting, access to the PC-1 and PC-3 ship's systems will utilize connections in the left main gear wheel well through a temporary external line to the wind-tunnel interface system.

4.2.5 *Electrical system*- When the aircraft is mounted in the wind tunnel, electrical power will be required for:

- Pre-run checkout and troubleshooting
- Starting
- Operation of remote control actuators
- Instrumentation
- Operation of aircraft electrical systems for those test runs with rotors off and engines not running

Normal operation of these systems on the ground is through use of a ground cart connected to the external power plug in the fuselage. For the wind-tunnel operation, electrical power is supplied from fixed DC generator sets (ref. 4) through wiring up the support struts to the aircraft systems (fig. 4-13). The design and provisions for connection of the aircraft systems to the wind-tunnel power supply will be the responsibility of the contractor. The wiring for the tunnel installation is shown in BHT dwg 301-099-014.

4.2.6 *Research instrumentation and data acquisition*- Research instrumentation for the wind-tunnel test consists of the aircraft on-board systems (ref. 14) and the wind tunnel data acquisition system (ref. 4). The on-board systems consist of sensors, data acquisition, signal conditioning, encoding and recording (PCM tape). The contractor has the responsibility to select and program the on-board data acquisition system to satisfy the data requirements of the wind tunnel test plan. The contractor shall also conduct pre- and post-run calibration and functional checks of the on-board system to ensure its accuracy and functional capability and assist the tunnel staff with the aircraft/tunnel interface.

The wind-tunnel data acquisition system is described in reference 4 and has conditioning, monitoring, reduction, analysis, display, and recording capabilities. The responsibility for implementation, operation, and maintenance of this instrumentation and its interface with the on-board system is a combined effort between the wind-tunnel staff and ~~Ams~~ support services.

The on-board research instrumentation and the interface with the 40 x 80 data systems are listed in tables III and IV and shown in figure 4-14. When



the detailed run by run test plan has been established, this instrumentation list will be prioritized to indicate critical channels which must be operative for either safety or data requirements.

During the wind-tunnel test, the on-board PCM tape recorder will be installed in the control room to provide access during a test run.

*4.2.7 Computation and data reduction-* Requirements for computation and data reduction and display will be established and detailed in the Wind-Tunnel Test Plan (ref. 7). Included will be the type and format of data for monitoring and recording and the calibration and corrections to be applied and summary and reformatting requirements. Portions of this computation and data reduction will be done on-line and displayed and recorded. The rotor/wing/pylon dynamic stability and system damping will be analyzed on-line using the wind-tunnel Dynamics Analysis System (ref. 4) and the on-board dynamic excitation system. To facilitate this analysis, direct access will be provided to certain sensors on the wing and pylon (table IV). Following the test, additional computation and data reduction may be required and will be provided by the Computation Division through computer terminals at the wind tunnel. Implementation of the computation and data reduction is the responsibility of the wind-tunnel staff.

*4.2.8 Configuration control-* The aircraft will be under configuration control as defined in the Program Plan. All Engineering Change Orders involving aircraft modification or component installation will require NASA/Army coordination. A configuration sheet in the aircraft log book will maintain status of permanent or temporary deviations from the as-built configuration. Test items installed temporarily will require an entry in the aircraft log book. Assembly Inspection Logs (AIL) for serialized assemblies will be maintained.

## 5. PROGRAM SAFETY

The principal system safety objective for the XV-15 Tilt Rotor Research Aircraft Project is the completion of all project objectives without personnel injury or loss of life and without significant property damage or loss. Assuring accomplishment of this objective involves preparation of safety plans, identification of responsibility of all involved participants, adherence to applicable criteria and the provisions for safety analysis reviews and analysis of the test system. The test system is defined to encompass the aircraft and its components, interfacing subsystems, equipment, instrumentation and test crews. Requirements, provisions, and responsibility for assuring safe conduct of the wind tunnel tests at Ames are defined in references 8 to 11. These references enumerate the specific analysis and documentation to be submitted to the Ames Management prior to start of testing and include problem, failure reporting, wind tunnel operating hazard analysis and incident and/or accident investigation and reporting procedures and responsibilities.

## 5.1 Systems Safety Analysis

The Systems Safety Analysis Report is the primary document which enumerates the aircraft and test operation safety provisions for conduct of the wind-tunnel tests. This document will be prepared by the contractor in accordance with reference 4 and submitted for approval at least **30** days prior to start of testing. The Safety Analysis will consist of a gross hazard study or comprehensive assessment of the safety features of the aircraft and test systems to adequately evaluate the wind-tunnel test procedures, precautions, facilities, and capabilities in relation to applicable safety criteria to verify that the XV-15 may be safely tested in the wind tunnel. The safety engineering analysis shall be made in sufficient depth to assure maximum safety consistent with operation requirements. Special emphasis will be placed on emergency procedures and other safety features. Additionally, the safety analysis will include pre-test predictions of loads, fatigue life, and dynamic stability to establish boundary conditions for safe test operation.

**5.1.1 Pre-test analysis-** A pre-test analysis will be made by the contractor which will include an estimate of loads on critical members, flapping angles, dynamic modes, and level of stability to cover expected conditions within the test envelope. A written summary will be furnished at least 2 months prior to the tests.

**5.1.1.1 Loads and strength evaluation:** For the airplane as mounted on the support system in the wind tunnel, the contractor will provide estimates of the maximum loads, both steady and dynamic, to be expected during the wind tunnel tests and calculate the strength, safety margins and fatigue life of critical elements. The analysis will also include hoisting slings, strut adaptors, and any other structural components used for the wind tunnel test. Substantiation of these estimates will be made where test data is available. Components are considered critical if failure could result in loss of the aircraft, personnel injury, damage to the tunnel or scale system, or termination of the test. The maximum loads expected to be imposed on the struts and scale system will also be calculated by the contractor to assure that they are within the capacity of these systems as stated in reference 4.

**5.1.1.2 Dynamic stability:** The contractor will estimate the aircraft and rotor stability boundaries for comparison with the test operating boundaries. The coupled aircraft, tunnel support and balance dynamics will also be analyzed to determine potential resonances. The 40 x 80 foot wind tunnel staff will make an independent analysis. If resonance problems at operating conditions are indicated, recommendations will be made for change in stiffness and/or mass characteristics to avoid potential resonances or the test plan will be modified to avoid the resonances. After the aircraft is installed in the wind tunnel, shake tests will be made prior to wind on testing to verify predicted mode shapes, frequencies, and damping values.

**5.1.2 Simulation and crew training-** Prior to the wind-tunnel tests, crew training in operation of the remote systems will be conducted. This training will occur during the latter part of the Ground Tiedown Test at the contractor's facility following installation and functional checkout of the remote system (section 4.1.1).

Also, if time and facilities availability permit, it is planned to conduct a simulation of the test operation at Ames using components of the FSAA simulator. This simulation will:

- Evaluate procedures for safe operations of the aircraft in the wind tunnel.
- Train operators in both normal and emergency operating procedures.
- Provide a pre-test wind-tunnel data predictions capability to evaluate operating conditions for proximity to boundaries and identify potentially dangerous emergency conditions.

This simulation will use the complete aircraft math model without FFS or SCAS that was used for the flight simulation. Inputs to the math model will be adjusted to correspond to the aircraft as mounted in the wind tunnel.

The simulation will be conducted in-house. If feasible, the simulation will include an operator training portion and will involve both the 40 × 80 foot wind tunnel and contractor personnel.

**5.1.3 Operation and monitoring procedures-** As part of the Systems Safety Analysis, the contractor will define test start up and shutdown procedures, identify all probable failures in the various aircraft and tunnel systems and evaluate their impact on the safe operation of the test. He will determine their probability of occurrence and resulting hazards and develop emergency procedures to cope with the failure.

Procedures for monitoring specific test parameters for determining proximity to test boundaries, load limits, etc. will be provided by the contractor prior to the test in the form of an Instrumentation Test Plan. This plan will show in detail the components instrumented, instruments used, circuit diagrams, and calibrations. The instrumentation list will be prioritized to indicate which channels must be operative to start or to continue each test run. Additional details of the data acquisition system are given in section 4.2.6.

Any incidents or accidents that occur will be investigated and reported in accordance with the requirements of reference 11.

**5.1.4 Fire protection-** A fire detection and extinguishing system is incorporated in the aircraft. This system is pilot operated. For the wind-tunnel tests, the fire indication and operation of the extinguishing system will be moved from the cockpit to the remote control console (fig. 4-8). The fire extinguishing system also includes a fuel shutoff at the pylons which closes when the fire handle is pulled. Additional control of fuel flow is described under Fuel System in section 4.2.3.

**5.1.5 Emergency egress system-** An emergency egress system is installed in the aircraft for flight operations and includes pilot and co-pilot ejection seats (ref. 15) and emergency release side and overhead panels. For the wind-tunnel tests, the ballistics for the ejection seats and the detonator chord

for window release will be either removed, disarmed or otherwise safetied. The contractor has responsibility for deactivation of the egress system.

## 5.2 Viewing System

Because of hazards from parts that may be released as a result of a structural failure on the aircraft most of the tunnel sides, including viewing windows, are covered with armor plate. Visual monitoring of the aircraft in the tunnel during the test will be provided by closed circuit television (ref. 4) using four remote TV cameras having scan and zoom capability. The system has provision for 10 camera locations and includes 3 video recorders and 5 monitors.

## 5.3 Test Readiness Review

To assure that all aspects of test planning, operation safety, and emergency procedures have been properly considered prior to start of tests all items pertinent to the proposed tests will be reviewed by personnel from the wind tunnel, project office, and the contractor. The Test Readiness Review and other checklists will be submitted to the 40 x 80 foot wind tunnel operations manager and branch chief for review and approval. Approval is required before tests will be permitted to start.

## 6. SUPPORT REQUIREMENTS

Although the overall direction, management, and coordination of the wind tunnel test program is the responsibility of the XV-15 Project Office, accomplishment of the detailed tasks is a combined effort by many groups. These include:

- Contractor
- Large Scale Aerodynamics Branch
- Aircraft Services Branch
- Aircraft Inspection Branch
- Simulations Investigations Branch
- Photo Technology Branch
- Computer Systems Branch
- R&QA Office

Primary support for the wind tunnel tests is provided by the ~~Ames~~ Large Scale Aerodynamics Branch through their Test Operations Group and Rotary Wing Group. Supporting services from other organizations at ~~Ames~~ is authorized by reference 16. The organizational structure for the supporting services is shown in figure 6-1 and 6-2. Much of the support effort is a dual responsibility with overlapping assignments for various phases of the support requirements. These include:

Planning  
Hardware  
Operation  
Reporting

The distribution of responsibility is summarized in table V.

## 7. REPORTING AND DOCUMENTATION

Prior to, during, and following the tunnel test, various planning documents, schedules, progress and data reports will be required. Some of these have been discussed in other sections and are included in the following summary of the documentation and reporting required for the wind-tunnel test. These include:

Test Plan  
Instrumentation Plan  
System Safety Analysis  
Wind Tunnel Operating Hazard Analysis  
Failure Reporting  
Incident/Accident Reports  
Test Readiness Report  
Test Emergency Procedures  
Engine/Rotor Operators Run Checklist  
Test Report

In addition to the above, certain wind tunnel related documentation is required to assure proper operation of support equipment during the test. These are described in reference 8 and include:

Preparation Checklist  
    Test Section  
    Instrumentation  
    Aircraft Mechanics  
Balance House Pre-Run Checklist  
Preventive Maintenance Work Sheet  
    Mechanical  
    Electrical

Preparation of these latter documents is the responsibility of the Tunnel Operations Group and are usually implemented on either a regular maintenance schedule or as part of the test preparation.

### 7.1 Test Plan

A plan for conduct of the wind tunnel test shall be prepared and submitted by the contractor in accordance with the requirements of references 4 and 5. A draft version of the plan shall be submitted twelve (12) months

prior to the test which shall include a brief discussion of test objectives, scope and duration, and indicate test techniques, range of test variables, test configurations and data requirements. Details of the plan shall be finalized and submitted two (2) months prior to the test and include a detailed description of each run stating the test configuration, test variables, and instrumentation and data reduction.

The Test Plan shall also define the specific government/contractor personnel requirements and responsibilities, sharing of instrumentation, data reduction and operations tasks.

## 7.2 Instrumentation Plan

Data requirements for the wind-tunnel test are identified in the Test Plan. The instrumentation for this data measurement is described in reference 14. For the wind-tunnel test, an Instrumentation Plan shall be prepared and submitted by the contractor showing in detail the components instrumented, sensor calibrations and expected ranges, circuit diagrams, and the interface with the wind-tunnel instrumentation, and the instrumentation and display requirements. The instrumentation list will be prioritized to indicate which channels must be operative for either safety or data requirements. All critical channels must be operative prior to start of each run. Failure of any critical channel will require termination of the run.

From this plan, the Wind-Tunnel Instrumentation Group will prepare an instrumentation document detailing the interface and instrumentation and display requirements and the sensor channel location on each of the wind-tunnel instruments and displays.

## 7.3 Systems Safety Analysis Report

A report presenting the results of the systems safety analysis described in section 5.1 shall be prepared and submitted by the contractor. As indicated in reference 5, portions of the report are required to be submitted up to six (6) months prior to the test date. The complete report is required (1) month prior to test.

## 7.4 Wind-Tunnel Operating Hazard Analysis

A hazard analysis will be performed on hazards that could occur during the wind tunnel test. The analysis will consider those procedures unique to wind-tunnel operations. Reports of pertinent hazards will be presented in a format determined by the contractor.

## 7.5 Failure Reporting

Failure and Maintenance Action Reports shall be prepared and submitted by the contractor in accordance with NAS2-7800 reporting requirements. These reports shall be prepared and submitted in standard contractor format.

## 7.6 Incident/Accident Reports

Requirements for Incident/Accident investigations and reporting procedures and responsibilities are defined in reference 11.

## 7.7 Test Readiness Report

The Test Readiness Report is described in reference 8 and section 5.3. This report must be submitted for review and approved by the Wind-Tunnel Operations Manager and Branch Chief before tests will be permitted to start.

## 7.8 Test Emergency Procedures

Emergency operation procedures are developed as part of the Systems Safety Analysis. These procedures will be prepared and displayed in a format readily available to the operators and test engineers during test operation. Prior to each run, the applicable procedures will be reviewed and during any emergency these procedures will be strictly adhered to.

## 7.9 Engine/Rotor Operator's Checklist

In accordance with the planning requirements of reference 4, an operator's run checklist will be prepared. This list will be displayed where it will be readily available to the operators during test operations, and will include procedures for:

- Pre-start
- Start
- Operating limits
- Monitoring and data requirements
- Shutdown

## 7.10 Test Report

A final wind tunnel test report shall be prepared by the contractor. This report shall include a statement of the test objectives, test procedures, test configuration, a discussion of the test results, and conclusions. The review of the results shall include recommendations as to whether modifications to the research aircraft are desirable prior to initiation of the flight program.

## 8. REFERENCES

1. NASA/Army Project Plan for Development of the XV-15 Tilt Rotor Research Aircraft, January 1974.
2. V/STOL Tilt Rotor Research Aircraft XV-15 Program Plan, Bell Helicopter Company, August 1974.
3. Test and Evaluation Plan, Appendix III to Contract NAS2-7800 Statement of Work.
4. Guide for Planning Investigations in the ~~Ames~~ 40 × 80 Foot Wind Tunnel, June 1975.
5. Planning Rotor Tests for the 40 × 80 Foot Wind Tunnel, June 1977.
6. Johnson, W. and Biggers, J. C., Shake Tests of Rotor Test Apparatus in the 40 × 80 Foot Wind Tunnel, NASA TMX-62,418, February 1975.
7. Marr, R. L., Test Plan for the XV-15 Tilt Rotor Aircraft in the ARC 40- by 80-Foot Wind Tunnel, BHT Report 301-083-005, October 3, 1977.
8. Operations Safety - 40 × 80 Foot Wind Tunnel, AHB 1750-1, July 1973.
9. XV-15 Systems Safety and R&QA Plan, Appendix V to Contract NAS2-7800, October 1973.
10. NASA Safety Manual, Volume 1, Basic Safety Requirements NHB 1700.1(VI).
11. ~~Ames~~ Research Center Safety Manual AHB 1700-1, January 1975.
12. Leibensberger, C. E., Ground Tiedown Aircraft Test Plan for XV-15 (Model 301) Aircraft No. 1, Part I, BHT Report 301-993-001, November 23, 1976.
13. V/STOL Tilt Rotor Research Aircraft - Vol. 4 Subsystem Analysis, BHT Report 301-199-004.
14. Instrumentation and Data Acquisition Manual, BHT Report 301-099-003B, June 28, 1974.
15. T.O. IL-IOA-2-3 LW-3B Aircrew Escape System.
16. Mark, H. and Yaggy, P. F., Memo for Organizational Directors, Division Chiefs, Branch Chiefs, and Section Heads NASA-Ames D:200-1, Moffett Field, California, June 27, 1973.



## APPENDIX A

### FUELING PROCEDURES FOR WIND TUNNEL OPERATION

#### A1.0 Wing Tank Defueling Procedure

The following defueling procedures are to be used for the BHT 301-060-600 fuel system installation (wing) in preparation for the wind-tunnel tests (reference BHT dwg 301-099-016).

- A1.1 Aircraft to be as level as possible.
- A1.2 Observe the requirements of BHT Report 301-959-001, XV-15 Aircraft Fuel Cells, Draining, Purging and Pressurizing Procedures.
- A1.3 Attach a hose to the defuel valve. The open end of the hose must be passed overboard and placed in a reservoir so that gravity will permit fuel to be drained. Existing cap must be removed before hose can be attached.
- A1.4 Open the defuel valve. This is operated manually by a handle on the valve.
- A1.5 From the pilot's console, position the switch that operates the equalizer valve to the open position (read TANK INTCON).
- A1.6 When the tanks are depleted of fuel, close the defuel valve and disconnect the drain hose.
- A1.7 Operate the sump drain valves (one in each wing) catching the fuel in a container until the tanks are empty.
- A1.8 Purge the tanks observing safety instructions of BHT Report 301-959-001.
- A1.9 Break into the vent lines at the points indicated and add one cap in each wing to the tank side portion of the line.
- A1.10 Attach a hose to the defuel valve (or more convenient opening to tanks). Attach the other end of the hose to the nitrogen supply. Add the system pressure relief valve and the system pressure gage to the nitrogen supply as shown on BHT dwg 301-099-016. With the defuel valve and the equalizer valve in the open position, fill the cells per safety instructions.  
  
Note: If alternate opening is used, the defuel valve must be closed.
- A1.11 Follow the safety plan to the conclusion of the purge procedure.

## APPENDIX A (Cont.)

### A2.0 Fueling Procedure Preparation

Following are the fueling procedures in preparation for the wind tunnel tests.

- A2.1 Break the crossfeed line as shown on BHT dwg 301-099-016 and add (2) AN929-10 caps (1 L/H and 1 R/H) to the existing tee fittings.
- A2.2 Plug and stow the hose with AN 806-10D plug, L/H and R/H.
- A2.3 Operate the crossfeed valve to the open position by operating the switch on the pilot's console (reads FUEL XFEED).
- A2.4 On the R/H wing only, open the existing line by removing a cap on the tee provided.
- A2.5 Attach the hose indicated to the open port in the tee. Add the connectors as shown. Add the filter and the upper tube as indicated. Add the middle tube and the tee to the base of the filter as shown. The tee must have (2) unions and (2) packings assembled to the tee prior to the attachment of the tube assemblies. Attach the busing or reducer with (1) MS 29512-10 packing. Add the pressure switch and (1) MS 29512 packing. Wire as indicated. Add the lower tube assembly to the base of the tee. Add the valve after attaching (2) connectors as shown.

Note: The items in this step of the procedure to be installed on the inside or the outside of the wind-tunnel strut fairing as determined by NASA personnel.

- A2.6 Attach the hose from the valve to the facility regulator.

Table I.- Angle of Attack Range for the XV-15 in the Ames 40- by 80-Foot Wind Tunnel

MAIN STRUT (FEET)	MAIN TIP (INCHES)	AFT TIP (INCHES)	AFT EXT.	ANGLE		ROTOR & LOC. (INCHES)	STRUT TILT	
				-	+		FW'D	HT?
				③		②		
15	6	12	IN	18½	11½	-39	-½	3½
15	6	24	IN	21½	9	-39	0	3½
15	6	36	IN	22½ <sup>(1)</sup>	6	-39	1	2½
15	6	48	IN	22½ <sup>(1)</sup>	3	-39	2	3½
15	6	48	OUT	7½	22½ <sup>(1)</sup>	-39	14½	3½
15	33	12	IN	12½	18	-12	4½	2½
15	33	24	IN	15½	15	-12	2	2½
15	33	36	IN	18½	12½	-12	½	2½
15	33	48	IN	21	9½	-12	½	2½
15	60	12	IN	4	22½ <sup>(1)</sup>	+15	11	2
15	60	24	IN	9	22½	+15	7	2
15	60	36	IN	11½	19	+15	4	2
15	60	48	IN	15	16	+15	2	2

- ① BALL SOCKET LIMIT  $\pm 22\frac{1}{2}^\circ$   
 ② + ABOVE TUNNEL &, - BELOW  
 ③ ROTOR/FAIRING INTERFERENCE LIMITS NEGATIVE CL  
 ④ STRUT TIP ARRANGEMENT PER

TABLE II .- WDRALJLIC POWER DISTRIBUTION

Component	Type	Subsystem		
		PC 1	PC 2	PC 3
		Swivel location		
		outboard (pylon)	inboard (pylon)	inboard (spindle)
		Pump location		
		L/H transmission	R/H transmissior	L/H transmission
Fore/aft cyclic	T	X	X	
Elevator	T	X	X	
Flaperon	T+	X	X	X <sub>1</sub>
Rudder	S		X	
Lateral cyclic	S		X	
Excitation	S			X <sub>2</sub>
Conversion	D	X	X	
Collective	T+	X	X	X.
RPM governor	T	X	X	
SCAS - Pitch	D	X	X	
Roll	D	X	X	
Yaw	S		X	
Force Feel -				
Pitch	S		X	
Roll	S		X	
Yaw	S		X	
Pitch				
Trim	S		X	
Emergency conversion	Motor			X
Heat exchanger blower	Motor		X	X
Landing gear	S			X <sub>2,3</sub>

Remarks :

Type

T Tandem actuator

T+ Tan? an actuator with shuttle valve to permit PC, backup for PC,

D Dual actuator

S Single actuator

Subscripts:

1. Employed upon loss of PC,

2. Isolated from PC<sub>3</sub> upon loss of PC<sub>2</sub> or PC,

3. Pneumatic backup employed after loss of PC,, or PC<sub>3</sub>.

Table III - Aircraft Instrumentation  
(a) Propulsion System Measurements

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Fuel systems	Right engine	Total fuel flow	R516	8 DMX	lb	100	0.1 gals	Mass fuel flow
	Left engine	Total fuel flow	R517	8 DMX	lb	100		Mass fuel flow
	Right engine	Fuel flow rate	R328	1 AMX	lbs/hr	10		Mass fuel flow
Torque system	Right engine	Fuel flow rate	R329	1 AMX	lbs/hr	10		Mass Fuel Flow
	Right engine	Torque (Simmonds Precision system)	M335	1 AMX	in.-lb	50	+2.5 V	Voltage output
	Left engine	Torque (Simmonds Precision system)	M336	1 AMX	in.-lb	50		Voltage output
Turbine speeds	Interconnect	Torque (Simmonds Precision system)	M337	1 AMX	in.-lb	50		Voltage output
	Right engine	Gas producer speed (NI)	R503	1 AMX	rpm	50		Tachometer generator
	Left engine	Gas producer speed (NI)	R515	1 AMX	rpm	50		Tachometer generator
Engine vibration	Right engine	Power turbine speed (NII)	R338	1 AMX	rpm	10		Voltage output
	Left engine	Power turbine speed (NII)	R339	1 AMX	rpm	10	+2.5 V	Voltage output
Pylon temperatures	Right engine	Inlet case - fore and aft	A500	1 AMX	g	50	+5 V	Accelerometer
	Left engine	Inlet case - vertical	A502	1 AMX	g	50	+5 V	Accelerometer
	Right engine	Inlet case - lateral	A501	1 AMX	g	50	+5 V	Accelerometer
Pylon temperatures	Right engine	Inlet case - fore and aft	A507	1 AMX	g	50	+5 V	Accelerometer
	Left engine	Inlet case - vertical	A514	1 AMX	g	50	+5 V	Accelerometer
	Right engine	Inlet case - lateral	A508	1 AMX	g	50	+5 V	Accelerometer
Pylon temperatures	Right engine	1. Transmission compartment ambient	T506	1 AMX*	of	100	6 mV	Temperature scanner
	Left engine	2. Blower air - outlet of heat exchanger						
	Right engine	3. Transmission oil into cooler						
Pylon temperatures	Left engine	4. Transmission oil into cooler						
	Right engine	5. Transmission case surface						
	Left engine	6. Transmission case surface						

\*Thermocouples go through a switch and appear as a single channel in the program board. One for each pylon and one for the fuselage. Sensitivity is 3 mV = 100°F.

Table III - Aircraft Instrumentation  
(b) Propulsion Systems Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
	Right system (continued)	<p>7. Transmission case surface</p> <p>8. Transmission case surface</p> <p>9. ECU bleed air to swivel</p> <p>10. PC<sub>2</sub> hyd reservoir pressure port</p> <p>11. Engine oil outlet</p> <p>12. Turbine inlet (Lycoming T-7 harness)</p> <p>PC<sub>2</sub> hyd cooler fluid in</p> <p>PC<sub>2</sub> hyd cooler fluid out</p> <p>ECU cooler bleed air in</p> <p>Fuel</p> <p>Engine inlet housing</p> <p>Engine accessory housing</p> <p>Engine axial compressor</p> <p>Engine centrifugal compressor</p> <p>Engine compressor diffuser</p> <p>Engine exhaust diffuser</p> <p>Engine ignition unit</p> <p>Engine fuel control</p> <p>Engine igniter solenoid valve</p> <p>Engine air bleed control</p> <p>Engine thermocouple harness connector</p> <p>Starter generator</p> <p>NI tachometer generator</p> <p>Engine compartment above inlet</p> <p>Tail pipe fairing compartment</p>						

Table III - Aircraft Instrumentation  
(c) Propulsion Systems Measurements (cont)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
	Left system	1. Transmission compartment ambient 2. Blower air outlet of heat exchanger 3. Transmission oil into cooler 4. Transmission oil out of cooler 5. Transmission case surface 6. Transmission case surface 7. Transmission case surface 8. Transmission case surface 9. PC <sub>1</sub> hyd reservoir pressure port 10. PC <sub>3</sub> hyd reservoir pressure port 11. Engine oil outlet 12. Turbine inlet (Lycoming T-7 harness) PC <sub>1</sub> hyd cooler fluid in PC <sub>1</sub> hyd cooler fluid out PC <sub>3</sub> hyd cooler fluid in PC <sub>3</sub> hyd cooler fluid out Inlet temperature 00 position Inlet temperature 1200 position Inlet temperature 2400 position Transmission case surface Transmission case surface Transmission case surface	T513	1 ANDX*	OF	100	6 mV	Temperature sensor
					4 @ 3, 6, 12, 24, 48, 96, 192, 384, 768, 1536, 3072, 6144, 12288, 24576, 49152, 98304, 196608, 393216, 786432, 1572864, 3145728, 6291456, 12582912, 25165824, 50331648, 100663296, 201326592, 402653184, 805306368, 1610612736, 3221225472, 6442450944, 12884901888, 25769803776, 51539607552, 103079215104, 206158430208, 412316860416, 824633720832, 1649267441664, 3298534883328, 6597069766656, 13194139533312, 26388279066624, 52776558133248, 105553116266496, 211106232532992, 422212465065984, 844424930131968, 1688849860263936, 3377699720527872, 6755399441055744, 13510798882111488, 27021597764222976, 54043195528445952, 108086391056891904, 216172782113783808, 432345564227567616, 864691128455135232, 1729382256910270464, 3458764513820540928, 6917529027641081856, 13835058055282163712, 27670116110564327424, 55340232221128654848, 110680464442257309696, 221360928884514619392, 442721857769029238784, 885443715538058477568, 1770887431076116955136, 3541774862152233910272, 7083549724304467820544, 14167099448608935641088, 28334198897217871282176, 56668397794435742564352, 113336795588871485128704, 226673591177742970257408, 453347182355485940514816, 906694364710971881029632, 1813388729421943762059264, 3626777458843887524118528, 7253554917687775048237056, 14507109835375550096474112, 29014219670751100192948224, 58028439341502200385896448, 116056878683004400771792896, 232113757366008801543585792, 464227514732017603087171584, 928455029464035206174343168, 1856910058928070412348686336, 3713820117856140824697372672, 7427640235712281649394745344, 14855280471424563298789490688, 29710560942849126597578981376, 59421121885698253195157962752, 118842243771396506390315925504, 237684487542793012780631851008, 475368975085586025561263702016, 950737950171172051122527404032, 1901475900342344102245054808064, 3802951800684688204490109616128, 7605903601369376408980219232256, 15211807202738752817960438464512, 30423614405477505635920876929024, 60847228810955011271841753858048, 121694457621910022543683507716096, 243388915243820045087367015432192, 486777830487640090174734030864384, 973555660975280180349468061728768, 1947111321950560360698936123457536, 3894222643901120721397872246915072, 7788445287802241442795744493830144, 15576890575604482885591488987660288, 31153781151208965771182977975320576, 62307562302417931542365955950641152, 124615124604835863084731911901282304, 249230249209671726169463823802564608, 498460498419343452338927647605129216, 996920996838686904677855295210258432, 1993841993677373809355710590420516864, 3987683987354747618711421180841033728, 7975367974709495237422842361682067456, 15950735949418990474845684723364134912, 31901471898837980949691369446728269824, 63802943797675961899382738893456539648, 127605887595351923798765477786913079296, 255211775190703847597530955573826158592, 510423550381407695195061911147652317184, 1020847100762815390390123822295304634368, 2041694201525630780780247644590609268736, 4083388403051261561560495289181218537472, 8166776806102523123120990578362437074944, 16333553612205046246241981156724874149888, 32667107224410092492483962313449748299776, 65334214448820184984967924626899496599552, 130668428897640369969935849253798993199104, 261336857795280739939871698507597986398208, 522673715590561479879743397015195972796416, 1045347431181122959759486794030391945592832, 2090694862362245919518973588060783891185664, 4181389724724491839037947176121567782371328, 8362779449448983678075894352243135564742656, 16725558898897967356151788704486271129485312, 33451117797795934712303577408972542258970624, 66902235595591869424607154817945084517941248, 133804471191183738849214309635890169035882496, 267608942382367477698428619271780338071764992, 535217884764734955396857238543560676143529984, 1070435769529469910793714477087121352287059968, 2140871539058939821587428954174242704574119936, 4281743078117879643174857908348485409148239872, 8563486156235759286349715816696970818296479744, 17126972312471518572699431633393941636592959488, 34253944624943037145398863266787883273185918976, 68507889249886074290797726533575766546371837952, 137015778499772148581595453067151533092743675904, 274031556999544297163190906134303066185487351808, 548063113999088594326381812268606132370974703616, 1096126227998177188652763624537212264741949407232, 2192252455996354377305527249074424529483898814464, 4384504911992708754611054498148849058967797628928, 8769009823985417509222108996297698117935595257856, 17538019647970835018444217992595396235871190515712, 35076039295941670036888435985190792471742381031424, 70152078591883340073776871970381584943484762062848, 140304157183766680147553743940763169886969524125696, 280608314367533360295107487881526339773939048251392, 561216628735066720590214975763052679547878096502784, 1122433257470133441180429951526105359095756193005568, 2244866514940266882360859903052210718191512386011136, 4489733029880533764721719806104421436383024772022272, 8979466059761067529443439612208842872766049544044544, 17958932119522135058886879224417685745532099088089088, 35917864239044270117773758448835371491064198176178176, 71835728478088540235547516897670742982128396352356352, 143671456956177080471095033795341485964256792704712704, 287342913912354160942190067590682971928513585409425408, 574685827824708321884380135181365943857027170818850816, 1149371655649416643768760270362731887714054341637701632, 2298743311298833287537520540725463775428108683275403264, 4597486622597666575075041081450927550856217366550806528, 9194973245195333150150082162901855101712434733101613056, 18389946490390666300300164325803710203424869466203226112, 36779892980781332600600328651607420406849738932406452224, 73559785961562665201200657303214840813699477864812904448, 147119571923125330402401314606429681627398955729625808896, 294239143846250660804802629212859363254797911459251617792, 588478287692501321609605258425718726509595822918503235584, 1176956575385002643219210516851437453019191645837006471168, 2353913150770005286438421033702874906038383291674012942336, 4707826301540010572876842067405749812076766583348025884672, 9415652603080021145753684134811499624153533166696051769344, 18831305206160042291507368269622999248307066333392103538688, 37662610412320084583014736539245998496614132666784207077376, 75325220824640169166029473078491996993228265333568414154752, 150650441649280338332058946156983993986456530667136828309504, 301300883298560676664117892313967987972913061334273656619008, 602601766597121353328235784627935975945826122668547313238016, 1205203533194242706656471569255871951891652245337094626476032, 2410407066388485413312943138511743903783304490674189252952064, 4820814132776970826625886277023487807566608981348378505904128, 9641628265553941653251772554046975615133217962696757011808256, 19283256531107883306503545108093951230266435925393514023616512, 38566513062215766613007090216187902460532871850787028047233024, 77133026124431533226014180432375804921065743701574056094466048, 154266052248863066452028360864751609842131487403148112188932096, 308532104497726132904056721729503219684262974806296224377864192, 617064208995452265808113443459006439368525949612592448755728384, 1234128417990904531616226886918012878737051899225184897511456768, 2468256835981809063232453773836025757474103798450369795022913536, 4936513671963618126464907547672051514948207596900739590045827072, 9873027343927236252929815095344103029896415193801479180091654144, 19746054687854472505859630190688206059792830387602958360183308288, 39492109375708945011719260381376412119585660775205916720366616576, 78984218751417890023438520762752824239171321550411833440733233152, 157968437502835780046877041525505648478342643100823666881466466304, 315936875005671560093754083051011296956685286201647333762932932608, 631873750011343120187508166102022593913370572403294667525865865216, 1263747500022686240375016332204045187826741144806589335051731730432, 2527495000045372480750032664408090375653482289613178670103463460864, 5054990000090744961500065328816180751306964579226357340206926921728, 10109980000181489923000130657632361502613929158452714680413853843456, 20219960000362979846000261315264723005227858316905429360827707686912, 40439920000725959692000522630529446010455716633810858721655415373824, 80879840001451919384001045261058892020911433267621717443310830747648, 161759680003037838768002090522117784041822866535243434886621661495296, 323519360006075677536004181044235568083645733070486869773243322990592, 647038720012151355072008362088471136167291466140973739546486645981184, 1294077440024302710144016724176942272334582932281947479092973291962368, 2588154880048605420288033448353884544669165864563894958185946583924736, 5176309760097210840576066896707769089338331729127789916371893167849472, 10352619520194421681152133793415538178676663458255579832743786335698944, 20705239040388843362304267586831076357353326916511159665487572671397888, 41410478080777686724608535173662152714706653833022319330975145342795776, 82820956161555373449217070347324305429413307666044638661950290685591552, 165641912323110746898434140694648610858826615332089277323900581371183104, 331283824646221493796868281389297221717653230664178554647801162742366208, 662567649292442987593736562778594443435306461328357109295602325484732416, 1325135298584885975187473125557188886870612922656714218591204650969464832, 2650270597169771950374946251114377773741225845313428437182409301938929664, 5300541194339543900749892502228755547482451690626856874364818603877859328, 10601082388679087801499785004457511094964903381253713748729637207755718656, 21202164777358175602999570008915022189929806762507427497459274415511437312, 42404329554716351205999140017830044379859613525014854994918548831022874624, 84808659109432702411998280035660088759719227050029709989837097662045749248, 169617318218865404823996560071320177519438454100059419979674195324091498496, 339234636437730809647993120142640355038876908200118839959348390648182996992, 678469272875461619295986240285280710077753816400237679918696781296365993984, 1356938545750923238591972480570561420155507632800475359837393562592731987968, 2713877091501846477183944961141122840311015265600950719674787125185463975936, 5427754183003692954367889922282245680622030531201901439349574250370927951872, 10855508366007385908735779844564491361244061062403802878699148500741855903744, 21711016732014771817471559689128982722488122124807605757398297001483711807488, 43422033464029543634943119378257965444976244249615211514796594002967423614976, 86844066928059087269886238756515930889952488499230423029593188005934847229952, 173688133856118174539772477513031861779904976998460846059186376011869694459904, 347376267712236349079544955026063723559809953996921692118372752023739388919808, 694752535424472698159089910052127447119619907993843384236745504047478777839616, 1389505070848945396318179820104254894239239815987686768473491008094957555679232, 2779010141697890792636359640208509788478479631975373536946982016189915111358464, 5558020283395781585272719280417019576956959263950747073893964032379830222716928, 11116040566791563170545438560834039153913918527901494147787928064759660445433856, 22232081133583126341090877121668078307827837055802988295575856129519320890867712, 44464162267166252682181754243336156615655674111605976591151712259038641781735424, 88928324534332505364363508486672313231311348223211953182303424518077283563470848, 177856649068665010728727016973344626462622696446423906364606849036154567126941696, 355713298137330021457454033946689252925245392892847812729213698072309134253883392, 711426596274660042914908067893378505850490785785695625458427396144618268507766784, 1422853192549320085829816135786757011700981571571391250916854792289236537015533568, 2845706385098640171659632271573514023401963143142782501833709584578473074031067136, 5691412770197280343319264543147028046803926286285565003667419169156946148062134272, 1138282554039456068663852908629			

Table III - Aircraft Instrumentation  
(d) Propulsion System Measurements (cont)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Pylon pressure	Right system A	Atmospheric (static ref) Transmission compartment static	P505 P504	1 PSF 1 PSF	psi psi	100 100	+10 mV +10 mV	Pressure Transducer Pressure Transducer
	Left system A	Atmospheric (static ref) Transmission compartment static Engine compartment air scoop (Total and static - 5 ports) Engine inlet bell mouth (Total and static - 39 ports) Engine tail pipe (Static - 4 ports) Engine inlet bell mouth High frequency @ 1600 Engine inlet bell mouth High frequency @ 3200	P512	1 PSF*	psi	100	+10 mV	Scanivalve
			P518	1 AMX	psi	100	50 mV	Transducer
			P519	1 AMX	psi	100	50 mV	Transducer

- A These 19 measurements may not be required after cooling and temperature surveys are documented
- A These 10 measurements may not be required after cooling, temperature, and inlet surveys are documented
- A These 2 measurements may not be required after temperature and cooling surveys are documented
- A These 52 measurements may not be required after cooling, temperature, inlet, and tail pipe surveys are documented.

\*Thermocouples go through a switch and appear as a single channel at the program board. One for each pylon and one for the fuselage. Sensitivities are 3 mV = 100°F.



Table III - Aircraft Instrumentation  
(e) Airframe Load Measurements

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Right Wing	BL 0 0	Upper panel outer skin stress	S628	1 PSF	in.-lb	50	±5 mV	4-arm strain gage
		Lower panel outer skin stress	S629					
		Upper panel inner skin stress *	S609					
	WS 22 0	Lower panel inner skin stress *	S610					
		Wing chord bending	B603					
		Wing beam bending	B600					
		Wing torque	M606				±5 mV	
	WS 6 0	Wing front spar shear (upper)	S630				±2.5 mV	
		Wing front spar shear (lower)	S631					
		Wing rear spar shear (upper)	S632					
Left Wing	WS 142 0	Wing rear spar shear (lower)	S633					4-arm strain gage
		Wing front spar shear (upper)	S634					
		Wing front spar shear (lower)	S635					
		Wing rear spar shear (upper)	S636					
		Wing rear spar shear (lower)	S637					
	WS 22 0	Left wing chord bending	B625					
		Left wing beam	B626					
		Left wing torque	M627					
	BL +0.25	Beam bending	D260					
	BL -0.25	Beam bending	B261					
Right horizontal stabilizer	BL 7 7	Beam bending	D262					4-arm strain gage
	BL 7 7	Chord bending	D263					
	BL 3 0	Torque bending	M266					
	BL 68 0	Chord bending	D265					
	BL 65 0	Beam bending	D264					
	BL 68 0	Torque	M267				±2.5 mV	
	WL 108 0	Chord bending	B271				±5 mV	
	WL 108 9	Beam bending	D270				±5 mV	
	WL 103 68	Torque	M273				±2.5 mV	
	WL 97 0	Chord bending	D269					
Right vertical stabilizer	WL 95 6	Beam bending	B268					4-arm strain gage
	WL 97 98	Torque	M272					
		Beam bending	D165					
		Chord bending	B166					
		Beam bending	D165					
		Chord bending	B166					
		Beam bending	D165					
		Chord bending	B166					
		Beam bending	D165					
		Chord bending	B166					
Right pylon conversion spindle		Beam bending	D165					4-arm strain gage
		Chord bending	B166					

\* REDUNDANT GAGES INSTALLED IN THESE LOCATIONS

Table III - Aircraft Instrumentation  
(f) Airframe Load Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Pylon conversion actuator		Axial load	F611	1 PSF	1b	100	±10 mv	0-arm strain gage
Right pylon		Lower cowl outboard support strut axial load	F522			50	±10 mv	
		Lower cowl inboard support strut axial load	F523					
Left pylon		Lower cowl outboard support strut axial load	F520			50		
		Lower cowl inboard support strut axial load	F521		1b			
Control surfaces								
Right flap	WS 25.0	Drive tube torque	M612		in.-lb	100		
		Beam bending	B613					
Left flap		Drive tube torque	M619		in.-lb			
		Beam bending	B618					
Right flap/eron	WS 107.0	Control arm force	F614		lb			
		Beam bending	B615		in.-lb			
Left flap/eron		Control arm force	F621		lb			
		Beam bending	B622		in.-lb			
Elevator								
Right elevator	BL 3.8	Drive tube torque	M275		lb			
	BL 49.5	Beam bending	B274		in.-lb			
Left elevator	BL 3.8	Drive tube torque	M279		lb			
	BL 49.5	Beam bending	B282	1 PSF	in.-lb	100	±10 mv	C-arm strain gage

Table III - Aircraft Instrumentation  
 (g) Airframe Load Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Right rudder	WL 105.93 WL 118.76	Drive tube torque Beam bending	M276 B278	1 PSF	lb in.-lb	100	±10 mV	4-arm strain gage
Left rudder	WL 105.93 WL 118.76	Drive tube torque Beam bending	M277 B280	1 PSF	lb in.-lb	100	±10 mV	4-arm strain gage
Horizontal* Stabilizer		Incidence actuator force	F286	1 AMX	lb			
Left Pylon								
Pylon conversion spindle		Beam bending Chord bending	B190 B191	1 PSF 1 PSF	in.-lb. in.-lb.	50 50	±2.5 mV ±2.5 mV	
Pylon conversion actuator		ail Load	F638	1 PSF	lb	100	±50 mV	4-arm strain gage

\* To be used at a later date.

Table III - Aircraft Instrumentation  
(h) Airframe Load Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Pilot flight controls								
Cyclic stick		Fore and aft force Lateral force	F330 F331	1 PSF	lb	10	$\pm 25$ mV	4-arm strain gage
Right pedal		Force	F333				$\pm 25$ M	
Left pedal		Force	F334	1 PSF	lb	10		
Landing gear, right main								
Trunnion arm		Vertical bending	B333	1 AMX	in.-lb	50	$\pm 10$ mV	
Oleo strut		Fore and aft bending Lateral bending	B354 B316		in.-lb		$\pm 10$ mV	
Drag strut		Axial force	F303		lb		$\pm 25$ mV	
Landing gear, left main								
Trunnion arm		Vertical bending	B310		in.-lb		$\pm 10$ mV	
Oleo strut		Fore and aft bending Lateral bending	B311 B312		in.-lb		$\pm 10$ mV	
Drag strut		Axial force	F313	1 AMX	lb	50	$\pm 25$ mV	4-arm strain gage

Table III - Aircraft Instrumentation  
(i) Airframe Load Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
<u>Nose gear</u>								
Right trunnion		Vertical bending	B343	1 AMX	in.-lb	50	±10 mV	4-arm strain gage
Left trunnion		Vertical bending	B344					
Oleo strut		Fore and aft bending Lateral bending	B345 B346		in.-lb	50	±10 mV	4-arm strain gage
Drag strut		Axial force	F347	1 AMX	lb		±25 mV	4-arm strain gage

Table III - Aircraft Instrumentation  
(j) Rotor Load Measurements

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
<u>Rotor blade</u>	Sta 9.5	Leading edge stress	S145	1 PSF	psi	100	$\pm 10$ mV	4-arm strain gage
Right rotor red blade	Sta 22.8 Sta 52.5	Trailing edge stress	S146		in.-lb		$\pm 5$ mV	
		Beam bending	B120				$\pm 25$ mV	
		Beam bending	B122				$\pm 25$ mV	
		Chord bending	B123				$\pm 25$ mV	
	Sta 75.0	Torque	M129				$\pm 10$ mV	
		Beam bending	B124				$\pm 10$ mV	
		Chord bending	B125				$\pm 10$ mV	
		Beam bending	B126				$\pm 10$ mV	
Left rotor red blade	Sta 22.8	Chord bending	B127				$\pm 5$ mV	
		Torque	M128				$\pm 10$ mV	
		Beam bending	B130				$\pm 5$ mV	
		Beam bending	B132				$\pm 25$ mV	
	Sta 52.5	Chord bending	B133				$\pm 25$ mV	
		Torque	M139				$\pm 10$ mV	
		Beam bending	B134				$\pm 10$ mV	
		Chord bending	B135				$\pm 10$ mV	
	Sta 75.0	Beam bending	B136				$\pm 10$ mV	
		Chord bending	B137				$\pm 5$ mV	
		Torque	M138		in.-lb		$\pm 10$ mV	
Left rotor red blade	Sta 9.5	Leading edge stress	S147		psi		$\pm 10$ mV	
		Trailing edge stress	S148				$\pm 10$ mV	
<u>Rotor hub</u>								
Right red spindle	Sta 9.0	Beam bending	B112		psi		$\pm 5$ mV	
		Chord bending	B113				$\pm 5$ mV	
Right white spindle	Sta 9.0	Beam bending	B171		in.-lb		$\pm 5$ mV	
		Chord bending	B172					
Right Green spindle	Sta 9.0	Beam bending	B173		in.-lb		$\pm 5$ mV	
		Chord bending	B174	1 PSF		100	$\pm 5$ mV	4-arm strain gage

Table III - Aircraft Instrumentation  
(k) Rotor Load Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Left red spindle	Sta 9.0	Beam bending	B114	1 PSF	in.-lb	100	$\pm 5$ mV	4-arm strain gage
Left white spindle	Sta 9.0	Chord bending	B115					
Left green spindle	Sta 9.0	Beam bending	B192					
		Chord bending	B193					
		Beam bending	B194					
		Chord bending	B195	1 PSF	in.-lb	100	$\pm 5$ mV	4-arm strain gage
RIGHT HAST		PARALLEL BENDING	B108	PSF	in.-lbs	100	$\pm 5$ mV	4-arm strain gage
		PERPENDICULAR BENDING	B109				$\pm 5$ mV	
		TORQUE	H107	PSF	in.-lbs	100	$\pm 2.5$ mV	4-arm strain gage

R-

Table III - Aircraft Instrumentation  
(1) Rotor Load Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Left mast		Parallel bending	B140	1 PSF	in.-lb	100	±5 mV	4-arm strain gage
		Perpendicular bending Torque	B141 M143		in.-lb		±5 mV ±2.5 mV	
Rotor pitch change links	Right	Red link axial force	F103		lb		±5 mV	
	Left	White link axial force Green link axial force Red link axial force White link axial force Green link axial force	F104 F055 F060 F061 F062		lb			
Swashplate drive link	Right	Driver bending	B052	1 PSF	lb	100	±5 mV	4-arm strain gage
	Left	Driver bending	B142		lb			
			B1 B1 B1 B1					



Table III - Aircraft Instrumentation  
(m) Rotor Load Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Control boost actuators	Right pylon	Cyclic fore and aft axial force Lateral axial force Collective axial force	F162 F163 F164	1 PSF	lb	100	±5 mV	4-arm strain gage
	Left pylon	Cyclic fore and aft axial force Lateral axial force Collective axial force	F187 F188 F189	1 PSF	lb	100	±5 mV	4-arm strain gage

Table III - Aircraft Instrumentation  
(n) Position Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Airframe Flaps and flap- aperons	Right flap	Position measurement	D617	1 AMX	deg	10	±3 mV	Rotary potentiometer
	Left flap		D620					
	Right flap- eron		D616					
Elevator	Left flap-eron	Position measurement	D623	1 AMX	deg	10	±3 mV	Rotary potentiometer
	Right elevator		D281					
Rudder	Right rudder	Position measurement	D284	1 AMX	deg	10	±3 mV	Rotary potentiometer
Main landing gear	Right actuator	Position measurement	D317	1 AMX	deg	10	±3 mV	Cable potentiometer
	Oleo extension		D305		in.			
	Left actuator		D314		deg			
	Oleo extension		D315		in.			
	Actuator		D348		deg			
Nose landing gear	Oleo extension	Position measurement	D349	1 AMX	in.	10	±3 mV	Cable potentiometer
	Steering		D350		deg			
	Incidence actuator		D287		deg			
	Right Left		D645 D646		deg deg			

\* If

Table III - Aircraft Instrumentation  
(o) Position Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Pilot Controls								
Cyclic stick	Fore and aft	Position measurement	D021	1 AMX	deg	10	$\pm 3$ V	Rotary potentiometer
Power lever	Lateral		D022					
Rudder pedals			D023					
Fuel Control Lever	Right		D024					
	Left		D509 D510		deg	10		Rotary potentiometer
Flap controls	Flap lever		D309		deg	10		Rotary potentiometer
SCAS system	Fore and aft		D306		in.	50		Linear potentiometer
	Lateral		D307		in.	50		Linear potentiometer
	Directional		D308		in.	50		Linear potentiometer
Diff. cyc. washout act. pos.			D318		in.	10		Linear potentiometer
Rotor Positions								
Hub spring motion	Right - fore and aft		D156		deg			LVDT
	Right - lat.		D157					
	Left - fore and aft		D181					
	Left - lat.	Position measurement	D182	1 AMX	deg	10	$\pm 3$ V	LVDT

Table III - Aircraft Instrumentation  
(p) Position Measurements (cont.)

AN	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Gimbal trunnion flapping	Right rotor Left rotor	Position measurement	D110 D144	1 AMX	deg	10 10	±3 V	Rotary potentiometer
Red blade feathering	Right rotor Left rotor		D111 D066		deg	20 20		Rotary potentiometer
Collective motion	Right act. Left act.		D158 D183		in.	10		Linear potentiometer
Swashplate motion	Right - fore and aft Right - lat. Left - fore and aft Left - lat.		D159 D160 D184 D185		in.	10		Linear potentiometer
Conversion motion	Right pylon Left pylon	Position measurement	D161 D136	1 AMX	deg deg	10 10	±3 V	Rotary potentiometer Rotary potentiometer
Rotor azimuth	Right rotor Left rotor	One per rev 512 per rev One per rev 512 per rev	R018 R053 R058 R059	1 DMX *1 FM 1 DMX *1 FM	blip blip blip blip	digital digital digital digital		Photo cell encoder Photo cell encoder Photo cell encoder Photo cell encoder

\* Pallet has 40x80 connector for line driver; blip data.

512P also multiplexed @ lowest sub-carrier group.

location at about every 60° of rotor azimuth (Carbure location  
based on  $\Delta t = 50 \text{ SPS}$  (same rate). 7M track T/R also

Table III - Aircraft Instrumentation  
(q) Miscellaneous Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
<u>Aircraft state measurements</u>	Nose boom	Pitot port	P002	1 ANX	psi	10	±5 V	Pressure transducer
		Static port	P342		psi		±5 V	Pressure transducer
		Radar altimeter	D327		feet		0-40 V	Recorder output
		Temperature probe	T322		°F		3 mV	Total air temperature system
		Angle of attack	D008		deg		±3 V	Government-furnished equipment
Aircraft attitude	Nose boom	Angle of sideslip	D007		deg	10	±3 V	Government-furnished equipment
		Roll	D009				±3 V	Attitude gyro
		Pitch	D010				±3 V	Attitude gyro
		Yaw	D011		deg		±3 V	Attitude gyro
		Roll	V012		deg/sec		±2.5 V	Rate gyro
Aircraft angular rates		Pitch	V013		deg/sec		±2.5 V	Rate gyro
		Yaw	V014		deg/sec		±2.5 V	Rate gyro
Vertical acceleration	Aircraft cg		A352	1 ANX	g	10	±5 V	Servo accelerometer
<u>Aircraft systems monitors</u>								
Hydraulic system	Right pylon	Pressure #2	PL13	1 PSF	psi	100	±25 mV	Pressure transducer
	Left pylon	Pressure #1	PL18	1 PSF	psi	100	±25 mV	Pressure transducer
	Left pylon	Pressure #3 (standby)	FL49	1 PSF	psi	100	±25 mV	Pressure transducer

Signal input limited to ±10V

Table III - Aircraft Instrumentation  
(r) Miscellaneous Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Electrical system	Right	Dc generator - potential	E154	1 AMX	volt	100	0-28 V	Shunt
	Left	Dc generator - current	E155		amp	100	0-50 mV	
	Right	Dc generator - potential	E179		volt	100	0-28 V	
	Left	Dc generator - current	E180		amp	100	0-50 mV	
Fuel system	Right	Quantity	R320		lb	10		Recorder output
	Left	Quantity	R321		lb	10		
Temperature	Right wing, left wing, and fuselage	Thermocouples	T351	1 AMX*	°F	100	3 mV	Temperature scanner
Oil pressure	Right engine	Pressure	P323		psi	10		Pressure transducer
	Left engine	Pressure	P324	1 PSF	psi	10	±10 mV	
	Right trans-mission	Pressure	P325		psi	10		
	Left trans-mission	Pressure	P326		psi	10		
Aircraft Accelerations	Fore and aft	Accelerations	A301		g	50		Strain gage accelerometer
	Lateral		A300			50	±10 mV	
Aircraft center of gravity	Vertical		A005			50	±25 mV	Strain gage accelerometer
	Right - fore and aft		A150			100		
	Right - lat.		A151					
	Right - vert.		A152					
Pylons	Left - fore and aft		A175					Strain gage accelerometer
	Left - lat.		A176					
	Left - vert.	Accelerations	A177	1 PSF	g	100	±25 mV	Strain gage accelerometer

\* 1 CHAN AMX (Temp switch) temp ref 3 mV = 100°F

*Signal input limited to ±10V*

Table III - Aircraft Instrumentation  
(s) Miscellaneous Measurements (cont.)

Area	Location	Description	Item Code	Number & Type of Channels	Units	Response (hertz)	Approx Full Scale Xducer Signal Output	Transducer
Cockpit - pilot	Lateral	Accelerations	A302	1 PSF	g	50	±25 mV	Strain gage accelerometer
	Vertical		A019					
Cockpit - copilot	Lateral	Accelerations	A304	1 PSF	g	50	±25 mV	Strain gage accelerometer
	Vertical		A020					
Voltage sensor	RR1	J-Box Signal Power Supply Voltage	E072	1 AMX	Volts	10	0-10V	Power Supply
	RR2		E073					
	RP1		E196					
	RP2		E197					
	RW1		E647					
	RW2		E648					
	LR1		E074					
	LR2		E075					
	LP1		E198					
	LP2		E199					
	LW1		E649					
	CP1		E369					
	CP2		E370					
	CP3		E371					
	CAB1		E373					
	N1		E372					
Calibration Voltage	ENG 1	J-Box Signal Power Supply Voltage	E374	1 AMX	Volts	10	0-10V	Power Supply
	LNG1		E375					
	ENP1		E298					
	ENP2		E299					
	RNDU #1	Calibration Voltage	E367	1 AMX	Volts	10	0-10V	Power Supply
	RNDU #2	Calibration Voltage	E368	1 AMX	Volts	10	0-10V	Power Supply

Table IV.- Wind-Tunnel Data Requirements

MEASUREMENT #	DESCRIPTION	INPUT TSP	<del>PCM</del> Word	OGR	CRC	HS	TCS	DAS	P-P	DPH OBS	DAC	Load Ref
B122	Right Bld Beam 52.5		B1-10		2	1		29	1		A6	Load Ref
B132	Left " "		B1-8			2		30	2		A4	"
B123	Right " Chord		B1-20		6	3		28	3		A10	
B133	Left " " "		B1-9			4			4		A5	
F103	Right Pitch Link		B1-45			5		31	5		A24	Load Ref
F060	Left " " "		B1-21		3	6			6		A11	"
B165	Right Conv Spindle Beam		B1-57			7			7		A27	"
B190	Left " " "		B2-54			8			8		A29	"
B166	Right " " Chord		B2-57			9			9		A30	
B191	Left " " "		B1-55			10			10		A26	
F611	Right " " Actuator Load		B1-7			11			11		A3	
F638	Left " " "		A1-5			12			12		C1	
B112	Right Yoke Beam 9.0		B1-48		1	13			13		A25	
B114	Left " " "		B1-15			14			14		A7	
B113	Right " " Chord		B1-34		5	15			15		A18	Load Ref
B115	Left " " "		B1-16			16		27	16		A8	"



Table IV.- (Continued)

MEASUREMENT #	DESCRIPTION	INPUT TSP	<del>PCM Word</del> PCM Word	OGR	CRO	HS	TCS	DAS	P-P	DPH	OBS	DAC	Load Panel
B109	Right Lerp Mast Bending		A1-21			17			17			E4	
B141	Left " " "		B1-18			18			18			A9	"
M107	Right Mast Torque		B1-6			19		14	19	3		A2	"
M143	Left " " "		B1-5			20		15	20	2		A1	"
D156	Right F/A Flapping	T104				21		22	21				AC Cons
D181	Left " " "	T122				22		23	22				"
D157	Right Lat	T101				23		24	23				"
D182	Left " " "	T119				24		25	24				"
B656	Right Wing Beam 22	T107, 108,109				25	1	4	25				
B626	Left " " "	T125, 126,127				26	2	5	26				
B655	Right " Chord	T110, 111,112				27	3	6	27				
B625	Left " " "	T128, 129,130				28	4	7	28				
M657	Right " Torsion	T113, 114,115				29	5	8	29				
M627	Left " " "	T131, 132,133				30	6	9	30				
E747	Flapiron Exciter	T137				31		2					
E746	Collective	T140				32		3					

Table IV.- (Continued)

MEASUREMENT #	DESCRIPTION	INPUT TSP	<del>FROM WIND</del> FROM WIND	OGR	CRO HS	TCS	DAS	P-P	DPH	OBS	DAC
A150	Right Pylon F/A Accel		B1-37		33		16				A19
A175	Left " "		B1-30		34		17				A15
A151	Right " Lat "		B1-38		35		18				A20
A176	Left " " "		B1-31		36		19				A16
A152	Right " Vent "		B1-39		37		20				A21
A177	Left " " "		B1-32		38		21				A17
RSFAA	Right Strut F/A "	T004, 005,006			39	7	10				
LSFAA	Left " " "	T010, 011,012			40	8	11				
ESLAA	Right " " Lat "	T001, 002,003			41	9	12				
LSLAA	Left " " "	T007, 008,009			42	10	13				
B262	Right Horiz. Beam 8.0		B1-58		43		26	31			A28
B259	Left " " "		B2-60		44			32			A32
B263	Right " Chord "		B2-58		45			33			A31
F052	Right Swash Plate Driver		B1-44		46			34			A23
F14215	Left " " "		B1-24		47			35			A12
F162	Right F/A Control / and		B1-40		48			38			A22

Table IV.- (Continued)

MEASUREMENT #	DESCRIPTION	INPUT TSP	<del>PCM</del> Word	OGR	CRO HS	TCS	DAS	P-P	DPH OBS	DAC
F187	Left F/A Cyc Act Load		B1-27					39		A13
F163	Right Lat		A1-29		49			40		C5
F188	Left		B1-28		50			41		A14
F164	Right Collective		B1-19		51			42		B1
F189	Left		B1-29		52			43		B2
B120	Right Blade Beam 22.8		A1-12		53			36		C2
B130	Left		B1-43		54			37		B5
D158	Right Collective Pitch		B4-82		55					AC Cons B13
D183	Left		B3-79		56					B10
D159	Right F/A cyclic		B5-82		57					B15
D184	Left		B4-79		58					B12
D160	Right Lat		A2-72		59					AC Cons C6
M266	Right Horiz Torsion 80		B1-59		60					BUC E6
B124	Right Blade Beam 75		B1-35							BUC B3
B125	Left		B1-36							BUC B4
B126	Right		B1-16							BUC C3

Table IV.- (Continued)

MEASUREMENT #	DESCRIPTION	INPUT TSP	<del>AC M</del> Waved	OGR	CRO	HS	TCS	DAS	P-P	DPH	OBS	DAC	AC Cons
D185	Left Lat Cyc		B5-79									B14	
	Shaker excitation												"
	Az Right					(V)	(V)	(V)					
	Az Left					(V)	(V)	(V)					
	NPR Right					(V)	(V)	(V)					CTR 1
	NPR Left					(V)	(V)	(V)					CTR 2
D021	F/A stick pos		B 1-78							1		B7	
D022	Lat " "		B 2-78							4		B8	
D023	Power Lever		B 3-78							5		B9	
D024	Pedal		B 4-79							6		B11	

TABLE V: WIND-TUNNEL TEST RESPONSIBILITY

ITEM	PROJECT OFFICE			WIND-TUNNEL STAFF			CONTRACTOR		
	Responsibility	Review	Approval	Responsibility	Review	Approval	Responsibility	Review	Approval
<u>PLANNING</u>									
Test Plan			X		X		X		
Instrumentation Plan			X		X		X		
aircraft			X		X		X		
wind tunnel		X		X				X	
Systems Safety Analysis			X		X		X		
Test Readiness Report		X				X		X	
<u>HARDWARE</u>									
Aircraft		X			X		X		
Wind Tunnel									
Remote control		X			X		X		
Interface		X		X				X	
fuel & hydraulics				X					
electrical							X		
instrumentation				X					
Data displays									
wind tunnel				X					
console							X		
<u>OPERATIONS</u>									
Operators				X			X		
Inspect. & Maint.							X		
Test Direction	X			X			X		
Consumables				X					
Data reduction									
Wind tunnel				X					
PCM tape							X		
<u>REPORTING</u>									
Failure & Maint.		X					X		
Incident/Accident		X		X			X		
Systems Safety Rept.		X				X	X		
Test Report			X		X		X		




Figure 3-1.- Wind-tunnel test program management.




Figure 4-1 - Schedule for wind-tunnel test.





Figure 4-Z - Aircraft Schedule








(a) Front view

Figure 4-4.- The XV-15 in the 40- by 80-Foot Wind Tunnel



(b) Side view  
Figure 4-4. Concluded





Figure 4-5.- Rotor/tunnel wall clearance for the XV-15  
in the 40- by 80-Foot Wind Tunnel



78.5' x 49' TOP DOOR OPENING




Figure 4-6.- Hoisting arrangement.





Figure 4-7.- Flight controls schematic.



(a) Control panel  
Figure 4-8.- Remote control console

LH MAST TORQUE M :43	RH MAST TORQUE M 107	LH SPINDLE BENDING B 140	RH SPINDLE BENDING B 165
LH MAST BENDING B 141	RH MAST BENDING B 109	LH RED BLADE PITCH LINK F 060	RH RED BLADE PITCH LINK F 109
LH YOKE CHORD B 115	RH YOKE CHORD B 113	LH RED BLADE BEAM STAKE B 132	RH RED BLADE BEAM STAKE B 122

(b) Loads panel

Figure 4-8. - Concluded.






Figure 4-9 . — Wind-Tunnel Control Room




Figure 4-10 . — Fuel System Schematic








Figure 4-13 - Electrical system block diagram




Figure 4-14.- Data system block diagram




Figure 6-1.- Organizational structure of support elements.




Figure 6-2. - Wind-tunnel staff organization.



1. Report No. NASA TM-78562 AVRADCOM Tech. Rep. 79-7(AM)		2. Government Accession No.		3. Recipient's Catalog No.	
4. Title and Subtitle NASA/ARMY XV-15 TILT ROTOR RESEARCH AIRCRAFT WIND-TUNNEL TEST PROGRAM PLAN				5. Report Date	
				6. Performing Organization Code	
7. Author(s) James A. Weiberg and Martin D. Maisel				8. Performing Organization Report No. A-7740	
9. Performing Organization Name and Address Ames Research Center, NASA, and AVRADCOM Research and Technology Laboratories Moffett Field, Calif. 94035				10. Work Unit No. 744-01-01	
				11. Contract or Grant No.	
12. Sponsoring Agency Name and Address National Aeronautics and Space Administration, Washington, D. C. 20546 and U.S. Army Aviation Research and Development Command, St. Louis, MO 93166				13. Type of Report and Period Covered Technical Memorandum	
				14. Sponsoring Agency Code	
15. Supplementary Notes					
16. Abstract  The program plan for conducting wind-tunnel tests of the NASA/Army XV-15 Tilt Rotor Research Aircraft is described. This aircraft is a proof-of-concept vehicle and a research tool for integrated wind tunnel, flight simulation, and flight test investigations. Discussions of special design provisions, safety considerations and management structure for conduct of the wind-tunnel tests are included in this report.					
17. Key Words (Suggested by Author(s))  V/STOL tilt rotor Research aircraft Wind tunnel test			18. Distribution Statement  STAR Category - 05		
19. Security Classif. (of this report) Unclassified		20. Security Classif. (of this page) Unclassified		21. No. of Pages 74	
				22. Price* \$4.50	