



TWR-17272 Vol. VIII

**Flight Set 360L001 STS-26
Systems Tunnel Component Final Report
Volume VIII
Final Release**

14 April 1989

**(NASA-CR-183710) FLIGHT SET 360L001 STS-26
SYSTEMS TUNNEL COMPONENT, VOLUME 8 Final
Report (Morton Thiokol) 10 p**

N89-71398

**00/20 Unclass
0224008**

**NATIONAL AERONAUTICS AND SPACE ADMINISTRATION
GEORGE C. MARSHALL SPACE FLIGHT CENTER
MARSHALL SPACE FLIGHT CENTER, ALABAMA 35812**


**Contract No. NAS8-30490
DR. No. 3-5
WBS.No. 4B601-04-01
 ECS SS-0956**

MORTON THIOKOL, INC.

Aerospace Group

Space Operations

P.O. Box 707, Brigham City, Utah 84302-0707 (801) 863-3511



DOC NO.

TWR-17272 Vol. VIII

REV

L212-FY89-M234

TITLE

Flight Set 360L001 STS-26
Systems Tunnel Component Final Report
Volume VIII
Final Release

14 April 1989

Prepared by:

M. Perry
M. Perry
Insulation Design

Concurred by:

Steve Hicken
S. Hicken, Group Leader
Insulation Design

R. Kirby
R. Kirby
Component Design

Approved by:

F. Baugh
F. Baugh, Supervisor
Insulation Design

D. M. Ketner
D. Ketner, Manager
Motor Performance

James M. Seiler 5/12/89
J. Seiler
Project Engineer

B. Crosbie
B. Crosbie
Program Manager

Fred Dursch Jr.
Reliability Assurance
Liaison/Problem Reporting

R. Williams
K. Sanofsky
Systems Safety

MORTON THIOKOL, INC.

T. A. O'Brien
Certification Planning

Space Division

P.O. Box 524, Brigham City, Utah 84302-0524 (801) 863-3511

P. Tydeck
P. Tydeck 5-12-89
Release
ECS SS-0956

MORTON THIOKOL INC.

Aerospace Group

Space Operations

ABSTRACT

Volume VIII deals with the systems tunnel component of the RSRM-1 flight set. Postflight inspections of the floor plate and splice plates, the thermal protection system and the bondlines are discussed. All observations were as expected, with no problems seen.

REVISION _____

FORM TC 7994-310 (REV 2-88)

DOC
NO.
SEC

TWR-17272

VOL VIII

PAGE

i

MORTON THIOKOL INC.

Aerospace Group

Space Operations

ACRONYMS

EPDM Ethylene Propylene Diene Monomer
KSC Kennedy Space Center
PEEP Postflight Engineering Evaluation Plan
RSRM Redesigned Solid Rocket Motor
STS Space Transportation System
TPS Thermal Protection System
USB I United Space Boosters, Inc.

REVISION _____

FORM TC 7994-310 (REV 2-88)

DOC			
NO.	TWR-17272	VOL	VIII
SEC		PAGE	ii

MORTON THIOKOL INC.

Aerospace Group

Space Operations

CONTENTS

<u>Section</u>	<u>Page</u>
1.0 INTRODUCTION	1
2.0 OBJECTIVE	1
3.0 SUMMARY	1
4.0 CONCLUSION	1
5.0 RECOMMENDATION	2
6.0 DISCUSSION	2
REFERENCES	3
DISTRIBUTION	5

Figures

<u>Figure</u>	<u>Page</u>
1 Systems Tunnel Cross Section	4

REVISION _____

FORM TC 7994-310 (REV 2-88)

DOC NO.	TWR-17272	VOL	VIII
SEC	PAGE	iii	

1.0 INTRODUCTION

STS-26 was launched from KSC pad 39B on 29 September 1988. Two of the RSRMs were part of the launch system and are designated by RSRM-1A (360L001A) and RSRM-1B (360L001B). Both motors incorporated the aluminum floor plate systems tunnel as shown in Figure 1. Following booster separation and splashdown, the motors were recovered and returned to Cape Canaveral Hangar AF for disassembly and inspection.

In an attempt to standardize and document the evaluation of flight RSRM's, a PEEP has been written (Reference 1). The PEEP outlines the basic evaluations to be performed at Hangar AF. Appropriate procedures contained in this plan were used to evaluate the systems tunnel component. The intent of these procedures is to insure that all pertinent evaluation points are examined and documented in a consistent and complete manner.

2.0 OBJECTIVE

The objective of this report is to document the postflight condition of the systems tunnel components used on RSRM-1A and RSRM-1B.

3.0 SUMMARY

The TPS coated covers were observed to be intact and undented during open assessment. Small areas of paint blistering and TPS pock marks were observed. Sooting was seen on the TPS surface, but not in the pock marks, indicating damage due to splashdown. Following open assessment, hydrolaze removal of the systems tunnel TPS was performed. Inspection of the Morton Thiokol components and bondlines followed decabbling. No loose, missing or damaged components were seen. The shear ply to case and shear ply to aluminum floor plate bondlines appeared perfect.

4.0 CONCLUSION

Insulation and Component Design found no reportable conditions and concluded the RSRM-1A and RSRM-1B systems tunnel components performed as designed.

5.0 RECOMMENDATION

Insulation and Component Design recommend that the systems tunnel component continue to be inspected postflight to verify performance as designed.

6.0 DISCUSSION

The first inspection (visual) of the RSRM-1A and RSRM-1B systems tunnels was performed during open assessment, immediately following removal from the water, safing of the linear shaped charge and prior to hydrolazing. The inspection of the tunnel covers is performed to find potential damage to Morton Thiokol's underlying components. The system tunnel covers and TPS coverings are the responsibility of United Space Boosters Inc. The system tunnel covers were intact and undented. Small areas of paint thermal-blistering and TPS pockmarks were noted on the bondline cork insulation, typically less than an inch in diameter. The pock marks were shallow, typically less than 0.1 inch deep, and attributed to nozzle severance and splash-down debris. No sooting or heat effect was evident within the pocks.

Following open assessment, the boosters were moved into the hydrolazing bay to remove bondline insulation (cork, STW4-2700) and the tunnel cover TPS (K5NA (STW5-3183) and a USBI ablative material). Cover removal and decabling followed. The exposed floor plates, splice plates and bondlines were then inspected. The plates and associated structures were all intact, undamaged and firmly held in place. The shear ply to case and shear ply to aluminum floor plate bondlines were visually inspected and probed with a steel rule every 6 to 12 inches on both sides of the systems tunnel. No unbonds or bondline voids were detected.

In addition to the postflight assessments, a pull test was performed on some of the system tunnel floor plates at the Clearfield H-7 facility to develop new proof test loadings (See Reference 2).

MORTON THIOKOL INC.

Aerospace Group

Space Operations


REFERENCES

1. TWR-16475 Vol. VIII Book 1, 'KSC Postflight Engineering Evaluation Plan (Systems Tunnel Component)', S. Olsen and J. Bailey, 1 September 1988.
2. TWR-18865, 'STS-26 Postflight Systems Tunnel Aluminum Floor Plate Pull Test Report', M. Perry and B. Traveller, January 1989.

REVISION _____

FORM TC 7994-310 (REV 2-88)

DOC NO.	TWR-17272	VOL	VIII
SEC	PAGE	3	



Systems Tunnel Cross Section

Figure 1

REVISION _____

FORM TC 7994-310 (REV 2-88)

DOC
NO.
SEC

TWR-17272

VOL VIII

PAGE

4

MORTON THIOKOL, INC.

Aerospace Group

Space Operations

DISTRIBUTION

F. Baugh	L21
S. Hicken	L21
R. Hyer	L10
D. Ketner	L21
R. Kirby	L23B
M. Loosle	851
B. McQuivey	L10
S. Medrano	L10
T. Morgan	L10
M. Perry	L21
K. Sanofsky	851
J. Seiler	L10
Insulation File	L21
Print Crib (5)	K23B1

REVISION _____

FORM TC 7994-310 (REV 2-88)

DOC NO.	TWR-17272	VOL	VIII
SEC	PAGE	5	