

1811

2N-81-TM
190591

COST CONTAINMENT AND KSC SHUTTLE FACILITIES

OR

COST CONTAINMENT AND AEROSPACE CONSTRUCTION

BY

JOSEPH ANDREW BROWN, CCE

KSC FACILITIES ENGINEERING DIVISION
LEAD COST ENGINEER
KSC HEADQUARTERS BUILDING ROOM 3638E
KENNEDY SPACE CENTER, FLORIDA 32899
(305)----867-3268

29th ANNUAL AACE MEETING
JULY 1-3, 1985
DENVER, COLORADO

(NASA-TM-109320) COST CONTAINMENT
AND AEROSPACE CONSTRUCTION (NASA)
11 p

N94-70592

Unclass

Z9/81 0190591

COST CONTAINMENT AND KSC SHUTTLE FACILITIES OR COST CONTAINMENT AND AEROSPACE CONSTRUCTION

Joseph A. Brown

INTRODUCTION

The purpose of this presentation is to show examples of Cost Containment of Aerospace Construction at Kennedy Space Center that were used in the four major levels of Project Development of the Space Shuttle Facilities. The Levels are: 1. Conceptual Criteria and Site Selection; 2. Design - of Construction and Ground Support Equipment; 3. Construction of Facilities and Ground Support Equipment (GSE); 4. Operation and Maintenance. These Cost Containment methods were so successful that the Space Shuttle is now operational with three (3) Orbiters - Columbia, Challenger, and Discovery, now scheduled for monthly launches and landings in 1985.

Space Shuttle Estimating - Cost Management Background

The concept of the Kennedy Space Center (KSC) Shuttle facilities was developed in late 60's and early 70's based on limited criteria, reuse of Apollo facilities, as much as possible and two simultaneous Shuttle-Orbiter flows, was conceptually costed by KSC's Design Engineering March-October 1970.

The conceptual construction cost estimate of facilities was \$147,573,000, which included 10% contingencies and 7% S&A. This was further developed and escalated to \$297,330,000 and included GSE equipment.

The construction of facilities was budgeted in the early 1970's at \$150 M of 1970 dollars. The actual in-place cost through April 1980 was \$225.3 M which is about 2% less than the original escalated budgeted amount. Quite a remarkable achievement. Some important scope changes that made this cost management more critical was the added Sound Suppression System and the redesign of the Rotary Service Structure for extra Air Force requirements after bidding LC-39 Pad A (during construction of the foundation).

A summary cost breakdown for the Cof F Shuttle	<u>Millions</u>
Orbiter Landing Facility	27.3
Orbiter Processing Facility	27.4
Launch Complex 39 Pad A	40.4
Launch Complex 39 Pad B	51.7
Mobile Launcher Platform #1	13.8

COST CONTAINMENT AND KSC SHUTTLE FACILITIES OR
COST CONTAINMENT AND AEROSPACE CONSTRUCTION

Joseph A. Brown


Mobile Launcher Platform #2	13.9
Vehicle Assembly Building	23.8
Launch Control Center	2.0
Solid Rocket Booster Disassembly (Hangar AF)	6.2
Parachute Facility	1.7
Hypergol Maintenance Facility	5.3
Launch Equipment Test Facility	2.0
Rehabilitation of Barge Channels	2.1
Construction Emergency Power Facility	2.2
Mods to Crawler Transporter Maintenance Facility	1.3
Shuttle/Carrier Aircraft Mating Facility	1.7
Miscellaneous Modifications	<u>2.5</u>
Subtotal Shuttle	225.3

The successful construction of the KSC Shuttle facilities under budget on schedule is a tribute to the remarkable KSC Design Engineering and construction management team. This is especially noteworthy for a research and development project. Many Research & Development (R&D) projects during the 70's were costing two times to three times budgeted costs due to the energy crisis; social, environmental and economical regulations; environmental requirements and concerns, and erratic (volatile) economy.

These, and many other problems, were solved by fast tracking, detail planning and scheduling, cost and design engineering solutions through an unusual efficient construction management program.

See Figure A, page 3, for KSC major Facilities Pictorial Baseline.
See Figure B, page 3, for the Space Shuttle Mission Profile.

Aerospace construction is similar to building, civil, petro-chemical process industry, construction in that it uses concrete, steel, form work and most conventional materials but it is different and more costly due to its higher



KSC Major Shuttle Facilities - Pictorial Baseline

FIGURE A




FIGURE B

COST CONTAINMENT AND KSC SHUTTLE FACILITIES OR COST CONTAINMENT AND AEROSPACE CONSTRUCTION

Joseph A. Brown

reliability requirements, tolerance, and safety requirements because of the hazardous operations, remote controlled fuels and gases and some exotic materials.

EXAMPLES OF COST CONTAINMENT AND KSC SPACE SHUTTLE FACILITIES

Level I Conceptual Criteria and Site Development

A. KSC was selected as the major launch and landing site after studying six locations throughout the United States of America (USA). They were White Sands Missile Range, Western Test Range, Edwards AFB, Wendover AFB, Ideal Location, and Kennedy Space Center (KSC). KSC was selected because it was the most cost effective for the following reasons:

1. Lower facility construction cost. Do to reuse of Apollo Launch Facilities. Example use of VAB, Launch Pads, and Crawleraway. This was proven by excellent Conceptual Cost Estimating and Cost /Engineering for all six locations. This has been documented in KSC Design Engineering Study dated October 1970.
2. Lower cost by using existing downrange tracking facilities.
3. Provides the safety of over water launches. (See Figure B)
4. Less environmental effect than other locations.
5. More payload boost with less fuel at this latitude or giving an extra 1000 pound payload per launch.

B. The location of new buildings and facilities was again for cost containment by locating the new Shuttle Landing Facility (SLF) near the Vehicle Assembly Building (VAB)/Crawleraway and Launch Pads. The Orbiter Processing Facility (OPF) was located on the Towaway between the SLF and the VAB, See Figure A - This was done to keep costs contained due to the high cost of new roads, utilities, etc.

C. The criteria was developed by a team effort National Aeronautics and Space Administration (NASA) Civil Service/Private Industry/Support Contractors/ Architect Engineers/Construction/ Aerospace Contractors.

The conceptual criteria and site selection is providing a good choice as noted in Space Shuttle Estimating Cost Management Background, as under budget and on schedule and by fourteen successful launches and two landings at KSC.

6

COST CONTAINMENT AND KSC SHUTTLE FACILITIES OR
COST CONTAINMENT AND AEROSPACE CONSTRUCTION

Joseph A. Brown

Level 2 Design of Construction and GSE

Examples of Cost Containment at this Level are:

1. The use of design to cost limits in Architect/Engineers (A&E) Contracts.
2. Cost Engineering throughout the design cycle in budget, Preliminary Engineering Report (PER) at the 30%, 60%, 90% and 100% design milestones, see SRB Comparison of Budgeted and Estimated Cost. See Figure C. paage 7.
3. The use of Consultants where needed.
4. The use of the Construction Management Concept for many major projects. Examples: Pad B, Mobile Launch Platform #3 (MLP).
5. The use of Detail Planning and Scheduling and Fast-tracking to save time and money. Example of Phased design are the runway in three phases, the Launch Pads and MLP's.
6. The use of Computer Aided Design/Drafting.
7. The special use of cost engineering by developing new estimating specification - (Construction and GSE) a KSC Cost Index, an Aerospace Price Book, A Summary of Abstract of Bids, and A Cost Engineering Format for Construction Management. With these tools the engineers were able to recognize cost/value. An example was the use of aluminum duct in the Orbiter Processing Facility (OPF) to provide clean air to high bay. The A&E had designed a stainless steel duct system which cost \$250,000 extra. This helped keep the cost of the OPF within the budget. Millions of dollars of other saving have been documented in piping, cabling, and bridges and GSE.
8. The use of working models so engineers and others could understand and make it work - better - especially useful on Rotary Service Structure (RSS), GSE, Platforms.

Level 3 - Construction, Fabrication Assembly and Testing

Examples of Cost Containment are:

1. Coordinated Design Engineering (DE) /A&E/Construction Contractor/Vendors/Fabrications and Government Furnished Equipment (GFE).

COST CONTAINMENT AND KSC SHUTTLE FACILITIES OR COST CONTAINMENT AND AEROSPACE CONSTRUCTION

Joseph A. Brown

2. The use of detail and overview planning and scheduling, Critical Path Method (CPM), Quality Control, and Safety Requirements.
3. Construction Inspection and Site Surveillance.
4. Pre-Bid and Pre-Work Conferences.
5. By using unit prices in bid to help eliminate contractor contingencies, example: Shuttle Landing Facility (SLF), (Excavation), Launch Complex (LC) 39 Pad B - Piling.
6. By using contract clauses such as joint occupancy, downtime, etc., in major contracts where needed. It allowed the government to Bid Change Orders - If necessary - Mobile Launch Platform (MLP) 2 and Pad A sound Suppression, etc.
7. Trying to limit design changes - Is it that necessary?
8. By reviewing the Government Estimate with the Low Bidder when a large difference. Show some contractor's their mistakes thus giving the government better and more complete construction with less claims.
9. By Phased Construction of Runway, Launch Pads, MLP's, Shuttle/Carrier Aircraft Mating Facility.

The effectiveness of KSC Cost Containment was again proved by construction completion on schedule and under budget.

Level 4 - Operations and Maintenance

In construction this may be referred to as Occupancy and Use Phase. Some examples of cost containment at this level are:

1. The continued use and reuse of existing facilities some to be used up to 325 times such as VAB, Crawler, and Crawlaway and Launch Pads, etc.
2. The reuse of most parts of the Shuttle Fleet. Such as the Orbiters to be reused up to 100 times and the Solid Rocket Booster (SRB) Shells and casings to be used up to twenty-five times.

FIGURE C

COMPARISON OF BUDGETED AND ESTIMATED COSTS									
DRAWING NUMBER	79C21364 SPECS. 79C21365 DAG.	SHEETS	860 154	PCN	81302	LOCATION	KSC	ESTIMATOR G.L. FILES, DMM	CHICKEN
ARCHITECT/ENGINEER	DANIEL, MANN, JOHNSON & HENDERSON	1979	NOT SHOWN	6-5-81	7-8-81	8-13-81	10-23-81	12-16-81	3-12-82
BUDGETED COSTS		%	CODE	B-30	%	CODE	B-30	%	CODE
BUDGETED LINE ITEMS		%	CODE	B-30	%	CODE	B-30	%	CODE
I SITEWORK									
II BLDG. STRUCTURE									
R/P BLDG.									
ARCH/STR	4,504,550	-10	4,063,000	-4	2,895,000	-2	2,960,000	-1	2,960,000
MECHANICAL	120,600	+21	145,300	-27	106,050	+25	132,840	+12	148,412
ELECTRICAL	654,750	-18	375,000	-4	361,600	-9	329,800	+3	340,010
R/P TOTAL	5,079,900	-10	4,583,300	-5	4,362,650		4,422,640	-1	4,362,780
SUPPORT BLDG.									
ARCH/STR	257,960	+13	291,500	-8	267,000	-16	274,800	-46	120,450
MECHANICAL	54,480	+41	79,920	-22	59,670	+3	61,600	+5	64,670
ELECTRICAL	41,760	+47	270,000	-84	42,200	+24	52,270	+15	60,070
S.B. TOTAL	354,200	+80	638,420	-42	368,870	-8	338,670	-28	245,190
STORAGE/SURGE BUDS.									
ARCH/STR	1,195,900	+22	1,456,000	-8	1,335,660	+2	1,366,800	-10	1,225,380
ELECTRICAL	66,600	+36	90,800	+8	98,400	+10	108,000	-10	96,960
S/S.B. TOTAL	1,262,500	+23	1,546,800	-7	1,434,060	+3	1,474,800	-10	1,322,340
UTILITIES TOTAL	653,250	+4	682,000	+16	793,700	+24	980,900	-4	941,400
PLC WITHOUT SPL. COND.	8,039,100	0	8,024,270	-6	7,559,280	+3	7,786,610	-4	7,482,522
ESCALATION/SPL. COND.	1,951,351	-19	1,588,780	-31	1,095,820	-3	1,066,590	-20	851,368
SUB-TOTAL	9,990,451	-4	9,613,000	-10	8,655,100	+2	8,853,200	-6	8,333,890
SUPER. & ADMINISTRATION	1,012,033	-5	961,100	-11	858,800	+3	885,300	-6	832,810
CONTINGENCIES	1,112,061	-5	1,054,900	-10	949,800	+2	973,700	-6	914,300
USE	12,114,545	-4	11,629,000	-10	10,463,700	+2	10,712,200	-6	10,081,000
IV SPECIALIZED CONSTR.	735,400	+24	910,000	-4	870,000	-18	711,000	0	721,000
TOTAL	10,200,000		12,849,945	-2	12,539,000	-10	11,423,200	-5	10,802,000
PER DIFFERENCE, BUDGETED/ESTIMATED TOTALS		+26		+23		+12		+1	

NOTES: PROJECT: \$10,200,000 BUDGET. \$2,200,000 TWO 200 TON BRIDGE CRANES. (1) BRIDGE CRANES N/C. (2) STEEL, TONNAGE REDUCED. (3) STEEL PRICE INCREASED. (4) B-30 HAD REMAINING MARK UPS. (5) STEEL TONNAGE REDUCED. (6) 54.7% INCREASE DUE TO ADDED 2,000 RVA SUB-STATION. (7) SCOPE CHANGE TO TWO 8 SEGMENT STORAGE/SURGE BUDS. (8) STEEL TONNAGE REDUCED. (9) SUB-STATION TRANSFERRED FROM BLDG. TO SITE. (10) CHANGE IN SCOPE AND SITE. (11) ESCALATION CHANGED FROM 1.7% TO 9.7% PER YEAR. (12) DETAILS ON PLATFORM WORK INDICATE MORE WORK THAN PROVISIONALLY ALLOWED. (13) CHANGED TO PRE-FAB BLDG. (14) REDUCED BLDG. SIZE. (15) CHANGED PLATFORM DECK FROM ALUMINUM TREAD PLATE TO GALV. STEEL. (16) LABOR RATE INCREASE. (17) ADDED SPL. SYSTEMS. (18) CHANGED ROOF INSULATION. (19) ADDED REQUIREMENT FOR BORING & JACKING. (20) SLIP IN SCHEDULE. (21) DESIGN DEVELOPMENT. (22) \$9,513,490 PLUS \$1,798,000 (CRANE BID) = \$11,311,490. -9% DELTA OF \$12,400,000 TOTAL PROJECT BUDGET. (23) REDUCED BY 10-FED-1 AND -31.

COST CONTAINMENT AND KSC SHUTTLE FACILITIES OR
COST CONTAINMENT AND AEROSPACE CONSTRUCTION

Joseph A. Brown

3. The special Research and Development (R&D) effort to develop efficient cost effective GSE such as Special Mechanical/Machinery and Platforms to speed operations, maintenance and check-out - Transporters, canisters, dollies, handling equipment, remote controlled electronic mechanical systems, swing arms, etc.
4. Re-bid and consolidation of Operation Support Contractors - Example: Shuttle Processing Contract (SPC). Combining many contractors to Lockheed, Base Operation Contract (BOC), EG&G, and any future Cargo Processing Contracts (CPC).
5. Providing mass purchasing for large use items such as a GN₂ Manufacturing Plant build by Big 3 at Gate 2, State Road 3.
6. Continuing effort to contain cost by studying other potential savings such as polygeneration to save rocket fuel and energy cost.
7. The use of full scale mock-ups to test and check-out Facilities and Operation. The "enterprise" Orbiter check-out of VAB and Launch Pad Rotary Service Structure.

The success of these cost containment methods has again been proven by the continued reduction of processing time from landing to launching.

Conclusion

The real proof of the success of The Cost Containment of the KSC Shuttle Facilities will be known at the successful completion of the Space Shuttle Era and its use in the Proposed Space Station Program scheduled for 1992-93. In the mean time these facilities are being used to successfully process, check-out, launch and recovery elements of the Space Transport System which assures the United States continued pre-eminence in Space Exploration and Development.

COST CONTAINMENT AND KSC SHUTTLE FACILITIES OR
COST CONTAINMENT AND AEROSPACE CONSTRUCTION

Joseph A. Brown

REFERENCES

1. Brown, Joseph A., June/July 1975, KSC Cost Index for Constr. Mgmt. 19th Annual AACE Mtg, Orlando, FL.
2. Brown, Jos. A., July 1979, Constr. Bid. Cost of KSCs Space Shuttle Fac. 23rd Annual AACE Mtg, Cincinnati, OH.
3. KSC Tech. Report, Dec. 1984, TR-1508, Budget Cost Data for Fac. Constr. Elements
4. KSC Tech. Report, Sept. 15, 1984, TR-1511, KSC Monthly Fac. Constr. Cost Index
5. Brown, Jos. A., July 1980, Conceptual Cost Est. using KSC Cost Index for Constr. Mgmt., 24th Annual AACE Mtg, Wash. D.C.
6. KSC/DD-FED, Jan. 1974/Oct, 1984, Abstracts of Bids Cost Summary
7. Brown, Jos. A., June 1977, KSC Est. Format for Constr. Mgmt., 21st AACE Annual Mtg, Milwaukee, Wis.
8. Space Transp. Sys. - Fac. & Opns, KSC-K-STIS-MO-1, Appx. A.
9. Brown, Jos. A., How to Sharpen you Bidding thru Plan Read., Cost Est., Cost Engr. and Constr. Mgmt. Est. Workbooks, Vol. II, 10-28, 1977-1984
10. Rand Corp. Dept. Energy Study R-2481, Cost Growth in Pioneer Energy Process Plants in Constant Dollars
11. KSC Design Engr. Study of Cost Est. for Horizontal Concept - Locations - Ideal, KSC White Sands, Western Test Range, Edwards AFB and Wendover AFB, Oct. 1970.
12. Brown, Jos. A., Feb. 1982, Conceptual Cost Est. using KSC Budget Cost Data for Constr. Mgmt of Space Shuttle Fac., 11th Annual Winter Symposium, Miami, FL
13. Brown, Jos. A., Aerospace Construction Price Book, 7th International Cost Engineering Congress, London, England, Oct. 5-6, 1982
14. Brown, Jos. A., Construction Estimating - Cost Engineering - Construction Management, Seminar Workbook, Volume II, Philadelphia, PA, 1983, p.104-164.

COST CONTAINMENT AND KSC SHUTTLE FACILITIES OR
COST CONTAINMENT AND AEROSPACE CONSTRUCTION

Joseph A. Brown

15. KSC Compiling Constructions Cost Estimates Specification, G0002, Rev. A, Aug. 1980.
16. KSC Ground Support Equipment Cost Estimating Specification, G0003 - July 5, 1977

BIOGRAPHY

JOSEPH ANDREW BROWN, CCE

Lead Cost Engineer for KSC Facilities Engineering Division, DD-FED, Kennedy Space Center, Florida 32899

Biography: Mr. Joseph A. Brown is employed as a Lead Cost Engineer for the National Aeronautics & Space Administration's Design Engineering Directorate. He prepares and reviews government and contractor's construction and GSE cost estimates of over \$3 billion for design, fabrication and construction. He has received AACE's admission to grade of Fellow and the prestigious astronaut's "Silver Snoopy" for professional excellence and his contributions to the success of our manned space efforts. He has written an Estimating Workbook and is writing "Estimation of Construction Costs and Cost Engineering." He has conducted Construction Cost Engineering Seminars from Miami to Montreal, Canada.

