Conductron Corporation

FINAL REPORT

RADOME FACILITY

Report No. 0038-RF-1

Prepared For:

National Aeronautics and Space Administration
Goddard Space Flight Center
Greenbelt, Maryland

Under:

Contract No. NAS 5-3232

Comsat Research Branch Code 625

CONDUCTRON CORPORATION
343 S. Main Street
Ann Arbor, Michigan

TABLE OF CONTENTS

TABLE OF ILLUSTRATIONS

1. INTRODUCTION

This report describes work performed under Contract No. NAS-5-3232 dealing specifically with the construction, installation and check out of a radome measurement facility located at the Conductron Radar Cross Section Measurement Range in Augusta Township, Washtenaw County, Michigan. The purpose of this facility is to provide a capability for the electrical evaluation of passive communications satellite materials.

The report discusses the support facility, the radome, the radome installation and electrical evaluation, and the facility instrumentation. As presently designed this facility provides a capability for measuring the microwave reflection and transmission characteristics of reflective materials. Twenty-two foot segments of passive communications satellites up to 400 feet in diameter can be evaluated. With this fixture, it is possible to maintain the segment radius of curvature as material skin stress increases for any material which would be practical in the design of passive communications satellites.

2. RADOME SUPPORT FACILITY

The radome support facility encompasses all of the structures which are necessary to make the test site operational but which, because of their nature, cannot be removed from the site. These structures include the working buildings and storage space, the concrete runways around the site, and the hydraulic equipment in the radome. A complete set of facility drawings is shown in Appendix A.

All working buildings and storage areas were constructed underground for the purpose of minimizing radar reflection problems. There are two separate underground rooms. The master control room is located at one end of the facility and the radome equipment room is located at the other end, directly under the radome. The general layout and size of these rooms is shown in Appendix A.

A picture of the master control room is shown in Figure 2.1. This room has a floor space of approximately 324 square feet and houses all microwave equipment, pressure monitoring equipment, and position monitoring and control equipment for both the antennas and the test fixture. A reinforced concrete slab floor, 4 inches thick, rests on reinforced concrete perimeter footings 20 inches deep by 12 inches wide. A minimum of 4 inches of sand fill was used under the floor. The walls are constructed of 12 inch concrete block reinforced every third course with "Wal-Lock" and waterproofed with two coats of Thoroseal. The ceiling was slightly pitched and constructed of preformed concrete slabs 18 feet long, 4 feet wide and 5 inches thick, which span the exterior walls. The finished ceiling was intentionally constructed to be below the final grade level so that final grading could be accomplished by gravel fill. The gravel and the slight pitch which was built into the ceiling prevent an excessive amount of ground water from accumulating. Access to the room is gained by a set of wooden stairs which were made portable so that heavy, delicate equipment, such as microwave receivers and recorders, could be transported by an overhead crane. The floor plan of the rooms underneath the radome is shown in Appendix A. As can be seen, the general room area is irregular in shape, conforming to the circular contour of the radome pad support footing. The total floor space is approximately 672 square feet. The outside walls are recessed 12 inches from the radome pad footing and are constructed of 12 inch concrete block. These walls are reinforced every third course with "Wal-Lock" and are sealed on the outside with two coats of Thoroseal. The interior walls are constructed of 8 inch block and are also reinforced every third course



Figure 2.1 Master Control Room

with "Wal-Lock".

The blower room has a floor space of approximately 200 square feet and houses the radome inflation blower system and the emergency power system, which are discussed in detail in Section 3 of this report, and shown in Figure 3.2. The duct which supplies make-up air for the blower system was brought in through one wall of the blower room. The air duct is constructed of preformed concrete pipe, having an inside diameter of 30 inches, and is approximately 195 feet long. The positioning of the duct is shown in Appendix A. The primary reason for the length of the duct is that in order to provide enough air, the intake port must be removed from any obstruction which might cause turbulence. The radome causes significant air turbulence under windy conditions. The duct also provides a method for running instrumentation cables between the radome and the master control room. An eight inch duct connects the master control room to the make-up air duct for this purpose.

The furnace room has a floor space of approximately 200 square feet and houses the furnace, the hydraulic pump and the hydraulic fluid storage units. The furnace is described in Section 3.3 of this report and shown in Figure 3.4. The hydraulic system is discussed below.

The concrete runways provide surfaces over which materials and equipment can be moved with a minimum of difficulty. The runway which is shown as the bistatic track in Appendix A provides a surface for movement of the antenna towers. This track is 86.5 feet long, 8 feet wide and 5 inches thick, and rests on a minimum of 1 foot of sand fill. The front edge of the track is a 30 degree segment of a circle 150 feet in radius. The runway which connects the bistatic track to the radome pad is 120 feet long, 12 feet wide and 5 inches thick, and also rests on a minimum of 1 foot of sand fill.

The radome pad is made of reinforced concrete and is 64 feet in diameter and 6 inches thick. It rests on a reinforced footing, 48 inches deep by 10 inches wide, extending around the entire perimeter. Part of the pad serves as the ceiling for the underground rooms and the remainder was constructed over at least 2 feet of sand fill. The pad surface within the radome is flat while outside, the pad slopes sharply down to the final grade level in order to provide drainage.

The radome is attached to the pad by means of anchor bolts set in the concrete. Being an air supported structure, the radome exerts a considerable lifting force on

the attachment bolts. In the maximum pressure condition the total lifting force is in excess of 200,000 pounds. A total of 96 anchor bolts are used (as shown in Drawing No. Sk 1946 in Appendix A) making the lifting force on each bolt slightly in excess of 2,000 pounds. The anchor bolts are welded to reinforcing rods which extend around the entire radome perimeter. These rods are attached periodically to other rods which extend down into the footings. This is shown in detail in Appendix A. The attachment method spreads the lifting force uniformly over the attachment area and provides a uniform surface which will not be affected by frost heaving.

A hydraulic system has been installed inside the radome to lift the test fixture above the radome floor so that radar reflection and transmission measurements can be made. The hydraulic post and cylinder was manufactured by the Joyce-Cridland Company and has 14 feet of travel. The post is shown in the fully extended position in Figures 4.1 and 4.2. The post is powered by a single phase 220 Volt electric pump rated at 5 hp. Hydraulic fluid reservoirs having a total capacity of 132 gallons have been provided. This equipment is shown in Figure 2.2. A non-rotating device has been incorporated into the system so that a fixed angular reference can be obtained. The height of the hydraulic post is controlled by means of push button switches located in the stairwell leading from the air lock to the radome. The post position and the test fixture position can thus be observed while changes in the post position are being made. The post position can be changed in increments of less than 0.25 inch using the push button controls.



Figure 2.2 Hydraulic Pump and Fluid Storage Unit

3. RADOME

The radome is an air supported truncated sphere 60 feet in diameter and 37.5 feet high and is shown in Figure 3.1.

3.1 Radome Construction

The basic material used in the construction of the radome was a white vinyl coated nylon fabric weighing approximately 29 ounces per square yard. Gore construction was used and the gores are tied together and reinforced at the top by a pole cap. A crown plate was placed at the pole which will withstand a downward force of 500 pounds. A provision was made for the installation of an eye ring in this plate so that a small hoist can be installed for handling small pieces of equipment.

A 1/2 inch braided nylon rope is bonded to the radome material around the bottom of the radome. The radome is attached to the pad by bolting the material between a metal plate, which is set into the concrete, and a piece of channel stock with the rope below the bolt line. This is shown in Drawing #SK 1946 in Appendix A. An extra piece of material was bonded to the exterior surface of the radome at the bottom which protects the attachment area from weathering.

Since the radome is to be used in the performance of radar cross section measurements, discontinuities in the radome surface were carefully avoided. All blowers and associated equipment were placed underground. There are no doors in the radome and entrance is gained by a stairwell in the floor leading from the underground air lock. The crown plate was made from a dielectric material as were the two exhaust ports in the side of the radome.

3.2 Radome Operation

The radome is an air-supported structure requiring a certain minimum internal pressure in order to remain erect. The pressurization system consists of two centrifugal backward-blade blowers whose operation is controlled manually and/or automatically. A picture of this system is shown in Figure 3.2. Blower No. 1 is a high-volume, low-pressure blower designed to run continuously and is the larger of the two blowers. The blower motor is rated at 5 hp and requires 60 cps 220 V single-phase power. An On-Off switch and



Figure 3.1 Radome



Figure 3.2 Blower System

indicating light on the control panel are connected through a magnetic starter to this blower. Normal operating pressure, with this blower alone, should be approximately 2.5 inches of water.

The smaller blower is used for higher pressure or when additional air flow is required. Normally, higher pressures are required only when the wind is between 70 and 100 mph. Additional air flow is required only for initial erection of the radome or for abnormal loss of air due to large area venting for greater circulation of air. The blower motor is rated at 2 hp and requires 60 cps 220 V single-phase power. This blower is controlled through a three-position switch, AUTO ON, MAN ON, and OFF or RESET, mounted on the control panel. The blower installation is shown in detail in Drawing #SK 1938 in Appendix A.

For normal operation the switch for Blower No. 1 is left in the ON position. The blower will run continuously providing an operating pressure of approximately 2.5 inches of water which is sufficient for wind speeds up to 70 mph. The switch for Blower No. 2 is set to the AUTO ON position. (See Figure 3.3 for guide to operating pressures.)

If at any time, with main power ON, the pressure level in the radome drops to 1.5 inches of water, the pressure switch will turn on the warning and, after a 20 second delay, start Blower No. 2 which will continue to run until the switch is turned to the OFF or RESET position. If the winds exceed 70 mph, or gusts are sufficient to cause the envelope to distort, the pressure is raised. It is then necessary to manually switch on Blower No. 2. The exact pressure level required for any given wind velocity is shown in Figure 3.3. However, it is not absolutely necessary to know the exact velocity as the basic reason for the increased pressures is to prevent radome distortion or whipping, and this condition is readily visible.

The structural stability of the radome is dependent upon a continual source of blower power. An emergency motor-generator has been installed which will supply blower power in the event of a line power failure. The generator is a single phase Kohler Model #10RM61 and will supply 44 amps at 230 V at 60 cps. If line power is lost, the motor-generator is automatically started and



Figure 3.3 Operating Pressure as a Function of Wind Velocity

supplies power to the high pressure blower. When line power is restored the motor-generator automatically shuts off. The emergency system is equipped with an exercising unit so that the equipment can be exercised periodically. This is a device for automatically turning the system on, allowing it to run for a predetermined period of time, and automatically shutting the system off. The number of exercise periods per week can be varied; Conductron exercises the system at least twice each week.

In the winter it is necessary to take certain additional precautions to insure that there not be an excessive build up of ice and snow. Due to the spherical design of the radome, snow will not usually accumulate on the structure. However, in the case of wet snow, some accumulation might occur which would cause a distortion of the radome surface. In order to prevent this, a Shafconaire Model SC-350 horizontal oil-fired furnace which produces 350,000 btu per hour output has been installed. A picture of this furnace is shown in Figure 3.4. The main furnace unit is 96 inches long by 39 inches wide by 32 inches high and it is mounted on an angle bracket skid approximately 8 inches high. Both the cold air return and the heater inlet duct are 28.5 inches by 36 inches. Warm air is forced into the radome by means of a 1 hp blower motor. A 500 gallon underground oil tank has been provided to supply fuel for the furnace which consumes approximately 3 gallons of fuel oil per hour. Since the furnace is used primarily for ice and snow removal, the amount of underground oil storage is adequate. If the furnace were to be used to provide a warm working environment it would be advisable to install a tank with greater capacity. The furnace is exhausted through a Transite exhaust duct which is equipped with a draft-inducing fan to assist in ventilation.

3.3 Radome Erection

The radome arrived at Conductron folded into a compact package for shipment and ease of handling. A Birdair engineer, Mr. Charles Hoff, was present to assist during the erection procedure. The erection took place on a relatively calm day when the winds were less than 10 miles per hour. A crew of seven men and a portable boom crane were necessary to complete the erection. The entire operation was completed in less than 4 hours.



Figure 3.4 Furnace System

The folded radome package was placed near the center of the radome pad and the radome was unfolded toward the edges of the pad. A line was attached from the overhead crane to an eye bolt in the crown plate of the radome. The crane lifted the center of the radome off the pad to allow personnel access to the underside of the radome to make the attachments between the radome pad and the radome. As discussed in Section 3.1 above, the attachment is made by bolting the radome material between an anchor plate set into the concrete curbing and the channel clamp ring. The attachment hardware is shown in Drawing #SK 1946 of Appendix A. The channel clamp ring is first put in place and the nuts installed finger tight. The material was then straightened and smoothed and the nuts tightened securely.

When all 16 channel clamp rings were in place the blower system was turned on and the radome was slowly inflated. When power was first supplied to the blower system the Low Pressure Warning Light came on. The switch for Blower No. 1 was turned to the ON position and the switch for Blower No. 2 was turned to the AUTO ON position to provide maximum delivery of air for inflation. As soon as the Low Pressure Warning Light went out, the switch on Blower No. 2 was turned to the OFF position. This prevented over-pressurization of the radome until the anchorage and attachments were secured. The radome was then inspected for leaks and fabric alignment. The structure was tight and no problems were encountered.

3.4 Electrical Evaluation

This section will present both the theoretical and experimental evaluation of the radome. Particular attention has been given to the electrical properties of the radome and their relative effects on the measurements of large (22 foot diameter) segments of reflecting material. The theoretical effort was devoted primarily to the discovery of factors which could cause measurement error. The experimental effort was devoted to evaluating these factors and establishing practical limitations on the type of measurements which can be performed. In addition, attention has been given to using the radome for housing a transmitting antenna. The results indicate that no major problems will be encountered; however, an adequate evaluation of the

radome for this purpose requires a different series of tests than those performed under this program.

3.4.1 Reflection Coefficients

Prior to the purchase of the radome, reflection coefficients were calculated for two different radome samples (A & B) supplied by Birdair Structures, Inc. of Buffalo, New York. Several experiments were conducted on these samples at the Conductron Corporation Radar Range, to provide the information necessary to compute the reflection coefficient. The 6 inch by 6 inch samples of flexible radome material were attached to flat, relatively thick, slabs of polystyrene foam (styrofoam). This was necessary to offer the support needed to maintain the sample as true as possible for controlled test conditions.

The tape (Scotch Brand #810) used to attach the sample to the styrofoam was applied very smoothly, and it would appear that the combination is accurately modeled by two parallel dielectric sheets in air. A theoretical analysis of the measurement program is shown below.

We will first assume that both materials are non-conducting. In this case, Maxwell's equations may be written

$$\nabla \times \vec{E} = -\frac{1}{c}\vec{B} \qquad \nabla \cdot \vec{D} = 0$$

$$\nabla \times \vec{H} = \frac{1}{c}\vec{D} \qquad \nabla \cdot \vec{B} = 0$$

If the incident field is normal to the interfaces, the fields in all of the regions in Figure 3.5 take the form

$$E_z = Ae^{ikx} + A_1 e^{-ikx}$$

and

$$H_y = -\frac{c}{\omega}\frac{k}{\mu}(Ae^{ikx} - A_1 e^{-ikx})$$

where we assume that $\mu = 1$ for all materials.



Figure 3.5

Geometry for Analysis of Two Parallel Dielectric Sheets

Since the tangential components of $\vec{E}$ and $\vec{H}$ must be continuous across the interfaces, A_1, B, B_1, C, C_1 and D can be found by solving the six independent equations represented by

A_1	B	B_1	C	C_1	D		A
1	-1	-1				=	-1
-1	$-\eta_1$	η_1				=	-1
	γ_{11}	$1/\gamma_{11}$	$-\gamma_{21}$	$-1/\gamma_{21}$		=	0
	$\eta_1\gamma_{11}$	$-\eta_1/\gamma_{11}$	$-\eta_2\gamma_{21}$	η_2/γ_{21}		=	0
			γ_{22}	$1/\gamma_{22}$	$-\gamma_{02}$	=	0
			$\eta_2\gamma_{22}$	$-\eta_2/\gamma_{22}$	$-\gamma_{02}$	=	0

where $k_1 = \eta_1 k$, $k_2 = \eta_2 k$, $\gamma_{11} = e^{ik_1 d_1}$, $\gamma_{21} = e^{ik_2 d_1}$, $\gamma_{22} = e^{ik_2 d_2}$, and $\gamma_{02} = e^{ikd_2}$.

If we introduce $r_1 = \dfrac{1 - \eta_1}{1 + \eta_1}$ and $r_2 = \dfrac{1 - \eta_2}{1 + \eta_2}$,

the reflection coefficient of any two layers of dielectric in air is,

$$R_{12} = |A_1|^2$$

$$= \left| \frac{\left\{ \eta_1 \left(1 + \frac{1}{\gamma_{11}^2} r_1\right) \left(1 - \frac{\gamma_{22}^2}{\gamma_{21}^2} r_2\right) - \eta_2 \left(1 - \frac{1}{\gamma_{11}^2} r_1\right) \left(1 + \frac{\gamma_{22}^2}{\gamma_{21}^2} r_2\right) \right\}}{\left\{ \eta_1 \left(1 + \frac{1}{\gamma_{11}^2} r_1\right) \left(1 - \frac{\gamma_{22}^2}{\gamma_{21}^2} r_2\right) + \eta_2 \left(1 - \gamma_{11}^2 r_1\right) \left(1 + \frac{\gamma_{22}^2}{\gamma_{21}^2} r_2\right) \right\}} \right|^2$$

The subscript on R indicates that the field strikes the material having propagation constant k_1 first. When the layers are reversed so that the field strikes material 2 first, the same formal result is true if the various parameters are permuted appropriately. In particular as,

$$R_{12} \longrightarrow R_{21};\ \gamma_{11} \longrightarrow \gamma'_{11} = r_{22}/\gamma_{21},\ \gamma_{21} \longrightarrow \gamma'_{21} = \gamma_{12}/\gamma_{11}$$

$$\gamma_{02} \longrightarrow \gamma'_{22} = \gamma_{12} \text{ and } \gamma_{02} \longrightarrow \gamma'_{02} = \gamma_{02}$$

while

$$d_1 \longrightarrow d'_1 = d_2 - d_1,\ d_2 \longrightarrow d'_2 = d_2,$$

as

$$\eta_1 \longrightarrow \eta_2 \text{ and } \eta_2 \longrightarrow \eta_1$$

The reflection coefficient is now,

$$R_{21} = \left| \frac{\left\{ -\eta_1 \left(1 + \gamma_{11}^2 r_1\right) \left(1 - \frac{\gamma_{21}^2}{\gamma_{22}^2} r_2\right) + \eta_2 \left(1 - \gamma_{11}^2 r_1\right) \left(1 + \frac{\gamma_{21}^2}{\gamma_{22}^2} r_2\right) \right\}}{\left\{ \eta_1 \left(1 + \gamma_{11}^2 r_1\right) \left(1 - \frac{\gamma_{21}^2}{\gamma_{22}^2} r_2\right) + \eta_2 \left(1 - \gamma_{11}^2 r_1\right) \left(1 + \frac{\gamma_{22}^2}{\gamma_{21}^2} r_2\right) \right\}} \right|^2$$

We note that the denominators of R_{12} and R_{21} are the same and that the numerators are just negative complex conjugates of each other. Therefore, the power reflection coefficient is independent of whether the sample or support faces the transmitter if both are dielectrics.

If the measured values of R_{12} and R_{21} are different, this must be attributed to either experimental error or to non-zero conductivity.

Measurements were made on both samples A and B at 5.45 kmc. Each sample was .05 cm thick, while the supporting material was 2.54 cm thick.

From the experimental data:

Sample A

$$\sigma_{12}^A = \sigma_{\text{cond.}} R_{12}^A = 1.54 \times 10^{-3} \text{ m}^2$$

$$\sigma_{21}^A = \sigma_{\text{cond.}} R_{21}^A = 2.44 \times 10^{-3} \text{ m}^2$$

Sample B

$$\sigma_{12}^B = \sigma_{\text{cond.}} R_{12}^B = 2.15 \times 10^{-3} \text{ m}^2$$

$$\sigma_{21}^B = \sigma_{\text{cond.}} R_{21}^B = 3.77 \times 10^{-3} \text{ m}^2$$

The cross section, $\sigma_{\text{cond.}}$ of a 6 inch x 6 inch plate is

$$\sigma_{\text{cond.}} = \frac{4\pi}{\lambda^2} A^2 = 2.23 \text{ m}^2.$$

So, the reflection coefficients are bounded by,

$$0.69 \times 10^{-3} \leq R_A \leq 1.09 \times 10^{-3}$$

$$0.96 \times 10^{-3} \leq R_B \leq 1.69 \times 10^{-3}$$

The averages are

$$\bar{R}_A = 0.89 \times 10^{-3}$$

$$\bar{R}_B = 1.32 \times 10^{-3}$$

The reflection coefficients R_{12} or R_{21} have been evaluated at the experimental frequency of 5.45 kmc and plotted in Figure 3.6 versus the index of refraction of the samples A and B for several values of η_2, the refractive index of the supporting material. According to VonHippel(1)

$$\eta_2 = 1.015.$$

We see that Sample A satisfies the experimental data if

$$1.455 \leq \eta_1^A \leq 1.535$$

and similarly for Sample B

$$1.512 \leq \eta_1^B \leq 1.628$$

Corresponding to $\bar{R}_A$ and $\bar{R}_B$ we have

$$\bar{\eta}_1^A = 1.500$$

$$\bar{\eta}_1^B = 1.575$$

The reflection coefficient of the NASA radome material is easily obtained now that we know its dielectric constant. According to Stratton(2), the reflection coefficient of a dielectric sheet in the air is,

---

(1) VonHippel, A., "Dielectric Materials and Applications", pp. 337.

(2) Stratton, J.A., "Electromagnetic Theory", McGraw-Hill Publications, pp. 514.



Figure 3.6 Reflection Coefficients of a 2-Layer Dielectric Sandwich

$$R(\lambda)_{\text{radome}} = \frac{4r^2 \sin^2 (\eta_1 \, kd_1)}{(1 - r^2)^2 + 4r^2 \sin^2 (\eta_1 \, kd_1)} \approx 4r^2 \sin^2 (\eta_1 kd)$$

where

$$r = \frac{1 - \eta_1}{1 + \eta_1}$$

Since the values for η_1 determined graphically are only valid at the experimental frequency, $R(\lambda)_{\text{radome}}$ will only give the general character of the reflection coefficient as a function of frequency. We will evaluate R_{radome} from the above (Figure 3.7) for frequencies near the experimental frequency of 5.45 kmc. Note the agreement of $R(\lambda)_{\text{radome}}$ with $R_{2\text{-layer}}$ in the limiting case where $\eta_2 = 1.00$.

We see that depending on the nature of the difference between R_{12} and R_{21}, that the reflection coefficient of the radome materials at 5.45 kmc are,

$$1.0 \times 10^{-3} \leq R^A_{\text{radome}} \leq 1.5 \times 10^{-3}$$

and

$$1.3 \times 10^{-3} \leq R^B_{\text{radome}} \leq 2.35 \times 10^{-3}$$

or

$$\bar{R}^A_{\text{radome}} = 1.25 \times 10^{-3}$$

and

$$\bar{R}^B_{\text{radome}} = 1.75 \times 10^{-3}$$

Using the above reflection coefficients, $\bar{R}^A$ and $\bar{R}^B$, we find that the radar cross section of a radome 60 feet in diameter is

$$\sigma_{\text{radome}} = \bar{R} \, \pi \, a^2 = 262.6 \, \bar{R} \, m^2$$

$$= 3.3 \times 10^{-1} \, m^2 \quad \text{For Sample A}$$

$$= 4.6 \times 10^{-1} \, m^2 \quad \text{For Sample B}$$



Figure 3.7 Radome Reflection Coefficient Vs. Frequency

The effect on the 2-layer reflection coefficient of assuming that one or both dielectrics have a very slight conductivity can most easily be seen by allowing η_1 and η_2 to be complex in our expressions for R_{12} and R_{21} and expanding around the real part. The complex part of polystyrene foam is small

$$\eta_2 = 1.015 + i\ 10^{-4}$$

and can in fact be ignored since it cannot account for the observed Δ R.

If we set $\eta_1 = 1.5 + 1\eta_1''$ and solve for η_1', we find that the observed Δ R requires $\eta_1'' = 10^{-2}\ \eta_1'$.

Even that value of η_1'' cannot greatly effect the radome reflection coefficient which must still lie between the bounds determined earlier, i.e.,

$$10^{-3} \leq R_A \leq 1.4 \times 10^{-3}$$

and

$$1.5 \times 10^{-3} \leq R_B \leq 2.2 \times 10^{-3}.$$

3.4.2 Analysis of Radome - Target Interaction Effects

It is clear that in addition to primary reflections from the radome surface, any reflection data obtained on the segment material might be affected by interactions between the radome and the target. In order to evaluate the extent to which such interactions might affect the measurement data, a theoretical analysis was performed and the results are described below. The analysis was concerned with two separate phenomena; first, assuming that a target inside the radome is illuminated with a plane wave, it is necessary to determine the extent to which the far field reflection pattern is distorted by the radome; and second, the effect of multiple reflections must be minimized by correct placement of the target in the radome.

3.4.2.1 High-Frequency Scattering from a Conducting Sphere Surrounded by a Thin-Wall Radome

It is first necessary to investigate the radar cross section distortions produced by a large and spherical thin-wall radome surrounding a perfectly con-

ducting target. In considering this problem it is convenient to confine attention to the specular backscatter generated by a plane electromagnetic wave incident upon the system. In particular, we shall consider the problem of scattering by a perfectly conducting sphere placed at the center of the spherical dielectric housing or radome. Since all boundary surfaces are now concentric spheres, the exact Mie series can be obtained in straight-forward fashion and the high-frequency fields can be evaluated by standard analytical techniques.

Specifying the problem, we have a plane electromagnetic wave

$$\vec{E} = \hat{x}\, e^{-i\omega t + ikz}, \quad k = \omega\,(\epsilon_o\, \mu_o)^{1/2} \tag{3.1}$$

incident upon a perfectly conducting sphere with radius c covered by two concentric layers. The outer layer consists of a dielectric with relative electric permittivity ϵ and with relative magnetic permeability $\mu = 1$. The inside radius of this layer will be denoted by b, its outside radius by a, and its thickness by $\delta = a-b$. In general, the products $k\delta$ and $k_1\delta$, where $k_1 = \sqrt{\epsilon}k$ is the propagation constant within the dielectric, will be assumed much smaller than unity. The outer layer, then, represents the thin-wall radome. The inner layer extending from radius c to radius b consists of free space. We shall take the free-space constants ϵ_o and μ_o to be equal to unity. Ordinarily, the inner free-space layer is thick so that $k(b-c)$ is much larger than one; however, we have no need to use this fact in the calculations.

We shall consider in turn the magnetic field on the surface of the conducting sphere at the backscattering specular point and the far-zone electric field scattered in the back direction. In both cases the exact Mie series are represented as contour integrals by means of the Watson transform technique. The contour integrals are evaluated asymptotically under the following conditions

$$kc,\ kb \gg 1,$$

$$k\delta,\ k_1\delta \ll 1$$

to yield the first two terms in the asymptotic series corresponding to a Luneberg-Kline expansion. The creeping wave or diffracted field contribution is not obtained.

Before investigating the exact Mie series representations it is useful to obtain the geometrical-optics fields by means of ray-tracing. This is easily done and the result will act as both a check and a guideline for the complicated expansions to follow.

GEOMETRICAL-OPTICS

In the geometrical-optics approximation, the effect of the radome wall is most conveniently represented in terms of transmission and reflection coefficients, these coefficients being calculated by replacing the curved surface of the radome by a plane sheet. For a thin wall and normal incidence, the amplitude reflection and transmission coefficients for the electric and magnetic fields are given by

$$\begin{aligned} R_H &= -R_E = \frac{k\delta}{2i}(\epsilon-1) + 0\,(k\delta)^2 , \\ T_H &= T_E = 1 - \frac{k\delta}{2i}(\epsilon-1) + 0\,(k\delta)^2 . \end{aligned} \tag{3.2}$$

In all of our calculations we shall keep only the first order in $k\delta$ and hence only the first order in the reflection coefficient.

At the specular point (x=o, y=o, z= -c) on the surface of the metal sphere, the magnetic field is, by geometrical optics,

$$H_y^{surf} = 2\,T_H\,e^{-ikc} + 2\,T_H\,R_H\,\left(\frac{b}{3b-2c}\right)e^{-ikc}\,e^{2ik(b-c)} , \tag{3.3}$$

where the second term corresponds to a double bounce in the free-space layer. Higher order multiple bounces introduce higher powers of the reflection coefficient and are neglected. Introducing (3.2) into (3.3) we have explicitly

$$H_y^{surf} = 2e^{-ikc}\left\{\left[1 - \frac{1\delta}{2i}(\epsilon-1)\right] + \frac{k\delta}{2i}(\epsilon-1)\left(\frac{b}{3b-2c}\right)e^{2ik(b-c)}\right\} \tag{3.4}$$

Similarly, the far backscattered electric field in the optics approximation is

$$E_x^{bs} = - T_E^2 \left(\frac{c}{2r}\right) e^{ik(r-2c)} + R_E \left(\frac{b}{2r}\right) e^{ik(r-2b)}$$

$$+ T_E^2 R_E \left(\frac{c}{2r} \frac{b}{2b-c}\right) e^{ik(r-2c)} e^{2ik(b-c)}, \tag{3.5}$$

or, in explicit form, we have

$$E_x^{bs} = - \frac{c}{2r} e^{ik(r-2c)} \left\{ \left[1 - 2 \frac{k\delta}{2i} (\epsilon-1) \right] + \frac{k\delta}{2i} (\epsilon-1) \left(\frac{b}{2b-c}\right) e^{2ik(b-c)} \right.$$

$$\left. + \frac{k\delta}{2i} (\epsilon-1) \left(\frac{b}{c}\right) e^{-2ik(b-c)} \right\} . \tag{3.6}$$

Equations (3.4) and (3.6) represent the expected first order terms in a Luneberg-Kline expansion. To obtain higher order terms we turn to the exact Mie series representation.

FIELD ON THE CONDUCTING SPHERE

After much algebra the electromagnetic field on the surface of the conducting sphere is found to be

$$H_\theta = - \frac{4 \sin\varphi}{ikc} \sum_{n=1}^{\infty} i^n \frac{2n+1}{n(n+1)} \left\{ \frac{1}{ia_n'} \frac{\partial}{\partial\theta} - \frac{1}{b_n'} \frac{1}{\sin\theta} \right\} P_n^1 (\cos\theta),$$

$$H_\varphi = - \frac{4 \cos\varphi}{ikc} \sum_{n=1}^{\infty} i^n \frac{2n+1}{n(n+1)} \left\{ \frac{1}{ia_n'} \frac{1}{\sin\theta} - \frac{1}{b_n'} \frac{\partial}{\partial\theta} \right\} P_n^1 (\cos\theta), \tag{3.7}$$

$$E_r = - \frac{4 \cos\varphi}{(kc)^2} \sum_{n=1}^{\infty} i^n (2n+1) \frac{P_n^1 (\cos\theta)}{b_n'},$$

where

$$a_n' = h_n^{(1)}(ka) \left[\sqrt{\frac{\epsilon}{\mu}} \frac{\partial^2 C_n}{\partial(k_1 b)\, \partial (k_1 a)} C_n' - \frac{\partial C_n}{\partial(k_1 a)} \frac{\partial C_n'}{\partial(kb)} \right]$$

$$- h_n'^{(1)}(ka) \left[\frac{\partial C_n}{\partial(k_1 b)} C_n' - \sqrt{\frac{\mu}{\epsilon}} \frac{\partial C_n'}{\partial(kb)} C_n \right] \tag{3.8}$$

and where b_n' is obtained from a_n' by replacing C_n' with $\partial C_n'/\partial(kc)$ and by interchanging ϵ and μ. In the above

$$C_n = h_n^{(1)}(k_1 a)\, h_n^{(2)}(k_1 b) - h_n^{(1)}(k_1 b)\, h_n^{(2)}(k_1 a),$$

$$C_n' = h_n^{(1)}(kb)\, h_n^{(2)}(kc) - h_n^{(1)}(kc)\, h_n^{(2)}(kb), \qquad (3.9)$$

and the spherical Hankel functions are given by

$$h_n^{(1)(2)}(x) = \sqrt{\pi x/2}\;\; H_\nu^{(1)(2)}(x)$$

with $\nu = n + 1/2$.

Setting $a = b + \delta$ we now expand those Hankel functions which are functions of ka or $k_1 a$ into Taylor series, thus e.g.

$$h_n^{(1)(2)}(ka) = h_n^{(1)(2)}(kb) + (k\delta)\, h_n'^{(1)(2)}(kb) + \ldots ,$$

and we find, by making use of the Wronskian relation

$$h_n'^{(1)}\, h_n^{(2)} - h_n^{(1)} h_n'^{(2)} = 2i,$$

that

$$C_n = 2i\,(k_1\delta), \quad \frac{\partial C_n}{\partial(k_1 a)} = -\frac{\partial C_n}{\partial(k_1 b)} = 2i,$$

$$\frac{\partial^2 C_n}{\partial(k_1 b)\;\partial\,(k_1 a)} = 2i\,(k_1\delta)\left[\,1 - \frac{n(n+1)}{(k_1 b)^2}\,\right].$$

Terms of order $(k_1\delta)^2$ have been neglected. Employing the immediately preceding equations and recalling that $\mu = 1$, we find that a_n' and b_n' take the form

$$a'_n = 4\, h_n^{(1)}(kc)\, A'_n \,,$$

$$b'_n = 4\, h_n'^{(1)}(kc)\, B'_n \,, \tag{3.10}$$

where

$$A'_n = 1 - \frac{k\delta}{2i}(\epsilon-1)\frac{h_n^{(1)}(kb)}{h_n^{(1)}(kc)}\, C'_n \,, \tag{3.11}$$

$$B'_n = 1 - \frac{k\delta}{2i}(\epsilon-1)\frac{h_n'^{(1)}(kb)}{h_n'^{(1)}(kc)}\,\frac{\partial^2 C'_n}{\partial(kb)\partial(kc)} - \frac{k\delta}{2i}\left(1-\frac{1}{\epsilon}\right)\frac{h_n^{(1)}(kb)}{h_n'^{(1)}(kc)}\,\frac{\partial C'_n}{\partial(kc)}\,\frac{n(n+1)}{(kb)^2} \,.$$

At the backscattering specular point, $\theta = \pi$ and

$$\frac{P_n^1}{\sin\theta} \to (-)^n\,\frac{n(n+1)}{2} \,, \quad \frac{\partial P_n^1}{\partial\theta} \to -(-)^n\,\frac{n(n+1)}{2} \,;$$

hence at this point the only non-zero component of the electromagnetic field is

$$H_y = -\frac{1}{2ikc}\sum_{n=1}^{\infty}(-i)^n\,(2n+1)\left\{\frac{1}{i\, h_n^{(1)}(kc)\, A'_n} + \frac{1}{h_n'^{(1)}(kc)\, B'_n}\right\} . \tag{3.12}$$

To effect a high-frequency asymptotic evaluation, we convert the summation over n into a contour integral: define

$$f(\nu) = \frac{1}{i\, h_n^{(1)}(kc)\, A'_n} + \frac{1}{h_n'^{(1)}(kc)\, B'_n} \tag{3.13}$$

with $\nu = n + 1/2$, then

$$H_y = \frac{1}{2kc}\left\{\frac{1}{i}\, f\left(\tfrac{1}{2}\right) + e^{-i\frac{\pi}{4}}\int_C \frac{d\nu\,\nu}{\cos\nu\pi}\, e^{i\frac{\nu\pi}{2}}\, f(\nu)\right\} . \tag{3.14}$$

The contour C, which encircles the positive real axis in a clockwise fashion, can be deformed into the path C' passing from the fourth quadrant through the origin to the second quadrant. Any poles of the integrand which are captured by this contour deformation contribute to the diffracted field and are not of interest here.

It is an easy matter to show that the factor A_n' in the denominator in (3.13) has no zeros on the real ν axis. From (3.11),

$$A_n' = 1 - \frac{k\delta}{2i} (\epsilon-1) \frac{h_n^{(1)}(kb)}{h_n^{(1)}(kc)} C_n'$$

where

$$C_n' = h_n^{(1)}(kb)\, h_n^{(2)}(kc) - h_n^{(1)}(kc)\, h_n^{(2)}(kb)$$

$$= 2i \{j_n(kc)\, y_n(kb) - j_n(kb)\, y_n(kc)\} .$$

Thus C_n' is pure imaginary for real n. In order for A_n' to be zero, the ratio $h_n^{(1)}(kb)/h_n^{(1)}(kc)$ must therefore be real, so we must have

$$\mathrm{Im} \frac{h_n^{(1)}(kb)}{h_n^{(1)}(kc)} = \frac{j_n(kc)\, y_n(kb) - j_n(kb)\, y_n(kc)}{j_n^2(kc) + y_n^2(kc)} = 0 .$$

But if this is true, then C_n' is zero. Therefore A_n' has no zeros on the real ν axis. Similar, but more complicated, considerations apply to B_n'. Thus on the real ν axis the integrand in (3.14) possesses poles only at the zeros of $\cos \nu\pi$.

The line integral over C' can be evaluated asymptotically at the stationary point $\nu = 0$ following the technique of Scott[3]. Using the asymptotic approximations (x being large)

(3) Scott, J. M. C., A.E.C. Research Est. Rpt. T/M 30 (1949).

$$h_n^{(1)}(x) \sim \exp\left(ix - \frac{i\nu\pi}{2} + \frac{i\nu^2}{2x} - \frac{i\pi}{4}\right)\left\{1 - \frac{i}{8x} + \frac{1}{4}\frac{\nu^2}{x^2} + \frac{i\nu^4}{24\,x^3} + \cdots\right\},$$

$$h_n^{(2)}(x) \sim \exp\left(-ix + \frac{i\nu\pi}{2} - \frac{i\nu^2}{2x} + \frac{i\pi}{4}\right)\left\{1 + \frac{i}{8x} + \frac{1}{4}\frac{\nu^2}{x^2} - \frac{i\nu^4}{24\,x^3} + \cdots\right\},$$

we obtain the following expansion for $f(\nu)$

$$f(\nu) \sim \frac{1}{i}\exp\left(-ikc + \frac{i\nu\pi}{2} - \frac{i\nu^2}{2kc} + \frac{i\pi}{4}\right)\left\{2 + \frac{i}{4kc} - \frac{i\nu^4}{12(kc)^3}\right\}\left\{1 - \frac{k\delta}{2i}(\epsilon-1)\right\}$$

$$- \frac{1}{i}\frac{k\delta}{2i}\left(1-\frac{1}{\epsilon}\right)\exp\left(-ikc + \frac{i\nu\pi}{2} - \frac{i\nu^2}{2kc} + \frac{i\pi}{4}\right)\left\{\frac{\nu^2}{(kb)^2}\right\}$$

$$+ \frac{1}{i}\frac{k\delta}{2i}(\epsilon-1)\exp\left[ik(2b-3c) + \frac{i\nu\pi}{2} + \frac{i\nu^2}{k}\left(\frac{1}{b} - \frac{3}{2c}\right) + \frac{i\pi}{4}\right]\left\{2 - \frac{i}{2k}\left(\frac{1}{b} - \frac{3}{2c}\right) +\right.$$

$$\left. + \frac{i\nu^4}{6k^3}\left(\frac{1}{b^3} - \frac{3}{2c^3}\right)\right\} - \frac{1}{i}\frac{k\delta}{2i}\left(1-\frac{1}{\epsilon}\right)\exp\left[ik(2b-3c) + \frac{i\nu\pi}{2} + \frac{i\nu^3}{k}\left(\frac{1}{b} - \frac{3}{2c}\right) + \frac{i\pi}{2}\right]$$

$$\left\{\frac{\nu^2}{(kb)^2}\right\}. \qquad (3.15)$$

We also note the exact identity

$$f\left(\frac{1}{2}\right) = 2e^{-ikc}\left\{1 + \frac{k\delta}{2i}(\epsilon-1)\left[e^{2ik(b-c)} - 1\right]\right\}. \qquad (3.16)$$

When (3.15) is substituted into (3.14) the resulting line integral is of the form considered by Scott[4]. The combination of the asymptotic expression for the line integral and the term involving $f(1/2)$ in the expression (3.14) gives the Luneberg-Kline contribution to the surface field. We obtain

---

(4) Scott, Ibid.

$$H_y^{surf} \sim 2e^{-ikc}\left\{\left[1 - \frac{k\delta}{2i}(\epsilon-1)\right] - \frac{1}{ikc}\frac{k\delta}{2i}\left(1 - \frac{1}{\epsilon}\right)\frac{c^2}{b^2}\right\}$$

$$+ 2e^{ik(2b-3c)}\left\{\frac{k\delta}{2i}(\epsilon-1)\left(\frac{b}{3b-2c}\right) + \frac{1}{3ikc}\frac{k\delta}{2i}(\epsilon-1)\left[1 - \frac{3b^3-2c^3}{(3b-2c)^3}\right]\right.$$

$$\left. - \frac{1}{ikc}\frac{k\delta}{2i}\left(1 - \frac{1}{\epsilon}\right)\frac{c^2}{b^2}\left(\frac{b}{3b-2c}\right)^2\right\}. \qquad (3.17)$$

One verifies that the first order term in this expansion agrees with the geometrical-optics expression given in (3.4).

THE BACKSCATTERED FIELD

The asymptotic expansion of the backscattered field can be obtained in a fashion analogous with that presented above. One finds that the far backscattered field may be written in the form

$$E_x^{bs} = \frac{e^{ikr}}{ikr}\sum_{n=1}^{\infty}(-)^n\left(n+\frac{1}{2}\right)\frac{i\,(A_n - B_n)}{L_\nu(A_n)\,L_\nu(B_n)}$$

$$= -\frac{e^{ikr}}{2kr}\left\{\frac{A_o - B_o}{L_{\frac{1}{2}}(A_o)\,L_{\frac{1}{2}}(B_o)} + \int_C \frac{d\nu\,\nu}{\cos\nu\pi}\frac{i\,(A-B)}{L_\nu(A)\,L_\nu(B)}\right\}, \qquad (3.18)$$

where

$$L_\nu(A_n) = h_n^{(1)}(ka)\,A_n - h_n'^{(1)}(ka) \qquad (3.19)$$

and similarly for $L_\nu(B_n)$. The coefficients A_n and B_n are given by Bowman [5] in connection with the problem of a doubly absorber-coated sphere. For application to the problem at hand, we simply state that one finds, again after much manipulation, the following expansion to first order in $(k\delta)$

(5) Bowman, J. J., Conductron Memorandum D0620-177-M, 24 September 1963.

$$\frac{A-B}{L_\nu(A)L_\nu(B)} = \frac{-1}{h_n^{(1)}(kc)\, h_n'^{(1)}(kc)} \left\{ 1 + \frac{k\delta}{4}(\epsilon-1)\left[\frac{\partial C_n'}{\partial(kb)} \frac{\partial^2 C_n'}{\partial(kb)\partial(kc)} - C_n' \frac{\partial C_n'}{\partial(kc)}\right]\right.$$

$$+ \frac{k\delta}{2i}(\epsilon-1)\left[\frac{h_n^{(1)}(kb)}{h_n^{(1)}(kc)} C_n' + \frac{h_n'^{(1)}(kb)}{h_n'^{(1)}(kc)} \frac{\partial^2 C_n'}{\partial(kb)\,\partial(kc)}\right] \qquad (3.20)$$

$$\left. + \frac{k\delta}{2i}\left(1 - \frac{1}{\epsilon}\right) \frac{n(n+1)}{(kb)^2}\left[\frac{h_n^{(1)}(kb)}{h_n'^{(1)}(kc)} \frac{\partial C_n'}{\partial(kc)} - \frac{C_n'}{2i} \frac{\partial C_n'}{\partial(kc)}\right]\right\}$$

where C_n' is defined in Equation (3.9).

To evaluate the line integral in (3.18) asymptotically at the stationary point $\nu = 0$ we require the following expansion

$$\frac{A-B}{L_\nu(A)\, L_\nu(B)} \sim -e^{-2ikc + i\nu\pi} \left\{ \right\}, \qquad (3.21)$$

where

$$\left\{ \right\} = \exp\left(-\frac{i\nu^2}{kc}\right) \left\{ \left[1 + \frac{i}{4kc} - \frac{i\nu^4}{12(kc)^3}\right] \left[1 - 2\frac{k\delta}{2i}(\epsilon-1)\right] - \frac{k\delta}{2i}\left(1 - \frac{1}{\epsilon}\right)\left[\frac{\nu^2}{(kb)^2}\right]\right\}$$

$$+ \exp\left[-2ik(b-c) - \frac{i\nu^2}{kb}\right] \left\{\frac{k\delta}{2i}(\epsilon-1)\left[1 + \frac{i}{4kb} - \frac{i\nu^4}{12(kb)^3}\right] - \frac{k\delta}{4i}\left(1 - \frac{1}{\epsilon}\right)\left[\frac{\nu^2}{(kb)^2}\right]\right\}$$

$$+ \exp\left[2ik(b-c) + \frac{i\nu^2}{k}\left(\frac{1}{b} - \frac{2}{c}\right)\right] \left\{\frac{k\delta}{2i}(\epsilon-1)\left[1 - \frac{i}{4k}\left(\frac{1}{b} - \frac{2}{c}\right) + \frac{i\nu^4}{12k^3}\left(\frac{1}{b^3} - \frac{2}{c^3}\right)\right]\right.$$

$$\left. - \frac{k\delta}{4i}\left(1 - \frac{1}{\epsilon}\right)\left[\frac{\nu^2}{(kb)^2}\right]\right\}. \qquad (3.22)$$

$$\frac{A_o - B_o}{L_{1/2}^{(A_o)} L_{1/2}^{(B_o)}} = \frac{1}{i} e^{-2ikc} \left\{ \left[1-2 \frac{k\delta}{2i} (\epsilon-1) \right] + 2 \frac{k\delta}{2i} (\epsilon-1) \cos 2k(b-c) \right\} . \tag{3.23}$$

When (3.21) and (3.22) and substituted into (3.18) the resulting line integral is again of the form considered by Scott[6]. The combination of the asymptotic expression for the line integral and the term given by (3.23) in the expression (3.18) yields the Luneberg-Kline contribution to the back-scattered field, namely

$$E_x^{bs} \sim - \frac{c}{2r} e^{ik(r-2c)} \left\{ \left(1 + \frac{1}{2ikc} \right) \left[1-2 \frac{k\delta}{2i} (\epsilon-1) \right] - \frac{1}{ikc} \frac{k\delta}{2i} \left(1 - \frac{1}{\epsilon}\right) \frac{c^2}{b^2} \right\}$$

$$- \frac{b}{2r} e^{ik(r-2b)} \left\{ \left(1 + \frac{1}{2ikb} \right) \frac{k\delta}{2i} (\epsilon-1) - \frac{1}{2ikc} \frac{k\delta}{2i} \left(1 - \frac{1}{\epsilon}\right) \right\}$$

$$- \frac{c}{2r} e^{ik(r+2b-4c)} \left\{ \frac{k\delta}{2i} (\epsilon-1) \left(\frac{b}{2b-c}\right) + \frac{2}{3ikc} \frac{k\delta}{2i} (\epsilon-1) \left[1 - \frac{1}{4} \frac{2b^3 - c^3}{(2b-c)^3} \right] \right.$$

$$\left. - \frac{1}{2ikc} \frac{k\delta}{2i} \left(1 - \frac{1}{\epsilon}\right) \frac{c^2}{b^2} \left(\frac{b}{2b-c}\right)^2 \right\} \tag{3.24}$$

The first order term in this expansion agrees with the geometrical-optics expression given in (3.6).

The dominant contribution to the backscattered field arises, of course, from the term

$$- \frac{c}{2r} e^{ik(r-2c)}$$

corresponding to specular reflection from the conducting sphere. The next important contributor to the geometrical-optics field arises from

(6) Scott, Ibid.

$$-\frac{b}{2r}\frac{k\delta}{2i}(\epsilon-1)\,e^{ik(r-2b)}$$

corresponding to reflection from the radome itself. This term is small compared to the leading term provided

$$k\delta(\epsilon-1)\frac{b}{c} \ll 1.$$

3.4.2.2 Target Location

Since no radome material exists which will transmit all frequencies of interest with 100 per cent efficiency, it is necessary to locate the segment where the smallest amount of multiply-reflected energy returns to the radar. To determine this location, considerations were given to the key factors shown below.

A. Scattering from the Edges of the Balloon and Mounting Structure

Even though the termination is designed to minimize backscattering, the relatively small radius of curvature here will tend to scatter energy off the roof and floor of the radome. This can be minimized by locating the segment half way between the top and bottom of the radome. The return from this contribution will be approximately,

$$\sigma_I \approx R\,\frac{\pi\, a^2\, R_o}{4\sqrt{2}\, d}$$

where $2\,R_o$ is the diameter of the balloon segment $2\,R_o \approx 22$ feet, a is the radius of curvature of the termination, d is distance from termination to radome and R is reflection coefficient of radome.

B. Standing Waves Set up Between Parallel Surfaces

If the segment is located incorrectly it is possible for the surfaces to be parallel and perpendicular to the line joining them. If so, a standing wave will be set up between the surfaces which will be fed by almost any direct source of scattering in the neighborhood.

Equation of Radome: $R_R^2 = X_R^2 + Y_R^2$

Normal: $\hat{N}_R = {}^{X_R}/_{R_R}\ \hat{X} + {}^{Y_R}/_{R_R}\ \hat{Y}$

Equation of Segment: $R_B^2 = (X_B - X_1)^2 + (Y_B - Y_1)^2$

Normal: $\hat{N}_B = (X_B - X_1)/(R_B\ \hat{X} + (Y_B - Y_1)/R_B\ \hat{Y}$

A line passing through the center of curvature of the segment will intersect both segment and radome normally only if it passes through the radome center.

$$\tan \phi_B = {}^{Y_1}/_{X_1} \quad \text{(Condition II)}$$

The condition in Section A requires (X_1, Y_1) to be high enough that the lower edge of the segment is approximately at radome center. The above condition II and condition I can be satisfied if the segment is moved forward from the center of the radome but not if the segment is moved backward.

C. Focusing

There are two important foci of the radome. The first is due to the reflection of energy off the rear of the radome. This energy will be focused near $(Y = 0, X = 1/2\ R_R)$. The second focus is at the center of the radome. Scattering from any small discontinuity in the radome or from an object at the center of the radome will be focused here.

If the segment is located at the center or towards the rear, the lower edge of the termination will be in or near one or the other of these foci.

D. Backscattering

The condition required for backscattering is that the ray deflected from the balloon surface at an angle $2\ \phi_B$ be reflected normally from the radome surface. This occurs when

$$R_B \sin \phi_B + X_1 \sin 2\phi_B - Y_1 \cos 2\phi_B = 0$$

ϕ_B is limited by the size of the segment

$$\phi_B - 180 = \frac{S_B}{R_B} = \frac{22'}{67.5'} = 0.163 \text{ rad} = 9.32^o$$

In the worst cases $\phi_B = 180 \pm 9.32$

$$\mp .162\ (67.5) \pm X_1\ (.320) - Y_1\ (.950) = 0$$

and

$$Y_1 = \mp 11.5 \pm .336\ X_1 = \pm 6.3' \text{ (If segment is 15' forward)}$$
$$= \pm 12.3' \text{ (If segment is at center)}$$
$$= \pm 18.3' \text{ (If segment is 15' back)}$$

In order to avoid backscattering of this type, the center of the balloon segment must be higher than the maximum values given above at each location.

Within conditions I, II, and III, we see that only in the forward position where $Y_1 \approx 9.5'$ can condition IV be satisfied.

NOTE: at center position $Y_1 \approx 11'$
at rear position $Y_1 \approx 10'$

At the position $X_B = -10'$ (10 feet forward) Y_1 must be greater than 8.0' to satisfy (IV) at this position, (I) requires $Y_1 = 10.5'$.

3.4.3 Measurement Considerations

In a CW measurement system of the type which Conductron uses, background contributions can be a serious problem. If an unbalanced system is used, the amplitude of the reflected wave must be sufficiently below the amplitude of the wave scattered from the target to preclude errors due to phase additions and subtractions. If, on the other hand, a balanced system is used, we are less concerned with the background and much more concerned with extent to which the background is modified by the placement of the target in the field.

The results of the theoretical analyses shown above indicate that the level of energy backscattered directly from the radome should be well below



Figure 3.8 The Optimum Location of the Test Fixture

that of the usual target measured inside the radome. However, when the target is located in the equatorial plane of the radome, three specular sources, the near and far side of the radome plus the target, contribute to the backscattered field. When no target is in the radome the field comes primarily from the front and rear specular points of the radome. This field is designated:

$$E_{radome} = E_i e^{i\phi_1} + E_2 e^{1\phi_2}$$

When the CW radar bridge is balanced this involves the introduction of signal into the detector such that:

$$E_{detected} = E_1 e^{i\phi_1} + E_2 e^{i\phi_2} - E_1 e^{i\phi_1} - E_2 e^{i\phi_2} = 0$$

Thus when a target is placed in the radome the detected signal becomes:

$$E_{detected} = E_1 e^{i\phi_1} + E_2 e^{i\phi_2} - E_1 e^{i\phi_1} - E_2 e^{i\phi_2} + E_3 3^{i\phi_3} = E_3 e^{i\phi_3}.$$

However, when a target large enough to completely shield the rear specular zone is measured, the detected signal is:

$$E_{detected} = E_3 e^{i\phi_3} - E_2 e^{i\phi_2}$$

Since $|E_2|^2 \approx \frac{1}{2} |E_1|^2$ the measured cross section of a target placed in the radome's equatorial plane is,

$$\sigma_{meas.} \approx \sigma_{target} + \frac{1}{2} \sigma_{radome} - \sqrt{2} (\sigma_t \sigma_r)^{1/2} \cos (\phi_3 - \phi_2).$$

The phase, $\phi_3 - \phi_2 = 2k \ell$, varies as a function of the distance between the target and the back wall and it can be seen that if σ_r is much greater than $0.02 \sigma_t$, a noticeable error could result. This error can be eliminated by moving the target up in the radome. The target must be located sufficiently above the equatorial plane so that the shadow area which is caused by the placement of the target in the field is not a significant contributor to the

radar cross section of the radome. As noted above, σ_{r_2} is of the order of 0.5 m^2. For the segments σ_t is of the order of 1200 m^2 and thus no noticeable errors should be introduced by shadowing the back wall.

Except as noted above, the radome-target multipath contributions are approximately,

$$\sigma_{multipath} \approx R\ \sigma_{target}$$

where R ($\approx 2 \times 10^{-3}$) is the radome reflection coefficient. These contributions can be safely ignored for the large backscattered echo area targets usually measured inside the radome.

The above considerations eliminate the necessity of further considering the multipath errors caused by the general range geometry. After the radome is eliminated as a significant source of backscattered energy, the problem reduces to one of the same type as has previously been considered in other phases of this program. One might point out that the radome, being spherical in shape, is an isotropic scatterer and thus the fresnel zone on the ground will be illuminated with energy which is of the same intensity as the primary wave. It can be shown, however, that the pattern of the receiving antenna is such that the energy from the fresnel zone is not received in the area of a pattern maximum. Even if this were not the case, and the waves were of equal amplitude at the receiving antenna, the magnitude of the radome reflection coefficient is such that the resultant effective echo area would still be less than $1m^2$, and thus of no importance to segment measurements.

3.4.4 Experimental Evaluation

In addition to the above described analytical evaluations, the radome was evaluated experimentally. A series of measurements were performed in the X- and C-band microwave frequency regions on several different spheres and flat plates to determine if their reflection patterns or echo areas were changed by placement in the radome.

For radar cross section measurements, Conductron generally uses a CW measurement technique. For this project a bistatic system with $\beta \leq 3^o$ was

used and Figure 3.9 is a representative block diagram of such a system. In general, the measurement system consists of a microwave network used in conjunction with a Scientific-Atlanta series 402B Wide Range Receiver and a Scientific-Atlanta model APR-23 linear-logarithmic rectangular recorder. The output data were provided in rectangular analog recordings of backscattered power versus azimuth rotation angle. The recorder specifications include accuracies of ± 0.25 db in power and ± 0.05° in azimuth angle, and a linearity of 0.5 db over the full 40 db dynamic range.

The microwave network consists of a frequency source, an antenna, and the necessary microwave components and transmission lines. For this project the frequency sources used were phase-stabilized klystron oscillators having output powers of greater than 0.5 watt. Linearly polarized parabolic reflector antennas were used as the radiation sources and were mounted in such a way that the electric vector could be oriented at any angle. A Scientific-Atlanta Model PP-13 polarization positioner, having an angular accuracy of 0.05°, was used for this purpose.

The first step in the measurement procedure was to place an azimuth positioner in the correct spot and make sure that the turntable was perfectly level. When this was accomplished, a Dylite support column was set in place. The column was rotated and a K & E model KE-1E theodolite was used to assure that the column was centered and level. The composite background return, including reflections from the model support structure as well as from the radome and the general range, was cancelled in a balancing network. The model was then placed on the support column and the theodolite was used to minimize position error. The model was then rotated 360° in azimuth and the backscattered power plotted as a function of rotation angle. After the measurement was completed the model was removed from the column and a check made to assure that the background level had not changed. In cases where the background level had changed, the data was discarded.

Figures 3.10 through 3.22 are typical of the measurement data which was obtained. The information in the data box of each pattern will serve to identify the pattern. It will be seen that four separate targets were



Figure 3.9 Block Diagram of Typical Bistatic CW Measurement System


Figure 3.10
Pattern 6637
Frequency: 1300
Polarization: Vert
Range: 160 ft.
Model: 1 Ft^2 Flat Plate
Calibration 3.5" Sphere
RELATIVE POWER ONE WAY (db)
ANGLE
0
1°
6°
36°
2°
12°
72°
3°
18°
108°
4°
24°
144°
30°
CHART No. 121
SCIENTIFIC-ATLANTA, INC., ATLANTA, GEOR


Figure 3.11
Pattern 5856R
Frequency 1.3K
Polarization: Vert
Range: 180 ft.
Model: 1 Ft. Sq. Flat Plate
Calibration: none
RELATIVE POWER ONE WAY (db)
RELATIVE POWER ONE WAY (db)
ANGLE


Figure 3.12
Pattern 5858R
Frequency: 1.3K
Polarization: Horz
Range: 180 ft.
Model: 1 Ft. Sq. Flate Plate
Calibration: none
RELATIVE POWER ONE-WAY (db)
ANGLE
CHART No. 121
SCIENTIFIC-ATLANTA, INC., ATLANTA, GEO


Figure 3-13
Pattern 5859R
Frequency: 1.3K
Polarization: Horz
Range: 180 ft.
Model: 2 Ft. Sq. Flat Plate
Calibration: none
RELATIVE POWER ONE-WAY (db)
ANGLE


Figure 3.14
Pattern 5860R
Frequency: 1.3K
Polarization: Horz
Range: 180 ft.
Model: Background
Calibration: 3.5" Sphere
RELATIVE POWER ONE WAY (db)
ANGLE
CHART No. 121
SCIENTIFIC-ATLANTA, INC. ATLANTA, GEOR


Figure 3.15
Pattern 5853R
Frequency: 1.73K
Polarization: Vert
Range: 180 ft.
Model: 1 ft. Sq. Flat Plate
Calibration: none
RELATIVE POWER ONE WAY (db)
ANGLE
SCIENTIFIC-ATLANTA, INC. ATLANTA, GEO.
CHART No. 181



Figure 3.16
Pattern 5850R
Frequency: 1.73K
Polarization: Horz
Range: 180 ft.
Model: 1 Ft. Sq. Flat Plate
Calibration: none


Figure 3.17
Pattern 585LR
Frequency: 1.73K
Polarization: Horz
Range: 180 ft.
Model: 2 Ft. Sq. Flat Plate
Calibration: none
RELATIVE POWER ONE-WAY (db)
ANGLE



Figure 3.18
Pattern 5852R
Frequency: 1.73K
Polarization: Vert.
Range: 180 ft.
Model: 2 ft. sq. Flat Plate
Calibration: none


Figure 3.19
Pattern 585AR
Frequency: 1.73K
Polarization: Vert
Range: 180 ft.
Model: Background
Calibration: 11.85" Sphere
RELATIVE POWER ONE WAY (db)
ANGLE


Figure 3.20
Pattern 5855R
Frequency: 1.73 K
Polarization: Horz
Range: 180 ft.
Model: Background
Calibration: 11.85" Sphere
RELATIVE POWER-ONE WAY (db)
ANGLE
CHART NO. 181
SCIENTIFIC-ATLANTA, INC., ATLANTA, GA.


Figure 3.21
Pattern 5883R
Frequency: 5.6G
Polarization: Horn
Range: 150 Ft.
Model: Background
Calibrations: 3-0° Sphere
RELATIVE POWER-ONE WAY (db)
ANGLE
CHART No. 181


Figure 3.22
Pattern 5886R
Frequency: 5.6K
Polarization: Horz
Range: 150 Ft.
Model: 1" Sq. Flat Plate
Calibration: none
RELATIVE POWER ONE-WAY (db)
ANGLE
CHART No. 121
SCIENTIFIC-ATLANTA, INC., ATLANTA, GEO

measured: a flat plate 1 foot square, a flat plate 2 feet square, a sphere 3.5 inches in diameter, and a sphere 11.85 inches in diameter. The results of these measurements indicated an excellent agreement with the theory.

For example, Figure 3.10 is the radar cross section of a flat plate which is 1 foot square, as measured outside the radome, and Figure 3.11 is the same plate measured inside the radome. This was a very important test since the radar cross section of the flat plate is very nearly equal to that of the radome. In Section 3.4.1 above, the radome was estimated to have a radar cross section of approximately 0.5 square meters or -6.0 db $> m^2$. The flat plate radar cross section is given by:

$$\sigma_{\text{flat plate}} = \frac{4\pi A^2}{\lambda^2}$$

where

A = flat plate area

λ = wavelength and at 1.3 kmc = .23 meters

$\sigma_{\text{flat plate}} = 3.1$ square meters

$\tilde{=} 5.0$ db $> m^2$

Thus the difference in radar cross section between the flat plate and the radome is approximately 11 db and thus we would expect some distortion of the flat plate pattern as taken in the radome. Figure 3.11 shows some distortion in the sidelobe structure and indicates that the estimate of the radome echo area is essentially correct.

Figure 3.13 shows two reflection patterns of a flat plate 2 feet square mounted in the radome. These two patterns were taken at two different times and show the repeatability which can be obtained. Time stability is necessary to the correct evaluation of the ECHO segments and this pattern shows that the time stability of the measurement system is not affected by the presence of the radome. In general,the experimental data was consistent with previous estimates and it appears that excellent results will be obtained on the segment measurements, with no adverse effects introduced by the radome.

3.4.5 The Radome as a Housing for a Transmitting Antenna

As indicated at the beginning of Section 3.4, Conductron performed a limited analysis to determine the suitability of the radome as a housing for a transmitting antenna. The theoretical hypothesis was that a free space dipole antenna was located at the center of a large, spherical, thin-wall radome. The problem is to determine the extent to which the antenna radiation pattern is affected by the presence of the radome.

If the dipole source is located at the center of the spherical dielectric shell, the problem is straightforward and has already been solved by the Kellers[7] who considered the more general three-medium problem. Hence for our purpose, all that is required is to modify their results.

The notation we shall use is the same as in Reference (8) and differs from the Kellers' notation. The electromagnetic fields $\vec{E}\, e^{-i\omega t}$ and $\vec{H}\, e^{-i\omega t}$ are written in terms of the vector potential $\vec{A}\, e^{-i\omega t}$ satisfying

$$(\nabla^2 + k^2)\, \vec{A} = 0 \qquad (3.25)$$

in the following manner

$$\vec{H} = \nabla \wedge \vec{A}\ ,$$

$$\vec{E} = \frac{i\omega}{k^2} [\nabla (\nabla \cdot \vec{A}) + k^2 \vec{A}]. \qquad (3.26)$$

For a point dipole with axis in the z-direction, in a medium of infinite extent, the solution of Equation (3.25) is found to be a vector with a single component

$$A_z = A_o\, (e^{ikr}/r), \qquad (3.27)$$

where A_o is a constant proportional to the dipole strength.

---

(7) H. B. Keller and J. B. Keller, "Reflection and Transmission of Electromagnetic Waves by a Spherical Shell", J. App. Phys. 20, 393-396 (1949).

(8) J. J. Bowman, "High-Frequency Scattering from a Conducting Sphere Surrounded by a Thin-Wall Radome", Conductron Memo D4420-233-M, August 20, 1964.

With the presence of the spherical dielectric shell, the solution of Equation (3.25) is a vector with the following non-zero component

$$A_z = A_o \frac{e^{ikr}}{r} + A_1 \frac{e^{-ikr}}{r}, \quad 0 < r < b$$

$$A_z = A_2 \frac{e^{ik_1 r}}{r} + A_3 \frac{e^{-ik_1 r}}{r}, \quad b < r < a \tag{3.28}$$

$$A_z = A_4 \frac{e^{ikr}}{r}, \quad a < r$$

where $k_1 = \sqrt{\epsilon} k$ is the propagation constant with the dielectric. The coefficient A_1 for the reflected field and the coefficient A_4 for the transmitted field are given by Keller. Adopting and simplifying their expressions to suit our problem, we find

$$\frac{A_1}{A_o} e^{-2ikb} = \frac{(1-\epsilon)\left[F(\sqrt{\epsilon})\, G^*(-\sqrt{\epsilon}) - F(-\sqrt{\epsilon})\, G^*(\sqrt{\epsilon})\, e^{2ik_1\delta}\right]}{(1+\sqrt{\epsilon})^2 F(\sqrt{\epsilon})\, G(\sqrt{\epsilon}) - (1-\sqrt{\epsilon})^2 F(-\sqrt{\epsilon})\, G(-\sqrt{\epsilon})\, e^{2ik_1\delta}}, \tag{3.29}$$

$$\frac{A_4}{A_o} = \frac{4\sqrt{\epsilon}\, e^{-ik\delta}}{(1+\sqrt{\epsilon})^2 F(\sqrt{\epsilon})\, G(\sqrt{\epsilon})\, e^{-ik_1\delta} - (1-\sqrt{\epsilon})^2 F(-\sqrt{\epsilon})\, G(-\sqrt{\epsilon})\, e^{ik_1\delta}}, \tag{3.30}$$

where

$$F(\sqrt{\epsilon}) = 1 - \frac{1}{ika}\left(1 - \frac{1}{\sqrt{\epsilon}}\right) - \frac{1}{k^2a^2}\left(1 - \frac{1}{\sqrt{\epsilon}}\right)^2 - \frac{1}{i\sqrt{\epsilon}}\,\frac{1}{k^3a^3}\left(1 - \frac{1}{\sqrt{\epsilon}}\right),$$

$$G(\sqrt{\epsilon}) = 1 + \frac{1}{ikb}\left(1 - \frac{1}{\sqrt{\epsilon}}\right) - \frac{1}{k^2b^2}\left(1 - \frac{1}{\sqrt{\epsilon}}\right)^2 + \frac{1}{i\sqrt{\epsilon}}\,\frac{1}{k^3b^3}\left(1 - \frac{1}{\sqrt{\epsilon}}\right),$$

and $\delta = a-b$. When ka and kb become infinite while $a-b = \delta$ and $r-b = x$ remain

finite and A_o (e^{ikb}/r) approaches a limit A_o', the problem reduces to that of plane waves normally incident on a flat plate separating two identical half-infinite media [See e.g. Reference (2) pp. 512(9)].

We are interested in the expansion of the transmitted field under the conditions

$$kb \gg 1 ,$$

$$k_1\delta \ll 1 ,$$

and we obtain, to first order in $k\delta$,

$$\frac{A_4}{A_o} = 1 - \frac{k\delta}{2i}(\epsilon-1) + \frac{1}{ikb}\,\frac{\delta}{2b}\,\frac{(\epsilon-1)(\epsilon-2)}{\epsilon} + O\left(\frac{1}{k^3b^3}\right) . \qquad (3.31)$$

Recall that to this order in $k\delta$, the amplitude transmission coefficient for a plane sheet is given by

$$T_E = T_H = 1 - \frac{k\delta}{2i}(\epsilon-1) \qquad (3.32)$$

Since the transmission coefficient of the material in the NASA radome is high, we would not expect to encounter any difficulty in using this radome as a housing for a transmitting antenna.

4. TEST FIXTURE

A test fixture has been constructed inside the radome which is capable of accepting segments of satellite material for radar transmission and reflection testing. The basic structure is constructed of light-weight aluminum and is 20 feet in diameter. An inflatable torus is fitted around the outside circumference to achieve an overall diameter of 22 feet. The satellite material is mounted on the front of the fixture with its edge passing over the torus. An air-tight seal is made between the satellite material and structure. An inflation envelope is made by enclosing the back of the fixture with a film of mylar 0.0075 inch thick. An air tight seal is also made between the mylar film and the structure. The fixture is mounted on a heavy duty, three-axis antenna positioner which was supplied to Conductron for use on this project by the National Aeronautics and Space Administration. The concept is shown in Drawing #124204 in Appendix B, and the assembled test fixture is shown in Figure 4.1 and 4.2.

4.1 Construction of Basic Structure

The basic structure is circular in shape and constructed of light-weight aluminum. A complete set of fabrication drawings are included in this report as Appendix B.

The outer rim of the structure is made of 14 aluminum castings having a configuration as shown in Drawing #122402. As can be seen from the drawing, each casting has a doubly curved surface. The concave rim surface has a 6 inch radius of curvature and was designed as a mounting face for the inflatable torus. The convex rim surface is curved so that when the castings are bolted together end to end, a circular structure 20 feet in diameter is formed. Each casting was fabricated using typical sand casting techniques and X-rayed to insure freedom from structural defects. The surface irregularities were removed by sandblasting or hand grinding wherever necessary. The planer surface of each casting was milled to a tolerance of $\pm$ .005 inch to provide a flat mounting surface for the support trusses, the segment material, and the mylar film.

The rim structure is supported by four trusses which are constructed of aluminum tubing. Mounting plates are welded to each end of the truss structure so that the truss can be bolted to the rim and to the positioner mounting plate. The



Figure 4.1 Test Fixture, Front View



Figure 4.2 Test Fixture, Rear View

support trusses also provide a mounting base for the transmission measurement antenna assembly. The truss assembly is shown in Drawing #122407 and in Figure 4.2, the mounting plate is shown in Drawing #122430, and the antenna assembly is shown in Drawing #122457.

The fixture is assembled by first bolting together the rim structure in an inverted position so that the planer mounting surface is upward. A cork gasket is then cemented to the mounting surface and the mylar backing material is bonded to the cork. The support trusses are then bolted to the rim structure and the positioner mounting plate is bolted to the trusses tying the entire structure together. Figure 4.3 shows the method which is used to attach the rim sections together and the attachment between the rim and the support trusses. Figure 4.4 shows the attachment between the support trusses and the positioner mounting plate.

The mylar retaining ring is then bolted into place making an air-tight seal between the rim structure and the mylar. The retaining ring is constructed of 0.125 inch aluminum and is 3.9 inches wide. It is made in seven sections which are arranged so that each joint in the rim structure is spanned. A cork gasket is bonded to the under side of the ring, to insure the mylar air seal, and a foam rubber gasket is bonded to the upper side to protect the segment material from any sharp edges. The retaining ring is slotted and keyed to prevent interference with the support trusses.

The entire structure is then turned over, so that the mounting plate is on the under side, and placed on the antenna positioner. The weight of the structure is approximately 650 pounds, thus in order to turn it over, it is necessary that an overhead support mechanism, such as a crane, be employed to insure personnel and equipment safety. When the structure is turned over the positioner mounting plate is fastened securely to the antenna positioner using twelve 0.5 inch diameter bolts.

The torus is then installed by first positioning the air inlet valves on the inside diameter of the torus with the pass holes in the rim structure. The torus is then fitted to the outside rim in the same manner as an inner tube would be positioned. When the torus has been mounted and inflated the segment material can be mounted so that it passes over the torus. The material is held securely in place by the segment retaining ring. This ring is also constructed of 0.125 inch



Figure 4.3 Rim Attachments



Figure 4.4 Mounting Plate Attachments

aluminum but is only 2.0 inches wide. It is made in seven sections and the bolting arrangement is such that each joint in the rim structure and in the mylar retaining ring spand. A foam rubber gasket is bonded to the under side of the ring to insure an air seal between the segment material and the rim structure and to prevent damage to the segment material from any sharp metallic edges. A cross section of this entire assembly is shown in Drawing #124205.

4.2 Construction of the Torus

The torus is a bi-tubular structure designed to be capable of increasing its outside diameter, uniformly, from 22 feet to 22.5 feet. One tube, referred to as the main torus, has an outside diameter of 22 feet and a tube diameter of 1 foot. This is maintained at a constant pressure level so that it never changes size or shape. The second tube, referred to as the bladder, is attached to the outer circumference of the main torus. The bladder is expandable as a function of internal pressure and provides the capability for increasing the outside diameter from 22 feet to 22.5 feet. Figure 4.5 shows the torus with the bladder deflated, and Figure 4.6 shows the bladder inflated. The torus was designed and built by Raven Industries, Ind. of Sioux Falls, South Dakota.

The objective in constructing this torus was to provide a method for maintaining the overall radius of curvature as the segment skin stress increases. When the segment is initially mounted on the test fixture, the envelope formed between the segment and the mylar film is inflated just enough so that the segment will assume its designed shape.

The segment contour is measured using an optical technique. A vertical index rod is placed close to the segment with the plane defined by the fixture rim normal to the ground. A horizontal index rod is placed underneath the segment and fixture. A photograph is then taken and compared with a standard grid. In this way a silhouette contour is obtained. The segment is then rolled about its axis and silhouette contours are obtained to insure that the segment is symmetrical. Figure 4.7 is a curve showing segment radius of curvature as a function of the distance between the segment center and the plane defined by the front edge of the torus.

When the initial contour has been defined it is necessary to maintain that



Figure 4.5 Torus, Bladder Inflated



Figure 4.6 Torus, Bladder Deflated



Figure 4.7 Radius of Curvature VS Deflection for a 22 Foot Diaphram Tester

contour throughout the remainder of the tests. As the internal pressure between the segment and the mylar film is increased the segment skin stress increases and the segment material expands. The overall radius of curvature may be maintained by expanding the edge diameter to compensate for the material expansion. As the material skin stress increases the tension loading on the torus increases proportionately.

The main torus is a gored structure made of a dacron-mylar material. The tolerance on the inside diameter was specified to be + 0 and -1/4% of the inside diameter when the structure is maintained at the operating pressure under no load. The tolerance on the outside diameter was specified to be $\pm$ 0.5 inch when maintained at the operating pressure under no load and with the bladder collapsed. The bladder is a nylon-mylar material constructed in the same way as the main torus.

One of the more important problems in the design of the torus was to determine the material strength required to withstand the shear forces exerted by the segment material. If one considers a torus supporting a spherical cap, as shown below, the material stresses in the cap should be the same as those in a full sphere having the same radius of curvature and the same internal pressure, p_s. The stresses should then be given as



$$S_s = \frac{p_s \; r}{2t} \text{ psi}$$

where t is thickness and r is radius, both in inches. If the maximum inflation pressure were .0723 (2 inches of water) in a sphere of 67.5 ft. radius, the skin stresses per unit thickness will be

$$S_s t = \frac{p_s \; r}{2} = \frac{.0723 \cdot 67.5 \cdot 12}{2} = 29.28 \text{ lbs./in.} \quad \text{(See Figure 4.8)}$$

One can then consider the half torus shown below as loaded evenly with centrally directed loads of L lbs./in. about its circumference. A free force analysis of this section then indicates that the components of load directed normal to the diameter of the torus along which it was severed must be opposed by the forces on



Figure 4.8 Pressure VS Stress for S-SIN-1 & 2 Material at Various Radii ($t = 7.35 \times 10^{-4}$ in)

the severed cross sections, i.e.



$$2p_{iA} = \pi\ r\ L \int_{o}^{\pi} \sin\theta\ d\theta$$

$$2p_i\ \pi\ r^2 = \pi\ r\ L\ 2$$

$$p_i = \frac{L}{r} = \frac{29.28\ \text{lbs./in.}}{6\ \text{in.}}$$

$$p = 4.88\ \text{psi}$$

In a case in which the structure is to be used repeatedly and must never be allowed to expand into an inelastic region of elongation, safety factors of three or more are justifiable. The greatest stress on the torus will be in a circumferential direction given by

$$S_c = \frac{p_i\ r}{t}$$

for a tube radius of 6 inches, an internal pressure of 5 psi, and a safety factor of 3, a material strength of

$$S_{ct} = 15.6 = 90\ \text{lbs./in.}$$

is necessary.

High-strength fabric materials are usually heavy and stiff and, therefore, unsuitable for repeated handling. The only material which was suitable for this application was the dacron-mylar bi-laminate. This material is light, weighing only 3.2 ounces per square yard, and is flexible and easy to handle. The material has a strength of approximately 140 pounds per inch.

The second main design problem was the construction of the bladder. In order to properly design the bladder it was necessary to determine the way in which

a bladder expands as a function of tension in the segment material and pressure in the bladder. Tests were performed on a cylinder section, approximately five feet in height and one foot in cross section, simulating a section of the actual torus. Tests were conducted on bladders of six inch and eight inch diameters (fully expanded). The entire test model was constructed of nylon-mylar material.

The test apparatus is shown schematically in Figure 4.9. The basic support was a cylinder section made of sheet steel in the form of a 5" arc of a 1 foot diameter cylinder, five feet long, (C). (A) and (B) are the main torus and bladder, respectively, (D) is a 0-2 psi pressure gauge and (E) and (F) are control valves to allow reading the air pressure in the bladder. (G) are screw closure valves leading to the bladder and torus, respectively. (H) is a Hunter load gauge, (L) is the loading membrane, and K is a crank to allow adjustment of the load.

The experimental procedure is as follows:
The cylinder section, with the bladder collapsed, is placed in the rig and the desired air pressure is placed in the main tube, which is then sealed off. The desired load level is registered on the Hunter gauge by adjusting crank K. The bladder is then inflated slowly, while maintaining a constant load on the membrane. As the pressure in the bladder increases, the increase in the bladder expansion along the x axis of Figure 4.9, is recorded as a function of pressure by measuring the distance between the outermost point of the bladder and a fixed reference point on the x axis.

These points are shown in the graphs Figure 4.10 and 4.11, for the six inch and eight inch diameter bladders, respectively. The theoretical curves shown in each of these graphs are plotted from the results of a theoretical analysis of the bladder operation.

Assuming the bladder material to be partially in the form of two half cylinders of radius r and the rest in the form of two cylinder segments subtending an angle θ at the center of the main cylinder as shown below. These sections have radii of R and R + 2r. The total surface area of the bladder must always be a constant given by $A_T = 2\pi r_o h$ where r_o is the radius of the fully expanded bladder, and h is the cylinder height.

The loaded membrane may, at any time, be considered as being supported by the area A, given by



Stress Model



Figure 4.9 Bladder Test Fixture



Figure 4.10 Comparison of Theory and Experiment 6" Bladder



Figure 4.11 Comparison of Theory and Experiment 8" Bladder

$$A = \frac{\theta\ 2\pi}{2\pi}\ (R+2r)h = \theta h\ (R+2r)$$



Now θ may be found from the fact that surface area of the bladder is a constant so that

$$A_T = 2\pi\ r_o h = \theta h\ (R+2r) + \theta\ Rh$$

or

$$\theta = \frac{\pi\ (r_o - r)}{R + r}$$

$$\therefore\ A = \frac{h\ (R + 2r)\ \pi\ (r_o - r)}{R + r}$$

The force exerted by the tension in the loading medium must be counteracted by the pressure, P, in the bladder acting over area A . .

$$PA = 2T = \text{const.}$$

One additional limitation on θ exists, however, in that the bladder is taped to the main torus over a reasonably large area so that full expansion is not possible.

In the case of the six inch diameter tube, the minimum value that θ can attain is 2/3 rad. resulting in a maximum bladder diameter of 2.8 inches as shown by the rapid "tailing off" of the P vs d curve in Figure 4.10. A similar analysis shows that the maximum diameter for the eight inch bladder should be 3.81 inches. These lines are shown as theoretical cut-off lines in Figures 4.10 and 4.11. Of course, the bladder will not be in the assumed shape throughout its expansion. Thus the agreement between experiment and theory is expected primarily as low pressures. Also, it is probable that readings will be obtained above the

theoretical limit. Also, 2T was taken as 100 lbs. throughout the tests. The pressure in the main torus was maintained at 1.0 psi.

The agreement between theory and experiment is excellent for the six inch bladder and is fairly good for the eight inch bladder. A good deal more difficulty was encountered in obtaining the latter data due to the difficulty in keeping the bladder from rotating as the load membrane was adjusted. This difficulty is not expected in the actual torus, partly because the hoop stresses on the inflating bladder will tend to make it maintain its position and partly because frictional forces between the bladder and segment material are expected to be much smaller.

It is expected, therefore, that theory will provide a reasonably accurate representation of bladder pressure vs expansion.

The eight inch diameter bladder was adopted for use in the torus itself since the pressure vs expansion curve will remain in the near-linear range over the 3 inch expansion desired.

5. INSTRUMENTATION

The instrumentation at the radome facility was designed for the measurement of large pressurized segments. The four systems which comprise the facility instrumentation are:

(1) R. F. System
(2) Pressure monitoring System
(3) Positioning system
(4) Bistatic Cart

A block diagram of the instrumentation is shown in Figure 5.1.

5.1 R. F. System

The R. F. system consists of a setup for measuring the amount of energy which is reflected from the front side of the segment, and a setup for measuring the amount of energy which is transmitted through the segment.

The reflection measurement setup is considerably different from the one discussed in Section 3.4 above. No balancing network is required for measuring segment reflection since the segment radar cross section is the order of 1200 square meters. Therefore, the segment reflection characteristics can be measured with a simple two antenna system as shown in Figure 5.2 below.



Figure 5.2 Reflection Measurement System

The transmitted antenna is fixed at one end of the bistatic track. The receiving antenna is mounted on a portable tower. The tower rests on rails which extend the length of the bistatic track and is motor driven so that the position of the tower on the bistatic track can be changed remotely. Reflection



Figure 5.1 Radome Facility Instrumentation

measurements are possible using this antenna system at any bistatic angle from 0 to 30^{o}. The receiving antenna tower is discussed more completely in section 5.4 below. Both reflection and transmission measurements are possible at three different microwave frequencies. L. F. E. Series 814 ultrastable microwave oscillators are used as R.F. sources for all three (L, C, and X) frequency bands. These units have frequency stability of the order of 1 part in 10^{6}, long term and 3 parts 10^{8}, short term. The receiving and recording units are the Scientific-Atlanta series 402B and series APR-20 respectively. The specifications for this equipment are shown below.

RECEIVER SPECIFICATIONS MODEL 402B

Frequency Coverage	30 mc - 100 kmc
Dynamic Range	40db
Sensitivity	(30 mc - 10 kmc) = - 85 dbm
I.F. Frequency	65 mc
I.F. Bandwidth	1 mc
Linear Deviation of output	0.5 db

RECORDER SPECIFICATIONS MODEL APR-20

Pen Writing Speed = 40 inches/sec.
Pen Accuracy = 0.25 db
B.W. = 2% of center frequency @ 3 db
Chart Speed = 12 inches/sec.
Chart Cycle Length = 20 inches

The transmission measuring system consists of six standard gain horns, two each for the L, C and X band frequency regions. During operation, one antenna for each of the three bands is inserted into the pressurized compartment at the center of the radome, directly behind the test segment, (see Figure 5.3) thus allowing transmission measurement through the material to be made. The other three antennas are identical to the first, and are used to receive the direct signal from the transmitter, thereby providing the necessary calibration infor-



Figure 5.3 Antennas Used for a Transmission Measurements as Mounted on the Test Fixture

mation. The power received by the antennas is fed into a Hewlett Packard model 431B power meter which provides a visual indication of the transmitted power.

5.2 Pressure Monitoring System

The pressure monitoring equipment consists of one Equibar Type 120 pressure meter, which is used for monitoring segment pressure. One Marsh 0-10 PSI pressure meter which is used to monitor torus pressure, and one Monroe model 117A differential pressure transducer is used to measure the bladder pressure. The outputs of the models 117A and 120 pressure meters are fed to a Bausch and Lomb model VOM-5 recorder.



All of the pressure readings are taken relative to the radome pressure which is maintained at approximately 2.5 inches of water.

5.3 Positioning System

The positioning system consists of a 14 foot hydraulic cylinder, and a Scientific Atlanta azimuth over elevation over azimuth positioner.

The hydraulic cylinder can be controlled from within the radome, and provide continuous height adjustment of the segment. When the hydraulic system is in the full down position, the fixture is approximately 4.5 feet above the radome floor and provides an easy working height for segment mounting. This system is discussed more completely in Section 2 above.

The three-axis positioner provides continuous remote control of the targets pitch, roll and azimuth position, and is controlled at the mast control room by means of a Scientific-Atlanta model PC-4 positioner control. A few of the positioners specifications are listed below

Azimuth Accuracy	= $\pm$ .05^{o}
Elevation Accuracy	= $\pm$ 0.1^{o}
Azimuth Speed	= 1.5 RPM
Elevation Speed	= 90^{o}/Min.

1:1 and 36:1 syncros are provided on all three axes of the positioner, to drive the remote position indicator units, and necessary chart drive.

5.4 Bistatic Cart

The bistatic cart is driven by means of a remote controlled 3/4 H.P. D.C. motor and a 50:1 gear reduction. The drive motor is controlled by using a Scientific-Atlanta model Pc-4 Positioner Control Unit. The speed of the cart may be continuously adjusted from 0 to approximately 35 feet per minute, thus allowing the 30^{o} arc to be transversed in approximately 2.5 minutes. The antenna tower which is mounted on top of the bistatic cart allows continuous antenna height adjustment to approximately 15 feet above ground level. The antenna tower, cart and bistatic track are shown in Figure 5.4.

A 1:1 syncro transmitter is located on the receiver cart and is used to provide the necessary chart drive to the recording and position-indicating equipment. A drawing of the receiver tower is shown in Appendix A.





Figure 5.4 Bistatic Cart

APPENDIX A - SUPPORT FACILITY DRAWINGS



REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED

BIRDAIR #6406-4-6

QTY REQD 464	QTY REQD 364	QTY REQD 146	QTY REQD 101	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

SYM IDENTIFICATION
A:
B:
C:
D:
E:
F:

SHEET NO.	NEXT ASSY	USED ON

APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS .005 TO .015
TOLERANCES ON
DECIMALS XX ± .1 | DECIMALS XXX ± .02 | ANGLES ± 1°

MATERIAL

FINISH

DRAWN BY C. CEH
DATE DRAWN 1-8-64
DATE CHK'D
CLASS
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation
ANN ARBOR MICHIGAN

TITLE
BLOWER INSTALLATION
CONDUCTRON CORP.

CODE IDENT NO.	SIZE	DRAWING NUMBER
17468	D	SK-1936

SCALE 1/10 WEIGHT SHEET

[redacted]

REVISIONS

SYM	ZONE	DESCRIPTION	DATE	APPVD



QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION
1ST	2ND	3RD	4TH						

LIST OF MATERIALS

NEXT ASSY	USED ON

APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS .005 TO .015
TOLERANCES ON

DECIMALS	FRACTIONS	ANGLES
XX ±	XXX ±	±

MATERIAL

FINISH

DRAWN BY
DATE | BATCH | CHK'D | CLASS

CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation
ANN ARBOR MICHIGAN

TITLE

CODE IDENT NO.	SIZE	DRAWING NUMBER
17468	D	SK-1937

SCALE	WEIGHT	SHEET

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	SIZE	PART OR IDENT. DWG. NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION
SASSY 1A1	SASSY 1A2	SASSY 1A3	SASSY 1A4						

LIST OF MATERIALS

SYM	IDENTIFICATION
1	ASSEMBLY DRAWING
2	PARTS LISTING
3	SPECIFICATIONS AND/OR DRAWINGS
4	WIRE LIST AND/OR DIAGRAM
5	SCHEMATIC DIAGRAM
6	MISCELLANEOUS

SASSY NO.	NEXT ASSY	USED ON
APPLICATION		

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS - .005 TO .010
TOLERANCES ON

DECIMALS	DECIMALS	ANGLES
XX ±	XXX ±	±

MATERIAL

FINISH

DRAWN BY F.A. BETROS — DATE DRAWN — DATE CHECK — CLASS

CHECKED BY

MECH ENG

ELEC ENG

RELIABILITY

DESIGN APPR

APPROVED

Conductron Corporation — ANN ARBOR MICHIGAN

TITLE: BLOWER ASSY

CODE IDENT NO.	SIZE	DRAWING NUMBER
17488	D	SK-1938

SCALE 3/8"=1" — WEIGHT — SHEET

[redacted]

REVISIONS			
SYM	ZONE	DESCRIPTION	DATE



QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION
DASH NO.	DASH NO.	DASH NO.	DASH NO.						

LIST OF MATERIALS

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS - .005 TO .010
TOLERANCES ON
DECIMALS XX ± | DECIMALS XXX ± | ANGLES ±

MATERIAL

FINISH

APPLICATION

NEXT ASSY | USED ON

DRAWN BY F.A. BETROSS
DATE DRAWN | DATE CHK'D | ECSS
CHECKED BY
MECH ENG
ELEC ENG
REL/ABILITY
DESIGN APPR
APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE
RADOME

CODE IDENT NO. 17488 | SIZE D | DRAWING NUMBER SK 1939
SCALE | WEIGHT | SHEET

[redacted]

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION
								LIST OF MATERIALS	

SYM	IDENTIFICATION
A1	
A2	
A3	
A4	
A5	
A6	
A7	
A8	

SHEET NO.	NEXT ASSY	USED ON
	APPLICATION	

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS - .009 TO .015
TOLERANCES ON

DECIMALS	DECIMALS	ANGLES
.XX ±	.XXX ±	±

MATERIAL

FINISH

DESIGN APPR

APPROVED

DRAWN BY
DATE DRAWN | DATE CHK'D | CLASS

CHECKED BY

MECH ENG

ELEC ENG

RELIABILITY

Conductron Corporation ANN ARBOR MICHIGAN

TITLE

CODE IDENT NO.	SIZE	DRAWING NUMBER
17488	D	SK1941
SCALE	WEIGHT	SHEET



REVISIONS

SYM	ZONE	DESCRIPTION	DATE	APPROVED

LIST OF MATERIALS

QTY REQD ASSY NO. 1	QTY REQD ASSY NO. 2	QTY REQD ASSY NO. 3	QTY REQD ASSY NO. 4	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS - .005 TO .010
TOLERANCES ON
DECIMALS .XX ±
DECIMALS .XXX ±
ANGLES ±

DRAWN BY E.A. BETROSS
DATE 3/66/72
DATE CHK'D
CLSD
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE
CONTROL ROOM

CODE IDENT NO. 17[illegible]
SIZE D
DRAWING NUMBER SK1943
SCALE 1/4" = 1'-0"
WEIGHT
SHEET

MATERIAL	NEXT ASSY	USED ON
FINISH		
APPLICATION		

[redacted]

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



QTY REQD Mk	QTY REQD M1	QTY REQD 100	QTY REQD 101	ITEM NO.	MFR'S	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

[redacted]

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



FOOTING - 20" WIDE x 12" DEEP REINFORCED WITH TWO #4 RODS. 2500 PSI CONCRETE

QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

NEXT ASSY	USED ON
APPLICATION	

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS - .005 TO .010
TOLERANCES ON

DECIMALS	DECIMALS	ANGLES
XX ±	XXX ±	±

MATERIAL

FINISH

DRAWN BY F.A. BETROSS
DATE | CLASS
CHECKED BY
MECH. ENG.
ELEC. ENG.
RELIABILITY
DESIGN APPR.
APPROVED

Conductron Corporation
ANN ARBOR MICHIGAN

TITLE
CONTROL ROOM

CODE IDENT NO.	SIZE	DRAWING NUMBER
17488	D	SK1945

SCALE 1/2" = 1' | WEIGHT | SHEET

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



2 - ANCHOR BOLTS BY OTHERS.

1 - CHANNEL & PLATE RING BY BIRDAIR.

NOTE 1.



CLAMP RING UNIT
16 REQ'D.
SCALE: 1/2" = 1'-0"



SECT A-A
SCALE: 1/2 SIZE

QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION
SUBST 16A	SUBST 12A	SUBST 10A	SUBST 8A						

LIST OF MATERIALS

SYM	IDENTIFICATION
CE	ENGINEERING DRAWING
CS	SPECIFICATION
CM	MANUFACTURING SPECIFICATION
CA	ASSEMBLY DRAWING
CI	INSTALLATION DRAWING
CW	WIRING DIAGRAM

ASSY NO.	NEXT ASSY	USED ON
APPLICATION		

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS - .005 TO .015
TOLERANCES ON

DECIMALS	DECIMALS	ANGLES
XX ±	XXX ±	±

MATERIAL

FINISH

DRAWN BY D. FLEMING
DATE 5/8/64
DATE CHK'D
CLASS
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation
ANN ARBOR MICHIGAN

TITLE
BASE CLAMP RING ANCHORAGE LAYOUT
60' DIA. RADOME

CODE IDENT NO.	SIZE	DRAWING NUMBER
17488	D	SK1946

SCALE 1/2" = 1'-0" WEIGHT 514857

APPENDIX B - TEST FIXTURE DRAWINGS



REFERENCE DOG ONLY

			UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE PLATING OF FINISH	DRAWN BY		Conductron Corporation	ANN ARBOR MICHIGAN
			TOLERANCES ON: FRACTIONS / DECIMALS / ANGLES	DATE	1-21-65	TITLE	LAYOUT SEGMENT SUPPORT STRUCTURE
				CHECKED			
				ENGR APPR			
				SUPV APPR			
				QUALITY			
			MACH AND "ALLOW - ONE TO ANY	RELIABILITY			
			MATERIAL	DESIGN APPR		CODE IDENT NO.	SIZE / DRAWING NUMBER
QTY	NEXT ASSY	USED ON	FINISH	APPROVED		19468	E 5K 20019
APPLICATION						SCALE 1/7	WEIGHT / SHEET



PART NO. 122398-1

Conductron Corporation		ANN ARBOR MICHIGAN
TITLE: NUT		
CODE IDENT NO. 17468	SIZE B	DRAWING NUMBER 122398
SCALE 1:1	WEIGHT	SHEET



PART NO. 122399-1

Conductron Corporation		ANN ARBOR MICHIGAN
TITLE: NUT, RETAINING		
CODE IDENT NO. 17468	SIZE B	DRAWING NUMBER 122399
SCALE 1:1	WEIGHT	SHEET

NOTICE—WHEN GOVERNMENT DRAWINGS, SPECIFICATIONS, OR OTHER DATA ARE USED FOR ANY PURPOSE OTHER THAN IN CONNECTION WITH A DEFINITELY RELATED GOVERNMENT PROCUREMENT OPERATION, THE GOVERNMENT THEREBY INCURS NO RESPONSIBILITY, NOR ANY OBLIGATION WHATSOEVER; AND THE FACT THAT THE GOVERNMENT MAY HAVE FORMULATED, FURNISHED, OR IN ANY WAY SUPPLIED THE SAID DRAWINGS, SPECIFICATIONS, OR OTHER DATA IS NOT TO BE REGARDED BY IMPLICATION OR OTHERWISE AS IN ANY MANNER LICENSING THE HOLDER OR ANY OTHER PERSON OR CORPORATION, OR CONVEYING ANY RIGHTS OR PERMISSION TO MANUFACTURE, USE, OR SELL ANY PATENTED INVENTION THAT MAY IN ANY WAY BE RELATED THERETO.

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



PART No. 122400-1

QTY REQD EXHIBIT 104	QTY REQD EXHIBIT 103	QTY REQD EXHIBIT 105	QTY REQD EXHIBIT 101	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

SYM IDENTIFICATION
A ASSEMBLY DRAWINGS
B BULK ITEMS
C SPECIFICATIONS (CONDUCTRON)
D DETAIL ITEMS (FAB)
R REFERENCE DRAWINGS
V VENDOR ITEMS

EXHIBIT NO.	NEXT ASSY	USED ON

APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS-.005 TO .010
TOLERANCES ON

DECIMALS	DECIMALS	ANGLES
.XX ±.01	.XXX ±	±

MATERIAL
FA-20 THD ROD CRES

FINISH

DRAWN BY D.J. McCallum
DATE DRAWN 12/1/65
DATE CHK'D
CLASS
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation
ANN ARBOR MICHIGAN

TITLE
CRANK

CODE IDENT NO.	SIZE	DRAWING NUMBER
17488	C	122400

SCALE 1:1 WEIGHT SHEET

REVISIONS				
QTY	ZONE	DESCRIPTION	DATE	APPROVED
A		ECN 30982	10/5/67	



NOTES:
1. USE MIN. BEND RADIUS FOR MATERIAL SPEC.

PART NO. 122401-1

QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

DRAWN BY	DATE 7/14/67	SIZE	CODE
CHECKED BY			
MACH ENG			
QUAL ENG			
RELIABILITY			
DESIGN APPR			
APPROVED			

Conductron Corporation — ANN ARBOR MICHIGAN

TITLE: BRACKET

CODE IDENT NO.	SIZE	DRAWING NUMBER
17455	D	122401

SCALE 1:1 — WEIGHT — SHEET

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS-.015 TO .030
TOLERANCES ON
DECIMALS: XX ±.01 | DECIMALS: XXX ± | ANGLES: ± 1°

MATERIAL AL-ALLOY 6061-T6 .063 THK.

FINISH

AREA IDENTIFICATION	
A	
B	
C	
D	
E	
F	

CHART NO.	NEXT ASSY	USED ON
APPLICATION		



REVISIONS

SYM	ZONE	DESCRIPTION	DATE	APPROVED
A		24.39 and 24.33	11/64	
B		.68 R. ADDED .50 TYP. ADDED	11/64	
C		.546 ± .005 R. ADDED .515 THK	1/65	
D		.515 and .50	1/65	
E		118 BOLTS NO. 8-32 UNC. 24.33 and 24.39 .44 DIA. ADDED CAIN SHOE ADDED	11/64	
F		ALL .005 TOL	2/65	

LIST OF MATERIALS

ITEM NO.	QTY REQD 104	QTY REQD 103	QTY REQD 102	QTY REQD 101	DASH	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

SYM	IDENTIFICATION
01	ASSY DRAWING
02	DETAILS
03	INSTALLATION AND ASSEMBLY DRG
04	INSTALLATION DRG
05	REFERENCE DRAWINGS
06	SPECIFICATIONS

NEXT ASSY	USED ON
APPLICATION	

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND BREAK SHARP EDGES
RADII AND FILLETS - .005 TO .010
TOLERANCES ON

DECIMALS	DECIMALS	ANGLES
.XX ±	.XXX ±	±

MATERIAL 356-T51 ALUM
FINISH

DRAWN BY [illegible] DATE 11/64
TRACED
CHECKED BY
ENGR GRP
ILLEG GRP
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE SEGMENT RING SECTION (CASTING)

CODE IDENT NO.	SIZE	DRAWING NUMBER
17488	D	122402

SCALE AS SHOWN | WEIGHT | SHEET

NOTICE: THIS DOCUMENT CONTAINS INFORMATION OF OTHER DATA WHICH ARE THE PROPERTY OF CONDUCTRON CORP. IT SHOULD NOT BE COPIED OR REPRODUCED WITHOUT CONSENT, NOR USED FOR MANUFACTURING PURPOSES, NOR THAT THEY THE DOCUMENT(S) MAY NOT BE LOANED, PURCHASED, OR OF ANY KIND DISCLOSED TO OTHERS FOR ANY PURPOSE, AS IN ANY MANNER WHATSOEVER THE RELEASE OF ANY OTHER INFORMATION NOT DIRECTLY OR INDIRECTLY RELATED THERETO.

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



PART No. 122403-1

QTY REQD DASH 104	QTY REQD DASH 103	QTY REQD DASH 102	QTY REQD DASH 101	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

SYM IDENTIFICATION
A ASSEMBLY DRAWINGS
B BULK ITEMS
C SPECIFICATIONS (CONDUCTRON)
D DETAIL ITEMS (FAB)
R REFERENCE DRAWINGS
V VENDOR ITEMS

DASH NO.	NEXT ASSY	USED ON

APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS-.005 TO .010
TOLERANCES ON

DECIMALS	DECIMALS	ANGLES
.XX ±.010	.XXX ±.005	± —

MATERIAL 6061-T6 AL. ALLOY
FINISH

DRAWN BY Walter Field
DATE DRAWN 11/1/60 | DATE CHK'D | CLASS
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE SHIM

CODE IDENT NO.	SIZE	DRAWING NUMBER
17488	C	122403

SCALE 1:1 | WEIGHT | SHEET

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED





PART No. 122404-1

QTY REQD DASH 104	QTY REQD DASH 103	QTY REQD DASH 102	QTY REQD DASH 101	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

SYM IDENTIFICATION
A ASSEMBLY DRAWINGS
B BULK ITEMS
C SPECIFICATIONS (CONDUCTRON)
D DETAIL ITEMS (PAIR)
R REFERENCE DRAWINGS
V VENDOR ITEMS

DASH NO.	NEXT ASSY	USED ON

APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS-.005 TO .010
TOLERANCES ON

DECIMALS .XX ±.010	DECIMALS .XXX ± —	ANGLES ± —

MATERIAL 6061-T6 AL. ALLOY.
FINISH

DRAWN BY [signature]
DATE DRAWN 10/15/57 | DATE CHK'D | CLASS
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE ANGLE-SPLICE

CODE IDENT NO.	SIZE	DRAWING NUMBER
17468	C	122404

SCALE 1-2 | WEIGHT | SHEET

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



PART No 122405-1

QTY REQD DASH 100	QTY REQD DASH 103	QTY REQD DASH 105	QTY REQD DASH 101	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

SYM IDENTIFICATION
A ASSEMBLY DRAWINGS
B BULK ITEMS
C SPECIFICATIONS (CONDUCTRON)
D DETAIL ITEMS (FAB)
R REFERENCE DRAWINGS
V VENDOR ITEMS

DASH NO.	NEXT ASSY	USED ON

APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS - .005 TO .010
TOLERANCES ON

DECIMALS	DECIMALS	ANGLES
.XX ±.010	.XXX ±	±

MATERIAL 6061-T6 ALALLOY - 0.125 THK
FINISH

DRAWN BY [signature]
DATE DRAWN 1/20/65 | DATE CHK'D | CLASS
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation — ANN ARBOR MICHIGAN

TITLE
RETAINING RING SEGMENT.

CODE IDENT NO.	SIZE	DRAWING NUMBER
17488	C	122405

SCALE 0.1=1° | WEIGHT | SHEET

NOTICE—WHEN GOVERNMENT DRAWINGS, SPECIFICATIONS, OR OTHER DATA ARE USED FOR ANY PURPOSE OTHER THAN IN CONNECTION WITH A DEFINITELY RELATED GOVERNMENT PROCUREMENT OPERATION, THE UNITED STATES GOVERNMENT THEREBY INCURS NO RESPONSIBILITY NOR ANY OBLIGATION WHATSOEVER; AND THE FACT THAT THE GOVERNMENT MAY HAVE FORMULATED, FURNISHED, OR IN ANY WAY SUPPLIED THE SAID DRAWINGS, SPECIFICATIONS, OR OTHER DATA IS NOT TO BE REGARDED BY IMPLICATION OR OTHERWISE AS IN ANY MANNER LICENSING THE HOLDER OR ANY OTHER PERSON OR CORPORATION OR CONVEYING ANY RIGHTS OR PERMISSION TO MANUFACTURE, USE, OR SELL ANY PATENTED INVENTION THAT MAY IN ANY WAY BE RELATED THERETO

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



PART No. 122406-1

QTY REQD DASH 104	QTY REQD DASH 103	QTY REQD DASH 102	QTY REQD DASH 101	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

SYM	IDENTIFICATION
A	ASSEMBLY DRAWINGS
B	BULK ITEMS
C	SPECIFICATIONS (CONSTRUCTION)
D	DETAIL ITEMS (FAB)
R	REFERENCE DRAWINGS
V	VENDOR ITEMS

DASH NO.	NEXT ASSY	USED ON

APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS-.005 TO .010
TOLERANCES ON

DECIMALS	DECIMALS	ANGLES
.XX ± .010	.XXX ± X	± X

MATERIAL 6061-T6 AL. ALLOY, 0.125 THK
FINISH

DRAWN BY [signature]
DATE DRAWN 1/16/65
DATE CHK'D
CLASS
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation
ANN ARBOR MICHIGAN

TITLE
RETAINING RING
MYLAR

CODE IDENT NO.	SIZE	DRAWING NUMBER
17488	C	122406

SCALE 0.1=1 | WEIGHT | SHEET

REVISIONS				
QTY	ZONE	DESCRIPTION	DATE	APPROVED





NOTES

△1 TRUSS ASSEMBLIES TO BE MADE IN SETS. ONE SET CONSISTS OF 2 122407-1 AND 2 122407-2. TOLERANCE ON ALL DIMENSIONS IS ±.13. DIMENSIONS LABLED WITH NOTE ARE TO BE THE SAME WITHIN ±.030 IN ANY ONE SET.

2. ALL JOINTS TO BE 100% WELDED TO AEST COMMERCIAL STANDARDS.

PART No.	
122407-2	98.05
122407-1	94.06

PART No. SEE TABLE 1 NOTE 1

QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

QTY.	NEXT ASSY	USED ON
APPLICATION		

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS .005 TO .010
TOLERANCES ON
DECIMALS XX ± .01 XXX ± .005
ANGLES ±
MATERIAL NOTED
FINISH

DRAWN BY
DATE 7/61
CHECKED BY
MFGR. ENG.
ELEC. ENG.
RELIABILITY
DESIGN APPR.
APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE TRUSS ASSEMBLY: WELDED

STOCK SHEET NO.	SIZE	DRAWING NUMBER
17488	D	122407

SCALE 1:1" WEIGHT SHEET



NOTE
1. ALL BEND RADII .060"
2. DIMENSIONS ARE TO OUTSIDE OF .80X UNLESS SHOWN.
3. WELDS TO BE BEST COMMERCIAL STANDARDS.

REVISIONS			
SYM	ZONE	DESCRIPTION	DATE / APPROVED
A		ADD REF.	2-5-64
B		ADD 3 .81 DIA.	9-24-64

QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	ZONE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION
			12	5		AN 175H	V	RIVET-FLAT HD	MS 214 X 5016 CRES
			5	4	D	122408-4	D	SUPPORT	
			5	3	D	122408-3	D	STIFFENER	
			2	2	D	122408-2	D	STIFFENER	
			1	1	D	122408-1	D	HOUSING	

LIST OF MATERIALS

NEXT ASSY	USED ON
APPLICATION	

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS .005 TO .010
TOLERANCES ON
DECIMALS .XX ± .010 .XXX ± .005 ANGLES ± --

MATERIAL

FINISH

DRAWN BY
DATE
CHECKED BY
DESIGN APPR
APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE
SUPPORT ASSY
ANTENNA

CURR ASSY NO. 17466 | SIZE D | DRAWING NUMBER 122408

SCALE 1:1 | WEIGHT | SHEET 1 OF 2

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED
A		PER 122409 REV. ADDED SUPPORT & STANDOFF	10-29	



QTY REQD 1ST	QTY REQD 2ND	QTY REQD 3RD	QTY REQD 4TH	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION
								LIST OF MATERIALS	

ECR IDENTIFICATION	SERIAL NO.	NEXT ASSY	USED ON
A1 ADDITIONS			
A2 DELETIONS			
A3 SPECIFICATIONS REVISED/NEW		APPLICATION	
A4 RETAIL ITEMS ONLY			
A5 ENGINEERING CHANGES			
A6 MANUFACTURING CHANGES			

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS .005 TO .010
TOLERANCES ON

DECIMALS XX ± .0	DECIMALS XXX ±	ANGLES ±

MATERIAL
AS NOTED
FINISH

DRAWN BY [illegible]
DATE 7-11 | CLASS
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation
ANN ARBOR MICHIGAN

TITLE
SUPPORT ASSY
ANTENNA

CODE IDENT NO 17488 | SIZE D | DRAWING NUMBER 122408
SCALE 1/2 | WEIGHT | SHEET 2



Conductron Corporation		ANN ARBOR MICHIGAN
TITLE: HANDLE - CRANK		
CODE IDENT NO. 17468	SIZE B	DRAWING NUMBER 122409
SCALE	WEIGHT	SHEET

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



NOTES:
1. MATCHDRILL WITH D/122417-1

PART NO. 122416-1

QTY PCSD	QTY PCSD	QTY PCSD	QTY PCSD	ITEM NO.	CODE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

SYM	IDENTIFICATION
1	
2	
3	
4	
5	
6	
7	
8	
9	
10	

ITEM NO.	NEXT ASSY	USED ON

APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS - .005 TO .015
TOLERANCES ON

DECIMALS XX ±.01	DECIMALS .XXX ±.005	ANGLES ±

MATERIAL ALUM. 6061-T6 OR EQUAL
FINISH

DRAWN BY J. R. Williams — DATE 4-6-65 — CHK'D
CHECKED BY
DESIGN ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation — ANN ARBOR MICHIGAN

TITLE: FRAME, OUTER

CODE IDENT NO. 17488 — SIZE D — DRAWING NUMBER 122416

SCALE 1:2 — WEIGHT — SHEET

REVISIONS				
QTY	ZONE	DESCRIPTION	DATE	APPROVED



NOTES
1. MATCH DRILL USING D122416-1 AS TEMPLATE.

PART NO. 122417-1

QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	STK	NOMENCLATURE OR DESCRIPTION	SPECIFICATION
SHEET NO.	SHEET NO.	SHEET NO.	SHEET NO.						

LIST OF MATERIALS

STK IDENTIFICATION	QTY REQD	NEXT ASSY	USED ON
		APPLICATION	

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
BROKEN EDGES ARE SHARP EDGES
RADII AND FILLETS - .005 TO .010
TOLERANCES ON
DECIMALS XX ± .01 | DECIMALS .XXX ± .005 | ANGLES ±

MATERIAL 10-1008 ROLL-TIN .118 THICK
FINISH

DRAWN BY BJ McCall DATE 8-14-7 | DATE CHK'D | CLASS
CHECKED BY
MFGR ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE
FRAME, INNER

CODE IDENT NO. 17488 | SIZE D | DRAWING NUMBER 122417
SCALE 1/2 | WEIGHT | SHEET

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



PART NO. 122428-1

QTY REQD DASH 104	QTY REQD DASH 103	QTY REQD DASH 102	QTY REQD DASH 101	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

SYM IDENTIFICATION
A ASSEMBLY DRAWINGS
B BULK ITEMS
C SPECIFICATIONS (CONDUCTRON)
D DETAIL ITEMS (PAR)
R REFERENCE DRAWINGS
V VENDOR ITEMS

DASH NO.	NEXT ASSY	USED ON

APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS-.005 TO .010
TOLERANCES ON

DECIMALS	DECIMALS	ANGLES
XX ±.01	.XXX ±.005	±

MATERIAL .25 X 2 X 2 EXT. ALUM. ANGLE 6063-T5

FINISH

DRAWN BY D. J. McCallum
DATE DRAWN 7/25/65 | DATE CHK'D | CLASS
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE SLIDE, SUPPORT

CODE IDENT NO.	SIZE	DRAWING NUMBER
17468	C	122428

SCALE 1:2 | WEIGHT | SHEET

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



PART No. 122430-1

QTY REQD DASH 104	QTY REQD DASH 105	QTY REQD DASH 106	QTY REQD DASH 101	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

SYM IDENTIFICATION
A ASSEMBLY DRAWINGS
B BULK ITEMS
C SPECIFICATIONS CONDUCTRON
D DETAIL ITEMS (PAR)
R REFERENCE DRAWINGS
V VENDOR ITEMS

DASH NO.	NEXT ASSY	USED ON

APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS - .005 TO .010
TOLERANCES ON

DECIMALS	DECIMALS	ANGLES
.XX ± .03	.XXX ± —	± —

MATERIAL 6061-T6 AL. ALLOY.
FINISH

DRAWN BY Dick Tuttle
DATE DRAWN 4/22/65
DATE CHK'D
CLASS
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE PLATE - MOUNTING

CODE IDENT NO.	SIZE	DRAWING NUMBER
17468	C	122430

SCALE 1/1 WEIGHT SHEET



Conductron Corporation		ANN ARBOR MICHIGAN
TITLE: CLAMP. CHANNEL		
CODE IDENT NO. 17468	SIZE B	DRAWING NUMBER 122431
SCALE 1:1	WEIGHT	SHEET

NOTICE — WHEN GOVERNMENT DRAWINGS, SPECIFICATIONS, OR OTHER DATA ARE USED FOR ANY PURPOSE OTHER THAN IN CONNECTION WITH A DEFINITELY RELATED GOVERNMENT PROCUREMENT OPERATION, THE UNITED STATES GOVERNMENT THEREBY INCURS NO RESPONSIBILITY NOR ANY OBLIGATION WHATSOEVER; AND THE FACT THAT THE GOVERNMENT MAY HAVE FORMULATED, FURNISHED, OR IN ANY WAY SUPPLIED THE SAID DRAWINGS, SPECIFICATIONS OR OTHER DATA IS NOT TO BE REGARDED BY IMPLICATION OR OTHERWISE AS IN ANY MANNER LICENSING THE HOLDER OR ANY OTHER PERSON OR CORPORATION OR CONVEYING ANY RIGHTS OR PERMISSION TO MANUFACTURE, USE, OR SELL ANY PATENTED INVENTION THAT MAY IN ANY WAY BE RELATED THERETO

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



QTY REQD DASH 104	QTY REQD DASH 103	QTY REQD DASH 102	QTY REQD DASH 101	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION
			4	6		MS16995-18	V	SCREW, SOC HD CAP	#6-32 X .50 CRES
			4	5		MS35338-79	V	WASHER, LOCK	#6 CRES
			4	4		MS122118	V	INSERT, HELI-COIL	#6
			1	3	C	122456-3	D	RETAINER	
			1	2	C	122456-2	D	RETAINER	
			1	1	C	122456-1	D	PLATE, MOUNTING	

LIST OF MATERIALS

SYM IDENTIFICATION
A ASSEMBLY DRAWINGS
B BULK ITEMS
C SPECIFICATIONS (CONSTRUCTION)
D DETAIL ITEMS (FAB)
R REFERENCE DRAWINGS
V VENDOR ITEMS

DASH NO.	NEXT ASSY	USED ON

APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS-.008 TO .010
TOLERANCES ON

DECIMALS .XX ±	DECIMALS .XXX ±	ANGLES ±

MATERIAL NOTED

FINISH

DRAWN BY D. J. McCallum
DATE DRAWN 2/8/65 | DATE CHK'D | CLASS
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY

DESIGN APPR

APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE MOUNTING PLATE ASSY

CODE IDENT NO.	SIZE	DRAWING NUMBER
17468	C	122456

SCALE	WEIGHT	SHEET

REVISIONS				
DASH	ZONE	DESCRIPTION	DATE	APPROVED
A		PER ECN 4	4/24/65	



NOTES:
1. INSERT SHIM .015 THK. UNDER ITEM 3, 3 PLACES. TIGHTEN ITEM 19 AND REMOVE SHIMS.

QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION
AR	AR	AR	AR	23			V	CORK	1/8 X 1
				22	C	122436-101	D	MOUNTING PLATE ASSY	
				21		MS24996-18	V	SCREW, SOC HD CAP	10-32 X 1 CRES
				20		AN315A10-10R	V	NUT, HEX	10-32 CRES
				19		MS35338-81	V	WASHER, LOCK, SPLIT	#10 CRES
				18		MS16995-52	V	SCREW, SOC HD CAP	1/4-20 X 1
				17		MS35691-610	V	NUT, HEX	1/4-20 CRES
				16		MS16997-24	V	SCREW, SOC HD CAP	3/8-32 X 1 CAD PLTD
				15		MS35649-68	V	NUT, HEX	3/8-32 CRES
				14		MS35338-79	V	WASHER, LOCK, SPLIT	#6 CRES
				13		MS15795-810	V	WASHER, FLAT CRES	.065 X .281 I.D. X .625 A.D.
				12		MS15795-813	V	WASHER, FLAT CRES	.095 X .531 I.D. X 1.188 O.D.
				11		MS16562-168	V	PIN, TUBULAR, SPLIT	.062 DIA. X .75 LG.
				10		MS35649-15	V	GROMMET	
4				9			V	WASHER, FLAT, .101 NYLON	.688 X .437 D.A. X .750 O.D.
2				8		UG-492A/U	V	CONNECTOR	BNC-BHC-ASSM1-SR
				7				2" BAND FEED FOR 6" DIAM	
				6				1" BAND FEED FOR 6" DIAM	
				5					
				4	A	122398-1	D	NUT	
				3	A	122399-1	D	NUT, RETAINING	
				2	A	122403-1	D	HANDLE, CRANK	
				1	C	122400-1	D	CRANK	
				3	C	122428-1	D	SLIDE, SUPPORT	
				2	D	122401-1	D	BRACKET	
				1	D	122402-101	A	SUPPORT ASSY	

LIST OF MATERIALS

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE PLATING. REMOVE BURRS AND SHARP EDGES. RADII AND FILLETS .005 TO .015. TOLERANCES ON: DECIMALS XX ±, DECIMALS XXX ±.005, ANGLES ±

DRAWN BY J.J. Nicholson — DATE 7/15/65 — CLASS

CHECKED BY

MECH ENG

ELEC ENG

RELIABILITY

DESIGN APPR

APPROVED

MATERIAL

FINISH

APPLICATION — NEXT ASSY — USED ON

Conductron Corporation — ANN ARBOR MICHIGAN

TITLE: ANTENNA ASSY

CODE IDENT NO. 17468 — SIZE D — DRAWING NUMBER 122457

SCALE 1:1 — WEIGHT — SHEET

REVISIONS				
SYM	ZONE	DESCRIPTION	DATE	APPROVED



POSITIONER	1625 LBS	
SEGMENT (CANTILEVER) RING	350 LBS @ ≈ 4' =	1400 FT-#
ATTACHMENT PLATE	208 LBS @ ≈ 1' =	208 FT-#
FOOT PLATES	67 LBS @ ≈ 9' =	603 FT-#
ATTACHMENT STRUTS	98 LBS @ ≈ 3' =	294 FT-#
SEGMENT STRUTS	100 LBS @ ≈ 8' =	800 FT-#
	2448 LBS.	3305 FT-#
HARDWARE	55 LBS @ ≈ 3' =	165 FT-#
	2493 LBS.	3470 FT-#

QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	ZONE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION
NEXT ASSY	NEXT ASSY	NEXT ASSY	NEXT ASSY						

LIST OF MATERIALS

SYM	IDENTIFICATION
A	ASSEMBLY DRAWINGS
B	BOAT TYPES
C	SPECIFICATIONS AND DESCRIPTIONS
D	DETAIL PARTS LIST
E	INSTALLATION DRAWINGS
F	VENDOR ITEMS

ITEM NO.	NEXT ASSY	USED ON
APPLICATION		

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS - .005 TO .010
TOLERANCES ON

DECIMALS	FRACTIONALS	ANGLES
XX ±	XXX ±	±

MATERIAL

FINISH

DRAWN BY	A.J. McCall
DATE	11/4/64
CHECKED BY	
ENGR GRP	
ELEC GRP	
RELIABILITY	
DESIGN APPR	
APPROVED	

Conductron Corporation — ANN ARBOR MICHIGAN

TITLE: MEASUREMENT FIXTURE CONCEPT

CODE IDENT NO.	SIZE	DRAWING NUMBER
17488	D	124204

SCALE 1"=1' | WEIGHT | SHEET



REVISIONS			
SYM	ZONE	DESCRIPTION	DATE	APPROVED

QTY REQD NEXT ASSY	QTY REQD NEXT ASSY	QTY REQD NEXT ASSY	QTY REQD NEXT ASSY	ITEM NO.	SIZE	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION

LIST OF MATERIALS

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES
AND INCLUDE PLATING
SHARP EDGES ARE BREAK EDGES
RADII AND FILLETS-.005 TO .010
TOLERANCES ON
DECIMALS XX ± | DECIMALS XXX ± | ANGLES ±

MATERIAL

FINISH

DRAWN BY A. S. McCall DATE 4/11/62
TRACED DATE
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation ANN ARBOR MICHIGAN

TITLE PRESSURE SEAL ASSY

CODE IDENT NO. 17468 | SIZE D | DRAWING NUMBER 124205

SCALE 1/1 | WEIGHT | SHEET

SHEET NO.	NEXT ASSY	USED ON
	APPLICATION	

REVISIONS				
QTY	ZONE	DESCRIPTION	DATE	APPROVED





ANTENNA MOUNTING PLATE — 1 REQD





CLAMP — 4 REQD

ITEM NO.	PART OR IDENTIFYING NO.	SYM	NOMENCLATURE OR DESCRIPTION	SPECIFICATION	QTY REQD SHORT VAT	QTY REQD SHORT HILL	QTY REQD SHORT VAN	QTY REQD SHORT DEL
10			WELD ITEM 6 TO ITEM 9 SPACER ITEM 9 TO ITEM 8		—			
9			ANTENNA MOUNT 3/8 x 4 x 9		—			
8			1 1/4 x 3 CLAMP AL ALY 6061-T6		1			
7			3/8 WASH. WITH CA. MC WITH		1 EA			
6			PLY 2 1/2 PULLEY		2 EA			
5			3/8 THK AL (WINCH MOUNT)		—			
4			5/8 ø SOLID ROUND AL TUBING 6061-T6		24'			
3			1/4 x 1 1/2 x 1 1/2 AL ANGLE 6061-T6		9'			
2			1/8 x 3 x 6 AL TEE 6061-T6		30'			
1			1/8 x 6 AL CHANNEL 6061-T6		30'			
REF			MATERIAL		AMT			

LIST OF MATERIALS

SYM	IDENTIFICATION
A	DIRECTION OF VIEW
B	QUALITY
C	SPECIFICATIONS (CONSUMPTION)
D	DETAIL ITEMS SPLIT
E	SUPERSEDE DRAWINGS
F	REVISION SYSTEM

DWG NO.	NEXT ASSY	USED ON
APPLICATION		

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND INCLUDE PLATING
REMOVE BURRS AND SHARP EDGES
RADII AND FILLETS - .005 TO .015
TOLERANCES ON

DECIMALS	ORDINALS	ANGLES
XX ±	XXX ±	±

MATERIAL
FINISH

DRAWN BY
DATE 11/1/68 | MFR. CHK'S
CHECKED BY
MECH ENG
ELEC ENG
RELIABILITY
DESIGN APPR
APPROVED

Conductron Corporation — ANN ARBOR MICHIGAN

TITLE ANTENNA TOWER ASSY

CODE IDENT NO.	SIZE	DRAWING NUMBER
17488	D	124208

SCALE Mint | WEIGHT | SHEET