

THE **BOEING** COMPANYAIRPLANE DIVISION
P.O. BOX 707
RENTON, WASHINGTON 98055

CODE IDENT. NO. 81205

NUMBER D6-15000

NASA CR-62036

TITLE: Large Transport Landing Characteristics as
Simulated in Flight and on the GroundFOR LIMITATIONS IMPOSED ON THE USE OF THE INFORMATION
CONTAINED IN THIS DOCUMENT AND ON THE DISTRIBUTION
OF THIS DOCUMENT, SEE LIMITATIONS SHEET.MODEL 367-80 CONTRACT NAS2-3224ISSUE NO. 26 ISSUED TO: Nasa Ames

PREPARED BY	<u>J. W. Kerrigan</u>	<u>2/4/66</u>
	J. W. Kerrigan	
PREPARED BY	<u>R. G. Root</u>	<u>2/4/66</u>
	R. G. Root	
SUPERVISED BY	<u>L. G. Kimbrel</u>	
	L. G. Kimbrel	
APPROVED BY	<u>H. C. Higgins</u>	
	H. C. Higgins	
APPROVED BY		(DATE)

ACTIVE SHEET RECORD

SHEET NUMBER	REV LTR	ADDED SHEETS				SHEET NUMBER	REV LTR	ADDED SHEETS			
		SHEET NUMBER	REV LTR	SHEET NUMBER	REV LTR			SHEET NUMBER	REV LTR	SHEET NUMBER	REV LTR
Title Page						VI-43					
1						VI-44					
11						VI-45					
111						VI-46					
1v						VI-47					
2						VI-48					
3						VI-49					
I-4						VI-50					
II-5						VI-51					
III-6						VI-52					
III-7						VI-53					
III-8						VI-54					
III-9						VI-55					
IV-10						VI-56					
IV-11						VI-57					
IV-12						VII-58					
IV-13						VII-59					
IV-14						VII-60					
V-15						VII-61					
V-16						VII-62					
VI-17						VII-63					
VI-18						VII-64					
VI-19						VII-65					
VI-20						VII-66					
VI-21						VII-67					
VI-22						VII-68					
VI-23						VII-69					
VI-24						VII-70					
VI-25						VII-71					
VI-26						VII-72					
VI-27						VII-73					
VI-28						VII-74					
VI-29						VII-75					
VI-30						VII-76					
VI-31						VII-77					
VI-32						VII-78					
VI-33						VII-79					
VI-34						VII-80					
VI-35						VII-81					
VI-36						VII-82					
VI-37						VII-83					
VI-38						VII-84					
VI-39						VII-85					
VI-40						VII-86					
VI-41						VII-87					
VI-42						VII-88					

ACTIVE SHEET RECORD

SHEET NUMBER	REV LTR	ADDED SHEETS				SHEET NUMBER	REV LTR	ADDED SHEETS			
		SHEET NUMBER	REV LTR	SHEET NUMBER	REV LTR			SHEET NUMBER	REV LTR	SHEET NUMBER	REV LTR
VII-89						IX-135					
VII-90						X-136					
VII-91						X-137					
VII-92						X-138					
VII-93						X-139					
VII-94						X-140					
VII-95						X-141					
VII-96						X-142					
VII-97						X-143					
VII-98						X-144					
VII-99						X-145					
VII-100						X-146					
VII-101						X-147					
VIII-102						A1-1					
VIII-103						A1-2					
VIII-104						A1-3					
VIII-105						A1-4					
VIII-106						A1-5					
VIII-107						A1-6					
VIII-108						A1-7					
VIII-109						A1-8					
VIII-110						A1-9					
VIII-111						A1-10					
VIII-112		VIII-112A				A1-11					
VIII-113						A1-12					
VIII-114						A1-13					
VIII-115						A1-14					
VIII-116						A1-15					
VIII-117						A1-16					
VIII-118						A1-17					
VIII-119						A1-18					
VIII-120						A1-19					
VIII-121						A1-20					
VIII-122						A1-21					
IX-123						A1-22					
IX-124						A1-23					
IX-125						A2-1					
IX-126						A2-2					
IX-127						A2-3					
IX-128						A2-4					
IX-129						A2-5					
IX-130						A2-6					
IX-131						A2-7					
IX-132						A2-8					
IX-133						A2-9					
IX-134						A2-10					

ACTIVE SHEET RECORD

SHEET NUMBER	REV LTR	ADDED SHEETS				SHEET NUMBER	REV LTR	ADDED SHEETS			
		SHEET NUMBER	REV LTR	SHEET NUMBER	REV LTR			SHEET NUMBER	REV LTR	SHEET NUMBER	REV LTR
A3-1											
A3-2											
A4-1											
A4-2											
A4-3											
A4-4											
A4-5											
A4-6											
A4-7											
A4-8											
A4-9											
A4-10											
A4-11											
A4-12											
A5-1											
A5-2											
A5-3											
A5-4											
A5-5											
A5-6											
A5-5											
A5-6											
A6-1											
A6-2											
A6-3											

R E V I S I O N S			
REV SYM	DESCRIPTION	DATE	APPROVAL

BOEING

PAGE **iv**

✈
6-7000

Table of Contents

	<u>Page</u>
I. Summary	
II. References	
III. List of Illustrations	
IV. List of Symbols	
V. Introduction	
VI. Documentation of Basic Configuration	
A. Airborne Simulation	
B. Ground Based Simulation	
VII. Longitudinal Configuration Characteristics	
A. Airborne Simulation	
B. Ground Based Simulation	
VIII. Lateral Configuration Characteristics	
A. Airborne Simulation	
B. Ground Based Simulation	
IX. Documentation of the 367-80 with Boundary Layer Control	
X. Inflight - Ground-Based Simulator Comparison	
 APPENDIX	
1. Description of the Ames Large Transport Configurations	
A. Airborne Simulator	
B. Ground Based Simulation	
2. Basic 367-80 Description	
3. Control Force Characteristics	

Table of Contents (cont'd)

4. Derivation of Theory
5. Ground Based Analog Simulation Description
6. Description of Documentation Maneuvers

I. SUMMARY

32624

The stability and control characteristics during low speed landing approaches of various Ames large transport configurations were evaluated using the Boeing 367-80 airplane and the Ames moving base analog simulator. This report documents comparisons of the 367-80 and the moving base simulators to the theoretically calculated characteristic responses of the large transport configurations. For all maneuvers performed the simulation accuracy was satisfactory.

AUT NOR

II References

1. D6-19860. 367-80 Airplane Variable Stability Simulation System
(NASA Ames Large Transport Simulation Program). (NASA CR-62037)
2. Etkin, Bernard; Dynamics of Flight. John Wiley & Sons, Inc., 1962.

III. LIST OF ILLUSTRATIONS

Fig. No.	Description	Page
1	367-80 Schematic	V-16
2-10	Documentation of the basic longitudinal inflight configuration	VI-18 to 27
11-22	Documentation of the basic lateral inflight configuration	VI-29 to 41
23-36	Documentation of the typical ground based configurations	VI-43 to 57
37	Summary of normalized pitch rate reversals for inflight configurations	VII-62
38-39	Column steps for inflight configurations	VII-63 to 64
40-55	Wind up turns for inflight configurations	VII-65 to 80
56-63	Speed stability tests for inflight configurations	VII-81 to 88
64	Pitch attitude change for an inflight configuration	VII-89
65-67	Elevator pulses for inflight configurations	VII-90 to 92
68-69	Column steps for ground based configurations	VII-97 to 98
70-72	Elevator pulses for ground based configurations	VII-99 to 101
73	Summary plot of steady roll rates for inflight configurations	VIII-104
74-77	Roll rate reversals for inflight configurations	VIII-106 to 109
78	A 20° heading change for an inflight configuration	VIII-110
79-81	Roll response to wheel steps for varying ground based augmentation systems	VIII-115 to 117

Fig. No.	Description	Page
32	Effect of τ_R on roll response to a wheel step for ground based configurations	VIII-118
33	Effect of τ_R on roll response to an aileron step for ground based configurations	VIII-119
34-36	Wheel step for ground based configurations	VIII-120 to 122
37-96	Documentation of the 367-80 with boundary layer control	IX-124 to 135
97	Wheel step comparing inflight and ground based configurations	X-138
98	Wheel pulse comparing inflight and ground based configurations	X-139
99	Rudder pulse comparing inflight and ground based configurations	X-140
100	Elevator pulse comparing inflight and ground based configurations	X-141
101	Column step comparing inflight and ground based configurations	X-142
102	Flight Data Comparison for Column Step	X-143
103	Ground Data Comparison for Column Step	X-144
104	Ground-Flight Comparison for Column Step	X-145
105	Ground-Flight Comparison for Column Step	X-146
106	Ground-Flight Comparison for Column Step	X-147
A2-1 to A2-4	Characteristics of 367-80 speed brakes	A2-6
A2-5	Pitching moment characteristics of the 367-80 thrust reversers	to A2-9 A2-10
A3-1	Control system force characteristics for the airborne and ground based simulators	A3-2

Table No.	Description	Page
1	Airborne simulation longitudinal run log	VII-59
2	Phugoid characteristics for inflight configurations	VII-61
3	Ground based simulation longitudinal run log	VII-94 to 96
4	Airborne simulation lateral run log	VIII-103
5	Wheel step results for inflight configurations	VIII-105
6	Ground based simulation lateral run log	VIII-112 to 114
A1-1	Aerodynamic characteristics for the basic inflight configurations	A1-2 to 5
A1-2	Variations of aerodynamic characteristics for simulated configurations	A1-6
A1-3	367-80 BLC aerodynamic characteristics	A1-8 to 12
A1-4	Ground based configuration description	A1-4
A1-5	Ground based simulation longitudinal run log	A1-15 to 17

Table No.	Description	Page
A1-6	Ground based simulation lateral run log	A1-18 to 21
A1-7	Lateral directional stability augmentation system	A1-22
A1-8	Equivalent lateral-directional aerodynamic coefficients	A1-23
A2-1	367-80 longitudinal characteristics (unaugmented)	A2-2 to 5
A5-1	Ground based simulation equations of motion	A5-2 to 4
A5-2	Ground based simulation system capabilities	A5-6

12

IV. SYMBOLS

Coefficients and Derivatives

C_D	Drag Coefficient, Drag/ qS_w
C_L	Lift Coefficient, Lift/ qS_w
C_l	Rolling Moment Coefficient, Rolling Moment/ $qS_w b$
C_m	Pitching Moment Coefficient, Pitching Moment/ $qS_w \bar{c}$
C_n	Yawing Moment Coefficient, Yawing Moment/ $qS_w b$
C_y	Side Force Coefficient, Side Force/ qS_w
$C_{D\alpha} = 0$	Drag Coefficient at $\alpha = 0$
$C_{D\alpha}$	Drag-Curve Slope, $\partial C_D / \partial \alpha$
$C_{L\alpha} = 0$	Lift Coefficient at $\alpha = 0$
$C_{L\alpha}$	Lift-Curve Slope, $\partial C_L / \partial \alpha$
$C_{L\dot{\alpha}}$	Lift Coefficient Due to Angle-of-Attack Rate $\partial C_L / \partial \dot{\alpha}$
$C_{L\delta}$	Lift Coefficient Due to Surface Deflection $\partial C_L / \partial \delta$
$C_{L_{i_H}}$	Lift Coefficient Due to Horizontal Stabilizer Incidence $\partial C_L / \partial i_H$
$C_{L_q}, C_{L\dot{\theta}}$	Lift Coefficient Due to Pitch Rate, $\partial C_L / \partial q$
$C_{l\beta}$	Effective Dihedral Derivative, $\partial C_l / \partial \beta$
$C_{l\delta}$	Roll Control Derivative, $\partial C_l / \partial \delta$
$C_{l_p}, C_{l\dot{\phi}}$	Rolling Moment Due to Roll Rate, $\partial C_l / \partial p$
$C_{l_r}, C_{l\dot{\psi}}$	Rolling Moment Due to Yaw Rate, $\partial C_l / \partial r$
$C_{m\alpha} = 0$	Pitching moment Coefficient at $\alpha = 0$
$C_{m\alpha}$	Static Longitudinal Stability Derivative, $\partial C_m / \partial \alpha$
$C_{m\dot{\alpha}}$	Pitching Moment Coefficient Due to Angle-of-Attack Rate, $\partial C_m / \partial \dot{\alpha}$

$C_{m\delta}$	Pitch Control Power Derivative, $\partial C_m / \partial \delta$
$C_{m\dot{1}_H}$	Pitching Moment Due to Horizontal Stabilizer Incidence, $\partial C_m / \partial \dot{1}_H$
$C_{mq}, C_{m\dot{\Theta}}$	Pitching Moment Coefficient Due to Pitch Rate, $\partial C_m / \partial q$
$C_{n\beta}$	Static Directional Stability Derivative, $\partial C_n / \partial \beta$
$C_{n\delta}$	Yawing Moment Coefficient Due to Surface Deflection, $\partial C_n / \partial \delta$
$C_{np}, C_{n\dot{\phi}}$	Yawing Moment Coefficient Due to Roll Rate, $\partial C_n / \partial p$
$C_{nr}, C_{n\dot{\psi}}$	Yawing Moment Coefficient Due to Yaw Rate, $\partial C_n / \partial r$
$C_{Y\beta}$	Side-Force Derivative, $\partial C_Y / \partial \beta$
$C_{Y\delta}$	Side-Force Coefficient Due to Surface Deflection, $\partial C_Y / \partial \delta$
$C_{Yp}, C_{Y\dot{\phi}}$	Side-Force Coefficient Due to Roll Rate, $\partial C_Y / \partial p$
$C_{Yr}, C_{Y\dot{\psi}}$	Side-Force Coefficient Due to Yaw Rate, $\partial C_Y / \partial r$
C_A	BLC Blowing Coefficient
$(\dot{})$	Time derivative $d() / dt$

General

a.c.	Aerodynamic Center
a_y	Side Acceleration Normal to the Flight Path
a_z	Vertical Acceleration Normal to the Flight Path (positive downward)
b	Wing Span
c	Chord
$\bar{c}$	Mean Aerodynamic Chord

F	Control Force
g	Gravitational Constant, 32.2 feet/second ²
GW	Gross Weight
h	Altitude
I	Moment of Inertia Slug-feet ²
IRIG	Clock Time
i _H	Horizontal Stabilizer Incidence Relative to the Wing Chord Plane
L	$\left\{ \begin{array}{l} \text{Rolling Acceleration, } C_{\ell_s} S_{MAX} q S b / I_{xx} \\ \text{Lift Acceleration, } a_z / V, \frac{C_{L\alpha} \alpha q S}{mV}, \frac{C_{L_s} S q S}{mV} \end{array} \right.$
m	Mass
M	Pitching Acceleration $\frac{C_{m_s} S_{MAX} q S \bar{c}}{I_{yy}}$
MAC or m.a.c.	Mean Aerodynamic Chord
M _{CG}	Pitching Moment about CG
n, n _z	Load Factor, g's (body axis)
P	Damped Period
p	Rolling Velocity
q	Dynamic Pressure, Pitching Velocity
r	Yawing Velocity
S	Area
T, TH	Thrust
T _{1/2} , t _{1/2}	Time to Half Amplitude
t _{sa max}	Time to maximum aileron
U	Change in Velocity
V _e	Equivalent Airspeed
V _i	Indicated air speed

V_S	Velocity at Stall
V_T	True Airspeed
W	Weight
α	Angle of Attack of Horizontal Reference Line
α_w	Angle of Attack of the wing mean chord
β	Sideslip Angle
β_{NB}	Sideslip Angle measured at nose boom
δ	Surface Deflection
γ	Flight Path Angle
ζ	Damping Ratio
θ	Angle between the Horizontal Reference Line and the Horizon
τ	Time Constant
ϕ	Roll Angle
ψ	Yaw Angle
$ \phi/\beta $	Roll Angle to Sideslip Ratio
ω_d	Dutch Roll Undamped Natural Frequency
ω_n	Undamped Natural Frequency
ω_D	Damped Natural Frequency

Subscripts


a, A	Aileron
a.c.	Aerodynamic Center
C	Thrust modulator clamshell door
CG	Center of Gravity
Col	Column
d	Dutch Roll
e, E	Elevator
H	Horizontal Stabilizer
MAX	Maximum
N	Net
O	Reference, Free Stream
P	Pedal
r, R	Rudder, Roll mode
s	Spoiler
SB	Speed Brake
S.P.	Short Period
ss	Steady State
trim	Trim Condition
W, WH	Wheel
XX, } YY, } ZZ, } XZ, }	Moment of Inertia Designation

V. INTRODUCTION

Large transport airplanes of the type capable of making shortfield landings at 500,000 lb gross weight were evaluated using the Boeing 367-80 in-flight dynamic simulator in conjunction with the Ames Moving Base Transport Simulator, during late 1965 (7 September to 14 December). Stability and control characteristics in the landing approach were evaluated by NASA/Ames pilots. The ground based simulation was used to investigate a large number of configurations while the in-flight simulation was used to substantiate the results.

The purpose of this report is to describe and document the configurations evaluated on the 367-80 and the ground-based simulators. The accuracy and validity of the simulations are shown in Section VI where response characteristics are presented in detail for basic or typical configurations. Response characteristics of other important configurations are shown in Sections VII, VIII and IX along with a tabulation of dynamic characteristics for all of the configurations evaluated. Section IX presents the response characteristics of the Boeing 367-80 with boundary layer control, one of the configurations evaluated. Section X compares the inflight and ground based simulations of several configurations. The documentation maneuvers performed to measure these characteristics are described in Appendix 6.

The Boeing 367-80 airplane (707 prototype) is shown in Fig. 1. Its description as a five-degree-of-freedom variable stability airplane for in-flight dynamic simulation of a large transport airplane is detailed in Reference 1. A description of the Ames moving base transport simulation system is given in Appendix 5.



WING:

AREA 2821.36FT²
 ASPECT RATIO 6.0
 SWEEP @ .25C 35.0°
 INCIDENCE 2.0°
 DIHEDRAL 7.0°
 MAC 20.05FT.

HORIZONTAL TAIL:

AREA 625FT²
 ASPECT RATIO 3.37
 SWEEP @ .25C 35.0°
 TAPER RATIO .421
 DIHEDRAL 7.0°
 V_H .638

VERTICAL TAIL:

AREA 312 FT²
 ASPECT RATIO 1.46
 SWEEP @ .25C 31.0°
 TAPER RATIO .45
 V_V .0447

CALC			REVISED	DATE	367-80 CHARACTERISTICS	06-150
CHECK						
APR.						FIG. 1
APR.						PAGE V 16
					THE BOEING COMPANY RENTON, WASHINGTON	


VI. Documentation of the Basic Configuration**A. Airborne Simulation**

The characteristics of the basic longitudinal configuration (designated 101A) and the basic lateral configuration (designated 1209) for a large transport aircraft are presented in Figs. 2 to 21. The maneuvers performed to determine the aerodynamic characteristic are listed below along with brief comments on the agreement between flight test data and theory. The theoretical characteristics shown are derived in Appendix 4.

Longitudinal:

Maneuver	Comments
Pitch Rate Reversal	Fig. 2. The 367-80 accurately simulated the basic 101A configuration for a pitch rate reversal. An example of how the data was obtained is shown in Fig. 3.
Column Step	Fig. 4. A time lag is evident in the flight test time history when compared to a theoretically calculated column step. This is probably caused by aerodynamic and control surface lags which are not included in the theory. The column step was usually reversed prematurely before the peak load factor was reached.
Wind Up Turn	Figs. 5 & 6. The wind up turn flight test data agrees quite well with theory when the data are shifted to allow for mis-trim during the flight test.
Speed Stability	Fig. 7. The flight test data shows a slight mis-trim but otherwise agrees quite well with theory for configuration 101A.

PITCH RATE REVERSAL




AIRPLANE	367-80	101A
FLIGHT TEST	686-2	686-2
FLAP	30°	
V _i ~ KTS	117	117
ALTITUDE	4,300 FT	SEA LEVEL
G.W. ~ LBS	162,200	500,000
C.G.	30.2%	25%

IRIG 11:05:XX


CALC			REVISED	DATE	PITCH RATE REVERSAL	367-80
CHECK					FLIGHT TEST 686-2	FIG. 2
APR					CONFIGURATION 101A	
APR					THE BOEING COMPANY	PAGE VI-18
					D6-15000	

PITCH RATE REVERSALS




ENGR.			REVISED	DATE	SAMPLE OF FLIGHT TEST DATA FOR PITCH RATE REVERSALS	D6-15000
CHECK						FIG. 3
APR					THE BOEING COMPANY RENTON, WASHINGTON	VI-19
APR						

COLUMN STEP CONFIG. 101A




CALC		REVISED	DATE	COLUMN STEP	367-80
CHECK				FLIGHT TEST 686-3	
APR				CONFIGURATION 101A	FIG. 4
APR				THE BOEING COMPANY	PAGE
				D6-15000	VI-20

WINDUP TURN



CALC			REVISED	DATE	WINDUP TURN FL. TEST: 686-2 & -3 CONFIG.: 101A THE BOEING COMPANY 06-15000	367-80
CHECK						
APR						FIG. 5
APR						PAGE VI-21

WINDUP TURN




CALC			REVISED	DATE	WINDUP TURN FL. TEST 686-2 & 3 CONFIG. : 101A THE BOEING COMPANY DG-15000	367-80
CHECK						FIG. 6
APR						PAGE
APR						VI-22

SPEED STABILITY


AIRPLANE	367-80	101-A
FL TEST	686-2	686-2
FLAPS	30°	
VE - KTS.	117	117
ALTITUDE	4760 FT.	SEA LEVEL
G.W. - LBS.	159000	159000
C.G.	38.2%	35.9%

IRIG 11:15:11X

*Theoretical Force
variation for
Aves large
Transport?*



CALC		REVISED	DATE	SPEED STABILITY FL. TEST: 686-2 CONFIG. 101A THE BOEING COMPANY	367-80
CHECK					FIG. 7
APPD.					PAGE VI-23
APPD.					7



VI-23-2

Phugoid

Fig. 8. The measured period of the phugoid agrees very well with the theoretical while the measured damping ratio is approximately 40% of the theoretical value. The damping ratio, however, is very difficult to measure accurately since only one cycle of the phugoid was recorded.

Pitch Attitude

Fig. 9. Approximately 3 seconds are required for a change in pitch attitude of 8 degrees.


Elevator Pulse

Fig. 10. The 367-80 simulated the elevator pulse of the basic configuration accurately.

PHUGOID CHARACTERISTICS

AIRPLANE	367-80	101A
FLIGHT TEST	686-2	686-2
FLAP	30°	
V _L KTS	117	117
ALTITUDE	4,900 FT	SEA LEVEL
G.W. LBS	151,500	500,000
C.G.	30.2%	25%

IRIG 11:27:XX



--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

CALC		REVISED	DATE
CHECK			
APR			
APR			


PHUGOID CHARACTERISTICS
FLIGHT TEST 686-2
CONFIGURATION 101A

THE BOEING COMPANY

DE-15000

367-80
FIG. 8
PAGE
VI-25

PITCH ATTITUDE



AIR PLANE	367-80	101A
FLIGHT TEST	686-2	686-2
FLAP	30°	
$V_1 \sim \text{KTS}$	117	117
ALTITUDE	3,500 FT	SEA LEVEL
G.W. $\sim$ LBS	166,500	500,000
C.G.	30.2%	25%

CALC		REVISED	DATE
CHECK			
APR			
APR			


PITCH ATTITUDE
FLIGHT TEST 686-2
CONFIGURATION 101A

THE BOEING COMPANY
D6-15000

367-80
FIG. 9
PAGE
VI-26

30

ELEVATOR PULSE




$M_{\text{max}} = -50G$

$M_{\text{g}} = .587$

AIRPLANE	367-80	101A
FLIGHT TEST	686-2	686-2
FLAPS	30°	
V _I ~ KTS	117	117
ALTITUDE	4,500 FT	SEA LEVEL
G.W. ~ LBS	162,600	500,000
C.G.	30.2%	25%


CALC			REVISED	DATE	ELEVATOR PULSE FLIGHT TEST 686-2 CONFIGURATION 101A	367-80
CHECK						FIG. 10
APPD.						
APPD.						
					THE BOEING COMPANY DG-15000	PAGE VI-21-1



VI-27.2

Lateral:	
Maneuver	Comments
Steady Roll Rate	Fig. 11. The Steady State roll rate characteristics of the 367-80 were nonlinear whereas the theory is linear. The maximum roll rate achieved in flight was somewhat less than theory predicts. A sample of how the flight test data was reduced is shown in Fig. 12.
Roll Rate Reversal	Fig. 13. The 367-80 accurately simulated the basic 1209 configuration roll acceleration. Fig. 14 shows how the flight data were reduced.
Yaw Rate Reversal	Fig. 15. The yaw acceleration was slightly larger than predicted by the theory. Fig. 16 shows how flight data were reduced.
Steady Sideslip	Fig. 17. The 367-80 exhibited a low lateral control deflection to balance the sideslip angles generated,
Spiral Stability	Fig. 18. Theory gives the time to half amplitude as 18.3 seconds. Flight Test data indicated a time to half amplitude on the order of 100 seconds.
20° Heading Change	Fig. 19. A 20° heading change was accomplished in approximately 10.5 seconds. Opposite wheel is required to stop the roll at the desired bank angle.

STEADY ROLL RATE



O 684-3

AIRPLANE	367-80	1209
FLIGHT TEST	684-3	684-3
FLAP	30°	
V ₁ ~ KTS	117	117
ALTITUDE	7,500 FT	SEA LEVEL
G.W. ~ LBS	162,200	500,000
C.G.	31.1%	25%


IRIG 11:21:XX

CALC			REVISED	DATE
CHECK				
APR				
APR				

STEADY ROLL RATE
FLIGHT TEST 684-3
CONFIGURATION 1209


THE BOEING COMPANY
06-15000

367-80
FIG. 11
PAGE
VI-29



ENGR.			REVISED	DATE	SAMPLE OF FLIGHT TEST DATA FOR STEADY ROLL RATE.	D6-15000
CHECK						FIG. 12
APR						
APR						
					THE BOEING COMPANY RENTON, WASHINGTON	VI-30


ROLL RATE REVERSAL



SYM TEST TRIG
 O 684-3 11:15:XX
 Δ 686-2 11:45:XX


AIRPLANE	367-80	1209
FLIGHT TEST	{ 686-2 684-3	686-2 684-3
FLAP	30°	
V ₁ ~ KTS	117	117
ALTITUDE	{ 3,800 FT 7,500 FT	SEA LEVEL
G. W. ~ LBS	{ 156,500 162,200	500,000
C. G.	{ 30.2% 31.1%	25%

CALC	REVISED	DATE	ROLL RATE REVERSAL	367-80
CHECK			FLIGHT TEST 686-2 & 684-3	
APR			CONFIGURATION 1209	FIG. 13
APR			THE BOEING COMPANY	PAGE VI-31
			D6-15000	



ENGR.			REVISED	DATE	SAMPLE OF FLIGHT TEST DATA FOR ROLL RATE REVERSAL.	367-80
CHECK						FIG. 14
APR						VI-32
APR						
					THE BOEING COMPANY RENTON, WASHINGTON D6-15000	

YAW RATE REVERSAL




CALC			REVISED	DATE
CHECK				
APR				
APR				

YAW RATE REVERSAL
FLIGHT TEST 684-4 & 686-2
CONFIGURATION 1209

THE BOEING COMPANY
D6-15000


367-80
FIG.15
PAGE
VI-33

YAW RATE REVERSAL



ENGR.			REVISED	DATE	SAMPLE OF FLIGHT TEST DATA FOR YAW RATE REVERSALS. THE BOEING COMPANY RENTON, WASHINGTON	D6-15000
CHECK						FIG. 16
APR						
APR						VI-34

STEADY SIDESLIP CHARACTERISTICS



CALC			REVISED	DATE	STEADY SIDESLIP CHARACTERISTICS FLIGHT TEST 684-2, 686-2 CONFIGURATION 1209	367-80 FIG. 17
CHECK						
APPD.						
APPD.						
					THE BOEING COMPANY	PAGE
					D6-15000	VI-32

SPIRAL MODE

RIGHT BANK

LEFT BANK

RD
18
16
14
12
10
8
6
4
2
0


TIME - SEC

FLIGHT TEST LONG
THEORY 18.3


AIRPLANE	367-80	1209
FLIGHT TEST	684-2	684-2
CLAP	20°	
WIND KTS	117	117
ALTITUDE	5,000 FT	SEA LEVEL
G.W. - LBS	141,300	500,000
C.G.	25.8%	25%

18.3

CALC			REVISED	DATE	SPIRAL STABILITY FLIGHT TEST 684-2 CONFIGURATION 1209 THE BOEING COMPANY D6-15000	367-80
CHECK						FIG.18
APR						PAGE
APR						VI-36




VI-35-2





CALC			REVISED	DATE	20° HEADING CHANGE FLIGHT TEST 686-2 CONFIGURATION 1209	367-80
CHECK						FIG. 19
APR						
APR						
					THE BOEING COMPANY	PAGE VI-37
					D6-15000	

WHEEL STEP CHARACTERISTICS



AIR PLANE	367-80	1209
FLIGHT TEST	684-4	684-4
FLAP	30°	
V _i ~ KTS	117	117
ALTITUDE	3,500 FT	SEA LEVEL
G.W. ~ LBS	163,800	500,000
C.G.	30.8%	25%



CALC			REVISED	DATE	WHEEL STEP CHARACTERISTICS	367-80
CHECK					FLIGHT TEST 684-4	
APR					CONFIGURATION 1209	FIG. 20
APR					THE BOEING COMPANY	PAGE VI-38
					D6-15000	

Wheel Step


Fig. 20. Flight test roll angle data lags behind the six degree of freedom digital computer values for the wheel step shown. This is probably due to the aerodynamic and control surface lags which are not incorporated into the digital computer program.

Wheel Pulse

Fig. 21. Flight test data shows a good correlation with the theory for the basic 1209 configuration with the exception of sideslip angle.

Rudder Pulse


Fig. 22. Good correlation is evident with the exception of sideslip angle at the first reversal.




CALC			REVISED	DATE	WHEEL PULSE FLIGHT TEST 686-5 CONFIGURATION: 1209	367-80
CHECK						
APPD.						FIG. 21
APPD.						PAGE VI-40-
					THE BOEING COMPANY 06-15000	

VI-10-2

AIRPLANE	367-50	1209
FLIGHT TEST	686-5	686-5
FLAPS	30°	
$V_i \sim WTS$	117	117
ALTITUDE	4,000 FT	SEA LEVEL
G.W. ~ LBS	166,900	500,000
C.G.	30.6%	25%




RUDDER PULSE



AIRPLANE	367-80	1209
FLIGHT TEST	686-5	686-5
FLAPS	30°	
VI ~ KTS	117	117
ALTITUDE	5000 FT	SEA LEVEL
G.W. ~ LBS	158,300	500,000
C.G.	28.5%	25%


CALC			REVISED	DATE	RUDDER PULSE FLIGHT TEST 686-5 CONFIGURATION: 1209 THE BOEING COMPANY	D6-15000 FIG. 22 PAGE VI-41
CHECK						
APPD.						
APPD.						



VI-41
-2

B. Ground Based Simulation

The characteristics of a typical longitudinal configuration (G 100) and lateral directional configuration (G1202A), are presented in Figs. 23 thru 36. The theoretical characteristics shown are derived using the methods of Appendix 4. The parameters presented in these figures were used to validate the accuracy of the ground based simulation. Figs. 23 thru 36 indicate that the simulation was an accurate representation of the desired configurations.



CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				
				5

COLUMN STEP
GROUND BASED SIMULATOR
CONFIGURATION G101A

THE BOEING COMPANY

D6-15000


FIG. 23

PAGE
VI-43

PHUGOID

PHUGOID CHARACTERISTICS

W/D
RAD/SEC
THEORY .174
MEASURED .180
Y
.139
.170



CALC	R. Root	2-1-66	REVISED	DATE
CHECK				
APR				
APR				


PHUGOID CHARACTERISTICS
GROUND BASED SIMULATOR
CONFIGURATION G100

THE BOEING COMPANY


D6-15000

FIG. 24

PAGE
VI-44




CALC	R. Root	2-1-66	REVISED	DATE	SHORT PERIOD CHARACTERISTICS GROUND BASED SIMULATOR CONFIGURATION GIOIA THE BOEING COMPANY	D6-15000
CHECK						FIG. 25
APR						PAGE
APR						VI-45




CALC	R. Root	2-2-66	REVISED	DATE	ELEVATOR PULSE GROUND BASED SIMULATOR CONFIGURATION G100 THE BOEING COMPANY	D6-15000
CHECK						FIG. 26
APR						PAGE
APR						VI-46

SPEED STABILITY



$$M_{\delta e} = -3.62 / \text{SEC}^2$$

$$\delta e / \text{FOOT} = -3.29 \text{ DEG/IN.}$$



CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				

SPEED STABILITY
GROUND BASED SIMULATOR
CONFIGURATION G100


THE BOEING COMPANY

D6-15000

FIG. 27


PAGE
VI-47

PITCH REVERSALS



CALC	R. Root	2-2-66	REVISED	DATE	PITCH REVERSALS GROUND BASED SIMULATOR CONFIGURATION G100 & G101A THE BOEING COMPANY	D6-15000
CHECK						FIG. 28
APR						PAGE
APR						VI-48


WHEEL REVERSAL



CALC	R. Root	2-2-66	REVISED	DATE	WHEEL REVERSAL GROUND BASED SIMULATOR CONFIGURATION G1202A THE BOEING COMPANY	D6-15000
CHECK						
APR						FIG.29
APR						PAGE VI-49


ROLL RATE

ONE DEGREE OF FREEDOM



CALC	R. Root	2-2-66	REVISED	DATE	ROLL RATE GROUND BASED SIMULATOR CONFIGURATION G1202A THE BOEING COMPANY	D6-15000
CHECK						FIG. 30
APR						PAGE
APR						VI-50

YAW RATE REVERSAL



CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				

YAW RATE REVERSAL
GROUND BASED SIMULATOR
CONFIGURATION G1202A


THE BOEING COMPANY

DO-15000


FIG. 31

PAGE
VI-51


STEADY SIDESLIP




CALC	R. Root	2-2-66	REVISED	DATE	STEADY SIDESLIP CHARACTERISTICS GROUND BASED SIMULATOR CONFIGURATION G1202	D6-15000
CHECK						FIG. 31A
APR						
APR						
					THE BOEING COMPANY	PAGE VI-52



CALC	R. Root	2-2-66	REVISED	DATE	SPIRAL MODE GROUND BASED SIMULATOR CONFIGURATION G1202 A THE BOEING COMPANY	D6-15000
CHECK						FIG.32
APR						PAGE
APR						VI-53



CALC	R. Root	2-2-66	REVISED	DATE	DUTCH ROLL MODE GROUND BASED SIMULATOR CONFIGURATION G1202A THE BOEING COMPANY	D6-15000
CHECK						
APR						FIG. 33
APR						PAGE VI-54



CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				


RUDDER PULSE
 GROUND BASED SIMULATOR
 CONFIGURATION G1202A

THE BOEING COMPANY


D6-15000

FIG. 34

PAGE
VI-55



CALC	R. Root	2-2-66	REVISED	DATE	WHEEL PULSE GROUND BASED SIMULATOR CONFIGURATION G1202A THE BOEING COMPANY	D6-15000
CHECK						
APR						FIG. 35
APR						
						PAGE VI-56



CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				

WHEEL STEP
GROUND BASED SIMULATOR
CONFIGURATION G1202A

THE BOEING COMPANY

D6-15000
FIG. 36
PAGE
VI-57

VII. LONGITUDINAL CONFIGURATION

A. Airborne Simulation

Eight variations of the basic longitudinal configuration are discussed in this section. The documentation maneuvers performed with each configuration are summarized in a single Figure or Table whenever possible. They are eliminated entirely when the response does not change significantly from that of the basic configuration. For the purposes of evaluating and documenting the longitudinal mode the lateral configuration was always the basic 1209.

Table 1 contains a summary of the longitudinal configurations evaluated on the Airborne Simulation. The numbers shown are theoretical values equivalent to the theoretical lines shown on the Figures. The longitudinal aerodynamic coefficients used to obtain these characteristics are listed in Appendix 1.

CONFIG.	L_{α} /SEC-RAD	M_{α} /SEC ²	$L_{\delta \text{COL.}}$ /SEC-IN/RAD/SEC	$M_{\delta \text{COL.}}$ /SEC	$\dot{M}_{\delta}$ /SEC	L_{δ} /RAD	SHORT PERIOD		PHUGOID		COMMENTS INCREASED (+) DECREASED (-)
							ω_h RAD/SEC	ζ	ω_n RAD/SEC	ζ	
101A	.521	-.506	.00313	.0252	-.587	.0516	.907	.7033	.1720	.1490	BASIC
100			-.00262	.0167							- SENSITIVITY
105A			-.00625	.0504							+ SENSITIVITY - LIFT WITH $\delta \text{COL.}$
105 *			-.00792								+ SENSITIVITY - LIFT WITH $\delta \text{COL.}$
151B			-.00010	.0252							++ LIFT WITH $\delta \text{COL.}$
151C			-.00164								+ LIFT WITH $\delta \text{COL.}$
151D			-.00020	.0504							+ SENSITIVITY ++ LIFT WITH $\delta \text{COL.}$
158A	.552	-1.012	-.00635		-1.174	.0984	1.330	.7205	.1693	.1845	+ SENS. - LIFT WITH $\delta \text{COL.}$ + DAMPING + STATIC STABILITY
159A	.521	-.506	-.00316	.0252	-1.174	.0984	1.071	.8647	.1446	.2352	+ DAMPING
159B	.521	-.506	-.00635	.0504	-1.174	.0984	1.071	.8647	.1446	.2352	+ SENS. - LIFT WITH $\delta \text{COL.}$ + DAMPING
161B	.497	-.128	-.00635		-.587	.0516	.650	.9423	.1200	.3320	+ SENS - LIFT WITH $\delta \text{COL.}$ - STATIC STAB.
-80 BLC	.459	-.469	-.00278	.0641	-.125	0	1.347	.5245	.1352	.1244	+ DAMPING + STATIC STABILITY

ENGR.		REVISED	DATE	AIRBORNE SIMULATION LONGITUDINAL RUN LOG	TABLE 1
CHECK					D6-15000
APR				THE BOEING COMPANY RENTON, WASHINGTON	VII-59
APR					

A summary of pitch rate reversals for all configurations is shown in Fig. 37 normalized to the pitch control sensitivity of the basic 101A configuration. This curve shows some scatter in the data but generally good agreement with the theoretical for all configurations.

Column steps are shown in Figs. 38 & 39 for two configurations, 151B and 151C, which point out changes in lift due to column deflection when compared to the basic 101A configuration (Fig. 4). A lag is apparent in the flight test data that does not show up in the theoretical results. This could be due to an aerodynamic lag or a lag in the lift control (spoilers) which does not appear in the theory.

The wind up turn data is shown for all configurations in Figs. 40 through 55 and matches the theoretical calculations accurately.

Speed stability tests were performed and correlation with the theoretical static characteristics was good. Results are shown in Figs. 56 through 63.

A summary of phugoid characteristics for all configurations is shown in Table 2. The damping ratios were difficult to measure accurately since only one cycle of the phugoid was recorded and they do not compare accurately with the theoretical. The period, on the other hand, was easily determined and agrees closely with theory.

TABLE 2


PHUGOID CHARACTERISTICS

CONFIGURATION	PERIOD (SEC)		DAMPING RATIO	
	Flight Test	Theory	Flight Test	Theory
-80B	40.9	46.5	.140	.1244
100	36.6	36.9	.078	.1490
101A	36.0	36.9	.062	.1490
105*	29.6	36.9	.058	.1490
105A	30.0	36.9	.063	.1490
151B	26.2	36.9	.093	.1490
151C	31.2	36.9	.070	.1490
158A	35.8	37.8	.102	.1845
159A	40.8	44.5	.128	.2352
161B	31.3	55.5	.090	.3320

A pitch attitude change is shown for configuration 158A in Fig. 64.


Comparison with the basic 101A configuration (Fig. 9) shows the effect of changing lift with column deflection.

Elevator pulses are shown in Figs. 65 thru 67 for three configurations, 158A, 159A and 161B. Comparison of these pulses with the 101A configuration (Fig. 10) and with one another shows the effect static stability and pitch damping.



CALC			REVISED	DATE	NORMALIZED PITCH RATE REVERSALS - SUMMARY	367-80
CHECK						FIG. 37
APR						
APR						
					THE BOEING COMPANY D6-15000	PAGE VII-62

COLUMN STEP CONFIGURATION 151B



AIRPLANE	367-80	151B
FLIGHT TEST	686-9	686-9
FLAP	30°	
$V_i \sim \text{KTS}$	117	117
ALTITUDE	7,600	SEA LEVEL
G.W. → LBS	140,800	500,000
C.G.	28.3%	25%

IRIG 12:03:KK


CALC			REVISED	DATE
CHECK				
APR				
APR				

COLUMN STEP
FLIGHT TEST 686-9
CONFIGURATION 151 B

THE BOEING COMPANY
D6-15000

367-80
FIG.38
PAGE
VII-63

COLUMN STEP CONFIG. 151C



AIRPLANE	367-80	151C
FLIGHT TEST	686-8	686-8
FLAP	30°	
V_L ~ KTS	117.	117.
ALTITUDE	4,300 FT.	SEA LEVEL
G.W. ~ LBS.	166,400	500,000
G.G.	30.6%	25.0%

1916 14:34:XX

CALC			REVISED	DATE
CHECK				
APR				
APR				

COLUMN STEP
FLIGHT TEST 686-8
CONFIGURATION 151C

367-80


FIG. 39

THE BOEING COMPANY

DG-15000


PAGE
VII-64

WINDUP TURN




CALC			REVISED	DATE	WINDUP TURN	367-80
CHECK					FL. TEST : 686-1	
APR					CONFIG. : 100	FIG. 40
APR					THE BOEING COMPANY	PAGE VII-65
					DG-15000	

WINDUP TURN




CALC		REVISED	DATE	WINDUP TURN FL. TEST : 686-11 CONFIG. : 100 THE BOEING COMPANY DG-15000	367-80
CHECK					
APR					FIG. 41
APR					PAGE VII-66

WINDUP TURN



CALC			REVISED	DATE	WINDUP TURN	367-80
CHECK					FL. TEST: 686.9	
APR					CONFIG. 105*	FIG. 42
APR					THE BOEING COMPANY	PAGE
					D6-15000	VII-67

WINDUP TURN



CALC			REVISED	DATE	WINDUP TURN FL. TEST: 686-9 CONFIG. : 105*	367-80
CHECK						
APR						FIG.43
APR						
					THE BOEING COMPANY D6-15000	PAGE VII-68


WINDUP TURN



0


AIRPLANE	367-80	105A
FL. TEST	686-7	686-7
FLAPS	30°	
VE ~ KTS.	117	117
ALTITUDE	4500 FT.	SEA LEVEL
G.W. ~ LBS.	162000	500000
C.G.	30.7%	25.9%

IRIG 11:50:XX




CAIC			REVISED	DATE	WINDUP TURN	367-80
CHECK					FL. TEST : 686-7	
APR					CONFIG.: 105A	FIG. 44
APR					THE BOEING COMPANY	PAGE VII-69
					D6-15000	

WINDUP TURN




CALC			REVISED	DATE	WINDUP TURN FL. TEST : 686-7 CONFIG. : 105A THE BOEING COMPANY D6-15000	105A
CHECK						
APR						FIG. 45
APR						PAGE VII-70

WINDUP TURN




CALC			REVISED	DATE	WINDUP TURN	367-80
CHECK					FL. TEST: 686-9	FIG. 46
APR					CONFIG. 151B	PAGE
APR					THE BOEING COMPANY	VII-71
					D6-15000	

WINDUP TURN




CALC			REVISED	DATE	WINDUP TURN FL. TEST : 686-9 CONFIG. : 151B THE BOEING COMPANY D6-15000	151-B
CHECK						
APR						FIG. 47
APR						PAGE VII-72

WINDUP TURN




CALC			REVISED	DATE	WINDUP TURN	367-80
CHECK					FL. TEST. : 686-8	
APR					CONFIG. 151C	FIG. 48
APR					THE BOEING COMPANY	PAGE VII-73
					D6-15000	

WINDUP TURN



CALC			REVISED	DATE	WINDUP TURN	151-C
CHECK					FL. TEST : 686-B	FIG.49
APR					CONFIG. : 151-C	PAGE
APR					THE BOEING COMPANY	VII-74
					D6-15000	

WINDUP TURN




AIRPLANE	367-80	158A
FL. TEST	686-10	686-10
FLAPS	30°	
V_L ~ KTS.	117	117
ALTITUDE	8300 FT.	SEA LEVEL
G.W. ~ LBS.	167200	500000
C.G.	30.4%	25%

IRIG 13:44:XX

IRIG 13-44-18

CALC			REVISED	DATE	WINDUP TURN	367-80
CHECK					FL. TEST: 686-10	
APR					CONFIG.: 158A	FIG. 50
APR					THE BOEING COMPANY	PAGE
					D6-15000	VII-75

WINDUP TURN



CALC			REVISED	DATE	WINDUP TURN FL. TEST. 686-10 CONFIG. : 158A THE BOEING COMPANY DG-15000	158A
CHECK						
APR						FIG. 51
APR						PAGE VII-76

WINDUP TURN

δ_c
IN.

30
25
20
15
10
5
0

THEORY

AIRPLANE	367-80	159A
FL. TEST	686-B	686-B
FLAPS	30°	
V_c - KTS.	117	117
ALTITUDE	4800 FT.	SEA LEVEL
G.W. - LBS.	159300	500000
C.G.	31%	25%


IRIG 14:59:XX

1.0 1.04 1.08 1.12 1.16 1.20 1.24

n_z ~ LOAD FACTOR - g's.

CALC			REVISED	DATE	WINDUP TURN	367-80
CHECK					FL. TEST : 686-B	
APR					CONFIG. 159A	FIG. 52
APR					THE BOEING COMPANY	PAGE VII-77
					DG-15000	

WINDUP TURN




AIRPLANE	367-90	159A
FL. TEST	686-5	686-5
FLAPS	30°	
V _L - KTS.	117	117
ALTITUDE	4800 FT.	SEA LEVEL
G.W. - LBS.	159300	500000
C.G.	31.9%	25.9%

IRIG 14:59:XX

n_z ~ LOAD FACTOR ~ g's.

CALC			REVISED	DATE	WINDUP TURN	159A
CHECK					FL. TEST : 686-5	FIG.53
APR					CONFIG. : 159A	
APR					THE BOEING COMPANY	PAGE
					PG-15000	VII-78

WINDUP TURN



CALC			REVISED	DATE
CHECK				
APR				
APR				

WINDUP TURN
FL. TEST : 686-10
CONFIG. : 161 B


THE BOEING COMPANY
D6-15000

367-80

FIG. 54

PAGE
VII-79

WINDUP TURN




CALC			REVISED	DATE	WINDUP TURN FL. TEST : 686-10 CONFIG. : 161B THE BOEING COMPANY D6-15000	161 B
CHECK						FIG.55
APR						PAGE
APR						VII-80

SPEED STABILITY


AIRPLANE :	367-80	100
FL. TEST	686-1	686-1
FLAPS	30°	
V _R - KTS	117	117
ALTITUDE	4000 FT. SEA LEVEL	
G.W. - LBS.	154000	150000
C.G.	25.0%	25.0%

IRIG 14-511X



CALC		REVISED	DATE	SPEED STABILITY FL. TEST : 686-1 CONFIG. : 100 THE BOEING COMPANY	367-80
CHECK					FIG. 56
APPD.					PAGE
APPD.					VII-31


VII-81
2




SPEED STABILITY

AIRPLANE	367-80	105-A
FL TEST	686-7	686-7
FLAPS	30°	
V _L - KTS	117	117
ALTITUDE	4000 FT. SEA LEVEL	
G.W. - LBS.	157600	500000
C.G.	25.9%	25.9%

IRIG 11:53:00



CALC			REVISED	DATE	SPEED STABILITY FL. TEST : 686-7 CONFIG. 105-A THE BOEING COMPANY D6-15000	367-80
CHECK						FIG.57
APPD.						PAGE
APPD.						VII-32



VII-82
29

98

SPEED STABILITY

AIRPLANE :	367-80	105*
FL TEST	686-9	686-9
FLAPS	30°	
V _R KTS.	117	117
ALTITUDE	5000 FT. SEA LEVEL	
GW - LBS.	170000	200000
C.G.	30.5%	25.9%

IRIG 12:05:XX

20

10

0

-10

-20

30

170000

117

30

CALC		REVISED	DATE
CHECK			
APPD.			
APPD.			

SPEED STABILITY
FL. TEST : 686-9
CONFIG. : 105*


THE BOEING COMPANY
D6-15000

367-80

FIG. 58

PAGE
VII-33

THEORY
TEST POINT




VII-83-2

18

SPEED STABILITY

AIRPLANE :	367-80	151-B
FL TEST	686-9	686-9
FLAPS	30°	
VL ~ KTS	117	117
ALTITUDE	6100 FT.	SEA LEVEL
G.W. ~ LBS	157000	500000
C.G.	20.5%	25%


IRIG 1231KX



THEORY
Q TEST POINT

CALC		REVISED	DATE	SPEED STABILITY FL TEST : 686-9 CONFIG. : 151-B THE BOEING COMPANY	367-80
CHECK					FIG. 59
APPD.					PAGE
APPD.					VII-34

VII-84-2




21

SPEED STABILITY


AIRPLANE	367-80	151C
FL. TEST	686-8	686-8
FLAPS	30°	
V ₀ - KTS.	117	117
ALTITUDE	3800 FT. SEA LEVEL	
G.W. - LBS.	166000	50000
C.G. -	30.6%	25%

RIG 14381XX



THEORY
○ TEST POINT

CALC		REVISED	DATE	SPEED STABILITY FL. TEST : 686-8 CONFIG. : 151C THE BOEING COMPANY	367-80
CHECK					FIG. 60
APPD.					PAGE VII-35
APPD.					D6-15000



VII-85-2

SPEED STABILITY

AIRCRAFT	367-80	158-A
FL. TEST	686-10	686-10
FLAPS	30°	
V ₀ - KTS	117	117
ALTITUDE	5500 FT	SEA LEVEL
G.W. - LBS.	67200	50000
C.G.	30.4%	25.0%

RIG 131401XX




CALC		REVISED	DATE
CHECK			
APPD.			
APPD.			

SPEED STABILITY
FL. TEST : 686-10
CONFIG. : 158-A

THE BOEING COMPANY D6-15000

367-80
FIG. 61
PAGE
VII-30-1


III-862



SPEED STABILITY

AIRPLANE :	367-80	159A
FL. TEST	CG-8	686-8
PLANS	30	
VC - KTS	111	117
ALTITUDE	5000 FT	SEALVEL
GW - LBS.	120300	500000
C.G.	31.0%	25%

RIG 15:00'XX




CALC			REVISED	DATE
CHECK				
APPD.				
APPD.				

SPEED STABILITY
FL. TEST : 686-8
CONFIG. : 159 A

367-80
FIG. 62
PAGE
VII-7

THE BOEING COMPANY DG-15000



II-81-2

SPEED STABILITY

AIRPLANE	367-80	161 B
FL TEST	686-10	686-10
FLAPS	30°	
V _L - KTS.	117	117
ALTITUDE	8100 FT.	SEA LEVEL
G.W. - LBS.	153000	500000
C.G.	28%	25%

TRIG 14:26:XX

20 10 0 -10 -20 30

F_s

100

THEORY

Q TEST POINT


CALC		REVISED	DATE
CHECK			
APPD.			
APPD.			


SPEED STABILITY
FL TEST : 686-10
CONFIG : 161 B

THE BOEING COMPANY

DB-15000
FIG. 63
PAGE
VII-53-1

VII-88-2





CALC			REVISED	DATE	PITCH ATTITUDE FLIGHT TEST 686-10 CONFIGURATION 158A	367-80
CHECK						
APR						FIG. 64
APR						PAGE VII-89
					THE BOEING COMPANY D6-15000	

93

CALC			REVISED	DATE
CHECK				
APPD.				
APPD.				

ELEVATOR PULSE
FLIGHT TEST 686-10
CONFIGURATION 158 A

THE BOEING COMPANY D6-15000


367-80
FIG. 65
PAGE
VII-10


ELEVATOR PULSE

$M_x = -1.012$

$M_y = 1.174$

AIRPLANE	367-80	158 A
FLIGHT TEST	686-10	686-10
FLAPS	30°	
V_i ~ KTS	117	117
ALTITUDE	10,500 FT	SEA LEVEL
G.W. ~ LBS.	173,300	500,000
C.G.	30.2%	25%






VII-90-2

h0

CALC			REVISED	DATE	ELEVATOR PULSE FLIGHT TEST 686-8 E-14 CONFIGURATION 159 A	367-80
CHECK						FIG. 66
APPD.						
APPD.						
					THE BOEING COMPANY DG-15000	PAGE VII-11


TD 1053-R5

ELEVATOR PULSE




VII-91-2

$M_A = -506$
 $M_B = 1174$



ELEVATOR PULSE



$$M_{\alpha} = -1.128$$

$$M_{\delta} = .587$$

AIRPLANE	367-80	161B
FLIGHT TEST	686-10	686-10
FLAPS	30°	
V _i ~ KTS	117	17
ALTITUDE	8,200 FT	SEA LEVEL
G.W. ~ LBS	173,300	500,000
C.G.	30.2%	25%


CALC			REVISED	DATE
CHECK				
APPD.				
APPD.				

ELEVATOR PULSE
FLIGHT TEST 686-10
CONFIGURATION 161B

367-80
FIG.67

THE BOEING COMPANY D6-15000

PAGE
VII-92



VII-92
-2

B. Ground Based Simulation

The longitudinal characteristics of all the configurations evaluated on the ground based simulator are presented in Table 3. The longitudinal aerodynamic coefficients used to obtain these characteristics are listed in Appendix 1. The effect of elevator lift on pitch response during a step column maneuver is shown for the basic configuration in Fig. 23 (page ~~V~~^r43). The response of configurations with no elevator lift ($L_{\delta_E} = 0$) and elevator lift opposite the basic configuration ($L_{\delta_E} = -$ basic value) are shown in Figs. 68 and 69 for comparison. The effect of changes in static stability and damping are presented in Figs. 70, 71, and 72 for an elevator pulse. These are comparable to the typical response shown in Fig. 26 (page ~~V~~^r44).

1b

AD 1040C-R3

6-7000

GROUND BASED CONFIG	L _d	M _d	M	L _{δcol}	M _{δcol}	M _δ	F _{col} /δ _{col}	SHORT PERIOD		PHUGOID		δ _E /δ _{col}
								ω _n	ξ	ω _n	ξ	
G-	1/SEC·RAD	1/SEC ²	RAD/SEC ²	1/SEC·IN	RAD/SEC ² ·IN	1/SEC	LB/IN	RAD/SEC	-	RAD/SEC	-	DEG./IN
100	.571	-.506	.166	.00195	.0219	-.585	4.4457	.928	.707	.177	.142	-3.29
100A			.332		.0499		4.4					
100X			.166	.00391	.0219		5.7					
101A			.240	.00195	.0316		4.4457					
102			.193		.0176		4.4					
103			.107		.0141							
103A				.00391	.0281							
105			.166		.0438							
105A			.245		.0646		5.7					
105*			.166	.00588	.0658							
105 ² X				.01175								
106		-.245		.00195	.0219		4.4	.772	.843	.148	.205	-3.29
107		0.						.575	1.100	-	-	
108			.107		.0141							
109			.213		.0282							
109A			.166	.00391	.0438							
110		+.245		.00195	.0219			.295	2.200			-3.29
111	.302	-.506						.834	.629	.197	.116	
112		-.735						.957	.546	.206	.119	
112A		-.980						1.075	.485	.212	.124	
113		-.343						.732	.716	.184	.124	
113A						-.296		.666	.580	.203	.083	
115		0.				-.585		.420	1.340	-	-	
120	.571	-.506				-.242		.817	.605	.201	.081	

CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				

GROUND BASED SIMULATION
LONGITUDINAL RUN LOG

THE BOEING COMPANY
RENTON, WASHINGTON D6-15000

TABLE
3
PAGE
VII-94

CALC	CHECK	APR	APR	GROUND BASED CONFIG	L_d 1/SEC.RAD	M_d 1/SEC ²	M RAD/SEC ²	$L_{\delta_{col}}$ 1/SEC.IN	$M_{\delta_{col}}$ RAD/SEC ² .IN	$M_{\dot{\theta}}$ 1/SEC.	F_{col}/δ_{col} LB/IN	SHORT PERIOD		PHUGOID		δ_e/δ_{col} DEG/IN
												ω_n RAD/SEC.	γ	ω_n RAD/SEC.	γ	
				G~												
				122A	.571	-.980	.166	-.00195	.0219	-.585	4.4	1.151	.569	.198	.130	-3.29
				123	.925	-.506						1.036	.799	.158	.170	
				123A				-.00391	.0438							-6.58
				123B			.245		.0646		5.7					
				124		-.122	.166	-.00195	.0219		4.4	.805	1.000	.099	.416	-3.29
				125		.098						.660	1.24			
				126		-.245	.107		.0141			.883	.93	.127	.260	
				126A			.166	-.00391	.0438							-6.58
				127		0	.107	-.00195	.0141			.73	1.115			-3.29
				128		-.245				-.245		.725	.92	.160	.091	
				129		0						.520	1.195			
				130			.166		.0219	-.585		.695	1.115			
				131		-.122				-.245		.635	1.040	.128	.169	
				132		-.506	.107		.0141			.882	.762	.184	.073	
				150	.571		.166		.0219	-.585		.927	.716	$C_{D_0} = 1.77 \times B_{ASFC}$		
				151				+.00195						.177	.140	
				151B			.245	+.00165	.0273		5.7					-2.78
				151C				0								
				151C*			.166		.0219							-3.29
				151D			.245	+.00391	.0646							-6.58
				152		-1.420	.166	-.00195	.0219	-1.173	4.4	1.466	.645	.190	.155	-3.29
				153			.332		.0439							
				154		-.506	.166		.0219			1.089	.865	.151	.225	
				155			.332		.0439							

GROUND BASED SIMULATION
LONGITUDINAL RUN LOG.

THE BOEING COMPANY

RENTON, WASHINGTON D6-15800


TABLE I

3

PAGE

VII-95

[illegible]



CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				


COLUMN STEP
GROUND BASED SIMULATOR
CONFIGURATION G151B

THE BOEING COMPANY


D6-15000

FIG.68


PAGE
VII-97




CALC	R. Root	2-2-66	REVISED	DATE	COLUMN STEP GROUND BASED SIMULATOR CONFIGURATION G151C	D6-15000
CHECK						FIG. 69
APR						PAGE
APR						VII-98
					THE BOEING COMPANY	



CALC	R. Root	2-2-66	REVISED	DATE	ELEVATOR PULSE GROUND BASED SIMULATOR CONFIGURATION G161B THE BOEING COMPANY	D6-15000
CHECK						FIG. 70
APR						PAGE
APR						VII-99



CALC	R. Root	2-266	REVISED	DATE	ELEVATOR PULSE GROUND BASED SIMULATOR CONFIGURATION G159A	D6-15000
CHECK						FIG. 71
APR						PAGE
APR						VII-100
					THE BOEING COMPANY	



CALC	R. Root	2-2-66	REVISED	DATE	ELEVATOR PULSE GROUND BASED SIMULATOR CONFIGURATION G158A THE BOEING COMPANY	D6-15000
CHECK						FIG.72
APR						PAGE
APR						VII-101

VIII. LATERAL CONFIGURATION CHARACTERISTICS

A. Airborne Simulation

The characteristics of the four lateral directional configurations evaluated on the airborne simulation which are different from the basic 1209 configuration are documented in this section.

The responses to the documentation maneuvers are summarized or eliminated when there is negligible change from the basic configuration. During all the lateral flight test documentation and evaluation the longitudinal configuration was the basic 101A configuration.

Table 4 contains a summary of the lateral directional configurations evaluated on the Airborne Simulation. The lateral-directional aerodynamic coefficients used to obtain these characteristics are listed in Appendix 1. A summary plot of the steady roll rate maneuver is shown in Fig. 73 for several configurations. The maximum steady state roll rate available agrees fairly well with the theoretical value.

The roll rate reversal data is shown in Figs. 74 thru 77 for four configurations. Comparison of these configurations with the basic, 1209 (Fig. 13), and with each other shows the effect of roll control sensitivity (slope) and total roll control power ($\ddot{\phi}_{\max}$). The roll control power available in flight test is generally lower than theory predicts whereas the sensitivity is accurately predicted.


901

CONFIG.	L RAD/SEC ²	$\delta_{W_{EFF}}$ DEG	$L_{\delta W}$ 1/SEC ²	$t_{\delta a_{MAX}}$ SEC	τ_{3D} SEC	P_{SS} RAD/SEC	ϕ_1 DEG	ϕ_2 DEG	DUTCH ROLL		COMMENTS
									ω_n	ζ	
1209	.267	50	.306	.48	1.14	.348	RT 2.10 LT 2.10	11.3 13.0	.508	.329	BASIC
1203A	.240	30	.458			.358	1.89	10.02			+ ROLL CONTROL SENSITIVITY
1207A	.150	30	.286			.196	1.20	7.25			- ROLL CONTROL POWER
1235	.267	30	.511		.60	.167	1.90	8.95	.533	.380	+ DAMPING IN ROLL + ROLL SENSITIVITY
1237	.250	50	.286	.84	1.14	.326	1.40	9.10	.508	.329	+ TIME TO MAX. AILERON
-80BLC	.323	NON LINEAR	1.200	.48	NON LINEAR	NON LINEAR	4.00	20.72	.513	.564	++ ROLL SENSITIVITY + POWER + DAMPING

MEASURED DURING
FLIGHT TEST

ENGR.				REVISED	DATE	AIRBORNE SIMULATION LATERAL RUN LOG	TABLE 4
CHECK							D6-15000
APR						THE BOEING COMPANY RENTON, WASHINGTON	VIII-103
APR							

ROLL RATE



CALC		REVISED	DATE
CHECK			
APR			
APR			

SUMMARY OF STEADY ROLL RATES

THE BOEING COMPANY DG-15000

367-80

FIG. 73

PAGE
VIII-104


A 20° heading change is presented for configuration 1235 in Fig. 78. The high roll damping of this configuration is evident when the time history of the wheel activity is compared to that of the basic 1209 configuration. (Fig. 19).

Table 5 shows the results of wheel steps.

TABLE 5
WHEEL STEP

CONFIG.	ϕ_1	ϕ_2	β_1	β_2	δw_1	δw_2
1203A	1.89	10.02	.23	1.76	75.6	75.6
1207A	1.20	7.25	.16	1.00	75.6	75.6
1209 Left	2.10	11.3	.30	1.56	75.6	75.6
1209 Right	2.10	13.0	.41	2.03	75.6	75.6
1235	1.90	8.95	.07	1.12	75.6	75.6
1237	1.40	9.1	.11	1.28	75.6	75.6
-80 BLC	4.00	20.72	.74	2.11	75.6	75.6

ROLL RATE REVERSAL




CALC			REVISED	DATE
CHECK				
APR				
APR				

ROLL RATE REVERSAL
FLIGHT TEST 686-4 & 5
CONFIGURATION 1203A

THE BOEING COMPANY 06-15000

367-80
FIG. 74
PAGE
VIII-106

ROLL RATE REVERSAL




SYM TEST IRIG
O 686-6 14:34:XX

AIRPLANE	367-80	1207A
FLIGHT TEST	686-6	686-6
FLAP	30°	
$V_1 \sim \text{KTS}$	117	117
ALTITUDE	7,000 FT	SEA LEVEL
G.W. $\sim$ LBS	158,900	500,000
C.G.	30.7%	25%

CALC		REVISED	DATE	ROLL RATE REVERSAL	367-80
CHECK				FLIGHT TEST 686-6	
APR				CONFIGURATION 1207A	FIG. 75
APR				THE BOEING COMPANY DG-15000	PAGE VIII-107

ROLL RATE REVERSAL



SYM TEST IRIG
O 686-4 14:04:XX

$L = .267$
 $L_{SWH} = .511$

AIRPLANE	367-80	1235
FLIGHT TEST	686-4	686-4
FLAP	30°	
V _I ~ KTS	117	117
ALTITUDE	5,200 FT	SEA LEVEL
G. W. ~ LBS	158,500	500,000
C. G.	29.3%	25.7%


CALC			REVISED	DATE
CHECK				
APR				
APR				

ROLL RATE REVERSAL
FLIGHT TEST 686-4
CONFIGURATION 1235

THE BOEING COMPANY DG-15000

367-80
FIG. 76
PAGE
VIII-108

ROLL RATE REVERSAL



CALC			REVISED	DATE
CHECK				
APR				
APR				


ROLL RATE REVERSAL
FLIGHT TEST 686-6
CONFIGURATION 1237

THE BOEING COMPANY D6-15000

367-80

FIG. 77

PAGE
VIII-109



CALC			REVISED	DATE	20° HEADING CHANGE FLIGHT TEST 686-4 CONFIGURATION 1235	367-80
CHECK						D6-15000
APR						FIG. 78
APR						PAGE
					THE BOEING COMPANY	VIII-110

113

B. Ground Based Simulation

The lateral-directional characteristics of all the configurations evaluated on the ground based simulator are presented in Table 6. The aerodynamic coefficients and augmentation system used to obtain these characteristics are listed in Appendix 1. Lateral-Directional aerodynamic characteristics which are equivalent to the basic values with augmentation are also presented. Figures 79, 80, and 81 present roll response ϕ_1 and ϕ_2 as a function of control power for the three augmentation systems used (described in Appendix 1). The effect of roll time constant (τ_R) on roll response is presented in Fig. 82 for a step wheel and Fig. 83 for step aileron. Figs. 84 and 85 give roll response for typical configurations with augmentations 2 and 3. A typical roll response with augmentation 1 was presented in Fig. 36 (page VII-57). Figure 86 presents roll response of a configuration with low available aileron rate (60 °/sec).

GROUND BASED CONFIG	L	δ_{WH} EFF.	$L\delta_{WH}$	$t\delta_{a\max}$	τ_{ROLL}	$\dot{\phi}_{SS}$	ϕ_1	ϕ_2	F_W δ_W	AIR SYSTEM	DUTCH ROLL		SPIRAL
											ω_n	$\int$	
GN	END PT	DEG.	1/SEC ²	SEC.	SEC.	DEG/SEC.	DEG.	DEG.	LB/OLG		RAD/SEC.		SEC.
1	20	50	.229	.10	1.42	16.3	4.4	14.2	.28	2	.449	.339	2.5
1					1.14	13.1	4.1	15.8		3	.508	.329	18.3
1h					1.42	16.3	4.4	14.2	.14	2	.449	.339	2.5
2	30		.344			24.4	6.5	21.2	.28				
3	40		.458			32.6	8.7	28.1					
4	50		.573			40.7	10.8	35.0					
5	60		.688			48.9	13.0	42.0					
5A	80		.917			65.1	17.4	56.2					
5B	10		1.146			81.5	21.6	70.					
5C	15		.172			12.2	9.3	10.9		1			
5C					1.14	9.8	9.0	12.0		3	.508	.329	18.3
5D	25		.143		1.42	10.2	2.8	9.0		2	.449	.339	2.5
5E	9		1.031			73.2	19.5	63.					
5F	10		.115			8.1	2.2	6.8		1			
5G	05		.057		1.14		1.0	4.0		3	.508	.329	18.3
5H	90		.032										
5J	30		.096							1			
6	15		.286		1.42	12.2	9.3	10.9		2	.449	.339	2.5
6					1.14	9.8	9.0	12.0		3	.508	.329	18.3
7A	10		.191		1.42	8.1	2.2	6.8		2	.449	.339	2.5
8	30	75	.229			14.4	6.5	21.2		1			
8A	15		.115		1.14	9.8	3.0	12.0		3	.508	.329	18.3
9	40		.306		1.42	32.6	8.7	28.1		2	.449	.339	2.5
10	90		.255							1			

CALC	R. Root	2-2-66
CHECK		
APR		
APR		

REVISED	DATE

GROUND BASED SIMULATION
LATERAL RUN LOG.

THE BOEING COMPANY
RENTON, WASHINGTON

TABLE 6
D6-15000
PAGE
VIII-112

GROUND BASED CONFIG	L	δ_{WH} EFF.	$L\delta_{WH}$	$t\delta_{MAX}$	τ_{ROLL}	$\dot{\phi}_{SS}$	ϕ_1	ϕ_2	$\frac{F_W}{\delta_W}$	KG SYSTEM	OUTCH ROLL	SPIRAL	
CALC	R. Root												
CHECK													
APR													
APR													
GROUND BASED CONFIG	L	δ_{WH} EFF.	$L\delta_{WH}$	$t\delta_{MAX}$	τ_{ROLL}	$\dot{\phi}_{SS}$	ϕ_1	ϕ_2	$\frac{F_W}{\delta_W}$	KG SYSTEM	OUTCH ROLL	SPIRAL	
G2													
11	.30	90	.191	.10	1.42	24.4	6.5	21.2	.28	2	.449	.339	2.5
12	.20		.127			16.3	4.4	14.2					
13	.125		.080			10.2	2.8	9.0					
14	.15		.0955		1.14	9.8	3.0	12.0		3	.508	.329	18.3
16		50	.172	.18	1.42	12.2	3.1	10.2		2	.449	.339	2.5
16					1.14	9.8	2.9	11.5		3	.508	.329	18.3
17	.25		.287		1.42	20.4	5.2	17.0		2	.449	.339	2.5
18	.35		.401			28.5	7.2	24.0					
19	.15		.172	.30		12.2	2.7	9.4		2			
19					1.14	9.8	2.5	10.7		3	.508	.329	18.3
20	.25		.287		1.42	20.4	4.6	15.8		2	.449	.339	2.5
21	.35		.401			28.5	6.2	22.0					
22	.30		.344	.18			6.8	24.8			.403	.223	
23	.20		.229				4.4	16.5					
23A	.15		.172				3.4	12.3					
24	.30		.344		1.03	17.7	5.9	18.6			.474	.377	3.8
25	.15		.172			8.9	3.0	9.2					
25A	.20		.229			11.8	3.9	12.3					
26				.10	1.42	16.3	4.4	14.2	.21		.449	.339	2.5
27									.42				
28									.64				

GROUND BASED SIMULATION
LATERAL RUN LOG.

THE BOEING COMPANY
RENTON, WASHINGTON

TABLE
6
DG-15000
PAGE
VIII-112A

GROUND BASED CONF.	GROUND CONF.	L	δ_{WH} EFF.	$L\delta_{WH}$	$t\delta_{MAX}$	τ_{ROLL}	$\dot{\phi}_{SS}$	ϕ_1	ϕ_2	$\frac{F_W}{\delta_W}$	ALG SYST	DUTCH ROLL ω_n	SPIRAL $T_{1/2}$
CALC	CHECK	APR	APR	REVISED	DATE	SEC.	DEG/SEC	DEG	DEG	LB/DIA	2	RAD/SEC	SEC
202A		.25	50	.287	.20	1.14	16.35	5	19.2	.28	3	.508	18.3
205C		.15		.172			9.8	2.9	11.5				
205F		.10		.115			6.54	1.9	7.6				
207A		.15	30	.286			9.8	2.9	11.5				
216			50	.172	.36			2.5	10.8				
219					.60			1.7	9.5				
219A		.10		.115			6.54	1.1	4.9				
224A		.50		.573	.36	.93	26.6	8.0	31.0	.519		.346	23.5
231		.16		.184	.20	1.59	14.6	3.4	14.5	.479		.305	11.7
232A		.26		.298		.72	10.7	4.8	18.2	.529		.367	31.2
233A		.43		.493			17.7	8.0	30.7				
234A		.15		.173			6.19	2.8	10.5				
236		.25		.287	.50	1.14	16.35	4.1	17.9	.508		.329	19.3
237					.75			3.5	16.3				
1202		.30	50	.344	.20	1.14	19.6	5.7	20.1	.19	1	.508	18.3
1202A		.25		.287			16.35	4.8	16.7	.19128			
1203		.40		.458			26.1	7.5	26.8	.28			
1203A		.24	30	.459			15.7	4.6	16.0	.19			
1203A ^B		.15		.478			16.35	4.8	16.7				
1205C		.15	50	.172			9.80	2.8	10.0	.28			
1205D		.25	75	.191			16.35	4.8	16.7	.19			
1205F		.10	50	.115			6.54	1.9	6.6				

GROUND BASED SIMULATION
LATERAL RUN LOG.

THE BOEING COMPANY
RENTON, WASHINGTON

TABLE
6
D6-15000
PAGE
VIII-113

GROUND BASED CONFIG.	L	S _{WH} EFF.	L _{S WH}	t _{S Omax.}	τ _{BOLL}	P _{SS}	φ ₁	φ ₂	F _W / S _W	DUTCH ROLL		SPIRAL
										ω _n	ζ	
G ~	RAD/SEC.	DEG.	1/SEC ²	SEC.	SEC.	DEG/SEC	DEG.	DEG.	LB/DEG	RAD/SEC.	T _{1/2}	φ/β
1206	.10	30	.191	.2	1.14	6.54	1.9	6.6	.28	.508	18.9	1.33
1207A	.15		.286			9.8	2.8	10.0	.19			
1209A		75	.115						.194.28			
1209A	.40		.306			26.2	7.5	26.8	.28			
1222	.30	50	.344	0	1.59	27.4	8.0	27.0		.479	.305	11.7
1223					1.14	19.6	7.5	22.5		.508	.329	18.3
1224					.93	16.0	5.6	20.0		.519	.346	23.5
1230	.15		.172	.2	1.59	13.7	3.1	12.0		.479	.305	11.7
1231	.16		.184			14.6	3.3	12.9				
1232	.28		.321		.72	11.5	4.6	15.1		.529	.367	31.2
1233	.47		.539			19.4	7.8	24.4				
1233B					.60	16.2	7.4	22.8	.194.28	.533	.380	38.2
1234B	.15		.172		.72	6.18	2.5	8.0	.28	.529	.367	31.2
1235	.267		.306		.60	9.2	4.2	13.3	.19	.533	.380	38.2
1236	.25		.287	.5	1.14	16.35	3.5	16.0	.28	.508	.329	18.3
1236B	.43	30	.821	.2	.60	14.8	6.8	21.0	.19	.533	.380	38.2
1237	.25	50	.287	.75	1.14	16.35	3.2	13.0	.28	.508	.329	18.3
1237A				0			5.3	18.5				

CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				

GROUND BASED SIMULATION
LATERAL RUN LOG.

THE BOEING COMPANY
RENTON, WASHINGTON

TABLE

D6-15000

PAGE

VIII-114

ROLL RESPONSE


BASIC AUGMENTATION

$$\delta R / \delta W = -1.75$$

$$\delta W / \psi = -1.0$$

$$\delta R_{MAX} = \pm 20^\circ$$

$$\delta \dot{\alpha} = 225^\circ / \text{SEC} \quad (t_{\delta \dot{\alpha}} = .2 \text{ SEC})$$



CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				

ROLL RESPONSE - WHEEL STEP
GROUND BASED SIMULATOR
AUGMENTATION 1


THE BOEING COMPANY

FIG. 79

D6-15000


PAGE
VIII-115

ROLL RESPONSE




CALC	R. Root	2-2-66	REVISED	DATE	ROLL RESPONSE - WHEEL STEP GROUND BASED SIMULATION AUGMENTATION 2	FIG. 80
CHECK						
APR					THE BOEING COMPANY	D6-15000
APR						PAGE VIII-116

ROLL RESPONSE



CALC	R. Root	2-2-66	REVISED	DATE	ROLL RESPONSE - WHEEL STEP GROUND BASED SIMULATOR AUGMENTATION 3	FIG. 81
CHECK						D6-15000
APR						PAGE
APR						VIII-117
					THE BOEING COMPANY	



CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				

STEP WHEEL RESPONSE
GROUND BASED SIMULATOR
EFFECT OF T_R

THE BOEING COMPANY

FIG. 82

D6-15000

PAGE

VIII-118

STEP AILERON RESPONSE

ϕ
DEG

SYM	CONFIG	T_R
---	G 1222	3 1.59
---	G 1223	3 1.14
---	G 1224	3 .93
AUG. SYSTEM		1

ϕ
DEG

$T_R = 1.59$
 $T_R = 1.14$
 $T_R = .93$

β
DEG

S_R
DEG

t - SEC

CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				


STEP AILERON RESPONSE
GROUND BASED SIMULATOR
EFFECT OF T_R

THE BOEING COMPANY


FIG. 83

D6-15000

PAGE
VIII-119



CALC	R. Root	2-2-66	REVISED	DATE	STEP WHEEL RESPONSE GROUND BASED SIMULATOR CONFIGURATION G16	FIG. 84
CHECK						D6-15000
APR						PAGE
APR						VIII-120
					THE BOEING COMPANY	



CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				

STEP WHEEL RESPONSE
GROUND BASED SIMULATOR
CONFIGURATION G205 C


THE BOEING COMPANY

FIG. 85

D6-15000

PAGE

VIII-121



CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				

STEP WHEEL RESPONSE
GROUND BASED SIMULATOR
CONFIGURATION G1237

THE BOEING COMPANY

FIG. 86

D6-15000

PAGE
VIII-122

1076

IX. DOCUMENTATION OF THE 367-80 WITH BOUNDARY LAYER CONTROL

The longitudinal and lateral characteristics of the 367-80 with Boundary Layer Control (BLC) are documented in Figs. 87 to 96. The dynamic characteristics are included in Tables 1 and 4 (pages ^{VII}59 and ^{VIII}103). A description in terms of aerodynamic coefficients is given in Appendix 1.

The purpose of going to the BLC configuration was to create the large roll control power required for evaluation. It should be noted, however, that this configuration has many characteristics other than roll control power which are different from the basic 1209 and 101A configuration. The 367-80 (BLC) should not be compared directly to the basic (1209) configuration with the intent of isolating the effects of increased roll control power.

Comments on the flight test and theoretical response to the documentation maneuvers performed are listed below.

Longitudinal

Pitch Rate Reversal

Fig. 87. The pitch control sensitivity is accurately predicted by theory

Wind Up Turn

Figs. 88 & 89. Wind up turn data agrees quite well with the theoretical calculation when the data is shifted to allow for mis-trim.


Speed Stability

Fig. 90. A mis-trim in the flight test data is evident when compared to the theory.

Pitch Attitude

Fig. 91. Approximately 3 seconds are required for a pitch attitude change of 9 degrees.

PITCH RATE REVERSAL




AIRPLANE	367-80	-80BLC
FLIGHT TEST	686-12	686-12
FLAP	30°	
V _I ~ KTS	117	117
ALTITUDE	8,100 FT	SEA LEVEL
G. W. ~ LBS	147,400	500,000
C. G.	30.3%	25%

18-C 10:45:XX


CALC			REVISED	DATE	PITCH RATE REVERSAL	367-80
CHECK					FLIGHT TEST 686-12	D6-15000
APR					CONFIGURATION -80BLC	FIG. 87
APR					THE BOEING COMPANY	PAGE
						IX-124

WINDUP TURN



CALC			REVISED	DATE	WINDUP TURN FL. TEST : 686-12 CONFIG. : -80 BLC THE BOEING COMPANY	367-80 D6-15000
CHECK						FIG. 88
APR						PAGE
APR						IX-125

WINDUP TURN



CALC			REVISED	DATE	WINDUP TURN FL. TEST : 686-12 CONFIG. : -80 THE BOEING COMPANY	-80 D6-15000
CHECK						FIG. 89
APR						PAGE
APR						IX-126

SPEED STABILITY

AIRPLANE	367-80	-80B
FL TEST	686-12	686-12
FLAPS	50%	50%
V _L - KTS.	117	117
ALTITUDE	BOOFT SEA LEVEL	
G.W. - LBS.	147000	150000
C.G.	30.3%	30.3%

1816 101714

F_s

~ LBS.

SPEED STABILITY
FL. TEST : 686-12
CONFIG. : -80B

THE BOEING COMPANY


367-80
D6-15000


FIG. 90

PAGE
IX-127

THEORY
TEST POINT

IE 127-2





CALC		REVISED	DATE	PITCH ATTITUDE FLIGHT TEST 686-12 CONFIGURATION -80BLC THE BOEING COMPANY	367-80
CHECK					DG-15000
APR					FIG. 91
APR					PAGE
					IX-128

Lateral

Steady Roll Rate

Fig. 92. The theoretical and flight test data agree for the steady roll rate.

Roll Rate Reversal

Fig. 93. The theoretical roll acceleration matches the flight test data for small wheel deflections but non-linearity in the airplane characteristic causes inaccuracies for wheel deflections greater than about 15° .

Yaw Rate Reversal

Fig. 94. The yaw rate reversal data agrees fairly well with the theoretically calculated line.

Steady Sideslip

Fig. 95. The steady sideslip characteristics of the 367-80 BLC configuration agree with theory.


Spiral Stability

Fig. 96. The theoretical time to half amplitude in the spiral mode is 124 seconds. The flight test time to half amplitude is 16.3 seconds.

Wheel Step

Fig. 96A. The wheel step took approximately .35 seconds to maximum wheel. The sideslip angle was small in the first second and the roll angle after one second was 3.8° .

ROLL RATE REVERSAL



CALC		REVISED	DATE
CHECK			
APR			
APR			

ROLL RATE REVERSAL
FLIGHT TEST 686-13
CONFIGURATION -80 BLC


THE BOEING COMPANY

367-80.
DG-15000

FIG.93

PAGE
IX-131

YAW RATE REVERSAL



CALC			REVISED	DATE
CHECK				
APR				
APR				


YAW RATE REVERSAL
FLIGHT TEST 686-13
CONFIGURATION -80 BLC

THE BOEING COMPANY

367-80
D6-15000
FIG. 94

PAGE
IX-132


STEADY SIDESLIP CHARACTERISTICS



CALC			REVISED	DATE	STEADY SIDESLIP CHARACTERISTICS FLIGHT TEST 686-12 CONFIGURATION -80 BLC	367-80 DG-15800 FIG. 95
CHECK						
APPD.						
APPD.						
					THE BOEING COMPANY	PAGE IX-133

IX-133-

13 ~ DEG



AIRPLANE	BASIC 367-80	367-80	-80 BLC
FLIGHT TEST	659-6	686-12	686-12
FLAP	50°	30°	
ALTITUDE	3,300 FT	8,100 FT	SEA LEVEL
GW. ~ LBS	16,200	143,400	150,000
C.G.	31.5%	30.3%	30
IRIG	17:30:XX	11:06:XX	

TX-133-2


SPIRAL MODE -80BLC

CALC			REVISED	DATE
CHECK				
APR				
APR				

SPIRAL MODE
FLIGHT TEST 686-12
CONFIGURATION -80BLC

THE BOEING COMPANY

367-80
D6-15000
FIG. 96
PAGE
IX-134



AIRPLANE	367-80	-80BLC
FLIGHT TEST	686-12	686-12
FLAP	50°	50°
V ₁ ~ KTS	117	117
ALTITUDE	6,600 FT	SEA LEVEL
G.W. ~ LBS	168,400	150,000
C.G.	30.37%	30%

FLIGHT TEST	16.3
THEORY	12.4

11.03%

WHEEL STEP CHARACTERISTICS

ϕ
~ DEG

10

5

0

$\phi = 20.72^\circ$

AIRPLANE	367-80	-80BLC
FLIGHT TEST	686-13	686-13
FLAP	50°	50°
V _I ~ KTS	117	117
ALTITUDE	7000 FT	SEA LEVEL
G.W. ~ LBS	163,700	150,000
C.G.	30.1%	30%

1216 13/35 XX

β
~ DEG

20

10

0

δ_w
~ DEG

80

40

0

t ~ SEC

CALC			REVISED	DATE
CHECK				
APR				
APR				

WHEEL STEP CHARACTERISTICS
FLIGHT TEST 686-13
CONFIGURATION -80 BLC

THE BOEING COMPANY

367-80
D6-15000
FIG. 96A
PAGE
IX-135


X. INFLIGHT - GROUND-BASED SIMULATOR COMPARISON

Dynamic characteristics of similar configurations evaluated on the ground based and inflight simulators are presented herein. Figs. 97 and 98 present wheel step and wheel pulse response characteristics comparing configurations G1202A (ground based) and 1209 (inflight). These are similar configurations but the numbers are different because of changes in the in-flight simulator parameters after program initiation. Response differences are due to the different initial response characteristics of the in-flight simulation caused by control surface nonlinearities and aerodynamic lags and a somewhat differently shaped roll control input. The pilot was requested to input a step wheel. The control input shown was the result. Response of these configurations to a rudder pulse is shown in Fig. 99.


Longitudinal response characteristics are presented in Fig. 100 for an elevator pulse and Fig. 101 for a column step comparing similar configurations. Fig. 101 compares the dynamic characteristics of configurations G151C and 151B. These configurations have similar stability, elevator lift and control power and slightly different lift curve slope and lift due to pitch rate (C_{L_0}). They have similar dynamic characteristics. The configuration numbers are different because of changes in the in-flight simulator parameters after program initiation. The responses to a column step of three configurations (101A, 151B, and 151C) evaluated on the inflight simulation are shown in Fig. 102. This figure presents the effect of elevator lift on longitudinal response. Fig. 103 presents the longitudinal response of three configurations (G101A, G151B, G151C), evaluated on the ground based simulator showing the effect of elevator lift.

Figs. 104, 105, and 106 compare configurations 101A, 151B, and 151C with G101A, G151B, and G151C as evaluated on the inflight and ground based simulators. Response differences are due to changes in the characteristics as listed in Table 1 and Table 3. Most of the increment in response shown on these curves is due to the difference in elevator lift between the two simulators for a given configuration number.


WHEEL STEP



CALC	R. Root	2-1-66	REVISED	DATE	WHEEL STEP GROUND - FLIGHT COMPARISON CONFIG: G1202A & 1209 THE BOEING COMPANY	D6-15000
CHECK						FIG. 97
APR						PAGE
APR						X-138



CALC	R. Root	2-1-66	REVISED	DATE	CONFIG. G1202A & 1209 WHEEL PULSE DATA COMPARISON THE BOEING COMPANY	D6-15000
CHECK						FIG. 98
APR						PAGE
APR						X-139



CALC	R. Root	2-1-66	REVISED	DATE
CHECK				
APR				
APR				

RUDDER PULSE
 GROUND ~ FLIGHT COMPARISON
 CONFIG. : G1202A & 1209

THE BOEING COMPANY

D6-15000

FIG. 99

PAGE
X-140

ELEVATOR PULSE

ADW
DEG

M ₀	L ₀	SYM.	CONFIGURATION
-.562	.0701	---	FLIGHT DATA (101A)
-.55	.0333	---	GROUND DATA (G101A)
-.562	.0701	---	THEORY (101A)


M₀ = -.506

ADW
DEG


ADW
DEG

t - SEC


CALC	R. Root	2-2-66	REVISED	DATE	ELEVATOR PULSE	D6-15000
CHECK					GROUND-FLIGHT DATA COMPARISON	FIG.100
APR					CONFIG. G101A & 101A	PAGE
APR					THE BOEING COMPANY	X-141




CALC	R. Root	2-2-66	REVISED	DATE	COLUMN STEP GROUND-FLIGHT COMPARISON CONFIG.: G151C & 151B THE BOEING COMPANY	D6-15000
CHECK						FIG. 101
APR						PAGE
APR						X-142



CALC	R. Root	2-9-66	REVISED	DATE	COLUMN STEP FLIGHT DATA COMPARISON CONFIG. 15IC, 15IB & 10IA THE BOEING COMPANY	D6-15000
CHECK						FIG. 102
APR						PAGE X-143
APR						




CALC	R. Root	2-4-66	REVISED	DATE	COLUMN STEP GROUND DATA COMPARISON CONFIG. G101A, G151B & G151C THE BOEING COMPANY	D6-15000
CHECK						FIG. 103
APR						PAGE X-144
APR						



CALC	R. Root	2-2-66	REVISED	DATE	COLUMN STEP GROUND-FLIGHT COMPARISON CONFIG. GIOIA & IOIA THE BOEING COMPANY	D6-15000
CHECK						FIG. 104
APR						
APR						
						PAGE X-145



TD 461 C-R4



CALC	R. Root	2-2-66	REVISED	DATE	COLUMN STEP GROUND-FLIGHT COMPARISON CONFIG. G15IC & 15IC. THE BOEING COMPANY	D6-15000
CHECK						FIG. 106
APR						PAGE
APR						X-147

APPENDIX 1**DESCRIPTION OF THE AMES LARGE TRANSPORT CONFIGURATIONS****A. Airborne Simulator**

A description of the basic Ames large transport configuration is given in Table A1-1 and variations from the basic are shown in Table A1-2.

152

TABLE A1-1

Basic 101A Longitudinal CharacteristicsFlight Condition

V_e	117 Kts
Gross Weight	500,000 lbs.
C. G. Location	25% MAC

Airplane Constants

Wing Area	5500 sq. ft.
Wing Span	215 ft.
MAC	28.75 ft.

Lift Derivatives

$C_{L_{Trim}}$	1.94
$\alpha_{Trim_{wcp}}$	4.7°
$C_{L_{\alpha}}$	6.2 /rad
$C_{L_{\dot{\alpha}}}$	-.537 /rad/sec
$C_{L_{\dot{\theta}}}$	.613 /rad/sec
$C_{L_{\dot{\delta}_e}}$	.835 /rad

Drag Derivatives

$C_{D_{Trim}}$	.45
$C_{D_{\alpha}}$	1.07 /rad

TABLE A1-1 (CONT.)

Pitching Moment Derivatives

$C_{m\alpha}$	-2.07 /rad
$C_{m\dot{\alpha}}$	-.555 /rad/sec
$C_{m\ddot{\alpha}}$	-2.387/rad/sec
$C_{m\delta_E}$	-2.30 /rad
I_y	30.0×10^6 slug-FT ²

Longitudinal Dynamic CharacteristicsShort Period

Damped Natural Frequency	.645 rad/sec
Undamped Natural Frequency	.907 rad/sec
Damping Ratio	.703

Phugoid

Damped Natural Frequency	.170 rad/sec
Undamped Natural Frequency	.172 rad/sec
Damping Ratio	.149

TABLE A1-1 (CONT.)

Basic 1209 Lateral - Directional CharacteristicsSide Force Derivatives

$C_{y\beta}$	-.9773	/rad
$C_{y\dot{\phi}}$	.06	/rad/sec
$C_{y\dot{\psi}}$	.1105	/rad/sec
$C_{y\dot{\beta}}$	-.074	/rad/sec
$C_{y\delta_R}$	.2464	/rad
$C_{y\delta_W}$	-.0366	/rad

Rolling Moment Derivatives

$C_{l\beta}$	-.1955	/rad
$C_{l\dot{\phi}}$	-.2442	/rad/sec
$C_{l\dot{\psi}}$	.1955	/rad/sec
$C_{l\delta_R}$	.00229	/rad
$C_{l\dot{\beta}}$	-.00069	/rad/sec
$C_{l\delta_W}$	.0975	/rad
I_{X_B}	17.5×10^6	slug-FT ²

TABLE A1-1 (CONT.)

Yawing Moment Derivatives

$C_{n\beta}$	.218	/rad
$C_{n\dot{\phi}}$	.0905	/rad/sec
$C_{n\dot{\psi}}$	-.2883	/rad/sec
$C_{n\dot{\beta}}$	.036	/rad/sec
$C_{n\delta_R}$	-.12	/rad
$C_{n\delta_W}$	-.0001	/rad
I_{Z_B}	45.0×10^6	slug-FT ²
$I_{X_Z_B}$	$.95 \times 10^6$	slug-FT ²

Spiral Divergence

Time Constant	26.5	sec
Time to Half Amplitude	18.3	sec

Roll Convergence

Time Constant	1.14	sec
---------------	------	-----

Dutch Roll

Damped Natural Frequency	.479	rad/sec
Undamped Natural Frequency	.508	rad/sec
Damping Ratio	.329	
$\frac{ \phi }{ \beta }$	1.33	

CONFIG.	$C_{m\delta e}$ 1/RAD	$C_{L\delta e}$ 1/RAD	$\delta e/\delta c$	$C_{m\alpha}$ 1/RAD	$C_{L\alpha}$ 1/RAD	$C_{m\dot{\theta}}$ 1/RAD/SEC	$C_{L\dot{\theta}}$ 1/RAD/SEC	$C_{L\delta w}$ 1/RAD	$C_{L\dot{\phi}}$ 1/RAD/SEC	$\delta w_{EFF.}$ DEG
101A	-2.30	.835	-1.5	-2.07	6.2	-2.4	.613			
100	-1.56	.705	-1.5	-2.07	6.2	-2.4	.613			
105A	-2.30	.835	-3.0	-2.07	6.2	-2.4	.613			
105*	-1.56	.705	-4.5	-2.07	6.2	-2.4	.613			
151B	-2.30	.026	-1.5	-2.07	6.2	-2.4	.613			
151C	-2.30	.435	-1.5	-2.07	6.2	-2.4	.613			
151D	-2.30	.026	-3.0	-2.07	6.2	-2.4	.613			
158A	-2.30	.844	-3.0	-4.14	6.57	-4.8	1.17			
159A	-2.30	.844	-1.5	-2.07	6.2	-4.8	1.17			
159B	-2.30	.844	-3.0	-2.07	6.2	-4.8	1.17			
161B	-2.30	.844	-3.0	-.52	5.91	-2.4	.613			
-80BLC	-.917	.297	-2.2	-1.917	5.46	-5.131	0	.180	-3064	
1209								.0975	-2442	50
1203A								.1460	-2442	30
1207A								.0914	-2442	30
1235								.1630	-5100	30
1237								.0914	-2442	50

ENGR.			REVISED	DATE	AIRBORNE SIMULATION AERODYNAMIC CHARACTERISTICS THE BOEING COMPANY RENTON, WASHINGTON	TABLE A1-2
CHECK						D6-15000
APR						
APR						A1-6

A description of Boeing 367-80 with boundary layer control (used as a large transport configuration) is shown in Table A1-3.

TABLE A1-3

367-80 BLC Longitudinal CharacteristicsFlight Condition

V_e	117 Kts
Flap Angle	50°
BPR	4:1
Gross Weight	150,000 lbs.
C. G. Location	30% MAC
Speed Brake Trim Angle	6°

Airplane Constants

Wing Area	2821 sq. ft.
Wing Span	130.8 ft.
MAC	20.1 ft.

Lift Derivatives

$C_{L_{Trim}}$	1.14
$\alpha_{Trim_{wcp}}$	2.3°
$C_{L\alpha}$	4.53 /rad
$C_{L\delta_R}$	.297
$\frac{\partial C_L}{\partial v}$	-.001875 /ft/sec

Drag Derivatives

$C_{D_{Trim}}$	.183
$C_{D\alpha}$	.63 /rad

TABLE A1-3 (CONT.)

Pitching Moment Derivatives

C_{m_v}	-.0012	/ft/sec
C_{m_α}	-1.197	/rad
$C_{m_{\dot{\alpha}}}$	-.1283	/rad/sec
$C_{m_{\dot{\phi}}}$	-.5131	/rad/sec
$C_{m_{\dot{\phi}_R}}$	-.8124	/rad
I_y	2.25×10^6	slug-FT ²

Longitudinal Dynamic CharacteristicsShort Period

Damped Natural Frequency	1.147	rad/sec
Undamped Natural Frequency	1.30	rad/sec
Damping Ratio	.5245	

Phugoid

Damped Natural Frequency	.1342	rad/sec
Undamped Natural Frequency	.1352	rad/sec
Damping Ratio	.1244	

TABLE A1-3 (CONT.)

367-80 BLC Lateral - Directional CharacteristicsSide Force Derivatives

$C_{y\beta}$	-.773	/rad
$C_{y\dot{\phi}}$	.3376	/rad/sec
$C_{y\dot{\psi}}$	.1035	/rad/sec
$C_{y\dot{\beta}}$	-.259	/rad/sec
$C_{y\delta_R}$	.1992	/rad
$C_{y\delta_W}$	-.032	/rad

Rolling Moment Derivatives

$C_{l\beta}$	-.1507	/rad
$C_{l\dot{\phi}}$	-.1951	/rad/sec
$C_{l\dot{\psi}}$	.1407	/rad/sec
$C_{l\dot{\beta}}$	-.0268	/rad/sec
$C_{l\delta_R}$	.0206	/rad
$C_{l\delta_W}$	.180	/rad
I_{x_B}	2.57×10^6	slug-FT ²

Yawing Moment Derivatives

$C_{n\beta}$	.0555	/rad
$C_{n\dot{\phi}}$	-.0207	/rad/sec
$C_{n\dot{\psi}}$	-.0677	/rad/sec
$C_{n\dot{\beta}}$	.0484	/rad/sec
$C_{n\delta_R}$	-.0777	/rad

THE **BOEING**

COMPANY

TABLE A1-3 (CONT.)

Yawing Moment Derivatives (cont'd)

$C_{n\delta_W}$	.0125	/rad
I_{Z_B}	4.73×10^6	slug-ft ²
$I_{X_{Z_B}}$	0	slug-ft ²

367-80 BLC Stability Augmentation System

	<u>Gain</u>	<u>Time Constant</u>
$\frac{\delta_R}{\delta_{WH}}$	0	0
$\frac{\delta_R}{\beta}$	0	0
$\frac{\delta_R}{\beta}$	-1.3	.27 sec
$\frac{\delta_R}{\phi}$	- .5	1.0 sec
$\frac{\delta_A}{\psi}$	- .9	0.1 sec
$\frac{\delta_A}{\beta}$	1.0	0.1 sec
$\frac{\delta_A}{\phi}$	-1.2	0.1 sec

Lateral Dynamic CharacteristicsSpiral Divergence

Time Constant	180.0	sec
Time to Half Amplitude	124.4	sec

Roll Convergence

Time Constant	Non-linear	sec
---------------	------------	-----

102

TABLE A1-3 (CONT.)

Dutch Roll

Damped Natural Frequency	.423	rad/sec
Undamped Natural Frequency	.513	rad/sec
Damping Ratio	.564	
$\frac{ \phi }{ \beta }$	.468	

B. Ground Based Simulation

Following is a description of the aerodynamic and physical characteristics of the configurations evaluated on the ground based simulation.

The following information is included:

- a. Basic configuration description (Table A1-4)
- b. Longitudinal changes (Table A1-5)
- c. Lateral Directional changes (Table A1-6)
- d. Lateral Directional Stability Augmentation System (Table A1-7)
- e. Equivalent coefficients (aerodynamic coefficients equivalent to the basic configuration with augmentation) (Table A1-8).

CONFIGURATION DESCRIPTION AMES LARGE TRANSPORT GROUND BASED SIMULATION

BASIC AERODYNAMIC COEFF.'S

DRAG : $C_{D\text{TRIM}} = .45$
 $C_{D\alpha} = 1.07 \text{ 1/RAD}$

LIFT : $C_{L\text{TRIM}} = 1.94$
 $C_{L\dot{\theta}} = .8043 \text{ SEC/RAD}$
 $C_{L\dot{\alpha}} = -.3959 \text{ SEC/RAD}$
 $C_{L\alpha} \text{ \& } C_{L\delta_e} \text{ VARIED}$

PITCH : $C_{m\dot{\alpha}} = -.555 \text{ SEC/RAD}$
 $C_{m\dot{\omega}} = -.0545 \text{ 1/RAD}$
 $C_{m\alpha}, C_{m\delta_e} \text{ \& } C_{m\dot{\theta}} \text{ VARIED}$

ROLL : $C_{l\beta} = -.395 \text{ 1/RAD.}$
 (UNAug.) $C_{l\dot{e}} = .3045 \text{ SEC/RAD}$
 $C_{l\delta_r} = .00229 \text{ 1/RAD}$
 $C_{l\dot{p}} \text{ \& } C_{l\dot{\omega}} \text{ VARIED}$

YAW
 (UNAug.) $C_{n\beta} = .179 \text{ 1/RAD.}$
 $C_{n\dot{p}} = -.1579 \text{ SEC/RAD}$
 $C_{n\dot{r}} = -.267 \text{ SEC/RAD}$
 $C_{n\delta_a} = .0213 \text{ 1/RAD}$
 $C_{n\delta_r} = -.120 \text{ 1/RAD}$

SIDE FORCE
 (UNAug.) $C_{y\beta} = -.83 \text{ 1/RAD}$
 $C_{y\dot{p}} = .572 \text{ SEC/RAD}$
 $C_{y\dot{r}} = .02995 \text{ SEC/RAD}$
 $C_{y\delta_a} = -.0803 \text{ 1/RAD}$
 $C_{y\delta_r} = .2464 \text{ 1/RAD}$

PHYSICAL CHARACTERISTICS

WEIGHT = 500000 LBS.
 CENTER OF GRAVITY = .25 $\bar{c}$
 WING AREA, S = 5,500 FT^2
 M.A.C., $\bar{c}$ = 28.75 FT.
 SPAN, b = 215.0 FT.
 VELOCITY, V = 117.0 KTS.
 = (197.5 FT/SEC)
 $\alpha_{\text{TRIM}}, \alpha_T$ = 2.7 DEG.
 (SEA LEVEL), q = 46.4 LB/FT^2

$I_{xx} = 17.5 \times 10^6 \text{ SLUG/FT}^2$
 $I_{yy} = 30.0 \times 10^6 \text{ SLUG/FT}^2$
 $I_{zz} = 45.0 \times 10^6 \text{ SLUG/FT}^2$
 $I_{xz} = .95 \times 10^6 \text{ SLUG/FT}^2$

ENGR.	R. Root	2-1-66	REVISED	DATE	CONFIGURATION DESCRIPTION	TABLE A1-4
CHECK						D6-15000
APR						
APR						
					THE BOEING COMPANY RENTON, WASHINGTON	A1-14

GROUND BASED CONFIG.	$C_{L\alpha}$	$C_{m\alpha}$	$C_{m\dot{\theta}}$	$C_{L\delta_e}$	$C_{m\delta_e}$	$\delta e / \delta c_{ol}$
	1/RAD	1/RAD	SEC/RAD	1/RAD	1/RAD	DEG/IN
G ~						
100	6.81	-2.07	-2.39	.409	-1.56	-3.29
100A					-3.12	
100X				.818	-1.56	
101A				.409	-2.25	
102					-1.25	
103					-1.0	
103A						-6.58
105					-1.56	
105A					-2.3	
105*					-1.56	-9.87
105*X				.818		
106		-1.0		.409		-3.29
107		0				
108					-1.0	
109					-2.0	
109A					-1.56	-6.58
110		+1.0				-3.29
111	3.6	-2.07				
112		-3.00				
112A		-4.00				
113		-1.40				
113A		-1.40	-1.21			
115		0	-2.39			
120	6.81	-2.07	-1.00			

CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				

GROUND BASED SIMULATION
LONGITUDINAL RUN LOG

THE BOEING COMPANY

RENTON, WASHINGTON

TABLE

A1-5

D6-15000

PAGE

A1-15

RENTON, WASHINGTON D6-15000

GROUND BASED CONFIG.	CL α	Cm α	Cm $\dot{\alpha}$	CL δe	Cm δe	$\delta e / \delta_{COL}$
	1/RAD	1/RAD	SEC/RAD	1/RAD	1/RAD	DEG/IN
G-						
156	6.81	-4.00	-2.39	.409	-3.12	-3.29
157			-4.80		-1.56	
157A			-2.39			
158			-4.80			-6.58
158A			-4.80		-2.3	
158A*			-2.39		-1.56	
158X			-2.39		-2.30	
159		-2.07	-4.80		-1.56	
159A					-2.30	-2.78
159B					-2.30	-6.58
160		-6.00			-1.56	
161		-.50	-2.39		-1.56	
161B		-.50			-2.30	
162		-.20			-1.56	
163	11.00	-4.00				
163A	11.00	-4.00				-3.29

CALC

CHECK

APR

APR

R. Root

2-2-66

REVISED

DATE

GROUND BASED SIMULATION

LONGITUDINAL RUN LOG

THE BOEING COMPANY

RENTON, WASHINGTON D6-15000

TABLE

A1-5

PAGE

A1-17

AD 1040C-R3

CA. C	CHECK	APR	APR	R. Root	2-2-66	REVISED	DATE	GROUND BASED CONFIG	$Cl_{\delta W}$		δW_{EFF}		Cl_P	Aug.
									$1/RAD$	$1/RAD$	DEG	SEC/RAD		
								G~	.073		50	-.239		
								1					2	
								1h					3	
								1h					2	
								2	.110					
								3	.146					
								4	.183					
								5	.219					
								5A	.293					
								5B	.365					
								5C	.054					
								5C	.054				3	
								5D	.046				2	
								5E	.330					
								5F	.037					
								5G	.018				3	
								5H	.010		90			
								5J	.030		30			
								6	.091				2	
								6	.091				3	
								7A	.061				2	
								8	.073		75		2	
								8A	.037				3	
								9	.098				2	
								10	.082		90		2	

GROUND BASED SIMULATION
LATERAL RUN LOG

THE BOEING COMPANY

RENTON, WASHINGTON DG-15000

TABLE
A1-6PAGE
A1-18

PAGE
A1-19

CALC	CHECK	APR	APR	GROUND BASED CONFIG	$C_{L\delta W}$		δW_{EFF}		C_{Lp}		AUG	
					1/RAD	DEG	SEC/RAD	DEG	SEC/RAD	DEG	SEC/RAD	DEG
				G~								
				202A	.091	50	-239	3				
				205C	.055							
				205F	.036							
				207A	.091	30						
				216	.055	50						
				219	.055							
				219A	.036							
				224A	.183		-306					
				231	.059		-153					
				232A	.095		-411					
				233A	.158							
				234A	.055							
				236	.091		-239					
				237	.091		-239					
				1202	.109	50	-239	1				
				1202A	.091							
				1203	.146							
				1203A	.147	30						
				1203A*	.155	30						
				1205C	.055	50						
				1205D	.061	75						
				1205F	.036	50						

GROUND BASED SIMULATION
LATERAL RUN LOG

THE BOEING COMPANY

RENTON, WASHINGTON

D6-15000

TABLE

A1-6

PAGE

A1-20

172

LATERAL DIRECTIONAL STABILITY AUGMENTATION SYSTEM

BASIC SYSTEM

RUDDER : $\delta_r = \left[\frac{\delta_r}{\dot{\beta}} \right] \dot{\beta} + \left[\frac{\delta_r}{\dot{\phi}} \right] \dot{\phi} + \left[\frac{\delta_r}{\delta_w} \right] \delta_w$

WHEEL : $\delta_w = \left[\frac{\delta_w}{\beta} \right] \beta + \left[\frac{\delta_w}{\dot{\psi}} \right] \dot{\psi}$

WHERE : $\dot{\beta} = \left[\frac{\partial}{\partial \psi} \right] \dot{\phi} - \dot{\psi} = .163 \dot{\phi} - \dot{\psi}$

BASIC GAINS

$$\left[\frac{\delta_r}{\dot{\beta}} \right] = - .3$$

$$\left[\frac{\delta_r}{\dot{\phi}} \right] = - 2.07$$

$$\left[\frac{\delta_w}{\beta} \right] = 1.83$$

AUG. SYSTEM 1

$$\left[\frac{\delta_r}{\delta_w} \right] = .178$$

$$\left[\frac{\delta_w}{\dot{\psi}} \right] = -1.00$$

$$[\delta_{r_{MAX}}] = \pm 20^\circ$$

AUG. SYSTEM 2

$$\left[\frac{\delta_r}{\delta_w} \right] = 0$$

$$\left[\frac{\delta_w}{\dot{\psi}} \right] = -2.82$$

$$[\delta_{r_{MAX}}] = \pm 50^\circ$$

AUG. SYSTEM 3

$$\left[\frac{\delta_r}{\delta_w} \right] = 0$$

$$\left[\frac{\delta_w}{\dot{\psi}} \right] = -1.0$$

$$[\delta_{r_{MAX}}] = \pm 50^\circ$$

ENGR.	R. Root	2-1-66	REVISED	DATE	LATERAL DIRECTIONAL STABILITY AUGMENTATION SYSTEM	TABLE AI-7
CHECK						D6-15000
APR						AI-22
APR					THE BOEING COMPANY RENTON WASHINGTON	

EQUIVALENT LATERAL - DIRECTIONAL AERODYNAMIC COEFFICIENTS

YAWING MOMENT

$$\begin{aligned}
 C_{n\dot{\beta}} &= C_{n\dot{\beta} \text{ BASIC}} + C_{n\delta_r} \left(\frac{\delta r}{\beta} \right) &= .036 \text{ SEC./RAD} \\
 C_{n\dot{\phi}} &= C_{n\dot{\phi} \text{ BASIC}} + C_{n\delta_r} \left(\frac{\delta r}{\dot{\phi}} \right) &= .0905 \text{ SEC./RAD} \\
 C_{n\beta} &= C_{n\beta \text{ BASIC}} + C_{n\delta_w} \left(\frac{\delta w}{\beta} \right) &= .218 \text{ 1/RAD} \\
 C_{n\dot{\psi}} &= C_{n\dot{\psi} \text{ BASIC}} + C_{n\delta_w} \left(\frac{\delta w}{\dot{\psi}} \right) &= -.267 + .0213 \left(\frac{\delta w}{\dot{\psi}} \right) \text{ SEC/RAD} \\
 C_{n\delta_w} &= C_{n\delta_w \text{ BASIC}} + C_{n\delta_r} \left(\frac{\delta r}{\delta w} \right) &= .0213 - .12 \left(\frac{\delta r}{\delta w} \right) \text{ 1/RAD}
 \end{aligned}$$

ROLLING MOMENT

$$\begin{aligned}
 C_{l\dot{\beta}} &= C_{l\dot{\beta} \text{ BASIC}} + C_{l\delta_r} \left(\frac{\delta r}{\beta} \right) &= -.00069 \text{ SEC/RAD} \\
 C_{l\dot{\phi}} &= C_{l\dot{\phi} \text{ BASIC}} + C_{l\delta_r} \left(\frac{\delta r}{\dot{\phi}} \right) &= C_{l\dot{\phi}} + .00229 \left(\frac{\delta r}{\dot{\phi}} \right) \text{ SEC/RAD} \\
 C_{l\beta} &= C_{l\beta \text{ BASIC}} + C_{l\delta_w \text{ BASIC}} \left(\frac{\delta w}{\beta} \right) &= -1955 \\
 C_{l\dot{\psi}} &= C_{l\dot{\psi} \text{ BASIC}} + C_{l\delta_w \text{ BASIC}} \left(\frac{\delta w}{\dot{\psi}} \right) &= .3045 + .109 \left(\frac{\delta w}{\dot{\psi}} \right) \text{ SEC/RAD} \\
 C_{l\delta_w} &= C_{l\delta_w \text{ BASIC}} + C_{l\delta_r} \left(\frac{\delta r}{\delta w} \right) &= C_{l\delta_w} + .00229 \left(\frac{\delta r}{\delta w} \right) \text{ 1/RAD}
 \end{aligned}$$

SIDE FORCE

$$\begin{aligned}
 C_{y\dot{\beta}} &= C_{y\dot{\beta} \text{ BASIC}} + C_{y\delta_r} \left(\frac{\delta r}{\beta} \right) &= -.074 \text{ SEC/RAD} \\
 C_{y\dot{\phi}} &= C_{y\dot{\phi} \text{ BASIC}} + C_{y\delta_r} \left(\frac{\delta r}{\dot{\phi}} \right) &= .060 \text{ SEC/RAD} \\
 C_{y\beta} &= C_{y\beta \text{ BASIC}} + C_{y\delta_w} \left(\frac{\delta w}{\beta} \right) &= -.9773 \text{ 1/RAD} \\
 C_{y\dot{\psi}} &= C_{y\dot{\psi} \text{ BASIC}} + C_{y\delta_w} \left(\frac{\delta w}{\dot{\psi}} \right) &= .02995 - .0805 \left(\frac{\delta w}{\dot{\psi}} \right) \text{ SEC/RAD} \\
 C_{y\delta_w} &= C_{y\delta_w \text{ BASIC}} + C_{y\delta_r} \left(\frac{\delta r}{\delta w} \right) &= -.0805 + .2464 \left(\frac{\delta r}{\delta w} \right) \text{ 1/RAD}
 \end{aligned}$$

ENGR.	R. Root	2-1-66	REVISED	DATE	EQUIVALENT LATERAL - -DIRECTIONAL AERODYNAMIC COEFFICIENTS.	TABLE A1-B
CHECK						D6-15000
APR						
APR						
					THE BOEING COMPANY RENTON, WASHINGTON	A1-23

APPENDIX 2

BASIC 367-80 DESCRIPTION

The aerodynamic characteristics of the unaugmented 367-80 inflight simulator are described in Table A2-1 and in Figures A2-1 thru A2-5. Characteristics presented are those used in the control command equations presented in Ref. 1. These equations are used to determine the control gains necessary to augment the aerodynamic characteristics of the 367-80 to the proposed Ames large transport configurations.

Figure A2-1 shows the pitching moment characteristics of the spoilers. The calibration of the inboard to outboard spoilers is presented in Figure A2-2. The lift and drag characteristics of the speed brakes are presented in Figures A2-3 and A2-4. The pitching moment characteristics of the thrust reversers are shown in Figure A2-5.

Several parameters varied during the test flights due to fuel consumption. The center of gravity of the 367-80 airplane varied from 29-31%. The weight varied from approximately 172,000 lbs at take-off to 137,000 at touchdown. The lateral directional moments of inertia vary ± 15 percent from the values shown in Table A2-1. The pitch moment of inertia varies ± 3.3 percent from those presented in Table A2-1.

TABLE A2-1

367-80 Longitudinal CharacteristicsFlight Condition

V_e	117 Kts
Flap Angle	30°
BPR	1
Gross Weight	150,000 lbs.
C. G. Location	30% MAC
Speed Brake Trim Angle	6°

Airplane Constants

Wing Area	2821 sq. ft.
Wing Span	130.8 ft.
MAC	20.1 ft.

Lift Derivatives

$C_{L_{Trim}}$	1.146
$\alpha_{Trim_{wcp}}$	8.5°
$C_{L \alpha}$	5.45 /rad
$C_{L \delta_E}$	.52 /rad

Drag Derivatives

$C_{D_{Trim}}$	.139
$C_{D \alpha}$	.544 /rad

TABLE A2-1 (CONT.)

Pitching Moment Derivatives

$C_{m\alpha}$	-1.11	/rad
$C_{m\dot{\alpha}}$	-.272	/rad/sec
$C_{m\dot{\theta}}$	-.710	/rad/sec
$C_{m\delta_E}$	-.975	/rad
I_y	2.25×10^6	slug-FT ²

Speed Brakes

$C_{L\delta_{SB}}$	1.11	/rad
$C_{m\delta_{SB}}$	See Fig.	/rad

Longitudinal Dynamic CharacteristicsShort Period

Damped Natural Frequency	1.04	rad/sec
Undamped Natural Frequency	1.42	rad/sec
Damping Ratio	.68	

Phugoid

Damped Natural Frequency	.157	rad/sec
Undamped Natural Frequency	.157	rad/sec
Damping Ratio	.0906	

TABLE A2-1 (CONT.)

367-80 Lateral - Directional CharacteristicsSide Force Derivatives

$C_{y\beta}$	-.838	/rad
$C_{y\dot{\phi}}$	.270	/rad/sec
$C_{y\dot{\psi}}$	.0727	/rad/sec
$C_{y\dot{\epsilon}}$	0	/rad
C_{yS_R}	.211	/rad
$C_{yS_{WH}}$	-.0252	/rad

Rolling Moment Derivatives

$C_{l\epsilon}$	-.1743	/rad
$C_{l\dot{\phi}}$	-.120	/rad/sec
$C_{l\dot{\psi}}$	.104	/rad/sec
$C_{l\dot{\epsilon}}$	0	/rad
C_{lS_R}	.0149	/rad
$C_{lS_{WH}}$	.06	/rad
I_{X_B}	2.57×10^6	slug-FT ²

Yawing Moment Derivatives

$C_{n\beta}$	.0909	/rad
$C_{n\dot{\phi}}$	-.0179	/rad/sec
$C_{n\dot{\psi}}$	-.1071	/rad/sec

TABLE A2-1 (CONT.)

Yawing Moment Derivatives (cont'd)

$C_{n\dot{\epsilon}}$	-.0747	/rad
$C_{n\delta_R}$	-.0749	/rad
$C_{n\delta_{WH}}$	.0030	/rad
I_{Z_B}	4.73×10^6	slug-FT ²
$I_{X_{Z_B}}$	$.156 \times 10^6$	slug-FT ²

Lateral Dynamic CharacteristicsSpiral Divergence

Time Constant	15.7	sec
Time to Half Amplitude	10.87	sec

Roll Convergence

Time Constant	1.04	sec
---------------	------	-----

Dutch Roll

Damped Natural Frequency	.77	rad/sec
Undamped Natural Frequency	.77	rad/sec
Damping Ratio	.018	
	1.584	


FLAPS 30°
 BRP 10
 S.W. 144,000 LBS
 C.G. 29.0 %
 TEST NO. 675-3,675-1

$\alpha_{WCP} = 6.3^\circ$
 $V_C = 120 \text{ KTS}$

○ FROM CONSTANT ANGLE OF ATTACK TEST
 △ " " AIRSPEED TEST

NOTE:

- 1.) α AND V CHANGES CORRECTED
- 2.) THIS CURVE REPLACES FIGURES 5 AND 6 OF AERO COORD. SHEET # 170



$S_{E \text{ OUTSIDE}} - \text{DEG}$

CALC	P.S.	11/65	REVISED	DATE
CHECK				
APR				
APR				

PITCHING MOMENT CHARACTERISTICS OF SPOILERS.

THE BOEING COMPANY D6-15000

387-80

FIG. A2-1

PAGE
A2-6

δ_{SB}^{AVG}
INBOARD
~ DEG

-12

-10

-8

-6

-4

-2

0

0

-2

-4

-6

-8

-10


-12

-14


δ_{SB}^{AVG} OUTBOARD
~ DEG

TEST 675-2, -3

②⑤⑥④③ - OUTB'D SPOILERS
④③⑤⑥④③ - INB'D SPOILERS




CALC	W.M.E.	11-1-65	REVISED	DATE	SPEED BRAKE OPERATION CALIBRATION TESTS	367-80
CHECK						FIG. A2-2
APR						PAGE
APR						A2-7
					THE BOEING COMPANY	DG-15000



TEST 675-2,-3

CAIC	W.M.E.	10-29-65	REVISED	DATE	SPEED BRAKE CHARACTERISTICS LIFT	367-80
CHECK						
APR						FIG. A2-3
APR						
					THE BOEING COMPANY D6-15000	PAGE A2-8

$C_{L\text{TRIM}} = 1.14$
 $\alpha_{WCP} = 9.2^\circ$
 $\delta_{SB\text{TRIM}} = 6^\circ \text{ OUTBOARD}$
 SPEED BRAKES 5A+6A UP
 FLAPS 30° BPR 1



TEST 675-2, -3

CALC	W. M. E.	10-29-65	REVISED	DATE	SPEED BRAKE CHARACTERISTICS DRAG	367-80
CHECK						
APR						FIG. AR-4
APR						
THE BOEING COMPANY					06-15000	PAGE A2-9

ELEVATOR TO TRIM, DEG.

10
8
6
4
2
0
-2
-4
-6
-8
-10


○ DYNAMIC DATA
BPR 1 FLAPS 30°
△ STATIC DATA
BPR 4 FLAPS 50°
□ STATIC DATA
BPR 1 FLAPS 30°
SOLID POINTS FROM
AERO # 96.

20 25 30 35 40 45 50
CLAMSHELL DOOR POSITION ~ DEG.

CALC			REVISED	DATE	FLIGHT TEST DATA THRUST REVERSER PITCH. M. THE BOEING COMPANY D6-15000	767-80
CHECK						FIG. A2-5
APR						PAGE
APR						A2-10

APPENDIX 3

Typical control system force characteristics for the ground based and airborne simulations are presented in Fig. A3-1, for column, wheel, and rudder pedals. Wheel and Column forces were varied on the ground based simulation during the evaluations. These variations are listed in Tables 3 and 6 of section VII and VIII. Forces were kept constant on the airborne simulation. The pilots had the capability of varying column force characteristics in flight, but little variation was noted.



CALC	R. Root	2-2-66	REVISED	DATE
CHECK				
APR				
APR				

CONTROL SYSTEM FORCE CHARACTERISTICS

THE BOEING COMPANY

FIG. A3-1

D6-15000

PAGE A3-2

APPENDIX 4

Derivation of Theory

The theoretical characteristics presented for the control pulses and steps were obtained from 6-degree-of-freedom digital computer programs. The theoretical equations involved can be found in Reference 2.

The theoretical characteristics of the documentation maneuvers performed other than the pulses and steps are derived on the following pages.

APPENDIX 4

THEORETICAL CALCULATIONS

Speed Stability

$$C_L = C_{L_0} + C_{L_\alpha} \Delta \alpha + C_{L_{\dot{\alpha}}} \dot{\alpha} + C_{L_{\ddot{\alpha}}} \ddot{\alpha} + C_{L_V} \Delta V + C_L \delta_E \quad (1)$$

and

$$C_M = C_{M_0} + C_{M_\alpha} \Delta \alpha + C_{M_{\dot{\alpha}}} \dot{\alpha} + C_{M_{\ddot{\alpha}}} \ddot{\alpha} + C_{M_V} \Delta V + C_M \delta_E \quad (2)$$

For the steady state case $\dot{\alpha} = \ddot{\alpha} = 0$ and equations (1) and (2) become

$$C_L = C_{L_0} + C_{L_\alpha} \Delta \alpha + C_{L_V} \Delta V + C_L \delta_E \quad (3)$$

and

$$C_M = C_{M_0} + C_{M_\alpha} \Delta \alpha + C_{M_V} \Delta V + C_M \delta_E \quad (4)$$

Differentiating equation (3)

$$\frac{d C_L}{d V} = C_{L_\alpha} \frac{d \Delta \alpha}{d V} + C_{L_V} + C_L \delta_E \frac{d \delta_E}{d V} \quad (5)$$

Rearranging terms in equation (5) gives

$$\frac{d \Delta \alpha}{d V} = \frac{1}{C_{L_\alpha}} \left[\frac{d C_L}{d V} - C_{L_V} - C_L \delta_E \frac{d \delta_E}{d V} \right] \quad (6)$$

Differentiating equation (4)

$$0 = C_{M_\alpha} \frac{d \Delta \alpha}{d V} + C_{M_V} + C_M \delta_E \frac{d \delta_E}{d V} \quad (7)$$

Substituting equation (6) into equation (7) gives

$$0 = \frac{C_{M_\alpha}}{C_{L_\alpha}} \left[\frac{d C_L}{d V} - C_{L_V} - C_L \delta_E \frac{d \delta_E}{d V} \right] + C_{M_V} + C_M \delta_E \frac{d \delta_E}{d V} \quad (8)$$

Solving for $\frac{d \delta_E}{d V}$ in equation (8)

$$\frac{d \delta_E}{d V} = \frac{C_{M_\alpha} C_{L_V} - C_{M_\alpha} \frac{d C_L}{d V} - C_{M_V} C_{L_\alpha}}{C_{L_\alpha} C_M \delta_E - C_{M_\alpha} C_L \delta_E} \quad (9)$$

Speed Stability

The lift equation is

$$L_0 = \frac{1}{2} \rho V^2 S C_{L_0} \quad (10)$$

Differentiating equation (10)

$$0 = \frac{1}{2} \rho S (C_{L_0} 2V dV + V^2 dC_L).$$

Solving this for dC_L gives

$$\frac{dC_L}{dV} = -\frac{2C_{L_0}}{V} \quad (11)$$

Substituting equation (11) into equation (9)

$$\frac{d\delta_E}{dV} = \frac{C_{M_\alpha} C_{L_V} + C_{M_\alpha} \frac{2C_{L_0}}{V} - C_{M_V} C_{L_\alpha}}{C_{L_\alpha} C_{M\delta_E} - C_{M_\alpha} C_{L\delta_E}} \quad (12)$$

Substituting equation (11) into equation (6) gives

$$\frac{d\alpha}{dV} = \frac{1}{C_{L_\alpha}} \left[\frac{-2C_{L_0}}{V} - C_{L_V} - C_{L\delta_E} \frac{d\delta_E}{dV} \right] \quad (13)$$

Integrating equation (12) yields

$$\delta_E = \int_{V_0}^V \frac{d\delta_E}{dV} dV = \frac{C_{M_\alpha} C_{L_V} - C_{M_V} C_{L_\alpha}}{C_{L_\alpha} C_{M\delta_E} - C_{M_\alpha} C_{L\delta_E}} \int_{V_0}^V \frac{dV}{V} + \frac{C_{M_\alpha} \frac{2C_{L_0}}{V} - C_{M_V} C_{L_\alpha}}{C_{M\delta_E} C_{L_\alpha} - C_{M_\alpha} C_{L\delta_E}} \int_{V_0}^V \frac{dV}{V}$$

$$\delta_E = + \frac{2C_{L_0} C_{M_\alpha}}{C_{M\delta_E} C_{L_\alpha} - C_{M_\alpha} C_{L\delta_E}} \ln \frac{V}{V_0} - \frac{C_{M_V} C_{L_\alpha} - C_{L_V} C_{M_\alpha}}{C_{M\delta_E} C_{L_\alpha} - C_{M_\alpha} C_{L\delta_E}} (V - V_0) \quad (14)$$

$$\delta_{COL} = \left(\frac{1}{\delta_E / \delta_{COL}} \right) \delta_E$$

$$F_S = \left(\frac{F_S}{COL} \right) \delta_{COL}$$

Speed Stability

Integrating equation (13) yields

$$\alpha = \int \frac{d\alpha}{dv} dv = - \frac{1}{C_{L\alpha}} \left[\int_{v_0}^v \frac{2 C_{L_0}}{v} dv + \int_{v_0}^v C_{L_V} dv + \int_{v_0}^v C_{L\delta_E} \frac{d\delta_E}{dv} dv \right]$$

$$= - \frac{2 C_{L_0}}{C_{L\alpha}} \ln v/v_0 - \frac{C_{L_V}}{C_{L\alpha}} (v - v_0) - C_{L\delta_E} \delta_E$$

THEORETICAL CALCULATIONS

Wind Up Turn

$$C_L = C_{L_0} + C_{L_\alpha} \alpha + C_{L_{\dot{\theta}}} \dot{\theta} + C_{L_{\dot{\alpha}}} \dot{\alpha} + C_{L_V} V + C_{L_{\delta_E}} \delta_E \quad (1)$$

and

$$C_m = C_{m_0} + C_{m_\alpha} \alpha + C_{m_{\dot{\theta}}} \dot{\theta} + C_{m_{\dot{\alpha}}} \dot{\alpha} + C_{m_V} V + C_{m_{\delta_E}} \delta_E \quad (2)$$

The increments from trim are

$$\Delta C_L = C_L - C_{L_0} = (n-1)C_{L_0} \quad (3)$$

and

$$\Delta C_m = C_m - C_{m_0} = 0.$$

For the steady state case $V = \text{constant}$ and $\dot{\alpha} = 0$. Solving for the steady state $\Delta \delta_E$ in equation (2) gives

$$\Delta \delta_E = - \frac{C_{m_\alpha} \Delta \alpha + C_{m_{\dot{\theta}}} \dot{\theta}}{C_{m_{\delta_E}}} \quad (4)$$

and solving for $\Delta \alpha$ in equation (1) gives

$$\Delta \alpha = \frac{C_L - C_{L_0} - C_{L_{\dot{\theta}}} \dot{\theta} - C_{L_{\delta_E}} \Delta \delta_E}{C_{L_\alpha}} \quad (5)$$

Substituting equation (3) into equation (5)

$$\Delta \alpha = \frac{(n-1)C_{L_0} - C_{L_{\dot{\theta}}} \dot{\theta} - C_{L_{\delta_E}} \Delta \delta_E}{C_{L_\alpha}} \quad (6)$$

Equations (4) and (6) can be combined with $\dot{\theta} = \frac{(n^2 - 1)}{n} g/v$ (chapter 9, page 301, Reference 2) for a wind up turn to give

$$\frac{\Delta \delta_E}{(n-1)} = \frac{-C_{m_\alpha} C_{L_0} + \frac{(1+n)}{n} (C_{L_{\dot{\theta}}} C_{m_\alpha} - C_{L_\alpha} C_{m_{\dot{\theta}}}) g/v}{C_{m_{\delta_E}} C_{L_\alpha} - C_{L_{\delta_E}} C_{m_\alpha}} \quad (7)$$

$$\frac{\Delta \delta_c}{(n-1)} = \frac{\Delta \delta_E}{(n-1)} \cdot \frac{(\delta_c)}{(\delta_E)} \quad (8)$$

Wind Up Turn

From Equation 6

$$\frac{\Delta \alpha}{(n-1)} = \frac{C_{L_0} - C_{L_0} \frac{(n+1)}{n} \frac{g}{v} - C_{L_0} \delta_E \frac{\delta_E}{(n-1)}}{C_{L_\alpha}}$$

or

$$\frac{(n-1)}{\Delta \alpha} = \frac{C_L}{C_{L_0} - C_{L_0} \frac{(n+1)}{n} \frac{g}{v} - C_{L_0} \delta_E \frac{\delta_E}{(n-1)}}$$

THEORETICAL CALCULATIONS

Steady Sideslip

The yawing moment equation is

$$C_n = C_{n_0} + C_{n_\beta} \beta + C_{n_{\dot{\beta}}} \dot{\beta} + C_{n_{\dot{\psi}}} \dot{\psi} + C_{n_{\dot{\phi}}} \dot{\phi} + C_{n_{\delta_R}} \delta_R + C_{n_{\delta_{WH}}} \delta_{WH} \quad (1)$$

The side force equation is

$$C_y = C_{y_0} + C_{y_\beta} \beta + C_{y_{\dot{\beta}}} \dot{\beta} + C_{y_{\dot{\psi}}} \dot{\psi} + C_{y_{\dot{\phi}}} \dot{\phi} + C_{y_{\delta_{WH}}} \delta_{WH} + C_{y_{\delta_R}} \delta_R + C_{y_{\dot{\psi}}} \dot{\psi} \quad (2)$$

The rolling moment equation is

$$C_l = C_{l_0} + C_{l_\beta} \beta + C_{l_{\dot{\beta}}} \dot{\beta} + C_{l_{\dot{\psi}}} \dot{\psi} + C_{l_{\dot{\phi}}} \dot{\phi} + C_{l_{\delta_{WH}}} \delta_{WH} + C_{l_{\delta_R}} \delta_R \quad (3)$$

For the steady state case equation (1), (2) and (3) become

$$0 = C_{n_\beta} \beta + C_{n_{\delta_R}} \delta_R + C_{n_{\delta_{WH}}} \delta_{WH}, \quad (4)$$

and

$$0 = C_{y_\beta} \beta + C_{y_{\delta_R}} \delta_R + C_{y_{\dot{\phi}}} \dot{\phi} + \cancel{C_{y_{\delta_{WH}}} \delta_{WH}}^{\text{negligible}} \quad (5)$$

$$0 = C_{l_\beta} \beta + C_{l_{\delta_{WH}}} \delta_{WH} + C_{l_{\delta_R}} \delta_R \quad (6)$$

Combining equations (4) and (6) yields

$$\frac{\delta_R}{\beta} = \frac{-C_{n_\beta} C_{l_{\delta_{WH}}} + C_{l_\beta} C_{n_{\delta_{WH}}}}{C_{n_{\delta_R}} C_{l_{\delta_{WH}}} - C_{n_{\delta_{WH}}} C_{l_{\delta_R}}}$$

and

$$\frac{\delta_{WH}}{\beta} = \frac{-C_{n_{\delta_R}} C_{l_\beta} + C_{n_\beta} C_{l_{\delta_R}}}{C_{n_{\delta_R}} C_{l_{\delta_{WH}}} - C_{n_{\delta_{WH}}} C_{l_{\delta_R}}}$$

also

$$\frac{\delta_P}{\beta} = \frac{\delta_R}{\beta} \frac{\delta_P}{\delta_R}$$

Steady Sideslip

From equation (2)

$$\frac{\phi}{\beta} = -\frac{1}{C_{Y\phi}} \left[C_{Y\beta} + C_{Y\delta_R} \frac{\delta_R}{\beta} \right] \quad (6)$$

Substituting $C_L = C_{Y\phi}$ in equation (6)

$$\frac{\phi}{\beta} = -\frac{1}{C_L} \left[C_{Y\beta} + C_{Y\delta_R} \frac{\delta_R}{\beta} \right]$$

THEORETICAL CALCULATION

Steady Roll Rate

The rolling moment equation is

$$C_L = \frac{I_{xx}}{qsb} \ddot{\phi} = C_{L\beta} \beta + C_{L\dot{\beta}} \dot{\beta} + C_{L\ddot{\phi}} \ddot{\phi} + C_{L\dot{\psi}} \dot{\psi} + C_{L\delta_{WH}} \delta_{WH} + C_{L\delta_R} \delta_R \quad (1)$$

For a steady state roll rate $\ddot{\phi} = 0$, so equation (1) becomes

$$0 = C_{L\beta} \beta + C_{L\dot{\beta}} \dot{\beta} + C_{L\ddot{\phi}} \ddot{\phi} + C_{L\dot{\psi}} \dot{\psi} + C_{L\delta_{WH}} \delta_{WH} + C_{L\delta_R} \delta_R \quad (2)$$

If the flight test maneuver to determine steady roll rate is performed correctly then $\delta_R = \beta = \dot{\psi} = \dot{\beta} = 0$. The flight test data was adjusted to fit these conditions so

$$0 = C_{L\ddot{\phi}} \ddot{\phi}_{SS} + C_{L\delta_{WH}} \delta_{WH}$$

$$\frac{\ddot{\phi}_{SS}}{\delta_{WH}} = \frac{C_{L\delta_{WH}}}{C_{L\ddot{\phi}}}$$

THEORETICAL CALCULATION

Roll Acceleration

The rolling moment equation is

$$C_L = \frac{I_{xx}}{qsb} \ddot{\phi} = C_{L\beta} \beta + C_{L\dot{\beta}} \dot{\beta} + C_{L\dot{\phi}} \dot{\phi} + C_{L\psi} \psi + C_{L\delta_{WH}} \delta_{WH} + C_{L\delta_R} \delta_R \quad (1)$$

The roll rate reversal data was measured at a point where $\phi = \dot{\psi} = \beta = \delta_R = \dot{\beta} = 0$
so equation (1) becomes

$$\frac{I_{xx}}{qsb} \ddot{\phi} = C_{L\delta_{WH}} \delta_{WH}$$

solving for $\ddot{\phi} / \delta_{WH}$

$$\frac{\ddot{\phi}}{\delta_{WH}} = C_{L\delta_{WH}} \frac{qsb}{I_{xx}}$$

THEORETICAL CALCULATIONS**Yaw Acceleration**

The yawing moment equation is

$$C_n = \frac{I_{zz}}{qsb} \ddot{\psi} = C_{n\beta} \beta + C_{n\dot{\beta}} \dot{\beta} + C_{n\dot{\psi}} \dot{\psi} + C_{n\dot{\phi}} \dot{\phi} + C_{n\delta_R} \delta_R + C_{n\delta_{WH}} \delta_{WH} \quad (1)$$

The roll rate reversal data was measured at a point where $\beta = \dot{\beta} = \dot{\psi} = \dot{\phi} \cdot \delta_{WH} = 0$
so equation (1) becomes

$$\frac{I_{zz}}{qsb} \ddot{\psi} = C_{n\delta_R} \delta_R$$

solving for $\ddot{\psi} / \delta_R$

$$\ddot{\psi} / \delta_R = C_{n\delta_R} \frac{qsb}{I_{zz}}$$

Multiplying equation (2) by the pedal to rudder gearing gives

$$\ddot{\psi} / \delta_P = C_{n\delta_R} \frac{qsb}{I_{zz}} \left(\frac{\delta_R}{\delta_P} \right)$$

THEORETICAL CALCULATIONS

Pitch Acceleration

The pitching moment equation is

$$C_M = \frac{I_{yy}}{qsc} \ddot{\theta} = C_{M_\alpha} \Delta\alpha + C_{M_{\dot{\theta}}} \dot{\theta} + C_{M_{\ddot{\theta}}} \ddot{\theta} + C_{M_{\dot{U}}} \dot{U} + C_{M_{\ddot{U}}} \ddot{U} + C_{M_{\delta_E}} \delta_E \quad (1)$$

The pitch acceleration was measured at a point where $\Delta\alpha = \dot{\theta} = \ddot{\theta} = dU = 0$

so equation (1) becomes

$$\frac{\ddot{\theta}}{\delta_E} = C_{M_{\delta_E}} \frac{qsc}{I_{yy}} \quad (2)$$

Multiplying equation (2) by the column to elevator gearing gives

$$\frac{\ddot{\theta}}{\delta_{COL}} = C_{M_{\delta_E}} \frac{qsc}{I_{yy}} \left(\frac{\delta_E}{\delta_{COL}} \right)$$

APPENDIX 5

A. Ground Based Analog Simulation Description

The ground-based flight simulator used for these studies was the Ames Research Center, moving-base transport simulator with a color TV visual scene. The visual scene, projected to simulate daylight flying, was produced by the Ames Research Center landing-approach color image generator. The simulation solved the six degree of freedom equations of motion of the airplane and presented the solutions in cab motions, instrument readings, and visual display changes. Linearized aerodynamic coefficients were used in the equations of motion. The equations of motion are given in Table A5-1.

The moving-base transport simulator utilized a transport-type (C-130) cab with conventional seating, instrumentation, and controls for two pilots. The left hand seat was used for these tests. A hydraulic feel system allowed for variation of the control system parameters. The instrument panel included the following instruments:

1. Air-speed
2. Altitude
3. Rate of climb
4. Angle of attack
5. Angle of sideslip
6. Turn and slip
7. Heading
8. Attitude
9. Localizer and glide slope error.

TABLE A5-1

Ground Based Simulation Equations of Motion:

DRAG

$$C_D = C_{D_{\alpha=0}} + C_{D_{\alpha}} \alpha$$

$$\dot{V} = \frac{1}{m} (T_N - g S C_D - W \sin \gamma)$$

$$V = V_T = \int \dot{V} dt + V_0 \quad (V_0 = \text{initial velocity})$$

$$x = x_0 + \int (V \cos \gamma \cdot \cos \psi) dt \quad (x_0 = \text{initial distance from runway threshold})$$

$$V_e = \sqrt{\sigma} V + V_{eUST}$$

$$g = \frac{V_e^2}{295}$$

$$T_N = T_{N_0} + \frac{\partial T_N}{\partial V} u \quad (T_{N_0} = \text{initial net thrust for trim})$$

$$u = V - V_0$$

PITCH

$$C_m = C_{m_q} q + C_{m_{\dot{\alpha}}} \dot{\alpha} + C_{m_{\alpha=0}} + C_{m_{\alpha}} \alpha + C_{m_{\delta_e}} \delta_e + C_{m_{i_H}} i_H$$

$$I_{YY} \frac{\dot{q}}{57.3} = q S \bar{c} C_m$$

$$q = \int \dot{q} dt$$

200

TABLE A5-1 (CONT.)

$$C_{n_w} = C_{n_{\delta_s}} \delta_s + C_{n_{\delta_a}} \delta_a + C_{n_{\delta_r}} \delta_r + C_{n_{\beta_w}} \beta_w + C_{n_P} (P) + C_{n_r} (r)$$

$$I_{xx} \frac{\dot{r}}{57.3} = I_{xz} \left(\frac{\dot{r}}{57.3} \right) + g S b C_l$$

$$I_{zz} \frac{\dot{r}}{57.3} = g S C_n b$$

$$P = \int \dot{P} dt$$

$$r = \int \dot{r} dt$$

$$\dot{\phi} = P + r \frac{\theta}{57.3}$$

$$\dot{\psi} = r \cos \phi + g \sin \phi$$

$$\phi = \int \dot{\phi} dt + \phi_0 \quad (\phi_0 = \text{initial roll angle})$$

$$\psi = \int \dot{\psi} dt + \psi_0 \quad (\psi_0 = \text{initial yaw angle})$$

SIDE FORCE

$$C_Y = C_{Y_{\delta_s}} \delta_s + C_{Y_{\delta_r}} \delta_r + C_{Y_{\beta_w}} \beta_w + C_{Y_P} (P) + C_{Y_r} (r) + C_{Y_{\delta_w}} \delta_w$$

$$a_Y = \frac{1}{m} (g S C_Y + W \sin \phi + T \frac{\beta r}{57.3})$$

$$\dot{\beta}_P = P \frac{\alpha}{57.3} - r + \frac{57.3}{V} a_y$$

$$\beta_P = \int \dot{\beta}_P dt + \beta_0 \quad (\beta_0 = \text{initial sideslip angle})$$

$$\beta = \beta_P + \beta_{GUST}$$

$$S_Y = S_{Y_0} + \int V \sin \psi_P dt \quad (S_{Y_0} = \text{initial lateral distance from runway})$$

$$\psi_P = \int \left(\frac{a_Y}{V} \cos \phi - g \sin \phi \right) dt$$

TABLE A5-1 (CONT.)

$$\alpha_P = \alpha_0 + \int \left(q + 57.3 \frac{a_z}{V} \right) dt \quad (\alpha_0 = \text{initial } \alpha \text{ for trim})$$

$$\alpha = \alpha_P + \alpha_{GUST}$$

$$\theta = \gamma + \alpha_P$$

LIFT

$$C_L = C_{L\alpha=0} + C_{L\alpha} \alpha + C_{L\delta_e} \delta_e + C_{L\dot{i}_H} \dot{i}_H + C_{L\dot{\alpha}} \dot{\alpha} + C_{Lq} q$$

$$(C_{L\alpha=0} + C_{L\alpha} \alpha \text{ limited to } C_{L_{MAX.}})$$

$$-a_z = \frac{1}{M} (q S C_L - W \cos \phi \cos \gamma)$$

$$\dot{\gamma} = - \frac{57.3}{V} (a_z \cos \phi + a_y \sin \phi)$$

$$\gamma = \int \dot{\gamma} dt - \gamma_0 \quad (\gamma_0 = \text{initial flight path angle})$$

$$\dot{h} = V \sin \gamma$$

$$h = \int \dot{h} dt + h_0 \quad (h_0 = \text{initial altitude})$$

ROLL AND YAW

$$C_l = C_{l_W} - C_{n_W} \frac{\alpha}{57.3} \quad (C_{l_W} \text{ and } C_{n_W} \text{ defined below})$$

$$C_n = C_{n_W} + C_{l_W} \frac{\alpha}{57.3}$$

$$C_{l_W} = C_{l\delta_s} \delta_s + C_{l\delta_a} \delta_a + C_{l\delta_r} \delta_r + C_{l\beta_w} \beta_w + C_{l_P} (P) + C_{l_r} (r)$$

702

The pilots outside view was limited to the visual TV scene by blocking out all windows not directly in front of him.

Motion of the cab was controlled by three linear hydraulic servo actuators. These were operated differentially or synchronously for three degrees of motion; roll, pitch, and heave (vertical). The actuators were controlled in a closed loop fashion by the simulation. The roll axis of motion was scaled down by a factor of two so that a simulated roll angle of ten degrees produced five degrees of cab roll motion. This resulted in less side acceleration error apparent to the pilot in a steady turn due to gravity. The pilot received the proper roll cues from the instruments and visual scene. A tabulation of the moving-base transport simulator physical characteristics is shown in Table A5-2.

The visual scene was produced by a closed circuit color television system which utilized a scale contour map including roads, buildings and fields, as well as the runway to which the approaches were conducted. A color television camera was positioned by electric servos and driven closed loop by the simulation. The scope of the simulated airplane movements was limited only by the boundaries of the contour map. Descent through a cloud layer was simulated by obliterating the picture to a pre-selected altitude. The tabulated physical characteristics of the visual display system are shown in Table A5-2.

TABLE A5-2
SYSTEM CAPABILITIES

Ames Moving-Base Transport Simulator

Motions Generated:	<u>Acceleration</u>	<u>Displacement</u>
Roll	1 Rad/Sec ²	± 9°
Pitch	0.5 Rad/Sec ²	+ 14° - 6°
Heave (vertical)	± 0.8g (from ambient)	24 inches

Ames Landing-Approach Color Television Display

Motions Generated	<u>Velocity</u>	<u>Displacement</u>
Roll	0.35 Rad/Sec	--
Pitch	0.52 Rad/Sec	--
Yaw	0.17 Rad/Sec	360°
Lateral	240 Knots	2 1/2 miles
Vertical	6000 ft/min.	1500 ft. to 20 ft.
Longitudinal (runway length)	240 knots --	9 miles 10,000 ft. (model scale 1:1200)

APPENDIX 6

The following is a description of the documentation maneuvers performed by the evaluation pilots:

Longitudinal Maneuvers

Pitch Rate Reversal

The airplane was trimmed by the safety pilot before engaging simulation. After stabilizing in steady flight pitch rate reversals were performed. The maneuver was initiated by applying a sharp column input, then quickly applying a step column input in the opposite direction. The column was stabilized, the airspeed held within 2 knots of trim, and the angle of attack held within 1° of trim when the pitch rate reversed.

Column Step

From a stabilized flight condition, an aft column step was applied with amplitude sufficient to give a 1.2g maneuver. Recover was initiated after peak load factor was reached.

Wind Up Turn

Wind up turns to 45° bank angle were performed, stabilizing in 5° bank increments.

Speed Stability

The safety pilot trimmed the airplane in level flight. From initial trim the speed was increased and decreased in 5 kts increments using elevator only.

Phugoid

The airspeed was decreased 10 kts from trim using elevator only. The controls were released and the phugoid was allowed to continue for two cycles. If the phugoid was divergent the maneuver was repeated with an initial 5 knot decrease in airspeed.

205

Pitch Attitude

A precision pitch attitude change of 5° to 10° was performed in minimum time, using the flight director for attitude reference.

Elevator Pulse

The airplane was trimmed in the initial configuration by the safety pilot before engaging simulation. The column pulse was then applied from the computer.

Lateral Maneuvers**Steady Roll Rate**

The airplane was stabilized in a steady turn and step wheel inputs were applied.

Roll Rate Reversal

The roll rate reversals were initiated by pulsing the wheel sharply, then applying the specified step wheel input in the opposite direction. When done properly the wheel was stabilized and the sideslip angle was less than 2° when the roll rate reversed.

Yaw Rate Reversal

After the safety pilot trimmed the airplane, the yaw rate reversal was initiated by the evaluation pilot with an 8° sharp rudder input followed by an opposite rudder step input as required. When done properly the sideslip was less than 2° and the rudder pedals were stabilized when the yaw rate reversed.

Steady Sideslip

With the airplane in the trimmed condition the evaluation pilot stabilized in a 10° sideslip, released the controls, and re-stabilized in level flight.

Spiral Stability

The configuration was stabilized in a 10° right turn and the controls were released. Recovery was initiated when the bank angle reached either 5° or 20° .

20° Heading Change

The evaluation pilot performed a 20° heading change in minimum time.

Wheel Step

With the airplane in level flight a full wheel step was applied rapidly with recovery initiated when the bank angle reached 15°.

Wheel Pulse

The airplane was trimmed in the initial configuration by the safety pilot before engaging simulation. The wheel pulse was applied from the computer.

Rudder Pulse

The airplane was trimmed in the initial configuration by the safety pilot before engaging simulation. The rudder pulse was applied from the computer.