


General Disclaimer

One or more of the Following Statements may affect this Document

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.
- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.
- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.
- This document is paginated as submitted by the original source.
- Portions of this document are not fully legible due to the historical nature of some of the material. However, it is the best reproduction available from the original submission.

NT
Kennedy



ENGINEERING DEPARTMENT

TECHNICAL REPORT

TR-RE-CCSD-1135-3

August 10, 1968

SATURN IB PROGRAM


TEST REPORT FOR

GLOBE VALVE, 2 INCH, 6000 PSIG

Vacco Valve Company, Part Number M-6P-X469-2G

(With Modification Kit KM 7403)

NASA Drawing Number 10428530



N 69-13609

(ACCESSION NUMBER)

(THRU)

(PAGES)

(CODE)

(NASA CR OR TMX OR AD NUMBER)

(CATEGORY)

SPACE DIVISION



**CHRYSLER
CORPORATION**

TEST REPORT

FOR

GLOBE VALVE, 2 INCH

Vacco Valve Company Part Number M-6P-X469-2G

NASA Drawing Number 10428530

ABSTRACT

This report presents the results of tests performed on one specimen of Globe Valve 10428530. The following tests were performed:

- | | |
|-------------------------|-----------------|
| 1. Receiving Inspection | 4. Seat Erosion |
| 2. Proof Pressure | 5. Surge |
| 3. Functional | 6. Cycle |

The specimen's performance was in accordance with the specification requirements of NASA Drawing Number 10428530, except following the seat erosion test and during the cycle test.

Following the seat erosion test, the threaded area of the stem began to bind due to metallic particles shearing off in the bonnet section. The threads were cleaned and lubricated, and testing was resumed.

Following the first 25 cycles of the cycle test, the specimen's seat leakage exceeded 1460 scim. Examination revealed that the seat had become eroded. A new seat was installed, and the test was resumed. During the twelfth cycle the seat again became eroded sufficiently to allow excessive leakage. A second replacement seat was installed, and testing was resumed with pressure being applied to the inlet port only. After 975 successful cycles, it was decided that the remaining 25 cycles should be performed with the outlet port pressurized. Cycle testing was permanently discontinued after 984 cycles due to an eroded seat.

All seat failures took place while the outlet port was pressurized. The sample performed satisfactorily with the inlet port pressurized.

COMPONENT DATA	NASA DWG/SPEC/CODE NO.	FILE NO.
	10428530	GENERIC CODE D361102070020
	FIND NO. AI4629	COMPLEX 34
	REF DESIG. NO.	SYSTEM Pneumatic Supply
NOMENCLATURE	PRIORITY IV	SUBSYSTEM
	MANUFACTURER	
Manual Globe Valve 2-Inch 6000 psig	Vacco Valve Co.	Helium Storage Battery
		NHA DWG. NO. 75M25415
CRITICALITY NO.	MFG MODEL NO.	STOCK CODE NO.
CEI NO.	MFG PART NO. M-6P-X469-2G with Mod. Kit KM7403	REVISION: DATE 10-18-68
MAINTENANCE MANUAL TM-417-D	MFG DWG NO.	PREPARING ORGANIZATION Chrysler Corporation

SPECIFICATION REQUIREMENTS:

Operating Media: GN₂, GHe
 Operating Pressure: 0 to 6000 psig
 Proof Pressure: 11,000 psig
 Burst Pressure: 24,000 psig
 Maximum Torques
 Breakaway: 100 ft-lb with 6000 psig above seat
 Running: 50 ft-lb
 Seating: 100 ft-lb against 6000 psig
 Body Material: 316 CRES
 End Connections: 2 1/2 Grayloc XXS hubs
 Flow Capacity: C_v = 22.0 min.

FUNCTION:

The valve is used in the high pressure helium system to isolate the high pressure storage bottles from the compressor.

ASSESSMENT & RECOMMENDATIONS:

The valve successfully completed all tests in the primary flow direction. However, galling occurred on the poppet above the seat, after the seat erosion test. The valve was cleaned and lubricated and no further galling occurred. The soft seat ruptured during cycle testing in the reverse flow direction.

The valve is qualified for a mono directional flow valve. It should not be used where bidirectional flow is required.

TEST HISTORY:		Sheet <u>2</u> of <u>2</u>
---------------	--	----------------------------

TEST REPORT NO.	TEST TYPE	REMARKS
TR-RE-CCSD-FO-1135-3	Receiving Inspection Proof Pressure Functional Seat Erosion Surge Test Cycle Test	Satisfactory Satisfactory Satisfactory No seat leakage. Stem binding following test. Satisfactory Satisfactory in the primary flow direction. Soft seat ruptured in reverse flow direction.

SERVICE HISTORY:

None - Modified part.

APPROVAL

TEST REPORT

FOR

GLOBE VALVE

2 INCH, 6000 PSIG

Vacco Valve Company Part Number M-6P-X469-2G

(With Modification Kit KM 7403)

NASA Drawing Number 10428530

SUBMITTED BY:

G. Collins
G. Collins

Test and Evaluation Section

APPROVED BY:

R. W. Claunch
R. W. Claunch

Program Supervisor

APPROVED BY:

V. J. Vehko
V. J. Vehko, Director

Engineering Department

TEST REPORT

FOR

GLOBE VALVE, 2 INCH, 6000 PSIG

Vacco Valve Company Part Number M-6P-X469-2G

(With Mod. Kit KM 7403)

NASA Drawing Number 10428530

AUGUST 10, 1968

FOREWORD

The tests reported herein were conducted for the John F. Kennedy Space Center by Chrysler Corporation Space Division (CCSD), New Orleans, Louisiana. This document was prepared by CCSD under Contract NAS8-4016, Part VII, CWO 271620.

TABLE OF CONTENTS

<u>Section</u>		<u>Page</u>
I	INTRODUCTION.....	1-1
II	RECEIVING INSPECTION.....	2-1
III	PROOF PRESSURE TEST.....	3-1
IV	FUNCTIONAL TEST.....	4-1
V	SEAT EROSION TEST.....	5-1
VI	SURGE	6-1
VII	CYCLE TEST.....	7-1

LIST OF ILLUSTRATIONS


<u>Figure</u>	<u>Page</u>
2-1 RECEIVING INSPECTION.....	2-3
3-1 PROOF PRESSURE TEST SCHEMATIC.....	3-3
3-2 PROOF PRESSURE TEST SETUP.....	3-6
4-1 FUNCTIONAL TEST SCHEMATIC.....	4-4
4-2 FUNCTIONAL TEST SETUP.....	4-7
5-1 SEAT EROSION TEST SCHEMATIC.....	5-3
5-2 SEAT EROSION TEST SETUP.....	5-7
5-3 METAL PARTICLES PRODUCED FROM METAL TO METAL CONTACT.....	5-8
6-1 SURGE TEST SCHEMATIC	6-3
6-2 TYPICAL SURGE WAVEFORMS	6-5
6-3 SURGE TEST SETUP.....	6-9
7-1 CYCLE TEST SCHEMATIC.....	7-5
7-2 CYCLE TEST SETUP	7-18
7-3 TYPICAL ERODED SEAT FAILURE.....	7-19

LIST OF TABLES

<u>Table</u>	<u>Page</u>
2-1 RECEIVING INSPECTION TEST EQUIPMENT LIST.....	2-2
2-2 SPECIMEN DIMENSIONS.....	2-2
3-1 PROOF PRESSURE TEST EQUIPMENT LIST.....	3-4
3-2 PROOF PRESSURE TEST DATA.....	3-5
4-1 FUNCTIONAL TEST EQUIPMENT LIST.....	4-5
4-2 INITIAL FUNCTIONAL TEST DATA.....	4-6
5-1 SEAT EROSION TEST EQUIPMENT LIST.....	5-4
5-2 SEAT EROSION TEST DATA (INLET PORT PRESSURIZED).....	5-5
5-3 FUNCTIONAL TEST DATA FOLLOWING SEAT EROSION TEST.....	5-5
5-4 SEAT EROSION TEST DATA (OUTLET PORT PRESSURIZED).....	5-6
5-5 FUNCTIONAL TEST DATA FOLLOWING SEAT EROSION TEST.....	5-6
6-1 SURGE TEST EQUIPMENT LIST.....	6-4
6-2 FUNCTIONAL TEST DATA PRIOR TO SURGE TEST (72 HOUR LAPSE TIME)....	6-6
6-3 FUNCTIONAL TEST DATA (INLET PRESSURIZED) FOLLOWING SURGE TEST....	6-7
6-4 FUNCTIONAL TEST DATA (OUTLET PRESSURIZED) FOLLOWING SURGE TEST...6-8	6-8
7-1 CYCLE GROUPS.....	7-4
7-2 CYCLE TEST EQUIPMENT LIST.....	7-6
7-3 FUNCTIONAL TEST DATA PRIOR TO CYCLE TEST (72 HOUR LAPSE TIME)....	7-7
7-4 FIRST 25 CYCLES OF CYCLE GROUP.....	7-8
7-5 FUNCTIONAL TEST DATA AFTER 25 CYCLES.....	7-8
7-6 FUNCTIONAL TEST FOLLOWING INSTALLATION OF NEW SEAT.....	7-9
7-7 CYCLE TEST RESUMED WITH NEW SEAT.....	7-10
7-8 FUNCTIONAL TEST DATA AFTER INSTALLATION OF SECOND NEW SEAT.....	7-11

LIST OF TABLES (CONTINUED)

<u>Table</u>		<u>Page</u>
7-9	CYCLE TEST DATA AFTER SECOND NEW SEAT INSTALLATION.....	7-12
7-10	FUNCTIONAL TEST DATA AFTER 25 CYCLES.....	7-13
7-11	FUNCTIONAL TEST DATA AFTER 50 CYCLES.....	7-14
7-12	FUNCTIONAL TEST DATA AFTER 100 CYCLES.....	7-15
7-13	FUNCTIONAL TEST DATA AFTER 500 CYCLES.....	7-16
7-14	FUNCTIONAL TEST DATA AFTER 975 CYCLES.....	7-17



Globe Valve 10428530

CHECK SHEET

FOR

GLOBE VALVE, 2 INCH, 6000 PSIG

MANUFACTURER: Vacco Valve Company

MANUFACTURER'S PART NUMBER: M-6P-X469-2G (With Modification Kit KM 7403)

NASA PART NUMBER: 10428530

TESTING AGENCY: Chrysler Corporation Space Division, New Orleans, Louisiana

AUTHORIZING AGENCY: NASA KSC

I. FUNCTIONAL REQUIREMENTS

- A. OPERATING MEDIUM: GN_2 , He
- B. OPERATING PRESSURE: Zero to 6000 psig
- C. PROOF PRESSURE: 9000 psig
- D. BURST PRESSURE: 24,000 psig
- E. TORQUE REQUIREMENTS: Breakaway - 100 ft-lb max with 6000 psig above the seat
 - Running - 50 ft-lb max
 - Seating - 100 ft-lb max against 6000 psig

II. CONSTRUCTION

- A. BODY MATERIAL: 316 CRES
- B. END FITTING: 2-1/2 Inch XXS Grayloc Hubs
- C. SEALS: Buna-N
- D. SEAT: KEL-F

III. ENVIRONMENTAL CHARACTERISTICS

OPERATING TEMPERATURE RANGE: -20 to +120°F

IV. SPECIAL REQUIREMENTS

CLEANING SPECIFICATION: LOX Service per 10509305

V. LOCATION AND USE: Used in the high pressure helium system to isolate the high pressure storage bottles from the converter compressor facility.

TEST SUMMARY

GLOBE VALVE, 2 INCH, 6000 PSIG

NASA 10428530

Environment	Units	Operational Boundry	Test Objective	Test Results	Remarks
Receiving Inspection	1	Drawings and Specifications	Check for conformance to documentation and for manufacturing defects	Satisfactory	Completed
Proof Pressure Test	1	9000 psig for 5 minutes	Check for leakage and distortion	Satisfactory	No leakage or distortion
Functional Test	1	Inlet and outlet pressures to 6000 psig Closing torque 100 ft-lbs max. Breakaway torque 100 ft-lbs max. Running torque 50 ft-lbs max.	Check for leakage and distortion	Satisfactory	No leakage or distortion
Seat Erosion Test	1	Inlet and outlet pressures to 6000 psig flowing approximately 100 scfm for 4 hours	Verify that specimen's seat is not impaired by high pressure flow	Satisfactory	No deterioration to seat during test. Stem binding following test.
Surge Test	1	Inlet then outlet pressurized from zero to 6000 psig within 100 milliseconds	Verify that environment does not cause degradation or deformation	Satisfactory	No degradation or deformation
Cycle Test	1	6000 psig to inlet or outlet port with the specimen vented to atmosphere for certain cycles and the downstream valve closed for the remaining cycles.	Determine if specimen operation is impaired by cycling	Inlet pressurized satisfactory Outlet pressurized unsatisfactory	Seat failures caused by pressurizing outlet port

SECTION I
INTRODUCTION

1.1 SCOPE

1.1.1 This report describes the results of tests that were performed to determine if 2 Inch, Manually Operated Globe Valve 10428530 meets the operational and environmental requirements of John F. Kennedy Space Center Launch Complexes 34 and 37B.

1.1.2 One specimen was tested.

1.2 ITEM DESCRIPTION

The specimen has an operating pressure range from zero to 6000 psig. Globe Valve 10428530 is used in the high pressure helium system.

1.3 APPLICABLE DOCUMENTS

The following documents contain the test requirements for Globe Valve 10428530:

- a. 10428530, Component Specification**
- b. KSC-STD-164(D), Standard Environmental Test Methods for Ground Support Equipment Installations at Cape Kennedy**
- c. 10M01671 Level IV, Cleanliness Specification**
- d. Test Plan and Requirements CCSD-FO-1135-1**
- e. Test Procedure CCSD-FO-1135-2**

SECTION II

RECEIVING INSPECTION

2.1 REQUIREMENTS

The globe valve shall be checked for conformance with the applicable NASA specification and applicable vendor data to the extent possible without disassembly of the test specimen. The specimen shall also be inspected for poor workmanship and manufacturing defects.

2.2 PROCEDURE

- 2.2.1 The specimen was visually and dimensionally inspected for conformance with NASA specification 10428530. The specimen was also checked for defective threads.

2.3 TEST RESULTS

The specimen complied with NASA specification 10428530. No evidence of poor workmanship or manufacturing defects was observed.

2.4 TEST DATA

Receiving inspection test equipment list and dimensional test data are presented in tables 2-1 and 2-2.

Table 2-1. Receiving Inspection Test Equipment List

Item No.	Item	Manufacturer	Model/ Part No.	Serial No.	Calibration Date
1	24 in. scale	L.S. Starrett Co.	No. 16R graduated	NASA 08-113 113-50- 1061-C	N/A

Table 2-2. Specimen Demensions

Description	Actual Values
Weight of Specimen	46.7 lbs
Length from Inlet to Outlet Port	12-29/64 in.
Height (Valve opened)	13-3/8 in.
Height (Valve closed)	12.0 in.
Handle Diameter	8-15/16 in.
Inlet and Outlet Flange Diameter	5.0 in.
Inlet Port Opening	1-25/32 in.
Outlet Port Opening	1-25/32 in.




Figure 2-1. Receiving Inspection

SECTION III

PROOF PRESSURE TEST

3.1 TEST REQUIREMENTS

3.1.1 A proof pressure of 9000 psig shall be applied to the inlet port with the outlet port capped and the specimen in the open position for a period of 5 minutes.

3.1.2 Any leakage or distortion shall be monitored.

3.2 TEST PROCEDURE

3.2.1 The proof pressure test setup was assembled as shown in figures 3-1 and 3-2 using equipment listed in table 3-1.

3.2.2 All hand valves were closed and regulator 6 was adjusted for zero outlet pressure.

3.2.3 The outlet port of specimen 1 was capped and the specimen was completely opened.

3.2.4 Hand valves 3 and 7 were opened and pressure was applied using source 2.

3.2.5 Pressure gauge 5 indicated 10,000 psig.

3.2.6 Regulator 6 was adjusted until 9000 psig was established on pressure gage 8.

3.2.7 The 9000 psig pressure was maintained for 5 minutes.

3.2.8 Regulator 6 was adjusted for zero outlet pressure.

3.2.9 Hand valve 9 was opened to vent the specimen.

3.2.10 All test data was recorded.

3.3 TEST RESULTS

No leakage or distortion was observed.

3.4 TEST DATA

Proof pressure data is presented in tabel 3-2.




Figure 3-1. Proof Pressure Test Schematic

Table 3-1. Proof Pressure Test Equipment List

Item No.	Item	Manufacturer	Model/ Part No.	Serial No.	Remarks
1	Test Specimen	Vacco Valve Company	M-6P-X469-2G (Modification Kit KM 7403)	22144-1	2 inch Globe Valve
2	GN ₂ Pressure Source	CCSD	N/A	N/A	10,000 psig
3	Hand Valve	Combination Pump and Valve Co.	380-3	N/A	1-1/2 inch
4	Filter	Microporous	4813-F-2DM	N/A	2-micron
5	Pressure Gage	Ashcroft	N/A	NASA 200G13-3	0 to 20,000 psig ±0.5% FS accuracy 12-7-67
6	Pressure Regulator	Tescom Corp.	25-102-1-20	3024	10,000 psig inlet 10,000 psig outlet
7	Hand Valve	Robbins Aviation	SSKG-250-4T	N/A	1/4 inch
8	Pressure Gage	Heise	H49 & 80	NASA-95- 1653-B	0 to 10,000 psig ±0.1% FS accuracy 1-5-68
9	Hand Valve	Robbins Aviation	SSKG-250-4T	N/A	1/4 inch

Table 3-2. Proof Pressure Test Data

Pressure	9000 psig/5 minutes (GN₂)
Leakage	Zero
Distortion	Zero




Figure 3-2. Proof Pressure Test Setup

SECTION IV
FUNCTIONAL TEST

4.1 TEST REQUIREMENTS

- 4.1.1 The test specimen shall be checked for leakage during a five minute period with the inlet port of the specimen pressurized to 6000 psig, specimen closed, and the outlet port vented. Any leakage shall be recorded.**
- 4.1.2 The opening, closing, and normal running torque of the valve shall be determined with the inlet port pressurized to 6000 psig. Record all data.**
- 4.1.3 The procedure described in 4.1.1 shall be performed once for the initial functional test and once for all subsequent functional tests. Procedures described in 4.1.2 shall be performed 5 times for each functional test.**
- 4.1.4 The procedures described in 4.1.1 through 4.1.3 shall be repeated with pressure applied to the outlet port.**

4.2 TEST PROCEDURE

- 4.2.1 Line 14 was connected to the inlet port of the specimen and line 15 was connected to the outlet port.**
- 4.2.2 The test setup was assembled as shown in figures 4-1 and 4-2 using the equipment listed in table 4-1.**
- 4.2.3 The hand wheel of the test specimen was replaced with torque wrench 13 and the test specimen was closed using the specified maximum seating torque.**
- 4.2.4 All regulators were adjusted for zero outlet pressure and all hand valves were closed.**
- 4.2.5 Hand valve 3 was opened. The supply pressure on gage 5 indicated 7000 psig.**

- 4.2.6 Regulator 6 was adjusted to establish 6000 psig on pressure gage 7.
- 4.2.7 Hand valve 10 was opened and leakage was monitored over a five minute period. When bubbles appeared in water tank 12, the amount of leakage was determined by the displacement of water in graduated cylinder 11.
- 4.2.8 Regulator 6 was adjusted for zero outlet pressure. Hand valve 8 was then opened to vent the specimen.
- 4.2.9 Hand valve 8 and 10 were closed.
- 4.2.10 Regulator 6 was slowly adjusted to apply 6000 psig pressure to the specimen.
- 4.2.11 The breakaway torque of the specimen was measured by slowly applying the maximum torque required to unseat the specimen.
- 4.2.12 After the breakaway torque was measured, the specimen was completely opened. The running torque required from breakaway until the specimen was fully opened was measured.
- 4.2.13 The specimen was then closed. The closing running torque and closing torque with flow were measured.
- 4.2.14 Hand valve 9 was opened and closed to vent the outlet pressure of the specimen. Hand valve 10 was opened.
- 4.2.15 The specimen was slowly opened until bubbles appeared in water tank 12.
- 4.2.16 The specimen was slowly closed and the torque that was required to stop the bubbles in water tank 12 was measured. This was the closing torque for the specimen.
- 4.2.17 The procedures described in 4.2.11 through 4.2.16 were repeated for a total of five runs.
- 4.2.18 The procedures of 4.2.7 were repeated.
- 4.2.19 Regulator 6 and hand valve 10 were closed.

4.2.20 Hand valves 8 and 9 were opened and closed to vent the specimen.

4.2.21 Line 14 was attached to the outlet port of the specimen and line 15 was attached to the inlet port. The procedures of 4.2.3 through 4.2.20 were repeated.


4.2.22 All data was recorded.

4.3 TEST RESULTS

The test specimen functioned satisfactorily during the initial functional test.

4.4 TEST DATA

Initial functional test data is presented in table 4-2.



NOTE: All lines 1/4 inch.
Refer to table 4-1 for item identification

Figure 4-1. Functional Test Schematic

Table 4-1. Functional Test Equipment List

Item No.	Item	Manufacturer	Model/ Part No.	Serial No.	Remarks
1	Test Specimen	Vacco Valve Co.	M-6P-X496 2G (With Mod. Kit KM 1430)	22144-1	2 inch Globe Valve 6000 psig
2	He Source	CCSD	N/A	N/A	7000 psig
3	Hand Valve	Combination Pump and Valve Co.	N/A	N/A	1-1/2 inch
4	Filter	Microporous	4813-F2DM	N/A	0 to 10,000 psig
5	Pressure Gage	Ashcroft	1850	NASA 20059-4P	$\pm 0.5\%$ FS accuracy Cal date 12-7-67
6	Regulator	Tescom Corp.	26-1002	1009	7000 psig inlet 0 to 7000 psig outlet
7	Pressure Gage	Ashcroft	1850	NASA 200594-Q	0 to 10,000 psig $\pm 0.25\%$ FS accuracy Cal date 12-7-67
8	Hand Valve	Grove	N/A	N/A	1/4 inch
9	Hand Valve	Robbins	SSKG-250-4T	N/A	1/4 inch
10	Hand Valve	Robbins	SSKG-250-4T	N/A	1/4 inch
11	Graduated Cylinder	N/A	N/A	N/A	For leakage measurement
12	Water Tank	CCSD	N/A	N/A	Leakage detector
13	Torque Wrench	Sturtevant	S-200-1	N/A	Replaces hand wheel of specimen (when required) Cal date 7-5-66
14	Line	Superior Tube Co.	N/A	N/A	1/4 inch

Table 4-1. Functional Test Equipment List (Cont'd)

Item No.	Item	Manufacturer	Model/ Part No.	Serial No.	Remarks
15	Line	Superior Tube Co.	N/A	N/A	1/4 inch
16	Thermocouple	Minneapolis Honeywell	30112	N/A	-50 to +200 (+2.5)°F (temperature test only)
17	Thermal Chamber	Conrad	N/A	NASA 200494-1	-25 to +200°F (temperature test only)

Table 4-2. Initial Functional Test Data

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	200	6000	0	0
2	200	0	6000	0

Run	Applied Seating Torque (in-lbs)	Specimen Inlet Pressure (psig)	Specimen Outlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
					Opening	Closing	
1	400	6000	0	300	18	10	450
2	450	6000	0	325	15	10	500
3	500	6000	0	375	15	10	300
4	300	6000	0	300	15	10	200
5	200	6000	0	300	15	10	200
6	200	0	6000	125	15	15	150
7	150	0	6000	125	15	15	125
8	125	0	6000	125	20	10	150
9	150	0	6000	120	15	15	300
10	300	0	6000	100	15	10	200

Note: No leakage




Figure 4-2. Function Test Setup

SECTION V
SEAT EROSION TEST

5.1 TEST REQUIREMENTS

- 5.1.1 A seat erosion test shall be performed on the test specimen.**
- 5.1.2 The specimen inlet shall be pressurized to 6000 psig. The specimen shall be adjusted to flow approximately 100 scfm of GN₂ for four hours with the outlet pressure maintained below 50 psig.**
- 5.1.3 A functional test shall be performed within one hour following the test.**
- 5.1.4 The procedures described in 5.1.1 through 5.1.3 shall be repeated with pressure applied to the outlet port.**

5.2 TEST PROCEDURE

- 5.2.1 The seat erosion test equipment was assembled as shown in figures 5-1 and 5-2. The equipment used is listed in table 5-1. Line 11 was attached to the specimen's inlet port and line 12 was attached to the outlet port.**
- 5.2.2 Hand valve 2 and the test specimen were closed and regulator 5 was adjusted for zero outlet pressure.**
- 5.2.3 Hand valve 2 was opened.**
- 5.2.4 The supply pressure on gage 4 indicated 7000 psig.**
- 5.2.5 Regulator 5 was adjusted to establish 6000 psig on pressure gage 6.**
- 5.2.6 The test specimen was adjusted to provide 100 (+5) scfm flow while the outlet pressure was maintained below 50 psig.**
- 5.2.7 The conditions described in 5.2.6 were maintained for four hours.**


- 5.2.8 A functional test was performed within one hour following the seat erosion test.
- 5.2.9 Line 12 was then attached to the specimen's inlet port and line 11 was attached to the outlet port. The procedures of 5.2.2 through 5.2.8 were repeated.
- 5.2.10 All test data was recorded.

5.3 TEST RESULTS

- 5.3.1 The test specimen successfully flowed approximately 100 scfm; first through the inlet port and then through the outlet port for four hours each. There was no apparent deterioration caused to the specimen.
- 5.3.2 During the functional test following the seat erosion test, the valve stem began binding. It was noted that small steel particles were present on the threaded area, apparently caused by metal to metal contact in the bonnet section. The particles were washed off with freon, the stem re-lubricated, and testing was resumed. Torque values were still according to specification.

5.4 TEST DATA

- 5.4.1 Test data recorded during the seat erosion test and the subsequent functional test are presented in tables 5-2 through 5-5.
- 5.4.2 A photograph of the steel particles which caused the specimen's stem to bind is shown in figure 5-3.



Note: All lines 1/2-inch.
Refer to table 5-1 for item Identification.

Figure 5-1. Seat Erosion Test Schematic

Table 5-1. Seat Erosion Test Equipment List

Item No.	Item	Manufacturer	Model/ Part No.	Serial No.	Remarks
1	Test Specimen	Vacco Valve Co.	M-6P-X469-2G (With Mod. Kit 7403)	22144-1	2 inch Globe Valve 6000 psig
2	Hand Valve	Controls Components	MV-1004-P-P	N/A	1-1/2 inch
3	Filter	Permanent Filter Corp.	9377-3154	CPB-D10	2-micron
4	Pressure Gage	Ashcroft Corp.	N/A	NASA-95 1648-B	0 to 10,000 psig $\pm 0.5\%$ FS accuracy Cal date 11-11-67
5	Pressure Regulator	Tescom Corp.	26-1021-20	3025	7000 psig inlet 0 to 6000 psig outlet
6	Pressure Gage	Heise	N/A	NASA 012452	0 to 10,000 psig $\pm 0.1\%$ FS accuracy Cal date 11-11-67
7	Temperature Probe	Honeywell Corp.	30112	N/A	-50 to +200°F $\pm 2.5^\circ\text{F}$
8	Flow Nozzle	Flowdyne Corp.	XN160450-SA	2375	Calibrated nozzle, D ₂ =.4545 to flow 100 scfm of GN ₂ at inlet pressure of less than 50 psig
9	Pressure Gage	Heise	H34951	NASA 014227	0 to 100 psig $\pm 0.1\%$ FS accuracy
10	GN ₂ Source	CCSD	N/A	N/A	7000 psig
11	Line	Superior Tube Co.	N/A	N/A	1/2 inch
12	Line	Superior Tube Co.	N/A	N/A	1/2 inch
13	Gage Saver	Fisher Controls	N/A	N/A	Set at 95 psig

Table 5-2. Seat Erosion Test Data (Inlet Port Pressurized)

Readings taken at 1/2 hour intervals	Pressure upstream of specimen (psig)	Pressure between specimen and nozzle (psig)	Temperature between specimen & .4545 inch diameter nozzle	
			°F	°Rankine
1	6000	21.0	5	465
2	6000	19.3	2	462
3	6000	18.0	0	460
4	6000	25.5	0	460
5	6000	20.0	5	465
6	6000	20.0	5	465
7	6000	21.4	2	462
8	6000	20.0	5	465
9	6000	19.0	5	465

Table 5-3. Functional Test Data Following Seat Erosion Test

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	450	6000	0	0
2	450	0	6000	0

Run	Applied Seating Torque (in-lbs)	Specimen Inlet Pressure (psig)	Specimen Outlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
					Opening	Closing	
1	450	6000	0	150	20	15	225
2	225	6000	0	150	20	15	225
3	225	6000	0	150	20	15	300
4	300	6000	0	250	20	20	300
5	300	6000	0	250	20	20	300
6	300	0	6000	250	20	15	250
7	250	0	6000	300	20	18	250
8	250	0	6000	300	20	18	350
9	350	0	6000	300	20	18	400
10	400	0	6000	350	20	18	400

Table 5-4. Seat Erosion Test Data (Outlet Port Pressurized)

Readings taken at 1/2 hour intervals	Pressure upstream of specimen (psig)	Pressure between specimen and nozzle (psig)	Temperature between specimen & .4545 inch diameter nozzle	
			°F	°Rankine
1	6000	22.5	5	465
2	6000	21.7	5	464
3	6000	19.0	5	465
4	6000	17.0	5	465
5	6000	22.2	0	460
6	6000	20.0	0	460
7	6000	19.0	0	460
9	6000	21.0	0	460

Table 5-5. Functional Test Data Following Seat Erosion Test

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	500	6000	0	0
2	400	0	6000	0

Run	Applied Seating Torque (in-lbs)	Specimen Inlet Pressure (psig)	Specimen Outlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
					Opening	Closing	
1	400	6000	0	350	20	18	500
2	400	6000	0	400	20	18	400
3	425	6000	0	400	20	18	400
4	425	6000	0	425	20	18	800
5	425	6000	0	650	300	100	700
See note at bottom of page							
6	400	0	6000	150	40	25	400
7	400	0	6000	150	40	25	425
8	425	0	6000	150	40	25	425
9	425	0	6000	150	50	25	425
10	425	0	6000	150	50	25	425

Note: During the fourth and fifth cycle the valve stem began binding. Small particles were noted on the stem. These particles were cleaned off, the stem re-lubricated, and testing was resumed.




Figure 5-2. Seat Erosion Test Setup




Figure 5-3. Metal Particles Produced from Metal to Metal Contact

SECTION VI

SURGE TEST

6.1 TEST REQUIREMENTS

- 6.1.1 The test specimen shall be subjected to 10 pressure surges with the specimen closed and 10 with the specimen 1/4 open, to determine if the environment causes degradation or deformation.
- 6.1.2 Each surge shall be an increase from zero to 6000 psig within 100 milliseconds. Pressure shall be applied to the specimen's inlet port. A functional test shall be performed within one hour following the test.
- 6.1.3 The procedures described in 6.1.1 and 6.1.2 shall be repeated with pressure applied to the outlet port.

6.2 TEST PROCEDURE

- 6.2.1 The test setup was assembled as shown in figures 6-1 and 6-3 using the equipment listed in table 6-1. Line 9 was attached to the inlet port of the test specimen and line 14 to the outlet port. All hand valves and the test specimen were closed.
- 6.2.2 Regulator 12 was adjusted for zero outlet pressure.
- 6.2.3 Hand valve 3 was then opened.
- 6.2.4 Pressure gage 5 indicated approximately 7000 psig.
- 6.2.5 Regulator 12 was adjusted until gage 13 indicated 6000 psig. Oscilloscope 8 was turned on.
- 6.2.6 Switch 11 was closed to actuate solenoid valve 6.
- 6.2.7 The output of pressure transducer 7 was monitored and recorded on oscilloscope 8.


- 6.2.8 Switch 11 was opened to deactuate solenoid valve 6.
- 6.2.9 The procedures described in 6.2.6 through 6.2.8 were repeated for a total of 10 cycles. Water tank 15 was monitored for evidence of specimen internal leakage throughout the test.
- 6.2.10 Line 14 was removed from tank 15. The stem was then turned until the specimen was approximately 1/4 opened and steps 6.2.6 through 6.2.8 were repeated for 10 additional cycles.
- 6.2.11 A functional test was performed within one hour following the test.
- 6.2.12 Line 9 was then attached to the specimen's outlet port and line 14 to the inlet port.
- 6.2.13 The procedures described in 6.2.6 through 6.2.11 were repeated.
- 6.2.14 The specimen was checked for deformation and degradation. All test data was recorded.

6.3 TEST RESULTS

The test specimen withstood 20 surge cycles from 0 to 6000 psig at the inlet port and 20 subsequent cycles at the outlet port. Functional test results following each phase of cycling were satisfactory.

6.4 TEST DATA

- 6.4.1 Typical surge waveforms as recorded during the tests are presented in figures 6-2. Functional test data following the surge tests is presented in tables 6-3 and 6-4.



Note: All lines 1/2-inch.
Refer to table 6-1. for item identification.

Figure 6-1. Surge Test Schematic

Table 6-1. Surge Test Equipment List

Item No.	Item	Manufacturer	Model/ Part No.	Serial No.	Remarks
1	Test specimen	Vacco Valve Co.	M-6P-X469-2G (With Mod. Kit KM 7403)	22144-1	2 inch Globe Valve 6000 psig
2	GN ₂ Source	CCSD	N/A	N/A	10,000 psig
3	Hand Valve	Combination Pump and Valve Co.	N/A	N/A	1-1/2 inch
4	Filter	Microporous	4813-F-DM	N/A	2 micron
5	Pressure Gage	Ashcroft	1850	NASA 200594-P	10,000 psig ±0.5% FS accuracy Cal date 6-7-67
6	Solenoid Valve	Marotta Valve Co.	MV-583	2915	3 way, 1/2 inch normally closed
7	Pressure Transducer	Statham	PA826-10M	NASA-95 1651-B	0 to 10,000 psig ±0.25% FS accuracy Cal date 5-25-67
8	Oscillograph Recorder	CEC	124	NASA 012586	Used to record Pressure Impulse Cal date 8-2-67
9	Line	Superior Tube Company	N/A	N/A	1/2 inch
10	Power Supply	Lab Source	N/A	N/A	28 vdc, 5 amp
11	Switch	Cutler Hammer	N/A	N/A	SPST
12	Regulator	Tescom Corporation	26-1002	1009	6500 psig inlet 0 to 6000 psig outlet
13	Pressure Gage	Ashcroft	1850	NASA 200594-Q	0 to 10,000 psig ±0.5% FS accuracy
14	Line	Superior Tube Co.	N/A	N/A	1/2 inch
15	Water Tank	CCSD	N/A	N/A	Leakage detector
16	Graduated Cylinder	Pyrex Co.	NA	N/A	For leakage measurement





Figure 6-2. Typical Surge Wave Form
6-5

Table 6-2. Functional Test Data Prior to Surge Test (72 Hours Lapse Time)

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	445	0	6000	0
2	300	6000	0	0

Run	Applied Seating Torque (in-lbs)	Specimen Inlet Pressure (psig)	Specimen Outlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
					Opening	Closing	
1	350	6000	0	150	40	20	300
2	475	6000	0	375	30	25	475
3	450	6000	0	400	40	25	450
4	400	6000	0	375	35	30	400
5	450	6000	0	400	35	25	450
6	445	0	6000	150	30	20	400
7	400	0	6000	200	40	25	400
8	400	0	6000	150	50	25	400
9	400	0	6000	125	45	25	300
10	300	0	6000	125	40	25	300

Table 6-3. Functional Test Data (Inlet Pressurized) Following Surge Test

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scin)
1	450	6000	0	0
2	400	0	6000	0

Run	Applied Seating Torque (in-lbs)	Specimen Inlet Pressure (psig)	Specimen Outlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
					Opening	Closing	
1	450	6000	0	400	35	25	450
2	450	6000	0	425	35	25	450
3	450	6000	0	425	35	25	400
4	400	6000	0	425	35	25	400
5	400	6000	0	300	35	25	400
6	400	0	6000	200	35	25	400
7	400	0	6000	175	35	25	400
8	400	0	6000	150	35	25	400
9	400	0	6000	150	35	25	400
10	400	0	6000	150	35	25	400

Table 6-4. Functional Test Data (Outlet Pressurized) Following Surge Test

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scm)
1	400	6000	0	0
2	400	0	6000	0

Run	Applied Seating Torque (in-lbs)	Specimen Inlet Pressure (psig)	Specimen Outlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
					Opening	Closing	
1	400	6000	0	400	35	20	400
2	400	6000	0	400	35	20	400
3	400	6000	0	150	35	20	400
4	400	6000	0	250	35	20	400
5	400	6000	0	150	35	20	400
6	400	0	6000	175	30	25	400
7	400	0	6000	175	30	25	400
8	400	0	6000	175	30	25	400
9	400	0	6000	175	30	25	400
10	400	0	6000	175	30	25	400




Figure 6-3. Surge Test Setup

SECTION VII

CYCLE TEST

7.1 TEST REQUIREMENTS

- 7.1.1 A cycle test shall be performed on the test specimen to determine if the environment causes degradation or deformation.
- 7.1.2 Two types of cycles shall be performed. One type with the inlet port pressurized to 6000 psig and another type with the outlet port pressurized to 6000 psig.
- 7.1.3 Certain cycles (to be called type I) shall be performed with the specimen vented to the atmosphere and with minimum flow restrictions upstream of the specimen. The other cycles (type II) shall be performed with the downstream line closed. However, the line shall be opened between cycles to vent downstream pressure.
- 7.1.4 Cycles shall be performed in groups as specified in table 7-1. A functional test shall be performed following each group of cycles. A total of 1000 cycles shall be performed on the specimen.

7.2 TEST PROCEDURE

- 7.2.1 A functional test was performed due to a delay of over 72 hours since the last functional tests.
- 7.2.2 The test setup was then assembled as shown in figures 7-1 and 7-2 using the equipment listed in table 7-2.
- 7.2.3 All valves were closed and the regulators were adjusted for zero outlet pressure.
- 7.2.4 The inlet port or the outlet port of the specimen was connected to the upstream line according to the sequence shown in table 7-1.
- 7.2.5 Hand valve 10 was opened.
- 7.2.6 Hand valves 4 and 6 were then opened.

- 7.2.7 Pressure regulator 5 was adjusted to establish 6000 psig on pressure gage 8.

TYPE I CYCLES

- 7.2.8 Solenoid valves 16a, 16b and 16c were energized to the open position.
- 7.2.9 Solenoid valve 9 was opened to pressurize the dome of regulator 11 which then established 6000 psig on pressure gage 13.
- 7.2.10 Motor 15 was rotated counter clockwise, by energizing cycle timer 17, to open the specimen.
- 7.2.11 Motor 15 was then reversed, by changing the polarity with cycle timer 17, to close the specimen.

TYPE II CYCLES

- 7.2.12 Solenoid valve 9 was opened to pressurize the dome of regulator 11 which then established 6000 psig on pressure gage 13.
- 7.2.13 Motor 15 was rotated counter clockwise, by energizing cycle timer 17, to open the specimen.
- 7.2.14 Motor 15 was then reversed, by changing the polarity with cycle timer 17, to close the specimen.
- 7.2.15 Solenoid valve 16c was opened to vent the downstream pressure.
- 7.2.16 Solenoid valve 16c was then closed.

7.3 TEST RESULTS

- 7.3.1 The test specimen was subjected to 25 type I cycles as described in 7.2.8 through 7.2.11. Following the 25 cycles, leakage past the


seat exceeded 1460 scim even with the maximum torque (1200 in-lbs) applied. The damaged seat was replaced and testing was continued. With the inlet port pressurized, ten (10) type I cycles were successfully completed. The outlet port was then pressurized and during the second cycle the seat was damaged. Leakage could not be stopped even with the maximum allowable torque applied.

7.3.2 Another seat was installed and a total of 975 cycles were successfully completed. At the request of CCSD-FO, only the inlet port was pressurized during these cycles. It was then requested that the outlet port be pressurized for the remaining 25 cycles. Cycle testing was permanently discontinued after 984 cycles due to an eroded seat.

7.3.3 A photograph of a typical eroded seat is shown in figure 7-3.

Table 7-1. Cycle Groups

Groups	Pressurized Port	Cycles	Cycle Type
1	inlet	1 - 5	I
	outlet	6 - 10	
	inlet	11 - 15	
	outlet	16 - 20	
	inlet	21 - 25	
2	outlet	26 - 35	II
	inlet	36 - 50	
3	inlet	51 - 75	I
	outlet	76 - 100	
4	inlet	101 - 200	II
	outlet	201 - 300	
	inlet	301 - 400	
	outlet	401 - 500	
5	inlet	501 - 600	II
	outlet	601 - 700	
	inlet	701 - 800	
	outlet	801 - 900	
	inlet	901 - 975	
6	outlet	976 - 985	I
	inlet	986 - 990	
	outlet	991 - 995	
	inlet	996 - 1000	



Note: Main flow lines 3/4-inch. All other lines 1/4-inch.
Refer to table 7-2 for item identification.

Figure 7-1. Cycle Test Schematic

Table 7-2. Cycle Test Equipment List

Item No.	Item	Manufacturer	Model/ Part No.	Serial No.	Remarks
1	Test Specimen	Vacco Valve Company	M-6P-X469 2G (With Mod Kit KM 7403)	22144-1	2 inch Globe Valve
2	GN ₂ Source	CCSD	N/A	N/A	10,000 psig
3	Filter	Permanent Filter	937-73154	6P8-010	2 micron
4	Hand Valve	Aminco	44-13126	58965	0 to 30,000 psig
5	Pressure Regulator	Tescom Corp.	26-1021-20	3024	10,000 psig inlet 10,000 psig outlet
6	Hand Valve	Aminco	44-13126	58965	30,000 psig
7	Vent Valve	Aminco	44-13106	50011A	30,000 psig
8	Pressure Gauge	Heise	H34955	NASA 014231	0 to 10,000 psig <u>+0.1%</u> FS accuracy Cal date 1-10-68
9	Solenoid Valve	Marotta	MB-510-H	190	6000 psig
10	Control Valve	Fisher	470-D	3572094	10,000 psig
11	Dome Regulator	Grove Valve	211-B	110751-1	10,000 psig
12	Thermocouple	Minneapolis Honeywell	N/A	N/A	-50 to 200 (<u>+2.5</u>)°F
13	Pressure Gauge	Heise	H-49480	NASA 95-1653-B	0 to 10,000 psig <u>+0.1%</u> FS accuracy Cal date 1-10-68
14	Clutch	Boston	Type V	R-025956	35 RPM
15	Motor	Westinghouse	Type CSP	CNO-5943	3 HP
16	Solenoid Valve (a)	Marotta	MB-583	2885	6000 psig
	Solenoid Valve (b)	Marotta	MB-583	2916	6000 psig
	Solenoid Valve (c)	Marotta	MB-583	372	6000 psig
17	Cycle Timer	Cramer Controls	540	73336A	115 VDC

Table 7-3. Functional Test Data Prior to Cycle Test (72 Hours Lapse Time)

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	350	0	6000	0
2	400	6000	0	0

Run	Applied Seating Torque (in-lbs)	Specimen Inlet Pressure (psig)	Specimen Outlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
					Opening	Closing	
1	400	6000	0	350	35	20	350
2	350	6000	0	350	35	20	450
3	450	6000	0	350	35	20	450
4	450	6000	0	300	35	20	450
5	450	6000	0	375	35	20	450
6	400	0	6000	175	35	20	350
7	350	0	6000	175	35	20	300
8	300	0	6000	175	35	20	300
9	300	0	6000	175	35	20	300
10	300	0	6000	175	35	20	300

Table 7-4. First 25 Cycles Of Cycle Group

Group	Pressurized Port 6000 psig	Cycles 1 to 25	Cycle Type	Remarks
1	Inlet Outlet Inlet Outlet Inlet	1-5 6-10 11-15 16-20 21-25	I	Functional test to be performed after 25 cycles

Table 7-5. Functional Test Data After 25 Cycles

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	800	6000	0	> 1460
2	800	0	6000	> 1460

Note: The valve stem was torqued to the maximum 1200 in-lbs. Leakage was still in excess of 1460 scim. A new seat was installed.

Table 7-6. Functional Test Following Installation of a New Seat

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	250	6000	0	0
2	250	0	6000	0

Run	Specimen Outlet Pressure (psig)	Specimen Inlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
				Opening	Closing	
1	6000	0	150	10	10	350
2	6000	0	175	10	10	200
3	6000	0	100	10	10	200
4	6000	0	100	10	10	200
5	6000	0	100	10	10	200
6	0	6000	175	10	10	250
7	0	6000	175	10	10	350
8	0	6000	300	10	10	350
9	0	6000	325	10	10	350
10	0	6000	325	10	10	350

Note: No leakage existed during the functional test

Table 7-7. Cycle Test Resumed With New Seat

Group	Pressurized Port (6000 psig)	Cycles 1 to 25	Cycle Type	Remarks
1	Inlet	1-10	I	No leakage
	Outlet	11-12	I	Leakage in excess of 1460 scim after completion of the twelfth cycle

Note: The valve stem was torqued to the maximum 1200 in-lbs. Leakage was still in excess of 1460 scim. Inspection revealed eroded seat.

Table 7-8. Functional Test Data After Installation of Second New Seat

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	260	6000	0	0

Run	Applied Seating Torque (in-lbs)	Inlet Port Pressurized (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
				Opening	Closing	
1	260	6000	210	9.5	5	270
2	300	6000	200	12.0	5	300
3	305	6000	275	35.0	5	375
4	375	6000	300	35.0	5	525
5	575	6000	375	40.0	5	400

Note: No Leakage.

Table 7-9. Cycle Test Data After Second New Seat Installation

Group	Pressurized Port (6000 psig)	Stem Torque (in-lbs)	Cycles	Cycle Type	Remarks
1	inlet	450	1-10	I	No leakage for first 10 individual cycles
1	inlet	450	11-25	I	No leakage
2	inlet	450	26-50	II	No leakage
3	inlet	450	51-100	I	No leakage
4	inlet	550	101-500	II	No leakage
5	inlet	850	501-975	II	No leakage
6	outlet	850	976-978	I	Leakage exceeded 800 scim
6	outlet	900	979-981	I	Leakage exceeded 1050 scim
6	outlet	1200	982-984	I	Leakage exceeded 1460 scim
	Note: Test permanently discontinued after 984 cycles due to eroded seat				

Table 7-10. Functional Test Data After 25 Cycles

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	450	6000	0	0

Run	Applied Seating Torque (in-lbs)	Inlet Port Pressurized (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
				Opening	Closing	
1	450	6000	350	30	5	450
2	450	6000	375	25	5	450
3	450	6000	350	25	5	450
4	450	6000	400	25	5	450
5	450	6000	400	25	5	450

Table 7-11. Functional Test Data After 50 Cycles

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	450	6000	0	0

Run	Applied Seating Torque (in-lbs)	Specimen Inlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
				Opening	Closing	
1	500	6000	475	35	5	535
2	525	6000	500	35	5	525
3	525	6000	500	35	5	525
4	525	6000	500	35	5	525
5	525	6000	500	35	5	525

Note: No Leakage.

Table 7-12. Functional Test Data After 100 Cycles

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	550	6000	0	0

Run	Applied Seating Torque (in-lbs)	Specimen Inlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
				Opening	Closing	
1	550	6000	500	40	5	550
2	550	6000	550	40	5	550
3	550	6000	550	40	5	550
4	550	6000	550	40	5	550
5	550	6000	550	40	5	550

Note: No Leakage.

Table 7-13. Functional Test Data After 500 Cycles

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	550	6000	0	0

Run	Applied Seating Torque (in-lbs)	Specimen Inlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
				Opening	Closing	
1	550	6000	550	40	5	550
2	500	6000	550	40	5	550
3	550	6000	550	40	5	550
4	550	6000	550	40	5	550
5	550	6000	550	40	5	550

Note: No Leakage.

Table 7-14. Functional Test Data After 975 Cycles

Run	Applied Seating Torque (in-lbs)	Inlet Pressure (psig)	Outlet Pressure (psig)	Leakage (scim)
1	850	6000	0	0

Run	Applied Seating Torque (in-lbs)	Specimen Inlet Pressure (psig)	Opening Torque (in-lbs)	Running Torque (in-lbs)		Closing Torque (in-lbs)
				Opening	Closing	
1	750	6000	750	40	5	750
2	750	6000	800	40	5	800
3	800	6000	850	40	5	850
4	850	6000	850	40	5	850
5	850	6000	850	40	5	850

Note: No leakage. Test was discontinued after 984 cycles due to excessive seat leakage.




Figure 7-2. Cycle Test Setup




Figure 7-3. Typical Eroded Seat Failure.