


General Disclaimer

One or more of the Following Statements may affect this Document

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.
- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.
- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.
- This document is paginated as submitted by the original source.
- Portions of this document are not fully legible due to the historical nature of some of the material. However, it is the best reproduction available from the original submission.



~~N71-30152 N71-80102~~
ALL INFORMATION CONTAINED
HEREIN IS UNCLASSIFIED
DATE 11/10/01 BY 60322 UCBAW/STP
170
P. 03
G-3
15



FAIRCHILD HILLER
STRATOS-WESTERN
1800 ROSECRANS AVENUE
MANHATTAN BEACH, CALIF. 90266

REPORT ER 834-7
FINAL REPORT
FOR
RELIEF VALVE ASSY

Stratos PN 834000
NASA Spec. 20M32254

Prepared By: J. Morando
J. Morando, Product Manager

Approved By: J. Feld
J. Feld, Chief Engineer


Approved By: T. Earl
T. Earl, Manufacturing Manager

FACILITY FORM 602

N71-30152
(ACCESSION NUMBER) (THRU)

(PAGES) (CODE)

(NASA CR OR TMX OR AD NUMBER) (CATEGORY)



20 May 1971

MURCHILD HILLER
STRATOS - WESTERN
1800 ROSECRANS AVENUE
MANHATTAN BEACH, CALIF., 90267

TABLE OF CONTENTS

Section	Title	Page
I	Introduction	1
II	Summary	2
III	Design and Development (Phase I)	3
1.0	Design Selection	4
2.0	Material Selection	7
3.0	Design Analysis	7
4.0	Hardware Design	8
5.0	Hardware Fabrication	8
6.0	Development Verification Test Procedure	8
7.0	Development Tests	8
8.0	Acceptance Test Procedure	8
9.0	Qualification Test Procedure	12
10.0	Phase I Approval	
IV	Phase II	13
1.0	Acceptance Test Plan	13
2.0	Acceptance Tests	13
V	Pre-Flight Certification Tests (Phase III)	
1.0	Valve Qualification Tests	14
VI	Results and Conclusions	16
1.0	Results	16
2.0	Conclusions	18

SECTION I

INTRODUCTION

This report presents the results of a program to develop, manufacture, and qualify a relief valve assembly in accordance with MSFC Design Procurement Drawing 20 M 32254.

The valve is intended for use in the metabolic activity system of the biological experiments to be conducted in the Orbital Workshop (OWS) Vehicle.

The design was limited to the use of state-of-the-art techniques regarding valve design and fluid material compatibility.

The basic work performed and the three phases into which it was divided were as follows:

- | | |
|-----------|--|
| Phase I | Design, manufacture, and development test of one prototype relief valve. |
| Phase II | Manufacture of twelve relief valves per approved drawings of Phase I, two of which were used for pre-flight certification testing. |
| Phase III | The performance of pre-flight certification tests on two units. |

SECTION II

SUMMARY

The relief valve assembly development program described in this document was performed under Contract NAS 8-26358. The program achieved all of the established requirements; and in addition demonstrated that the valve, based on design used in this program, is capable of meeting even more stringent performance requirements for internal leakage and pressure band (reseat to full flow).

The first phase culminated with the design approval of the valve, based on the results of analyses and development tests performed. The Phase I effort consisted of several tasks as described in Section III of this report. The second phase work consisted of fabrication of the individual parts, assembly of the valves, functional operation checkout, and acceptance testing. The consistency of the test results demonstrated the valve's ability to meet the specified requirements on a production quantity basis. No changes of design were required as a consequence of this phase of the program.

The third phase of the program consisted of conducting all of the tests outlined in ER 834-4 "Qualification Test Procedure", as pre-flight certification tests.

The valve successfully passed all of the specified requirements outlined in the reference engineering report as documented in the Qualification Test Report, ER 834-6. There were no changes in design required for accomplishment of this part of the program.

SECTION III

Phase I - Design and Development

This phase of the program was devoted to the detail design, analysis, prototype fabrication, and test evaluation of the relief valve assembly.

The tasks involved in this phase were as follows:

<u>Task</u>	<u>Description</u>	<u>Document No.</u>	<u>Addendum</u>
1	Design Selection	ER 834-2	I
2	Materials Selection	ER 834-2	I
3	Design Analysis	ER 834-2	I
4	Layout, Detail Design, and Checking	Drawings listed in Drawing 834001	I
5	Prototype Hardware Fabrication and Assembly	ER 834-3	
6	Development Verification Test Procedure	ER 834-1 "A"	I
7	Development Verification Tests	ER 834-5	I
8	Acceptance Test Procedure	834002	I
9	Qualification Test Procedure	ER 834-4	I
10	Phase I Approval	C-26358-005	

1.0 DESIGN SELECTION


A survey was conducted during Phase I to take advantage of currently reported information pertaining to the design effort. The results of this review were integrated into the design analysis and had an important role in the selection of the inverted type valve.

The valve design configuration is an in-line inverted poppet-type relief valve. This valve design inverts the control element (refer to Figure 1) and seat of the conventional relief valve in such a way that the seat is spring-loaded closed against the control element (poppet). In this case, the seat loading spring (main spring) establishes the reference force which reacts against the increase in inlet (upstream) pressure. The seat and poppet move together, compressing the seat loading spring. As inlet pressure rises, the poppet is forced harder against the seat, increasing the seating pressure until the poppet strikes the stop pin. Inlet pressure, acting in the annular area between the bellows mean diameter and the seat diameter, moves the seat away from the now stationary poppet, causing the seat pressure to decrease rapidly until the valve opens.

As in conventional relief valves, the inverted type requires a positive seat load to prevent leakage. Below the minimum level required for sealing (established by the poppet-seat materials and seat geometric configuration), the valve starts to leak.

With the inverted relief valve, the actuation value of cracking pressure is much closer to the ideal cracking pressure than with the conventional valve. Figure 2 shows seating pressure versus inlet pressure for this inverted valve design and for an identical geometry conventional type. P_{sc} and P_{ic} are the actual dribble pressures for the standard and inverted design respectively.

Since the seating surface area is exceedingly small in comparison with the bellows area (240:1), the additional pressure force tending to open the valve after cracking is negligible and the valve does not open more than necessary to pass a required flow, and reseats very close to cracking pressure (0.10 to 0.40 psi lower). These characteristics render this valve design virtually chatter-free. Until the poppet reaches the stop pin, the seat-bellows assembly breathes like an accumulator, smoothing out minor pressure fluctuations.




DIRECTION OF FLOW

FIGURE 1

- | | |
|-------------------|------------------------|
| ① HOUSING | ⑥ POPPET SPRING |
| ② BELLOWS ASS'Y | ⑦ MAIN SPRING |
| ③ GUIDE RING | ⑧ END PLATE & STOP PIN |
| ④ SPRING RETAINER | |
| ⑤ POPPET | |

J. MORANDO
E-12-71

FIGURE 2 SEATING PRESSURE VS
INLET PRESSURE



2.0 MATERIAL SELECTION

An investigation was conducted to select materials for the poppet-seat sealing interface to meet the low leakage requirements with the small seating load available (leakage is measured 0.50 psi below reseal pressure). (Refer to NASA Specification 20 M 32254.) Based on the required load per square inch for the different candidate materials, the actuator bellows were sized to generate the necessary cracking force (reference Addendum I, ER 834-2). The final selection was made based on bellows availability and fluid media compatibility, namely, 304L CRES for the seat material and KEL-F per AMS 3650 for the poppet material.

3.0 DESIGN ANALYSIS

A design analysis was initiated concurrently with the design review and material selection. (Refer to Addendum I, ER 834-2.) The purpose of the analysis was to provide the basis for engineering decisions, relating to the hardware detail design, of the prototype valve to be built at the end of Phase I of the program. The design analysis was concerned with establishing the valve internal configuration and determining all critical dimensions and finishes as well as all major stress levels.

Additional subjects covered because of the specific requirements of this design included: bellows life prediction and critical pressures, pressure drop, environmental effects, and structural considerations.

3.1 Environmental Effects

The environmental analysis was limited to consideration of acceleration and vibration forces. (Refer to Addendum I, ER 834-2.)

3.2 Bellows Operational Life

The valve design includes a bellows assembly as a dynamic seal and actuator combination between the inlet and outlet pressure side. The bellows, therefore, is compressed when the valve is moved to the open position and at null when the valve is in the closed position. The inside diameter of the bellows is normally exposed to 7.0 psia with a proof pressure of 18 psia.

The outside and inside diameter of the bellows were restricted by valve geometry. Within these constraints, the bellows design was selected. The analysis is presented in Addendum I, ER 834-2.

3.4 Structural Analysis

The structural analysis was confined exclusively to critical stress levels and pressures. The analysis was directed toward demonstrating that a large enough safety factor existed in all cases. (Refer to Addendum I, ER 834-2.)

4.0 HARDWARE DESIGN

The hardware design consisted of: A layout drawing of the valve design and all detail, subassembly and assembly drawings as necessary for prototype fabrication and assembly. The valve drawing list is shown in Figure 3. The assembly drawing, 334001, is included in Addendum J.

5.0 HARDWARE FABRICATION

Phase I, hardware fabrication, consisted of the prototype fabrication of all the necessary parts for one valve assembly conforming to the approved drawings.

6.0 DEVELOPMENT VERIFICATION TEST PROCEDURE

The development verification test procedure was prepared in accordance with the contract requirements specified in NASA Specification 20 M 32254. All of the details regarding this procedure can be found in Addendum I, ER 834-1, Revision "A".

7.0 DEVELOPMENT TESTS

The results of the development tests are presented in Table I. A more detailed discussion is included in Addendum I, ER 834-5. The prototype valve tested, successfully completed all of the development tests specified.

8.0 ACCEPTANCE TEST PROCEDURE

The acceptance test procedure was prepared and submitted as Document 834002; it describes the tests to be performed on the valve to establish its performance capability.

PARTS LIST

ASSY. TITLE

VALVE ASSY, RELIEF

ASSY. P/N

834001

REV.

E

PREPARED BY
DATE

CHECKED BY
DATE

APPROVED BY
DATE

ITEM	ZONE	QTY.	DESCRIPTION	PART NO.	REV.	CODE IDENT	EFFECTIVITY		MATERIAL	SPECIFICATION
							FROM	TO		
1		1	VALVE ASSY	834001	E	01359				
2		1	VALVE BODY	834008	C	"			304 L CRES	QQ-S-763
3		1	BELLOWS ASSY	834010		"				
4		1	SEAT, BELLOWS PLT	834028	C	"			304 L CRES	QQ-S-763
5		1	BELLOWS, E. D.	834027		16519			NICKEL DEPOSITED	
6		1	END PLT. BELLOWS	834020		01359			304 L CRES	QQ-S-763
7		1	RING GUIDE	834007		"			TEFLON	AMS-3651
8		1	RETAINER SPRING	834013		"			304 L CRES	QQ-S-763
9		1	SPRING POPPET	834014	B	"			302 CRES	QQ-W-423 B
0		1	POPPET	834015		"			KEL-F	AMS-3650
1		1	RING DAMPER	834016		"			TEFLON	AMS-3651
2		1	SPRING MAIN	834017	A	"			302 CRES	QQ-W-423 B
3		1	FLANGE, OUTLET	834018		"			304 L CRES	QQ-S-763
4		1	TUBE, OUTLET	834019		"			321 CRES	MIL-T-8808
5		AIR	SHIM	834029		"			301/302/304 CRES	MIL-S-5059 COND A
6		AIR	SHIM	834030		"			301/302 CRES	MIL-S-5059 COND. A
7		1	STENCIL	834012		"				
8										
9										
0										
1										
2										
3										
4										
5										
6										
7										
8										
9										
0										

SHEET 1 OF 1
 PART NO. 834001
 9

FIG. 3

NOTES

Table 1
RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

NASA Specification 20M32254

S-W Part No. 834000

S/N _____

Date _____

Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
6.1	Examination of Product	Acceptable/ Non-acceptable	Acceptable (dimensional inspection included)	
6.2	Internal Proof Pressure	Acceptable/ Non-acceptable	Acceptable	
6.3	External Proof Pressure	Acceptable/ Non-acceptable	Acceptable	
6.4 (a)	Internal Static Leakage	36 scch maximum	2.70 scch	
6.4 (b)	External Static Leakage	1.0×10^{-6} sccs	Non detectable leakage	
6.5	Relief Operation	a) P outlet = 14.7 psia crack: 21.7 psia min. full flow: 23.7 psia max. reseat: 21.7 psia min.	a) crack: 23.05 psia full flow: 23.30 psia reseat: 22.80 psia	

FAIRCHILD HILLER
STRATOS-WESTERN
 1800 ROSECRANS AVENUE, MANHATTAN BEACH, CALIF. 90288



ER 834-7

Page No. 10

E-117A WB REV. 5/65

Table 1 (Continued)
RELIEF VALVE ASSEMBLY - DEVELOPMENT DATA

NASA Specification 20M32254

S/W Part No. 834000

S/N _____

Date _____

Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
6. 8	Vibration	Sinusoidal Acceptable Nonacceptable Lift-off Acceptable Nonacceptable Random Acceptable Nonacceptable Ref. 6. 5 crack: 7. 0 min. psig full flow: 9. 0 psig max. reseal: 7. 0 min. psig	Acceptable Acceptable Acceptable Leakage: 3. 4 scch 8. 0 psig 8. 5 psig 7. 85 psig	
6. 9	Life Cycle Repeat 6. 5 every 250 cycles	1000 cycles Ref. 6. 5 crack: 7. 0 psig min. full flow: 9. 0 psig max. reseal: 7. 0 psig min internal leakage: 36 scch	8. 0 psig 8. 55 psig 7. 85 psig 2. 7 scch	
6. 10	Burst 6. 10. 1 Non des- destructive 6. 10. 2 Collapse 6. 10. 3 Destructive	Rupture - No rupture Collapse - No collapse Rupture Pressure 72 psig	No rupture No collapse	

FAIRCHILD HILLER
STRATOS-WESTERN
 1800 ROBERTS AVENUE, MANHATTAN BEACH, CALIF. 90286



ER 834-7

Page No. 11

1-117A W3 REV. 5/55

9.0 QUALIFICATION TEST PROCEDURE

The qualification test procedure was prepared and submitted in ER 834-4. A more detailed discussion can be found in Section IV of this report.

10.0 PHASE I APPROVAL

Approval of Phase I was received on October 27, 1970, in Document C-26358-005.(Refer to Addendum I.)

SECTION IV

Phase II

Phase II of the program consisted of fabrication and acceptance testing of twelve valve assemblies in compliance with the drawings and documentation approved in Phase I.

1.0 ACCEPTANCE TEST PLAN

The acceptance test plan is included in Addendum I as Drawing No. 834002.

2.0 ACCEPTANCE TESTS

The acceptance test results of all tested valves are included in Addendum II. Two valves presented anomalies during acceptance tests and were reported in Reliability Malfunction Report (RMR) 3382 and RMR 3383. The failure analysis for the subject valves, as well as the laboratory report, are part of Addendum II.

SECTION V

Phase III - Pre-flight Certification Tests

1.0 VALVE QUALIFICATION TESTS

1.1 Units Selection

Two units were selected at random from the twelve units manufactured and acceptance tested in Phase II and submitted to pre-flight certification tests.

1.2 Test Procedure

The test procedure and the applicable requirements are described in Engineering Report ER 834-4, Addendum I of this report.

1.3 Testing Agencies

All of the tests were conducted at Approved Engineering Test Laboratories (AETL), Los Angeles, California, with the exception of the performance tests after the CCOH environmental tests that were performed at Fairchild Stratos Division.

The results of outside tests are given in detail in AETL Test Report 5330-00-9545, dated April 30, 1971, included in Addendum I of Report ER 834-6.

1.4 Test Results

Both unit successfully completed all of the tests listed in Table 2, and, in all cases, exceeded the requirements listed in the qualification test procedure or the corresponding paragraph of NASA Specification 20 M 32254.

The results of all these tests were given in detail in Stratos Engineering Report ER 834-6.

TABLE 2			
Valve "A" SN005	Valve "B" SN012	Report ER 834-4 Para. No.	NASA Spec. 20M32254 Para. No.
Corrosion contaminants oxygen/humidity test (CCOH)	Corrosion contaminants oxygen/humidity test (CCOH)	5.1.1	4.3.4.1
Performance	Performance	5.2.1 to 5.2.3	4.3.3.3 and 4.3.3.4
High Temperature	High Temperature	5.1.2	4.3.4.3
Performance	Performance	5.2.1 to 5.2.3	4.3.3.3 and 4.3.3.4
Low Temperature	Low Temperature	5.1.3	4.3.4.4
Performance	Performance	5.2.1 to 5.2.3	4.3.3.3 and 4.3.3.4
Vibration	Vibration	5.1.4 a), b), c), & d)	4.3.4.6 (a), (b), (c), & (d)
Performance	Performance	5.2.1 to 5.2.3	4.3.3.3 and 4.3.3.4
Life Cycle	Life Cycle	5.1.5	4.3.4.8
Performance each 250 cycles	Performance each 250 cycles	5.2.1 to 5.2.3	4.3.3.3 and 4.3.3.4
Performance after 1000cycles	Performance after 1000 cycles	5.2.1 to 5.2.5	4.3.3.1, 4.3.3.2, 4.3.3.3, 4.3.3.4
Collapse Pressure	Collapse Pressure	5.1.6	4.3.4.10
Burst Pressure		5.1.7	4.3.4.9.1
	Ultimate Pressure	5.1.8	4.3.4.9.2

SECTION VI

RESULTS AND CONCLUSIONS

This section summarizes the results which were reported in Sections II and III, and it draws conclusions which are based on these results.

1.0 RESULTS

The results of the program effort are presented here in terms of their effect on the functional capacity of the valve.

1.1 Internal Leakage

The ability to achieve a closure leakage of less than 1×10^{-3} SCCS, under inlet pressure conditions in very close proximity to cracking pressure was demonstrated. Production testing showed a marked consistency in the internal leakage test results, that corroborated the findings of development testing.

1.2 Valve Pressure Drop Versus Flow Rate

The tested valves demonstrated that pressure drop at full flow condition was well below the maximum specified, to the extent that a change in the specification doubling the maximum flow rate (from 300 scim to 600 scim) was achieved without the need of any design changes.

1.3 Performance

The specified value of 2.0 psi band from reseal to full flow was met with ample margin in all valves tested. In general, the reseal to full flow band was $0.50 < \Delta P < 0.80$ psi with the variation due almost exclusively to friction in the guide rings (see Figure 1 and Table 3).

1.4 Contamination

Despite the small forces available, valve seating forces are sufficiently high to assure good closure even under contaminated conditions (refer to ER 834-5). Flow cycle life demonstrated that a 10 micron filter is effective in protecting the sealing surfaces from impairment due to contaminants.

Table 3. Summary of Production Acceptance Tests

Unit S/N	Crack Pressure (psig)	Reseat Pressure (psig)	$\Delta C - R$	Full Flow Pressure (psig)	$\Delta F - R$	Internal Leakage (scch)
12	8.30	7.80	0.50	8.60	0.80	0.30
11	8.50	8.40	0.10	8.90	0.50	0.90
10	8.00	7.90	0.10	8.30	0.40	0.12
9	8.00	7.80	0.20	8.30	0.50	N.D.
8	8.00	7.90	0.10	8.40	0.50	0.90
7	8.60	8.20	0.40	8.90	0.70	7.20
6	7.80	7.60	0.20	8.10	0.50	N.D.
5	7.90	7.80	0.10	8.30	0.50	N.D.
4	8.30	8.20	0.10	8.50	0.30	0.60
3	7.80	7.60	0.20	7.90	0.30	2.40

2.0 CONCLUSIONS

The results presented above lead to the following conclusion:

The present design has proven sound and no design changes, improvements, or modifications are deemed necessary to meet the present specification requirements. The design has capability to meet more stringent requirements as is, or with slight modifications.


FAIRCHILD HILLER
STRATOS-WESTERN
1800 ROSECrans AVENUE, MANHATTAN BEACH, CALIF. 90288

Page No.

ER 834-7

ADDENDUM I

REPORT NO. ER 834-1
DEVELOPMENT VERIFICATION TEST
PROCEDURE FOR

RELIEF VALVE ASSEMBLY

Stratos-Western P/N 834000
NASA Spec. No. 20M32254

J. Amelsberg
Prepared By: J. Amelsberg, Product Engineer

J. Morando
Approved By: J. Morando, Product Manager

J. Feld
Approved By: J. Feld, Chief Engineer

28 July 1970
Rev. A - 21 September 1970



FAIRCHILD HILLER
STRATOS - WESTERN
1800 ROSECRANS AVENUE
MANHATTAN BEACH, CALIF. 90267

CHANGE RECORD

REV.	SECTION	PAGE	DESCRIPTION	DATE/ APPROVAL
A	Cover		Reflects "A" revision	
	3.1	1	George C. Marshall Space Flight Center Report 20M32254 - Valve Assembly, Relief WAS "2AM32254"	
	6.1	5	"---requirements outlined in paragraph 3.5---" WAS "--- requirements outlines in paragraph 3.5 ---"	
	6.5	6	"---- outlet pressure of 14.7 psia. The valve assembly shall fo from seat to full open to reseal at inlet pressures between 7.0 to 9.0 psi above outlet pressure. Full open is defined as the inlet pressure required to sustain a flow rate of 775 scim minimum of N ₂ at 70°F inlet temperature with an outlet pressure of 14.7 psia. NOTE: Test conditions of 23.7 psia inlet, 14.7 psia outlet and 775 scim are equivalent to 9 psia inlet, 0 psia outlet and 300 scim." WAS "---outlet pressure of 14.7 psia. The cycles shall then be repeated with an outlet pressure of 4 psia max. The valve assembly shall go from seat to full open to reseal at inlet pressures between 7.0 to 9.0 psi above outlet pressure. Full open is defined as the inlet pressure required to sustain a flow rate of 300 scim minimum of N ₂ at 70°F inlet temperature with an outlet pressure of 1 x 10 ⁻⁶ Torr. When tests are conducted at 14.7 psia outlet pressure the flow shall be 775 scim minimum of N ₂ at 70°F. The test setup shall be as shown in figure 5."	
	6.6	6	"--- in accordance with 6.5. The test setup shall ---" WAS "--- in accordance with 6.5 except outlet pressure shall always be 14.7 psia. The test setup shall ---"	
	6.7	6	Same as change in paragraph 6.6 above.	

CHANGE RECORD				
REV.	SECTION	PAGE	DESCRIPTION	DATE/ APPROVAL
A	6.8	7 and 8	<u>Vibration</u> Completely revised and rewritten	
	6.9	8	"--- in accordance with 6.5." WAS "--- in accordance with 6.5 except outlet pressure shall always be 14.7 psia."	
	Figure 5	14	Revised schematic - Added "Calibrated for the corresponding outlet pressure."	
		15	Ref. paragraph 6.5 revised:	
				IS WAS
			a) P outlet	14.7 4.0 psia
		crack	21.7 11.0 psia max.	
		full flow	23.7 13.0 psia max.	
		reseat	21.7 11.0 psia max.	
		b) DELETED		
	Figure 6	17	Added new schematic "Figure 6. Component Vibration Axes."	

TABLE OF CONTENTS

PARAGRAPH	TITLE	PAGE
1.0	INTRODUCTION	1
2.0	PURPOSE	1
3.0	APPLICABLE DOCUMENTS	1
3.1	Listing	1
4.0	TEST FACILITIES	3
5.0	GENERAL TEST REQUIREMENTS	3
5.1	Order of Tests and Examinations	3
5.2	Test and Examination Conditions	3
5.3	Test Medium	3
5.4	Cleanliness - Test Equipment	4
5.5	Instrument Calibration	4
5.6	Test Data	
6.0	DEVELOPMENT VERIFICATION TESTS	5
6.1	Examination	5
6.2	Internal Proof Pressure	5
6.3	External Proof Pressure	5
6.4	Leakage	5
6.5	Relief Operation	6
6.6	High Temperature	6
6.7	Low Temperature	6
6.8	Vibration	7
6.9	Life Cycle	8
6.10	Burst Pressure	8

1.0 INTRODUCTION

This document describes the development tests to be performed on the Relief Valve Assembly, Part No. 834000.

2.0 PURPOSE

The purpose of these tests is to provide data for application in the design of the prototype units to be used in the qualification testing in accordance with NASA Specification 20M32254 Valve Assembly, Relief.

3.0 APPLICABLE DOCUMENTS.

3.1 Listing

The following documents, of the issue noted, form a part of this drawing to the extent specified herein. This document should prevail in case of conflict.

George C. Marshall Space Flight Center

20 M32254	Valve Assembly, Relief
MSFC-SPEC-101	Flammability Requirements and Test Procedures for Materials in Gaseous Oxygen Environments
MSFC-SPEC-135	Welding, Fusion, Specification for
MSFC-SPEC-164	Cleanliness of Components for use in Liquid Oxygen, Fuel and Pneumatic Systems, Specification for
MSFC-DWG-10509306	Radiographic Inspection Procedures and Acceptance Standards for Fusion Welded Joints in Stainless and Heat Resistant Steel, Specification for
MSFC-DWG-10509308	Welding, Carbon, Low Alloy, and Stainless Steel, Manual or Automatic, Specification for

Military Specifications

MIL-B-5087B	Bonding, Electrical, and Lightning Protection, for Aerospace Systems
MIL-C-5541	Chemical Films and Chemical Films Materials for Aluminum and Aluminum Alloys
MIL-A-8625	Anodic Coatings for Aluminum and Aluminum Alloys

Military Standards

MIL-STD-130	Identification Marking of U. S. Military Property
MIL-STD-143	Specifications and Standards, Order of Precedence for the Selection of
MIL-STD-810B	Environmental Test Methods for Aerospace and Ground Equipment
MIL-STD-831	Test Reports, Preparation of
MS-33586	Metal, Definition of Dissimilar

George C. Marshall Space Flight Center Standards

MSFC-STD-100	Castings, Aluminum and Magnesium Alloy, Radiographic Inspection of, Acceptance Standard for
MSFC-STD-105	Synthetic Rubber, Age Control of, Standard for

George C. Marshall Space Flight Center Publications

MSFC Engineering Standards Manual

Identification for Traceability (Quality and Reliability Assurance Laboratory).

Manned Spacecraft Center Publications

MSC-D-NA-0002 Procedures and Requirements for the
Flammability and Offgassing Evaluation
of Manned Spacecraft Nonmetallic Materials

4.0 TEST FACILITIES

The testing shall be performed at Stratos-Western Facilities,
Manhattan Beach, California, unless otherwise noted.

5.0 GENERAL TEST REQUIREMENTS

5.1 Order of Tests and Examinations.

The order of tests and examinations shall be as specified
herein.

5.2 Test and Examination Conditions.

Unless otherwise specified the tests and examinations shall
be performed under conditions as follows:

- a) Temperature - Standard temperature, 77°(± 18) F.
- b) Relative humidity - 95 percent maximum
- c) Atmospheric pressure - 14.7 (±0.7) pounds per square
inch absolute (psia)

Tests shall be conducted under the conditions of Specification
MIL-STD-810B, except as modified herein.

Equipment used to measure the unit parameters shall have an
accuracy of one order of magnitude (factor of ten) greater than
the required accuracy of the measurement to be made
within state-of-the-art limitations.

5.3 Test Medium.

Unless otherwise specified in the individual tests, the test
fluids used shall be as follows:

1. Nitrogen propellant pressurizing agent per MIL-P-27401
2. Helium propellant pressurizing agent per MIL-P-27407-1
3. Air

All fluids shall be passed through a 5 micron absolute level filter prior to entry into the test specimen.

5.4 Cleanliness - Test Equipment.

The level of cleanliness of the test equipment shall be such as to preclude damage to, or malfunction of the test specimen by contamination.

5.5 Instrument Calibration.

All inspection and measuring test equipment shall be calibrated against secondary standards which have been calibrated against primary standards by the National Bureau of Standards or an acceptable testing organization. Records shall be maintained including the data of last calibration. The due date shall be displayed on each item.

5.6 Test Data.

A note book type test log shall be kept throughout the testing. Each test shall be described in detail. All test data shall be recorded accurately and clearly.

The test data shall include, but is not limited to the following information.

1. Test agencies and personnel.
2. Test facilities location
3. Test schematic including control equipment
4. Equipment list
5. Test and measuring tolerances
6. Detail procedure
7. Accurate description and identification of test vehicle.

8. Strip charts shall be marked to show calibration and date.

6.0 DEVELOPMENT VERIFICATION TESTS

The unit shall be subjected to testing in the manner described. No deviation from these test sequence or procedures shall be made without prior project approval.

6.1 Examination.

The valve assembly shall be examined to check conformance to drawing number 834001.

All valve construction methods shall meet the requirements outlined in paragraph 3.5 of specification 20M32254.

6.2 Internal Proof Pressure.

The inlet and outlet ports of the valve assembly shall be slowly, pneumatically pressurized to 18 psig. This pressure shall be held for five minutes before reducing to zero. The valve assembly shall not present any sign of damage or permanent deformation. The test setup shall be as shown in figure 1.

6.3 External Proof Pressure.

The exterior of the valve assembly shall be slowly, pneumatically pressurized to 70 psig with the inlet and outlet ports at zero psig. This pressure shall be held for five minutes before reducing to zero. The valve assembly shall not present any sign of damage or permanent deformation. The test setup shall be as shown in figure 2.

6.4 Leakage.

Leakage testing shall be as follows:

- a) Inlet - The inlet port shall be pressurized to 6.5 psig with air, or N₂. The valve assembly shall not exceed a leakage flow rate of 1×10^{-2} sccs from the outlet port.

This shall be done three times with one crack,- reseal cycle minimum between tests. The test setup shall be as shown in figure 3.

- b) External - The exterior of the valve assembly shall be pressurized to 35 psig with air, H₂ or N₂. The valve assembly shall not exceed a leakage flow rate of 1.0×10^{-6} sccs from the inlet and outlet ports combined. The test setup shall be as shown in figure 4.

6.5 Relief Operation.

The valve assembly shall be tested to check for operational conformance through three cycles minimum from crack to full open back to reseal. These cycles shall be done with an outlet pressure of 14.7 psia. The valve assembly shall go from seat to full open to reseal at inlet pressures between 7.0 to 9.0 psi above outlet pressure. Full open is defined as the inlet pressure required to sustain a flow rate of 775 scim minimum of N₂ at 70°F inlet temperature with an outlet pressure of 14.7 psia.

NOTE: Test conditions of 23.7 psia inlet, 14.7 psia outlet and 775 scim are equivalent to 9 psia inlet, 0 psia outlet and 300 scim.

6.6 High Temperature.

The valve assembly shall be tested in accordance with Method 501, Procedure I, of Standard MIL-STD-810B except the exposure period at plus 160°F shall be four hours. Steps 4 and 5 of the procedure shall be deleted. After this the valve assembly shall be examined for failure and tested in accordance with 6.5. The test setup shall be as shown in figure 5.

6.7 Low Temperature.

The valve assembly shall be tested in accordance with Method 502, Procedure I, of MIL-STD-810B except that steps 4 and 5 of the procedure shall be deleted. The storage temperature shall be -40°F and the storage period shall be four hours. After this the valve assembly shall be examined for failure and tested in accordance with 6.5. The test setup shall be as shown in figure 5.

6.8 Vibration.

The valve assembly shall be installed in a test setup which simulates the vehicle installation. Vibration testing shall be as follows:

a) Vehicle dynamics criteria. The test setup shall be subjected to a sinusoidal scan at 3.0 octaves per minute along each of the three major axes, as indicated in figure 6. The levels and frequency ranges shall be as follows:

- (1) 3 to 7 Hz at 0.43 inches double amplitude displacement
- (2) 7 to 14 Hz at 1.1 g peak
- (3) 14 to 25 Hz at 0.11 inches double amplitude displacement
- (4) 25 to 60 Hz at 3.6 g peak

b) Sine evaluation criteria. The setup shall be subjected to a sinusoidal scan at 1.0 octave per minute along each of the three major axes, as indicated in figure 6. The levels and frequency ranges shall be as follows:

- (1) 20 to 100 Hz at 0.0020 inches double amplitude displacement.
- (2) 100 to 2000 Hz at 1.0 g peak

c) Lift-off random criteria. The test setup shall be subjected to 1.0 minute of random vibration along each of the three major axes, as indicated in figure 6. The levels shall be as follows:

- (1) 20 to 25 Hz at plus 10.0 db per octave
- (2) 25 to 80 Hz at 0.20 g² per Hz
- (3) 80 to 125 Hz at minus 6.0 db per octave
- (4) 125 Hz at 0.080 g² per Hz
- (5) 125 to 2000 Hz at minus 3.0 db per octave
- (6) 2000 Hz at 0.0050 g² per Hz

Composite equals 6.8 grms

d) Boost random criteria. The test setup shall be subjected to 2.0 minutes of random vibration along each of the major axes, as indicated in figure 6. The levels shall be as follows:

- (1) 20 Hz at 0.025 g^2 per Hz
- (2) 20 to 25 Hz at plus 10.0 db per octave
- (3) 25 to 80 Hz at 0.050 g^2 per Hz
- (4) 80 to 125 Hz at minus 6.0 db per octave
- (5) 125 Hz at 0.020 g^2 per Hz
- (6) 125 to 2000 Hz at minus 3.0 db per octave
- (7) 2000 Hz at 0.0012 g^2 per Hz

Composite equals 3.4 grms

At the conclusion of all vibration the valve assembly shall be examined for failure, and tested in accordance with 6.5 except outlet pressure shall always be 14.7 psia.

6.9 Life Cycle.

The valve assembly shall be subjected to 1000 cycles of operation. The cycles shall be from crack to full open back to reset. After every 250 cycles the valve assembly shall be examined for failure and tested in accordance with 6.5.

6.10 Burst Pressure.

6.10.1 Nondestructive.


The inlet and outlet ports of the valve assembly shall be slowly pressurized to 36 psig. This pressure shall be held for three minutes before reducing to zero. The valve assembly shall not present any signs of rupture.

6.10.2 Collapse Pressure.

The exterior of the valve assembly shall be slowly pressurized to 140 psig with the inlet and outlet ports at zero psig. This pressure shall be held for three minutes before reducing to zero. The valve assembly shall not present any signs of collapse


6.10.3 Destructive.

The inlet and outlet ports of the valve assembly shall be slowly pressurized to 36 psig. This pressure shall be held for three minutes. This pressure shall then be slowly increased until the valve assembly ruptures. The valve assembly shall rupture at 72 psig minimum.




1. Helium Pressure Source
2. Hand Valves
3. Pressure Gage 0-25 psig
4. Filter 5 μ or better
5. Mounting Fixture
6. Test Specimen

Figure 1. Internal Proof Pressure Schematic



1. Helium Pressure Source
2. Hand Valve
3. Pressure Gage 0-200 psig
4. Pressure Chamber
5. Mounting Fixture
6. Test Specimen.

Figure 2. External Proof Pressure Schematic



1. N₂ Pressure Source
2. Hand Valves.
3. Pressure Gage 0-25 psig
4. Filter 5 μ or better
5. Mounting Fixture
6. Test Specimen
7. Isobaric Volume Change Leakage Detector

Figure 3. Internal Static Leakage Schematic





Figure 4. External Static Leakage Schematic



- 1 N₂ Pressure Source
- 2 Hand Valves
- 3 Pressure Gage 0-25 psia
- 4 Filter 5 μ abs. or better
- 5 Piezometer or Equivalent
- 6 Differential Pressure Gage 0-10 psi
- 7 Mounting Fixture
- 8 Test Specimen
- 9 Flow Meter 0.02 to 1.00 scfm *
- 10 Thermocouples, 2-copper Constantan
- 11 Temperature Controller and Recorder
- 12 Temperature Chamber
- 13 3-Way Solenoid Valve

* The flow meter must be calibrated for the corresponding outlet pressure.

Figure 5. Relief Operation Schematic

RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

NASA Specification 20M32254		S-W Part No. 834000	S/N	Date
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
6.1	Examination of Product	Acceptable/Nonacceptable		
6.2	Internal Proof Pressure	Acceptable/Nonacceptable		
6.3	External Proof Pressure	Acceptable/Nonacceptabe		
6.4 (a)	Internal Static Leakage	36 scch maximum		
6.4 (b)	External Static Leakage	1.0 x 10 ⁻⁶ sccs		
6.5	Relief Operation	a) P outlet = 14.7 psia crack: 21.7 psia min. full flow: 23.7 psia max. reseat: 21.7 psia min.	a) crack: psia full flow: psia reseat: psia	

FAIRCHILD HILLER
STRATOS - WESTERN
 1800 ROSECRANS AVENUE, MANHATTAN BEACH, CALIF. 90266



ER 834-1 A

Page No. 15

2-117A WB REV 5/65

12
 E-1174 WB REV. 5/68

RELIEF VALVE ASSEMBLY - DEVELOPMENT DATA

NASA Specification 20M32254		S/W P/N 834000	S/N	Date
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
6.8	Vibration	Sinusoidal Acceptable Non-acceptable Lift-off Acceptable Non-acceptable Random Acceptable Non-acceptable Ref. 6.5 Crack: 7.0 min. psig Full Flow: 9.0 max. psig Reseat: 7.0 min. psig		
6.9	Life Cycle Repeat 6.5 every 250 cycles	1000 Cycles Ref. 6.5 Crack: 7.0 psig min. Full Flow: 9.0 psig max. Reseat: 7.0 psig min. Internal Leakage 36 scch		
6.10	Burst 6.10.1 Non-destructive 6.10.2 Collapse 6.10.3 Destructive	Rupture - No Rupture Collapse - No Collapse Rupture Pressure 72 psig		
Conclusions: Recommendations:				

FAIRCHILD HILLER
STATOS-WESTERN
 1800 ROSECRANS AVENUE, MANHATTAN BEACH, CALIF. 90286

Page No. 16
 ER 834-1 A




Figure 6. Component Vibration Axes.

REPORT NO. ER 834-2
DESIGN ANALYSIS VERIFICATION
FOR
RELIEF VALVE ASSEMBLY

STRATOS-WESTERN P/N 834000
NASA SPEC. NO. 20M32254

Prepared By: J. P. Amelsberg
J. Amelsberg, Product Engineer

Approved By: J. Morando
J. Morando, Product Manager

Approved By: J. Feld
J. Feld, Chief Engineer

31 July 1970


FAIRCHILD HILLER
STRATOS - WESTERN
1800 ROSECRANS AVENUE
MANHATTAN BEACH, CALIF. 90266

1.0 SCOPE

1.1 General

This design analysis verification establishes the assumptions and methods utilized in the dimensioning of Stratos-Western P/N 834000 relief valve assembly as set forth in NASA Spec. No. 20M32254.

1.2 Equipment Description

The relief valve assembly is intended to be used in the metabolic activity system of the Orbital Workshop (OWS).

2.0 GENERAL SPECIFICATION REQUIREMENTS

2.1 Working Pressures

2.1.1 Operational

- a) Internal 9 psig
- b) External 35 psig

2.1.2 Proof

- a) Internal 18 psig
- b) External 70 psig

2.1.3 Burst

- a) Internal 36 psig
- b) External 140 psig

2.2 Performance Requirements

2.2.1 Flow Rate

The flow shall be 300 scim of N₂ with an inlet pressure of 9.0 psia and an outlet pressure of 1×10^{-6} Torr at an inlet temperature of 70°F.

2.2.2 Operating Performance

The valve shall crack or reseal at a differential pressure of 7.0 psiΔ minimum and full flow at a differential pressure of 9.0 psiΔ maximum.

3.0 DESIGN ANALYSIS

3.1 Poppet Sizing

From paragraph 2.2.1.

Flow Rate : 300 scim GN₂

$$[1] \dot{W} = \frac{\text{scim} \times \text{Molecular Wt}}{4.01 \times 10^7}$$

Then:

$$\dot{W} = \frac{300 \times 28}{4.01 \times 10^7} = 2.095 \times 10^{-4} \text{ lbs/sec.}$$

P_{in} = 9.0 psia

P_{out} = 1 x 10⁻⁶ Torr

T_{in} = 70°F = 529.7°R ≈ 530°R

The flow equation for sonic flow condition is given by:

$$[2] \dot{W} = \frac{A P_{in} C_D \sqrt{gk \left(\frac{2}{k+1}\right)^{\frac{k+1}{k-1}}}}{\sqrt{RT}} \quad (\text{lbs/sec})$$

Where:

K = 1.4 specific heat ratio

$$R = \frac{1545}{\text{Molecular Wt.}} = \frac{1545}{28} = 55.2 \frac{\text{ft-lb}}{\text{lb}^\circ \text{R}}$$

C_D = 0.65 discharge coefficient

The orifice area required will then be:

$$[3] A = \frac{\dot{W} \sqrt{RT}}{P_{in} C_D S} \quad (\text{in}^2)$$

Where S is the sonic discharge constant for nitrogen ($P_2/P_1 < .528$)

$$[4] \quad S = \sqrt{gk \left(\frac{2}{k+1}\right)^{\frac{k+1}{k-1}}} = 3.88 \text{ ft}^{1/2} \text{ sec}^{-1}$$

Replacing in [3]

$$A = \frac{2.095 \times 10^{-4} \sqrt{55.2 \times 530}}{9.0 \times .65 \times 3.88} = 1.58 \times 10^{-3} \text{ in}^2$$

$$A = .00158 \text{ in}^2$$

$$d \approx .045 \text{ in}$$

The valve has been provided with four (4) .075 diameter orifices for flow passage through the valve poppet (see figure 1). The poppet seat diameter has been selected as:

$$D_{\text{seat}} = .175 \text{ in}$$

The required poppet stroke to obtain the minimum flow area is given by:

$$[5] \quad X_p = \frac{A}{\pi D_{\text{seat}}}$$

Replacing values:

$$X_p = \frac{.00158 \text{ in}^2}{3.14 \times .175 \text{ in}} = .0028 \text{ in}$$

$$\text{Selected } X_p = .015 \text{ in.}$$

3.2 Springs and Bellows Dimensioning

For the analysis that follows, refer to figure 1.

The following balance equations can be written:

A) The bellows will start to move at a pressure P_m given by:

$$[6] \quad P_m = \frac{F_{\text{assy 1}}}{A_B}$$

Where:

$F_{\text{assy 1}}$ = Assembly load of main spring

A_B = Bellows effective area = .403 in²

$P_m = 6.05$ psi adopted

Then:

$F_{assy1} = 6.05 \times .40 = 2.435$ lbs.

$F_{assy1} > \text{Max } G_{acc} \times M_D$

Where:

$M_D = \text{Dynamic mass} = .033$ lbs/g

$\text{Max } G_{acc} = 8$ g's

$F_{assy} > .033 \frac{\text{lbs}}{\text{g}} \times 8 \text{ g} = .264$ lbs.

The assembly load provided allows for almost 10 times the maximum vibration acceleration required.

B) At the moment the valve reaches cracking pressure, the balance equation is:

$$[7] \quad F_{assy1} + (R_1 + R_B) X_1 + F_{assy2} = P_C (A_B - A_P)$$

Where:

$A_P = \text{Poppet Area} = .024$ in.²

$R_1 = \text{Spring 1 Rate}$

$R_B = \text{Bellows Rate} = 2.00$ lbs/in.

$P_C = \text{Cracking pressure} = 7.8$ psi > 7.0 psi min.

$X_1 = \text{Bellows stroke: } .025$ in (adopted)

C) At full flow condition, the balance equation is:

$$[8] \quad F_{assy1} + F_{assy2} + (R_1 + R_B)(X_1 + X_p) + R_2 X_p = P_F (A_B - A_p)$$

Where:

$F_{assy2} = \text{Assembly load of poppet spring} = .30$ lbs.

$R_2 = \text{Spring 2 rate,}$ $A_p = \text{poppet area} = .024$ in.²

$X_p > .015$ in. poppet stroke $> .0028$ in min required.

$P_F = \text{Full open pressure} = 8.80$ psi < 9.0 psi max.

Subtracting 8 - 7

$$[9] (R_1 + R_2 + R_B) X_p = (P_F - P_C) (A_B - A_P)$$

$$[10] R_1 + R_2 \leq \frac{(P_F - P_C) (A_B - A_P)}{X_p} - R_B = 23 \text{ lbs/in.}$$

$$[11] R_1 \leq \frac{P_C (A_B - A_P) - F_{\text{assy1}} X_1 - F_{\text{assy2}}}{X_1} - R_B = 8.4 \text{ lbs/in.}$$

$$\therefore R_2 \leq 14 \text{ lbs/in.}$$

The spring rates adopted are:

$$R_1 = 8.0 \text{ lbs/in} \quad (X_1 = .026 \text{ in.})$$

$$R_2 = 4.0 \text{ lbs/in} \quad (X_p = .027 \text{ in.})$$

Note: These rates will provide a valve stroke with ample margin to meet flow requirements.

4.0 STRESS ANALYSIS

4.1 Component Parts

4.1.1 Main Spring

The spring total force is given by:

$$[12] F_T = F_{\text{assy1}} + R_1 (X_1 + X_p)$$

$$F_T = 2.400 + 8.0 (.050) = 2.800 \text{ lbs.}$$

The spring stress equation is given by:

$$[13] S_{\text{max}} = 2.55 \frac{F_T D_s K}{d^3}$$

Where:

D_s = Mean spring diameter . 520 in.

d = Wire diameter . 044 in.

$$K = \text{Wahl factor} = \frac{(4C-1)}{(4C-4)} + \frac{(.615)}{C} \quad [14]$$

$$C = \text{Spring index} = \frac{D}{d} = 11.8$$

Consequently:

$$K = \left(\frac{47.2-1}{47.2-4} \right) + \left(\frac{.615}{11.8} \right)$$

$$K = 1.07 + .052 = 1.122$$

Replacing in [13]

$$S_{\max} = \frac{2.55 \times 2.800 \times .520 \times 1.122}{8.55 \times 10^{-5}}$$

$$S_{\max} < 50,000 \text{ psi}$$

The maximum allowable stress for 302 CRES wire is 120,000 psi.

$$S_{\max} \ll S_{\text{allowable}}$$

4.1.2 Poppet Spring

The poppet spring selected has the following characteristics:

$$D_s = .250 \text{ in}$$

$$d = .024 \text{ in}$$

$$F_{\text{assy } 2} = .30 \text{ lbs.}$$

$$F_t = F_{\text{assy } 2} + R_2 X_P = .380 \text{ lbs}$$

$$C = \frac{.250}{.024} = 10.42$$

$$K = \left(\frac{41.7-1}{41.7-4} \right) + \left(\frac{.615}{19.42} \right) = 1.38$$

$$S_{\max} = \frac{2.55 \times .380 \times .250 \times 1.138}{1.38 \times 10^{-5}}$$

$$S_{\max} = 20,000 \text{ psi} \ll 120,000 \text{ psi}$$

4.1.3 Housing

At the larger diameter section:

$$[15] \quad S_T \text{ yield} = \frac{P_p D_{\max}}{2t}$$

P_p = Proof pressure S_t yield 304L : 28,000 psi

$$t \geq \frac{70 \times 1.00}{2 \times 28,000} = 1.25 \times 10^{-3} \text{ in}$$

$$t \geq .00125 \text{ in}$$

The minimum housing wall thickness has been established as $t = .034 \text{ in}$.

4.1.4 End Weld


For the end weld design, the following equation is used:

$$[16] P_{\text{proof}} = \left[\frac{4W}{D} \right] S_{T \cdot \text{yield}}$$

D = Weld joint diameter

W = Weld joint thickness

C_D = Diametral clearance



$$W = \frac{P_{\text{proof}} \times D}{4 S_t \text{ yield}}$$

P_{proof} (Internal) = 18 psig

$$W = \frac{18 \times 1.0}{4 \times 28,000} = 1.6 \times 10^{-4} \text{ in}$$

Adopted Weld Configuration

$$W = .015$$

$$H = .130$$

$$C_D = .003 \text{ max.}$$

4.1.4 Bellows Stability

Refer to Figure 1

The nominal pressure rating of the bellows is determined by

$$[17] P_R = \frac{1.25 \times 10^6 \times t^2}{(2h - t)^2}$$

Where:

$$h = \text{Convolution Height} = \frac{\text{O.D.} - \text{ID}}{2} = .132 \text{ in}$$

$$t = \text{Material Thickness} = .0010 \text{ in.}$$

$$P_R = 17.8 \text{ psi}$$

$$\text{Bellows Proof Pressure} = 1.75 P_R = 31.2 \text{ psi} > P_{\text{proof specified}}$$

$$P_{\text{burst}} = 2.5 P_R = 44.5 \text{ psi} > P_{\text{burst specified}}$$

Note: A teflon ring (3) has been provided on the bellows end plate-seat assembly (2) enclosing a gas volume that will serve as damping element, but pressure is allowed within the volume thru controlled clearance.

4.1.5 Bellows Hoop Stress

The bellows hoop stress is calculated by converting the total area per inch of bellows running length into a tube of equivalent wall thickness and using the standard equation for cylinder hoop stress.

The equivalent wall thickness is given by

$$t_e = nt \left[0.57 + \frac{2h}{e} \right]$$

$$t = \text{Thickness of one ply} = .001 \text{ in}$$

$$e = \text{pitch (length of one convolution)} = .058 \text{ in}$$

$$n = \text{No. of plies} = 1$$

$$h = \text{Height of a convolution} = \frac{D_o - D_i}{2} = .132 \text{ in}$$

$$t_e = .001 \left[0.57 + \frac{.264}{.058} \right] = .0051 \text{ in}$$

$$S_{\text{burst}}^{\text{max}} = \frac{P_B D_m}{2 t_e} \qquad S_{\text{proof}} = \frac{P_P D_m}{2 t_e}$$

$$D_m = \frac{D_o + D_i}{2} = .735$$

$$S_{\text{burst}} = 2580 \text{ psi} \qquad S_{\text{proof}} = 1290 \text{ psi}$$

$$S_{\text{burst}} \ll S_{PN_i}$$

Based on the stress levels determined in 4.1.4 and 4.1.5, the bellows expected cycle life will be:

$$L_C \gg 1 \times 10^8 \text{ cycles}$$

The specification requirement is 1×10^3 cycles

$$L_C \gg \text{Life Requirement}$$




FIGURE 1

REPORT ER 834-3
ASSEMBLY PROCEDURE
RELIEF VALVE ASSEMBLY

Stratos-Western P/N 834000

J. Amelsberg
Prepared By: J. Amelsberg, Senior Product Engineer

J. Morando
Approved By: J. Morando, Product Manager

R. V. Smith
Approved By: R. V. Smith, Staff Engineer, Reliability

30 September 1970


FAIRCHILD HILLER
STRATOS - WESTERN
1800 ROSEGRANS AVENUE
MANHATTAN BEACH, CALIF., 90267

1.0 INTRODUCTION

This document describes the procedure for assembling, adjusting, and pretesting the Relief Valve Assembly, Stratos-Western Part No. 834000.

2.0 APPLICABLE DOCUMENTS.

The following documents form a part of this document to the extent specified herein

Military

MIL-P-27401B	Propellant Pressurizing Agent, Nitrogen
--------------	--

NASA

Specification No. 20M32254	Specification for Relief Valve Assembly
-------------------------------	---

MSFC 164(4)	Cleanliness of Components for Use in Oxygen, Fuel and Penumatic System
-------------	---

Stratos-Western

999-331	Contamination Control Procedure
---------	---------------------------------

3.0 ASSEMBLY PROCEDURES

The unit shall be assembled and pretested in accordance with these procedures prior to final assembly.

3.1 Precleaning

All detail parts shall be precleaned in accordance with Stratos-Western Specification No. 999-331, with the following exceptions:

a) Part No. 834015, Kel-F material poppet shall only be exposed to these tests and sequences

- (1) Ultraviolet inspection
- (2) Swab with pluronic No. L62LF
- (3) Rinse with demineralized water

b) All remaining nonmetallic parts shall be cleaned per Specification No. 999-331, Section 'B', paragraph 4.3.

3.2 Preassembly Final Rinse

Qualitative tests are as follows:

a) Particulate contamination limits as taken from 500 milliliter minimum rinse sample:

Between 175 and 700 microns	Qty. 5 maximum
Between 700 and 2500 microns	Qty. 1 maximum
No particles greater than 2500 micron	

b) The nonvolatile residue shall not be greater than 0.001 grams per square foot of utilized fluid medium surface. This NVR shall be taken from the millipore rinse of the particulate count.

c) Immediately prior to assembling of unit, repeat ultraviolet inspection. No fluorescence of hydrocarbon smears shall be present.

REPRODUCIBILITY OF THE ORIGINAL PAGE IS POOR.


FAIRCHILD MILLER
STRATOS-WESTERN
1000 BROADWAY AVENUE, CHICAGO, ILL. 60601

Page No. 3

ER 834-3

3.3 Final Cleaning (After ATP)

- a) The unit shall be taken to the clean room.
 - b) Apply 10 psig of dry-filtered gaseous nitrogen to the inlet of the relief valve for 1 minute through a 2 micron absolute filter
 - c) After the first minute - stop - and insert a millipore and bomb downstream of the valve outlet. Purge unit again for one minute. Stop.
 - d) Remove and read the millipore pad. Particulate count must meet the particulate count limits of paragraph 3.2 (a)
 - e) Ultraviolet Examination: for hydrocarbon smears on exterior surface of the valve.
 - f) Visual Examination: inspect for exterior damage due to handling.
- Certified protective packaging shall be per Stratos-Western Specification No. 999-331, section 'B', paragraph 5.0.

4.0 PRELIMINARY ASSEMBLY

4.1 (Refer to drawing in figure 1.)

Install poppet (834015) in bellows assembly (834010), insert poppet spring (834014) and spring retainer (834013). Retain in place by using pin per MS51838-16 or equivalent. Measure force to start displacing the poppet from its seat. Add shims (834030) until the force required is equal to $F_0 = 0.70 \pm 0.02$ pounds.

NOTE: Extreme care must be taken in order not to damage the bellows:

The force to displace the poppet 0.010 inch shall be $F_g = 0.74 \pm 0.02$ pounds.

Finish assembling unit as shown in figure 1, using O-ring seals ARP568-016 and -019 installed in the location shown. After assembly retain unit together with assembly fixture shown in figure 2. Submit unit to pretest. Test for cracking pressure, full flow pressure, reseal pressure and leakage, in setup per figures 3 and 4. Reshim under the main spring (834017) with shims (834029) as necessary until the valve performance meets the requirements listed.

- a. Leakage at 6.5 psig inlet pressure 2×10^{-3} sccs
- b. Cracking pressure 7.5 psig minimum*
- c. Reseat pressure 7.5 psig minimum*
- d. Full flow pressure is the inlet pressure required to flow 775 scfm and shall not exceed 8.80 psig

All these values are to be met with an outlet pressure of 0 psig (14.7 psia).

4.2 Record final pretest performance, and number of shims required for poppet and main-springs.

* Cracking or reseating pressure is defined as the pressure required to sustain a flow of 50 scfm.




FIG 1



1	PIN	MS51833-16	16
1	SEAL, BUTYL	ARP563-016	15
1	SEAL, BUTYL	ARP563-019	14
A/R	SHIM	834030	13
A/R	SHIM	834029	12
1	TUBE, OUTLET	834019	11
1	FLANGE, OUTLET	834018	10
1	SPRING, MAIN	834017	9
1	RING, DAMPER	834016	8
1	POPPET	834015	7
1	SPRING, POPPET	834014	6
1	RETAINER, SPRING	834013	5
1	RING, GUIDE	834007	4
1	BELLOWS ASSY	834010	3
1	BODY, VALVE	834008	2
✓	VALVE ASSY	BASIC	1
QTY REQD	DESCRIPTION	PART NO.	ITEM

FIG 1






FIG 2



1. N₂ Pressure Source
2. Hand Valves.
3. Pressure Gage 0-25 psig
4. Filter 5 μ or better
5. Mounting Fixture
6. Test Specimen
7. Isobaric Volume Change Leakage Detector

Figure 3. Internal Static Leakage Schematic



- 1 N₂ Pressure Source
- 2 Hand Valves
- 3 Pressure Gage 0-25 psia
- 4 Filter 5 μ abs. or better
- 5 Piezometer or Equivalent
- 6 Differential Pressure Gage 0-10 psi
- 7 Mounting Fixture
- 8 Test Specimen
- 9 Flow Meter 0.02 to 1.00 scfm *

* The flow meter must be calibrated for the corresponding outlet pressure.

Figure 4 Relief Operation Schematic

QTP ER834 - 4

QUALIFICATION TEST
PROCEDURE

RELIEF VALVE ASSEMBLY

Stratos-Western P/N 834000
NASA Spec. No. 20M32254

Prepared by:

J. Amelsberg

J. Amelsberg, Product Engineer

Approved by:

R. Smith

R. Smith, Reliability Engineer

Approved by:

W. Wiegand

W. Wiegand, Test Supervisor

25 August 1970

Rev. A - 14 December 1970

Rev. B - 13 April 1971



FAIRCHILD HILLER
STRATOS - WESTERN
1800 ROSECRANS AVENUE
MANHATTAN BEACH, CALIF. 90266

<u>CHANGE RECORD</u>					
REV.	SECTION	PAGE	DESCRIPTION	DATE/ APPROVAL	
A	4.7	Title	CN 11254		
		5	Updated to A Revision - & Table of Contents Was: Flowmeter with 0 to 1.00 scfm range IS: Flowmeter with 0.2 to 1.30 scfm range		
	5.2.2	11		Was: Pressure gages: 0-50 psig, 0-10 psid, 0-25 psig IS: Pressure gages: 0-60 psig, 0-30 psid, 0-30 psid	
				Was: Pressurized to 35 psig with air, He, or N ₂ . IS: Pressurized to 35 psig with gaseous helium	
	5.2.3	11		Was: as shown in figure 1 IS: as shown in figure 4	
				Was: Flowrate of 775 scim IS: Flowrate of 1550 scim Was: sustained flowrate of 300 scim IS: Sustained flowrate of 600 scim.	
	5.2.5	11		NOTE: Was: Outlet and 775 scim IS: Outlet and 1550 scim.	
				Was: 0 psia outlet and 300 scim IS: 0 psia outlet and 600 scim.	
	Figure 1	13	Revised schematic		
	Figure 2	14	Revised Schematic		
Figure 3	15	Revised Schematic			
Figure 4	16	Revised Schematic			
Figure 5	17	Revised Schematic			
Figure 7	19	Revised Schematic			
	Test Logs	Sht. 1-18	Added to reflect actual tests		
B	5.2.3	11	WAS: Refer to figure 5. Repeat full open test once with an outlet pressure of 1×10^{-6} Torr. and minimum sustained flowrate of 600 scim Refer to figure 7. IS: Refer to figure 5. After performing the life cycle tests (para. 5.1.5) repeat a full open test once with a starting outlet pressure of 1×10^{-6} Torr. and a minimum sustained flowrate of 600 scim. Refer to figure 7. Changes Per CN 11587		

TABLE OF CONTENTS

1.0	Scope	1
	1.1 General	1
	1.2 Equipment Description	1
2.0	Applicable Documents	1
	2.1 Listing	1
3.0	Test Facilities	3
4.0	General Test Equipments	3
	4.1 General	3
	4.2 Data Recording	3
	4.3 Test and Failure Reporting	3
	4.4 Test Conditions and Equipment	4
	4.5 Cleanliness - Test Equipment	5
	4.6 Instrument Calibration	5
	4.7 Test Equipment	6
	4.8 Cleanliness Requisites	6
	4.9 Test Summary	7
5.0	Method of Testing	8
	5.1 Environmental Tests	8
	5.2 Performance Tests	10
	5.3 Completion of Tests	12
	5.4 Evidence of Satisfactory Valve	12
	5.5 Unsatisfactory Valve	12

LIST OF ILLUSTRATIONS

Figure		
1	Burst and Ultimate Pressure Schematic	13
2	Collapse Pressure Schematic	14
3	Internal Static Leakage Schematic	15
4	External Static Leakage Schematic	16
5	Relief Operation Schematic	17
6	Component Vibration Axes.	18
7	Relief Operation Schematic	19
	Test Logs - Sheets 1 through 18 (Reflect actual Tests)	1 - 18

1.0 SCOPE

1.1 General

This test plan establishes the conditions and procedures required for the qualification tests of the valve assembly, relief Stratos-Western part number 834000 as set forth in NASA specification 20M32254.

1.2 Equipment Description

The relief valve assembly is intended to be used in the metabolic activity system of the Orbital Workshop (OWS).

2.0 APPLICABLE DOCUMENTS

2.1 Listing

The following documents, of the issue noted, form a part of this drawing to the extent specified herein. This document should prevail in case of conflict.

George C. Marshall Space Flight Center

20M32254	Valve Assembly, Relief
MSFC-SPEC-101	Flammability Requirements and Test Procedures for Materials in Gaseous Oxygen Environments
MSFC-SPEC-135	Welding, Fusion, Specification for
MSFC-SPEC-164	Cleanliness of Components for use in Liquid Oxygen Fuel and Pneumatic Systems, Specifications for
MSFC-DWG-10509306	Radiographic Inspection Procedures and Acceptance Standards for Fusion Welded Joints in Stainless and Heat Resistant Steel, Specification for
MSFC-DWG-10509308	Welding, Carbon, Low Alloy, and Stainless Steel, Manual or Automatic, Specification for

Military Specifications

MIL-B-5087B	Bonding, Electrical, and Lightning Protection, for Aerospace Systems.
MIL-C-5541	Chemical Films and Chemical Films Materials for Aluminum and Aluminum Alloys
MIL-A-8625	Anodic Coatings for Aluminum and Aluminum Alloys

Military Standards

MIL-STD-130	Identification Marking of U. S. Military Property
MIL-STD-143	Specifications and Standards, Order of Precedence for the Selection of
MIL-STD-810B	Environmental Test Methods for Aerospace and Ground Equipment
MIL-STD-831	Test Reports, Preparation of
MS-33586	Metal, Definition of Dissimilar

George C. Marshall Space Flight Center Standards

MSFC-STD-100	Casting, Aluminum and Magnesium Alloy, Radiographic Inspection of, Acceptance Standard for
MSFC-STD-105	Synthetic Rubber, Age Control of, Standard for

George C. Marshall Space Flight Center Publications

MSFC Engineering Standards Manual

Identification for Traceability (Quality and Reliability Assurance Laboratory).

Manned Spacecraft Center Publications

MSC-D-NA-0002

**Procedures and Requirements for
the Flammability and Offgassing
Evaluation of Manned Spacecraft
Nonmetallic Materials**

3.0 TEST FACILITIES

The testing shall be performed at Stratos-Western Facilities, Manhattan Beach, California, unless otherwise noted.

4.0 GENERAL TEST REQUIREMENTS

4.1 General

The valve shall successfully meet the requirements, values and tolerances contained in section 5 of this test plan.

4.2 Data Recording

The results of the tests shall be recorded in the appropriate data sheets. Documentary data sheets shall be signed and retained for record purposes.

4.3 Test and Failure Reporting

4.3.1 Reliability Malfunction Reports. All malfunctions or failures observed during testing shall be immediately recorded on a Stratos-Western RMR form and reported by telephone to Stratos-Western Reliability Engineering. Subsequent test action shall be controlled by the instructions recorded on the RMR by Reliability Engineering.

4.3.2 Test Summary. Within five (5) days after completion of the valve qualification test, a test summary shall be prepared which will contain the following:

- a. Statement as to whether the unit passed or failed the test.
- b. If failure occurred, a failure analysis and proposed corrective action, which shall be subject to customer approval.

c. If retest is required, the extent of retest shall be specified by the customer, which shall not exceed the original requirement, and the next anticipated test date.

d. Sample of data.

4.3.3 Test Reports. Within thirty (30) days after completion of the valve qualification testing, a test report shall be prepared which will contain the following:

- a. Summary of results and conclusions.
- b. Description of test performed.
- c. Test conditions.
- d. List of test equipment and calibration data.
- e. Any test peculiarities or deviations.
- f. Reduced data and graphs.
- g. Original data sheets, including all test data from the time the valve was first presented for acceptance testing.

4.4 Test Conditions and Equipment

4.4.1 Order of Tests and Examinations. The order of tests and examinations shall be as specified herein.

4.4.2 Test and Examination Conditions. Unless otherwise specified the tests and examinations shall be performed under conditions as follows:

- a. Temperature = Standard temperature, $77^{\circ} (\pm 18^{\circ})\text{F}$.
- b. Relative humidity - 95 percent maximum.
- c. Atmospheric pressure - $14.7 (\pm 0.7)$ pounds per square inch absolute (psia).

Equipment used to measure the unit parameters shall have an accuracy of one order of magnitude (factor of ten) greater than the required accuracy of the measurement to be made within state-of-the-art limitations.

4.4.3 Test Medium. Unless otherwise specified in the individual tests, the test fluids used shall be as follows:

- a. Nitrogen propellant pressurizing agent for MIL-P-27401
- b. Helium propellant pressurizing agent for MIL-P-27407-1
- c. Air.

All fluids shall be passed through a 5 micron absolute level filter prior to entry into the test specimen.

4.5 Cleanliness - Test Equipment.

The level of cleanliness of the test equipment shall be such as to preclude damage to, or malfunction of the test specimen by contamination.

4.6 Instrument Calibration.

All inspection and measuring test equipment shall be calibrated against secondary standards which have been calibrated against primary standards by the National Bureau of Standards or an acceptance testing organization. Records shall be maintained including the date of last calibration. The due date shall be displayed on each item.

4.7 Test Equipment.

The following equipment or equivalents shall be used during testing:

- a. Air tight environmental chamber for leakage and vacuum tests.
- b. Mass spectrometer (CEC #24-120).
- c. Flow meter with 0.2 to 1.30 scfm range (Fisher and Porter).
- d. Temperature recorder -100°F to +200°F range (Honeywell Inc.).
- e. Pressure gages: 0-200 psig
0-60 psig, 0-25 psia, 0-30 psid
0-30 psig
0-500 psig
- f. Filter 5 micron absolute or better.



FAIRCHILD HILLER
STRATOS - WESTERN
1800 ROSECRANS AVE. MANHATTAN BEACH CALIF. 90266

Page No. 6

QTP ER834 - 4

- g. Hand valves (as required).
- h. Mounting fixture.
- i. Vacuum pump.
- j. Dew point monitor.
- k. Gas reservoir of 5000 inch³ minimum.
- l. Isobaric volume change leak detector.
- m. 3-way solenoid valve.

4.8 Cleanliness Requisites.

During testing, the cleanliness level of the valve shall be protected at all times. The inlet and outlet of the valve shall be protected by external filters having a 5 micron absolute rating, cleaned in accordance with 4.8.1. If filters cannot be directly attached to the valve, the intermediate fittings used shall be clean to the same cleanliness level as the valve. If pressure measurements, are required between the component and the external filters, the pressure tap shall also be provided with filters in accordance with the foregoing. The filters shall be applied to the valve in an area equivalent to clean room per 4.8.1 and shall not be removed until testing has been completed. Removal shall also take place under the same conditions. During testing, any other precautions necessary to assure that the valve will remain clean, shall be incorporated into the test procedure. Lint free gloves are to be worn whenever the unit is handled.

- 4.8.1 Cleanliness. The valve shall be thoroughly cleaned using procedures and equipment which will provide a valve which is clean to the level specified herein. The gases and liquids used in the process shall have been passed, finally, through a 5 micron absolute filter. The cleaning equipment shall be so arranged that contamination cannot get into the immediate area of the parts being cleaned. Fittings or tools which will come in contact with the parts being tested shall be cleaned to the same level of cleanliness as the parts. The parts shall be cleaned until the final rise solution contains no more than the number of particles shown below per 100 milliliter solution filtered through a standard HA millipore filter.

<u>Particle Size, Microns</u>	<u>Max. Number Particles</u>
10 - 25	120
25 - 40	80
40 - 80	20
80 - up	0

4.9 Test Summary.

The prototype valves shall be subjected to the acceptance tests procedure described in ATP 834002. After these tests the valves shall be identified as valve samples "A" and "B", and tests performed to each valve in the sequence shown in 4.9.1.

4.9.1 Listing.

<u>Valve "A"</u>	<u>Valve "B"</u>	<u>Paragraph</u>
Corrosive contaminants, oxygen/ humidity test (CCOH)		5.1.1
Performance	Performance	5.2.1 through 5.2.3
High Temperature	High Temperature	5.1.2
Performance	Performance	5.2.1 through 5.2.3
Low Temperature	Low Temperature	5.1.3
Performance	Performance	5.2.1 through 5.2.3
Vibration	Vibration	5.1.4
Performance	Performance	5.2.1 through 5.2.3
Life Cycle	Life Cycle	5.1.5
Performance (every 250 cycles)	Performance	5.2.1 through 5.2.3
Performance	Performance	5.2.4, 5.2.5.
Collapse Pressure	Collapse Pressure	5.1.6
Burst Pressure		5.1.7
	Ultimate Pressure	5.1.8

5.0 METHOD OF TESTING.

5.1 Environmental Tests.

5.1.1 Corrosive Contaminants, Oxygen/Humidity. The valve assembly shall be subjected to the environmental conditions of salt fog and oxygen/humidity in that order of sequence, with inlet and outlet ports capped.

The experiment hardware shall be exposed to a salt fog atmosphere for one hour in an unstowed configuration. The atmosphere shall be at ambient pressure, 90° to 97°F, and 85 +15, -10%, relative humidity. The salt solution shall be 1% sodium chloride by weight with a pH of 6.5 to 7.2. At the conclusion of this period, the experiment hardware shall be transferred within one hour to a chamber capable of performing the oxygen/humidity test. This portion of the test shall require that the experiment hardware, in an operation configuration shall be subjected to a 95± 5% oxygen atmosphere, a pressure of 5 psia (unless otherwise specified), and a temperature of 85 ± 5°F for a period of 12 hours.

At the conclusion of the twelve-hour period, moisture shall be introduced into the chamber within the first hour to obtain a relative humidity of 95 ± 5%. This condition shall then be maintained for a time period of 119 hours and within a temperature range of 40 to 90°F. Operation of the experiment hardware while in operational configuration shall be as specified in the equipment certification test specification. At no time during the performance of this test shall the experiment hardware be wiped or dried of any moisture or salt solution.

5.1.2 High Temperature. The valve assembly shall be tested in accordance with method 501, Procedure I, of MIL-STD-810B, except steps 4 and 5 shall be deleted. The exposure time to + 160° F shall be four hours. Test setup should be per figure 5.

5.1.3 Low Temperature. The valve assembly shall be tested in accordance with method 502, procedure I, of MIL-STD-810B, except steps 4 and 5 shall be deleted. The storage temperature shall be -40°F and the storage period shall be four hours. Test setup should be per figure 5.

5.1.4 Vibration

- a) Vehicle dynamics criteria. The test setup shall be subjected to a sinusoidal scan at 3.0 octaves per minute along each of the three major axes as indicated in figure 6. The levels and frequency ranges shall be as follows:
- (1) 3 to 7 Hz at 0.43 inches double amplitude displacement
 - (2) 7 to 14 Hz at 1.1 g peak
 - (3) 14 to 25 Hz at 0.11 inches double amplitude displacement
 - (4) 25 to 60 Hz at 3.6 g peak.
- b) Sine evaluation criteria. The setup shall be subjected to a sinusoidal scan at 1.0 octave per minute along each of the three major axes as indicated in figure 6. The levels and frequency ranges shall be as follows:
- (1) 20 to 100 Hz at 0.0020 inch double amplitude displacement
 - (2) 100 to 2000 Hz at 1.0 g peak
- c) Lift-off random criteria. The test setup shall be subjected to 1.0 minute of random vibration along each of the three major axes as indicated in figure 6. The levels shall be as follows:
- (1) 20 to 25 Hz at plus 10.0 db per octave
 - (2) 25 to 80 Hz at 0.20 g^2 per Hz
 - (3) 80 to 125 Hz at -6.0 db per octave
 - (4) 125 Hz at 0.080 g^2 per Hz
 - (5) 125 to 2000 Hz at minus 3.0 db per octave
 - (6) 2000 Hz at 0.0050 g^2 per Hz

Composite equals 6.8 grms

d) Boost random criteria. The test setup shall be subjected to 2.0 minutes of random vibration along each of the major axes, as indicated in figure 6. The levels shall be as follows:

- (1) 20 Hz at 0.025 g^2 per Hz
 - (2) 20 to 25 Hz at +10.0 db per octave
 - (3) 25 to 80 Hz at 0.050 g^2 per Hz
 - (4) 80 to 125 Hz at -6.0 db per octave
 - (5) 125 Hz at 0.020 g^2 per Hz
 - (6) 125 to 2000 Hz at -3.0 db per octave
 - (7) 2000 Hz at 0.0012 g^2 per Hz
- Composite equals 3.4 grms.

- 5.1.5 Life Cycle. The valve assembly shall be subject to 1000 cycles of operation. The cycles shall be from crack to full open to reseal. The test setup shall be per figure 5.
- 5.1.6 Collapse Pressure. The exterior of the valve assembly shall be slowly pressurized to 140 psig with the inlet and outlet ports of the valve vented to ambient. This pressure shall be held for three minutes before reducing to zero. The valve shall show no evidence of rupture, collapsing or destructive failure. The test setup shall be per figure 2.
- 5.1.7 Burst Pressure. The inlet and outlet ports of the valve assembly shall be slowly pressurized to 36 psig. This pressure shall be held for three minutes before reducing to zero. The valve shall show no signs of rupture, or destructive failure. The test setup shall be per figure 1.
- 5.1.8 Ultimate Pressure. The inlet and outlet ports of the valve assembly shall be slowly pressurized to 36 psig; this pressure shall be held for three minutes. Pressure shall then be slowly increased until the valve assembly ruptures. The ultimate pressure at which failure occurs shall be recorded. The test setup shall be per figure 1.

5.2 Performance Tests.

NOTE: All test setups shown can be combined into a single test setup to maintain an uninterrupted testing sequence.

- 5.2.1 Internal Static Leakage. The inlet port shall be pressurized to 6.5 psig with air, or N_2 . The valve assembly shall not exceed a leakage flow rate of 1×10^{-2} secs from the outlet port.

This shall be done three times with one crack, reseal cycle minimum between tests. The test setup shall be as shown in figure 3.

- 5.2.2 External Static Leakage. The exterior of the valve assembly shall be pressurized to 35 psig with gaseous helium. The valve assembly shall not exceed a leakage flow rate of 1.0×10^{-6} sccs from the inlet and outlet ports combined. The test set-up shall be as shown in figure 4.
- 5.2.3 Relief Operation. The valve assembly shall be tested to check for operation conformance through three cycles minimum from crack to full open back to reseal. These cycles shall be done with an outlet pressure of 14.7 psia. The valve assembly shall go from crack to fully open to reseal at inlet pressures between 7.0 to 9.0 psi above outlet pressure. Full open is defined as the inlet pressure required to sustain a flow rate of 1550 scim minimum of N_2 at 70°F inlet temperature with an outlet pressure of 14.7 psia. Refer to figure 5. After performing the life cycle tests (para. 5.1.5) repeat a full open test once with a starting outlet pressure of 1×10^{-6} Torr. and a minimum sustained flowrate of 600 scim. Refer to figure 7.
- NOTE: Test conditions of 23.7 psia inlet, 14.7 psia outlet and 1550 scim are equivalent to 9 psia inlet, 0 psia outlet and 600 scim.
- 5.2.4 Internal Proof Pressure. The inlet and outlet ports of the valve assembly shall be slowly, pneumatically pressurized to 18 psig. This pressure shall be held for five minutes minimum before reducing to zero. There shall be no evidence of damage, excessive permanent distortion, or deterioration. Refer to figure 1.
- 5.2.5 External Proof Pressure. The exterior of the valve assembly shall be slowly, pneumatically pressurized to 70 psig with the inlet and outlet ports at zero psig. This pressure shall be held for five minutes minimum before reducing to zero. There shall be no evidence of damage, excessive permanent distortion, or deterioration. Refer to figure 2.



FAIRCHILD HILLER
STRATOS - WESTERN
1800 ROSECRANS AVE. MANHATTAN BEACH CALIF. 90265

Page No. 12

QTP ER 834 - 4

5.3 Completion of Tests


Upon completion of the test, record completion date and indicate satisfactory test of the valve in the log book.

5.4 Evidence of Satisfactory Valve

Upon completion of the test, sign the data sheets as evidence of satisfactory results.


5.5 Unsatisfactory Valve

Failure of the valve to meet the test requirements shall constitute cause for remedial action. A failure report shall be made of each failure encountered during the test. A failure analysis and remedial action shall be submitted for approval.




1. Helium Pressure Source
2. Hand Valve
3. Pressure Gauge, 0-60 psig or 0-500 psig
4. Filter 5m or better
5. Holding Fixture
6. Test Specimen
7. Filter 5m absolute or better

Figure 1. Burst and Ultimate Pressure Schematic




1. Helium Pressure Source
2. Hand Valve
3. Pressure Gauge, 0-200 psig
4. Pressure Chamber
5. Test Specimen
6. Filter 5 m absolute or better

Figure 2. Collapse Pressure Schematic




1. N₂ Pressure Source
2. Hand Valves.
3. Pressure Gage 0-30 psig
4. Filter 5 μ or better
5. Pressure Chamber
6. Test Specimen
7. Isobaric Volume Change Leakage Detector
8. Flow Meter 0.2 - 1.30 scfm

Figure 3. Internal Static Leakage Schematic



1. Helium Pressure Source
2. Hand Valve.
3. Pressure Gauge, 0-60 psig
4. Pressure Chamber
5. Test Specimen'
6. Mass Spectrometer CEC #24-120 or equivalent.
7. Filter 5 m absolute or better

Figure 4. External Static Leakage Schematic



- 1 N₂ Pressure Source
- 2 Hand Valves
- 3 Pressure Gage 0-25 psia
- 4 Filter 5 μ abs. or better
- 5 Plezometer or Equivalent
- 6 Differential Pressure Gage 0-30 psi
- 7 Mounting Fixture
- 8 Test Specimen
- 9 Flow Meter 0.2 to 1.30 scfm *
- 10 Thermocouples, 2-copper Constantan
- 11 Temperature Controller and Recorder
- 12 Temperature Chamber
- 13 3-Way Solenoid Valve

* The flow meter must be calibrated for the corresponding outlet pressure.

Figure 5. Relief Operation Schematic





Figure 6. Component Vibration Axes.



- 1 N₂ Pressure Source
- 2 Hand Valves
- 3 Pressure Gage 0-25 psia
- 4 Filter 5 μ abs. or better
- 5 Piezometer or Equivalent
- 6 Differential Pressure Gage 0-10 psi
- 7 Mounting Fixture
- 8 Test Specimen
- 9 Flow Meter 0.22 to 1.30 scfm*
- 10 Ullage Gas Reservoir 5000 inch³ minimum
- 11 Vacuum Pump
- 12 Thermocouples, 2-copper Constantan
- 13 Temperature Controller and Recorder
- 14 Temperature Chamber
- 15 3-Way Solenoid Valve

*Calibrated for the corresponding outlet pressure.

Figure 7. Relief Operation Schematic

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 1 OF 18

PART NO. <u>834000</u> PART NAME <u>Relief Valve Assembly</u> MODEL NO. _____ SERIAL NO. _____ DATE _____	TEST DOC. <u>ATP ER 834-4</u> REV. A TEST FIXTURE _____ CUSTOMER INSP. _____ GOV'T. INSP. _____ CO. INSP. _____		
INSPECTION			
<table style="display: inline-table; border: none;"> <tr> <td style="border: none; padding-right: 10px;">STRATOS</td> <td style="border: none;">CUST</td> </tr> </table>		STRATOS	CUST
STRATOS	CUST		

5.1 Environmental Tests

5.1.1 Corrosive Contaminants, Oxygen/Humidity

Salt Fog - 1 hour

Temperature _____ °F

Relative Humidity _____ %

PH _____

Oxygen - 12 hours

Oxygen _____ %

Pressure _____ psia

Temperature _____ °F

Humidity - 119 hours

Relative Humidity _____ %

Temperature _____ °F

Performance Tests (paragraph 5.2)

Internal Static Leakage (paragraph 5.2.1)

A. Inlet Port: 6.5 psig	Actual _____	psig
Internal Leakage: 0.01 sccs	Actual _____	sccs
B. Inlet Port: 6.5 psig	Actual _____	psig
Internal Leakage: 0.01 sccs	Actual _____	sccs
C. Inlet Port : 6.5 psig	Actual _____	psig
Internal Leakage: 0.01 sccs max.	Actual _____	sccs

External Static Leakage (paragraph 5.2.2)

External Pressure: 35 psig Actual _____ psig

External Leakage: 1 x 10⁻⁶ sccs max. Actual _____ sccs

REMARKS: _____

TESTER _____

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 2 OF 18

PART NO. <u>834000</u> PART NAME <u>Relief Valve Assembly</u> MODEL NO. _____ SERIAL NO. _____ DATE _____	TEST SPEC. <u>QTP ER 834-4 A</u> TEST FIX _____ CUSTOMER _____ GOV'T. INSP. _____ CO. INSP. _____		
		INSPECTION	
		STRATOS	CUST.
<p>Relief Operation (paragraph 5.2.3)</p> <p>A. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p> Full Flow: 9.0 psid max. Actual _____ psid</p> <p> Reseat: 7.0 psid min. Actual _____ psid</p> <p>B. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p> Full Flow: 9.0 psid max. Actual _____ psid</p> <p> Reseat: 7.0 psid min. Actual _____ psid</p> <p>C. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p> Full Flow: 9.0 psid max. Actual _____ psid</p> <p> Reseat: 7.0 psid min. Actual _____ psid</p> <p>Repeat full flow test once with outlet pressure of 1×10^{-6} Torr. and minimum sustained flowrate of 600 scim.</p> <p> Full Flow: 9.0 max. Actual _____ psid</p>			
REMARKS: _____ _____ _____			
TESTER _____			

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 4 OF 18

PART NO. <u>834000</u> PART NAME <u>Relief Valve Assembly</u> MODEL NO. _____ SERIAL NO. _____ DATE _____	TEST SPEC. <u>QTP ER 834-4 A</u> TEST FIX _____ CUSTOMER _____ GOVT. INSP. _____ CO. INSP. _____		
		INSPECTION	
		STRATOS	CUST.

Relief Operation (paragraph 5.2.3)

A. Cracking Pressure: 7.0 psid min. Actual _____ psid
 Full Flow: 9.0 psid max. Actual _____ psid
 Reseat: 7.0 psid min. Actual _____ psid

B. Cracking Pressure: 7.0 psid min. Actual _____ psid
 Full Flow: 9.0 psid max. Actual _____ psid
 Reseat: 7.0 psid min. Actual _____ psid

C. Cracking Pressure: 7.0 psid min. Actual _____ psid
 Full Flow: 9.0 psid max. Actual _____ psid
 Reseat: 7.0 psid min. Actual _____ psid

Repeat full flow test once with outlet pressure of 1×10^{-6} Torr.
 and minimum sustained flowrate of 600 scim.

Full Flow: 9.0 max. Actual _____ psid

REMARKS: _____

TESTER _____

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 6 OF 18

PART NO. <u>834000</u> PART NAME <u>Relief Valve Assembly</u> MODEL NO. _____ SERIAL NO. _____ DATE _____	TEST SPEC. <u>QTP ER 834-4 A</u> TEST FIX _____ CUSTOMER _____ GOVT. INSP. _____ CO. INSP. _____		
		INSPECTION	
		STRATOS	CUST.
<p>Relief Operation (paragraph 5.2.3)</p> <p>A. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p>Full Flow: 9.0 psid max. Actual _____ psid</p> <p>Reseat: 7.0 psid min. Actual _____ psid</p> <p>B. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p>Full Flow: 9.0 psid max. Actual _____ psid</p> <p>Reseat: 7.0 psid min. Actual _____ psid</p> <p>C. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p>Full Flow: 9.0 psid max. Actual _____ psid</p> <p>Reseat: 7.0 psid min. Actual _____ psid</p> <p>Repeat full flow test once with outlet pressure of 1×10^{-6} Torr. and minimum sustained flowrate of 600 scim.</p> <p>Full Flow: 9.0 max. Actual _____ psid</p>			
REMARKS: _____ _____ _____			
TESTER _____			

FAIRCHILD HILLER STRATOS - WESTERN TEST LOG

SHEET 7 OF 18

<p>PART NO. <u>834000</u></p> <p>PART NAME <u>Relief Valve Assembly</u></p> <p>MODEL NO. _____</p> <p>SERIAL NO. _____</p> <p>DATE _____</p>	<p>TEST SPEC. <u>QTP ER 834-4 A</u></p> <p>TEST FIX _____</p> <p>CUSTOMER _____</p> <p>GOVT. INSP. _____</p> <p>CO. INSP. _____</p>		
		INSPECTION	
		STRATOS	CUST.
<p>5.1.4 <u>Vibration Tests</u></p> <p style="padding-left: 20px;">Sine: 1 min. per axes. Actual _____ min.</p> <p style="padding-left: 20px;">Liftoff Random: 1 min. per axes. Actual _____ min.</p> <p style="padding-left: 20px;">Boost Random: 2 min. per axes. Actual _____ min.</p> <p><u>Performance Tests (paragraph 5.2)</u></p> <p><u>Internal Static Leakage (paragraph 5.2.1)</u></p> <p>A. Inlet Port: 6.5 psig Actual _____ psig</p> <p style="padding-left: 40px;">Internal Leakage: 0.01 sccs max. Actual _____ sccs</p> <p>B. Inlet Port: 6.5 psig Actual _____ psig</p> <p style="padding-left: 40px;">Internal Leakage: 0.01 sccs max. Actual _____ sccs</p> <p>C. Inlet Port: 6.5 psig Actual _____ psig</p> <p style="padding-left: 40px;">Internal Leakage: 0.01 sccs max. Actual _____ sccs</p> <p>5.2.2 <u>External Static Leakage (paragraph 5.2.2)</u></p> <p style="padding-left: 40px;">External Pressure: 35 psig Actual _____ psig</p> <p style="padding-left: 40px;">External Leakage: 1×10^{-6} sccs max. Actual _____ sccs</p>			
<p>REMARKS:</p>			
<p>TESTER _____</p>			

**FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG**

SHEET 8 OF 18

PART NO. <u>834000</u> PART NAME <u>Relief Valve Assembly</u> MODEL NO. _____ SERIAL NO. _____ DATE _____	TEST SPEC. <u>QTP ER 834-4 A</u> TEST FIX _____ CUSTOMER _____ GOVT. INSP. _____ CO. INSP. _____		
		INSPECTION	
		STRATOS	CUST.
<p>Relief Operation (paragraph 5.2.3)</p> <p>A. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p>Full Flow: 9.0 psid max. Actual _____ psid</p> <p>Reseat: 7.0 psid min. Actual _____ psid</p> <p>B. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p>Full Flow: 9.0 psid max. Actual _____ psid</p> <p>Reseat: 7.0 psid min. Actual _____ psid</p> <p>C. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p>Full Flow: 9.0 psid max. Actual _____ psid</p> <p>Reseat: 7.0 psid min. Actual _____ psid</p> <p>Repeat full flow test once with outlet pressure of 1×10^{-6} Torr. and minimum sustained flowrate of 600 scim.</p> <p>Full Flow: 9.0 max. Actual _____ psid</p>			
REMARKS: _____			
TESTER _____			

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 9 OF 18

<table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:20%;">PART NO.</td> <td><u>834000</u></td> </tr> <tr> <td>PART NAME</td> <td><u>Relief Valve Assembly</u></td> </tr> <tr> <td>MODEL NO.</td> <td>_____</td> </tr> <tr> <td>SERIAL NO.</td> <td>_____</td> </tr> <tr> <td>DATE</td> <td>_____</td> </tr> </table>	PART NO.	<u>834000</u>	PART NAME	<u>Relief Valve Assembly</u>	MODEL NO.	_____	SERIAL NO.	_____	DATE	_____	<table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:20%;">TEST SPEC.</td> <td><u>QTP ER 834-4 A</u></td> </tr> <tr> <td>TEST FIX</td> <td>_____</td> </tr> <tr> <td>CUSTOMER</td> <td>_____</td> </tr> <tr> <td>GOVT. INSP.</td> <td>_____</td> </tr> <tr> <td>CO. INSP.</td> <td>_____</td> </tr> </table>	TEST SPEC.	<u>QTP ER 834-4 A</u>	TEST FIX	_____	CUSTOMER	_____	GOVT. INSP.	_____	CO. INSP.	_____
PART NO.	<u>834000</u>																				
PART NAME	<u>Relief Valve Assembly</u>																				
MODEL NO.	_____																				
SERIAL NO.	_____																				
DATE	_____																				
TEST SPEC.	<u>QTP ER 834-4 A</u>																				
TEST FIX	_____																				
CUSTOMER	_____																				
GOVT. INSP.	_____																				
CO. INSP.	_____																				
		INSPECTION																			
		STRATOS	CUST.																		
5.1.5	<u>Life Cycle Test</u> Cycle unit from crack to full open to reseal 250 cycles. Actual _____ cycles																				
5.2	<u>Performance Tests</u> (paragraph 5.2)																				
5.2.1	<u>Internal Static Leakage</u> (paragraph 5.2.1)																				
	A. Inlet Port: 6.5 psig	Actual _____ psig																			
	Internal Leakage: 0.01 sccs max.	Actual _____ sccs																			
	B. Inlet Port: 6.5 psig	Actual _____ psig																			
	Internal Leakage: 0.01 sccs max.	Actual _____ sccs																			
	C. Inlet Port: 6.5 psig	Actual _____ psig																			
	Internal Leakage: 0.01 sccs max.	Actual _____ sccs																			
5.2.2	<u>External Static Leakage</u> (paragraph 5.2.2)																				
	External Pressure: 35 psig	Actual _____ psig																			
	External Leakage: 1×10^{-6} sccs max.	Actual _____ sccs																			

REMARKS: _____

TESTER _____

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 10 OF 18

PART NO. <u>834000</u> PART NAME <u>Relief Valve Assembly</u> MODEL NO. _____ SERIAL NO. _____ DATE _____	TEST SPEC. <u>QTP ER 834-4 A</u> TEST FIX _____ CUSTOMER _____ GOV'T. INSP. _____ CO. INSP. _____		
		INSPECTION	
		STRATOS	CUST.

Relief Operation (paragraph 5.2.3)

A. Cracking Pressure: 7.0 psid min. Actual _____ psid
 Full Flow: 9.0 psid max. Actual _____ psid
 Reseat: 7.0 psid min. Actual _____ psid

B. Cracking Pressure: 7.0 psid min. Actual _____ psid
 Full Flow: 9.0 psid max. Actual _____ psid
 Reseat: 7.0 psid min. Actual _____ psid

C. Cracking Pressure: 7.0 psid min. Actual _____ psid
 Full Flow: 9.0 psid max. Actual _____ psid
 Reseat: 7.0 psid min. Actual _____ psid

Repeat full flow test once with outlet pressure of 1×10^{-6} Torr.
 and minimum sustained flowrate of 600 scim.

Full Flow: 9.0 max. Actual _____ psid

REMARKS: _____

TESTER _____

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 11 OF 18

<table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:20%;">PART NO.</td> <td><u>834000</u></td> </tr> <tr> <td>PART NAME</td> <td><u>Relief Valve Assembly</u></td> </tr> <tr> <td>MODEL NO.</td> <td>_____</td> </tr> <tr> <td>SERIAL NO.</td> <td>_____</td> </tr> <tr> <td>DATE</td> <td>_____</td> </tr> </table>	PART NO.	<u>834000</u>	PART NAME	<u>Relief Valve Assembly</u>	MODEL NO.	_____	SERIAL NO.	_____	DATE	_____	<table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:20%;">TEST SPEC.</td> <td><u>QTP ER 834-4 A</u></td> </tr> <tr> <td>TEST FIX</td> <td>_____</td> </tr> <tr> <td>CUSTOMER</td> <td>_____</td> </tr> <tr> <td>GOVT. INSP.</td> <td>_____</td> </tr> <tr> <td>CO. INSP.</td> <td>_____</td> </tr> </table>	TEST SPEC.	<u>QTP ER 834-4 A</u>	TEST FIX	_____	CUSTOMER	_____	GOVT. INSP.	_____	CO. INSP.	_____
PART NO.	<u>834000</u>																				
PART NAME	<u>Relief Valve Assembly</u>																				
MODEL NO.	_____																				
SERIAL NO.	_____																				
DATE	_____																				
TEST SPEC.	<u>QTP ER 834-4 A</u>																				
TEST FIX	_____																				
CUSTOMER	_____																				
GOVT. INSP.	_____																				
CO. INSP.	_____																				
		INSPECTION																			
		STRATOS	CUST.																		
<p>5.1.5 <u>Life Cycle Test (Continued)</u></p> <p align="center">Cycle unit from crack to full open to reseal 250 cycles.</p> <p>Performance Tests (paragraph 5.2) Actual _____ cycles.</p> <p>Internal Static Leakage (paragraph 5.2.1)</p> <p>A. Inlet Port: 6.5 psig Actual _____ psig</p> <p> Internal Leakage: 0.01 sccs max. Actual _____ sccs</p> <p>B. Inlet Port: 6.5 psig Actual _____ psig</p> <p> Internal Leakage: 0.01 sccs max. Actual _____ sccs</p> <p>C. Inlet Port: 6.5 psig Actual _____ psig</p> <p> Internal Leakage: 0.01 sccs max. Actual _____ sccs</p> <p>5.1 External Static Leakage (paragraph 5.2.2)</p> <p> External Pressure: 35 psig Actual _____ psig</p> <p> External Leakage: 1×10^{-6} sccs max. Actual _____ sccs</p>																					
REMARKS: _____																					
TESTER _____																					

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 12 OF 18

PART NO. <u>834000</u> PART NAME <u>Relief Valve Assembly</u> MODEL NO. _____ SERIAL NO. _____ DATE _____	TEST SPEC. <u>QTP ER 834-4 A</u> TEST FIX _____ CUSTOMER _____ GOVT. INSP. _____ CO. INSP. _____				
<table border="1" style="float: right; border-collapse: collapse;"> <tr> <th colspan="2" style="text-align: center;">INSPECTION</th> </tr> <tr> <td style="width:50%; text-align: center;">STRATOS</td> <td style="width:50%; text-align: center;">CUST.</td> </tr> </table>		INSPECTION		STRATOS	CUST.
INSPECTION					
STRATOS	CUST.				

Relief Operation (paragraph 5. 2. 3)

A. Cracking Pressure: 7. 0 psid min. Actual _____ psid
 Full Flow: 9. 0 psid max. Actual _____ psid
 Reseat: 7. 0 psid min. Actual _____ psid

B. Cracking Pressure: 7. 0 psid min. Actual _____ psid
 Full Flow: 9. 0 psid max. Actual _____ psid
 Reseat: 7. 0 psid min. Actual _____ psid

C. Cracking Pressure: 7. 0 psid min. Actual _____ psid
 Full Flow: 9. 0 psid max. Actual _____ psid
 Reseat: 7. 0 psid min. Actual _____ psid

Repeat full flow test once with outlet pressure of 1×10^{-6} Torr.
 and minimum sustained flowrate of 600 scim.

Full Flow: 9. 0 max. Actual _____ psid

REMARKS: _____

TESTER _____

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 13 OF 18

<table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:15%;">PART NO.</td> <td><u>834000</u></td> </tr> <tr> <td>PART NAME</td> <td><u>Relief Valve Assembly</u></td> </tr> <tr> <td>MODEL NO.</td> <td>_____</td> </tr> <tr> <td>SERIAL NO.</td> <td>_____</td> </tr> <tr> <td>DATE</td> <td>_____</td> </tr> </table>	PART NO.	<u>834000</u>	PART NAME	<u>Relief Valve Assembly</u>	MODEL NO.	_____	SERIAL NO.	_____	DATE	_____	<table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:15%;">TEST SPEC.</td> <td colspan="2"><u>QTP ER 834-4 A</u></td> </tr> <tr> <td>TEST FIX</td> <td colspan="2">_____</td> </tr> <tr> <td>CUSTOMER</td> <td colspan="2">_____</td> </tr> <tr> <td>GOVT. INSP.</td> <td colspan="2">_____</td> </tr> <tr> <td>CO. INSP.</td> <td>_____</td> <td align="center">INSPECTION</td> </tr> <tr> <td></td> <td align="center">STRATOS</td> <td align="center">CUST.</td> </tr> </table>	TEST SPEC.	<u>QTP ER 834-4 A</u>		TEST FIX	_____		CUSTOMER	_____		GOVT. INSP.	_____		CO. INSP.	_____	INSPECTION		STRATOS	CUST.
PART NO.	<u>834000</u>																												
PART NAME	<u>Relief Valve Assembly</u>																												
MODEL NO.	_____																												
SERIAL NO.	_____																												
DATE	_____																												
TEST SPEC.	<u>QTP ER 834-4 A</u>																												
TEST FIX	_____																												
CUSTOMER	_____																												
GOVT. INSP.	_____																												
CO. INSP.	_____	INSPECTION																											
	STRATOS	CUST.																											
5.1.5	<p><u>Life Cycle Test (Continued)</u></p> <p> Cycle unit from crack to full open to reseal 250 cycles.</p> <p>Performance Tests (paragraph 5.2) Actual _____ cycles</p> <p>Internal Static Leakage (paragraph 5.2.1)</p> <p>A. Inlet Port: 6.5 psig Actual _____ psig</p> <p> Internal Leakage: 0.01 sccs max. Actual _____ sccs</p> <p>B. Inlet Port: 6.5 psig Actual _____ psig</p> <p> Internal Leakage: 0.01 sccs max. Actual _____ sccs</p> <p>C. Inlet Port: 6.5 psig Actual _____ psig</p> <p> Internal Leakage: 0.01 sccs max. Actual _____ sccs</p> <p>External Static Leakage (paragraph 5.2.2)</p> <p> External Pressure: 35 psig Actual _____ psig</p> <p> External Leakage: 1×10^{-6} sccs max. Actual _____ sccs</p>																												
<p>REMARKS: _____</p>																													
<p>TESTER _____</p>																													

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 14 OF 18

PART NO. <u>834000</u> PART NAME <u>Relief Valve Assembly</u> MODEL NO. _____ SERIAL NO. _____ DATE _____	TEST SPEC. <u>QTP ER 834-4 A</u> TEST FIX _____ CUSTOMER _____ GOVT. INSP. _____ CO. INSP. _____		
		INSPECTION	
		STRATOS	CUST.

Relief Operation (paragraph 5.2.3)

A. Cracking Pressure: 7.0 psid min. Actual _____ psid
Full Flow: 9.0 psid max. Actual _____ psid
Reseat: 7.0 psid min. Actual _____ psid

B. Cracking Pressure: 7.0 psid min. Actual _____ psid
Full Flow: 9.0 psid max. Actual _____ psid
Reseat: 7.0 psid min. Actual _____ psid

C. Cracking Pressure: 7.0 psid min. Actual _____ psid
Full Flow: 9.0 psid max. Actual _____ psid
Reseat: 7.0 psid min. Actual _____ psid

Repeat full flow test once with outlet pressure of 1×10^{-6} Torr.
 and minimum sustained flowrate of 600 scim.

Full Flow: 9.0 max. Actual _____ psid

REMARKS: _____

TESTER _____

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 15 OF 18

<p>PART NO. <u>834000</u></p> <p>PART NAME <u>Relief Valve Assembly</u></p> <p>MODEL NO. _____</p> <p>SERIAL NO. _____</p> <p>DATE _____</p>	<p>TEST SPEC. <u>QTP ER 834-4 A</u></p> <p>TEST FIX _____</p> <p>CUSTOMER _____</p> <p>GOVT. INSP. _____</p> <p>CO. INSP. _____</p>		
		INSPECTION	
		STRATOS	CUST.
5.1.5	<p><u>Life Cycle Test (Continued)</u> Cycle unit from crack to full open to reseal 250 cycles Actual _____ cycles</p> <p><u>Performance Tests</u> (paragraph 5.2)</p> <p><u>Internal Static Leakage</u> (paragraph 5.2.1)</p> <p>A. Inlet Port: 6.5 psig Actual _____ psig Internal Leakage: 0.01 sccs max. Actual _____ sccs</p> <p>B. Inlet Port: 6.5 psig Actual _____ psig Internal Leakage: 0.01 sccs max. Actual _____ sccs</p> <p>C. Inlet Port: 6.5 psig Actual _____ psig Internal Leakage: 0.01 sccs max. Actual _____ sccs</p>		
5.2.2	<p><u>External Static Leakage</u> (paragraph 5.2.2)</p> <p>External Pressure: 35 psig Actual _____ psig External Leakage: 1×10^{-6} sccs max. Actual _____ sccs</p>		
REMARKS: _____			
TESTER _____			

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 16 OF 18

<table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:15%;">PART NO.</td> <td style="border-bottom: 1px solid black;">834000</td> </tr> <tr> <td>PART NAME</td> <td style="border-bottom: 1px solid black;">Relief Valve Assembly</td> </tr> <tr> <td>MODEL NO.</td> <td style="border-bottom: 1px solid black;"></td> </tr> <tr> <td>SERIAL NO.</td> <td style="border-bottom: 1px solid black;"></td> </tr> <tr> <td>DATE</td> <td style="border-bottom: 1px solid black;"></td> </tr> </table>	PART NO.	834000	PART NAME	Relief Valve Assembly	MODEL NO.		SERIAL NO.		DATE		<table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:15%;">TEST SPEC.</td> <td style="border-bottom: 1px solid black;">QTP ER 834-4 A</td> </tr> <tr> <td>TEST FIX</td> <td style="border-bottom: 1px solid black;"></td> </tr> <tr> <td>CUSTOMER</td> <td style="border-bottom: 1px solid black;"></td> </tr> <tr> <td>GOVT. INSP.</td> <td style="border-bottom: 1px solid black;"></td> </tr> <tr> <td>CO. INSP.</td> <td style="border-bottom: 1px solid black;"></td> </tr> </table>	TEST SPEC.	QTP ER 834-4 A	TEST FIX		CUSTOMER		GOVT. INSP.		CO. INSP.	
PART NO.	834000																				
PART NAME	Relief Valve Assembly																				
MODEL NO.																					
SERIAL NO.																					
DATE																					
TEST SPEC.	QTP ER 834-4 A																				
TEST FIX																					
CUSTOMER																					
GOVT. INSP.																					
CO. INSP.																					
		INSPECTION																			
		STRATOS	CUST.																		
<p><u>Relief Operation</u> (paragraph 5.2.3)</p> <p>A. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p> Full Flow: 9.0 psid max. Actual _____ psid</p> <p> Reseat: 7.0 psid min. Actual _____ psid</p> <p>B. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p> Full Flow: 9.0 psid max. Actual _____ psid</p> <p> Reseat: 7.0 psid min. Actual _____ psid</p> <p>C. Cracking Pressure: 7.0 psid min. Actual _____ psid</p> <p> Full Flow: 9.0 psid max. Actual _____ psid</p> <p> Reseat: 7.0 psid min. Actual _____ psid</p> <p>Repeat full flow test once with outlet pressure of 1×10^{-6} Torr. and minimum sustained flowrate of 600 scim.</p> <p> Full Flow: 9.0 max. Actual _____ psid</p>																					
<p>REMARKS: _____</p> <p>_____</p> <p align="center">TESTER _____</p>																					

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 17 OF 18

PART NO. <u>834000</u> PART NAME <u>Relief Valve Assembly</u> MODEL NO. _____ SERIAL NO. _____ DATE _____	TEST SPEC. <u>QTP ER 834-4 A</u> TEST FIX _____ CUSTOMER _____ GOV'T. INSP. _____ CO. INSP. _____
INSPECTION STRATOS CUST.	

Internal Proof Pressure (paragraph 5.2.4)

Apply 18 psig to the inlet and outlet ports and hold for 5 minutes minimum before reducing to zero

Actual _____ psig

Evidence of damage, excessive permanent distortion, or deterioration

Yes No

External Proof Pressure (paragraph 5.2.5)

Apply 70 psig to the exterior of the valve assembly, and hold for 5 minutes minimum before reducing to zero

Actual _____ psig

Evidence of damage, Excessive Permanent Distortion or deterioration

Yes No

5.1.6 Collapse Pressure Test

Apply 140 psig external pressure and hold for 3 minutes minimum before reducing to zero.

Actual _____ psig

Evidence of rupture, collapsing or destructive failure.

Yes No

REMARKS: _____

TESTER _____

FAIRCHILD HILLER
STRATOS - WESTERN
TEST LOG

SHEET 18 OF 18

PART NO. <u>834000</u> PART NAME <u>Relief Valve Assembly</u> MODEL NO. _____ SERIAL NO. _____ DATE _____	TEST SPEC. <u>QTP ER 834-4 A</u> TEST FIX _____ CUSTOMER _____ GOV'T. INSP. _____ CO. INSP. _____		
		INSPECTION	
		STRATOS	CUST.
5. 1. 7	<u>Burst Pressure Test (Valve A Only)</u> Apply 36 psig to the inlet and outlet ports and hold for 3 minutes minimum before reducing to zero. <div style="text-align: right;">Actual _____ psig</div> Evidence of rupture, or destructive failure. <div style="float: right;"> <input type="checkbox"/> Yes <input type="checkbox"/> No </div>		
5. 1. 8	<u>Ultimate Pressure Test (Valve B Only)</u> Apply 36 psig to the inlet and outlet ports and hold for 3 minutes minimum. <div style="text-align: right;">Actual _____ psig</div> Ultimate Pressure: <div style="float: right;">Actual _____ psig</div>		
REMARKS: _____			
TESTER _____			

REPORT ER 834-5
DEVELOPMENT VERIFICATION
TEST REPORT
FOR
RELIEF VALVE ASSEMBLY

Stratos-Western P/N 834000
NAS Spec. No. 20M32254

J. Amelsberg
Prepared By: J. Amelsberg, Product Engineer

J. Morando
Approved By: J. Morando, Product Manager

Date:



FAIRCHILD HILLER
STRATOS - WESTERN
1800 ROSECRANS AVENUE
MANHATTAN BEACH, CALIF. 90267

TABLE OF CONTENTS

	Page
1.0 Introduction	1
2.0 Applicable Documents	1
3.0 Test Procedure Summary	1
4.0 Test Methods and Results	2
5.0 Conclusions	2
6.0 Recommendations	2
Relief Valve Assembly - Acceptance Test Data	3
Relief Valve Assembly - Development Data	4
Figure 1. Component Vibration Axes	5
Appendix I	
Dimensional Inspection Record Sheets	
Development Test Log Sheets	
Vibration Results and Photographs	

1.0 INTRODUCTION

This report presents the results of development verification tests performed on the Relief Valve Assembly, Part No. 834000, Serial No. D.U. (development unit). The purpose of the tests was to provide data to be used in the design of prototype units for use in qualification testing in accordance with NASA Specification No. 20M32254 Valve Assembly, Relief.

2.0 APPLICABLE DOCUMENTS

NASA

20M32254, Change A Valve Assembly, Relief

Stratos-Western

ER 834-1, Change Development Verification Test Procedure
for Solenoid Valve, Part No. 683000

3.0 TEST PROCEDURE SUMMARY

The development verification tests were conducted in accordance with Procedure No. ER 834-1. The vibration tests were performed at Approved Engineering Test Laboratories, California, under the cognizance of Stratos-Western personnel. AETL's vibration test report containing the test procedure and results is included in Appendix I. All other tests were conducted at Stratos-Western facilities. The original data sheets are found in Appendix II.

Following assembly of the valve and prior to welding, the development test unit was pre-tested to verify, pressure drop, crack and reseal pressure. Pre-test included shimming of both the poppet and main springs to provide the required poppet stroke and seat pre-load. The unit was then welded and submitted for development verification testing.

After paragraph 6.10.2 of ER 834-1 (Collapse Pressure Test) the valve exhibited a leakage beyond the specification tolerance. It was then decided to eliminate testing per paragraph 6.10.3 (Destructive Pressure) in order to permit tear down of the valve for examination. It was found that contamination had located itself on the seat area restricting

the valve closure. The material was found to be Butyl rubber from one of the fittings used to adapt the valve to the burst pressure test setup. Photographs are shown in figures 2 - 8

4.0 TEST METHODS AND RESULTS

The results of all tests are listed in table 1.

The vibration axes were selected as shown in figure 1 and the vibration results are included in Appendix I together with copies of the test log book kept during development.

5.0 CONCLUSIONS.

From the results of the development verification tests, it is concluded that the 834000 Relief Valve Assembly design is suitable for qualification test. No problems of any kind were discovered during the performance of the tests.

6.0 RECOMMENDATIONS

A slight increase in poppet seat loading could facilitate production by diminishing leakage possibilities due to variations in the seat or poppet as result of dimensional tolerances.

RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

NASA Specification 20M32254		S-W Part No. 834000	S/N _____	Date _____
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
6.1	Examination of Product	Acceptable/ Nonacceptable	Acceptable (dimensional inspection included)	
6.2	Internal Proof Pressure	Acceptable/ Nonacceptable	Acceptable	
6.3	External Proof Pressure	Acceptable/ Nonacceptable	Acceptable	
6.4 (a)	Internal Static Leakage	36 scch maximum	2.70 scch	
6.4. (b)	External Static Leakage	1.0×10^{-6} sccs	Non detectable leakage	
6.5	Relief Operation	a) P outlet = 14.7 psia crack: 21.7 psia min. full flow: 23.7 psia max. reseat: 21.7 psia min.	a) crack: 23.05 psia full flow: 23.30 psia reseat: 22.80 psia	

FAIRCHILD HILLER
STATOS-WESTERN
 1800 ROSECRANS AVENUE, HANFORD, CALIF. 90388

RELIEF VALVE ASSEMBLY - DEVELOPMENT DATA

NASA Specification 20M32254		S/W Part No. 834000	S/N _____	Date _____
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
6.8	Vibration	Sinusoidal Acceptable Nonacceptable Lift-off Acceptable Nonacceptable Random Acceptable Nonacceptable Ref. 6.5 crack: 7.0 min. psig full flow: 9.0 max. psig reseal: 7.0 min. psig	Acceptable Acceptable Acceptable Leakage: 3.4 scch 8.0 psig 8.5 psig 7.85 psig	
6.9	Life Cycle Repeat 6.5 every 250 cycles	1000 cycles Ref. 6.5 crack: 7.0 psig min. full flow: 9.0 psig max. reseal: 7.0 psig min. internal leakage: 36 scch	8.0 psig 8.55 psig 7.85 psig 2.7 scch	
6.10	Burst 6.10.1 Nondes- tructive 6.10.2 Collapse 6.10.3 Destructive	Rupture - No rupture Collapse - No collapse Rupture Pressure 72 psig	No rupture No collapse Omitted	*

Conclusions:

Recommendations:
 *See paragraph 3.0

FAIRCHILD HILLEN
STATOS-WESTERN
 1800 ROBEKANS AVENUE, MANHATTAN BEACH, CALIF. 90288




Figure 1. Component Vibration Axes.


FAIRCHILD HILLER
STRATOS-WESTERN
1800 ROSECRANS AVENUE, MARINA DEL REY, CALIF. 90290

Page No.

ER 834-5

APPENDIX I


FAIRCHILD HILLER
STRATOS-WESTERN
1800 ROSECRANS AVENUE, MANHATTAN BEACH, CALIF. 90266

Page No.
Appendix I - Section I
ER 834-5

DIMENSIONAL INSPECTION
RECORD SHEETS

FAIRCHILD STRATOS

STRATOS DIVISION
MANHATTAN BEACH, CALIFORNIA

FIRST ARTICLE INSPECTION

ENDOR: STRATOS-R&D P. O. # _____ R. R. # _____

ART NAME: BODY, VALVE ASSY PART NO. 834008 N/C MRR # _____


TOOL ORDER NO. _____ DATE INSPECTED: 8/17/70 PROJ. # C-152

Note: All defects must be corrected and first article resubmitted before resuming manufacturing.

ITEM	B/P DIM	ACTUAL DIM.	DISC.	ITEM	B/P DIM	ACTUAL DIM.	DISC.
1	.188 ^{+0.01} _{-0.00} DIA.	.188		25	.625 ^{+0.005} _{-0.00} DIA.	.6255	
2	.012 ^{+0.002}	.014		26	1.282 ^{+0.010} _{-0.000}	1.285	
3	SHARP CORNER	OK		27	.844 ^{+0.010} _{-0.000}	.852	
4	.156 ^{+0.004} _{-0.001} DIA.	.1555		28	.050 ^{+0.015} _{-0.000} x 45°	.050 x 45°	
5	.187	.187		29	45°	45°	
6	.032 RAD	.03125		30	.130	.132	
7	.938 ^{+0.011}	.937		31	1.000 ^{+0.000} _{-0.005}	.998	
8	.050 ^{+0.015} _{-0.000} x 45°	.050 x 45°		32	.032 R	.03125	
9	.500 ^{+0.015}	.500		33	32	16	
10	.312 ^{+0.002}	.312					
11	.002 R MIN	.001					
12	SHARP CORNER	OK					
13	.015 ^{+0.002}	.015					
14	.562 ^{+0.002} _{-0.000} DIA.	.562					
15	32	16					
16	OB .002 DIA	.001					
17	.896 ^{+0.002} _{-0.000} DIA	.896					
18	OA .002 DIA	.001					
19	32	16					
20	.925 ^{+0.002} _{-0.000} DIA	.925					
21	.250 ^{+0.005} _{-0.000} DIA	.250					
22	15°	15°					
23	.040 R	.040					
24	.040 ^{+0.015} _{-0.000} x 45°	.042 x 45°					

MARKS: _____

APPROVED BY: _____

INSPECTED BY: [Signature] 

TOOLING APPROVED _____

TOOLING REJECTED _____

CASTING APPROVED _____

CASTING REJECTED _____

APPROVED BY: _____

FIRST ARTICLE INSPECTION

VE OR: STRATOS R. & D. P. O. # _____ R. R. # _____

PART NAME: SEAT, BELLOWS END PLATE PART NO. 834028 A MRR # _____

TOOL ORDER NO. _____ DATE INSPECTED: 8/18/70 PROJ. # C-152

Note: All defects must be corrected and first article resubmitted before resuming manufacturing.

ITEM	B/P DIM	ACTUAL DIM.	DISC.	ITEM	B/P DIM	ACTUAL DIM.	DISC.
1	.564 ^{+0.02}	.564		25	85° 30'	85° 30' (MILD)	
2	.032	.032		26 *	.158 ^{+0.02}	.158	
3	.038 ^{+0.01} _{-0.02}	.038		27	.050 R	.050 R	
4	.225	.225		28	.200 ^{+0.05} DIA. X 90°	.2003 X 90°	
5	.002 R MAX	.001 R		29	ØA .0005 DIA	.0003	
6	.062	.062		30	✓ 16°	✓ 16°	
7	.062 R	.0625		31	✓ 16°	✓ 16°	
8	45°	45°		32	.792 ^{+0.01}	.791	
9	.453 ^{+0.01} _{-0.02}	.452		33	.002 R MAX	.001 R	
10	45°	45°		34	.175 ^{+0.01} DIA	.174	
11	.188	.188		35	.067 ^{+0.01} _{-0.01} DIA. <small>IN LINE C-2</small> ^{21:425} <small>Ø67 IN LINE</small> ₁₀₀₀₅		
12	.094	.094		36	.005/.010 R TYP	.007 R	
13	.450 ^{+0.05} DIA.	.450		37	.375 ^{+0.01} _{-0.01} DIA	.3755	
14	.471 ^{+0.01} _{-0.02} DIA.	.471		38	✓ 32	✓ 32	
15	.850 ^{+0.01} _{-0.02} DIA.	.850		39	.406 ^{+0.01} _{-0.01} DIA.	.407	
16	.015 R	.012 R		40	.125 ^{+0.02}	.1265	
17	.02 R-4 pcs	.020 R		41	.187 ^{+0.02} _{-0.01}	.187	
18	.030 ^{+0.02}	.0295		42	.015 ^{+0.05} X .450	.010	
19	.090	.092					
20	.437 ^{+0.05} DIA.	.4375					
21	.132	.133					
22	.839 ^{+0.01}	.839					
23	.515 ^{+0.01} _{-0.02} DIA.	.515					
24	.001/.004 R ✓	.002 R ✓					

REMARKS: * (26) DIM CHANGED TO MATCH DIA. OF BALL .218 DIA.

DISPOSITION: _____

INSPECTED BY: [Signature] (31)

TOOLING APPROVED _____

TOOLING REJECTED _____

CASTING APPROVED _____

CASTING REJECTED _____

APPROVED BY: _____

FIRST ARTICLE INSPECTION

VE OR: STRATOS R. & D. P. O. # _____ R. R. # _____

PART NAME: SEAT, BELLOWS END PLATE PART NO. 834028 A MRR # _____


TOOL ORDER NO. _____ DATE INSPECTED: 8/18/70 PROJ. # C-152

Note: All defects must be corrected and first article resubmitted before resuming manufacturing.

ITEM	B/P DIM	ACTUAL DIM.	DISC.	ITEM	B/P DIM	ACTUAL DIM.	DISC.
1	.564 ^{+0.02}	.564		25	85° 30'	85° 30' (MOLD)	
2	.032	.032		26 *	.158 ^{+0.02}	.158	
3	.038 ^{+0.010} _{-0.012}	.038		27	.050 R	.050 R	
4	.225	.225		28	.200 ^{+0.015} DIA. X 90°	.2003 X 90°	
5	.002 R MAX	.001 R		29	ØA .0005 DIA	.0003	
6	.062	.062		30	✓ 16°	✓ 16°	
7	.062 R	.0625		31	✓ 16°	✓ 16°	
8	45°	45°		32	.792 ^{+0.01}	.791	
9	.453 ^{+0.010} _{-0.012}	.452		33	.002 R. MAX	.001 R	
10	45°	45°		34	.175 ^{+0.01} DIA	.174	
11	.188	.188		35	.067 ^{+0.010} _{-0.011} DIA. <small>IN LINE. 0.2</small> <small>21 INES</small> <small>Ø67 IN LINE 1.0005</small>		
12	.094	.094		36	.005/.010 R TYP	.007 R	
13	.450 ^{+0.015} DIA.	.450		37	.375 ^{+0.010} _{-0.011} DIA	.3755	
14	.471 ^{+0.010} _{-0.011} DIA.	.471		38	✓ 32	✓ 32	
15	.850 ^{+0.010} _{-0.011} DIA.	.850		39	.406 ^{+0.010} _{-0.011} DIA	.407	
16	.015 R	.012 R		40	.125 ^{+0.02}	.1265	
17	.02 R-4 pks	.020 R		41	.187 ^{+0.010} _{-0.011}	.187	
18	.030 ^{+0.02}	.0295		42	.015 ^{+0.015} X 45°	.010	
19	.090	.092					
20	.437 ^{+0.015} DIA.	.4375					
21	.132	.133					
22	.839 ^{+0.01}	.839					
23	.515 ^{+0.010} _{-0.011} DIA.	.515					
24	.001/.014 R. ✓	.002 R. ✓					

REMARKS: * (26) DIM CHANGED TO MATCH DIA. OF BALL .218 DIA.

DISPOSITION: _____

INSPECTED BY: [Signature] 

TOOLING APPROVED _____

TOOLING REJECTED _____

CASTING APPROVED _____

CASTING REJECTED _____

APPROVED BY: _____

VENDOR: STRATOS R. & D. P. O. # _____ R. R. # _____

PART NAME: RETAINER, SPRING PART NO. 834013 N/C MRR # _____

TOOL ORDER NO. _____ DATE INSPECTED: 8/19/70 PROJ. # C-152

Note: All defects must be corrected and first article resubmitted before resuming manufacturing.

ITEM	B/P DIM	ACTUAL DIM.	DISC.	ITEM	B/P DIM	ACTUAL DIM.	DISC.
1	.177 ^{+0.002}	.177					
2	.004 ^{+0.002} R	.004 R					
3	.405 ^{+0.002} DIA	.404					
4	.094	.094					
5	.188	.188					
6	.02 R - 4 PLCS	.020 - 4 PLCS					
7	.090	.091					
8	.187 ^{+0.004} DIA	.1875					
9	.281 ^{+0.004} DIA	.282					
10	.025 ^{+0.002}	.026					
11	.115 ^{+0.005}	.116					
12	.358 ^{+0.015} DIA	.360					
13	.020 R	.012					
14	.067 ^{+0.004} - 2 HOLE S IN LINE .067 - .001 IN LINE	.067					
15	.125 ^{+0.002}	<u>.119</u>					
16	.005 P MIX	.002					

REMARKS: USE AS IS / ACCEPTABLE

DISPOSITION: _____

INSPECTED BY: [Signature]
 TOOLING APPROVED _____
 TOOLING REJECTED _____
 CASTING APPROVED _____
 CASTING REJECTED _____

APPROVED BY: _____

VENDOR: STRATOS R. & D. P. O. # _____ R. R. # _____

PART NAME: RETAINER, SPRING PART NO. 834013 N/C MRR # _____

TOOL ORDER NO. _____ DATE INSPECTED: 8/19/70 PROJ. # C-152

Note: All defects must be corrected and first article resubmitted before resuming manufacturing.

ITEM	B/P DIM	ACTUAL DIM.	DISC.	ITEM	B/P DIM	ACTUAL DIM.	DISC.
1	.177 ^{+0.002} _{-0.002}	.177					
2	.004 ^{+0.002} _{-0.002} R	.004 R					
3	.405 ^{+0.002} _{-0.002} DIA	.404					
4	.094	.094					
5	.188	.188					
6	.02 R - 4 PLCS	.020 - 4 PLCS					
7	.090	.091					
8	.187 ^{+0.004} _{-0.004} DIA.	.1875					
9	.281 ^{+0.004} _{-0.004} DIA.	.282					
10	.025 ^{+0.002} _{-0.002}	.026					
11	.115 ^{+0.005} _{-0.005}	.116					
12	.358 ^{+0.005} _{-0.005} DIA.	.360					
13	.020 R	.012					
14	.067 ^{+0.004} _{-0.004} 2 HOLES ALL LINE .067 - .001 IN LINE	.067					
15	.125 ^{+0.002} _{-0.002}	<u>.119</u>					
16	.005 P MAX	.002					

REMARKS: USE AS IS / ACCEPTABLE

DISPOSITION: _____

INSPECTED BY: [Signature] (15)
 TOOLING APPROVED _____
 TOOLING REJECTED _____
 CASTING APPROVED _____
 CASTING REJECTED _____

APPROVED BY: _____

FIRST ARTICLE INSPECTION

DOR: STRATOS R. & D. P. O. # _____ R. R. # _____

PART NAME: POCKET RELIEF VALVE PART NO. 834015 A MRR # _____


TOOL ORDER NO. _____ DATE INSPECTED: 8/19/70 PROJ. # C-152

Note: All defects must be corrected and first article resubmitted before resuming manufacturing.

ITEM	B/P DIM	ACTUAL DIM.	DISC.	ITEM	B/P DIM	ACTUAL DIM.	DISC.
1	.607 ^{+0.01}	.607					
2	<u>✓</u>	<u>✓</u>					
3	.373 ^{+0.005} DIA	.3725					
4	Ø .001 DIA	.0005					
5	<u>✓</u>	<u>✓</u>					
6	80°	80°					
7	.121 ^{+0.002} DIA	.120					
8	.406 ^{+0.005}	.406					
9	.030	.030					
10	.076 ^{+0.004} DIA - 4 HOLES	.076 - 4 HOLES					
11	30° TYP	30°					
12	.005 R MAX	.003 R					
13	.086 ^{+0.010}	.087					
14	.218 DIA. x 120°	.217					
15	.281 ^{+0.005} DIA	.283					
16	.312 ^{+0.005} DIA	.3125					

REMARKS: _____

DISPOSITION: _____

INSPECTED BY: [Signature] 
 TOOLING APPROVED _____
 TOOLING REJECTED _____
 CASTING APPROVED _____
 CASTING REJECTED _____

APPROVED BY: _____

FIRST ARTICLE INSPECTION

DOR: STRATOS R & D P. O. # _____ R. R. # _____

PART NAME: POCKET RELIEF VALVE PART NO. 834015 A MRR # _____


TOOL ORDER NO. _____ DATE INSPECTED: 8/19/70 PROJ. # C-152

Note: All defects must be corrected and first article resubmitted before resuming manufacturing.

ITEM	B/P DIM	ACTUAL DIM.	DISC.	ITEM	B/P DIM	ACTUAL DIM.	DISC.
1	.607 ^{+0.01}	.607					
2	<u>✓</u> .32	<u>✓</u>					
3	.373 ^{+0.01} DIA	.3725					
4	ØA .001 DIA	.0005					
5	<u>✓</u>	<u>✓</u>					
6	80°	80°					
7	.121 ^{+0.02} DIA	.120					
8	.446 ^{+0.05}	.406					
9	.030	.030					
10	.076 ^{+0.01} DIA - 4 HOLES	.076 - 4 HOLES					
11	30° TYP	30°					
12	.005 R MAX	.003 R					
13	.086 ^{+0.010} -0.005	.087					
14	.218 DIA. X 120°	.217					
15	.281 ^{+0.01} -0.005 DIA	.283					
16	.312 ^{+0.05} -0.01 DIA	.3125					

REMARKS: _____

DISPOSITION: _____

INSPECTED BY: [Signature] 

TOOLING APPROVED _____

TOOLING REJECTED _____

CASTING APPROVED _____

CASTING REJECTED _____

APPROVED BY: _____

STRATOS DIVISION
MANHATTAN BEACH, CALIFORNIA FIRST ARTICLE INSPECTION

VENDOR: STRATOS R. + D. P. O. # _____ R. R. # _____

PA NAME: END PLATE, BELLOWS PART NO. 834020 N/C MRR # _____


TOOL ORDER NO. _____ DATE INSPECTED: AS 25 '70 PROJ. # C-152

Note: All defects must be corrected and first article resubmitted before resuming manufacturing.

ITEM	B/P DIM	ACTUAL DIM.	DISC.	ITEM	B/P DIM	ACTUAL DIM.	DISC.
1	.312 ^{+0.01}	.3115					
2	.094 ^{+0.010} -0.005	.094					
3	32	32					
4	.047	.049					
5	.004/0.03 R	.004					
6	.813 ^{+0.010} -0.002 DIA.	.811					
7	.923 ^{+0.005} -0.001 DIA.	.923					
8	32	32					
9	.010 ^{+0.05 R}	.010 R					
10	.866 DIA.	(.821)	ALL .029				
11	.187 ^{+0.01}	.187					
12	.015 ^{+0.01}	.015					
13	SHARP CORNER	OK					
14	⊙ B.005 DIA.	.001					
15	.010 ^{+0.05 R}	.005 R					
16	.015 ^{+0.01} x 45°	.016 x 45°					
17	.735 ^{+0.002} -0.002	.7385					
18	.600 DIA.	.600					
19	.250 ^{+0.005} -0.001	.250					
20	.593 ^{+0.001} -0.000 DIA.	.593					
21	⊙ A.001 DIA.	.0005					
22	32	32					
23	.010 R MAX	.003 R					
24	.005 R MAX	.002 R					

REMARKS: _____

DISPOSITION: USE AS IS Followed

INSPECTED BY: [Signature] 

TOOLING APPROVED _____

TOOLING REJECTED _____

CASTING APPROVED _____

CASTING REJECTED _____

APPROVED BY: _____

C. _____ MFG. _____ ENG. _____

VENDOR: STRATOS R. & D. P. O. # _____ R. R. # _____

PA NAME: END PLATE, BELLOWS PART NO. 834020 N/C MRR # _____

TOOL ORDER NO. _____ DATE INSPECTED: AS 25 '70 PROJ. # C-152

Note: All defects must be corrected and first article resubmitted before resuming manufacturing.

ITEM	B/P DIM	ACTUAL DIM.	DISC.	ITEM	B/P DIM	ACTUAL DIM.	DISC.
1	.312 ^{+0.01}	.3115					
2	.094 ^{+0.010} _{-0.000}	.094					
3	32	32					
4	.047	.049					
5	.004/0.03 R	.004					
6	.813 ^{+0.010} _{-0.000} DIA.	.811					
7	.923 ^{+0.010} _{-0.000} DIA.	.923					
8	32	32					
9	.010 ^{+0.005} R	.010 R					
10	.866 DIA.	.821	USE .029				
11	.187 ^{+0.001}	.187					
12	.015 ^{+0.001}	.015					
13	SHARP CORNER	OK					
14	Ø B .005 DIA.	.001					
15	.010 ^{+0.005} R	.005 R					
16	.015 ^{+0.010} _{-0.000} x 45°	.016 x 45°					
17	.735 ^{+0.002} _{-0.000}	.7385					
18	.600 DIA.	.600					
19	.250 ^{+0.005} _{-0.000}	.250					
20	.593 ^{+0.001} _{-0.000} DIA.	.593					
21	Ø A .001 DIA.	.0005					
22	32	32					
23	.016 R MAX	.003 R					
24	.005 R MAX	.002 R					

REMARKS:

DISPOSITION: USE AS IS *Juliano*

INSPECTED BY: *M. Gordon*

TOOLING APPROVED _____

TOOLING REJECTED _____

CASTING APPROVED _____

CASTING REJECTED _____

APPROVED BY:

C. _____ MFG. _____ ENG. _____


FAIRCHILD HILLER
STRATOS-WESTERN
1800 ROSECRANS AVENUE, MANHATTAN BEACH, CALIF. 90260

Page No.
Appendix I - Section 2
ER 834-5

DEVELOPMENT TEST
LOG SHEETS


FAIRCHILD HILLER
STRATOS-WESTERN
1800 ROSECRANS AVENUE, MANHATTAN BEACH, CALIF. 90260

Page No.
Appendix I - Section 2
ER 834-5

DEVELOPMENT TEST
LOG SHEETS

PRE TEST 9-1-70

SM

P ₂ Δ	LEAKAGE
5.0	0 SCCM
5.5	0 "
6.0	0 "
6.5	0 "
7.0	0 "
7.5	.14 "
8.0	2.0 "
8.3 CRACK	50 "
8.6 FULL FLOW	775 SCIM
8.2 RESET	50 SCCM
7.0	.54
6.5	.18
6.0	.06
5.5	.0
5.0	.0

PRE TEST 9-1-70

SAJ

P ₂ Δ	LEAKAGE	
5.0	0	SCCM
5.5	0	"
6.0	0	"
6.5	0	"
7.0	0	"
7.5	.14	"
8.0	2.0	"
8.3	CRACK	50 "
8.6	FULL FLOW	775 SCIM
8.2	RESET	50 SCCM
7.0	.54	
6.5	.18	
6.0	.06	
5.5	.0	
5.0	.0	

PRETEST AFTER WELD

9-1-70

JM

PSID			
5		.05	SCCM
5.5		.055	
6		.06	SCCM
6.5		.08	SCCM
7		.14	SCCM
7.5		.31	SCCM
8.			
8.55	8.60	CRACK	
8.8	8.8	FULL FLOW	
8.45	8.5	RESEAT	
8.			
7.5			
7		.30	SCCM
6.5		.075	SCCM .080
6.0		.065	

PRETEST AFTER WELD

9-1-70

SM

PSID			
5		.05	SCCM
5.5		.055	
6		.06	SCCM
6.5		.08	SCCM
7		.14	SCCM
7.5		.31	SCCM
8.			
8.55	8.60	CRACK	
8.8	8.8	FULL FLOW	
8.45	8.5	RESEAT	
8.			
7.5			
7		.30	SCCM
6.5		.075	SCCM .080
6.0		.065	

DEVELOPMENT VERIFICATION TESTS

9/3/70

P/N - 834000

3/P.

ER 834-1

PARA 6.0 DEVELOPMENT VERIFICATION TESTS.
 6.1 EXAMINATION -

25
GWS

6.2 INTERNAL PROOF PRESSURE.

REMARKS:

18 PSIG 5 MINUTES.

NONE

25
GWS

6.3 EXTERNAL PROOF PRESSURE.

70 PSIG 5 MINS.

NONE

6.4 LEAKAGE.

25
GWS

(A) INLET B.C.G.

LEAKAGE.

CRACK

RESULT.

6.5

.045

8.35

8.1

6.5

.030

8.3

8.1

25
GWS

6.5

.10

8.3

8.15

(B) EXTERNAL

25
GWS

35 PSIG

NDC

NONE.

6.5 RELIEF OPERATION.

SEE NEXT PAGE

Development Verification Tests

9/3/70

P/N 834000

S/N

ER 834-1

PARA 6.0 DEVELOPMENT VERIFICATION TESTS

6.1 EXAMINATION

SWD 32

6.2 INTERNAL PROOF PRESSURE

Remarks:

18 psig 5 MINUTES

NONE

SWD 32

6.3 EXTERNAL PROOF PRESSURE

20 psig 5 MINS.

NONE

6.4 LEAKAGE

SWD 32

(A) INLET P.S.I.G.

LEAKAGE

CRACK

RESULT

6.5

.045

8.35

8.1

6.5

.030

8.3

8.1

SWD 32

6.5

.10

8.3

8.15

(B) EXTERNAL

SWD 32

35 psig

NOL

NONE


6.5 RELIEF OPERATION

SEE NEXT PAGE

OUTLET VALVES

9/10

	CRACKING	RESET	FULL FLOW
1)	8.25 psig	7.95 psig	8.65 psig
2)	8.25	7.90	8.65
3)	8.25	7.90	8.65

PARA. 6.8) VIB. Q AETL 9/23/70 ^{SEP 23 70}  I. Tokuda
 PARA. 6.8 RELIEF OPERATION AFTER VIB.

	CRACKING	RESET	FULL FLOW
1)	8.0 psig	7.85 psig	8.47
2)	8.0	7.75	8.5
3)	8.0	7.70	8.55

PARA. 6.9) FIRE CYCLE 1100 cycles of operation 9/24
 RELIEF OPERATION AFTER EVERY 250 cycles.

Cycles	CRACKING			RESET			FULL FLOW		
	1	2	3	1	2	3	1	2	3
250	8.0	8.0	8.0	7.8	7.85	7.85	8.55	8.55	8.55
500	8.0	8.0	8.0	7.8	7.85	7.85	8.55	8.55	8.55
750	8.0	8.0	8.0	7.8	7.85	7.85	8.55	8.55	8.55
1100	8.0	8.0	8.0	7.8	7.85	7.85	8.55	8.55	8.55

PARA. 6.5 RELIEF OPERATION

9-15-70

OUTLET @ 14.7 PSIA

			PRESSURE @ 775 SCIM FLOW
(1) CRACKING	RESEAT		
8.15 PSIG	8.05		8.25 PSIG
(2) 8.20 "	8.0		8.25 "
(3) 8.15 "	8.05		8.25 "

RELIEF OPERATION AFTER 4.0 HRS. 9-16-70

@ +160°F

			PRESSURE @ 775 SCIM FLOW
CRACKING	RESEAT		
1) 8.2 PSIG	7.90 PSIG		8.60 PSIG
2) 8.2 "	7.95 "		8.60 "
3) 8.2 "	7.90 "		8.60 "

PARA. 6.7 RELIEF OPERATION AFTER 4.0 HRS @ -40°F ^{9/16}

			PRESSURE @ 775 SCIM FLOW
cracking	RESEAT		
1) 8.16 psig	7.85		8.6 psig
2) 8.15 psig	7.90		8.64
3) 8.15 psig	7.90		8.6

Para. 6.9)

LEAKAGE AFTER FIRE CYCLE - 9/24

6.5 psig INLET LEAKAGE WAS 1.6 sec/min.

BACK FLUSHED UNIT TO CLEAN. Repeat Leakage

6.5 psig INLET. LEAKAGE WAS .045 sec/min

Para. 6.10 BURST PRESSURE

9/24

6.10.1 NONDESTRUCTIVE

36 psig INLET & OUTLET PORTS NO DAMAGE (3 MINS.)

SWB 32

SEP 24 70

6.10.2 COLLAPSE PRESSURE

140 psig EXTERIOR OF VALVE, INLET & OUTLET PORTS & psig

NO DAMAGE (3 MINS.)

SWB 32

SEP 24 70

(Added Operation): RELIEF OPERATION

1) CRACK RESEAT FULL FLOW → 775 SUM

1) 8.25 psig 7.5 psig 9.0

2) 8.25 psig 7.5 9.0

3) 8.3 psig 7.5 9.0

SWB 32

SEP 24 70

9/24

1) 7.95 7.85 8.45

2) 7.9 7.85 8.45

3) 7.9 7.85 8.45

SWB 32

SEP 24 70

9/25/70

Leakage AFTER BURST WAS 2.0 Secm

6.5 psig INLET.



SEP 24 '70

VIBRATION RESULTS
AND PHOTOGRAPHS



APPROVED ENGINEERING TEST LABORATORIES

5320 W. 104th St., Los Angeles, Calif. 90045

AETL

Report No. 5330-00-9183

P.O. No. 5-4174

Date: 9-28-70

Government Contract No. NAS8-26358

5 Page Report

TESTED FOR

Fairchild-Hiller
1800 Rosecrans Avenue
Manhattan Beach, California

TEST ITEM

Relief Valve Assembly, Part Number 834000, "Development Unit"

TEST PERFORMED

Sinusoidal Vibration
Random Vibration

REFERENCES

George C. Marshall Space Flight Center Document Number 20M32254,
Paragraph 4.3.4.6

TEST EQUIPMENT

<u>AETL No.</u>	<u>Manufacturer</u>	<u>Instrument</u>
D10L	M. B. Electronics	Vibration Exciter
D11L	M. B. Electronics	Amplifier
D38L	Plotamatic	X-Y Plotter
D41L	Endevco Corp.	Accelerometer
D49L	Moseley	Automatic Logarithmic Converter
D70L	M. B. Electronics	Accelerometer Integrator/Amplifier
D830S	M. B. Electronics	Random Control Console
E249L	Spectral Dynamics	Sweep Oscillator Servo



APPROVED ENGINEERING TEST LABORATORIES
5320 W. 104th St., Los Angeles, Calif. 90045

AETL

Report No. 5330-00-9183

Date: 9-28-70

TEST PROCEDURE AND TEST RESULTS

Sinusoidal Vibration

The specimen was subjected to a sinusoidal sweep for a period of 1.2 minutes along each of the three major orthogonal axes over the frequency range of 3 to 60 Hz at the following intensities:

<u>Frequency(Hz)</u>	<u>Intensity</u>
3 - 7	0.43 inch da
7 - 14	1.1 g peak
14 - 25	0.11 inch da
25 - 60	3.6 g peak

Visual examination at the conclusion of each axis of testing revealed no damage or other adverse effects.

The specimen was then subjected to a sinusoidal sweep for a period of 6.6 minutes in each of the three major orthogonal axes over the frequency range of 20 to 2000 Hz at the following intensities:

<u>Frequency (Hz)</u>	<u>Intensity</u>
20 - 100	0.0020 inch da
100 - 2000	1.0 g peak

Visual examination at the conclusion of testing in each axis revealed no damage or other adverse effects.



APPROVED ENGINEERING TEST LABORATORIES
5320 W. 104th St., Los Angeles, Calif. 90045
AETL

Report No. 5330-00-9183

Date: 9-28-70

Random Vibration

The specimen was subjected to random vibration for a period of 1.0 minute in each of the three major orthogonal axes over the frequency range of 20 to 2000 Hz at the following intensities:

<u>Frequency (Hz)</u>	<u>Intensity</u>
20 - 25	10 db/octave rise
25 - 80	0.20 g ² /Hz
80 - 125	6 db/octave rolloff
125 - 2000	3 db/octave rolloff
Total acceleration: 6.8 grms	

Visual examination at the conclusion of testing in each axis revealed no damage or other adverse effects. The equalization plot is presented in this report.

The specimen was subjected to random vibration for a period of 2.0 minutes in each of the three major orthogonal axes over the frequency range of 20 to 2000 Hz at the following intensities:

<u>Frequency (Hz)</u>	<u>Intensity</u>
20 - 25	10 db/octave rise
25 - 80	0.05 g ² /Hz
80 - 125	6 db/octave rolloff
125 - 2000	3 db/octave rolloff
Total Acceleration: 3.4 grms	

Visual examination at the conclusion of testing in each axis revealed no damage or other adverse effects. The equalization plot is presented in this report.



SEP 28 1970


H.P. Schmitt 9/28/70
"COMPLETE TEST EVALUATION CONDUCTED"
DCASR/LA

STATE OF CALIFORNIA
COUNTY OF LOS ANGELES } ss.

TRUMAN D. HARRIS, Project Mgr. being duly sworn, deposes and says: That the information contained in this report is the result of complete and carefully conducted tests and is to the best of his knowledge true and correct in all respects.


Truman D. Harris

SUBSCRIBED and sworn to before me this 28 day of Sept. 1970
Karl G. Schmidt
Notary Public in and for the County of Los Angeles, State of California.



EQUALIZATION PLOT

Report No. 5330-00-9183




Customer TRACED HOLDING
Specimen RIKEL VALVE
Part No. 834000
Ser. No. DEV. 4215
Job No. 5330-00-9183
Axis AM
Date 9-23-70



Co. Sigma

FREQUENCY CPS

EQUALIZATION PLOT



Report No. 5330-00-9183

Customer Fajec Hydro Mille
 Specimen RELIST VALUE
 Part No. 836000
 Ser. No. DEV. UNIT
 Job No. 5330-00-9183
 Axis 011
 Date 9-23-70



3.4 grams

FREQUENCY CPS



Figure 3. Relief Valve Poppet




Figure 5. Relief Valve Body Assembly (Inside View)




Figure 4. Relief Valve Poppet Assembly

NASA RELIEF VALVE ASSEMBLY

P/N 834000




Figure 2.




Figure 6. Vibration Test - XX Axis




Figure 8. Vibration Test - ZZ Axis




Figure 7. Vibration Test - YY Axis

ASTRONAUTICS LABORATORY
ENGINEERING DIVISION

MEMORANDUM FOR:	Fairchild Hiller Corporation 1800 Rosecrans Avenue Manhattan Beach, California 90266	ATTN: Richard Roberts
		CONTRACT NO.: NAS8-26358
SUBJECT:	Review of Documents	DATE: October 27, 1970

The following documents have been reviewed and are approved:

1. Acceptance test procedure 834002 - CN10905 and CN11021.
2. Development test report ER834-5.
3. Qualification test procedure ER834-4.

This completes the requirements of phase I. Phase I is approved.

APPROVED BY: <i>C. Edwards</i> C. Edwards	CONCURRENCE: S&E-ASTN-EMA <u><i>[Signature]</i></u> S&E-ASTN-EMC <u><i>[Signature]</i></u> S&E-ASTN-EM <u><i>[Signature]</i></u>	NUMBER: C-26358-005 SHEET 1 OF 1
NASA	Technical Information Sheet	MSFC

ASTN-72 (OT) September 1970


FAIRCHILD HILLER
STRATOS-WESTERN
1800 ROSECRAHS AVENUE MANHATTAN BEACH, CALIF. 90266

Page No.

ER 834-7

ADDENDUM II



FAIRCHILD HILLER
STRATOS - WESTERN

INTER-OFFICE COMMUNICATION

Subject: NASA Relief Valve Assembly - P/N 834000
Reference: A. S/N 03825LO40005 - RMR 3382
B. S/N 03825LO40006 - RMR 3383

EM71- 2
January 4, 1971

To: R. Smith

From: R. Bertler

Both units in the above reference were disassembled for visual inspection. Contamination was found on both poppets and seats. Special relief valve inlet and outlet fittings were installed on the test stand prior to the acceptance test of both units. The fittings were only flush cleaned after weld. Component parts and fittings were delivered to Durkee Testing Laboratories for possible identification of constituents. The laboratory test report is attached.

Fairchild Hiller concludes the internal leakage reported for S/N 005 and the low reseal pressure reported for S/N 006 is the result of contamination from the component fittings on the test stand.


Corrective action has been implemented as follows:

1. New fittings were fabricated, wire brushed after weld and thoroughly flushed prior to use.
2. Production planning has been advised to revise sheet 5 of the Master Route Sheet to include cleaning per Stratos Spec. 999-331 after the spring retainer (834013) is welded to the bellows (834010).

RB:hb

cc: J. Feld
R. Harrison
E. LaPlante
J. Morando
R. Roberts

Attachment


R. Bertler

December 21, 1970

Lab No. 4-550

DURKEE TESTING LABORATORIES

1520 West 178th St. • Gardena, California 90247

Phone (213) 321-9800

Our Rec. Log No. F1196

Your P.O. No.: _____

Report To:

Fairchild Hiller
1800 Rosecrans Avenue
Manhattan Beach, California

METALLURGICAL TEST REPORT

Introduction

This report deals with the metallographic investigation conducted on two (2) T-Fittings identified as "Outlet" and "Inlet", manufactured from 316 Stainless Steel, after the components were submitted to this laboratory for examination and evaluation of the inside diameter surfaces.

Test Results

The two valve components were first cross-sectioned in such a manner as to include a complete inside diameter view and a transverse view of the T-Fitting fusion welds.

Examination of the metallographic cross-sections of the T-Fittings showed evidence of contamination which resembled high temperature "scale" in the weld heat affected zones.

The high temperature products were present in both a tight bond and a "loose scaly" deposition.

The loose scale present is probably the result of material products that formed during the fusion welding operation and the brownish contamination is the result of high temperature volatilization of one or more alloying constituents, still being intermetallic in nature, with the matrix material.

It is also believed that the contamination found on the poppet surfaces is a combination of the two aforementioned contaminants.



METALLOGRAPHER

Respectfully Submitted

DURKEE TESTING LABORATORIES

By 

PRODUCTION ACCEPTANCE TEST

RESULTS

RELIEF VALVE ASSEMBLY --ACCEPTANCE TEST DATA

NASA Specification 20M32254		S-W Part No. 834000	S/N 035254040012	Date FEB 25 1971
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
5.1.1	Examination of Product	Acceptable/Nonacceptable	FEB 25 1971	
5.1.2	Internal Proof Pressure	Acceptable/ Nonacceptable	18 psig MAR 3 '71	
5.1.3	External Proof Pressure	Acceptable/ Nonacceptable	35 psig MAR 3 '71	
5.1.4	Internal Static Leakage	36 scch maximum	1) scch 2) .18 scch 3) .3 scch	
5.1.5	External Static Leakage	1.0×10^{-6} sccs	$< 3.6 \times 10^{-7}$	
5.1.6	Relief Operation	P _{outlet} = 14.7 psia crack: 7.0 psid min. full flow: 9.0 psid max. reseat: 7.0 psid min.	(psid) crack: 8.3 8.3 8.3 full flow: 8.7 8.6 8.6 reseat: 7.8 7.8 7.8	

Approvals:

J. Schuler MAR 3 '71 Date . S-W Q-C

R. Wheeler MAR 3 '71 Date DCASR

NASA Rep. Date

FAIRCHILD HILLER
STRATOS-WESTERN
 1800 HOBOKEN AVENUE, MANHATTAN BEACH, CALIF. 90260

Page No. 15
 ATP 834002 "D"

RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

FAIRCHILD HILLER
STRATOS-WESTERN
 1800 ROSCRAVE AVENUE, MANHATTAN BEACH, CALIF. 90260

NASA Specification 20M32254		S-W Part No. 834000	S/N <i>03825/040011</i>	Date <i>12-1-71</i>
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
5.1.1	Examination of Product	Acceptable/Nonacceptable		
5.1.2	Internal Proof Pressure	Acceptable/Nonacceptable	<i>18 psig - 5 min.</i> 	<i>Helicoid</i> <i>0-30 psig</i>
5.1.3	External Proof Pressure	Acceptable/Nonacceptable	<i>70 psig - 5 min.</i> 	<i>Helicoid</i> <i>0-200 psig</i>
5.1.4	Internal Static Leakage	36 scch maximum	1) .9 scch 2) 2.7 scch 3) .9 scch	<i>Helicoid</i> <i>0-30 psig</i>
5.1.5	External Static Leakage	1.0×10^{-6} sccs	<i>5.8 X 10⁻⁷</i> 	<i>MAR3H</i> <i>0-60 psig</i>
5.1.6	Relief Operation	P _{outlet} = 14.7 psia crack: 7.0 psid min. full flow: 9.0 psid max. resat: 7.0 psid min.	(psid) crack: 8.5 8.5 8.5 full flow: 8.9 8.9 8.9 resat: 8.4 8.4 8.4 	<i>BARTON</i> <i>ΔP. 0-30psi</i>

ATP 834002
 Page No. 15

Approvals:

J. Tokuda JAN 13 '71 Date *DCASR* *Robert W. White* 15 JAN 71 Date *N/A* Date

S-W Q-C Date DCASR Date NASA Rep. Date

C152
PO 9460

RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

NASA Specification 20M32254

S-W Part No. 834000

S/N 03825/040010

Date FEB 25 1971

Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
5.1.1	Examination of Product	Acceptable/Nonacceptable	(T 24) (S) FEB 25 1971	
5.1.2	Internal Proof Pressure	Acceptable/Nonacceptable	18 PSIG - 5 MIN (T 8) FEB 26 71	
5.1.3	External Proof Pressure	Acceptable/Nonacceptable	70 PSIG - 5 MIN (T 8) FEB 26 71	
5.1.4	Internal Static Leakage	36 scch maximum	1) (T 8) scch 2) (T 8) FEB 26 71 scch 3) .12 scch	
5.1.5	External Static Leakage	1.0 x 10 ⁻⁶ sccs	< 3.7 x 10 ⁻⁷ (T 8) FEB 26 71	
5.1.6	Relief Operation	P outlet = 14.7 psia crack: 7.0 psid min full flow: 9.0 psid max reseat: 7.0 psid min	(psid) 1 2 3 crack: 8.0 8.0 8.0 full flow: 13.0 13.0 13.0 reseat: 7.9 7.9 7.9 (T 8) FEB 26 71	

Approvals:

Per [Signature]

Per [Signature]

FAIRCHILD HILLER
STRATOS-WESTERN
400 BOSTON AVENUE, MANASTAN BEACH, CALIF. 92008

Page No. 15
APP 51802

REPRODUCIBILITY OF THE ORIGINAL PAGE IS POOR.

REVISIONS



RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

FAIRCHILD HILLER
STRATOS-WESTERN
1800 ROSEBUSH AVENUE, MILPITAS, CALIF. 95028

NASA Specification 20M32254		S-W Part No. 834000	S/N 03825107009	Date FEB 25 1971
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
5.1.1	Examination of Product	Acceptable/Nonacceptable	FEB 25 1971	
5.1.2	Internal Proof Pressure	Acceptable/Nonacceptable	18 PSIG - 5 MIN T 8 FEB 25 71	
5.1.3	External Proof Pressure	Acceptable/Nonacceptable	20 PSIG - 5 MIN T 8 FEB 26 71	
5.1.4	Internal Static Leakage	36 scch maximum	1) scch 2) scch 3) scch FEB 26 71	
5.1.5	External Static Leakage	1.0 x 10 ⁻⁶ sccs	< 1.3 x 10 ⁻⁷ T 8 FEB 26 71	
5.1.6	Relief Operation	P _{outlet} = 14.7 psia crack: 7.0 psid min. full flow: 9.0 psid max. reseat: 7.0 psid min.	(psid) crack: 7.0 8.0 9.0 full flow: 7.3 7.3 8.3 reseat: 7.8 7.8 7.7 T 8 FEB 27 71	

Approvals:

REPRODUCIBILITY OF THE ORIGINAL PAGE IS POOR.

Page No. 18
228 834002

RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

FAIRCHILD HILLER
STRATOS-WESTERN
 1800 ROSEBANK AVENUE, MANHATTAN BEACH, CALIF. 90286

NASA Specification 20M32254		S-W Part No. 834000	S/N <i>03825/040008</i>	Date <i>12-9-70</i>																
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks																
5.1.1	Examination of Product	Acceptable/Nonacceptable																		
5.1.2	Internal Proof Pressure	Acceptable/Nonacceptable	<i>18 psig - 5 min</i> 	<i>Helicoid</i> <i>0-30 psig</i>																
5.1.3	External Proof Pressure	Acceptable/ Nonacceptable	<i>70 psig - 5 min.</i> 	<i>Helicoid</i> <i>0-200 psig</i>																
5.1.4	Internal Static Leakage	36 scch maximum	1) <i>2.4</i> scch 2) <i>1.2</i> scch 3) <i>0.9</i> scch	<i>Helicoid</i> <i>0-30 psig</i>																
5.1.5	External Static Leakage	1.0×10^{-6} scs	<i>< 2.2 x 10⁻⁷</i> 	<i>MARSH</i> <i>0-60 psig</i>																
5.1.6	Relief Operation	P _{outlet} = 14.7 psia crack: 7.0 psid min. full flow: 9.0 psid max. reset: 7.0 psid min.	<table border="1"> <tr> <td>(psid)</td> <td>1</td> <td>2</td> <td>3</td> </tr> <tr> <td>crack:</td> <td>8.0</td> <td>8.0</td> <td>8.0</td> </tr> <tr> <td>full flow:</td> <td>8.4</td> <td>8.4</td> <td>8.4</td> </tr> <tr> <td>reset:</td> <td>7.9</td> <td>7.9</td> <td>7.9</td> </tr> </table>	(psid)	1	2	3	crack:	8.0	8.0	8.0	full flow:	8.4	8.4	8.4	reset:	7.9	7.9	7.9	<i>BACTON</i> <i>AP-0-30psi</i>
(psid)	1	2	3																	
crack:	8.0	8.0	8.0																	
full flow:	8.4	8.4	8.4																	
reset:	7.9	7.9	7.9																	

Approvals:

<i>J. T. ...</i> S-W Q-C	Date .	<i>Robert W. ...</i> DCASR	<i>15 JAN 71</i> Date	<i>N/A</i> NASA Rep.	Date
-----------------------------	--------	-------------------------------	-----------------------	-------------------------	------

Page No. 15
 ATP 834002 "D"

RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

FAIRCHILD HILLER
STRATOS-WESTERN
 1800 ROSECRANS AVENUE, HANFORD, CALIF. 93230

NASA Specification 20M32254 S-W Part No. 834000 S/N *03825/040007* Date *12-1-71*

Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks																
5.1.1	Examination of Product	Acceptable/Nonacceptable																		
5.1.2	Internal Proof Pressure	Acceptable/ Nonacceptable	<i>18 psig - 5 min.</i> 	<i>Helicoid</i> <i>0-30 psig</i>																
5.1.3	External Proof Pressure	Acceptable/ Nonacceptabe	<i>70 psig - 5 min.</i> 	<i>Helicoid</i> <i>0-200 psig</i>																
5.1.4	Internal Static Leakage	36 scch maximum	1) <i>7.2 scch</i> 2) <i>6.0 scch</i> 3) <i>7.2 scch</i>	<i>Helicoid</i> <i>0-30 psig.</i>																
5.1.5	External Static Leakage	1.0×10^{-6} sccs	<i>5.3 x 10⁻⁷</i> 	<i>WASH</i> <i>0-60 psig</i>																
5.1.6	Relief Operation	P _{outlet} = 14.7 psia crack: 7.0 psid min. full flow: 9.0 psid max. reseal: 7.0 psid min.	<table border="1"> <tr> <td>(psid)</td> <td>1</td> <td>2</td> <td>3</td> </tr> <tr> <td>crack:</td> <td><i>8.6</i></td> <td><i>8.6</i></td> <td><i>8.6</i></td> </tr> <tr> <td>full flow:</td> <td><i>8.7</i></td> <td><i>8.9</i></td> <td><i>8.9</i></td> </tr> <tr> <td>reseal:</td> <td><i>8.2</i></td> <td><i>8.2</i></td> <td><i>8.2</i></td> </tr> </table>	(psid)	1	2	3	crack:	<i>8.6</i>	<i>8.6</i>	<i>8.6</i>	full flow:	<i>8.7</i>	<i>8.9</i>	<i>8.9</i>	reseal:	<i>8.2</i>	<i>8.2</i>	<i>8.2</i>	<i>BARTON</i> <i>DP. 0-30 psi</i>
(psid)	1	2	3																	
crack:	<i>8.6</i>	<i>8.6</i>	<i>8.6</i>																	
full flow:	<i>8.7</i>	<i>8.9</i>	<i>8.9</i>																	
reseal:	<i>8.2</i>	<i>8.2</i>	<i>8.2</i>																	

Approvals:
I. Tokuda JAN 13 71 *Robert W Wheeler* *13 Jan 71* *N/A*

S-W Q-C Date DCASR Date NASA Rep. Date

Page No. 15
 ATP 834002 "11"

RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

FAIRCHILD HILLER
 STANFORD WESTERN
 4100 ROSECRANS AVENUE, MANTANITA BEACH, CALIF. 90288

NASA Specification 20M32254		S-W Part No. 834000	S/N 03825LC40006	Date 3-17-71																
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks																
5.1.1	Examination of Product	Acceptable/ Nonacceptable	(SWB 24)	DIM. PERIDS																
5.1.2	Internal Proof Pressure	Acceptable/ Nonacceptable	18 psig (2)	NR 10 71																
5.1.3	External Proof Pressure	Acceptable/ Nonacceptable	70 psig (2)	NR 10 71																
5.1.4	Internal Static Leakage	36 scch maximum	1) \varnothing scch 2) \varnothing scch 3) \varnothing scch	NR 10 71																
5.1.5	External Static Leakage	1.0×10^{-6} sccs	7.2×10^{-7} (8)	NR 10 71																
5.1.6	Relief Operation	P _{outlet} = 14.7 psia crack: 7.0 psid min. full flow: 9.0 psid max. reseal: 7.0 psid min.	(psid) <table border="1"> <tr> <td></td> <td>1</td> <td>2</td> <td>3</td> </tr> <tr> <td>crack:</td> <td>7.9</td> <td>7.8</td> <td>7.8</td> </tr> <tr> <td>full flow:</td> <td>8.0</td> <td>8.1</td> <td>8.1</td> </tr> <tr> <td>reseal:</td> <td>7.6</td> <td>7.5</td> <td>7.6</td> </tr> </table>		1	2	3	crack:	7.9	7.8	7.8	full flow:	8.0	8.1	8.1	reseal:	7.6	7.5	7.6	NR 10 71
	1	2	3																	
crack:	7.9	7.8	7.8																	
full flow:	8.0	8.1	8.1																	
reseal:	7.6	7.5	7.6																	

Approvals:

I. Tokuda (W-1) MAR 10 1971 Date S-W Q-C
 R. Wheeler (164A) MAR 10 1971 Date DCASR
 _____ Date NASA Rep. _____ Date

ATP 834002

Page No. 15

"D"

RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

NASA Specification 20M32254		S-W Part No. 834000	S/N C3825/C4605	Date 3-19-71
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
5.1.1	Examination of Product	Acceptable/ Nonacceptable		PIMP PERIODS
5.1.2	Internal Proof Pressure	Acceptable/ Nonacceptable	18 psig	
5.1.3	External Proof Pressure	Acceptable/ Nonacceptable	70 psig	
5.1.4	Internal Static Leakage	36 scch maximum	1) -0 scch 2) -0 scch 3) -0 scch	
5.1.5	External Static Leakage	1.0×10^{-6} sccs	$< 1.8 \times 10^{-7}$	
5.1.6	Relief Operation	Poutlet = 14.7 psia crack: 7.0 psid min. full flow: 9.0 psid max. reseat: 7.0 psid min.	(psid) crack: 7.9 8.0 7.9 full flow: 8.2 8.3 8.3 reseat: 7.8 7.8 7.8	












FAIRCHILD MILLER
STRATOS-WESTERN
 1800 ROSCRANS AVENUE, HANBURY, SECON, CALIF. 92088

ATP 834002 "D"


Approvals:
I. Tokieda (T3) MAR 19 71 R. WHEELER DCASR Date NASA Rep. Date
 S-W Q-C Date

RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

FAIRCHILD HILLER
 STRATOS-WESTERN
 1000 BOSEMAN AVENUE, HANFORD, CALIF. 93230

NASA Specification 20M32254		S-W Part No. 834000	S/N <i>03825 K040004</i>	Date <i>12-7-70</i>	
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks	
5.1.1	Examination of Product	Acceptable/Nonacceptable			
5.1.2	Internal Proof Pressure	Acceptable/Nonacceptable	<i>18 psig - 5 min.</i>  DEC 7'70	<i>Helicoid</i> <i>0-30 psig</i> 	
5.1.3	External Proof Pressure	Acceptable/Nonacceptable	<i>70 psig - 5 min.</i>  DEC 7'70	<i>Helicoid</i> <i>0-200 psig</i> 	
5.1.4	Internal Static Leakage	36 scch maximum	1)  2) <i>.6 scch</i> 3) <i>.6 scch</i> DEC 7'70	<i>Helicoid</i> <i>0-30 psig</i> 	
5.1.5	External Static Leakage	1.0×10^{-6} sccs	<i>2.4×10^{-7}</i>  DEC 7'70	<i>MARSH</i> <i>0-60 psig</i> 	
5.1.6	Relief Operation	P _{outlet} = 14.7 psia crack: 7.0 psid min. full flow: 9.0 psid max. reseat: 7.0 psid min.	(psid)	<i>BAETO</i> <i>DP. 0-30 psi</i> 	
			crack:		<i>8.3</i> <i>8.2</i> <i>8.3</i>
			full flow:		<i>8.5</i> <i>8.5</i> <i>8.5</i>
			reseat:		<i>8.3</i> <i>8.3</i> <i>8.3</i>
			 JAN 13'71		

Approvals:

I. Tokuda  JAN 13'71 *Robert White* *15 JAN 71* *N/A*
 S-W Q-C Date DCASR Date NASA Rep. Date

Page No. 15
 ATP 834002
 "D"

RELIEF VALVE ASSEMBLY - ACCEPTANCE TEST DATA

FAIRCHILD HILLER
STATS-WEST FORM
1000 Aerospace and/or Maritime Applications

NASA Specification 20M32254		S-W Part No. 834000	S/N 03825K040003	Date 12-8-70
Ref. Paragraph	Test	Specification Requirements	Actual Performance	Remarks
5.1.1	Examination of Product	Acceptable/Nonacceptable	SWB 22 1/15/71	
5.1.2	Internal Proof Pressure	Acceptable/Nonacceptable	18 psig - 5 min. SWB 15 DEC 8'70	Helicoid 0-30 psig
5.1.3	External Proof Pressure	Acceptable/Nonacceptable	70 psig - 5 min. SWB 15 DEC 8'70	Helicoid 0-200 psig
5.1.4	Internal Static Leakage	36 scch maximum	1) SWB 1.5 scch 2) SWB 15 2.4 scch 3) DEC 8'70 2.4 scch	Helicoid 0-30 psig
5.1.5	External Static Leakage	1.0 x 10 ⁻⁶ scch	< 5.6 x 10 ⁻⁷ SWB 15 DEC 8'70	MARKSH 0-60 psig
5.1.6	Relief Operation	P _{outlet} = 14.7 psia crack: 7.0 psid min. full flow: 9.0 psid max. reset: 7.0 psid min.	(psid) crack: 7.8 7.8 7.8 full flow: 7.9 7.9 7.9 reset: 7.6 7.6 7.6 SWB 32 JAN 13 71	BARTON AP. 0-30 psi

Approvals: I. Tokuda SWB 32 JAN 13 71 Date . Robert White 15 JAN 71 DCASR Date N/A NASA Rep. Date

Page No. 15
ATP 834002 "D"

REPRODUCIBILITY OF THE ORIGINAL PAGE IS POOR.