

N72-30425

CASE FILE COPY


SUMMARY OF WORK PERFORMED UNDER

CONTRACT NO. NAS8-26348

SOLENOID VALVE, TYPE 1

NASA P/N 20M32258-1


(Carleton P/N 2426-0001-1)

PREPARED BY M. L. Baczkowski	6/15/72		CARLETON CONTROLS CORPORATION	EAST AURORA, NEW YORK 14052
APPROVED PROJ. ENGR. <i>M. L. Baczkowski</i>	16 JUNE 72	CODE IDENT. NO.	CR 150	REV.
APPROVED Q.C. ENGR. <i>E. Smolarek</i>	6-16-72	04577		
		CONTRACT NO. NAS8-26348	SHEET 1 OF 24	

REVISION STATUS OF SHEETS

Current Sheets of This Document are Listed Below

SHEET NO.	REV. LTR	SHEET NO.	REV. LTR	SHEET NO.	REV. LTR	SHEET NO.	REV. LTR




CARLETON CONTROLS CORP.
EAST AURORA, NEW YORK 14052

CODE IDENT.
04577

CR 150

REV.

SHEET 2

[illegible]

CARLETON CONTROLS CORP.
EAST AURORA, NEW YORK 14052

CODE IDENT.
04577

CR 150


REV.


SHEET 3

SCOPE


The purpose of this report is to document and summarize the results of Carleton's work on the Valve Assembly, Solenoid, 2-Way Normally closed, manufactured in accordance with MSFC drawing 20M32258, contract No. NAS8-26348, Carleton Controls PN 2426-0001-1.

The intended use of the valve was as a control element in the metabolic analyzer of biomedical experiment M-171 on the Skylab vehicle.

	CARLETON CONTROLS CORP. EAST AURORA, NEW YORK 14052	CODE IDENT. 04577	CR 150	REV. SHEET 4
---	---	-----------------------------	--------	-----------------



20M32258-1 Solenoid Valve, Type 1



CARLETON CONTROLS CORP.
EAST AURORA, NEW YORK 14052

CODE IDENT.
04577

CR 150

REV.

SHEET 5

HISTORY OF UNIT

The history of the unit will be covered in four steps:

- 1) Design Phase
- 2) Development Phase
- 3) Qualification Phase
- 4) Production Hardware

DESIGN PHASE

The design and development of this solenoid valve, MFSC PN 20M32258-1, presented several unique challenges which were successfully met in completing the order.

As in all spacecraft, minimization of equipment size and weight were important criteria. Page 26 of MSFC drawing 20M32258 (Exhibit A of Appendix) was used as a guide.

Looking at Carleton Controls drawing 2426-0002 (Exhibit B of Appendix) it is obvious that the specification goals were met and even bettered in the size and weight category.

To achieve this goal, extensive use was made of precision machined components optimized in size by design pressure requirements. In addition, the use of welding as an attachment and pressure retention device was utilized. See Carleton Controls drawing and parts list 2426-0001 (Exhibit C of Appendix). This eliminated the need for threaded fastenings to hold items ① and ③ of drawing 2426-0001 together, and, as these are pressure boundary parts, it also eliminated the need for an "O" Ring Seal at their

	CARLETON CONTROLS CORP. EAST AURORA, NEW YORK 14052	CODE IDENT. 04577	CR 150	REV.
				SHEET 6

interface.

Examination of item (6) Poppet and Plate Assembly on CCC drawing 2426-0001 will reveal two key features of the unit. One is the seat and seat retainer. The seat is retained in the core by a barbed metal center piece. This centers the seat in its cavity and by virtue of a slight undercut in the core piece creates a snap-in assembly. The need for thread retainers is eliminated making the design miniaturized and highly reliable. Another feature of this assembly is the centering effect the belleville spring, item (2), has on the poppet and plate assembly, item (6). This guides the assembly when the coil is energized and eliminates any sliding metal-to-metal contact.


DEVELOPMENT PHASE

The development phase of the contract consisted of testing during the assembly of the development unit, and after assembly, full fledged development testing.

During the pre-development testing, while the unit was being assembled, extensive work was done on the bifilar coil winding. Sample coils were wound, as below:

- a) Conventionally
- b) Conventionally on insulated copper spool
- c) Bifilar coil on insulated copper spool

Voltage traces were taken with the results showing the bifilar coil on the insulated copper spool to have the lowest back EMI. The purpose

	CARLETON CONTROLS CORP. EAST AURORA, NEW YORK 14052	CODE IDENT. 04577	CR 150	REV.
				SHEET 7

of this testing was to insure that the unit would meet the requirements of the "Orbital Workshop System (OWS) Electromagnetic Compatibility Control Plan No. 50M13087", particularly paragraph 5.4.5.2, Section d. This section states "transient levels on D.C. power busses do not exceed 50% of nominal bus voltage". Examining Exhibits E, F, and G, it is evident that the bifilar wound coil on the copper spool meets that requirement.

The development test procedure, CCC DTP 2426, was submitted to MSFC on 9 Sept. 1970. It was subsequently approved and the unit was then tested. The testing was successfully completed on 26 Feb. 1971 and results forwarded to MSFC under separate cover. A list of test sequences (Exhibit H) is enclosed in this report for reference.

QUALIFICATION PHASE

Two production units, serial no. 16 and 17 were selected to go through qualification testing per contract requirements. The qualification test procedure, CCC QTP 2426, was submitted to MSFC on 24 Sept. 1970, and subsequently approved.

The successful completion of qualification testing and submittal of qualification report QTR 2426 to MSFC was accomplished on 19 Nov. 1971.

PRODUCTION HARDWARE

Twenty eight (28) pieces of production hardware were shipped to MSFC to satisfy contract requirements. The program ran smoothly at Carleton for several reasons. One important one is the high level of technical

	CARLETON CONTROLS CORP. EAST AURORA, NEW YORK 14052	CODE IDENT. 04577	CR 150	REV.
				SHEET 8

competence exhibited at all levels in the Carleton organization. As an aid to assembly and testing of the valves, several documents were generated by Carleton Engineering personel. They proved to be invaluable during this phase of the contract. Exhibit J and K valve shimming set up sheets are an example of one of these documents. These sheets were used to set up each unit to acheive specified performance.

The critical assembly check list, Exhibit L, accompanied each valve through the assembly phase and provided Quality Control with a check list of operations performed.


Each valve was tested to and passed the requirements of CCC ATP 2426. This document met the testing requirements of MSFC Spec. 20M32258 and was approved by MSFC. This acceptance testing insured that the performance of the solenoid valves met design requirements. A sample set of data sheets has been included in this report as Exhibit M.

One failure occured during the production phase of the program. CFA 191 (Exhibit N) contains the analysis and corrective action required.


One failure occured during acceptance testing at MSFC. This is documented in CFA 222 (Exhibit P).

CONCLUSION

It is the opinion of Carleton Controls that all work performed under this contract was done in the best possible manner by the most expeditious route and at the most economical price. The cooperation exhibited by NASA personel during this program was at all times of the highest degree.


	CARLETON CONTROLS CORP. EAST AURORA, NEW YORK 14052	CODE IDENT. 04577	CR 150	REV.
				SHEET 9

Carleton further believes that the solenoid valve performance exceeds specification requirements, specifically in the areas of size, weight, and low leakage. This bonus was achieved by a combination of conscientious engineering, fabrication, inspection, and assembly.

	CARLETON CONTROLS CORP. EAST AURORA, NEW YORK 14052	CODE IDENT. 04577	CR 150	REV.
				SHEET 10

APPENDIX 1

Exhibits

	CARLETON CONTROLS CORP. EAST AURORA, NEW YORK 14052	CODE IDENT. 04577	CR 150	REV.
				SHEET 11

REVISIONS

SYM	DESCRIPTION	DATE	APPROVAL
-----	-------------	------	----------

A changed






FIGURE 1 - Configuration

*

CODE IDENT NO	DWG SIZE A	20M32258
		SHEET 26 of 26

[illegible][illegible]

YOMR	LTA	DESCRIPTION	DATE	REMARKS
	1	E.O. 2426-20	9 DEC 70	100%




NOTES:


- 1 SOLDER PER NASA PUBLICATION NHB 5303.4 (3A)
- 2 AFTER ASSY & TEST REMOVE TEMPORARY GASKET & ELECTRON BEAM WELD ALL AROUND
- 3 AFTER WELDING ALL FOUR MTG. FACES TO BE PARALLEL WITHIN .005 TIR
- 4 PURGE & BACKFILL WITH 1 ATM OF COMMERCIAL GRADE A OR AA HELIUM

CR 150
Exhibit C

Sheet 14




LOCATION OF
TEMPORARY GASKET
(NOT SHOWN)



SEE SEPARATE PARTS LIST

SCHEMATIC



REV	QTY	PART NUMBER	NOMENCLATURE	CODE IDENT	MATERIAL	SPECIFICATION	FINAL
1		2426-0001-1	VALVE, SOLENOID TWO WAY N.C.				
2							
3							
4							
5							
6							
7							
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							
22							
23							
24							
25							
26							

UNLESS OTHERWISE SPECIFIED:
DIMENSIONS ARE IN INCHES
ALL DIMENSIONS AFTER PLATING
ALL SURFACES TO BE $\sqrt{v}$ PER USAS 848.1 B2
ALL DIAMETERS TO BE CONCENTRIC
WITHIN .008 T.I.R.
ALL INTERNAL AND EXTERNAL
FILLET RADI .010 MAX.
BREAK SHARP EDGES .015 $\times$ 45° MAX.
ALL THREADS PER MIL-S-7742
FRACTION DECIMAL ANGLE
1/64 .0039 1/2°
1/32 .0078 1/2°
3/64 .0156 1/2°
1/8 .0312 1/2°
3/16 .0469 1/2°
1/4 .0938 1/2°
5/16 .0938 1/2°
3/8 .1250 1/2°
7/16 .1562 1/2°
1/2 .1875 1/2°
5/8 .2500 1/2°
3/4 .3125 1/2°
7/8 .3750 1/2°
1 .5000 1/2°

CONTRACT NO. NAS8-26348
DRAWN BY M. BAZKOWSKI
DESIGN
CHECK
PROJ ENGR
R. CUMMINS
APPROVAL DESIGN ACTIVITY
APPROVAL OTHER

ASSEMBLY
VALVE, SOLENOID
TWO WAY N.C.
CODE IDENT 04577
DRAWING NUMBER 2426-0001
REV E

PARTS LIST

CARLETON CONTROLS CORP.
EAST AURORA, NEW YORK 14052

CONTRACT NO.
NAS8-26348

CODE IDENT.
04577

PL 2426-0001

REV. LTR.

LIST TITLE

VALVE SOLENOID, 2-WAY NORMALLY CLOSED

AUTHENTICATION

M. Baczowski

DATE

7/31/70

REV. AUTHORIZATION NO.

50 2426-13

SHEET 2

OF 3

FIND NO.	QTY.	REQ'D.	SYMBOL	CODE IDENT.	PART NUMBER	DESCRIPTION	REMARKS
	-1				2426-0001	Assembly, Valve Solenoid	
					2426-0002	Installation, Valve Solenoid	
1	1				2426-0010-1	Body	
2	1				2426-0011-1	Belleville	
3	1				2426-0037-1	Solenoid Housing	
4	1				2426-0014-1	Spring Bearing Ring Outer	
5	1				2426-0015-1	Spring Bearing Ring Inner	
6	1				2426-0030-1	Poppet & Plate Assembly	1
7					NOT USED		
8					NOT USED		
9	1				2426-0023-1	Top Plate	
10	1				2426-0038-1	Solenoid Coil Assembly	1
11	1				2426-0026-1	Filter Retainer	
12	1				1030-0010-2	Lock Plug	
13	1		PP	14834	F-4173-41-10	Filter Disc	Microporous Filter Division
14	1		PP		MS 16624-18	Ring Retaining Ext.	
15	A/R				2426-0027-1	Shim	
16	A/R				2426-0027-3	Shim	
17	A/R				2426-0027-5	Shim	
18	A/R				2426-0027-7	Shim	
19	1				2426-0028-1	Coil Retaining Sleeve	
20	A/R				2426-0029-1	Spacer	
21	1		PP	11139	DBA53H-8-98PN	Receptacle, Connector	The Deutsch Company

SYMBOLS:

BI - Bulk Item SCD - Spec or Source
PP - Purchased Part Control Drawing



See Separate Parts List



Vendor Item - See Spec or Source Control Drawing


SHEET 3
OF 3

Vendor Item - See Spec or Source Control Drawing


VOLTAGE TRACE CONVENTIONALLY
WOUND COIL

0 Volts


14 VDC



VOLTAGE TRACE CONVENTIONALLY WOULD COIL ON INSULATED COPPER SPOOL



VOLTAGE TRACE BIFILAR WOUND COIL ON INSULATED COPPER SPOOL, THREE WIRE SIZE DIFFERENCE



CARLETON CONTROLS CORPORATION

SPEC. NUMBER	REVISION LETTER												PAGE
DTR 2426													7

4.0 TEST SEQUENCE

4.1 Development Tests:

Carleton DTP 2426 <u>Ref. Para.</u>	NASA 20M32258 <u>Ref. Para.</u>	<u>Test Description</u>
5.1	4.3.2	Examination of Product
5.2	4.3.3.1 a & b	Internal Proof Pressure
5.3	4.3.3.2 a & b	External Proof Pressure
5.4	4.3.3.3 a 1 & 2	Internal Leakage Check
5.5	4.3.3.3 b	External Leakage Check
5.6	4.3.3.4	Pull In, Drop Out Voltages
5.7	4.3.3.5	Insulation Resistance
5.8	4.3.3.6	Operating Current
5.9	4.3.4.5	Low Temperature
5.10	4.3.3	Functional Tests
5.11	4.3.4.4	High Temperature
5.12	4.3.3	Functional Tests
5.13	4.3.4.8	Vibration
5.14	4.3.3	Functional Tests
5.15	4.3.4.10	Equivalent Orifice
5.16	4.3.4.11	Duty Cycle
5.17	4.3.3	Functional Tests
5.18	4.3.4.12 (a)	Life Cycle - High Pressure
5.19	4.3.3	Functional Tests
5.20	4.3.4.13	Burst Pressures
5.21	4.3.4.14	Collapse Pressures

2426

SOLENOID VALVE

(1) A
-B

=C

(1a) E
-F

=G

(2) D
-G

=H

(3) C
-H

=In = POSSIBLE STROKE WITHOUT SPACERS

(4) .010 = DESIRED STROKE
-In

=Is = THICKNESS OF SPACERS REQUIRED FOR DESIRED STROKE

(5) J
-E

=K

(6) K
+.010

=L

(7) A
-M

=N



(8) N
-L

=Pn = BELLEVILLE DEFLECTION WITHOUT SPACERS

(9) .020
-Pn

Ps = THICKNESS OF SPACERS REQUIRED FOR DESIRED BELLEVILLE
DEFLECTION

2426 SOLENOID VALVE



BODY

CRITICAL ASSEMBLY CHECK
LIST
FOR 24-26

UNIT

S/N

OPERATION

INSPECTION

- 1) Install teflon into poppet
- 2) Check required stroke shimming
- 3) Check required balleville deflection shimming
- 4) Verify installation of filter
- 5) Tighten welding fixture screws
- 6) Verify coil removal prior to welding
- 7) Verify operation after welding
- 8) Use only a CCC NASA card holder for soldering
- 9) Perform post back filling leak check

CARLETON CONTROLS CORPORATION

SPEC. NUMBER ATP 2426	REVISION LETTER												PAGE A1

ACCEPTANCE TEST DATA

FOR

2426-0001-1 2-WAY SOLENOID VALVE

S/N 2

CARLETON CONTROLS CORPORATION

SPEC. NUMBER	REVISION LETTER	PAGE																		
ATP 2426	<table border="1" style="width: 100%; height: 20px; border-collapse: collapse;"> <tr> <td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td> </tr> </table>																			A2

Customer NASA - MSFC
 Specification _____
 P/N _____
 Test Time (hrs.) _____
 Total Operating Hrs. _____
 Operating Cycles/Test _____
 Total Operating Cycles _____
 Test Facility C.C.C.

CCC P/N 2426 0001-1
 S/N 2
 Date 3-9-71
 Test No. _____
 Ref. Paragraph _____
 Schematic Figure _____
 Temperature N/A
 Barometer/Pressure N/A
 Test Fluid N/A

DESCRIPTION OF TEST Examination of Product (4.3.2)

Ref. Para. 5.1

Examine the unit for conformance to:

CCC drawing 2426-0002

CONFORMS

Workmanship

ACCEPTABLE

Identification

CONFORMS

REMARKS:

Passed
Failed

Customer or Rep.

Date

Test Engineer

Date



3-9-71

Date

Quality Control

Date

CARLETON CONTROLS CORPORATION

SPEC. NUMBER	REVISION LETTER												PAGE	
ATP 2426	A	B												A3

Customer NASA - MSFC
 Specification _____
 P/N _____
 Test Time (hrs.) _____
 Total Operating Hrs. _____
 Operating Cycles/Test _____
 Total Operating Cycles _____
 Test Facility C. C. C.

CCC P/N 2426 0001-1
 S/N 2
 Date 3-9-71
 Test No. _____
 Ref. Paragraph _____
 Schematic Figure _____
 Temperature ROOM
 Barometer/Pressure LOCAL AMBIENT
 Test Fluid N₂

DESCRIPTION OF TEST Internal Proof Pressure (4.3.3.1)

Ref. Para. 5.2

(a) Housings - Apply 420 PSIG to the inlet with the outlet port capped and the unit in the open position for 5 minutes. (A)

(b) Inlet - With the unit in the closed position and the outlet open, apply 420 PSIG to the inlet for 5 minutes. (A) (B)

REMARKS:

Passed ☒
 Failed

Customer or Rep.

Date

Test Engineer

Date



Date

Quality Control

Date

CARLETON CONTROLS CORPORATION

SPEC. NUMBER ATP 2426	REVISION LETTER	PAGE A4																				
	<table border="1" style="width: 100%; height: 20px;"> <tr> <td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td> </tr> </table>																					

Customer NASA - MSFC
 Specification _____
 P/N _____
 Test Time (hrs.) _____
 Total Operating Hrs. _____
 Operating Cycles/Test _____
 Total Operating Cycles _____
 Test Facility C.C.C.

CCC P/N 2426 0001-1
 S/N 2
 Date 3-9-71
 Test No. _____
 Ref. Paragraph _____
 Schematic Figure _____
 Temperature ROOM
 Barometer/Pressure LOCAL AMBIENT
 Test Fluid N2

DESCRIPTION OF TEST External Proof Pressure (4,3,3,2)

Ref. Para. 5.3.

(a) Housing - With the unit inlet and outlet ports capped, apply 70 PSIG to the chamber and hold for 5 minutes.

(b) Outlet - With the inlet port capped and the outlet open, apply 70 PSIG to the chamber for 5 minutes.

REMARKS:

Passed ☒
 Failed ☐

Customer or Rep.

Date

Test Engineer

Date

Date

Quality Control

Date

CARLETON CONTROLS CORPORATION

SPEC. NUMBER ATP 2426	REVISION LETTER												PAGE A5
	A												

Customer NASA-MSEC
 Specification _____
 P/N _____

CCC P/N 2426 0001-1
 S/N 2
 Date 3-9-71

Test Time (hrs.) _____
 Total Operating Hrs. _____
 Operating Cycles/Test _____
 Total Operating Cycles _____
 Test Facility C.C.C.

Test No. _____
 Ref. Paragraph _____
 Schematic Figure _____
 Temperature ROOM
 Barometer/Pressure LOCAL AMBIENT
 Test Fluid N2

DESCRIPTION OF TEST Internal Leakage (4.3.3.3 (a) 1 & 2)

Ref. Para. 5.4.2

Apply 1, 15, 20 and 210 PSIG to the inlet of the unit. At each pressure (A)
 the unit shall be checked for leakage 3 times with a minimum of 1 cycle
 between checks.

Ref. Para. 5.4.3

At 1 and 15 PSIG the maximum allowed leakage is .001 sccs. (A)

Ref. Para. 5.4.5

At 20 and 210 PSIG the maximum allowed leakage is .01 sccs. (A)

Inlet PSIG	Max. Allowed Leakage	Actual Leakage		
		#1	#2	#3
1	.001 sccs	<.0001	<.0001	<.0001
15	.001 sccs	<.0001	<.0001	<.0001
20	.01 sccs	<.001	<.001	<.001
210	.01 sccs	<.001	<.001	<.001

REMARKS:

Passed ☒
 Failed

Customer or Rep.

Date

J. Wallerhausen 3-9-71
 Test Engineer Date



Date

Quality Control

Date

CARLETON CONTROLS CORPORATION

SPEC. NUMBER ATP 2426	REVISION LETTER												PAGE A6
	A												

Customer NASA - MSFC
 Specification _____
 P/N _____

CCC P/N 24 26 0001-1
 S/N 2
 Date 3-10-71
 Test No. _____
 Ref. Paragraph _____
 Schematic Figure _____
 Temperature _____
 Barometer/Pressure _____
 Test Fluid He

Test Time (hrs.) _____
 Total Operating Hrs. _____
 Operating Cycles/Test _____
 Total Operating Cycles _____
 Test Facility C.C.C.

DESCRIPTION OF TEST External Leakage (4.3.3.3 (b))

Ref. Para. 5.5.2

Apply 210 PSIG to the inlet and outlet of the unit. Let stabilize and monitor leakage (A)

Maximum allowable leakage 0.000001 sccs. (A)

Actual Leakage 2.1×10^{-9} sccs.

DESCRIPTION OF TEST Pull In, Drop Out Voltages (4.3.3.4)

Ref. Para. 5.6.2

Apply 210 PSIG to the inlet of the unit. On increasing voltage, the unit must open before 18 VDC. On decreasing voltage the unit must close before 2 VDC. (A)

	Open	Closed
Inlet	16.8 VDC	6.2 VDC
210	16.8 VDC	6.4 VDC
PSIG	16.8 VDC	6.3 VDC

REMARKS:

Passed ☒
 Failed

Customer or Rep.

Date

Test Engineer

Date

Date

Quality Control

Date

CARLETON CONTROLS CORPORATION

SPEC. NUMBER	REVISION LETTER	PAGE																		
ATP 2426	<table border="1" style="width: 100%; height: 20px; border-collapse: collapse;"> <tr> <td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td> </tr> </table>																			A7

Customer MDAC-MSFC
 Specification _____
 P/N _____

CCC P/N 2426 0001-1
 S/N 2
 Date 3-10-71

Test Time (hrs.) _____
 Total Operating Hrs. _____
 Operating Cycles/Test _____
 Total Operating Cycles _____
 Test Facility C.C.C.

Test No. _____
 Ref. Paragraph _____
 Schematic Figure _____
 Temperature Room
 Barometer/Pressure LOCAL AMBIENT
 Test Fluid N/A

DESCRIPTION OF TEST Insulation Resistance (4.3.3.5)

Ref. Para. 5.7.1

Apply 500 VDC to ungrounded terminal pins and unit body for 60 seconds.

The resistance shall be greater than 50 megohms.

Actual 80,000 megohms

REMARKS:

Passed ☒
 Failed

		<u>J. Wallenauer</u>	<u>3-10-71</u>
Customer or Rep.	Date	Test Engineer	Date
			
Date		Quality Control	Date

CARLETON CONTROLS CORPORATION

East Aurora, New York

FAILURE ANALYSIS REPORTREPORT S/N CFA 191DATE September 17, 1971CUSTOMER NASA Marshall Space Flight CenterP.O. NO. NAS8-26348CUSTOMER P/N 20M32258 Rev. S/N C.C.C. P/N 2426-0001-1 Rev. E S/N 10CUSTOMER REJECTION NOTICE NO. N/ADATE OF RECEIPT AT C.C.C. N/ADATE OF ORIGINAL MANUFACTURE 7/71COMPONENT SPECIFICATION 20M32258

PERSONNEL CONDUCTING ANALYSIS:

M. HulseE. SmolarekANALYSIS APPROVAL:Q.C. DEPT. *[Signature]*ENG. DEPT. *Ray Bergeron*

DESCRIPTION OF DISCREPANCY:

Failure while at ATP (2426 ref. para. 5.6), unit failed to open before the 18 VDC allowed - Actual pull in voltage was 18.2 VDC.

RETEST OR VERIFICATION TEST RESULTS:

The unit was re-energized several times and the voltage remained on the border line.

ANALYSIS OF FAILURE CAUSE:

It was found that the coil in this particular unit was wound to the high limit of B/P requirements.

REPAIR/REWORK DATA:

A new coil was installed in the unit and functioned perfectly thru all phases of testing.

CONCLUSION:

In preliminary testing and set up the unit functioned satisfactorily, however additional stabilization occurred and the coil required more voltage to operate - With the installation of a new coil (less amp. turns) voltage was reduced for actuation of the unit.

CORRECTIVE ACTION:

Coil winding has been controlled to keep resistance to a lower level to preclude a reoccurrence of this condition.

CARLETON CONTROLS CORPORATION

East Aurora, New York

FAILURE ANALYSIS REPORTREPORT S/N CFA 222DATE 4/24/72CUSTOMER M.S.F.C.P.O. NO. NAS8-26348CUSTOMER P/N 20M 32258-1 Rev. --- S/N 8C.C.C. P/N 2426-0001-1 Rev. E S/N 8CUSTOMER REJECTION NOTICE NO. M 12829DATE OF RECEIPT AT C.C.C. 3-27-72DATE OF ORIGINAL MANUFACTURE 4/71COMPONENT SPECIFICATION 20M 32258

PERSONNEL CONDUCTING ANALYSIS:

M. BaczkowskiE. SmolarekP. HartwellANALYSIS APPROVAL:Q.C. DEPT. *W. J. Heiser*ENG. DEPT. *M. L. Baczowski*

CUSTOMER DESCRIPTION OF DISCREPANCY:

Unit shorting out both coil leads to case.

RETEST OR VERIFICATION TEST RESULTS:

Rejection confirmed - Unit exhibited insulation on coils wires burned or melted off. Both leads shorting out to case. Upon installation of new coil with proper electrical characteristics, the unit exhibited a high pull in voltage of 22 VDC. (18 VDC Max. Spec. value).

ANALYSIS OF FAILURE CAUSE:

Possible incorrect application of power during testing of insulation resistance at customer facility. This would generate an excessive amount of heat in the unit, which could alter Solenoid Air Gap by changing Seat Footprint or warping gap adjustment shims. This would cause a high pull in voltage.

REPAIR/REWORK DATA:

Unit must be cut apart at Body/Coil Housing junction and seat examined for possible defects and replaced if necessary. Air Gap must be reset, unit re-welded, new coil installed and retested to ATP 2426.

CONCLUSION:

Incorrect application of power in excess of design limits (2 to 18 VDC Operating) will cause overheating of coil and breakdown of wire insulation, plus possible change in Air Gap by altering Seat Footprint and/or gap adjustment shims. The investigation of the unit indicated that this was the cause of failure.

CORRECTIVE ACTION:

Personnel connected with testing of unit to be re-instructed in proper method of performing Insulation Resistance Check.