

## **General Disclaimer**

### **One or more of the Following Statements may affect this Document**

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.
- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.
- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.
- This document is paginated as submitted by the original source.
- Portions of this document are not fully legible due to the historical nature of some of the material. However, it is the best reproduction available from the original submission.

# DOE/NASA CONTRACTOR REPORT

DOE/NASA CR-150593

## MODULAR CONTROL SUBSYSTEMS FOR USE IN SOLAR HEATING SYSTEMS FOR MULTI-FAMILY DWELLINGS


Prepared by

Solar Control Corporation  
5595 Arapahoe Road  
Boulder, CO 80302

Under Contract NAS8-32258 with

National Aeronautics and Space Administration  
George C. Marshall Space Flight Center, Alabama 35812

For the U. S. Department of Energy



(NASA-CR-150593) MODULAR CONTROL SUBSYSTEMS  
FOR USE IN SOLAR HEATING SYSTEMS FOR  
MULTI-FAMILY DWELLINGS Quarterly Report, 15  
Oct. 1976 - 15 Jan. 1977 (Solar Control  
Corp., Boulder, Colo.) 9 p HC A02/MF A01

N78-20613

Unclas  
G3/44 11847

# U.S. Department of Energy



**Solar Energy**

1. REPORT NO. DOE/NASA CR-150593	2. GOVERNMENT ACCESSION NO.	3. RECIPIENT'S CATALOG NO.	
4. TITLE AND SUBTITLE Modular Control Subsystems for Use in Solar Heating Systems for Multi-Family Dwellings		5. REPORT DATE January 1977	
		6. PERFORMING ORGANIZATION CODE	
7. AUTHOR(S)		8. PERFORMING ORGANIZATION REPORT #	
9. PERFORMING ORGANIZATION NAME AND ADDRESS Solar Control Corporation 5595 Arapahoe Road Boulder, CO 80302		10. WORK UNIT NO.	
		11. CONTRACT OR GRANT NO. NAS8-32258	
12. SPONSORING AGENCY NAME AND ADDRESS National Aeronautics and Space Administration Washington, D. C. 20546		13. TYPE OF REPORT & PERIOD COVERED Contractor Report Oct 15, 1976 - Jan 15, 1977	
		14. SPONSORING AGENCY CODE	
15. SUPPLEMENTARY NOTES This work was done under the technical management of Mr. James Hankins, George C. Marshall Space Flight Center, Alabama.			
16. ABSTRACT  This document is the first quarterly report from Solar Control Corporation reflecting the progress of work from October 15, 1976, through January 15, 1977. Solar Control, under NASA/MSFC Contract NAS8-32258, is developing three identical modular control sub-systems for use in solar heating systems for multi-family dwellings.  The quarterly report has been reformatted, and the pages renumbered. A limited amount of retyping has been done, and cost information removed.			
17. KEY WORDS		18. DISTRIBUTION STATEMENT Unclassified-Unlimited  <i>William A. Brooksbank, Jr.</i> WILLIAM A. BROOKSBANK, JR. Manager, Solar Heating & Cooling Proj Ofc	
19. SECURITY CLASSIF. (of this report) Unclassified	20. SECURITY CLASSIF. (of this page) Unclassified	21. NO. OF PAGES 9	22. PRICE NTIS

## TABLE OF CONTENTS

		<u>Page</u>
Part I	Summary	1
Part II	Contract	1
Part III	Schedules	2
Part IV	Technical Performance	2

Contract No. NAS 8-32258

Quarterly Report

Part I. Summary

This report details activity under the contract for the first quarterly period.

One change proposal, CP77-1, has been submitted by Solar Control Corporation (SCC) and has been accepted formally at MSFC. This addition to the contract will delay the original hardware delivery schedule about four weeks. Appropriate additions and changes to the baseline documents have been reported to the Technical Manager or are in process.

Technical status of the contract work is described. Data, curves, charts and test results are included. Also included is a forecast of activities needed for completion of the contract. One apparent remaining problem is discussed.

Part II. Contract

At the end of the first quarter year of the contract period, work and documentation for contract items is on schedule. However, the original schedule has been modified to accommodate a Change Proposal.

Change Proposal CP77-1, "Mechanical Packaging Addition", was submitted to Technical Director J. Hankins on January 15, 1977; this proposal has been informally accepted at MSFC. Baseline documents are being updated to reflect this change. The addition of CP77-1 to the contract will delay the original schedule for hardware delivery by about four weeks.

### Part III. Schedules

The development plan schedule has been updated to reflect CP77-1. The milestone chart has been modified accordingly.

#### Development Plan Schedule

Preliminary Design Review	Completed January 6, 1977
Quarterly Review	{ March 30, 1977
Prototype Design Review	
First Article Review	April 20, 1977
Hardware Delivery	May 18, 1977

### Part IV. Technical Performance

#### A. General description of work

Design: Circuit design is completed and drawings showing circuits are complete. PCB layout is completed. All electronic parts are on order. The mechanical housing authorized in CP77-1 has been ordered to a commercial drawing number. However, drawings reflecting this addition are not yet completed.

Manuals: Maintenance Manuals and Installation instructions had not been completed pending acceptance of CP77-1. These are now in process and the first draft should be completed prior to the Prototype Design Review. Detailed procedures for Verification and acceptance testing are being prepared.

Prototype Design Review: This has been re-scheduled for February 23, 1977, at Solar Control Corporation in Boulder, Colorado. It is assumed this review will also cover the required Quarterly Review.

#### B. Forecast of activities for completion

Key items to be completed are:

1. Installation instructions (preliminary)
2. Maintenance Manual (preliminary)
3. Top assembly drawings for 75-172, 75-173, and 75-175

These items are scheduled for completion by February 15, 1977.

C. Identification of problems


The largest problem remaining is to reach agreement with Underwriters Laboratories on the scope, schedule, and cost for UL testing and approval of the modules at 120 V. This agreement will be sought in the near future.

D. Verification Status and data.

Calculations were made to determine predicted performance of the 75-171 differential thermostat. Then calculated values were tested for the offset temperature, boil and freeze protect points. These tests covered items 1.7 (Control), 4.2 (Fail Safe Control), and 4.2.1 (System Failure Prevention) of the Verification Cross Reference Matrix. Details and results of the testing are attached.

## Calculated Performance

The differential controller utilizes a bridge configuration with a thermistor temperature sensing element in each leg.\* A voltage comparator inclosed across the bridge senses any imbalance of the bridge and provides a control signal when an imbalance exists. The switching point of the comparator exists at the point where the voltages are equal. Each element of the bridge illustrated below has a numerical assignment to identify it.



The voltage at the junction of a voltage divider (the junction of  $R_1$  &  $R_2$ , and the junction of  $R_3$  &  $R_4$ ) can be described mathematically by:

$$V = \frac{(R_2)(V_{REF})}{R_2 + R_1} \quad \text{and} \quad V = \frac{(R_3)(V_{REF})}{R_3 + R_4} \quad (1)$$

It is required to analyze the circuit operation at the point where it switches from one stage to the other. Since the switching point occurs where the two voltages are equal, the above equations are made equal to each other.

$$\frac{(R_2)(V_{REF})}{R_2 + R_1} = \frac{(R_3)(V_{REF})}{R_3 + R_4} \quad (2)$$

Solving for  $R_2$  we obtain:

$$R_2 = \frac{R_4 R_1}{R_3} \quad (3)$$

Thus we can obtain the resistance of  $R_2$  for any given resistance of  $R_1$ ,  $R_3$ , &  $R_4$ .  $R_2$  and  $R_4$  represent the temperatures of collector and storage. In testing the device, a calibrated resistance is substituted for  $R_4$ , representing a given temperature (see Table I, Thermal resistance chart). The measured resistance of  $R_2$  then related to the temperature of the collector, which can be found on the chart.

To produce an offset,  $R_1$  is altered by the parallel resistance of the "offset" resistor. The combination of the two is calculated by:

$$R_{OFF(COMBINATION)} = \frac{1}{1/R_1 + 1/R_{SET}} \quad (4)$$

\* The thermistor manufacturer provides a table of resistance vs. temperature.

This value is substituted in equation (3) and the value of  $R_2$  is calculated at each extreme of the temperature span of interest by using the corresponding resistance of  $R_4$  derived from Table I.

For example, if we desire to find the "off" point of the system when the storage is at  $100^\circ\text{F}$ , we convert to Centigrade:  
 $100^\circ\text{F} = 38^\circ\text{C}$

From the chart, we know that the storage probe resistance is 16,697 ohms. Substituting this value in equation (3) we obtain:

$$R_2 = \frac{16,697 \times 9130}{10000}$$

$$R_2 = 15244 \Omega$$

From the chart, we see that the collector must be close to  $40^\circ\text{C}$ . We have a differential of  $(40 - 38) = 2^\circ\text{C}$  or  $3.6^\circ\text{F}$ .

This calculation was carried out for  $40^\circ\text{F}$  and  $180^\circ\text{F}$  to establish the "off" points illustrated in Graph 1.

Similarly, a resistor is placed in parallel with the combination of  $R_1$  and the "off" resistor to establish the "on" set point. This is calculated by:

$$R_{\text{ON (COMBINATION)}} = \frac{1}{1/R_1 + 1/R_{\text{OFF (COMB)}}}$$


This value is plugged into equation (3) and the value of  $R_2$  is calculated at each extreme of the temperature span of interest by using the corresponding resistance of  $R_4$  derived from the table. This establishes the "on" point illustrated in graph 1.

To check linearity of the graphs, several intermediate points may be calculated using the same methods.

It should be noted that the charts show temperatures in Centigrade; conversion to Fahrenheit may be made for the convenience of the users of the graph.

#### Boil and Freeze Protect

The boil and freeze protect circuits operate in much the same manner as described above, except that one side of the bridge is composed of fixed resistors instead of a resistor and a temperature sensor. The trip points for these functions are set by the selection of the lower resistor ( $R_4$ ). This is accomplished by using the corresponding resistance of the desired temperature from the chart.



## Testing

It is desired to test whether the control "ON" and "OFF" points operate as intended. Since actual temperature changes for the probes would be awkward, and might tend to introduce error, a resistance substitution method was used. Precision resistors were substituted for the probes, the value of the resistor directly relating to temperature according to published charts of the manufacturer. (Guaranteed accuracy of the thermistors is 1%.)


The "on and "off" trip points were checked at three points: 40°F, 100°F, and 180°F. Circuit performance was verified at each point by checking it three times at each temperature.

The collector probe resistance was run down to 32° F to check for freeze control and the storage probe resistance was run up to 210° F to check for boil protect.

This test was carried out with the controller at three different temperatures: 40°F, 72°F (room temperature), and 140°F. In each case, the controller was held at that temperature for two hours prior to and during the test. Again, the "on" and "off" points were tested three times in each case.

### Test results

No measurable deviation from the predicted performance was observed in any of the above tests.



ORIGINAL PAGE IS  
OF POOR QUALITY

STORAGE TEMP IN °F  
75-171 CONTROLLER

G.A.R. 11-11-1

# INTERCHANGEABLE CURVE-MATCHED THERMISTOR

COLOR CODE: BROWN

(UNIT/RES) • 50000 OHMS/°C • 02 9 00 70 °C

40	1,204,600	37	17,441	114	1,085.9
39	1,125,000	38	16,697	115	1,054.1
38	1,051,100	39	15,999	116	1,023.3
37	982,390	40	15,314	117	993.53
36	918,590	41	14,672	118	964.74
35	859,280	42	14,059	119	936.91
34	804,130	43	13,475	120	909.99
33	752,820	44	12,919	121	884.55
32	705,070	45	12,380	122	859.76
31	660,620	46	11,861	123	834.39
30	619,200	47	11,368	124	810.81
29	580,020	48	10,907	125	787.98
28	541,050	49	10,497	126	765.89
27	511,100	50	10,077	127	744.50
26	479,810	51	9,676.0	128	723.78
25	450,610	52	9,292.8	129	703.73
24	423,340	53	8,926.7	130	684.31
23	397,870	54	8,576.9	131	665.49
22	374,070	55	8,242.5	132	647.27
21	351,830	56	7,922.7	133	629.60
20	331,030	57	7,617.0	134	612.50
19	311,580	58	7,324.6	135	595.91
18	293,370	59	7,044.8	136	579.83
17	276,330	60	6,777.1	137	564.26
16	260,370	61	6,520.9	138	549.15
15	245,420	62	6,275.6	139	534.50
14	231,410	63	6,040.8	140	520.30
13	218,280	64	5,815.9	141	506.52
12	205,960	65	5,600.4	142	493.16
11	194,410	66	5,394.0	143	480.10
10	183,560	67	5,186.2	144	467.61
9	173,380	68	5,006.6	145	455.41
8	163,820	69	4,824.8	146	443.57
7	154,840	70	4,650.5	147	432.07
6	146,490	71	4,483.4	148	420.91
5	138,470	72	4,323.0	149	410.08
4	131,000	73	4,169.1	150	399.56
3	123,990	74	4,021.4		
2	117,380	75	3,879.7		
1	111,160	76	3,743.7		
0	105,310	77	3,613.0		
1	99,792	78	3,487.5		
2	94,596	79	3,367.0		
3	89,698	80	3,251.2		
4	85,060	81	3,140.0		
5	80,725	82	3,033.0		
6	76,610	83	2,930.2		
7	72,738	84	2,831.3		
8	69,077	85	2,736.2		
9	65,620	86	2,644.8		
10	62,354	87	2,556.8		
11	59,268	88	2,472.2		
12	56,352	89	2,390.7		
13	53,594	90	2,312.3		
14	50,986	91	2,236.8		
15	48,519	92	2,164.2		
16	46,184	93	2,094.2		
17	43,974	94	2,026.8		
18	41,882	95	1,951.8		
19	39,900	96	1,899.3		
20	38,022	97	1,839.0		
21	36,242	98	1,780.8		
22	34,566	99	1,724.8		
23	32,950	100	1,670.0		
24	31,439	101	1,618.7		
25	30,000	102	1,569.4		
26	28,634	103	1,520.0		
27	27,338	104	1,473.2		
28	26,107	105	1,428.1		
29	24,937	106	1,384.5		
30	23,827	107	1,342.5		
31	22,771	108	1,301.9		
32	21,768	109	1,262.7		
33	20,814	110	1,224.9		
34	19,907	111	1,188.3		
35	19,044	112	1,153.0		
36	18,223	113	1,118.9		