General Disclaimer

One or more of the Following Statements may affect this Document

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.
- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.
- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.
- This document is paginated as submitted by the original source.
- Portions of this document are not fully legible due to the historical nature of some
 of the material. However, it is the best reproduction available from the original
 submission.

Produced by the NASA Center for Aerospace Information (CASI)

DOE/NASA CONTRACTOR REPORT

DOE/NASA CR-150630

PRELIMINARY DESIGN PACKAGE FOR SOLAR COLLECTOR AND SOLAR PUMP

Prepared by

Calmac Manufacturing Corporation 150 S. Van Brunt Street Englewood, New Jersey 07631

Under Contract NAS8-32253 with

National Aeronautics and Space Administration George C. Marshall Space Flight Center, Alabama 35812

For the Department of Energy





(NASA-CR-150630) PRELIMINARY DESIGN PACKAGE FOR SOLAR COLLECTOR AND SOLAR PUMP (CALMAC Mfg. Co.) 41 p HC A03/MF A01 CSCL 10A N78-22472

Unclas G3/44 16622

U.S. Department of Energy



		TECHN	ICAL REPORT STANDARD TITLE PAGE
1.	PEPORT NO. DOE/NASA CR-150630 2. GOVERNMENT A	CCESSION NO.	3. RECIPIENT'S CATALOG NO.
4.	TITLE AND SUBTITLE Preliminary Design Package for Solar Collect	tor and	5. REPORT DATE April 1978
	Solar Pump		6. PERFORMING ORGANIZATION CODE
7.	AUTHOR(S)		8. PERFORMING ORGANIZATION REPORT
9.	PERFORMING ORGANIZATION NAME AND ADDRESS		10. WORK UNIT NO.
	Calmac Manufacturing Corporation 150 S. Van Brunt Street		11. CONTRACT OR GRANT NO.
	Englewood, New Jersey 07631		NAS8-32253
2.	SPONSORING AGENCY NAME AND ADDRESS		Contractor Report
	National Aeronautics and Space Administration	n	
	Washington, D. C. 20546		14. SPONSORING AGENCY CODE
	Calmac Manufacuring is developing a secollector, for use on solar heating and cooling	and hot water sy	ystems. These systems are
į	or use in single-family, multi-family, or com- nformation necessary to evaluate the prelimin lowered pump, and is a collation of the following Verification Plans, Hazard Analysis, and other the subsystem.	ary design of the ng information:	Calmac collector and solar- preliminary design drawings,
	Renumbering of pages and some reform	atting have been	done in the interest of clarity.
7.	KEY WORDS	18. DISTRIBUTION	
		WILLIAM A.	BROOKSBANK, JR.
19.	SECURITY CLASSIF. (of this report) 20. SECURITY CLA	SSIF. (of this page)	21. NO. OF PAGES 22. PRICE
	Unclassified Unclas	sified	41 NTIS

TABLE OF CONTENTS

	Page
Part 1 Solar Flat Plate Collector	
Drawing List	1-2
Special Installation and Maintenance Tools	1-3
Hazard Analysis	1-4
Recommended Prototype Design Review Data	1-5
Government-Furnished Instrumentation	1-7
Design Standards and Symbology	1-8
Verification Plan	1-9
Part 2 Solar Pump	
Drawings Required for Evaluation	2-2
Special Installation and Maintenance Tools	2-3
Subsystem Hazard Analysis	2-4
Recommended Prototype Design Review Data	2-5
Design Standards and Symbology	2-6
Government Furnished Instrumentation	2-7
Verification Plan	2-8
Part 3 Preliminary Design Drawings	
Drier Tube, Solar Collector - SE0001	3-1
Twin Tubing - Cross Section - 130P-A	3-2
Copper U-Bend - ST-239	3-3

	Page
Subheader Takeoff & Tube for U-Bend-6438B	3-4
Subheader Assembly - ST-243	3-5
Sunmat Solar Collector Assembly - 155P	3-6
Sunmat Assembly - 156P	3-7
Assembly Detail, Sunmat - 157P	3-8
Solar Pump - 158P	3-9

PART I

Proliminary Design Review Data

Contract NASS-32253

Project: Flat Plate Collector

CALMAC Manufacturing Corporation 150 South Van Brunt Street Englewood, N.J. 07631



Drawings to Define Sybsystem

Contract NAS8-32253

Project: Flat Plate Collector

The following drawings are required to define the sybsystem:

- 1. Twin tubing cross section
- 2. Header assembly
- 3. U-bend
- 4. Tubes for header takeoffs and U-bends
- 5. Standard straight Sunmat
- 6. Collector assembly, top view, lengthwise cross section and widthwise cross section.

See Section 3 for drawings.

Special Installation and Maintenance Tools

Contract NAS8-32253

Project: Flat Plate Collector

Part Number: SN:001

Nomenclature: Stimpson Clamp Driver

Description and Use: The tool consists of a short length of 3/8" ID pipe with a 5/16" slot cut in one side, fastened to a handle. The tool slips over the EPDM tubing and is used to push Stimpson clamps over header nipples and U-bends.

Manufacturer: CALMAC Manufacturing Corporation

Justification: The best alternative using standard tools is to use a pair of pliers as a pushing tool with the clamp between its grip. Applying enough pressure to hold the clamps easily, however, damages the clamps, and the pliers tend to slip off the round shape of the clamps.

ORIGINAL PAGE IS OF POOR QUALITY 1. Identification and Control of Hazards. The sources of hazard in the collector sybsystem are excess temperatures and pressures within the piping and tubing, and the toxicity of the ethylene glycol heat transfer fluid. The hazards are only to personnel and not to equipment or buildings -- the temperatures and pressures involved are not high enough to ignite, collapse or otherwise damage equipment or buildings. The potential hazards to personnel, however, are major as serious burns, or poisoning could result from a malfunction.

The strategy for managing excess temperatures and pressures is primarily to relieve them before they build up to an excess. The use of a temperature and pressure relief valve in the system set at 225°F and 40 PSI accomplishes this objective. In addition, to minimize the risk of burns suffered from touching the cover panel which might reach to 180°F during no flow conditions, signs will be recommended when the collector is operated in areas subjected to public traffic. The toxicity of the glycol is managed by the use of a basin to catch fluid vented from the temperature/pressure relief valve. The other source of glycol contamination -- leaking from the collector or some other part of the system -- will be managed by recommending periodic inspection of the level of glycol in the system.

- 2. Residual Hazards. In a properly installed system -- and it should be made clear that the relief valve and the caten basin must be installed on site -- and a properly maintained system, residual hazards are low. These hazards are comparable to hazards associated with conventional systems -- the hazard of excess build up of hot water or steam pressure in hydronic heating systems, or the risk of leaks from gas stoves.
- 3. Component Failure. The malfunction of a temperature/pressure relief valve will significantly increase the hazard of excess temperature and pressure. Similarly, the malfunction of piping, tubing, gaskets, fittings or valves, or improper installation will increase the hazard from the toxicity of glycol.

Contract NAS8-32253

Project: Flat Plate Collector

We recommend use of the following data at the prototype design review:

1. Drawings:

- a. Twin tubing cross section
- b. Header assembly
- c. U-bend
- d. Tubes for header takeoffs and b-bends
- e. Standard straight SUNEAT
- f. Collector assembly, top view, lengthwise cross section and with wise cross section.

2. Test data:

- a. Collector efficiency
- b. operating temperature and pressure limits
- c. pressure drop through system
- d. freeze tolerance
- e. resistance to ponding
- f. fail-safe performance
- g. water potability
- h. resistance to solar degradation of EPDM
- i. resistance to fluttering by wind
- j. leakage
- k. resistance to thermal degradation
- 1. resistance to structural damage

ORIGINAL PAGE IS OF POOR QUALITY

Prototype Design Review Data (Continued)

- 3. Analyses:
 - a. noise and corrosion
 - b. structural calculations

Government-Furnished Instrumentation

Contract NAS8-32253

Project: Flat Plate Collector

No government-furnished instrumentation is required.

ORIGINAL PAGE IS OF POOR QUALITY

Design Standards and Symbology

Contract NAS8-32253

Project: Flat Plate Collector

We use design standards and symbology of the American Society of Mechanical Engineers. Symbols are published in American National Standard Graphical Symbols for Pipe Fittings, Valves and Piping.

> ORIGINAL PAGE IS OF POOR QUALITY

Verification Plan

Contract NAS8-32253

Project: Flat Plate Collector

CALMAC Manufacturing Corporation 150 South Van Brunt Street Englewood, N.J. 07631

- 1. Verification Matrix. See attached
- 2. Test Hardware. To perform tests at our location we will use the following hardware:

velometer - air velocity
rotometer - flow rate
potentiometer pyrometer - temperature
pressure gauges - pressure
pyranometer - insolation
manometer - pressure drop

This is all basic hardware for measuring the key parameters associated with plumbing and heating devices, except for the pyranometer, which is unique to the solar field.

Other testing requiring hardware and expertise outside our range of experience -- the chemical testing of water for potability, for example -- will be performed by outside laboratories. Testing to certify performance will be performed by an independent laboratory.

3. Test Schedule and Location:

Date	Test	Location
Feb 15	Freeze tolerance of system	CALMAC factory
Mar 1-30	Potability of water run through system	Outside lab to be determined
Mar 1	Pressure drop through system	CALMAC factory
Mar 2	Leakage	
Mar 8	Resistance to ponding	" "
Mar 9	Resistance to structural damage	" "
Mar 15	Resistance to fluttering by wind) 11 / 1 11
Mar 22	Fail-safe protection	/ 11 11
Mar 29	Temperature and Pressure limits	
Mar 1-15	Collector efficiency	" "
Mar 15-May 15		DSET, Phoenix, AZ

4. All this testing will be done during the qualification stage. We have enough experience with the operating characteristics of the collector, based on earlier models we have used, not to need testing at the development stage, and adequate data is available to verify all interim performance criteria at the development stage. Testing at the qualification stage is related primarily to durability and particularly to our use of the EPDM tubing, which, since it is manufactured especially for this application, is unique. The tests for freeze tolerance, potability, pressure drop, leakage, temperature and pressure limits, thermal degradation, and collector efficiency all stem from the use of EPDM. The need to test resistance to fluttering and ponding, on the other hand, stems from the unique structural design of the system. The fail-safe test is a precautionary measure to insure meeting safety requirements.

Testing at the acceptance stage should not be necessary, unless design changes are made following qualification testing. Our plan is to complete testing of all key areas here at our plant as early as possible in the qualification stage and then have DSET verify our findings to meet the need for certification by an independent agency.

VEIGHTCATION CROSS
REFERENCE MATRIX

VERIFICATION METHOD:

Flat Plate Collector

1. SIMILARLIY

3. INSPECTION N/A NOT APPLICABLE

2. ANALYSIS 4. TEST

PERFORMANCE	VERIFICATION PHASE			
REQUIREMENT	DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REMARKS
Subsystem Specification	1	4	4	
Interim Performance Criteria				
1.2.4	3	3	3	
1.3	3	3	3	
1.3.1	1	1	3	
1.4	3	3	3	
1.4.1	2	3	3	- 1
2.1	3	. 3	3	
2.1.1	2	3	3	
2.1.2	2	3	3	
2.1.3	2/1	4	3	
2.1.4	1	1	3	
2.1.5	3	3	3	
2.1.6	3	3	3	
2.1.7	1	4	3	
2.2	3	3,	3	
2.2.1	3	3	3	
2.2.2	3	3	3	
2.2.4	3	3	3	
2.2.5	3	3	3	
2.2.6	3	3	3 .	

Flat Plate Collector

V., IFICATION CROSS REFERENCE MAIRIX

VERIFICATION METHOD:

1. SIMILARITY 2. ANALYSIS 3. INSPECTION N/A NOT APPLICABLE

4. TUST

PERFORMANCE	VEI	VERIFICATION PHASE		
REQUIREMENT	DEVELOPMENT	QUALIFICATION	AUCEPTANCE	REMARKS
2.3	3	3	3	
2.3.1	1	4	3	
2.4	3	3	3	
2.4.1	1	1	3	
2.6.4	1	4	3	
2.8	3	3	3	
2.8.1	1	1	3	
3.1	3	3	3	
3.1.1	3	3	3	
3.1.2	2	3	3	
3.2	3	3	3	
3.2.1	2	2	3	
3.2.2	2	2	3	
3.2.4	2	2	3	
3.3	3	3	3	
3.3.1	. 2	4	3	
3.4	3	3	3	
3.4.1	2	2	3	
3.7				
3.7.1	2	: 1		
3.8	3	3	3	
3.8.1	2	2	3	
3.9	3	3	3	

PF01-358c

ITEM (NAME & PART NO.)

VERIFICATION CROSS

Flat Plate Collector

REFERENCE MATRIX

VERIFICATION METHOD:

1. SIMILARITY 2. ANALYSIS

3. INSPECTION N/A NOT APPLICABLE

4. TEST

PERFORMANCE	VEI	VERIFICATION PHASE			
REQUIREMENT	DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REMARKS	
3.9.1	1	4	3		
4.1	3	3	3		
4.1.1	3	. 3	3		
4.2	3	3	3		
4.2.1	1	4 '	3		
4.2.2	3	3	3		
4.3	3	3	3		
4.3.1	1.	1	3		
4.3.2	1	3 .	3		
4.4	3	3	3		
4.4.1	3	3	3		
4.4.2	3	3	3		
4.6	3 .	3	3		
4.6.1	2	4	3		
4.6.3	3	3	3		
4.6.4	. 2	3	3		
4.7	3	3	3		
4.7.1	2	3	3		
5.1	3	3	3		
5.1.1	1	4	3		
5.1.3	1	3	3		
5.1.4	1	3	3		
5.1.5	1	3	3 '		

PF01-358c

ITEM (NAME & PART NO.)

VERIFICATION CROSS

Flat Plate Collector

. REFERENCE MATRIX

VERIFICATION METHOD:

3. IN PECTION NIA NOT APPLICABLE

1. <u>SIMILABILY</u> 3. IN Pt. 2. ANALYSIS 4. TEST

PERFORMANCE	VEI	HEICATION PI	IASE	REMARKS
REQUIREMENT	DEVELOPMENT	QUALIFICATION	ACCEPTANCE	Newaline
5.1.6	2	4	3	
5.2	3	3	3	
5.2.1	1	4	3	
5.2.2	1	1	3	
5.2.3	2	2	2	
5.2.4	1	4	3	
5.2.5	1	1	3	
5.2.6	1	1	3	
5.3	3	2	3	
5.3.1	1/2	3	3	
5.3.2	2	2	3	
5.3.3	2	2	3	
5.3.4	2	2	3	
6.1	3	3	3	
6.1.1	3	3	3	
6.1.2	3	3	3	
6.1.3	3	3	3	
6.1.4	3	3	3	
6.1.5	3	3	3	
6.2	3	3	3	
6.2.1	3	3	3	
6.2.2	3	3	3	
6.2.3	3	3	3	

VERIFICATION CROSS
REFERENCE MATRIX

Flat Plate Collector

VOL WATKIA

VERIFICATION METHOD:

1. SIMILARITY
2. ANALYSIS

3. INSPECTION N/A NOT APPLICABLE

4. TEST

PERFORMANCE	VERIFICATION PHASE			
REQUIREMENT	DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REMARKS
6.2.4	3	3	3	
6.3	3	3	3	
6.3.1	3	3	3	
6.3.2	3	3	3	
11.2.1	2	2	3	
11.2.2	2	2	3	
11.3.1	1	1	3	

PART 2

Preliminary Design Review Data

Contract NAS8-32253

Project: Solar Pump

CALMAC Manufacturing Corporation 150 South Van Brunt Street Englewood, N.J. 07631

Drawings to Define Subsystem

Contract NAS8-32253

Project: Solar Pump

The following drawings are required to define the subsystem:

- 1. Pump top view and cross section
- 2. Vapor tube

Special Installation and Maintenance Tools

Contract NAS8-32253

Project: Solar pump

No special installation and maintenance tools are required.

1. Identification and Control of Hazards. The sources of hazard in the pump subsystem are excess temperatures and pressures wihtin the piping and tubing, and the toxicity of the ethylene glycol heat transfer fluid. The hazards are hazards only to personnel and not to equipment or buildings -- the temperatures and pressures involved are not high enough to ignite, collapse or otherwise, damage equipment or buildings. The potential hazards to personnel, however, are major as serious burns, or poisoning could result from a malfunction.

The strategy for managing excess temperatures and pressures is primarily to relieve them before they build up to an excess. The use of a temperature and pressure relief valve in the system set at 280°F and 28 PSI accomplishes this objective. In addition, to minimize the risk of burns suffered from touching the pump which might reach to 200°F during normal operation signs will be recommended when the pump is operated in areas subjected to public traffic. The toxicity of the glycol is managed by the use of a basin to catch fluid vented from the temperature/pressure relief valve. The other source of glycol contamination -- leaking from the pump or some other part of the system -- will be managed by recommending periodic inspection of the level of glycol in the system.

- Residual Hazards. In a properly installed system -- and it should be made clear that the relief valve and the catch basin must be installed on site -- and a properly maintained system, residual hazards are low. These hazards are comparable to hazards associated with conventional systems -- the hazard of excess build up of hot water or steam pressure in hydronic heating systems, or the risk of leaks from gas stoves.
- 3. Component Failure. The malfunction of a temperature/pressure relief valve will significantly increase the hazards of excess temperature and pressure. Similarly, the malfunction of piping, tubing, gaskets, fittings or valves, or improper installation will increase the hazard from the toxicity of glycol.

ORIGINAL PAGE IS OF POOR QUALITY Contract NAS8-32253

Project: Solar Pump

We recommend use of the following data at the prototype design review:

1. Drawings:

- a. Pung, top view
- b. Pump, cross section
- c. Vapor tube

2. Test data:

- a. Operating performance (flow rate, pressure output for various combinations of liquid temperature and steam pressure)
- b. Thermal degradation
- c. Fail-safe performance
- d. Leakage
- e. Vibration
- f. Water potability

3. Analyses:

- a. Noise and correston
- b. Structural calculations

Design Standards and Symbology

Contract NAS8-32253

Project: Solar Pump

We use design standards and symbology of the American Society of Mechanical Engineers. Symbols are published in American National Standard Graphical Symbols for Pipe Fittings, Valves and Piping.

Government-Furnished Instrumentation

Contract NAS8-32255

Project: Solar Pump

No government-furnished instrumentation is required.

ORIGINAL PAGE IS OF POOR QUALITY

Verification Plan

Contract NAS8-32253

Project: Solar Pump

CALMAC Manufacturing Corporation 150 South Van Brunt Street Englewood, N.J. 07631

- 1. Verification Matrix. See attached.
- 2. Test Hardware. To perform tests at our location we will use the following hardware:

rotometer - flow rate potentiometer pyrometer - temperature pressure gauges - pressure manometer - pressure drop

These instruments are all basic hardware for measuring the key parameter associated with plumbing and heating devices.

Other testing requiring hardware and expertise outside or range of experience -- the chemical testing of water for potability, for example -- will be performed by outside laboratories. Testing to certify performance will be performed by an independent laboratory.

3. Test Schedule and Loaction:

Date	Test	Location
Mar 1-30	Potability of water run through system	Outside lab to be determined
Mar 1-30	The rmal degradation	CALMAC factory
Mar 8	Leakage	
Mar 15	Vibration	
Mar 22	Fail-safe performance	
Mar 15-30	Operating performance and limits	" "
Ap 1-30	Operating performance and limits	DSET, Phoenix, AZ

4. All this testing will be done during the qualification stage. The critical problem in the case of the pump is the development of a design that will meet operating performance requirements -- pumping at specified pressures and flow rates -- not the development of designs that meet ruggedness and durability requirements. Solving this problem involves analyzing different shapes and designs of the cylinder chamber, valves, vapor tube and so forth, and does not lend itself to testing. Once the design is set and operating performance requirements met, then we can test rigorously both the pump's operating characteristics and its durability during the qualification stage. Unless design changes develop during this period we can proceed readily to certification by an outside angency (DSET) towards the end of the qualification stage.

ORIGINAL PAGE IS OF POOR QUALITY

VERIFICATION CROSS
REFERENCE MATRIX

VERIS	TADIE	ION M	ETH	CD:

Pump

1. SIMILARITY
2. ANALYSIS

3. INSPECTION N/A NOT APPLICABLE

4. TEST

PERFORMANCE	VEI	RIFICATION PH	IASE	
REQUIREMENT	DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REMARKS
Technical Performance Requ ements	2	4	3	
Interim Performance Criteria				
1.2.4	3	3	3	
2.1	3	3	3	
2.1.1	2	3	3	
2.1.2	2	3	3	
2.1.3	2	4	3	
2.1.5	3	3	3	
2.1.6	3	3	3	
2.2	3	3	3	
2.2.1	2	3	3	
2.2.2	2	4	3	
2.2.4	3	3	3	
2.2.5	2	3	3	
2.2.6	. 3	3	3	
2.3	3	3	3	
2.3.1	2	4	3	
2.6	3	3	3	
2.6.1	1	3	3	
2.6.3	3	3	3	
2.6.4	1	3	3	
2.7	3	3	3	

VERIFICATION CROSS REFERENCE MATRIX

VICOL	FICA	TION	METE	100.

Pump

1. SIMILARITY
2. ANALYSIS

3. INSPECTION N/A NOT APPLICABLE

4. TEST

PERFORMANCE	VERIFICATION PHASE				
REQUIREMENT	DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REMARKS	
2.7.1	3	3	3,		
2.8	3	3	3		
2.8.1	1	1	3		
3.1	3	3	3		
3.1.1	3	3	3		
3.1.2	2	3	3		
3.2	3	3	3		
3.2.1	2	2	3		
3.3	3	3	3		
3.3.1	2	2	3		
3.4	3	3	3		
3.4.1	2	2	3		
3.8	3	3	3		
3.8.1	2	2	3		
3.9.1	3	3	3		
4.1	. 3	3	3		
4.1.1	3	3	3		
4.2	3	3	3		
4.2.1	1	4	3		
4.2.2	3	3	3		
4.3	3	3	3	ORIGINAL PAGE IS	
4.3.1	2	1	3	OF POOR QUALITY	
4.4	3	3	3		

VERIFICATION CROSS
REFERENCE MATRIX

Pump

1. SIMILARITY

3. INSPECTION N/A NOT APPLICABLE

VERIFICATION METHOD:

2. ANALYSIS

A TEST

PERFORMANCE	, VEI	VERIFICATION PHASE			
REQUIREMENT	DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REMARKS	
4.4.1	3	3	3		
4.5	3	3	3		
4.5.2	3	3	3		
4.6	3	3	3		
4.6.3	3	3	3		
4.6.4	2	3	3		
4.7	3	3	3		
4.7.1	2	3	3		
5.1	3	3	3		
5.1.1	1	3	3		
5.1.3	1	3	3		
5.2	3	3	3		
5.2.1	1	4	3		
5.2.2	1	1	3		
5.2.3	2	2	3		
5.2.4	. 1	4	3		
5.2.5	1	1	3		
5.3	3	3	3		
5.3.1	1/2	3	3		
5.3.2	2	2	3		
5.3.3	2	2	3		
5.3.4	. 2	2	3		
5.4	. 3	3	3		

VERIFICATION CROSS REFERENCE MATRIX

Pump

1. SIMILARITY VERIFICATION METHOD:


3. INSPECTION


NOT APPLICABLE N/A_

2. ANALYSIS

4. TEST

PERFORMANCE REQUIREMENT DEVELOPMENT QUALIFICATION ACCEPTANCE 5.4.1 1 3 3 6.1 3 3 3 6.1.1 3 3 3 6.1.2 3 3 3 6.1.3 3 3 3 6.1.4 3 3 3 6.1.5 3 3 3 6.2.1 3 3 3 6.2.2 3 3 3 6.2.3 3 3 3 6.2.4 3 3 3 6.3.1 3 3 3 6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.3.1 1 1 3	PERFORMANCE	VEF	VERIFICATION PHASE		
6.1 3 3 3 6.1.1 3 5 3 6.1.2 3 3 3 6.1.3 3 3 3 6.1.4 3 3 3 6.1.5 3 3 3 6.2 3 3 3 6.2.1 3 3 3 6.2.2 3 3 3 6.2.3 3 3 3 6.2.4 3 3 3 6.3 3 3 3 6.3.1 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3 3		DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REMARKS
6.1.1 3 3 3 6.1.2 3 3 3 6.1.3 3 3 3 6.1.4 3 3 3 6.1.5 3 3 3 6.2 3 3 3 6.2.1 3 3 3 6.2.2 3 3 3 6.2.3 3 3 3 6.2.4 3 3 3 6.3 3 3 3 6.3.1 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3 3	5.4.1	1	3	3	
6.1.2 3 3 3 6.1.3 3 3 3 6.1.4 3 3 3 6.1.5 3 3 3 6.2 3 3 3 6.2.1 3 3 3 6.2.2 3 3 3 6.2.3 3 3 3 6.2.4 3 3 3 6.3 3 3 3 6.3.1 3 3 3 6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3 3	6.1	3	3	3	
6.1.3 3 3 3 6.1.4 3 3 3 6.1.5 3 3 3 6.2 3 3 3 6.2.1 3 3 3 6.2.2 3 3 3 6.2.3 3 3 3 6.2.4 3 3 3 6.3 3 3 3 6.3.1 3 3 3 6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3 3	6.1.1	3	3	3	
6.1.4 3 3 3 6.1.5 3 3 3 6.2 3 3 3 6.2.1 3 3 3 6.2.2 3 3 3 6.2.3 3 3 3 6.2.4 3 3 3 6.3 3 3 3 6.3.1 3 3 3 6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3 3	6.1.2	3	3	3	
6.1.5 3 3 3 6.2 3 3 3 6.2.1 3 3 3 6.2.2 3 3 3 6.2.3 3 3 3 6.2.4 3 3 3 6.3 3 3 3 6.3.1 3 3 3 6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3 3	6.1.3	3	3	3	
6.2 3 3 3 6.2.1 3 3 3 6.2.2 3 3 3 6.2.3 3 3 3 6.2.4 3 3 3 6.3 3 3 3 6.3.1 3 3 3 6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3 3	6.1.4	3	3	3	
6.2.1 3 3 3 6.2.2 3 3 3 6.2.3 3 3 3 6.2.4 3 3 3 6.3 3 3 3 6.3.1 3 3 3 6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3 3	6.1.5	3	3	3	
6.2.2 3 3 3 6.2.3 3 3 3 6.2.4 3 3 3 6.3 3 3 3 6.3.1 3 3 3 6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3 3	6.2	3	3	3	
6.2.3 3 3 3 6.2.4 3 3 3 6.3 3 3 3 6.3.1 3 3 3 6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3 3	6.2.1	3	3	3	
6.2.4 3 3 3 6.3 3 3 3 6.3.1 3 3 3 6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3	6.2.2	3	3	3	
6.3 3 6.3.1 3 6.3.2 3 8.3.1 3 11.2.1 2 2 3 3 3 4 3 5 3 6 3 7 3 8 3 9 3 11 2 2 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	6.2.3	3	3	3	
6.3.1 3 3 3 6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3	6.2.4	3	3	3	
6.3.2 3 3 3 8.3.1 3 3 3 11.2.1 2 2 3 11.2.2 2 3	6.3	. 3	3	3	
8.3.1 . 3 3 11.2.1 2 2 3 11.2.2 2 2 3	6.3.1	3	3	3	
11.2.1 2 2 3 11.2.2 2 2 3	6.3.2	3	3	3	
11.2.2 2 3	8.3.1	. 3	3	3	
	11.2.1	2	2	3	
11.3.1 1 3	11.2.2	2	2	3	
	11.3.1	1	1	3	






"FINISHED" DRIER TUBE

INSTRUCTIONS' 1. CUT PIPE TO SIZE i.e. 102'LG ORIGINAL PAGE IS 2. REMOVE BURRS OF POOR QUALITY 3. PRESS ONE END (USE \$2 SHIM FOR OPENING) 4. FILL WITH SILICA GEL, SIZE 3 ON & MESH 5. PRESS OTHER END (USE 1/32 SHIM FOR OPENING) 6. SEAL BOTH ENDS WITH REMOVABLE TAPE Rev By Date Revisions TOLERANCES : PRACTIONAL, 1 1/64 ; DECIMALS, \$ 405 ; ANGLES, \$ 1/2" DRN. 5-12-76 CALMAC MFG. CORP. CHK. L COM TITLE DRIER TUBE, SOL. COLL. Englewood, N.J. PRO SOL ENE Blank Size MATERIAL 34 COPPER PIPE, TYPE'L' -SE0001 SCALE FULL

3-1

WEB _ .015 ± .010 WIDE x .025 ± .015 THER



ORIGINAL PAGE IS OF POOR QUALITY

TOLERANCES: PRACTIONAL, 1 1/60; DECIMALS, 1.00; AMOLES, 11/2°


TITLE TWIN TUBING - CROSS SECTION TOOL NO.

MATERIAL 80-85 DUROMETER EPDM

Rew By Date

Rew By Dat

3-2



. ..

NOTE: STRAIGHT LENGTH OF TUB. BEFORE

BENDING 35; SEE DWG A-6438, ITEM-3.

STRAIGHT PC ANNIALLD @ 500° PRIOR.

TO BENDING

ORIGINAL PAGE IS OF POOR QUALITY

	H				
18. 11/2"	_			_	Revisions
001 No.	CHI	K. 4	- 6	私	Englewood, N.J.
lank Size	SCALE 1 2" A- ST		A- ST 239		
(ool No. CHI	ool No. CHK.	ool No. CHK L C	OOI NO. CHK. L CFA

