

N O T I C E

THIS DOCUMENT HAS BEEN REPRODUCED FROM
MICROFICHE. ALTHOUGH IT IS RECOGNIZED THAT
CERTAIN PORTIONS ARE ILLEGIBLE, IT IS BEING RELEASED
IN THE INTEREST OF MAKING AVAILABLE AS MUCH
INFORMATION AS POSSIBLE

NASA CR-166742

Dynamics Explorer

Interface Definition Study Final Report

Volume I

October 20, 1978

(NASA-CR-166742) DYNAMICS EXPLORER:
INTERFACE DEFINITION STUDY, VOLUME 1 Final
Report (RCA Astro-Electronics Div.) 419 p
HC A18/MF A01 CSCL 22B




Unclas
G3/15 39430

Prepared for
National Aeronautics and Space Administration
Goddard Space Flight Center
Greenbelt, Maryland

Prepared by
Dynamics Explorer Program Office
RCA Government Systems Division
Astro-Electronics, Princeton, New Jersey

Contract No. NAS5-25020

AE R-4270



Dynamics Explorer

Interface Definition Study Final Report

Volume I

October 20, 1978

Prepared for

National Aeronautics and Space Administration
Goddard Space Flight Center
Greenbelt, Maryland

Prepared by

Dynamics Explorer Program Office
RCA Government Systems Division
Astro-Electronics, Princeton, New Jersey

Contract No. NAS5-25020

AE R-4270

PREFACE

This final report of the Dynamics Explorer Interface Definition Study has been generated by RCA Astro-Electronics in response to the requirements of National Aeronautics and Space Administration Contract No. NAS5-25020.

The final report is submitted in two volumes comprising the following sections:

- 1.0 Introduction
- 2.0 Summary and Baseline Change List
- 3.0 Spacecraft System Design Notes
- 4.0 Thermal Subsystem Design Notes
- 5.0 Power Subsystem Design Notes
- 6.0 Communications Subsystem Design Notes
- 7.0 Plasma Wave Instrument Interface Definition Design Notes
- 8.0 Structure Design Notes
- 9.0 Attitude Control Subsystem Design Notes
- 10.0 Command and Data Handling Subsystem Design Notes
- 11.0 Mechanical Drawings
- 12.0 Reliability Predictions

Sections 1.0 through 7.0 are provided in this volume.

1.0 INTRODUCTION

TABLE OF CONTENTS

<u>Section</u>	<u>Title</u>
1.1	General
1.2	System Specification Changes

SECTION 1.0

INTRODUCTION

1.1 GENERAL

The work performed in response to GSFC-DE-100-017-0, the work statement for the interface definition study, is reported on (in part) in this document. Other deliverable items identified in the work statement are identified in Table 1.

TABLE 1. IDS DELIVERABLE ITEMS

Item	Status	Comments
System Specification Changes	Changes identified	See Section 1.2
Specifications - TX, Booms, SP	Complete	Released to Print File; Scan Platform revisions expected
EMI Test Plan	Complete	Delivered under DE File No. 2.3.3-026, 29 June '78
GIS ECN	Class I ECN Generated	Will be incorporated upon approval notification
MTM Test Plan	Complete	Released to Print File
Instrument UNDOCS	Investigator signature cycle in process	
Antenna Test Plan	Complete	Contained in 3.5.2-004-DN
S/C Preliminary Test Plan	Complete	Delivered with S/C Proposal
Antenna B/B	Delivered	Testing at GSFC initiated

The volume of material contained within this Final Report is the compilation of the work done in response to the work statement wherein a specific deliverable was not identified but where design and analysis tasks were identified. Within each section, a detailed table of contents is provided, listing the design notes which document the work performed.

1.2 SYSTEM SPECIFICATION CHANGES

The changes to the system specification, GSFC-DE-100-020-B, which will be incorporated in revision C are summarized below. These changes, which resulted from design and analytic efforts during the Interface Definition Study (IDS), have been reviewed with GSFC and agreed to during the negotiations for the spacecraft hardware contract modification.

Also included are the agreements in interpretation of the specification. While these agreements do not require changes in the language of the specification, they are included in this summary for completeness. The reference item numbers refer to the paragraphs of Part 2, Book 2, Section 4.0 of the Spacecraft Hardware Proposal, RCA No. 102658-C, 30 June, 1978.

4.1 INTERPRETATIONS

GSFC accepted the following RCA interpretations from Part 2, Book 2:

4.1.1	4.1.12
4.1.2	4.1.13
4.1.3	4.1.16
4.1.4	4.1.19
4.1.5	4.1.21
4.1.6	4.1.22
4.1.11	4.1.23

In addition, the following agreements were reached on the remainder of the interpretations.

4.1.7 Revision B of 100-020 changed the words "maintaining" to "detecting" such that the paragraph now reads:

"3.4.3.2.5 DE-A Horizon Sensing

The DE-A spacecraft shall contain earth horizon sensors oriented to produce an indication of the earth to sky and sky to earth transitions and earth chord widths as seen by the horizon sensors.

The sensors shall be capable of detecting the deviation of each edge of the earth crossing envelope pulse relative to a local vertical reference direction to within ± 0.2 degrees due to variations in mission operational orbit spin rate, sensor noise, and earth radiance variations. In addition, the sensors shall be capable of being aligned with respect to the spacecraft spin axis to within ± 0.1 degrees."

4.1.8 GSFC understands the interpretations. RCA has agreed to provide data on the sun sensor masking and effects on system capability.

4.1.9 Revision B of 100-020 changed "maintaining" to "detecting" such that the paragraph now reads:

"3.4.3.3.5 DE-B Horizon Sensing

The DE-B spacecraft shall contain earth horizon sensors oriented to produce an indication of earth/sky horizon transition and earth chord widths. Mechanical scanning shall be provided for the sensors by rotating component of the momentum wheel assembly. The sensors shall be capable of detecting the deviation of each edge of the earth crossing envelope pulse relative to a local vertical direction to within ± 0.2 degrees due to variations in mission operational orbit, mechanical rotational characteristics of the MWA, sensor noise, and earth radiation variations. In addition, the horizon sensors shall be capable of being aligned with respect to spacecraft spin axis to within ± 0.1 degree."

With respect to attitude determination accuracy, working meetings have been held with RCA, CSC and GSFC personnel in attendance. There has been a basic concurrence from CSC with RCA's position on the performance characteristics of the proposed sensors (REF: W. Fuldner to R. deBastos, Trip Report DE file 1.9.1-056 dated Oct. 2, 1978).

4.1.10 Same comment as 4.1.8.

4.1.14 Revision B of 100-020 changed the wording of Paragraph 3.4.5.6.6 from "n x 8 (n = integer 8)" to "n x 8 (in less than or equal to integer 8)". The paragraph now reads:

"3.4.5.6.6 Digital Words Format

Digital telemetry words of n x 8 (n less than or equal to integer 8) bit length which are assembled into the serial telemetry output of the spacecraft shall be provided."

4.1.15 The oscillator stability requirement was agreed to be "one part in 10^5 not including the initial frequency offset". Paragraph 3.4.5.6.8 of GSFC-DE-100-020 will be changed to reflect these words.

4.1.17 RCA submitted the following substitution for the 4.1.17 interpretation:

"4.1.17 DE-A Operational Requirements (Specification paragraph 3.4.6.2)

The proposed system, in conjunction with incorporation of the 70-rpm third state spin rate, demands that the DE-A S-band antenna be erected under internal spacecraft control subsequent to the

interstage adapter and prior to the 70-rpm spin-up maneuver. This results in the following antenna coverage:

At apogee and at perigee, the link performance will be as in the link tables regardless of the Z-axis orientation. When not at apogee or perigee, link performance will be degraded by an amount which depends on the orientation of the Z-axis. The worst-case will occur when the Z-axis lies in the orbit plane. In this case, approximately 75% of the orbit period will be available for commanding, 60% for ranging, and 50% for HEW telemetry. The contact time will be centered near apogee. There also will be a brief contact interval (approximately 2 minutes) near perigee.

As the precession maneuver moves the spin axis from the orbit plane to the operational orientation, the coverage capability increases until the operational capability as shown in the proposal is achieved.

RCA interprets the specification requirements to allow for the partial coverage during the turnaround maneuver as noted above to be acceptable."

This interpretation was acceptable to GSFC.

4.1.18 RCA understands that the test referenced will be done at GSFC, and that the Building 11 Sigma 5 computer will be used and is compatible with the software. The OCC may or may not be used.

4.1.20 RCA has agreed that the interpretation as contained in the proposal be modified to read:

"4.1.20 Magnetic Field (Specification Paragraph 4.2.7)

This specification invoked a measurement of magnetic signatures under worst case switching conditions. This measurement may be made while the spacecraft is illuminated and spun in the GFE facility."

4.1.24 RCA and GSFC agreed that the booms would not be extended in thermal-vacuum, but the instruments and booms are to be electrically functional within the physical constraints of the chamber.

4.2 DEVIATIONS

4.2.4

4.2.5

4.2.6 (Rev. B of DE-100-020 changed wording)

4.2.7 (Rev. B of DE-100-020 changed wording)

The following agreements were reached on the remaining exceptions:

- 4.2.1 RCA accepted the specification requirements of Paragraph 3.1.7 which requires internal operating equipment mounting surface temperatures to be maintained within the limits of 0° to 25°C for both spacecraft.
- 4.2.2 With respect to specification paragraph 3.4.2.4(b), the same comment as that of 4.2.1 applies.
- 4.2.3 GSFC agreed with the proposed C/4 charge rate. Paragraph 3.4.4.2.2 will be changed accordingly by GSFC.

4.3 EXCEPTIONS

GSFC accepted the following exceptions:

- 4.4(a) 4.4(f)
- 4.4(b) 4.4(g)
- 4.4(c) 4.4(h)
- 4.4(d) 4.4(i)

With respect to the remaining exceptions, the following agreements were reached:

- 4.4(e) RCA agrees that the GSFC Reliability and Quality Engineer will sign off on the Standard Repair MRB. This will be accomplished via the submittal to GSFC, for approval, of Standard Repair MRB.
- 4.3.1 GSFC agreed to change Paragraph 3.1.3.2.1 to specify a DE-B minimum duty cycle of 16 percent, with a design goal of 19 percent. RCA will present at the Spacecraft CDR or earlier a total definitized plan which shows how we will meet the specification requirement.
- 4.3.2 RCA accepted the specification requirements of 0° to 25°C. (See comment on 4.2.1.)

4.4 ADDITIONAL CHANGES

Subsequent to the proposal, RCA submitted an exception to the 70-dB requirement of Paragraph 3.4.6.1.1. It was agreed that this sentence would be deleted from that paragraph.

At the negotiations, RCA pointed out that the battery temperature requirements of Paragraph 3.4.4.2.6 were inconsistent with the spacecraft thermal operation of 0° to 25°C. Accordingly, RCA requested that Paragraph 3.4.4.2.6 be modified. On October 18, 1978, RCA and GSFC agreed that the last sentence of Paragraph 3.4.4.2.6 be changed to read: "The batteries shall be maintained in flight between 0° and 25°C, with occasional excursions to 30°C."

Several agreements were reached with respect to revised paragraphs in RCA specification PS-2295108. These agreements also required similar changes to GSFC-DE-100-020. The affected paragraphs of 100-020 are:

4.2.7	5.3.3.5(f)
5.3.3.5(b)	5.3.3.6

The changes to the above paragraphs are as follows:

Para. 4.2.7 Change the last sentence to read: "Spacecraft magnetic signature under worst case switching conditions shall be measured to determine if the DE spacecraft magnetic goals are achieved."

Para. 5.3.3.5(b) Change to read: "Operation of the spacecraft in the launch mode throughout pumpdown; including monitoring for electrical discharge."

Para. 5.3.3.5(f) Add the words "and levels" between "test configuration" and "as required."

Para. 5.3.3.6 Change the third sentence to read: "Under these conditions, a simulation of all instruments operating in concert shall be accomplished."

Subsequent RCA-NASA agreements were reached which provided the following changes:

Add a new Paragraph 3.6.2.3 as follows:

"3.6.2.3 Software and Instrument Test Support

Contractor shall participate in the development of the I&T software systems, its applications programs, and its test procedures. As a result of this participation, the contractor shall develop the capability to perform and evaluate routine tests (EPETS) of the instrument complement as well as adapt the EPETS for use during system level test. The contractor

shall develop, perform, and evaluate all system level test procedures and shall have a depth of knowledge sufficient to allow reliable fault isolation to a component or instrument level."

Para. 3.4.6.5.1(b)2

In Para. 3.4.6.5.1(b)2, change "+ 45 degrees" to "+ 44 degrees".
(This change is covered in the Deviations noted in Proposal Paragraph 4.2.5.)

2.0 SUMMARY AND BASELINE CHANGE LIST

SECTION 2.0

SUMMARY AND BASELINE CHANGE LIST

As indicated by the list of deliverables and by the topics addressed in the design notes, the Interface Definition Study (IDS) effort was directed primarily toward refining the detail knowledge of the system design, especially as it affects the interfaces of the spacecraft with the instrument complement.

Significant effort was spent in attempting to accommodate all of the instrument field-of-view requirements to establish instrument placement within the spacecraft and in establishing the system thermal design to provide a viable thermal environment for the instruments. The system performance was enhanced with the change to higher efficiency solar cells. In the area of communications, additional supportive analyses were performed and brass-board models of the three antennas to be used on the spacecraft were fabricated and delivered to GSFC to permit timely antenna testing. Detailed analyses of the elements of the Attitude Control System were performed, and the results were incorporated in a combined analysis with CSC (Computer Sciences Corp.) to assess the overall attitude determination performance which can be provided for the mission science. These analyses are continuing beyond the completion of the IDS.

The results of the work done to date have resulted in the following list of design tradeoffs and system changes which are yet to be performed.

1. Scan Platform Design Approach

A change from the proposed stepper motor and bearing assembly to a bearing and motor assembly similar to the MWA enhances the mechanical design. The effects of such a change to the electrical performance are presently under evaluation.

2. MWA Mirror Angle

Change from the baseline to a single scan angle of 50° simplifies the equipment design and offers improvements in attitude determination accuracy.

3. Solar Cell Cover Glass Thickness

Departure from the baseline 60-mil glass offers a weight advantage. The alternate glass thickness must yet be correlated with the program radiation policy.

4. S-Band Power Amplifier

Evaluation of the impact to system performance by the addition of a 10-watt power amplifier has yet to be performed.

5. Dual Crystal Oscillator

The assessment of the impact to make the crystal oscillator redundant has yet to be performed.

6. Dual Microprocessor

Same status as item 5. (Note that these two items are closely interrelated.)

7. Two-Bit Rate Command Link

The assessment of impact to utilize the two-command-rate feature of the transponder has yet to be performed.

8. Two-Speed Playback Rate

Same as item 7.

9. EMI Fixes

The impact to the hardware will be assessed for the major fixes to the system design when the "fix list" is specified.

10. Delta Interface

The system design has been modified to eliminate the requirement to impart system momentum to the DE-B spacecraft by rolling the second stage in favor of starting the momentum wheel from a signal generated in the DIGS.

**3.0 SPACECRAFT SYSTEM
DESIGN NOTES**

TABLE OF CONTENTS

<u>Design Note</u>	<u>Title</u>
2.2.2-004-DN	DE-A Acquisition Sequence
2.2.4-001-DN	DE-A Nadir Generator Error Sources
2.2.4-003-DN	Spacecraft Launch Configuration and Initialization
2.3.3-023-DN	Considerations Affecting the Implementation of Solar Cell Bypass Diodes and Resulting Solar Array Output Noise
2.4.1-004-DN	Dynamics Explorer Weight Report DE-A
Rev. H	
2.4.1-005-DN	Dynamics Explorer Weight Report DE-B
Rev. H	
2.4.1-013-DN	DE-A and -B Spacecraft Configuration and Mass Properties
2.4.4-003-DN	DE Radiation Environment Analysis

RCA Astro Electronics Division

Originating Project or Group Dynamics Explorer	Note No. 2.2.2-004-DN
Title DE-A Acquisition Sequence	
Written by: C. Hubert	Date June 1, 1978
Approved by: W. Fuldner <i>W Fuldner</i>	Date June 1, 1978
This DN supplements (S), replaces (R) DN Nos. () _____ () _____	Send one copy of this Note to the DCC (Library) attached to a copy of Form AED 1488.

Letter	Description	Date	Author

The proposed acquisition sequence is based on the assumption that the spacecraft core spin axis inertia is 50 slug ft^2 , the wire tip masses are 4.5 grams each, and the experiment booms are 9 in. diameter Astromasts. Variations of these parameters will affect the numbers presented, but the basic sequence of events should not change.

In the following discussion, recall that minimum wire tension occurs at the tip and maximum tension at the base.

Sequence of Events

- (1) Separate from the launch vehicle with a 40 rpm spin rate. This rate is the minimum achievable and was chosen in order to minimize the time required for the precession maneuver (event 3). This results in quicker acquisition of a favorable thermal environment, antenna coverage of earth throughout the orbit, and complete attitude determination throughout the orbit.
- (2) Deploy the S-band antenna. The timing of this event is not firm and it may occur prior to separation.
- (3) Magnetically precess the spacecraft angular momentum vector to the orbit normal.
- (4) Blow off all instrument covers. This event will occur at or shortly before the end of the precession maneuver. The timing provides in excess of 10 days for outgassing before the instruments are exposed.
- (5) Deploy the first 45 meters of the PWI wire antennas. This will approximately double the spin-axis moment of inertia and drop the spin rate to 19.6 rpm. The maximum wire tension during this phase of deployment will be 517 grams, occurring at a deployed length of approximately 35 meters. The minimum

wire tension will exceed 17 grams for deployed lengths greater than 1.5 meters.

- (6) Spin-up to 25 rpm.
- (7) Deploy the first three meters of the experiment booms. The spin rate will drop to 10.3 rpm. A maximum boom tension load of approximately 12 lb will occur during this phase of deployment.
- (8) Spin-up to 20 rpm. The tension at the base of the boom will rise to 26 lb.
- (9) Complete experiment boom deployment. A spin rate of 10.5 rpm results.
- (10) Spin up to 19 rpm. This represents slightly less than the final momentum. The experiment booms will experience tension loads of 36 lb (the greatest load applied during the acquisition sequence).
- (11) Complete wire antenna deployment. The peak wire tension load will be 624 grams and will be experienced at approximately 74 meters of deployed length. This represents the greatest tension experienced by the wires during the acquisition sequence. The spin rate will be reduced to 9.6 rpm.
- (12) Spin up to 10 rpm. The final spin-up is performed after wire deployment to avoid possible overshoot.
- (13) Deploy the spin axis tubular antennas. This event is scheduled last to minimize potential destabilizing effects.

The following table compares various requirements with the performance achieved by following the proposed sequence.

PERFORMANCE VS. REQUIREMENTS

		Requirements	Performance
Wire Antennas	Tension Upper Bound	8.0 lb	1.4 lb
	Tension Lower Bound	17 grams (after first few feet of deployment)	17 grams after 5 ft
	Number of Deployment Motor Starts	As few as possible	2
Experiment Booms	Maximum Spin Rate During Deployment	25 rpm	25 rpm
	Number of Deployment Motor Starts	As few as possible	2
	Maximum Tension Load		36 lb
Earth Sensor	Maximum Spin Rate	70 rpm	40 rpm
	Minimum Spin Rate	9 rpm	9.6 rpm
Scientific Instruments	Outgassing Time Before Exposure	At least 2 or 3 days	At least 10 days

**Originating Project or Group**

Note No. 2.2.4-001-DN

Title

DE-A Nadir Generator Error Sources

Written by:

W. V. Fuldner

Date _____

27 Sep 78

Approved by:

Date _____

10/10/78

This DN supplements (S), replaces (R) DN Nos.

REVISIONS

Letter	Description	Date	Author
			Standard Distribution: W. Hord (NASA) G. Hogan (NASA) D. Shipley R. deBastos S. Malyszka C. Hume

INTRODUCTION

This design note describes the operation of the nadir generator as it presently exists and provides a detailed error analysis of it. Reference (1) and (2) present the recently identified desires of the SAI instrument for accuracies of the nadir pulse generator to permit the present configuration of the instrument to obtain global auroral images. Table I summarizes the present spacecraft capabilities for nadir generation and Table II compares system performance with the SAI requirements.

DISCUSSION AND ANALYSIS

When mounted on the spacecraft (S/C), the optical axis of the body mounted horizon sensor (BMHS) will nominally lie in a plane which is normal to the X-Y plane of the S/C and θ_0 degrees away from the +Y axis as shown in Figure 1. Therefore, if it could be determined when the sensor optical axis passes through the nadir plane, it is known that S/C +Y axis would pass through nadir T_0 seconds later, where $T_0 = \theta_0/\omega_B$ and ω_B is the S/C body rate. Since it is not known in "real time" when the BMHS actually crosses nadir, but only when it makes sky-earth and earth-sky crossings, spacecraft +Y at nadir must be determined either as a lag of

$$T_0 + \frac{t_e}{2}$$

seconds from the BMHS sky-earth transition or as

as a lag of $T_0 - \frac{t_e}{2}$ seconds from the BMHS earth-sky transi-

tion, where t_e is the earth crossing time of the sensor. The former technique is the one used in the hardware implementation of the nadir generator.

In the implementation of the nadir pulse generator, two time counts are initiated as the BMHS makes a sky-earth transition (see Figure 2). The first (waveform B in Figure 2), which is driven by a 1024 Hz clock, counts the sensor earth crossing time, t_e ; the second (waveform C in Figure 2), driven by the S/C body clock, produces a count at each degree of body rotation. The earth time counter continues to count until the BMHS has an earth-sky transition, and holds its count, corresponding to t_e , until the body counter reaches a count of θ_0 . At this point the spacecraft +Y axis is nominally directed toward the sky-earth transition as shown in Figure 2. The t_e counter then counts down, driven by a 2048 Hz clock, reaching zero when the spacecraft +Y is along nadir. At this point, the nadir reference pulse (waveform D of Figure 2) is generated.

The accuracy of the nadir pulse so generated is a function of the altitude and rotation rate of the spacecraft. Table 1 provides the error summary for the case of the S/C rotating at 10 rpm. As seen in the table, the error contributors are distributed into three categories as follows: random errors, secular errors, and sensor bias errors.

Table 1.
Nadir Pulse Errors at a 10 rpm Spin Rate

Error Source	Worst case error - Degs	RSS Error Deg
I. Random Errors		--
Earth Time Threshold Jitter	0.164	
Spin Period Threshold Jitter	0.146	
Earth Time Clock Resolution	0.0879	
Spin Period Clock Resolution	0.052	
*RSS ₁		0.271
II. Secular Errors		
Earth Time Sample Rate - Δh	-0.0035	
Spin Period Sample Rate - Δh	0.030	
Earth Time Sample Rate - Δφ	-0.0070	
Spin Period Sample Rate - Δφ	+0.060	
Direct Sum		0.083
III. Sensor Bias Errors		
Threshold Drift	0.036	
Horizon Variation	0.120	
Earth's Oblateness	0.200	
Sensor Azimuth Alignment	0.1	
Dynamic Lag Calibration Uncertainty	0.2	
**RSS ₂		0.325
Error Summation	+1.18	+0.68

$$*RSS_1 = \sqrt{(0.164)^2 + (0.146)^2} + \sqrt{[0.5 (0.0879)]^2 + [0.5 (0.052)]^2} = 0.283$$

$$**RSS_2 = \sqrt{(0.036)^2 + (0.120)^2 + (0.200)^2 + (0.1)^2 + (0.2)^2} = 0.325$$

Table 2. Summary of SAI Nadir Requirements vs Spacecraft Performance

SAI Requirement	System Performance	Comment
<u>Orientation</u> Spin vector motion <0.25° p-p in 10 min.	Will meet requirements	Independent of Nadir performance. Function of total system momentum.
<u>Rate</u> Instantaneous rotational position <0.12° in 12 seconds.	Peak variation in angular position = 0.165° in any one 12 second interval	Assumes worst case reinforcement of thermoelastic induced body motion from successive eclipse exits.
<u>Azimuth</u> Nadir pulse (not a phase shifted nadir) measured to within ± 0.12° once per revolution	Short term RSS accuracy = +0.36° long term RSS accuracy = +0.68° Note: The accuracy for a phase shifted Nadir will be worse than the above.	Short term $\approx$ RSS random + secular errors of Table 1. Long term $\approx$ Short term + sensors bias error. Long term worst case number includes all factors at perigee operation.

!

- Random Errors - Random errors in nadir reference generation are produced by noise on the BMHS signal and the resolution of the various clocks.
- 1) BMHS Noise (Threshold Jitter) - Body horizon sensor noise produces jitter in the sky-earth and earth-sky edges of the earth envelope pulse (Figure 2, waveform A), therein inducing errors in both the spin period measurement which is used to control the body clock and the earth time measurement, t_e . Earth time measurements are affected by threshold jitter on both the sky-earth and earth-sky transitions. However, due to the nature of the generation scheme, the largest error in the nadir pulse location due to threshold jitter on the t_e measurement is the same as the largest error for a single threshold. The worst case threshold error, equal for both sky-earth and earth-sky transitions, is a function of the sensor noise level and the rate of S/C rotation. At a 10 rpm body rate, the worst-case threshold jitter amounts to 0.164° (at perigee), based upon the specified worst case 6:1 threshold to zero-to-peak noise ratio (See attachment (1) for noise calculations).

Referring to the 30 August memo (Reference 2), page 3, under the heading "comments": RCA concurs that the earth horizon sensors should be able to determine the earth horizon to within $\pm 0.2^\circ$. This was substantiated by the calculations presented to Iowa on 1 August during my visit there when the scan to scan jitter calculations (attachment 1) were presented which identified the scan to scan worst case jitter, due primarily to threshold to noise considerations, as $\pm 0.152^\circ$ at apogee and $\pm 0.164^\circ$ at perigee. As was noted at the time of the discussions, the shape of the distribution was not known and we recommended not treating the number as "n sigma" value. Subsequent to the discussions we verified that the analytic model did not utilize a simplified "step input" horizon, but did convolve the sensor field of view with a representative analytic model of the CO₂ horizon. The horizon model was extracted from "The Analysis of 15 micron Infrared Horizon Radiance Profile variations over a range of Meteorological, Geographical, and Seasonal Conditions", NASA CR-725, April, 1967.

Additional investigations to date as to the nature of the distribution of the errors has indicated that they result primarily from thermal noise, which is assumed to have a gaussian distribution, and $\frac{1}{f}$ noise, which does not. Since the horizon sensor is AC coupled, the $\frac{1}{f}$ contribution of the $\frac{1}{f}$ noise will probably be small compared to the thermal

noise and a gaussian distribution may be assumed. No empirical information is available to adequately characterize the noise and jitter distributions. The numbers used in the jitter analysis represent a worst case threshold to noise value. Thus, extrapolation back to a one sigma value, while probably a reasonable "guess", can only be done at ones own risk.

Spin period measurements are affected by the jitter on successive sky-earth transition thresholds. At 10 rpm, this amounts to a worst case error of 0.328 degrees (at perigee) per S/C rotation. However, the contributing error to the nadir reference pulse is $\theta_0/360$ times the error for an entire revolution. For this analysis, a value of 160 degrees was employed for θ_0 . This value is based upon the sensor's current design location on the S/C and certain calibration considerations.

- 2) Clock Resolution - There are essentially four clocks that are used in generating the S/C nadir reference pulse. These are the 1024 Hz and 2048 Hz clocks associated with the earth time up-down counter, -- the 131,072/360 Hz clock used to measure the S/C spin period and control the body clock, and the body clock which emits a pulse for every degree of S/C rotation.

Resolution errors in the earth time measurement are incurred at the sky-earth and earth-sky transition, i.e., at the start and end of the count up, and at the start of the double frequency count down (circled points Figure 2, waveform B). Since the counter contains an integral count after the sensor has crossed the earth, there is no resolution error at the end of the count down. At the 10 rpm body rate, the 1024 Hz clock has a resolution of 0.0586 deg/count, and the 2048 Hz clock has a resolution of 0.0293 deg/count.

Resolution errors in the spin period measurement are incurred at the start and the end of each count. At the 10 rpm body rate, the 364.1 Hz clock has a resolution of 0.165 deg/count, resulting in an error of 0.117 degree per S/C revolution. Again, this must be multiplied by the factor $\theta_0/360$ to obtain the error in the nadir reference pulse.

In the nadir generator, the body clock is used to determine when the S/C has rotated θ_0 degrees after the BMHS has a sky-earth transition. Since the body clock, which has a one degree resolution, is synchronized to the sky-earth transition threshold and since θ_0 is an integral number of degrees (160), it contributes no resolution error to the nadir reference pulse. It will contribute an error, however, in the phase shifted reference pulses supplied to the instruments as discussed below.

Assessment of the error introduced by the digital precision of the nadir generator has indicated the following:

Reference clock used	Worst case error at 10.000 rpm
131 kHz	0.165 ⁰ (baseline system design)
262 kHz	0.0825 ⁰
512 kHz	0.0413 ⁰ (upper limit allowable without major impact to CTP design)

Note that the worst case error is a linearly increasing function throughout one rotation of the spacecraft with the worst case error occurring at the 359° nadir pulse.

- Secular Errors - Errors in both earth type measurements and spin period measurements are produced as a result of S/C altitude changes and body rate changes, and also when there is a roll rate on the S/C. The errors are not random in nature, but rather add algebraically.
- 1. Altitude Change - Altitude change, as the S/C proceeds around in orbit, produces errors in the earth time and spin period measurements which are partially self compensating. The effect is best understood by considering a specific case as that of increasing altitude shown in Figure 3. Referring to Figure 3a, the BMHS makes a sky-earth transition at S/E and an earth-sky transition at E/S. The E/S point is moved into the smaller, dotted circle (earth) since the earth appears slightly smaller at the higher altitude achieved during the crossing. The earth time count will then be the time required for the sensor field-of-view (fov) to pass between these two points. Since the double frequency count down is initiated θ_0/ω_B seconds after the sensor sky-earth crossing, when spacecraft +Y is directed in space towards S/E, the nadir pulse (N_A) will occur at a point which is short of the true nadir (N_T).

For the spin period measurement, a count will begin when the sensor makes a sky-earth transition (S/E₁ in Figure 3b) and end on the following sky-earth transition (S/E₂). Since the earth has appeared to shrink in the time interval between the two transitions, the spin period count will be slightly larger than the actual spin period. Thus when the body clock counts the θ_0 degrees after the sky-earth transition, the S/C will have rotated through an angle greater than θ_0 which will tend to delay the start of the double frequency t_e count down and shift the nadir pulse toward earth-sky (N_A toward N_T in Figure 3a).

Thus it is seen that the earth time and spin period counts do partially compensate for one another when the S/C altitude is increasing. The effects are simply reversed when altitude decreases, with the errors again partially compensating.

The systematic rate of change of the scanned earth, as a function of the DE-A spacecraft altitude is addressed in the computer generated plots 1, 2, and 3. (Attachment 3). These three plots display theta, the true anomaly angle, satellite height above a mean earth radius, and $\Delta 2\beta$, the change in total scanned angle of the earth all as a function of time. Plot 1 includes the first 60 minutes from perigee, plot 2 includes the time during which the spacecraft is above are altitude and plot 3 includes the last 60 minutes concluding at perigee. A complete listing of the data plotted, in six second increments, around the entire orbit is available should more precise information be required. Note that in plot 2, the change in scanned earth angle over much of the time results in very

small changes scan-to-scan such that it is believed this systematic change will not result in significant nadir contamination of SAI pixel registration. Since the change is systematic and predictable, it does lend itself to correction by ground data processing.

2. S/C Roll Rate - The error induced in the nadir pulse location by a roll rate on the S/C is strictly analagous to that caused by a change in altitude. If the roll rate is such as to cause the BMHS to view smaller cross sections of the earth, as shown in Figure 4, the earth time and spin period measurements will be in error in the same sense as in the case of increasing altitude discussed above. Roll rates are negligably small throughout the orbit due to the "stiffness" of the DE-A spacecraft.

3. S/C Body Motion

The referenced 30 August memo also addresses the rotation rate and the stability thereof. The details of the operation of the nadir generator, including the constraints imposed by the physical positioning of the body horizon sensor relative to the reference nadir azimuth (the +y axis fo the DE-A spacecraft) result in a modification to the rotation rate requirement as stated to be over a nine second period rather than twelve seconds. This occurs because the nadir generating reference clock is updated one half rotation later rather than the assumed full rotation later. The approach taken to the calculation of worst case angular displacement is correct, however, the resulting peak displacement, assuming a worst case reinforcement of the motion from one eclipse exit to the following is 0.165°. (The calculation resulting in this value is shown in attachment 2). Attachment 4 graphically depicts the variations in true body rate for the disturbances imparted to the spacecraft. The upper curve shows the 41 second oscillation (solid curve) superimposed on the exponential spin rate decay (time constant of 55 seconds) with the worst case AC motion assuming the re-inforcement from one orbit to the next shown as the dotted curve.


The same motion, excluding the exponential decay is shown in the center curve, both for the expected and the worst case reinforced. Finally, the third curve shows the aerodynamic disturbance which builds up and decays in the vicinity of perigee. This disturbance, which has a period equal to the body rotation period is shown for about the 275 km perigee and the 190 km perigee conditions. As this disturbance both appears and disappears well below the 1 R_e altitude noted in the referenced 30 August memo, it is believed that its effects on nadir operation should be neglected.

● Sensor Bias Errors - There are several error sources associated with the BMHS which contribute to the uncertainty of the nadir reference pulse. These sources produce a bias shift in the earth pulse (Figure 2, waveform A) and hence produce a phase shift in the nadir pulse.

1. Threshold Drift - The BMHS on DE is an a.c. coupled sensor which employs independent thresholding of both the leading and trailing earth crossing pulses. The threshold circuits employed have a $\pm 1.5\%$ drift tolerance over time and temperature which results in a worst case drift per edge of ± 0.036 degree at 10 rpm in the nadir pulse.
2. Horizon Variation - Variations in both the shape and peak magnitude of the CO_2 horizon (the BMHS is sensitive to radiation in the 16-16 micron, CO_2 spectral interval) radiance profiles will vary the location of the sky-earth and earth-sky threshold points. The radiance (peak magnitude) errors are a function of the rotation rate of the sensor while the shape changes produce shifts which are primarily a function of altitude. The evaluation of these effects is based upon in-house computer simulations.
3. Earth's Oblateness - The bulge in the earth near the equator produces a shift in the earth transition pulse which is a function of the altitude of the S/C and the latitude of the nadir. The induced error is worst when the S/C passes through perigee. This parameter was used to obtain the results shown in Table I.
4. Sensor Azimuth Alignment - The azimuthal misalignment of the sensor produces a direct, one-to-one error in the nadir pulse as it represents a shift in the true value of θ_0 . The BMHS performance spec specifies that the optical axis of the sensor be aligned to within ± 0.1 degree.
5. Dynamic Lag Calibration Uncertainty - Due to the sensor dynamic response time and the earth's limb radiance phenomenon, there is a bias that exists between the earth envelope pulse and the true earth. Current procedures can achieve a calibration to within ± 0.2 degree.

REFERENCES:

- (1) ~~Nadir~~ Accuracy, Letter dated July 21, 1978 from J. Craven to K. Fellerman.
- (2) Updated Requirements for Nadir Generator, Letter dated August 30, 1978 from J. Craven to K. Fellerman.




X-Y PLANE PROJECTION OF NADIR GEOMETRY
FIGURE 1

ORIGINAL PAGE IS
OF POOR QUALITY

NADIR PULSE GENERATION FIGURE 2

ORIGINAL PAGE IS
OF POOR QUALITY






FIGURE 3a
 t_c MEASUREMENT




FIGURE 3b
SPIN PERIOD MEASUREMENT

GEOMETRY OF INCREASING ALTITUDE DURING TIME MEASUREMENTS
FIGURE 3

7/23/78

DE-A Noise Estimate

Apogee (Run 508)

$$S/E \text{ Slope} = \frac{.7709 - .7234 \text{ V}}{.001 \text{ sec}} = .0475 \text{ Volts/msec}$$

$$\text{Noise} \leq \frac{V_{\text{peak-to-peak}}}{12} = \frac{1.415}{12} \text{ V}$$

$$E_T = \frac{V_N}{S/E \text{ Slope}} = 2.54 \text{ msec}$$

$$\omega_s = 60^\circ/\text{sec}$$

$$\therefore \text{Noise error} = \omega_s E_T = 0.152^\circ \text{ per transition}$$

Perigee (Run 551)

$$S/E \text{ Slope} = \frac{.984 - .972}{.005 \text{ sec}} = .0594 \text{ Volts/msec}$$

$$\text{Noise} \leq \frac{V_{\text{peak-to-peak}}}{12} = \frac{1.96}{12} \text{ V}$$

$$E_T = \frac{V_N}{S/E \text{ Slope}} = 2.75 \text{ msec}$$

$$\omega_s = 60^\circ/\text{sec}$$

$$\therefore \text{Noise error} = \omega_s E_T = 0.164^\circ \text{ per transition}$$

Calculations will be updated, but expected to remain within 1%

ORIGINAL PAGE IS
OF POOR QUALITY

$$\Delta W = K(.003) \text{ Rev/min} \times \frac{1}{60} \frac{\text{min}}{\text{sec}} \times 360^\circ/\text{Rev} \sin \frac{2\pi}{41} x$$

$$= \frac{.62}{.4} (.003) 6 \sin \frac{2\pi}{41} x$$


NOTE $\frac{.62}{.4} = K$ is our assessment of the worst-case, in phase reinforcement of the 41 second period sine wave disturbance from one eclipse exit to the second exit.


$$\Delta W \equiv \Delta \dot{\Theta}, \quad \Delta \Theta = \int \Delta \dot{\Theta} dt$$


For a 6 second interval, the worst case $\Delta \Theta$ is twice the magnitude of the change along the cosine curve from the zero crossing to three seconds later.


$$\therefore \Delta \Theta = 2 \int_{10.25}^{13.25} \frac{.62}{.4} (.003) 6 \sin \frac{2\pi}{41} x$$

$$= 2 \frac{\left(\frac{.62}{.4}\right) (.003) 6}{\frac{2\pi}{41}} \sin \frac{2\pi}{41} x \bigg|_{10.25}^{13.25} = .165^\circ$$









FOLDOUT FRAME

2

Design Note

TREAT Astro Electronics

Originating Project or Group	Note No.
	2.2.4-003-DN
Title	
Spacecraft Launch Configuration and Initialization	
Written by:	Date
W. V. Fuldner <i>W. V. Fuldner</i>	October 16, 1978
Approved by:	Date
<i>W. G. Stapp</i>	10/16/78
This DN supplements (S), replaces (R) DN Nos.	

REVISIONS

Letter	Description	Date	Author

1.0 INTRODUCTION

The launch scenario for the stacked spacecraft and the subsequent orientation and initialization maneuvers take maximum advantage of the capabilities of the system design while minimizing the interfaces with the launch vehicle. The flow of activities from liftoff until the completion of the 30-day initialization maneuvers is shown in Figure 1.


2.0 DEPLOYMENT OF DE-B

The assembled stack, third stage, and second stage may require orientation to achieve a favorable sun angle during the coast phase between the first and second burns of the second stage. This is a departure from the normal Delta procedure of immediately orienting to the second burn orientation after SECO-1. Such maneuvering may be required as the forward facing end of the DE-B Spacecraft on the top of the stack is the same end which contains the thermal louvers. The thermal design of DE-B will not tolerate extended periods of direct solar input to this surface. The maneuvering required is an analysis task to be performed in conjunction with the Delta Office during the course of the program.

2.1 Yaw Orientation


Subsequent to the second burn of the second stage, the complete stack, under the control of the second stage guidance system, executes a yaw maneuver in excess of 75 degrees from the orbit plane, bringing the -Z axis to within 15 degrees of the positive orbit normal. This maneuver serves to establish the DE-B Spacecraft in nearly the desired orientation for the mission. The actual angle selected will be defined as a result of an analysis performed in conjunction with the Delta Office under two primary constraints, namely:

1. The spacecraft must be oriented sufficiently close to the mission mode to permit the wheel horizon sensors to scan the earth during the entire orbit.
2. A satisfactory forward velocity component can be maintained resulting from the separation spring action to achieve adequate and safe separation spacing between the DE-B spacecraft and the third stage at the time of third stage ignition.



*MAXIMUM TENSION OF 1900 GRAMS AT 38 METERS DURING THIS OPERATION.
MINIMUM TENSION >17 GRAMS.

FOLDOUT FRAME



FOLDOUT FRAME 2

Figure 1. Launch, Acquisition, and Initialization Sequence

2.2 DE-B Angular Momentum Establishment

In the interval between SECO-2 and the completion of the 75 degree yaw maneuver, the momentum wheel will be turned on in response to an electrical interface with the second stage sequencer. Reacting against the attitude control system of the second stage, the wheel will be rotated to 750 rpm, resulting in the establishment of approximately 500 in-lb-sec of momentum within the momentum wheel. Thus at separation, the DE-B spacecraft will possess the nominal system momentum required for the mission. --

2.3 Initialization of DE-B

Subsequent to deployment, the 30-day initialization period incorporates the following activities: The momentum wheel is commanded into pitch capture orienting the body of the spacecraft at 1 rpo. The remainder of the precession maneuver is completed using the attitude control torquers, aligning the -Z axis with the positive orbit normal. The system momentum is then "trimmed" to the nominal 500 in-lb-sec using the momentum torquer. Note that on the DE-B spacecraft, momentum torquing must be performed while in the 1-rpo state, as there is no sensor available to define commutation conditions as is done on the DE-A via the BHS.

During the time that the precession maneuver is completed and the momentum is augmented to the nominal system value, the spacecraft outgassing is completed and all "blow off" covers are ejected. All such ordnance-activated deployables will be ejected prior to the start of boom deployment. Also during this time, residual nutation will be removed by means of the fluid damper.

During the following deployments, the pitch control subsystem is operated in the "open loop" mode to avoid the potential for dynamic interactions between the erectables and the momentum wheel. One pair of the VEF 11-meter antennas in the X-Y plane is then deployed, followed by the second pair of X-Y plane VEF antennas. Next, the magnetometer boom is deployed. Completion of the deployment of this mechanism generates the inertial cross product required by the system to perform active nutation damping. Thus, upon completion of the deployment, the pitch control electronics are commanded to initiate active nutation damping.

The Z-axis 11-meter VEF antennas are deployed, followed by the erection of the LAPI magnetometer mast and the uncaging of the scan platform. Upon completion, the DE-B spacecraft is in the fully operational mission state.

2.4 Preparation for Third Stage Burn

Referring to Figure 1, subsequent to the deployment of the DE-B spacecraft, a return yaw maneuver is initiated on the remainder of the stack. This maneuver is interrupted to permit the deployment of the interstage adapter. Upon completion, maneuvering is re-initiated until the assembly is in the desired orientation for the third stage burn. The deployment of the 1828 adapter (interstage adapter) is sensed by the DE-A C&DH system to initiate erection of the DE-A S-band antenna. The third stage spin table is activated, achieving the planned 70-rpm rate. This rate has been selected to optimize the amount of time required, within the allowable range of 70 to 120 rpm to precess the spacecraft to the mission orientation, and also to optimize the accelerations imparted to the deployed antenna while still achieving the science driven orbit dispersions.

2.5 DE-A Precession Constraints

The primary concern of quickly accomplishing the precession maneuver is to minimize the time during which the spacecraft is oriented unfavorably for thermal system performance. Until the spin axis of DE-A is nearly aligned with the orbit normal, there are significant periods of time in each orbit where the thermal louvers on the anti-sun end of the spacecraft are not viewing the cold space sink but are viewing the earth instead. The system then has reduced capability to expel heat. Similarly, the BHS will not view the earth for significant portions of the orbit, and, in like manner, the pattern of the S-band antenna will not be favorable for portions of the orbit.

2.6 DE-A S-Band Antenna Considerations

At apogee and at perigee, the link performance will be as in the link tables (see 3.5.2-001-DN "DE-A and DE-B Link Analysis") regardless of the Z-axis orientation. When not at apogee or perigee, link performance will be degraded by an amount which depends on the orientation of the Z-axis. The worst-case will occur when the Z-axis lies in the orbit plane. In this case, approximately 75% of the orbit period will be available for commanding, 60% for ranging, and 50% for HEW telemetry. The contact time will be centered near apogee. There also will be a brief contact interval (approximately 2 minutes) near perigee.

As the precession maneuver moves the spin axis from the orbit plane to the operational orientation, the coverage capability increases until the operational capability as shown in the proposal is achieved.

2.7 Initialization of the DE-A Spacecraft

As noted above, the first maneuver performed subsequent to the third stage separation is the precession to align the spin axis to the orbit normal. While the total time from separation to mission configuration achievement is approximately the same for the total range of third stage spin rates, the percentages of this time allocated to precession and to momentum adjustment vary greatly. As was the case in DE-B, the outgassing of the spacecraft and the ejection of all blow-off covers will be achieved prior to the initiation of any deployables other than the S-band antenna.

The wire antennas are partially deployed (approximately 60 meters), thus reducing the body spin rate. The body rate is then approximately 25 rpm.

The PWI loop antenna is then uncaged, and the two instrument booms are partially deployed to approximately 4 meters resulting in a reduction in the body spin rate to approximately 11.7 rpm. The body rate is increased to 14 rpm by the addition of system momentum. Note that the addition of momentum to the system requires commutation of the momentum coils under control of the BHS which in turn, requires the spin axis to be aligned closely to the orbit normal. The 6 meter instrument booms are then deployed to their full length, followed by another augmentation of system momentum until the body rate is approximately 17 rpm. The deployment of the wire antennas to their full 100-meter length is then completed, with the body rate at the completion approximately 9.9 rpm. The momentum is then trimmed to the desired 10 rpm. The strategy of targeting the spin rate as slightly under 10 rpm at the completion of the wire antenna deployment is based on minimizing the amount of time taken in adding momentum to the system throughout the process. Upon completion of this maneuver, the 3-meter Z-axis antennas are deployed, and the DE-A spacecraft is in the operational mission condition. Assuming nominal unregulated bus voltages, which are the power source for the magnetic torquers, the total torquing and deployment tasks will be accomplished within the 30-day initialization period as indicated by the time allocations in Figure 1.

Design Note

REA Astro Electronics

Originating Project or Group DYNAMICS EXPLORER	Note No. 2.3.3-023-DN
Title CONSIDERATIONS AFFECTING THE IMPLEMENTATION OF SOLAR CELL BYPASS DIODES AND RESULTING SOLAR ARRAY OUTPUT NOISE	
Written by: W. Fuldner <i>W Fuldner</i>	Date May 15, 1978
Approved by: <i>R de Santos</i>	Date
This ON supplements (S), replaces (R) ON Nos.	


Letter	Description	Date	Author

INTRODUCTION


This design note addresses the effects on solar array output voltage and current resulting from the addition of bypass diodes to the solar cells of the solar array. Included in the evaluation presented are some alternative considerations to solar cell layouts and the complexities involved for the two different solar arrays for DE-A and DE-B. Also addressed is the proposed implementation technique for the installation of the diodes to minimize the impact on present solar array fabrication techniques. --

BACKGROUND

To assess the performance of the solar array and the need for bypass diodes, the following discussion is presented. Consider a series connected string of five solar cells as shown in Figure 1-a. As shown, each cell has a bypass diode in parallel with the cell. In the event one of the series cells is shadowed, the current generated by the remaining series cells can continue to flow via the diode of the shadowed cell, thus permitting continued energy generation in the presence of localized shadows to some cells in the string. While permitting the continued generation of current under shadowed conditions, there is a resulting decrease in the output voltage of the string shown schematically in Figure 1-b. In the unshadowed condition the output voltage is $5 \times 0.4 \text{ volts/cell} = 2.0 \text{ volts}$. When the shadow occurs, there is one less cell generating voltage and an additional drop of approximately 0.8 volts across the conducting diode. Thus, for every series cell that is shadowed, assuming a diode around each cell, the loss in output voltage is $0.4 + 0.8 = 1.2 \text{ volts}$. For the five cell series string of Figure 1, with one cell shadowed, the output reduces to 0.8 volts. Consider four series strings of "n" series cells, which are in turn connected in parallel to form an array as indicated in Figure 2. The solid line curves represent the normal (unshadowed) performance of each string and of the composite array. If a cell in string one is shadowed, the curve shape is the same except for the dotted portion as shown for string one, and its resulting impact to the composite array. In Figure 2, the load line of the shunt limiter is superimposed, and is shown intersecting the maximum power point on the solar array, the normal design practice when shadowing is not considered. With the effects of shadowing, however, as can be seen in Figure 2, the voltage reductions experienced when bypass diodes are employed result in significant movements of the operating point of the array output voltage (addressed below under discussion). For this reason, overdesign of the solar array can be considered by adding additional series cells to each string and intentionally establishing the shunt limiter at a non-optimum power point on the array curve. By so doing, the area of variation of the curve due to shadowing of any of the individual string cells is moved above the normal operating point on the array curve. This technique results in decreased array efficiency in that more solar cells are being flown than ordinarily required without shadowing, and adds additional constraints to the geometry considerations of the physical mounting of the cells to the spacecraft.



|||



NO SHADOW

$$V_{OUT} = 5(.4V) = 2.0V$$

SHADOW 1 CELL

$$V_{OUT} = (5-1)(.4) + (-.8) = 4.8V$$

FIG 1 - BASIC CELL SHADOWING CONSIDERATIONS.




FIG 2

DISCUSSION

Considering now the DE solar array, the basic operating curve for which is shown in Figure 3, with V_{oc1} the open circuit voltage of the normal array and I_{sc} the instantaneous short circuit current for the existing sun angle and hat orientation dictating how many of the available series strings are illuminated. If the spacecraft load requires a total current out of the solar array of I_{L1} , the shunt limiter is actuated and the excess current from the array $I_{L2} - I_{L1}$, is diverted to the shunt limiter, and the operating point of the solar array is at node "A". If a shadow -- is now experienced, leading to the dotted performance curve of the array, the operating point on the array moves to node "D", with a change in current in the shunt limiter of $I_{L2} - I_{L3}$. Note that this will result in a rapid change in shunt current but relatively little variation in solar array voltage. Conversely, consider the condition when the spacecraft-demanded load is approximately I_{L2} and a shadow occurs. Under the conditions prior to shadowing, the operating point is still node "A" but under these conditions, no current is flowing in the shunt. When the shadow occurs, the array seeks a new operating point, namely node "C" where it can again supply the demanded current I_{L2} , and a voltage variation of $V_{sh} - V_C$ is experienced.

If the geometry of the solar array precludes a solar cell layout which, in conjunction with the variations in array operating temperatures, precludes the addition of sufficient cells to "overdesign" the array (curve of V_{oc2} of Figure 3) such that the shadow variations occur above the shunt limiter operating point, two alternatives are available.

1. To minimize the voltage noise for instrument operation when shadowing will occur, operate the system either with a light enough load so that the voltage variations are minimized by having the shadow-induced operating changes not be significant enough to exit from shunt limiter operation; or, alternately,
2. Load the system sufficiently to get to a sufficiently low operating point on the array curve to be below shadow voltage variations.

If the prime noise concern is the current variations in the shunt limiter, then the first solution, even with the bypass diodes is less favorable than the second.

DE-A Side Panel Array Layout

Present predictions of operating temperatures for the side panels of the DE-A solar array indicate a requirement for 86 series solar cells in each string. As shown in Figure 4, the proposed solar cell array layout utilizes, for the blank panels (no cutouts), strings of cells which are three parallel cells by 86 cells long. This allows for no additional cells to be dedicated to compensation for diode voltage drops while retaining a design that permits discrete cell circuits to be dedicated to a single panel. Also shown in the Figure is the path to be followed by the return wire for the cells of the






FIG 3

ORIGINAL PAGE IS
OF POOR QUALITY

FIG 4 DE-M SIDE PANEL LAYOUT





continues for 2 more sections.

ORIGINAL PAGE IS
OF POOR QUALITY

FOLDOUT FRAME 2

particular string. If an aperture is required in the panel for an instrument, the same technique will be used except that the number of parallel cells will be reduced from 3 to 2 or from 3 to 1 depending on the size of the aperture.

DE-B Side Panel Layout

The same approach will be taken in the layout of the side panels of the DE-B solar array except that the only single parallel cell or at most two parallel cells will comprise the strings. This results from the expected operating temperature of the DE-B despun spacecraft solar array being warmer than that of DE-A and therefore requiring more series cells in the array to achieve the required operating voltage. With a thermally required 117 series cells in the DE-B array, and adding four additional cells for shadow compensation, the layout technique for DE-B will be the same as that for DE-A.

An assessment of this layout of the side solar arrays for both hats has indicated that the A array will consist of the following combination of strings of 86 series cells:

Panels with three parallel cells	20
Panels with two parallel cells	12
Panels of single cells	3

and DE-B side array will consist of the following combination of 121 series cells:

Panels of two parallel cells	28
Panels of single cells	5

Noise Signature on Solar Arrays

As was noted in the background discussion above, the addition of the bypass diodes will not eliminate voltage and/or current variations on the solar array resulting from shadowing unless "overdesign" of the array is included to move the operating point of the array/shunt limiter to below the worst-case voltage notch resulting from operation of the diodes. With the limitations imposed on the layout of the DE-B side array permitting no more than two parallel cells in any series string, the ability exists to increase the number of series cells from the required 117 to 129, thereby adding 12 series "overdesign" cells and eliminating or greatly reducing the voltage noise and shunt current noise described above.

For the DE-A side array, the 86 series cell requirement allows for no "overdesign" cells and thus would permit noise, as noted above, to exist if appropriate load programming cannot overcome the problem. In the event that the worst-case operating point is encountered for voltage noise (solar array operating just at the threshold of shunt limiting) and a maximum of four cells in a string are shadowed, then the worst-case shadow induced voltage variation would be (refer to Figure 1):

$$\begin{aligned} V_{out} \Big|_{\text{no shadow}} &= (82)(.46045) - 39.5V \\ - V_{out} \Big|_{\text{shadow}} &= (86-4)(0.46045) + (4)(-0.8) = \frac{34.56V}{4.94V} \end{aligned}$$

NOTE: In this calculation, the precise cell voltage of 0.46045V is used corresponding to the predicted side array temperature for DE-A as opposed to the 0.4V / cell of the simplified example in Figure 1.

Thus, with the array threshold at 39.5 volts (topmost solar cell string voltage), this shadow ripple would result in a peak voltage excursion of 4.94 volts. Initially, such a voltage ripple is judged to be unacceptable. However, consideration of the frequency of such a ripple may place it in a location in the spectrum where it is not of significance. The side array is rotating at 10 rpm; thus, the rate that any string of cells can experience shadowing is approximated by 35 strings per hat divided by half the spin period; 3 seconds. Half the spin period is considered as the shadow, in worst-case, must initiate and terminate only during the half of the rotation in which the array is illuminated. Thus, the maximum frequency of the ripple should have an upper bound of no more than 12 Hz. If this is out of the region of spectral interest, it is conceivable that such a shadow-generated noise is acceptable. Note also that the transition from illumination to shadow and back to illumination will be relatively slow as opposed to instantaneous step changes, thereby minimizing the spectral harmonic content of the ripple voltage.

Alternately, if the operating point of the system is such that significant shunt current is flowing (see background discussion), the voltage ripple may not exist, but current ripple in the shunt may vary at the same rate as noted above. Under this condition, assuming the shadowed cells are in parallel independent single cell strings (worst-case) then the current ripple could be $4 \times 110 \text{ ma/cell/hat} = 0.88 \text{ amps peak variation}$.

If the selected shunt dissipator design approach, and the return path for the array current approach is satisfactory, then the magnetic noise variations resulting at the approximate 12 Hz variation may not be unacceptable.

CONCLUSIONS

Initial assessment of solar array performance, including the effects of bypass diodes for shadowing indicates that the DE-A array has the potential for significant noise amplitudes in either current or voltage variation in the low frequency regime (less than 12 Hz). If the existence of the noise in this region does not pose a significant noise problem, it is recommended that the array design be so implemented. The DE-B side array can be "overdesigned" to move the operating point to a location which will preclude the existence of significant noise. Should the DE-A noise signature be unacceptable, then alternate array layouts, which require individual strings of the array to be physically housed on more than one side panel must be considered, along with the additional complexities in fabrication, fixturing and testing of the array panels.

DYNAMICS EXPLORER

Design Note

IRCE Astro Electronics

Distribution
 C. Chatpar
 R. deBastos
 W. Fuldner
 F. Gross
 R. Horner
 C. Hume
 K. Johnson
 D. Lacerda
 S. Malyszka
 J. Massari
 P. Nekrasov
 D. Shipley
 S. Roth
 File

Originating Project or Group

DYNAMICS EXPLORER

Note No.

2.4.1-004-DN

Title

DYNAMICS EXPLORER WEIGHT REPORT DE-A

Written by:

K. R. Johnson *KR Johnson*

Date 1 November 1977

Approved by:

W. Fuldner

Date

This DN supplements (S), replaces (R) DN Nos.

() ()

REVISIONS

Letter	Description	Date	Author
A	Monthly Update - December, 1977; Sheet 2 annotated, Sht. 3, 4 & 5 Revised	12/6/77	K. Johnson <i>KRJ</i>
B	Monthly Update - January, 1978 Sheet 2 annotated, Sht. 3, 4, & 5 Revised	1/12/78	K. Johnson <i>KRJ</i>
C	Monthly Update - February 1978. Sheet 2 annotated, sheet 3, 4 & 5 revised. Sheet 6 (summary) added.	2/1/78	K. Johnson <i>KRJ</i>
D	Monthly Update - March 1978 Sheet 2 annotated, sheet 3, 4, 5, & 6 revised	3/1/78	K. Johnson <i>KRJ</i>
E	Monthly Update - May 1978 Sheets 3 thru 8 revised	5/16/78	K. Johnson <i>KRJ</i>
F	Monthly Update - August 1978 Sheet 3 Annotated, Sheet 4 thru 8 Revised.	8/21/78	R. Crawford <i>RDC</i>
G	Monthly Update - September 1978 Sheet 3 Annotated, Sheets 4 thru 8 Revised.	9/15/78	R. Crawford <i>RDC</i>
H	Monthly Update - October 1978 Sheet 3 Annotated, Sheet 4 thru 8 Revised.	10/16/78	R. Crawford <i>RDC</i>

The attached is an equipment configuration and weight list by functional groupings for the DE-A spacecraft as of 1 December 1977. Each major entry is marked "+" to indicate that it is a sum of the indented entries below it. Weight entries are totals for the total quantity of any given line item.

For November 1977, the margin (or allowance for growth) is shown as zero and therefore the totals represent total hardware only, not total launch weight.

During November 1977, margins were set at 10% of the spacecraft total (49.0 lb), 15% of the Instrument total (26.3 lb) and 25 lb. misc. for a total of 100.3 lb margin. Thus, the total launch weight, including margin, is 790 lb.

For December 1977, the Instrument total weight changed from 174.38 lb. to 186.06. Accordingly, the GFE margin was adjusted down to 14.62 lb to maintain a constant spacecraft weight.

The January 1978 weight report shows an additional 4.0 lb. under spacecraft structure for the antenna support hardware and an additional 3.55 lb. under GFE for PWI growth. The margin allowances have been adjusted to maintain the launch weight constant at 790 lb.

During January 1978 the weight estimate for Instruments increased by 60.2 lbs. which breaks down as follows: PWI +2.9 lbs., SAI +45.3 lbs., and RIMS +12.0 lbs. (reported as 3 heads for the first time). The total Instrumentation weight has therefore grown beyond the amount reserved for it plus all GFE margin and miscellaneous margin and has now encroached on the spacecraft margin. Total margin is now 20.9 lbs.

The March 1, 1978 issue of this report (which shows updates received thru February 1978) includes a growth of 28.5 lb. for the spacecraft which is made up of the following: structure +12.5 lb., power +7.0 lb., communications +1.3 lb., C&DH +7.7 lb. A decrease of 42.5 lb. occurred for the instruments & subtotal (all SAI).

The attached weight report for May 1978 includes all updates and the revised system baseline as of May 1.

Three columns of weight entries are given. The first, labelled "Proposal Weight" is the weight, by subsystem, at the time of the original system definition (Feb. 1977). The second column, "Target weight", is the baseline weight allocated by the NASA Delta Project Office to each subsystem or equipment and represents the authorized weight for each. Column three, "estimated/actual weight", gives the current -- estimate (made by the supplier) for each component. Thus, a comparison of columns 2 and 3 will show whether any component is over or under the weight allocated to it on an individual basis.

Summaries of estimated instrumentation and spacecraft weights are given on the last page where they are compared against the program totals and program margins. Totals have been changed as a result of revised Delta performance estimates and this has resulted in revised margins.

In the previous weight report for May 1978 the balance weight of 50 lbs. was shown as part of the spacecraft margin. The updated report reflects a reapportioning of this weight to the spacecraft weight which caused an apparent increase in total hardware and decrease in the margin weight.

The August 1978 weight report shows an increase of 8.6 lbs. in total hardware weight. This change was due to the following changes: Attitude control + 11.4 lbs., Power - 3.54 lbs. and GFE + .63 lbs.

In the weight report for September 1978 a total of 13.488 lbs. were lost from total hardware weight. The difference is accounted for in the following areas: Upper Hat -.9 lbs., Lower Hat -.9 lbs., RF screens +.936 lbs., ATC brackets +2.01 lbs., Upper Solar Array -2.25 lbs., Lower Solar Array -2.25 lbs., Magnetometer Sensor -.64 lbs., Magnetometer Electronics -.494 lbs., HAPI cabling -1.5 lbs., Magnetometer Astromast -4.00 lbs., and PWI Astromast -4.00 lbs.

In October the total spacecraft weight increased by 11.892 pounds in the following areas by the following amounts: Shear Panels 1 thru 6 +6.00 lbs, End Hat Upper +0.9 lbs, End Hat Lower +0.9 lbs., Upper Solar Array +2.25 lbs, Lower Solar Array +2.25 lbs., PWI Harness +2.00 lbs., Magnetometer Harness -2.90 lbs. Shear Panels increased for needed thermal conductivity. Upper and Lower Hats and Upper and Lower Solar Arrays were returned to their values of August 1978.

61-12362-1178

STANLEY L. GILMAN

61-12362-1178

ITEM	ITEM	PROPOSAL PRICE	CURRENT PRICE	CURRENT ESTIMATED ACT WT	QTY	ISSUED NO	SOURCE
101-001	STRUCTURE-A- UPPER HP	134.00	765.00	77.828	1	2284655-501	
101-002	LOWER HP	0.0	0.0	184.175	1		AE-C
101-003	COVER COL	0.0	0.0	23.400	1		
101-004	COVER COL	0.0	0.0	22.800	1		
101-005	COVER COL	0.0	0.0	24.720	1		
101-006	COVER COL	0.0	0.0	9.200	1		
101-007	COVER COL	0.0	0.0	5.420	1		
101-008	COVER COL	0.0	0.0	3.420	1		
101-009	COVER COL	0.0	0.0	3.420	1		
101-010	COVER COL	0.0	0.0	15.300	1		
101-011	COVER COL	0.0	0.0	16.300	1		
101-012	COVER COL	0.0	0.0	24.050	1		
101-013	COVER COL	0.0	0.0	15.700	1		
101-014	COVER COL	0.0	0.0	4.350	1		
101-015	COVER COL	0.0	0.0	16.000	1		
101-016	COVER COL	0.0	0.0	4.500	1		
101-017	COVER COL	0.0	0.0	2.500	1		
101-018	COVER COL	0.0	0.0	1.000	1		
101-019	COVER COL	0.0	0.0	1.000	1		
101-020	COVER COL	0.0	0.0	1.000	1		
101-021	COVER COL	0.0	0.0	1.000	1		
101-022	COVER COL	0.0	0.0	1.000	1		
101-023	COVER COL	0.0	0.0	1.000	1		
101-024	COVER COL	0.0	0.0	1.000	1		
101-025	COVER COL	0.0	0.0	1.000	1		
101-026	COVER COL	0.0	0.0	1.000	1		
101-027	COVER COL	0.0	0.0	1.000	1		
101-028	COVER COL	0.0	0.0	1.000	1		
101-029	COVER COL	0.0	0.0	1.000	1		
101-030	COVER COL	0.0	0.0	1.000	1		
101-031	COVER COL	0.0	0.0	1.000	1		
101-032	COVER COL	0.0	0.0	1.000	1		
101-033	COVER COL	0.0	0.0	1.000	1		
101-034	COVER COL	0.0	0.0	1.000	1		
101-035	COVER COL	0.0	0.0	1.000	1		
101-036	COVER COL	0.0	0.0	1.000	1		
101-037	COVER COL	0.0	0.0	1.000	1		
101-038	COVER COL	0.0	0.0	1.000	1		
101-039	COVER COL	0.0	0.0	1.000	1		
101-040	COVER COL	0.0	0.0	1.000	1		
101-041	COVER COL	0.0	0.0	1.000	1		
101-042	COVER COL	0.0	0.0	1.000	1		
101-043	COVER COL	0.0	0.0	1.000	1		
101-044	COVER COL	0.0	0.0	1.000	1		
101-045	COVER COL	0.0	0.0	1.000	1		
101-046	COVER COL	0.0	0.0	1.000	1		
101-047	COVER COL	0.0	0.0	1.000	1		
101-048	COVER COL	0.0	0.0	1.000	1		
101-049	COVER COL	0.0	0.0	1.000	1		
101-050	COVER COL	0.0	0.0	1.000	1		
101-051	COVER COL	0.0	0.0	1.000	1		
101-052	COVER COL	0.0	0.0	1.000	1		
101-053	COVER COL	0.0	0.0	1.000	1		
101-054	COVER COL	0.0	0.0	1.000	1		
101-055	COVER COL	0.0	0.0	1.000	1		
101-056	COVER COL	0.0	0.0	1.000	1		
101-057	COVER COL	0.0	0.0	1.000	1		
101-058	COVER COL	0.0	0.0	1.000	1		
101-059	COVER COL	0.0	0.0	1.000	1		
101-060	COVER COL	0.0	0.0	1.000	1		
101-061	COVER COL	0.0	0.0	1.000	1		
101-062	COVER COL	0.0	0.0	1.000	1		
101-063	COVER COL	0.0	0.0	1.000	1		
101-064	COVER COL	0.0	0.0	1.000	1		
101-065	COVER COL	0.0	0.0	1.000	1		
101-066	COVER COL	0.0	0.0	1.000	1		
101-067	COVER COL	0.0	0.0	1.000	1		
101-068	COVER COL	0.0	0.0	1.000	1		
101-069	COVER COL	0.0	0.0	1.000	1		
101-070	COVER COL	0.0	0.0	1.000	1		
101-071	COVER COL	0.0	0.0	1.000	1		
101-072	COVER COL	0.0	0.0	1.000	1		
101-073	COVER COL	0.0	0.0	1.000	1		
101-074	COVER COL	0.0	0.0	1.000	1		
101-075	COVER COL	0.0	0.0	1.000	1		
101-076	COVER COL	0.0	0.0	1.000	1		
101-077	COVER COL	0.0	0.0	1.000	1		
101-078	COVER COL	0.0	0.0	1.000	1		
101-079	COVER COL	0.0	0.0	1.000	1		
101-080	COVER COL	0.0	0.0	1.000	1		
101-081	COVER COL	0.0	0.0	1.000	1		
101-082	COVER COL	0.0	0.0	1.000	1		
101-083	COVER COL	0.0	0.0	1.000	1		
101-084	COVER COL	0.0	0.0	1.000	1		
101-085	COVER COL	0.0	0.0	1.000	1		
101-086	COVER COL	0.0	0.0	1.000	1		
101-087	COVER COL	0.0	0.0	1.000	1		
101-088	COVER COL	0.0	0.0	1.000	1		
101-089	COVER COL	0.0	0.0	1.000	1		
101-090	COVER COL	0.0	0.0	1.000	1		
101-091	COVER COL	0.0	0.0	1.000	1		
101-092	COVER COL	0.0	0.0	1.000	1		
101-093	COVER COL	0.0	0.0	1.000	1		
101-094	COVER COL	0.0	0.0	1.000	1		
101-095	COVER COL	0.0	0.0	1.000	1		
101-096	COVER COL	0.0	0.0	1.000	1		
101-097	COVER COL	0.0	0.0	1.000	1		
101-098	COVER COL	0.0	0.0	1.000	1		
101-099	COVER COL	0.0	0.0	1.000	1		
101-100	COVER COL	0.0	0.0	1.000	1		
101-101	COVER COL	0.0	0.0	1.000	1		
101-102	COVER COL	0.0	0.0	1.000	1		
101-103	COVER COL	0.0	0.0	1.000	1		
101-104	COVER COL	0.0	0.0	1.000	1		
101-105	COVER COL	0.0	0.0	1.000	1		
101-106	COVER COL	0.0	0.0	1.000	1		
101-107	COVER COL	0.0	0.0	1.000	1		
101-108	COVER COL	0.0	0.0	1.000	1		
101-109	COVER COL	0.0	0.0	1.000	1		
101-110	COVER COL	0.0	0.0	1.000	1		
101-111	COVER COL	0.0	0.0	1.000	1		
101-112	COVER COL	0.0	0.0	1.000	1		
101-113	COVER COL	0.0	0.0	1.000	1		
101-114	COVER COL	0.0	0.0	1.000	1		
101-115	COVER COL	0.0	0.0	1.000	1		
101-116	COVER COL	0.0	0.0	1.000	1		
101-117	COVER COL	0.0	0.0	1.000	1		
101-118	COVER COL	0.0	0.0	1.000	1		
101-119	COVER COL	0.0	0.0	1.000	1		
101-120	COVER COL	0.0	0.0	1.000	1		
101-121	COVER COL	0.0	0.0	1.000	1		
101-122	COVER COL	0.0	0.0	1.000	1		
101-123	COVER COL	0.0	0.0	1.000	1		
101-124	COVER COL	0.0	0.0	1.000	1		
101-125	COVER COL	0.0	0.0	1.000	1		
101-126	COVER COL	0.0	0.0	1.000	1		
101-127	COVER COL	0.0	0.0	1.000	1		
101-128	COVER COL	0.0	0.0	1.000	1		
101-129	COVER COL	0.0	0.0	1.000	1		
101-130	COVER COL	0.0	0.0	1.000	1		
101-131	COVER COL	0.0	0.0	1.000	1		
101-132	COVER COL	0.0	0.0	1.000	1		
101-133	COVER COL	0.0	0.0	1.000	1		
101-134	COVER COL	0.0	0.0	1.000	1		
101-135	COVER COL	0.0	0.0	1.000	1		
101-136	COVER COL	0.0	0.0	1.000	1		
101-137	COVER COL	0.0	0.0	1.000	1		
101-138	COVER COL	0.0	0.0	1.000	1		
101-139	COVER COL	0.0	0.0	1.000	1		
101-140	COVER COL	0.0	0.0	1.000	1		
101-141	COVER COL	0.0	0.0	1.000	1		
101-142	COVER COL	0.0	0.0	1.000	1		
101-143	COVER COL	0.0	0.0	1.000	1		
101-144	COVER COL	0.0	0.0	1.000	1		
101-145	COVER COL	0.0	0.0	1.000	1		
101-146	COVER COL	0.0	0.0	1.000	1		
101-147	COVER COL	0.0	0.0	1.000	1		
101-148	COVER COL	0.0	0.0	1.000	1		
101-149	COVER COL	0.0	0.0	1.000	1		
101-150	COVER COL	0.0	0.0	1.000	1		
101-151	COVER COL	0.0	0.0	1.000	1		
101-152	COVER COL	0.0	0.0	1.000	1		
101-153	COVER COL	0.0	0.0	1.000	1		
101-154	COVER COL	0.0	0.0	1.000	1		
101-155	COVER COL	0.0	0.0	1.000	1		
101-156	COVER COL	0.0	0.0	1.000	1		
101-157	COVER COL	0.0	0.0	1.000	1		
101-158	COVER COL	0.0	0.0	1.000	1		
101-159	COVER COL	0.0	0.0	1.000	1		
101-160	COVER COL	0.0	0.0	1.000	1		
101-161	COVER COL	0.0	0.0	1.000	1		
101-162	COVER COL	0.0	0.0	1.000	1		
101-163	COVER COL	0.0	0.0	1.000	1		
101-164	COVER COL	0.0	0.0	1.000	1		
101-165	COVER COL	0.0	0.0	1.000	1		
101-166	COVER COL	0.0	0.0	1.000	1		
101-167	COVER COL	0.0	0.0	1.000	1		
101-168	COVER COL	0.0	0.0	1.000	1		
101-169	COVER COL	0.0	0.0	1.000	1		
101-170	COVER COL	0.0	0.0	1.000	1		
101-171	COVER COL	0.0	0.0	1.000	1		
101-172	COVER COL	0.0	0.0	1.000	1		
101-173	COVER COL	0.0	0.0	1.000	1		
101-174	COVER COL	0.0	0.0	1.000	1		
101-175	COVER COL	0.0	0.0	1.000	1		
101-176	COVER COL	0.0	0.0	1.000	1		
101-177	COVER COL	0.0	0.0	1.000	1		
101-178	COVER COL	0.0	0.0	1.000	1		
101-179	COVER COL	0.0	0.0	1.000	1		
101-180	COVER COL	0.0	0.0	1.000	1		
101-181	COVER COL	0.0	0.0	1.000	1		
101-182	COVER COL	0.0	0.0	1.000	1		
101-183	COVER COL	0.0	0.0	1.000	1		
101-184	COVER COL	0.0	0.0	1.000	1		
101-185	COVER COL	0.0	0.0	1.000	1		
101-186	COVER COL	0.0	0.0	1.000	1		
101-187	COVER COL	0.0	0.0	1.000	1		
101-188	COVER COL	0.0	0.0	1.000	1		
101-189	COVER COL	0.0	0.0	1.000	1		
101-190	COVER COL	0.0	0.0	1.000	1		
101-191	COVER COL	0.0	0.0	1.000	1		
101-192	COVER COL	0.0	0.0	1.000	1		
101-193	COVER COL	0.0	0.0	1.000	1		
101-194	COVER COL	0.0	0.0	1.000	1		
101-195	COVER COL	0.0	0.0	1.000	1		

1091500	SAT	0.0	34.00	34.00	1.	2295121-2
1091501	VTS SENSOR	0.0	0.0	22.67	2.	2295121-1
1091502	VTS COVER	0.0	0.0	11.13	1.	
1091503	VTS COVER	0.0	0.0	1.00	4.	
1091504	VTS COVER	0.0	0.0	2.00	1.	
1091505	VTS	0.0	0.0	1.00	1.	
1091506	MP1	0.0	22.00	22.00	1.	2295120-1
1091507	ELECTRONICS	0.0	0.0	9.00	1.	
1091508	ELECTRONICS	0.0	0.0	7.00	1.	
1091509	VPS	0.0	0.0	1.00	1.	
1091510	PS	0.0	0.0	3.00	1.	
1091511	PS	0.0	0.0	1.00	1.	
1091512	CARLING	0.0	0.0	0.50	1.	
1091513	RING	0.0	14.50	28.50	1.	
1091514	ELECTRONICS	0.0	0.0	6.00	1.	2295124-1
1091515	SENSOR	0.0	0.0	22.50	3.	2295123-2
1091516	FL	0.0	18.40	18.40	1.	2295121-1
1091517	TOOLING	0.0	0.0	16.00	1.	
1091518	YOUNG ANTENNA	0.0	0.0	6.90	2.	
1091519	DISPOSABLE	0.0	0.0	15.44	2.	
1091520	WALL MISC	0.0	5.50	11.00	1.	
1091521	INSTRUMENT	0.0	0.0	9.20	2.	
1091522	OUTSIDE AIR	0.0	0.0	0.10	2.	
1091523	WALL MISC	0.0	0.0	2.50	2.	
1091524	STANDARD	0.0	0.0	16.54	2.	
1091525	WALL MISC	0.0	0.0	9.00	1.	
1091526	WALL MISC	0.0	0.0	2.50	1.	
1091527	WALL MISC	0.0	0.0	1.10	1.	
1091528	WALL MISC	0.0	50.00	50.00	1.	
1091529	WALL MISC	0.0	0.0	42.35	1.	
1091530	WALL MISC	0.0	0.0	7.65	1.	
1091531	SUPPLY EQUIP	0.0	45.00	34.10	1.	
1091532	WALL MISC	0.0	0.0	14.00	1.	
1091533	WALL MISC	0.0	0.0	2.32	1.	
1091534	WALL MISC	0.0	0.0	11.60	1.	
1091535	WALL MISC	0.0	0.0	14.00	1.	
1091536	WALL MISC	0.0	0.0	2.32	1.	
1091537	WALL MISC	0.0	0.0	11.60	1.	
1091538	WALL MISC	0.0	0.0	14.00	1.	
1091539	WALL MISC	0.0	0.0	2.32	1.	
1091540	WALL MISC	0.0	0.0	11.60	1.	
1091541	WALL MISC	0.0	0.0	14.00	1.	
1091542	WALL MISC	0.0	0.0	2.32	1.	
1091543	WALL MISC	0.0	0.0	11.60	1.	
1091544	WALL MISC	0.0	0.0	14.00	1.	
1091545	WALL MISC	0.0	0.0	2.32	1.	
1091546	WALL MISC	0.0	0.0	11.60	1.	
1091547	WALL MISC	0.0	0.0	14.00	1.	
1091548	WALL MISC	0.0	0.0	2.32	1.	
1091549	WALL MISC	0.0	0.0	11.60	1.	
1091550	WALL MISC	0.0	0.0	14.00	1.	

ORIGINAL PAGE IS
OF POOR QUALITY

DYNAMICS ENLARGED M-A
CONF AND CHART SUMMARY
31 OCTOBER 1978

700	PROPOSAL WEIGHT	CURRENT TARGET WEIGHT	CURRENT ESTIMATED WEIGHT	CURRENT EST/ACT WT
1	425.00	572.00	575.72	797.831
2	147.29	142.20	172.122	575.778
3	25.00	50.00	50.000	172.122
				50.000
TOTAL SYSTEM LAUNCH WEIGHT INCLUDING WT				
SPACECRAFT HARDWARE WEIGHT INCLUDING PAL		638.00	765.00	797.831
GP INSTRUMENTATION WEIGHT		149.29	172.20	575.778
TOTAL BALANCE WEIGHT		25.00	50.00	172.122
				50.000

DE PROGRAM OVERVIEW WEIGHT SUMMARY

	1977						1978					
	NOV 1	DEC 1	JAN 1	FEB 1	MAR 1	APR 1	MAY 1	JUN 1	AUG 1	SEPT 1	OCT 1	
<u>DE-A</u>												
TOTAL WEIGHT	689.7	790.0	790.0	790.0	790.0		824.0		824.0	824.0	824.0	
TOTAL HDWRE	689.7	701.6	708.9	769.1	755.0		790.9		799.5	785.4	797.8	
SPACECRAFT	515.3	515.3	519.3	519.3	549.8		617.8		625.7	613.8	625.7	
INSTRUMENTS	174.4	186.1	189.6	249.8	207.2		173.1		173.8	171.6	172.1	
MARGIN		88.6	81.1	20.9	35.0		33.1		24.5	38.6	26.2	
S/C MARGIN		49.0	45.0	45.0	16.5		36.2		28.3	40.2	28.3	
INSTR MARGIN		14.6	11.1	-24.1	18.5		-3.1		-3.8	-1.6	-2.1	
MISC MARGIN		25.0	25.0									
<u>DE-B</u>												
TOTAL WEIGHT	772.2	883.0	883.0	883.0	883.0		862.0		862.0	862.0	862.0	
TOTAL HDWRE	772.2	772.6	776.6	776.6	805.1		810.6		805.4	801.0	797.4	
SPACECRAFT	551.2	551.2	555.2	555.2	583.7		634.3		630.6	627.9	625.1	
INSTRUMENTS	221.0	221.4	221.4	221.4	221.4		176.3		174.8	173.1	172.3	
MARGIN		110.4	106.4	106.4	77.9		51.4		56.6	61.0	64.6	
S/C MARGIN		52.6	48.6	48.6	20.1		37.7		41.4	44.1	46.9	
INSTR MARGIN		32.8	32.8	32.8	32.8		13.7		15.2	16.9	17.7	
MISC MARGIN		25.0	25.0	25.0	25.0							

DYNAMICS EXPLORER

Design Note

RCAN Astro Electronics

Distribution
 C. Chatpar
 R. deBastos
 W. Fulmer
 F. Gross
 R. Horner
 C. Hume
 K. Johnson
 D. Lacerda
 S. Malyska
 J. Nassari
 P. Nekrasov
 D. Shipley
 S. Toch
 File

Originating Project or Group

DYNAMICS EXPLORER

Note No.

2.4.1-005-DN

Title

DYNAMICS EXPLORER WEIGHT REPORT DE-B

Written by:

K. R. Johnson *K.R. Johnson*

Date

1 November 1977

Approved by:

W. J. Fulmer

Date

--

This DN supplements (S), replaces (R) DN Nos.

() ()

REVISIONS

Letter	Description	Date	Author
A	Monthly Update - December 1977 Sht. 2 Annotated, Sht. 3, 4, & 5 revised	12/6/77	K. Johnson <i>KJ</i>
B	Monthly Update - January 1978 Sheet annotated, Sht. 3, 4, 5 revised	1/12/78	K. Johnson <i>KJ</i>
C	Monthly Update - February 1978 Sheet 2 annotated, Sheet 3, 4 & 5 revised, sheet 6 (summary) added	2/1/78	K. Johnson <i>KJ</i>
D	Monthly Update - March 1978 Sheet 2 annotated, Sheet 3, 4, 5, & 6, revised	3/1/78	K. Johnson <i>KJ</i>
E	Monthly Update - May 1978 Sheets 3 thru 8 revised	5/16/78	K. Johnson <i>KJ</i>
F	Monthly Update - August 1978 Sheet 3 Annotated, Sheet 4 thru 8 Revised	8/21/78	R. Crawford <i>RDC</i>
G	Monthly Update - September 1978 Sheet 3 Annotated, Sheet 4 thru 8 Revised.	9/15/78	R. Crawford <i>RDC</i>
H	Monthly Update - October 1978 Sheet 3 Annotated, Sheet 4 thru 8 Revised.	10/16/78	R. Crawford <i>RDC</i>
ORIGINAL PAGE IS OF POOR QUALITY			

The attached is an equipment configuration and weight list by functional groupings for the DE-B spacecraft as of 1 December 1977. Each major entry is marked "+" to indicate that it is a sum of the indented entries below it. Weight entries are totals for the total quantity of any given line item.

For November 1977, the margin (or allowance for growth) is shown as zero and therefore the totals represent total hardware only, not total launch weight. --

During November 1977, margins were set at 10% of the spacecraft total (52.6 lb), 15% of the instrument total (33.2 lb) and 25 lb misc. for a total margin of 110.8 lb. Thus the total launch weight, including margin is 883 lb.

For December 1977, the instrument total weight changed from 221.0 lb to 221.4 lb. Accordingly, the GFE margin was adjusted down to 32.8 lb. to maintain a constant spacecraft weight.

The January 1978 weight report includes an additional 4.0 lb. under spacecraft structure for the antenna support. No other weight changes were noted. Spacecraft margin has been adjusted to maintain the system launch weight constant at 883 lb.

No changes reported during January 1978.

During February 1978, the spacecraft weight increased by 28.5 lb. as follows: structure +9.5 lb., power +7.0 lb., communications +4.3 lb., C&DH +7.7 lb. No changes were reported for GFE instruments and support equipment.

The attached weight report for May 1978 includes all updates and the revised system baseline as of May 1.

Three columns of weight entries are given. The first, labelled "Proposal Weight" is the weight, by subsystem, at the time of the original system definition (Feb. 1977). The second column, "Target weight", is the baseline weight allocated by the NASA Delta Project Office to each subsystem or equipment and represents the authorized weight for each. Column three, "estimated/actual weight", gives the current -- estimate (made by the supplier) for each component. Thus, a comparison of columns 2 and 3 will show whether any component is over or under the weight allocated to it on an individual basis.

Summaries of estimated instrumentation and spacecraft weights are given on the last page where they are compared against the program totals and program margins. Totals have been changed as a result of revised Delta performance estimates and this has resulted in revised margins.

The May 1978 weight report now reflects a shifting of the balance weight from the margin item to the spacecraft weight category. This caused an apparent increase of 25 lbs. in the total hardware weight and a decrease of 25 lbs. in the margin weight.

The weight report for August 1978 reflects changes in; Attitude Control of - 7.5 lbs., Power + 3.81 and GFE of - 1.5 lbs. The result was an overall decrease of 5.2 lbs. to the total hardware weight.

The September weight report shows a decrease of 4.36 lbs. The changes occurred in the following areas: ATC brackets +1.34 lbs., LAPI EPD system -1.9 lbs., and magnetometer Astromast -4.00 lbs.

The weight changes for October are: Magnetometer Sensor -0.640 lbs., Magnetometer Electric -0.062 lbs., Magnetometer Harness -2.90 lbs. Total weight change amounted to -3.602 pounds. Note the Magnetometer Sensor and Magnetometer Electric weights were inadvertently changed in the wrong program in the last weight update.

DYNAMICS EXPLORER DE-R
WEIGHT SUMMARY BY LEVELS
31 OCTOBER 1978

ID	NAME	PROPOSAL WEIGHT	CURRENT TARGET WEIGHT	CURRENT ESTIMATED ACT WT	QTY	DRAWING NO	SOURCE
100000	DE-R	682.68	761.40	797.301	1.	2294700-501	
101000	STRUCTURE-H-	136.90	165.80	162.160	1.		AE-C
101010	UPPER RP	9.0	0.0	23.400	1.		
101020	LOWER RP	0.0	0.0	22.820	1.		
101030	CC% COL/SH P	0.0	0.0	23.720	1.		
1010301	CENTER COL	0.0	0.0	9.200	1.		
1010302	SHR PANT 1	0.0	0.0	2.420	1.		
1010303	SHR PANT 2	0.0	0.0	2.420	1.		
1010304	SHR PANT 3	0.0	0.0	2.420	1.		
1010305	SHR PANT 4	0.0	0.0	2.420	1.		
1010306	SHR PANT 5	0.0	0.0	2.420	1.		
1010307	SHR PANT 6	0.0	0.0	2.420	1.		
1010500	SEC ADPT CLR	0.0	0.0	15.300	1.		
1010506	HAT UPPER	0.0	0.0	20.050	1.		
1010601	SIDES HU	0.0	0.0	15.700	1.		
1010602	SHR HU	0.0	0.0	4.350	1.		
1010700	HAT LOWER	0.0	0.0	20.050	1.		
1010701	SIDES HL	0.0	0.0	15.700	1.		
1010702	SHR HL	0.0	0.0	4.350	1.		
1010800	CENTER RING	0.0	0.0	16.000	1.		
1010801	WPS	0.0	0.0	4.500	1.		
1010802	BRACKETS	0.0	0.0	9.500	1.		
1010900	MAX SUPT CO	0.0	0.0	3.400	1.		
1011000	HARDWARE	0.0	0.0	1.000	1.		
1011100	BRKTS+SIGC	0.0	0.0	2.500	1.		
1011200	COVERS+SEALS	0.0	0.0	4.200	1.		
1011300	LIFTING HGR	0.0	0.0	1.200	1.		
1011400	RF SCREENS	0.0	0.0	1.200	1.		
1011500	WIRE BOX	0.0	0.0	2.000	1.		
1011600	ANTENNA SUPT	0.0	0.0	4.000	1.		
1011601	SHR GN RPD	0.0	0.0	1.500	1.		
1011602	HL GN BRCTV	0.0	0.0	2.500	1.		
1011700	ATC BRACKETS	0.0	0.0	1.340	4.		
1020000	THERMAL -R-	10.40	10.50	10.400	1.		
1020100	THR-UPR HAT	0.0	0.0	0.150	1.		
1020101	THR-UPR HAT	0.0	0.0	3.750	1.		
1020102	ATC-UPR HAT	0.0	0.0	2.400	4.	2271611-501	
1020300	THR-UPR R/P	0.0	0.0	0.240	1.		
1020301	TEMP SEQS-UP	0.0	0.0	0.240	1.		
1020400	THR-LAR R/P	0.0	0.0	3.950	1.		
1020401	TEMP SEQS-LB	0.0	0.0	0.240	1.		
1020402	THR-LAR R/P	0.0	0.0	3.750	1.		
1020500	TH PLATERS	0.0	0.0	0.100	1.		
1030000	ATT CONTR B	99.70	100.10	92.600	1.		
1030200	PITCH COU	0.0	0.0	8.400	1.	2271623-501	
1030300	SUN S-LSOR	0.0	0.0	3.800	1.		
1030301	DETECTORS	0.0	0.0	1.600	2.		
1030302	ELECTRONICS	0.0	0.0	2.200	2.		
1030400	NUL DPR+COIL	0.0	0.0	28.400	1.		

ORIGINAL PAGE IS
OF POOR QUALITY

103401	OUT JAMPER	0.0	0.0	16.400	1.
103402	ATT COIL	0.0	0.0	12.000	2.
103504	WITCH COIL	0.0	0.0	3.000	1.
103700	400 MHL ASSY	0.0	0.0	44.600	1.
103701	400 MHL ASSY	0.0	0.0	22.300	1.
103702	INERTIA COIL	0.0	0.0	22.300	1.
103800	400 MHL SENS	0.0	0.0	2.000	1.
103900	400 MHL SHIELD	0.0	0.0	2.400	1.
104000	POWER	127.10	127.10	136.515	1.
104100	UPPER SOL AS	0.0	0.0	25.860	1.
104101	CELL MODULES	0.0	0.0	26.090	1.
104102	SMALL CIRCUIT	0.0	0.0	2.450	1.
104103	MODULES	0.0	0.0	0.820	1.
104201	LOWER SOL AS	0.0	0.0	35.050	1.
104202	CELL MODULES	0.0	0.0	35.620	1.
104203	COIL WIRING	0.0	0.0	3.350	1.
104204	POWER	0.0	0.0	1.060	1.
104301	WATT 1	0.0	0.0	43.430	1.
104302	WATT 2	0.0	0.0	21.700	1.
104400	POWER	0.0	0.0	21.700	1.
104500	CONDUCTIVITY	24.36	24.36	22.460	1.
104501	TERMS / DOR	0.0	0.0	33.220	1.
104502	GROUP CABLE	0.0	0.0	15.060	1.
104503	LOW GAIN ANT	0.0	0.0	2.100	1.
104504	W. GAIN ANT	0.0	0.0	1.400	1.
104505	SHIELD MESH	0.0	0.0	7.100	1.
104506	SHIELD MESH	0.0	0.0	2.100	1.
104507	SHIELD MESH	0.0	0.0	4.400	1.
104508	SHIELD MESH	53.10	53.10	62.300	1.
104509	SHIELD MESH	0.0	0.0	0.0	1.
104510	SHIELD MESH	0.0	0.0	10.800	1.
104511	SHIELD MESH	0.0	0.0	3.400	1.
104512	SHIELD MESH	0.0	0.0	34.660	1.
104513	SVC HARNESS	64.70	64.70	64.700	1.
104514	UPPER WASH	0.0	0.0	21.500	1.
104515	LOWER WASH	0.0	0.0	21.500	1.
104516	GROUND BLOCK	0.0	0.0	0.400	1.
104517	GROUND BLOCK	0.0	0.0	0.300	1.
104518	SHIELD MESH	0.0	0.0	1.000	1.
104519	CLAVES	0.0	0.0	1.000	1.
104520	WATT	0.0	0.0	5.500	1.
104521	POWER CIRCUIT	0.0	0.0	1.500	1.
104522	SHIELD MESH	150.02	150.02	172.340	1.
104523	SHIELD MESH	0.0	0.0	16.716	1.
104524	PREHIPS	0.0	0.0	1.300	1.
104525	ELECTRONICS	0.0	0.0	6.600	1.
104526	SHIELD MESH	0.0	0.0	38.460	1.
104527	SHIELD MESH	0.0	0.0	8.140	1.
104528	SHIELD MESH	0.0	0.0	1.010	1.
104529	SHIELD MESH	0.0	0.0	6.530	1.
104530	SHIELD MESH	0.0	0.0	0.0	1.
104531	SHIELD MESH	0.0	0.0	7.500	1.
104532	SHIELD MESH	0.0	0.0	4.070	1.
104533	SHIELD MESH	0.0	0.0	3.430	1.
104534	SHIELD MESH	0.0	0.0	36.000	1.
104535	SHIELD MESH	0.0	0.0	9.300	1.
104536	SHIELD MESH	0.0	0.0	2.300	1.
104537	SHIELD MESH	0.0	0.0	0.800	1.
104538	SHIELD MESH	0.0	0.0	6.500	1.

109407	CABLEING	0.0	0.0	1.500	1.0
109408	PPS	0.0	0.0	4.000	2.0
109409	EXPS	0.0	0.0	2.400	2.0
109410	END SYST	0.0	0.0	0.500	1.0
109411	CEP	0.0	0.0	6.000	1.0
109412	EX ELECTR	0.0	0.0	1.600	1.0
109413	TUG HEART	0.0	0.0	0.200	1.0
109414	MAG SENSOR	0.0	0.0	0.750	1.0
109415	MAG DEPLOYER	0.0	0.0	0.750	1.0
109500	WCS	0.0	+	17.000	1.0
109501	ELECTRONICS	0.0	0.0	6.000	1.0
109502	INSTRUMENT	0.0	0.0	10.100	1.0
109503	C VER	0.0	0.0	0.890	1.0
109504	FPI	0.0	+	19.000	1.0
109505	ELECTRONICS	0.0	0.0	5.800	1.0
109506	INSTRUMENT	0.0	0.0	12.625	1.0
109507	CABLEING	0.0	0.0	0.200	1.0
109508	C VER	0.0	0.0	0.275	1.0
109509	WCS	0.0	+	17.000	1.0
109510	ELECTRONICS	0.0	0.0	8.000	1.0
109511	SAMPLER	0.0	0.0	2.100	1.0
109512	COVER	0.0	0.0	1.600	1.0
109513	LATCH	0.0	+	6.000	1.0
109514	SIG PROC	0.0	0.0	3.900	1.0
109515	FILTER BOX	0.0	0.0	1.000	2.0
109516	LATCH	0.0	0.0	0.400	2.0
109517	WCS	0.0	0.0	0.500	2.0
109518	CABLEING	0.0	0.0	5.200	1.0
109519	WCS	0.0	+	8.600	1.0
109520	ELECTRONICS	0.0	0.0	4.800	1.0
109521	CORRO	0.0	0.0	3.800	1.0
109522	BALANCE -B-	0.0	+	25.000	1.0
109523	SIG BALANCE	0.0	0.0	20.810	1.0
109524	WCS	0.0	0.0	4.150	1.0
109525	SUPPLY EQUIP	22.50	+	50.60	1.0
109526	WCS	22.50	+	14.000	1.0
109527	ASTROCAST	0.0	0.0	2.325	1.0
109528	ASTRO MONR	0.0	0.0	11.677	1.0
109529	HARDWARE MAG	0.0	0.0	1.600	1.0
109530	SIG PLATE	0.0	+	28.100	1.0
109531	WCS	0.0	0.0	0.400	1.0
109532	WCS	0.0	0.0	9.400	1.0
109533	WCS	0.0	0.0	3.500	1.0
109534	WCS	0.0	0.0	5.800	1.0
109535	WCS	0.0	+	2.0	1.0

DYNAMICS EXPLORER DE-B
 ZONE AND PHASE SUMMARY
 21 OCTOBER 1978

ZONE	PROPOSAL HEIGHT	CURRENT TARGET HEIGHT	CURRENT ESTIMATED HEIGHT
------	--------------------	-----------------------------	--------------------------------

1	531.76	614.30	650.346
2	150.92	122.10	172.348
3	0.0	25.00	25.000

PHASE	PROPOSAL WT	CURRENT TARGET WT	CURRENT EST/ACT WT
-------	-------------	----------------------	-----------------------

TOTAL SYSTEM LAUNCH WEIGHT INCL BAL WT	612.68	761.40	797.394
SPACECRAFT HARDWARE WEIGHT INCL BAL	531.76	614.30	650.346
GFT INSTRUMENTATION WEIGHT	150.92	122.10	172.348
TOTAL BALANCE WEIGHT	0.0	25.00	25.000

ORIGINAL PAGE IS
 OF POOR QUALITY

DE PROGRAM OVERVIEW WEIGHT SUMMARY

	1977					1978				
	NOV 1	DEC 1	JAN 1	FEB 1	MAR 1	APR 1	MAY 1	AUG 1	SEPT 1	OCT 1
<u>DE-A</u>										
TOTAL WEIGHT	689.7	790.0	790.0	790.0	790.0		824.0	824.0	824.0	824.0
TOTAL HDWRE	689.7	701.6	708.9	769.1	755.0		790.9	799.5	785.4	797.8
SPACECRAFT	515.3	515.3	519.3	519.3	547.8		617.8	625.7	613.8	625.7
INSTRUMENTS	174.4	186.1	189.6	249.8	207.2		173.1	173.8	171.6	172.1
MARGIN		88.6	81.1	20.9	35.0		33.1	24.5	38.6	26.2
S/C MARGIN		49.0	45.0	45.0	16.5		36.2	28.3	40.2	28.3
INSTR MARGIN		14.6	11.1	-24.1	18.5		-3.1	-3.8	-1.6	-2.1
MISC MARGIN		25.0	25.0							
						REPORT 2				
<u>DE-B</u>										
TOTAL WEIGHT	772.2	883.0	883.0	883.0	883.0		862.0	862.0	862.0	862.0
TOTAL HDWRE	772.2	772.6	776.6	776.6	805.1		810.6	805.4	801.0	797.4
SPACECRAFT	551.2	551.2	555.2	555.2	583.7		634.3	630.6	627.9	625.1
INSTRUMENTS	221.0	221.4	221.4	221.4	221.4		176.3	174.8	173.1	172.3
MARGIN		110.4	106.4	106.4	77.9		51.4	56.6	61.0	64.6
S/C MARGIN		52.6	48.6	48.6	20.1		37.7	41.4	44.1	46.9
INSTR MARGIN		32.8	32.8	32.8	32.8		13.7	15.2	16.9	17.7
MISC MARGIN		25.0	25.0	25.0	25.0					
						REPORT 2				

RCA Astro Electronics Division

REVISIONS

Letter	Description	Date	Author

1. Scope

This design note describes the "Spacecraft Configuration Reporting System" which is a computer program used to build and display a record of the physical characteristics of a spacecraft system. A Weight Report and Moment of Inertia Report are provided for the stowed and deployed configurations. Sketches of the configurations upon which the report was based are included as figures 1 thru 8 with their respective weights, inertias and inertia ratios.

2. Analytical Approach, Program Description

2.1 Weight Report

The Weight Report consists of three segments. First a weight summary is produced which lists the identification number, date the item was input, name, drawing number, source, zone, proposal weight, target weight, estimated or actual weight, percentage weight tolerance, weight tolerance, and quantity. This listing is primarily a display of the values input. The proposal weight is an initial estimated weight. The target is the desired weight for the component and is the current contact baseline weight. The estimated or actual weight is the current estimate of a component's weight or an actual value determined by weighing the component. The percentage weight tolerance is the allowable variation of the estimated or actual weight. The weight tolerance is this percentage of the estimated or actual weight.

The second segment of the Weight Report is an indented summary. The weights are summed to each level and printed in an indented list. That is, all level four components are summed to level three so that a box level printout would reflect the total of all components included. Similarly, level three is summed to level two which in turn is totaled to the highest level. The names appear indented to indicate the level.

2.2 Inertia Report

The final section of the program is a moment of inertia routine. The inertia of each component may be calculated or input. This provides an inertia in the component's frame of reference. If the component is not in the system reference frame (parallel to the system reference axis), the angles must be input through which the component will be rotated. With the distance to the system reference specified, the center of gravity of the system is located. Finally, the system can be dynamically balanced by indicating the position of the balance weights. For most geometric shapes, inertia calculations can be done in the program. For those with odd shapes, hand calculations must be made and the inertias input.

The program prints a list of all the inertia related input. The weight for each component is obtained from the weight data base established in Section 2.1 of the program. This is followed by a list of the inertias of each component in its reference frame.

3. Results of Analysis

3.1 Stowed Configuration

3.1.1 DE-A

The Inertia Report is based on Figures 1, 2, 3, and 4. The center of gravity of the stowed configuration is located at booster station 549.45 after balance weights have been added. The following data was taken from Appendix A.

The Inertias before balancing are:

$$I = \begin{bmatrix} 260744.81 & -1726.22 & -2288.39 \\ -1726.22 & 274844.06 & -2770.29 \\ -2288.39 & -2770.29 & 294752.31 \end{bmatrix} \text{ lbs. -in}^2$$

The ratio of spin axis inertia to maximum transverse inertia is 1.072.

Total balance weight required 26.8754 lbs.* computed on the basis of static and dynamic balance requirements.

Inertia matrix after balancing is:

$$I = \begin{bmatrix} 270639.12 & -1767.08 & 0.0 \\ -1767.08 & 288072.75 & 0.0 \\ 0.0 & 0.0 & 305667.94 \end{bmatrix} \text{ lbs. -in}^2$$

$$\text{or } I = \begin{bmatrix} 701.06 & -4.58 & 0.0 \\ -4.58 & 746.22 & 0.0 \\ 0.0 & 0.0 & 791.80 \end{bmatrix} \text{ in-lbs.-sec}^2$$

The inertia ratio of the maximum transverse inertia to the spin axis inertia is 1.060. (See Appendix A, after balancing)

3.1.2 DE-B

The B Inertia Report is based on Figures 1, 5, and 6. The center of gravity after balancing is located at booster station 491.75. The following data may be found in Appendix C.

Before balancing the inertias are:

$$I = \begin{bmatrix} 276181.37 & 579.51 & 1038.84 \\ 579.51 & 275851.0 & 5776.33 \\ 1038.84 & 5776.33 & 282365.56 \end{bmatrix}$$

The inertia ratio is 1.021

*Note: Balance weight will be reduced by base plate layout alterations.

Total balance weight required 13.63 lbs.* and is computed based on static balance requirements.

Inertia matrix after balancing is:

$$I = \begin{bmatrix} & & \\ & \text{TBS} & \\ & & \end{bmatrix}$$

$$I = \begin{bmatrix} & & \\ & & \\ & & \end{bmatrix}$$

The inertia ratio is equal to

3.1.3 Stacked - Stowed Configuration

Figure 1 shows the stacked configuration of DE-A and DE-B. The center of gravity is at booster station 520.485.

The stacked-stowed inertias about the center of gravity are:

$$\begin{aligned} I_{xx} &= 1.8718 \times 10^6 \text{ lbs.-in}^2 \\ I_{yy} &= 1.9034 \times 10^6 \text{ lbs.-in}^2 \\ I_{zz} &= 5.6833 \times 10^5 \text{ lbs.-in}^2 \end{aligned}$$

The above values were derived using data contained in Appendices A and C.

3.2 Deployed Configurations

3.2.1 DE-A

The Inertia Report for the deployed configuration of DE-A was based on Figures 2, 3, 4, and 7. The following data was taken from Appendix B.

$$I = \begin{bmatrix} 1918599.0 & -264734.25 & -1711.18 \\ 264734.25 & 1437994.0 & -4896.06 \\ -1711.18 & -4896.06 & 3083282.0 \end{bmatrix} \text{ lbs. in}^2$$

The inertia ratio is 1.515

3.2.2 DE-B

Figures 5, 6, and 8 were used when making the Inertia Report. The following data may also be found in Appendix D.

$$I = \begin{bmatrix} & & \\ & & \\ & & \end{bmatrix} \text{ lbs. -in}^2$$

With an inertia ratio of 0.983.

*Note: Balance weight will be reduced by base plate layout alterations.

4. Interpretation of Results

The weight data base after initially being created is periodically and systematically updated to show changes in the weight of the spacecraft. This weight data base, in addition to being a weight accounting system, is used as an input for inertia calculations.

The base plate configurations contained in this report, Figures 2, 3, 4, 5, and 6, are preliminary and will be modified to reduce the balance weight required. As more detailed information on box configurations and centers of gravity are made available, the inertia file will be updated.

The Inertia Report consists of five sections. Section one is a listing of components: locations, denoted by XBAR, YBAR, ZBAR, dimensions, LX, LY and LZ or inertias, Ixx, Iyy, and Izz; inner and outer radius if applicable and the weights. Section two is a listing by components of their respective inertias. Section three gives the information contained in Section two as well as the products of inertias resulting from a rotation of axes. Section four lists inertias of components relative to the spacecraft reference axes. Section five can appear in two forms; no balancing done on spacecraft and with balancing calculations. In either case, an output of the summation of component weights times their respective radii of gyration is printed. These values do not account for the components own local inertia (inertia about its own c.g.). If balancing is to be done, the balance weight position is input and the balance weight required at this location is calculated. In both cases the inertia matrix is calculated in two sets of units. The center of gravity is also calculated.

FIGURES






FIG. 1 STACKED-STOWED CONFIGURATION




F14.2





ORIGINAL PAGE IS
OF POOR QUALITY



ORIGINAL PAGE IS
OF POOR QUALITY







G

F

E

D

C

B

A





FIG. 7



ORIGINAL PAGE IS
POOR QUALITY

2297145

CONTRACT NO.	NA5-5-25020	DATE	6-1-70
DESIGNER	J.A. MASIARI	DATE	6-1-70
CHECKER		DATE	
ORBITAL CONFIGURATION		DE-A	
E 49671		22971	
SCALE 1/10			





FIG. 8



VEFI TEE (11m)
4 @ 45°, 6 TOTAL

FOLDOUT FRAME

ORIGINAL PAGE IS
OF POOR QUALITY

VEFI
TEE

CONTRACT NO. NAS-5-25022		DATE JAN 1964	
BY J. A. MASSAR, C. 7A		DATE JAN 1964	
BY K. B. [Signature]		DATE JAN 1964	
SCALE 1/10		SHEET 1 OF 2	
RCA ASTRO ELECTRONICS, PRINCETON, N.J.		ORBITAL CONFIGURATION DE-B	
E 49671		2297144	

2297144

APPENDIX A
DE-A STOWED MASS PROPERTIES
COMPUTER OUTPUT

DYNAMICS EXPLORER DE-A
SPACECRAFT CONFIGURATION
01 OCTOBER 1974 STOP

ORIGINAL PAGE IS
OF POOR QUALITY

DYNAMICS EXPLORER DE-A
FLIGHT SUMMARY BY LEVELS
1-2610013 1974

1	NAME	PROPOSAL WEIGHT	CURRENT TARGET WEIGHT	CURRENT ESTIMATED ACT WT	QTY	DRUNG NO	SOURCE
1000000	DE-L	432.49	765.00	791.82	1	2304686-551	
1010000	STRUCTURE-A-	134.70	180.20	174.176	1		AL-C
1010100	UPR	6.0	6.0	23.40	1		
1010200	UPR	6.0	6.0	22.863	1		
1010300	UPR	6.0	6.0	23.70	1		
1010400	UPR	6.0	6.0	9.202	1		
1010500	UPR	6.0	6.0	2.42	1		
1010600	UPR	6.0	6.0	1.42	1		
1010700	UPR	6.0	6.0	2.42	1		
1010800	UPR	6.0	6.0	3.42	1		
1010900	UPR	6.0	6.0	2.42	1		
1011000	UPR	6.0	6.0	2.42	1		
1011100	UPR	6.0	6.0	15.366	1		
1011200	UPR	6.0	6.0	16.20	1		
1011300	UPR	6.0	6.0	20.859	1		
1011400	UPR	6.0	6.0	1.788	1		
1011500	UPR	6.0	6.0	4.35	1		
1011600	UPR	6.0	6.0	14.000	1		
1011700	UPR	6.0	6.0	4.500	1		
1011800	UPR	6.0	6.0	9.500	1		
1011900	UPR	6.0	6.0	1.000	1		
1012000	UPR	6.0	6.0	2.500	1		
1012100	UPR	6.0	6.0	4.200	1		
1012200	UPR	6.0	6.0	6.700	1		
1012300	UPR	6.0	6.0	2.13	1		
1012400	UPR	6.0	6.0	1.06	6		
1012500	UPR	6.0	6.0	1.06	6		
1012600	UPR	6.0	6.0	2.00	1		
1012700	UPR	6.0	6.0	4.000	1		
1012800	UPR	6.0	6.0	1.50	1		
1012900	UPR	6.0	6.0	1.50	1		
1013000	UPR	6.0	6.0	1.00	1		
1013100	UPR	6.0	6.0	2.91	6		
1013200	UPR	6.0	6.0	2.01	1		
1020000	TEMP-LR-A-	12.60	12.10	12.07	1		
1020100	TEMP-LR-A-	6.0	6.0	5.74	1		
1020200	TEMP-LR-A-	6.0	6.0	1.998	6		
1020300	TEMP-LR-A-	6.0	6.0	5.74	1		
1020400	TEMP-LR-A-	6.0	6.0	3.75	1		
1020500	TEMP-LR-A-	6.0	6.0	1.099	6		
1020600	TEMP-LR-A-	6.0	6.0	0.242	1		
1020700	TEMP-LR-A-	6.0	6.0	0.242	1		
1020800	TEMP-LR-A-	6.0	6.0	0.242	1		
1020900	TEMP-LR-A-	6.0	6.0	0.242	1		
1021000	TEMP-LR-A-	6.0	6.0	0.242	1		
1021100	TEMP-LR-A-	6.0	6.0	0.242	1		
1021200	TEMP-LR-A-	6.0	6.0	0.242	1		
1021300	TEMP-LR-A-	6.0	6.0	0.242	1		
1021400	TEMP-LR-A-	6.0	6.0	0.242	1		
1021500	TEMP-LR-A-	6.0	6.0	0.242	1		
1021600	TEMP-LR-A-	6.0	6.0	0.242	1		
1021700	TEMP-LR-A-	6.0	6.0	0.242	1		
1021800	TEMP-LR-A-	6.0	6.0	0.242	1		
1021900	TEMP-LR-A-	6.0	6.0	0.242	1		
1022000	TEMP-LR-A-	6.0	6.0	0.242	1		
1022100	TEMP-LR-A-	6.0	6.0	0.242	1		
1022200	TEMP-LR-A-	6.0	6.0	0.242	1		
1022300	TEMP-LR-A-	6.0	6.0	0.242	1		
1022400	TEMP-LR-A-	6.0	6.0	0.242	1		
1022500	TEMP-LR-A-	6.0	6.0	0.242	1		
1022600	TEMP-LR-A-	6.0	6.0	0.242	1		
1022700	TEMP-LR-A-	6.0	6.0	0.242	1		
1022800	TEMP-LR-A-	6.0	6.0	0.242	1		
1022900	TEMP-LR-A-	6.0	6.0	0.242	1		
1023000	TEMP-LR-A-	6.0	6.0	0.242	1		
1023100	TEMP-LR-A-	6.0	6.0	0.242	1		
1023200	TEMP-LR-A-	6.0	6.0	0.242	1		
1023300	TEMP-LR-A-	6.0	6.0	0.242	1		
1023400	TEMP-LR-A-	6.0	6.0	0.242	1		
1023500	TEMP-LR-A-	6.0	6.0	0.242	1		
1023600	TEMP-LR-A-	6.0	6.0	0.242	1		
1023700	TEMP-LR-A-	6.0	6.0	0.242	1		
1023800	TEMP-LR-A-	6.0	6.0	0.242	1		
1023900	TEMP-LR-A-	6.0	6.0	0.242	1		
1024000	TEMP-LR-A-	6.0	6.0	0.242	1		
1024100	TEMP-LR-A-	6.0	6.0	0.242	1		
1024200	TEMP-LR-A-	6.0	6.0	0.242	1		
1024300	TEMP-LR-A-	6.0	6.0	0.242	1		
1024400	TEMP-LR-A-	6.0	6.0	0.242	1		
1024500	TEMP-LR-A-	6.0	6.0	0.242	1		
1024600	TEMP-LR-A-	6.0	6.0	0.242	1		
1024700	TEMP-LR-A-	6.0	6.0	0.242	1		
1024800	TEMP-LR-A-	6.0	6.0	0.242	1		
1024900	TEMP-LR-A-	6.0	6.0	0.242	1		
1025000	TEMP-LR-A-	6.0	6.0	0.242	1		

ORIGINAL PAGE IS
OF POOR QUALITY

ORIGINAL PAGE IS
OF POOR QUALITY

ORIGINAL PAGE IS
OF POOR QUALITY

1030006	ATT CONTR A	62.70	62.90	74.300	1.
1030170	BOY NO" SEMS	0.0	0.0	3.800	1.
1030300	WIN SEASOR	0.0	0.0	2.300	1.
1031301	ELECTRONICS	0.0	0.0	1.300	1.
1031302	DETECTOR	0.0	0.0	1.000	2.
1031400	DET DRACOLA	0.0	0.0	26.000	1.
1031401	NUT DAMPER	0.0	0.0	13.000	1.
1031402	ATT COIL	0.0	0.0	12.000	2.
1031500	MOMENT COIL	0.0	0.0	11.000	1.
1031600	PITCH HARPER	0.0	0.0	13.000	1.
1031700	POWER	120.10	127.10	123.560	1.
1031800	MULTI-GLASS	0.0	0.0	28.780	1.
1031901	CELL MODULES	0.0	0.0	24.680	1.
1031902	SOUND WIRING	0.0	0.0	3.100	1.
1031903	DIGGES	0.0	0.0	1.000	1.
1031904	LEVEL SOL AP	0.0	0.0	24.780	1.
1031905	CELL MODULES	0.0	0.0	24.680	1.
1031906	SOUND WIRING	0.0	0.0	1.100	1.
1031907	DIGGES	0.0	0.0	1.000	1.
1031908	BATTERIES	0.0	0.0	43.400	1.
1031909	MATT	0.0	0.0	21.700	1.
1031910	BATT	0.0	0.0	21.700	1.
1031911	OWN SUEL EL	0.0	0.0	22.600	1.
1031912	CONDUCTING A	10.70	18.50	14.500	1.
1031913	NO-INST YACOR	0.0	0.0	7.600	1.
1031914	RECORD CABLE	0.0	0.0	2.300	1.
1031915	NO-INST ANTENNA	0.0	0.0	1.400	1.
1031916	AVT MAST/SH	0.0	0.0	1.000	1.
1031917	SAFELY NTRK	0.0	0.0	1.800	1.
1031918	PR AND PROC	0.0	0.0	4.400	1.
1031919	C 3 DH	53.10	62.30	62.300	1.
1031920	CYC	0.0	0.0	9.100	1.
1031921	COIL	0.0	0.0	10.800	1.
1031922	RTA	0.0	0.0	4.400	1.
1031923	TAPR RECORDR	0.0	0.0	30.000	1.
1031924	TR RECORD	0.0	0.0	17.000	1.
1031925	TO RECORD	0.0	0.0	17.000	1.
1031926	S/C PARQUERS	64.70	64.70	64.700	1.
1031927	UPPER HAND	0.0	0.0	27.500	1.
1031928	LOWER HAND	0.0	0.0	27.500	1.
1031929	GROUND BLOCK	0.0	0.0	0.400	1.
1031930	GROUND BLOCK	0.0	0.0	0.300	1.
1031931	POTTING	0.0	0.0	1.000	1.
1031932	CLIMPS	0.0	0.0	1.000	1.
1031933	MAT	0.0	0.0	5.500	1.
1031934	SPID STRAP	0.0	0.0	1.500	1.
1031935	GFC UL-A	149.29	142.20	172.122	1.
1031936	MAG	0.0	7.10	4.600	1.
1031937	SENSOR	0.0	0.0	1.610	1.
1031938	ELECTRONICS	0.0	0.0	7.032	1.
1031939	TABUL BLUNT	0.0	0.0	0.0	1.
1031940	CL	0.0	24.50	26.960	1.
1031941	CREAMPS	0.0	0.0	1.320	4.
1031942	ELECTRONICS	0.0	0.0	2.100	1.
1031943	SHORT EL ANT	0.0	0.0	0.150	1.
1031944	SM EL ANT EL	0.0	0.0	0.020	1.
1031945	SPARK COIL	0.0	0.0	0.100	1.
1031946	SACH COIL EL	0.0	0.0	0.320	1.
1031947	LOOP ANTENNA	0.0	0.0	1.700	2.
1031948	LOOP ANTENNA	0.0	0.0	1.300	1.

Handwritten marks: a large 'A' and a smaller 'A'.

4.16.8-2

2295185-1

2295185-1

DYNAMICS EXPLORER DE-1
 ZONE AND PHASE SUMMARY
 31 OCTOBER 1974

ZONE	PROPOSAL WEIGHT	CURRENT TARGET WEIGHT	CURRENT ESTIMATED WEIGHT
------	--------------------	-----------------------------	--------------------------------

1	66.40	512.40	660.20
2	199.29	142.20	172.122
3	25.00	50.00	50.000

WAS	PROPOSAL WT	CURRENT TARGET WT	CURRENT EST/ACT WT
-----	-------------	----------------------	-----------------------

TOTAL SYSTEM LAUNCH WEIGHT INCL BAL WT	639.69	765.10	791.031
SPICECRAFT MANUFARE WEIGHT INCL BAL	660.00	172.00	649.700
GFC INSTRUMENTATION WEIGHT	199.29	142.20	172.122
TOTAL BALANCE WEIGHT	25.00	50.00	50.000

ORIGINAL PAGE IS
 OF POOR QUALITY

DYNAMICS EXPLORER DE-4
INPUT MOMENT OF INERTIA AND C.G. INFORMATION
31 OCTOBER 1978

NOMENCLATURE	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736	737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759	760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805	806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828	829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851	852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874	875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000	1001	1002	1003	1004	1005	1006	1007	1008	1009	1010	1011	1012	1013	1014	1015	1016	1017	1018	1019	1020	1021	1022	1023	1024	1025	1026	1027	1028	1029	1030	1031	1032	1033	1034	1035	1036	1037	1038	1039	1040	1041	1042	1043	1044	1045	1046	1047	1048	1049	1050	1051	1052	1053	1054	1055	1056	1057	1058	1059	1060	1061	1062	1063	1064	1065	1066	1067	1068	1069	1070	1071	1072	1073	1074	1075	1076	1077	1078	1079	1080	1081	1082	1083	1084	1085	1086	1087	1088	1089	1090	1091	1092	1093	1094	1095	1096	1097	1098	1099	1100	1101	1102	1103	1104	1105	1106	1107	1108	1109	1110	1111	1112	1113	1114	1115	1116	1117	1118	1119	1120	1121	1122	1123	1124	1125	1126	1127	1128	1129	1130	1131	1132	1133	1134	1135	1136	1137	1138	1139	1140	1141	1142	1143	1144	1145	1146	1147	1148	1149	1150	1151	1152	1153	1154	1155	1156	1157	1158	1159	1160	1161	1162	1163	1164	1165	1166	1167	1168	1169	1170	1171	1172	1173	1174	1175	1176	1177	1178	1179	1180	1181	1182	1183	1184	1185	1186	1187	1188	1189	1190	1191	1192	1193	1194	1195	1196	1197	1198	1199	1200	1201	1202	1203	1204	1205	1206	1207	1208	1209	1210	1211	1212	1213	1214	1215	1216	1217	1218	1219	1220	1221	1222	1223	1224	1225	1226	1227	1228	1229	1230	1231	1232	1233	1234	1235	1236	1237	1238	1239	1240	1241	1242	1243	1244	1245	1246	1247	1248	1249	1250	1251	1252	1253	1254	1255	1256	1257	1258	1259	1260	1261	1262	1263	1264	1265	1266	1267	1268	1269	1270	1271	1272	1273	1274	1275	1276	1277	1278	1279	1280	1281	1282	1283	1284	1285	1286	1287	1288	1289	1290	1291	1292	1293	1294	1295	1296	1297	1298	1299	1300	1301	1302	1303	1304	1305	1306	1307	1308	1309	1310	1311	1312	1313	1314	1315	1316	1317	1318	1319	1320	1321	1322	1323	1324	1325	1326	1327	1328	1329	1330	1331	1332	1333	1334	1335	1336	1337	1338	1339	1340	1341	1342	1343	1344	1345	1346	1347	1348	1349	1350	1351	1352	1353	1354	1355	1356	1357	1358	1359	1360	1361	1362	1363	1364	1365	1366	1367	1368	1369	1370	1371	1372	1373	1374	1375	1376	1377	1378	1379	1380	1381	1382	1383	1384	1385	1386	1387	1388	1389	1390	1391	1392	1393	1394	1395	1396	1397	1398	1399	1400	1401	1402	1403	1404	1405	1406	1407	1408	1409	1410	1411	1412	1413	1414	1415	1416	1417	1418	1419	1420	1421	1422	1423	1424	1425	1426	1427	1428	1429	1430	1431	1432	1433	1434	1435	1436	1437	1438	1439	1440	1441	1442	1443	1444	1445	1446	1447	1448	1449	1450	1451	1452	1453	1454	1455	1456	1457	1458	1459	1460	1461	1462	1463	1464	1465	1466	1467	1468	1469	1470	1471	1472	1473	1474	1475	1476	1477	1478	1479	1480	1481	1482	1483	1484
--------------	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------

[illegible]

INCRD VITE	100801	1	1	1	7.3	5.5	0.0	0.0	0.0	6.0	20.0	0.0	0.0	0.0
OUT-ED WIP	100802	1	1	1	7.3	5.5	0.0	0.0	0.0	-6.0	-20.0	0.0	0.0	0.0
OUT-ED WIP	100803	1	1	1	7.3	5.5	0.0	0.0	0.0	6.0	20.0	0.0	0.0	0.0
TIP PASS	100804	1	1	1	7.3	5.5	0.0	0.0	0.0	-6.0	-20.0	0.0	0.0	0.0
TIP PASS	100805	1	1	1	7.3	5.5	0.0	0.0	0.0	6.0	20.0	0.0	0.0	0.0
DISPERSE	100806	1	1	1	7.3	5.5	0.0	0.0	0.0	-6.0	-20.0	0.0	0.0	0.0
DISPERSE	100807	1	1	1	7.3	5.5	0.0	0.0	0.0	6.0	20.0	0.0	0.0	0.0
PRI SUPASSY	100901	11	1	1	12.0	0.0	0.5	0.0	0.0	-31.0	16.0	0.0	0.0	0.0
PRI MINGE	100902	1	1	1	5.0	3.0	0.0	0.0	0.0	-31.0	16.0	0.0	0.0	0.0
S/C BALANCE	110010	1	1	1	4.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
WAG BAL	110020	7	1	1	0.5	0.0	4.0	0.0	0.0	24.9	-11.0	0.0	0.0	0.0
WAG BAL	110030	2	1	1	0.0	0.0	0.0	0.0	0.0	-17.6	0.0	0.0	0.0	0.0
ASTRO WOPR	130012	2	1	1	0.0	0.0	5.0	0.0	0.0	-17.6	0.0	0.0	0.0	0.0
ASTRO WOPR	130020	3	1	1	15.0	0.0	0.0	0.0	0.0	17.6	-8.6	0.0	0.0	0.0
ASTRO WOPR	130021	1	1	1	15.0	0.0	0.0	0.0	0.0	17.6	-8.6	0.0	0.0	0.0
WARRNESS-01	130030	2	1	1	15.0	0.0	0.0	0.0	0.0	-17.6	0.0	0.0	0.0	0.0
WARRNESS-02	130040	3	1	1	15.0	0.0	0.0	0.0	0.0	17.6	-8.6	0.0	0.0	0.0

ORIGINAL PAGE IS
OF POOR QUALITY

DETECTOR	0.403	0.403	0.403	1
DETECTOR	0.403	0.403	0.403	1
ANTI DAMPER	5172.688	5172.688	5172.688	13
ATT COIL	1950.750	1950.750	3501.500	13
MOUNT COIL	1272.410	7473.210	7473.600	13
PITCH DAMPER	0211.128	0231.128	0050.750	13
UPP SOL AR	10116.602	10116.602	15901.301	13
LOWER SOL AR	10116.602	10116.602	15901.301	13
BATT 1	222.222	222.222	222.222	1
BATT 2	272.570	272.570	285.600	1
PUR SUPPL CL	231.742	547.290	597.389	1
ME-NSI 12MR	26.017	46.288	57.400	1
SPONOR COILF	0.106	10.009	17.059	1
NO GM AUTO-AR	1.779	0.708	1.779	3
ANT MASTASH	210.056	0.252	204.050	13
SW-FLY WTRK	10.773	6.375	13.563	1
PRMOD PROC	20.044	13.255	23.591	1
CIP	31.721	173.254	149.794	1
COU	112.049	145.072	117.025	1
PTM	113.046	87.535	92.574	1
TP KCBURI	165.240	290.417	350.167	1
TE KCBURI	157.700	290.417	354.167	1
SAC MARESS	21.27.42	21.27.492	20210.742	4
SENSOR	9.000	9.000	9.000	1
ELECTRONICS	62.361	76.185	71.052	1
TEMP'L AL'RY	0.0	0.0	0.0	1
BREANPS	0.000	0.218	3.000	1
BREAPPS	0.000	0.218	0.000	1
BREAPPS	0.000	0.218	0.000	1
BREAPPS	0.000	0.218	0.000	1
ELECTRONICS	356.270	356.270	512.000	1
SHORT EL BAT	3.033	7.201	7.201	10
SM EL BAT EL	0.000	0.000	1.174	1
SEARCH COIL	0.021	0.021	7.000	12
SKCH COIL EL	0.254	0.254	0.090	1
LOC2 ANT-AMA	106.407	106.407	0.670	4
LOOP ANT-AMA	106.407	106.407	0.670	4
LOOP ANT-AMA	0.000	0.000	0.000	2
LOOP ANT-AMA	0.000	0.000	0.000	2
VIS SENSOR	627.980	627.100	555.000	13
VIS SENSOR	627.980	627.100	555.000	13
VIS SENSOR	627.980	627.100	555.000	13
VIS COVER	0.000	0.000	0.000	13
VIS COVER	0.000	0.000	0.000	13
VIS COVER	0.000	0.000	0.000	13
VIS COVER	0.000	0.000	0.000	13
DCU	0.000	0.000	0.000	10
ELECTRONICS	0.000	0.000	0.000	1
ELECTRONICS	0.000	0.000	0.000	1
EET ASSV	0.000	0.000	0.000	1
NPVS	11.542	8.742	12.742	1
NPVS	11.542	8.742	12.742	1
NPVS	11.542	8.742	12.742	1
NPVS	11.542	8.742	12.742	1
RAU SML	0.000	0.000	0.000	1
CALING	0.000	0.000	0.000	1
ELECTRONICS	0.000	0.000	0.000	1
SENSOR	0.000	0.000	0.000	1
SENSOR	0.000	0.000	0.000	1
SENSOR	0.000	0.000	0.000	1
SENSOR	0.000	0.000	0.000	1
DISPENSER	193.000	167.300	47.900	13
DISPENSER	193.000	167.300	47.900	13
DISPENSER	193.000	167.300	47.900	13
DISPENSER	193.000	167.300	47.900	13

ORIGINAL PAGE IS
OF POOR QUALITY

INNOV WIRE	1.119	1.584	1.991	1
OUTERD WIRE	0.348	0.325	0.622	1
OUTERD WIRE	0.348	0.325	0.622	1
TIP MASS	0.091	0.137	0.162	1
TIP MASS	0.091	0.137	0.162	1
DISCENSEA	10.737	55.536	65.618	1
DISCENSEA	10.737	55.536	65.618	1
PHI SURASSY	10.912	0.223	16.912	11
PHI WING	1.117	1.182	2.614	1
S/C BALANCE	112.933	112.933	112.933	1
WAT BAL	11.407	77.456	34.477	3
EAST	29.338	58.308	58.868	2
ASTRO WDIR	106.008	292.008	292.008	2
WAST	22.100	29.770	54.000	3
ASTRO WDIR	292.008	106.008	292.008	1
WARRLESS-PV1	41.250	162.500	162.500	2
WARRLESS-VAC	40.000	20.300	40.000	2

[illegible]

INSTR VICE	1.467	1.131	1.991	0.097	-0.000	0.000	80.0	170.0	90.0	90.0
OUTDR VICE	2.521	0.553	0.422	0.030	-0.000	0.000	80.0	170.0	90.0	90.0
OUTDR VICE	0.551	0.553	0.422	0.030	-0.000	0.000	80.0	170.0	90.0	90.0
VIP WASH	0.135	0.192	0.162	0.060	-0.000	0.000	80.0	170.0	90.0	90.0
VIP WASH	2.130	0.192	0.162	0.060	-0.000	0.000	80.0	170.0	90.0	90.0
DISC WASH	0.260	0.192	0.162	0.060	-0.000	0.000	80.0	170.0	90.0	90.0
DISC WASH	59.709	0.192	0.162	0.060	-0.000	0.000	80.0	170.0	90.0	90.0
ASST WASH	2.130	0.192	0.162	0.060	-0.000	0.000	80.0	170.0	90.0	90.0
ASST WASH	2.130	0.192	0.162	0.060	-0.000	0.000	80.0	170.0	90.0	90.0
S/C WASH	112.933	112.933	112.933	0.000	-0.000	0.000	70.0	160.0	90.0	90.0
WASH	75.100	0.192	0.162	0.060	-0.000	0.000	80.0	170.0	90.0	90.0
WASH	50.100	0.192	0.162	0.060	-0.000	0.000	80.0	170.0	90.0	90.0
ASST WASH	172.070	265.023	292.000	-50.921	-0.000	0.000	180.0	240.0	90.0	90.0
WASH	24.100	52.020	50.000	-11.100	-0.000	0.000	65.0	120.0	90.0	90.0
ASST WASH	222.112	200.021	200.000	-20.000	-0.000	0.000	65.0	120.0	90.0	90.0
WASH	35.702	107.000	102.500	-31.121	-0.000	0.000	180.0	240.0	90.0	90.0
WASH	23.572	30.020	40.000	-7.660	-0.000	0.000	65.0	120.0	90.0	90.0

ORIGINAL PAGE IS
OF FOUR QUALITY

**DYNAMICS EXPLOREN DE-A
MOMENT OF INERTIA CALCULATIONS ABOUT S/C AXIS**

29 ASTERISK INDICATES THE TOTAL SUM OF THE MOMENTS OF FOX COMPONENTS

IN	NAME	ISA	ISA	ISA	ISA
121100	WATER	121100	121100	121100	121100
121101	WATER	121101	121101	121101	121101
121102	WATER	121102	121102	121102	121102
121103	WATER	121103	121103	121103	121103
121104	WATER	121104	121104	121104	121104
121105	WATER	121105	121105	121105	121105
121106	WATER	121106	121106	121106	121106
121107	WATER	121107	121107	121107	121107
121108	WATER	121108	121108	121108	121108
121109	WATER	121109	121109	121109	121109
121110	WATER	121110	121110	121110	121110
121111	WATER	121111	121111	121111	121111
121112	WATER	121112	121112	121112	121112
121113	WATER	121113	121113	121113	121113
121114	WATER	121114	121114	121114	121114
121115	WATER	121115	121115	121115	121115
121116	WATER	121116	121116	121116	121116
121117	WATER	121117	121117	121117	121117
121118	WATER	121118	121118	121118	121118
121119	WATER	121119	121119	121119	121119
121120	WATER	121120	121120	121120	121120
121121	WATER	121121	121121	121121	121121
121122	WATER	121122	121122	121122	121122
121123	WATER	121123	121123	121123	121123
121124	WATER	121124	121124	121124	121124
121125	WATER	121125	121125	121125	121125
121126	WATER	121126	121126	121126	121126
121127	WATER	121127	121127	121127	121127
121128	WATER	121128	121128	121128	121128
121129	WATER	121129	121129	121129	121129
121130	WATER	121130	121130	121130	121130
121131	WATER	121131	121131	121131	121131
121132	WATER	121132	121132	121132	121132
121133	WATER	121133	121133	121133	121133
121134	WATER	121134	121134	121134	121134
121135	WATER	121135	121135	121135	121135
121136	WATER	121136	121136	121136	121136
121137	WATER	121137	121137	121137	121137
121138	WATER	121138	121138	121138	121138
121139	WATER	121139	121139	121139	121139
121140	WATER	121140	121140	121140	121140
121141	WATER	121141	121141	121141	121141
121142	WATER	121142	121142	121142	121142
121143	WATER	121143	121143	121143	121143
121144	WATER	121144	121144	121144	121144
121145	WATER	121145	121145	121145	121145
121146	WATER	121146	121146	121146	121146
121147	WATER	121147	121147	121147	121147
121148	WATER	121148	121148	121148	121148
121149	WATER	121149	121149	121149	121149
121150	WATER	121150	121150	121150	121150
121151	WATER	121151	121151	121151	121151
121152	WATER	121152	121152	121152	121152
121153	WATER	121153	121153	121153	121153
121154	WATER	121154	121154	121154	121154
121155	WATER	121155	121155	121155	121155
121156	WATER	121156	121156	121156	121156
121157	WATER	121157	121157	121157	121157
121158	WATER	121158	121158	121158	121158
121159	WATER	121159	121159	121159	121159
121160	WATER	121160	121160	121160	121160
121161	WATER	121161	121161	121161	121161
121162	WATER	121162	121162	121162	121162
121163	WATER	121163	121163	121163	121163
121164	WATER	121164	121164	121164	121164
121165	WATER	121165	121165	121165	121165
121166	WATER	121166	121166	121166	121166
121167	WATER	121167	121167	121167	121167
121168	WATER	121168	121168	121168	121168
121169	WATER	121169	121169	121169	121169
121170	WATER	121170	121170	121170	121170
121171	WATER	121171	121171	121171	121171
121172	WATER	121172	121172	121172	121172
121173	WATER	121173	121173	121173	121173
121174	WATER	121174	121174	121174	121174
121175	WATER	121175	121175	121175	121175
121176	WATER	121176	121176	121176	121176
121177	WATER	121177	121177	121177	121177
121178	WATER	121178	121178	121178	121178
121179	WATER	121179	121179	121179	121179
121180	WATER	121180	121180	121180	121180
121181	WATER	121181	121181	121181	121181
121182	WATER	121182	121182	121182	121182
121183	WATER	121183	121183	121183	121183
121184	WATER	121184	121184	121184	121184
121185	WATER	121185	121185	121185	121185
121186	WATER	121186	121186	121186	121186
121187	WATER	121187	121187	121187	121187
121188	WATER	121188	121188	121188	121188
121189	WATER	121189	121189	121189	121189
121190	WATER	121190	121190	121190	121190
121191	WATER	121191	121191	121191	121191
121192	WATER	121192	121192	121192	121192
121193	WATER	121193	121193	121193	121193
121194	WATER	121194	121194	121194	121194
121195	WATER	121195	121195	121195	121195
121196	WATER	121196	121196	121196	121196
121197	WATER	121197	121197	121197	121197
121198	WATER	121198	121198	121198	121198
121199	WATER	121199	121199	121199	121199
121200	WATER	121200	121200	121200	121200
121201	WATER	121201	121201	121201	121201
121202	WATER	121202	121202	121202	121202
121203	WATER	121203	121203	121203	121203
121204	WATER	121204	121204	121204	121204
121205	WATER	121205	121205	121205	121205
121206	WATER	121206	121206	121206	121206
121207	WATER	121207	121207	121207	121207
121208	WATER	121208	121208	121208	121208
121209	WATER	121209	121209	121209	121209
121210	WATER	121210	121210	121210	121210
121211	WATER	121211	121211	121211	121211
121212	WATER	121212	121212	121212	121212
121213	WATER	121213	121213	121213	121213
121214	WATER	121214	121214	121214	121214
121215	WATER	121215	121215	121215	121215
121216	WATER	121216	121216	121216	121216
121217	WATER	121217	121217	121217	121217
121218	WATER	121218	121218	121218	121218
121219	WATER	121219	121219	121219	121219
121220	WATER	121220	121220	121220	121220
121221	WATER	121221	121221	121221	121221
121222	WATER	121222	121222	121222	121222
121223	WATER	121223	121223	121223	121223
121224	WATER	121224	121224	121224	121224
121225	WATER	121225	121225	121225	121225
121226	WATER	121226	121226	121226	121226
121227	WATER	121227	121227	121227	121227
121228	WATER	121228	121228	121228	121228
121229	WATER	121229	121229	121229	121229
121230	WATER	121230	121230	121230	121230
121231	WATER	121231	121231	121231	121231
121232	WATER	121232	121232	121232	121232
121233	WATER	121233	121233	121233	121233
121234	WATER	121234	121234	121234	121234
121235	WATER	121235	121235	121235	121235
121236	WATER	121236	121236	121236	121236
121237	WATER	121237	121237	121237	121237
121238	WATER	121238	121238	121238	121238
121239	WATER	121239	121239	121239	121239
121240	WATER	121240	121240	121240	121240
121241	WATER	121241	121241	121241	121241
121242	WATER	121242	121242	121242	121242
121243	WATER	121243	121243	121243	121243
121244	WATER	121244	121244	121244	121244
121245	WATER	121245	121245	121245	121245
121246	WATER	121246	121246	121246	121246
121247	WATER	121247	121247	121247	121247
121248	WATER	121248	121248	121248	121248
121249	WATER	121249	121249	121249	121249
121250	WATER	121250	121250	121250	121250
121251	WATER	121251	121251	121251	121251
121252	WATER	121252	121252	121252	121252
121253	WATER	121253	121253	121253	121253
121254	WATER	121254	121254	121254	121254
121255	WATER	121255	121255	121255	121255
121256	WATER	121256	121256	121256	121256
121257	WATER	121257	121257	121257	121257
121258	WATER	121258	121258	121258	121258
121259	WATER	121259	121259	121259	121259
121260	WATER	121260	121260	121260	121260
121261	WATER	121261	121261	121261	121261
121262	WATER	121262	121262	121262	121262
121263	WATER	121263	121263	121263	121263
121264	WATER	121264	121264	121264	121264
121265	WATER	121265	121265	121265	121265
121266	WATER	121266	121266	121266	121266
121267	WATER	121267	121267	121267	121267
121268	WATER	121268	121268	121268	121268
121269	WATER	121269	121269	121269	121269
121270	WATER	121270	121270	121270	121270
121271	WATER	121271	121271	121271	121271
121272	WATER	121272	121272	121272	121272
121273	WATER	121273	121273	121273	121273
121274	WATER	121274	121274	121274	121274
121275	WATER	121275	121275	121275	121275
121276	WATER	121276	121276	121276	121276
121277	WATER	121277	121277	121277	121277
121278	WATER	121278	121278	121278	121278
121279	WATER	121279	121279	121279	121279
121280	WATER	121280	121280	121280	121280
121281	WATER	121281	121281	121281	121281
121282	WATER	121282	121282	121282	121282
121283	WATER	121283	121283	121283	121283
121284	WATER	121284	121284	121284	121284
121285	WATER	121285	121285	121285	121285
121286	WATER	121286	121286	121286	121286

DYNAMICS EXPLORED DE-A
S/C MOMENTS OF INERTIA
01 OCTOBER 1978 Stowed Before Balancing.

THE TOTALS BEFORE BALANCING ARE-

SUM OF HEIGHTS = 0.70043115E+03
SUM OF HEIGHT * X DISTANCES = 0.34147335E+03
SUM OF HEIGHT * Y DISTANCES = 0.91029155E+02
SUM OF HEIGHT * Z DISTANCES = 0.05188501E+03
SUM OF HEIGHT * X * Z DISTANCES = 0.20423250E+04
SUM OF HEIGHT * Y * Z DISTANCES = 0.26349241E+04
SUM OF HEIGHT * X * Y DISTANCES = 0.1810027E+04
SUM OF HEIGHT * YZ = 0.81224125E+05
SUM OF HEIGHT * YZ = 0.55562875E+05
SUM OF HEIGHT * ZZ = 0.89597375E+05

SUM OF IX = 0.1059420E+05
SUM OF IY = 0.10456737E+06
SUM OF IZ = 0.14611109E+06

THE C.G. COORDINATES ARE-- XE = -0.44014E+00 YE = 0.117274E+00 ZE = -0.206135E+00

SUM OF IX = 0.88080933E+02
SUM OF IY = 0.0
SUM OF IZ = 0.0

DYNAMICS EXPLORER DE-A
S/C MOMENTS OF INERTIA
31 OCTOBER 1978

S/C MOMENTS OF INERTIA ANF-

* THE FOLLOWING VALUES HAVE UNITS OF LB.-IN²

IXZ=0.2627441E+06
IYZ=0.27484416E+06
IZZ=0.29475231E+06
IXZ=0.1248441E+06
IYZ=0.27750437E+06
IYZ=0.17252160E+06
IMAX=0.275231E+06
IMIN=0.2605305E+06

* THE FOLLOWING VALUES HAVE UNITS OF IN-LB-SEC²

IXZ=0.67543497E+07
IYZ=0.71175726E+07
IZZ=0.76327594E+07
IYZ=0.5272560E+07
IYZ=0.71761066E+07
IXZ=0.44011000E+07
IMAX=0.71240080E+07
IMIN=0.67484502E+07

INERTIA RATIO

Y / I = 1.072
SPIN/ TRANSVERSE MAX

DYNAMICS EXPLORER DE-A
S/C MOMENTS OF INERTIA
31 OCTOBER 1976

THE TOTALS & FORCE BALANCING ARE-

SUM OF WEIGHTS = 0.76743115E+03
SUM OF WEIGHT * Z DISTANCES = 0.3047339E+03
SUM OF WEIGHT * X DISTANCES = 0.9142418E+02
SUM OF WEIGHT * Y DISTANCES = 0.3510696E+03
SUM OF WEIGHT * X * Z DISTANCES = 0.2042325E+04
SUM OF WEIGHT * Y * Z DISTANCES = 0.2030923E+04
SUM OF WEIGHT * X * Y DISTANCES = 0.1681002E+04
SUM OF WEIGHT * YZ = 3.6122412E+05
SUM OF WEIGHT * XZ = 0.6558287E+05
SUM OF WEIGHT * XY = 3.4959737E+05

SUM OF IYZ = 0.1054603E+06
SUM OF IYZ = 0.1045073E+06
SUM OF IYZ = 0.1411190E+06

X = 20.000 Y1 = -20.000 Y2 = 20.000 Z1 = 15.000 Z2 = -15.000

BALANCE WEIGHTS AND LOCATIONS

W	X	Y	Z
(1)	-12.1157	-20.0000	0.0
(2)	5.3300	20.0000	0.0
(3)	-2.0368	0.0	-20.0000
(4)	-7.0130	0.0	20.0000

THE SUM OF THE BALANCE WEIGHTS IS 26.8730

THE C.G. COORDINATE AREAS IS X = 0.300216E+06 Y = 0.756136E+07 Z = 0.601166E+08

SUM OF IYZ = 0.9678193E+02
SUM OF IYZ = 0.0
SUM OF IYZ = 0.0

ORIGINAL PAGE IS
OF POOR QUALITY

NOTE THAT A NEGATIVE BALANCE WEIGHT DENOTES THAT A NONZERO X OR Y COORDINATE IS OF OPPOSITE SIGN

THE TOTALS AFTER BALANCING ARE-

SUM OF WEIGHTS = 0.4730444E+03
SUM OF WEIGHT * Z DISTANCES = 0.2186582E+03
SUM OF WEIGHT * X DISTANCES = 0.5123515E+04
SUM OF WEIGHT * Y DISTANCES = 0.5176162E+03
SUM OF WEIGHT * X * Z DISTANCES = 0.4082812E+03
SUM OF WEIGHT * Y * Z DISTANCES = 0.1464843E+02
SUM OF WEIGHT * X * Y DISTANCES = 0.1681002E+04
SUM OF WEIGHT * YZ = 0.8819350E+05
SUM OF WEIGHT * YZ = 0.6936275E+05
SUM OF WEIGHT * Z2 = 0.9560375E+05

SECTIONS OF INVERTS ARE-

SYMPTOMS OF INERTIA

01 OCTOBER 1972

THE FOLLOWING VALUES HAVE UNITS OF LB.-IN²

143-4-270630120-016

IV = 1.246772500

72-5174-6

NY 22-00054-2715-013

14-00000

NY 62-10077-127

12-30-24

INVESTIGATION NO. 627-0-941-01

~~ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED~~

100-371607-3

[illegible]

75411

91-561, 101-10-36

1472-03431-2

11-20606371-001

[illegible][illegible]

DISPATCH

1.063

SECRET - TRANSMITTED MAY

APPENDIX B
DE-A DEPLOYED MASS PROPERTIES
COMPUTER OUTPUT

01 OCTOBER 1976 DEBAND

ID	DATE	NAME	DAWG.NO.	SOURCE	ZONE	PROPOSAL WEIGHT	TARGET WEIGHT	EST/ACT WEIGHT	MT	TOL	QTY
100000	11 1 7	01-A	2294600-501		1-	0.0	0.0	0.0	0.0	0.0	1-
101000	11 1 7	STRUCTURE		4E-C	1-	134.20	140.20	0.0	0.0	0.0	1-
101011	11 1 7	01-A			1-	0.0	0.0	23.400	0.0	0.0	1-
101020	11 1 7	LOWER			1-	0.0	0.0	22.600	0.0	0.0	1-
101031	11 1 7	CEM			1-	0.0	0.0	0.0	0.0	0.0	1-
101041	11 1 7	01-A			1-	0.0	0.0	9.200	0.0	0.0	1-
101051	11 1 7	01-A			1-	0.0	0.0	2.920	0.0	0.0	1-
101061	11 1 7	01-A			1-	0.0	0.0	2.420	0.0	0.0	1-
101071	11 1 7	01-A			1-	0.0	0.0	2.420	0.0	0.0	1-
101081	11 1 7	01-A			1-	0.0	0.0	2.420	0.0	0.0	1-
101091	11 1 7	01-A			1-	0.0	0.0	2.420	0.0	0.0	1-
101100	11 1 7	01-A			1-	0.0	0.0	15.300	0.0	0.0	1-
101110	11 1 7	01-A			1-	0.0	0.0	16.300	0.0	0.0	1-
101120	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101130	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101140	11 1 7	01-A			1-	0.0	0.0	15.700	0.0	0.0	1-
101150	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101160	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101170	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101180	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101190	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101200	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101210	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101220	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101230	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101240	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101250	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101260	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101270	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101280	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101290	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101300	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101310	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101320	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101330	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101340	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101350	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101360	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101370	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101380	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101390	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101400	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101410	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101420	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101430	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101440	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101450	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101460	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101470	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101480	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101490	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101500	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101510	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101520	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101530	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101540	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101550	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101560	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101570	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101580	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101590	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101600	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101610	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101620	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101630	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101640	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101650	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101660	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101670	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101680	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101690	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101700	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101710	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101720	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101730	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101740	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101750	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101760	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101770	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101780	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101790	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101800	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101810	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101820	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101830	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101840	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101850	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101860	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101870	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101880	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101890	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101900	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101910	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101920	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101930	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101940	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101950	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101960	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101970	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101980	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
101990	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102000	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102010	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102020	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102030	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102040	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102050	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102060	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102070	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102080	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102090	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102100	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102110	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102120	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102130	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102140	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102150	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102160	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102170	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102180	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102190	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102200	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102210	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102220	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102230	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102240	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102250	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102260	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102270	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102280	11 1 7	01-A			1-	0.0	0.0	0.0	0.0	0.0	1-
102290	11 1 7										

[illegible]

1090301	10	1 A VTS SENSOR	2295121-2	2.00	0.00	11.336	0.00	0.00	2.00
1090302	10	1 A VUV SENSOR	2295121-3	2.00	0.00	11.336	0.00	0.00	1.00
1090303	10	1 A VTS COVER		2.00	0.00	0.000	0.00	0.00	1.00
1090304	10	1 A VUV COVER		2.00	0.00	0.004	0.00	0.00	1.00
1090305	10	1 A VUV		2.00	0.00	1.000	0.00	0.00	1.00
1090306	5	1 A MRF	2295120-1	2.00	0.00	0.00	0.00	0.00	1.00
1090307	5	1 A ELECTRONICS		2.00	0.00	9.000	0.00	0.00	1.00
1090308	5	1 A JET ASSY		2.00	0.00	7.000	0.00	0.00	1.00
1090309	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090310	5	1 A MRF		2.00	0.00	3.000	0.00	0.00	1.00
1090311	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090312	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090313	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090314	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090315	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090316	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090317	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090318	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090319	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090320	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090321	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090322	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090323	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090324	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090325	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090326	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090327	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090328	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090329	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090330	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090331	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090332	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090333	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090334	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090335	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090336	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090337	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090338	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090339	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090340	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090341	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090342	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090343	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090344	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090345	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090346	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090347	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090348	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090349	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090350	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090351	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090352	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090353	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090354	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090355	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090356	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090357	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090358	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090359	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090360	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090361	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090362	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090363	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090364	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090365	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090366	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090367	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090368	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090369	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090370	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090371	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090372	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090373	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090374	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090375	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090376	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090377	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090378	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090379	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090380	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090381	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090382	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090383	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090384	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090385	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090386	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090387	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090388	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090389	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090390	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090391	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090392	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090393	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090394	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090395	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090396	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090397	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090398	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090399	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090400	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090401	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090402	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090403	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090404	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090405	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090406	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090407	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090408	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090409	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090410	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090411	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090412	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090413	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090414	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090415	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090416	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090417	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090418	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090419	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090420	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090421	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090422	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090423	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090424	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090425	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090426	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090427	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090428	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090429	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090430	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090431	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090432	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090433	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090434	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090435	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090436	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
1090437	5	1 A MRF		2.00	0.00	1.000	0.00	0.00	1.00
10904									

DYNAMICS EXPLORER DE-A WEIGHT SUMMARY BY LEVELS 31 OCTOBER 1978

ID	NAME	PROPOSAL WEIGHT	CURRENT TARGET WEIGHT	CURRENT ESTIMATED ACT WT	QTY	DRWG NO	SOURCE
101000	DE-1	134.90	165.00	781.151	1	3904600-001	
101000	STRUCTURE-A-						
101010	UPPER RP	0.0	180.20	170.176	1		AE-C
101020	LOWER RP	0.0	0.0	23.402	1		
101030	CEN COL/SM	0.0	0.0	22.012	1		
101031	CENTER COL	0.0	0.0	23.721	1		
101032	SMR PANEL 1	0.0	0.0	2.421	1		
101033	SMR PANEL 2	0.0	0.0	2.421	1		
101034	SMR PANEL 3	0.0	0.0	2.420	1		
101035	SMR PANEL 4	0.0	0.0	2.420	1		
101036	SMR PANEL 5	0.0	0.0	2.420	1		
101037	SMR PANEL 6	0.0	0.0	2.420	1		
101038	SET ADPT UPR	0.0	0.0	15.100	1		
101039	SET ADPT LWR	0.0	0.0	16.300	1		
101040	MET UPPER	0.0	0.0	20.000	1		
101041	SLIDES M/L	0.0	0.0	15.300	1		
101042	SLIDES M/R	0.0	0.0	4.350	1		
101043	MAT LOWER	0.0	0.0	20.350	1		
101044	SIDES M/L	0.0	0.0	16.700	1		
101045	CEN M/L	0.0	0.0	4.350	1		
101046	CEN RING	0.0	0.0	16.000	1		
101047	RING	0.0	0.0	6.580	1		
101048	WACHTS	0.0	0.0	9.500	1		
101049	MEMORARE	0.0	0.0	1.000	1		
101050	REINFORC	0.0	0.0	2.500	1		
101051	CUMPS-SEALS	0.0	0.0	4.200	1		
101052	LIFTING MOVR	0.0	0.0	0.700	1		
101053	RF SCANS	0.0	0.0	0.130	1		
101054	RF SCANS UPR	0.0	0.0	1.000	6		
101055	RF SCANS LWR	0.0	0.0	1.060	6		
101056	M-DEANDL	0.0	0.0	2.000	1		
101057	ANTENNA SUPT	0.0	0.0	4.000	1		
101058	WAGE REC4	0.0	0.0	1.500	1		
101059	LAUNCH SUPT	0.0	0.0	1.500	1		
101060	ELEACE MVR	0.0	0.0	1.000	1		
101061	ATC WACHTS	0.0	0.0	2.010	6		
101062	ATC WACHTS	0.0	0.0	2.010	6		
102000	THRMAL -A-	12.00	12.10	12.070	1		
102001	THRM-UPR MAT	0.0	0.0	5.740	1		
102002	THRM-UPR MAT	0.0	0.0	3.750	1		
102003	ATC-UPR MAT	0.0	0.0	1.990	6		
102004	THRM-LWR MAT	0.0	0.0	5.740	1		
102005	THRM-LWR MAT	0.0	0.0	3.750	1		
102006	ATC-LWR MAT	0.0	0.0	1.990	6		
102007	THRM-UPR S/P	0.0	0.0	0.240	1		
102008	TEMP SENS-UPR	0.0	0.0	0.240	1		
102009	THRM-LWR S/P	0.0	0.0	0.240	1		
102010	TEMP SENS-LB	0.0	0.0	0.240	1		
102011	TH HEATERS	0.0	0.0	0.100	1		

103000	ATT CONTR A	62.90	•	62.90	79.380	1.
103010	MOV MOP SEVS	0.0	•	0.0	3.000	1.
103020	SUM SENSOR	0.0	•	0.0	3.100	1.
103030	ELECTRONICS	0.0	•	0.0	1.300	1.
103040	DETECTOR	0.0	•	0.0	1.000	2.
103050	MUT ELASCOIL	0.0	•	0.0	35.000	1.
103060	MUT DAMPER	0.0	•	0.0	15.000	1.
103070	ATT COIL	0.0	•	0.0	12.000	2.
103080	MORNT COIL	0.0	•	0.0	11.000	1.
103090	PITCH DAMPER	0.0	•	0.0	13.000	1.
103100	PITCH	120.10	•	127.10	123.560	1.
103110	MUTEL SOL AR	0.0	•	0.0	28.700	1.
103120	CELL MODULES	0.0	•	0.0	20.000	1.
103130	S-UNIT WIRING	0.0	•	0.0	3.100	1.
103140	ALONES	0.0	•	0.0	1.000	1.
103150	LUMK SOL AR	0.0	•	0.0	20.700	1.
103160	CELL MODULES	0.0	•	0.0	20.600	1.
103170	SUMIT WIRING	0.0	•	0.0	1.100	1.
103180	PIECES	0.0	•	0.0	1.000	1.
103190	BATT-IES	0.0	•	0.0	43.400	1.
103200	MAT 1	0.0	•	0.0	21.700	1.
103210	BATT 2	0.0	•	0.0	21.700	1.
103220	PJA SUPPL EL	0.0	•	0.0	22.000	1.
103230	CONCENS A	16.70	•	18.50	10.500	1.
103240	W-INST PPADE	0.0	•	0.0	7.600	1.
103250	CONCA CABLE	0.0	•	0.0	2.300	1.
103260	NO CA AMISK	0.0	•	0.0	1.000	1.
103270	ANT MAST-SE	0.0	•	0.0	1.000	1.
103280	S-FLY MTRK	0.0	•	0.0	1.000	1.
103290	PRECON PROC	0.0	•	0.0	0.000	1.
103300	C 1 DM	53.10	•	62.30	62.300	1.
103310	CTD	0.0	•	0.0	0.100	1.
103320	CDH	0.0	•	0.0	10.000	1.
103330	RT	0.0	•	0.0	0.000	1.
103340	TAP RECORDER	0.0	•	0.0	30.300	1.
103350	TR-CEDEI	0.0	•	0.0	12.000	1.
103360	T-RCOR2	0.0	•	0.0	17.000	1.
103370	SVC MATHS	64.70	•	64.70	64.700	1.
103380	MURER WARM	0.0	•	0.0	21.500	1.
103390	LOWER WARM	0.0	•	0.0	27.500	1.
103400	GROUND BLOCK	0.0	•	0.0	0.000	1.
103410	GROUND BLOCK	0.0	•	0.0	0.300	1.
103420	POTTING	0.0	•	0.0	1.000	1.
103430	CLAMPS	0.0	•	0.0	1.000	1.
103440	MAT	0.0	•	0.0	5.000	1.
103450	GRUD STRAP	0.0	•	0.0	1.000	1.
103460	GFE DE-A	149.29	•	142.20	172.122	1.
103470	MA	0.0	•	0.0	0.000	1.
103480	SENSOR	0.0	•	0.0	1.010	1.
103490	ELECTRONICS	0.0	•	0.0	7.032	1.
103500	TEMP BLUNT	0.0	•	0.0	0.000	1.
103510	CVI	0.0	•	0.0	26.900	1.
103520	PRFAPS	0.0	•	0.0	1.320	4.
103530	ELECTRONICS	0.0	•	0.0	31.100	1.
103540	SHORT EL ANT	0.0	•	0.0	0.150	1.
103550	SM EL ANT EL	0.0	•	0.0	0.020	1.
103560	SCAM COIL	0.0	•	0.0	0.100	1.
103570	SRCH COIL EL	0.0	•	0.0	0.327	1.
103580	LOOP ANTENNA	0.0	•	0.0	1.700	2.
103590	LOOP ANTENNA	0.0	•	0.0	1.100	1.

9.16.5-2

ORIGINAL PAGE IS
OF POOR QUALITY

1090300	SAT	0.0	30.00	30.220	1.	2299121-2
1090301	VIS SENSOR	0.0	0.0	22.672	2.	2299121-2
1090302	WIR SENSOR	0.0	0.0	11.136	1.	2299121-2
1090303	VIS COVER	0.0	0.0	1.604	2.	
1090304	VUV COVER	0.0	0.0	0.804	1.	
1090305	DCU	0.0	0.0	1.808	1.	
1090306	MAP1	0.0	22.00	22.000	1.	2299120-1
1090307	ELECTRONICS	0.0	0.0	1.002	1.	
1090308	DET ASSY	0.0	0.0	1.000	1.	
1090309	WPS	0.0	0.0	1.500	1.	
1090310	PS	0.0	0.0	3.064	1.	
1090311	SAN SWD	0.0	0.0	1.032	1.	
1090312	CABLEING	0.0	0.0	0.500	1.	
1090313	WPS	0.0	14.00	28.500	1.	
1090314	ELECTRONICS	0.0	0.0	6.002	1.	2299121-1
1090315	WPS	0.0	0.0	22.500	1.	2299121-2
1090316	WPS	0.0	10.00	10.000	1.	2299121-1
1090317	WPS	0.0	0.0	16.002	1.	
1090318	WPS	0.0	0.0	0.960	2.	
1090319	WPS	0.0	0.0	15.000	2.	
1090320	WPS	0.0	0.0	11.000	1.	
1090321	WPS	0.0	0.0	0.320	2.	
1090322	WPS	0.0	0.0	0.100	2.	
1090323	WPS	0.0	0.0	0.030	2.	
1090324	DISPENSER	0.0	0.0	10.500	2.	
1090325	DISP	0.0	0.0	2.000	1.	
1090326	DISP	0.0	0.0	0.000	1.	
1090327	DISP	0.0	0.0	1.100	1.	
1090328	DISP	0.0	0.0	50.000	1.	
1090329	DISP	0.0	0.0	0.300	1.	
1090330	DISP	0.0	0.0	7.650	1.	
1090331	DISP	0.0	0.0	34.100	1.	
1090332	DISP	0.0	0.0	10.000	1.	
1090333	DISP	0.0	0.0	2.320	1.	
1090334	DISP	0.0	0.0	11.600	1.	
1090335	DISP	0.0	0.0	10.000	1.	
1090336	DISP	0.0	0.0	2.320	1.	
1090337	DISP	0.0	0.0	11.600	1.	
1090338	DISP	0.0	0.0	6.000	1.	
1090339	DISP	0.0	0.0	1.600	1.	
1090340	DISP	0.0	0.0	0.0	1.	

DYNAMICS EXPLORER DC-A
ZONE AND PHASE SUMMARY
31 OCTOBER 1978

ZONE	PROPOSAL WEIGHT	CURRENT	
		TARGET WEIGHT	ESTIMATED WEIGHT
1	66.00	522.86	568.260
2	109.29	102.20	172.122
3	25.00	50.00	50.000

PHASE	PROPOSAL WT	CURRENT	
		TARGET WT	EST/ACT WT
TOTAL SYSTEM LAUNCH WEIGHT INCL PAL WT	639.49	765.00	791.830
SPACECRAFT MANEUVER WEIGHT INCL PAL	66.00	522.86	568.260
6FT INSTRUMENTATION WEIGHT	109.29	102.20	172.122
TOTAL BALANCE WEIGHT	25.00	50.00	50.000

DYNAMICS EXPLORER DE-A
INPUT MOMENT OF INERTIA AND C.G. INFORMATION
01 OCTOBER 1978

ENCLOSURE	ID NO.	IP	NO	PA	IX/INY	LY/INY	IZ/IZZ	RIO-0	RIO-1	YBAR	XBAR	ZBAR	WEIGHT
UPPER OP	110107	13	1	0	4145.9	4145.9	4291.0	0.0	0.0	0.0	0.0	-8.5	23.49
LOWER OP	110108	14	1	0	4145.9	4145.9	4291.0	0.0	0.0	0.0	0.0	0.0	23.49
CENTER COL	1010301	13	1	0	480.3	480.3	354.3	0.0	0.0	0.0	0.0	0.0	9.29
SMR PAWL 1	1010302	1	1	1	17.9	17.9	16.8	0.0	0.0	-15.2	0.0	0.0	2.42
SMR PAWL 2	1010303	1	1	1	18.9	18.9	16.8	0.0	0.0	-15.2	0.0	0.0	2.42
SMR PAWL 3	1010304	1	1	1	14.9	14.9	16.8	0.0	0.0	7.8	13.6	0.0	2.42
SMR PAWL 4	1010305	1	1	1	17.9	17.9	16.8	0.0	0.0	15.2	0.0	0.0	2.42
SMR PAWL 5	1010306	1	1	1	18.9	18.9	16.8	0.0	0.0	-13.6	0.0	0.0	2.42
SMR PAWL 6	1010307	1	1	1	18.9	18.9	16.8	0.0	0.0	-7.8	0.0	0.0	2.42
SEP ADPT UPR	1010400	13	1	0	1264.7	1264.7	553.3	0.0	0.0	0.0	0.0	-16.6	15.30
SEP ADPT LWR	1010500	13	1	0	1366.2	1366.2	589.3	0.0	0.0	0.0	0.0	16.6	15.30
SIDES MU	1010601	9	1	0	0.0	0.0	20.9	26.2	26.2	0.0	0.0	-12.5	15.70
END MU	1010602	9	1	0	0.0	0.0	0.5	26.2	26.2	0.0	0.0	-22.5	4.35
SIDES MU	1010701	9	1	0	0.0	0.0	20.9	26.2	26.2	0.0	0.0	15.70	15.70
END PL	1010702	9	1	0	0.0	0.0	0.5	26.2	26.2	0.0	0.0	22.5	4.35
CENTER WTC	1011001	9	1	0	0.0	0.0	3.0	26.2	26.2	0.0	0.0	0.0	16.00
PRISMATIC	1011101	9	1	0	0.0	0.0	45.2	25.1	25.1	0.0	0.0	0.0	3.50
COVERS+SEALS	1011200	4	1	0	0.0	0.0	45.2	25.1	25.1	0.0	0.0	0.0	4.20
LIFTING WTC	1011300	4	1	0	0.0	0.0	45.2	25.1	25.1	0.0	0.0	0.0	6.70
HEATING WTC	1011500	4	1	0	0.0	0.0	45.2	25.1	25.1	0.0	0.0	0.0	3.00
MISC WTC	1011601	1	1	0	2.0	2.0	2.5	6.0	6.0	-10.0	22.0	-23.0	1.50
LAUNCH SUPPLY	1011602	1	1	0	2.0	2.0	1.0	0.0	0.0	-10.0	0.0	-23.0	1.50
RELEASE WTC	1011603	1	1	0	2.0	2.0	1.0	0.0	0.0	-10.0	0.0	-23.0	1.50
ATC BRACKETS	1011700	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011701	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011702	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011703	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011704	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011705	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011706	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011707	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011708	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011709	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011710	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011711	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011712	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011713	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011714	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011715	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011716	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011717	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011718	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011719	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
ATC BRACKETS	1011720	4	1	0	0.0	0.0	0.7	1.5	1.5	0.0	0.0	-20.0	0.33
THRU-UPR WAT	1020101	4	1	0	0.0	0.0	20.9	25.0	24.9	0.0	0.0	-10.4	3.75
ATC-UPR WAT	1020102	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020103	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020104	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020105	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020106	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020107	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020108	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020109	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020110	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020111	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020112	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020113	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020114	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020115	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020116	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020117	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020118	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020119	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020120	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020121	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020122	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020123	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020124	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020125	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020126	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020127	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020128	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020129	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
ATC-UPR WAT	1020130	4	1	0	0.0	0.0	0.7	7.3	7.3	0.0	0.0	-20.0	0.33
TEMP SENS-LR	1020301	1	1	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.24
TH HEATERS	1020500	1	1	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.10
ADY HOR SENS	1030100	1	1	1	0.5	0.5	3.9	0.0	0.0	7.0	-21.1	-5.5	1.64

ORIGINAL PAGE IS
OF POOR QUALITY

DETECTOR	1030302	1	1	0	2.2	2.2	2.2	0.0	0.0	-24.0	0.0	-23.5	0.50
DETECTOR	1030302	1	1	0	2.2	2.2	2.2	0.0	0.0	-24.0	0.0	23.5	0.50
HUI DANGER	1030401	1	1	0	3042.0	5472.7	6512.5	0.0	0.0	14.8	0.0	0.0	13.88
ATT	1030402	13	1	0	1950.7	1950.7	3901.5	0.0	0.0	0.0	0.0	7.5	6.00
ROPEMNT COIL	1030500	13	1	0	12726.5	7476.7	7470.0	0.0	0.0	13.0	0.0	0.0	31.00
PITCH DAMPER	1030600	13	1	0	4211.2	4211.2	8422.7	0.0	0.0	0.0	0.0	19.5	18.04
UPPER SOL AR	1040100	13	1	0	10116.6	10116.6	15901.3	0.0	7.0	0.0	0.0	-17.1	28.78
LOWER SOL AR	1040200	13	1	0	10116.6	10116.6	15901.3	0.0	0.0	0.0	0.0	17.1	28.78
WALL 1	1040301	1	1	0	5.5	11.3	4.8	0.0	0.0	-17.7	7.5	11.1	21.70
WALL 2	1040302	1	1	0	11.3	5.5	4.8	0.0	0.0	-1.0	-20.7	11.1	21.70
CAR SUPPL FL	1040400	1	1	0	14.6	7.5	6.8	0.0	0.0	0.0	20.2	-13.1	22.60
WE-NST/2DR	1050200	1	1	0	7.8	3.5	3.5	0.0	0.0	11.8	0.0	10.5	2.30
SPONDER CABLE	1050300	1	1	0	5.5	5.5	3.5	0.0	0.0	11.8	9.0	10.5	2.30
VC SN AUT-SB	1050400	4	1	0	7.0	0.0	3.5	1.0	0.0	-10.0	6.0	-74.5	1.40
ANTI-BLAST-SB	1050500	12	1	1	0.0	0.0	0.0	0.0	0.0	0.0	13.0	0.0	1.00
SW-FLY WISN	1050600	1	1	0	5.5	7.8	3.5	0.0	0.0	-4.6	-18.8	10.5	1.00
PAFWD PROC	1050900	1	1	0	4.7	6.5	3.8	0.0	0.0	-11.5	4.0	12.5	4.40
CIP	1061100	1	1	0	12.1	6.8	4.8	0.0	0.0	0.0	10.0	13.1	0.30
CUU	1060200	1	1	0	9.2	4.9	8.8	0.0	0.0	-8.7	12.6	13.1	10.80
RTM	1060300	1	1	0	9.9	4.2	8.8	0.0	0.0	1.8	14.2	13.1	6.40
TP WCRDR1	1060400	1	1	0	12.0	9.0	6.0	0.0	0.0	-15.1	7.5	-11.1	12.00
TP WCRDR2	1060402	1	1	0	13.0	9.0	6.0	0.0	0.0	-15.2	-4.1	-11.8	17.00
S/C HARNESS	1060600	4	1	0	0.0	0.0	45.0	25.0	0.0	0.0	0.0	0.0	64.70
SEASDR	1061101	1	1	1	6.0	6.0	6.0	0.0	0.0	7.1	10.3	0.0	1.60
ELECTRONICS	1090102	1	1	0	8.5	7.0	7.6	0.0	0.0	7.2	-12.2	11.9	7.03
THRMAL HLNRY	1090103	1	1	0	0.5	7.0	7.4	0.0	0.0	7.2	-12.2	11.9	0.1
PREAMPS	1090201	1	1	1	1.3	3.8	0.5	0.0	0.0	0.0	17.0	0.0	0.00
PREAMPS	1090201	1	1	1	1.3	3.8	2.5	0.0	0.0	-1.8	-17.5	0.0	0.33
PREAMPS	1090201	1	1	0	3.8	1.3	2.5	0.0	0.0	0.0	-2.7	-12.9	0.33
ELECTRONICS	1090202	1	1	0	12.0	12.0	7.5	0.0	0.0	0.0	-10.9	-12.5	21.35
SHORT EL ANT	1090204	1	1	1	24.0	7.0	0.0	0.1	0.0	-243.0	114.0	0.0	0.15
SH EL ANT	1090205	1	1	1	3.1	4.8	1.5	0.0	0.0	-240.0	114.0	0.0	0.48
SEARCH CHIL	1090206	12	1	0	0.0	0.0	16.0	0.4	0.0	-244.0	116.0	0.0	0.30
SKCM COIL EL	1090207	1	1	1	1.3	1.3	2.4	0.0	0.0	-244.0	116.0	0.0	0.32
LOOP ANTENNA	1090208	4	1	1	0.0	0.0	45.0	0.4	0.0	-263.0	119.0	0.0	0.27
LOOP ANTENNA	1090209	3	1	1	0.0	0.0	45.0	0.4	0.0	-267.0	124.3	0.0	0.27
LOOP ANTENNA	1090209	3	1	1	0.0	35.0	0.0	0.4	0.0	-271.5	121.3	22.5	0.48
VIS SENSOR	1090301	13	1	1	461.0	627.1	555.5	0.0	0.0	-14.2	-13.5	0.4	11.34
VIS SENSOR	1090301	13	1	1	461.0	627.1	555.5	0.0	0.0	14.0	6.3	-0.4	11.34
WNV SENSOR	1090302	13	1	1	461.0	627.1	555.5	0.0	0.0	0.0	10.0	0.0	0.00
DCU	1090304	1	1	0	3.8	1.4	5.3	0.0	0.0	8.4	8.5	6.1	1.80
ELECTRONICS	1090401	1	1	0	6.3	7.9	5.5	0.0	0.0	-11.6	-14.6	-11.5	9.00
DET ASSY	1090402	1	1	1	1.0	7.5	0.0	0.0	0.0	-11.4	-11.4	0.0	0.00
HVFS	1090403	1	1	0	6.3	7.9	5.5	0.0	0.0	-11.6	-14.6	-11.5	1.50
FPS	1090404	1	1	0	6.3	7.9	5.5	0.0	0.0	-11.6	-14.6	-11.5	3.00
RAD SHLD	1090405	1	1	1	6.0	1.5	0.0	0.0	0.0	-20.4	-11.4	0.0	0.00
CAGLING	1090406	1	1	0	6.3	7.9	5.5	0.0	0.0	-11.6	-14.6	-11.5	0.50
ELECTRONICS	1090501	1	1	0	5.3	7.9	5.3	0.0	0.0	21.4	-1.5	-11.9	6.00
SENSOR	1090502	1	1	0	5.3	7.9	5.3	0.0	0.0	0.0	0.0	0.0	0.00
SENSOR	1090502	1	1	0	5.3	7.9	5.3	0.0	0.0	22.0	-8.8	18.5	7.50
SENSOR	1090502	1	1	1	5.0	7.8	5.7	0.0	0.0	20.1	10.7	-10.8	7.50
CIC	1090503	13	1	0	228.1	640.3	518.7	0.0	0.0	-15.1	-6.0	10.0	10.00
TUBF ANTENNA	1090701	12	1	0	0.0	0.0	118.1	0.6	0.0	0.0	0.0	0.0	0.00
TUBF ANTENNA	1090701	12	1	0	0.0	0.0	118.1	0.6	0.0	0.0	0.0	-01.6	0.00
DISPENSER	1090702	14	1	0	183.8	147.1	47.8	0.0	0.0	0.0	0.0	7.0	3.20
DISPENSER	1090702	14	1	0	183.8	147.1	47.8	0.0	0.0	0.0	0.0	0.0	0.00
INPRD WIRE	1090703	13	1	1	193.8	167.3	47.9	0.0	0.0	3.0	0.0	-7.2	7.72
INPRD WIRE	1090703	13	1	1	2822.8	0.0	0.0	0.0	0.0	249.7	1416.1	0.0	0.16
INPRD WIRE	1090801	2	1	1	2822.8	0.0	0.0	0.0	0.0	-249.7	-1416.1	0.0	0.16

CUTTED WIRE	1790002	2	1	1	1114.2	0.0	0.0	0.1	0.0	346.4	1464.7	0.0	0.05
CUTTED WIRE	1790002	2	1	1	1114.2	0.0	0.0	0.1	0.0	-346.4	-1464.7	0.0	0.05
TIP MASS	1790003	5	1	5	0.0	0.0	0.0	0.1	0.0	443.2	2613.1	0.0	0.01
TIP MASS	1790003	5	1	5	0.0	0.0	0.0	0.1	0.0	-443.2	-2613.1	0.0	0.01
DISPENSE	1790004	1	1	1	9.8	7.3	5.5	0.0	0.0	-6.0	-20.0	0.0	5.28
DISPENSE	1790004	1	1	1	9.8	7.3	5.5	0.0	0.0	6.0	20.0	0.0	5.28
PWT CURTESY	1790011	11	1	1	0.0	12.0	0.0	0.5	0.0	-242.0	114.0	0.0	0.90
PWT HINGE	1790012	1	1	1	2.0	5.0	3.0	0.0	0.0	-250.0	117.0	0.0	1.10
S/C BALANCE	1790010	1	1	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
MAG BAL	1790011	3	1	1	0.0	0.5	0.0	4.5	0.0	237.0	-110.5	0.0	7.05
WAST	1790011	3	1	1	232.6	0.0	0.0	4.5	0.0	-130.0	60.6	0.0	2.32
ASTRO HLR	1790012	2	1	1	15.0	0.0	0.0	5.0	0.0	-17.6	8.6	0.0	11.68
WAST	1790011	3	1	1	0.0	232.0	0.0	4.5	0.0	130.0	-60.6	0.0	2.32
ASTRO MPUR	1790012	2	1	1	15.0	0.0	0.0	5.0	0.0	17.6	-8.6	0.0	11.68
WAST	1790011	3	1	1	255.0	0.0	0.0	0.1	0.0	-118.8	68.6	0.0	6.68
WAST	1790011	3	1	1	0.0	255.0	0.0	0.1	0.0	118.8	-68.6	0.0	6.68

SAFETY VALUES

[illegible]

DETECTOR	0.403	0.403	0.403	1
DETECTOR	0.403	0.403	0.403	1
MUT DAMPER	5032.100	5072.499	6512.500	13
ATT COIL	1930.750	1950.750	3471.500	13
AGENCY COIL	12726.500	7470.500	7470.500	13
PATCH DAMPER	0231.119	0231.131	8052.230	13
UPPER SOL AR	10116.602	10116.602	15901.301	13
LOWER SOL AR	10116.602	10116.602	15901.301	13
DATE 1	212.513	96.166	285.600	1
PATT 2	04.316	272.570	285.600	1
FOR SUPPL FL	2.1.743	547.296	507.300	1
RE-INST LONDR	30.017	46.281	57.600	1
SPONDR CABLE	P.146	14.709	17.459	1
ANT AN ANT-SH	1.779	1.779	0.700	0
ANT MASTER	200.456	200.456	0.280	12
SOFTLY TURN	10.953	6.375	13.663	1
PRENO PROC	90.549	13.256	23.591	1
CYE	93.791	173.454	143.700	1
COIL	112.545	140.472	119.025	1
RTM	113.456	87.535	92.675	1
TP ACORBI	145.750	296.817	350.167	1
TP ACORBI	145.750	296.817	350.167	1
S/C MAR 100	21.27.492	21.27.492	20210.702	4
SELSOR	9.000	9.000	9.000	1
ELECTRONICS	02.501	76.186	71.052	1
THAIL PLMT	0.0	0.0	0.0	1
PRESSES	1.549	0.210	0.000	1
PREAMPS	0.549	0.210	0.000	1
PREAMPS	2.210	0.569	0.000	1
PREAMPS	2.210	0.569	0.000	1
ELECTRONICS	356.270	356.270	312.000	1
SHORT EL 107	0.003	7.201	7.201	10
SM EL ANT AL	1.000	0.052	1.176	1
SEARCH COIL	0.421	0.421	0.002	12
SRCH COIL EL	0.254	0.254	0.000	1
LOOP ANTENNA	106.087	106.087	0.070	4
LOOP ANTENNA	140.047	140.047	0.070	4
LOOP ANTENNA	49.444	49.444	49.444	3
LOOP ANTENNA	49.444	49.444	49.444	3
VIS 3F-90A	450.440	627.100	555.440	13
VIS 3F-90C	450.440	627.100	555.440	13
MOV SENSOR	450.440	627.100	555.440	13
DCU	4.049	6.379	2.652	1
ELECTRONICS	49.440	52.455	75.575	1
DEF ASSY	31.237	36.963	51.297	1
WVPS	11.592	8.742	12.762	1
PFS	23.150	17.445	25.526	1
RAD SHLD	7.322	5.281	7.328	1
CABLES	9.061	2.914	4.254	1
ELECTRONICS	45.113	27.563	47.813	1
SENSOR	4.225	30.856	55.581	1
SENSOR	30.925	30.956	55.581	1
SENSGH	70.756	32.452	53.164	1
EIC	270.120	440.120	518.690	13
TUBE ANTENNA	550.075	550.075	0.153	12
TUBE ANTENNA	550.075	550.075	0.153	12
DISPENSER	193.800	167.300	97.900	13
DISPENSER	193.800	167.300	97.900	13
IMPRD WIRE	0.001	106240.875	106240.875	2
IMPRD WIRE	0.001	106240.875	106240.875	2

OUTERD WIRE	0.000	5172.391	5172.391	2
OUTERD WIRE	0.100	5172.391	5172.391	2
TIP MASS	0.000	0.000	0.000	5
TIP MASS	0.100	0.000	0.000	5
DISPENSER	36.747	55.535	65.658	1
DISPENSER	36.747	55.535	65.658	1
PRI SUBASSY	10.012	0.725	10.012	11
PRI WIRE	3.117	1.152	2.658	1
S/C BALANCE	112.933	112.933	112.933	1
WAG PAL	34.007	77.456	35.887	3
WAST	23.437	1,017.711	1,017.711	2
ASIMO MIDIR	110.000	242.302	242.302	2
WAST	1,017.711	23.490	1,017.711	3
ASTRO WTR	106.000	292.000	292.000	2
HARNESSEWEL	0.055	15,221.898	15,221.898	2
HARNESSEWAG	9670.000	0.014	9670.000	3

ORIGINAL PAGE IS
OF POOR QUALITY

**DYNAMICS EXPLORER DE-A
MOMENT OF INERTIA CALCULATIONS
BOX AXIS ROTATION FOR NONPARALLEL AXES**

[illegible]

[illegible]

OUTING JIRE	516.918	155.760	5172.391	884.533	0.000	0.002	88.0	175.0	90.0	90.0
OUTING JIRE	519.414	155.764	5172.391	884.533	0.000	0.002	80.0	175.0	96.0	96.0
TIP PASS	6.000	0.000	0.000							
TIP PASS	6.000	0.000	0.000							
DISPENSE	30.000	37.504	65.668	3.215	-0.000	0.000	80.0	175.0	96.0	96.0
DISPENSE	30.000	37.504	65.668	3.215	-0.000	0.000	80.0	175.0	96.0	96.0
P41 SUBADSY	2.134	0.000	10.012	-0.000	-0.000	0.000	65.0	155.0	90.0	90.0
P41 MISC	1.000	0.000	0.000	-0.000	-0.000	0.000	65.0	155.0	90.0	90.0
S/C BALANCE	112.000	112.000	112.000							
MAST TOL	10.000	10.000	10.000	10.000	0.000	-0.000	65.0	155.0	90.0	90.0
MAST	10.000	10.000	10.000	10.000	0.000	0.000	155.0	245.0	90.0	90.0
ASINO MUP	10.000	10.000	10.000	10.000	0.000	0.000	155.0	245.0	90.0	90.0
MAST	10.000	10.000	10.000	10.000	0.000	0.000	65.0	155.0	90.0	90.0
ASTRO MUP	10.000	10.000	10.000	10.000	0.000	0.000	65.0	155.0	90.0	90.0
MASTESS-201	10.000	10.000	10.000	10.000	0.000	0.000	155.0	245.0	90.0	90.0
MASTESS-201	10.000	10.000	10.000	10.000	0.000	0.000	65.0	155.0	90.0	90.0

3) * ASTERISK INDICATES THE TOTAL SUM OF THE MOMENTS OF FOX COMPONENTS

TY	NAME	144	145	122
101100	TEMP 50	7624.5791	5409.4781	8091.0590
101200	TEMP 10	5745.4336	5785.4336	8281.0080
101301	TEMP COL	487.3401	480.7525	354.8203
101302	TEMP 1	50.9212	480.7525	623.4470
101303	TEMP 2	501.2360	577.7798	664.8030
101304	TEMP 3	555.3216	223.3158	664.8030
101305	TEMP 4	580.9212	580.9212	623.7354
101306	TEMP 5	600.8059	547.4315	646.7720
101307	TEMP 6	555.3216	223.3158	564.8030
101308	TEMP 7	5475.6036	5475.6036	543.3370
101309	TEMP 8	5032.0002	5032.0002	100.3060
101310	TEMP 9	5091.0124	1031.4928	1034.4667
101311	TEMP 10	3.36.0760	3.36.0760	1155.1814
101312	TEMP 11	5091.0124	1031.4928	1034.4667
101313	TEMP 12	5730.0760	3.36.0760	1009.1814
101314	TEMP 13	5419.0002	5419.0002	11214.8164
101315	TEMP 14	413.3856	515.4380	787.5127
101316	TEMP 15	1376.5745	1376.5745	1223.0215
101317	TEMP 16	220.4201	220.4201	220.5134
101318	TEMP 17	455.5117	455.5117	430.8103
101319	TEMP 18	1521.0025	944.7812	977.2812
101320	TEMP 19	754.1250	944.1250	151.0700
101321	TEMP 20	1754.0165	623.4165	624.4665
101322	TEMP 21	144.3348	728.1405	114.4407
101323	TEMP 22	201.0171	138.0154	101.2956
101324	TEMP 23	174.7371	183.6602	100.1700
101325	TEMP 24	144.3547	219.0221	100.2900
101326	TEMP 25	236.7952	137.2171	105.9456
101327	TEMP 26	174.5058	120.0171	101.2956
101328	TEMP 27	144.3348	224.1905	104.4900
101329	TEMP 28	231.0171	136.3358	101.2956
101330	TEMP 29	174.7371	183.6602	100.1700
101331	TEMP 30	144.3548	219.0421	100.2900
101332	TEMP 31	236.7952	137.2171	105.9456
101333	TEMP 32	174.5058	120.0171	101.2956
101334	TEMP 33	144.3348	219.0421	100.2900
101335	TEMP 34	236.7952	137.2171	105.9456
101336	TEMP 35	174.5058	120.0171	101.2956
101337	TEMP 36	144.3348	219.0421	100.2900
101338	TEMP 37	236.7952	137.2171	105.9456
101339	TEMP 38	174.5058	120.0171	101.2956
101340	TEMP 39	144.3348	219.0421	100.2900
101341	TEMP 40	236.7952	137.2171	105.9456
101342	TEMP 41	174.5058	120.0171	101.2956
101343	TEMP 42	144.3348	219.0421	100.2900
101344	TEMP 43	236.7952	137.2171	105.9456
101345	TEMP 44	174.5058	120.0171	101.2956
101346	TEMP 45	144.3348	219.0421	100.2900
101347	TEMP 46	236.7952	137.2171	105.9456
101348	TEMP 47	174.5058	120.0171	101.2956
101349	TEMP 48	144.3348	219.0421	100.2900
101350	TEMP 49	236.7952	137.2171	105.9456
101351	TEMP 50	174.5058	120.0171	101.2956
101352	TEMP 51	144.3348	219.0421	100.2900
101353	TEMP 52	236.7952	137.2171	105.9456
101354	TEMP 53	174.5058	120.0171	101.2956
101355	TEMP 54	144.3348	219.0421	100.2900
101356	TEMP 55	236.7952	137.2171	105.9456
101357	TEMP 56	174.5058	120.0171	101.2956
101358	TEMP 57	144.3348	219.0421	100.2900
101359	TEMP 58	236.7952	137.2171	105.9456
101360	TEMP 59	174.5058	120.0171	101

DYNAMICS EXPLORER DE-A
S/C MOMENTS OF INERTIA
01 OCTOBER 1978 DEP 24ED

THE TOTALS BEFORE BALANCING ARE-

SUM OF WEIGHTS = 0.7849725E+03
SUM OF WEIGHT * X DISTANCE = -0.73439990E+03
SUM OF WEIGHT * Y DISTANCE = 0.27169336E+03
SUM OF WEIGHT * Z DISTANCE = -0.64699731E+03
SUM OF WEIGHT * X * Z DISTANCES = -0.11025671E+04
SUM OF WEIGHT * Y * Z DISTANCES = -0.51862961E+04
SUM OF WEIGHT * X * Y DISTANCES = -0.27835287E+06
SUM OF WEIGHT * X2 = 0.11689820E+07
SUM OF WEIGHT * Y2 = 0.14798020E+07
SUM OF WEIGHT * Z2 = 0.10464394E+06

SUM OF IX = 0.13477534E+06
SUM OF IY = 0.16559812E+06
SUM OF IZ = 0.43526312E+06

THE C.G. COMPONENTS ARE-- X = -0.940562E+00 Y = 0.346115E+00 Z = -0.824222E+00

SUM OF IX = 0.13362957E+05
SUM OF IY = 0.6420363E+02
SUM OF IZ = 0.6627422E+02

ORIGINAL PAGE IS
OF POOR QUALITY

ORIGINAL PAGE IS
OF POOR QUALITY

DYNAMICS EXPLORER DE-A
S/C MOMENTS OF INERTIA
31 OCTOBER 1978

S/C MOMENTS OF INERTIA ARE-

• THE FOLLOWING VALUES HAVE UNITS OF LM.-IN2

IXX=0.19185345E+07
IYY=0.14377940E+07
IZZ=0.30832420E+07
IXZ=-0.13111743E+06
IYZ=-0.00396062E+06
IYYZ=-0.26073425E+06
IMAX=0.23354281E+07
IMIN=0.13297630E+07

• THE FOLLOWING VALUES HAVE UNITS OF IN-LBS-SEC2

IXX=0.04963945E+04
IYY=0.37244566E+04
IZZ=0.25004054E+04
IXZ=-0.00326068E+01
IYZ=-0.12682780E+02
IYZ=-0.66532480E+03
IMAX=0.52735172E+04
IMIN=0.30213108E+04

INERTIA RATIO

I / I SPIN/ TRANSVERSE MAX = 1.515

APPENDIX C
DE-B STOWED MASS PROPERTIES
COMPUTER OUTPUT

DYNAMICS EXPLORER DE-8
SPACECRAFT CONFIGURATION REPORT SYSTEM
01 OCTOBER 1978

ID	DATE	NAME	LAUS-NO.	SOURCE	ZORP	PROPOSAL	TARGET	EST/ACT	WTOL	QTY
						WEIGHT	WEIGHT	WEIGHT		
1000000	11 17	DE-8	2294700-501		1-	0.0	0.0	0.0	0.0	1-
1010000	5 1 8	STRUCTURE-A-		AE-C	1-	136.98	165.80	0.0	0.0	1-
1010100	11 17	UPPER SP			1-	0.0	0.0	23.400	0.0	1-
1010200	11 17	LOWER SP			1-	0.0	0.0	22.800	0.0	1-
1010300	11 17	CEN COL/SH P			1-	0.0	0.0	0.0	0.0	1-
1010301	11 17	CENTER COL			1-	0.0	0.0	9.200	0.0	1-
1010302	11 17	S4R PAWL 1			1-	0.0	0.0	2.420	0.0	1-
1010303	11 17	S4R PAWL 2			1-	0.0	0.0	2.420	0.0	1-
1010304	11 17	S4R PAWL 3			1-	0.0	0.0	2.420	0.0	1-
1010305	11 17	S4R PAWL 4			1-	0.0	0.0	2.420	0.0	1-
1010306	11 17	S4R PAWL 5			1-	0.0	0.0	2.420	0.0	1-
1010307	11 17	S4R PAWL 6			1-	0.0	0.0	2.420	0.0	1-
1010500	11 17	SEP ATPT LJR			1-	0.0	0.0	15.300	0.0	1-
1010600	8 1 8	MAT UPPER			1-	0.0	0.0	0.0	0.0	1-
1010601	8 1 8	SIDES QU			1-	0.0	0.0	15.700	0.0	1-
1010602	8 1 8	END HU			1-	0.0	0.0	4.350	0.0	1-
1010700	8 1 8	MAT LOWER			1-	0.0	0.0	0.0	0.0	1-
1010701	8 1 8	SIDES HL			1-	0.0	0.0	15.700	0.0	1-
1010702	8 1 8	END HL			1-	0.0	0.0	4.350	0.0	1-
1010800	3 1 8	CENTER KING			1-	0.0	0.0	0.0	0.0	1-
1010801	3 1 8	RING			1-	0.0	0.0	6.500	0.0	1-
1010802	3 1 8	BRACKETS			1-	0.0	0.0	9.500	0.0	1-
1010900	11 17	4RA SUPPT CO			1-	0.0	0.0	3.400	0.0	1-
1011000	11 17	HARDWARE			1-	0.0	0.0	1.000	0.0	1-
1011100	11 17	PRINTS-MISC			1-	0.0	0.0	2.500	0.0	1-
1011200	11 17	COVERS-SEALS			1-	0.0	0.0	4.200	0.0	1-
1011300	11 17	LIFTING HOOK			1-	0.0	0.0	1.200	0.0	1-
1011400	11 17	RF SCRFEYS			1-	0.0	0.0	0.300	0.0	4-
1011500	11 17	WIRE BOX			1-	0.0	0.0	2.000	0.0	1-
1011600	1 1 8	ANTENNA SUPY			1-	0.0	0.0	0.0	0.0	1-
1011601	9 1 8	DUL GN RPD			1-	0.0	0.0	1.500	0.0	1-
1011602	1 1 8	HI GN BRGTRY			1-	0.0	0.0	2.500	0.0	1-
1011700	9 1 8	ATC BRACKETS			1-	0.0	0.0	0.335	0.0	4-
1020000	5 1 8	TEMPAL -A-			1-	10.40	10.50	0.0	0.0	1-
1020100	11 17	THR-UPR MAT			1-	0.0	0.0	0.0	0.0	1-
1020101	8 1 8	THR-UPR MAT			1-	0.0	0.0	3.750	0.0	1-
1020102	11 17	ATC-UPR MAT	2271611-503		1-	0.0	0.0	0.600	0.0	4-
1020300	11 17	THR-UPR P/P			1-	0.0	0.0	0.0	0.0	1-
1020301	8 1 8	TEMP SENS-UB			1-	0.0	0.0	0.240	0.0	1-
1020400	11 17	THR-LVR P/P			1-	0.0	0.0	0.0	0.0	1-
1020401	8 1 8	TEMP SENS-LB			1-	0.0	0.0	0.240	0.0	1-
1020402	8 1 8	THR-LVR S/P			1-	0.0	0.0	3.750	0.0	1-
1020500	11 17	TH HEATERS			1-	0.0	0.0	0.100	0.0	1-
1030000	5 1 8	ATT CONTN B			1-	99.70	100.10	0.0	0.0	1-
1030200	8 1 8	BATCH CON EL	2271623-501		1-	0.0	0.0	0.400	0.0	1-
1030300	8 1 8	SUT SENSOR			1-	0.0	0.0	0.0	0.0	1-
1030301	8 1 8	DETECTORS			1-	0.0	0.0	0.009	0.0	2-
1030302	8 1 8	ELECTRONICS			1-	0.0	0.0	1.100	0.0	2-
1030400	11 17	NUT OPR+COIL			1-	0.0	0.0	0.0	0.0	1-
1030401	11 17	NUT DAMPER			1-	0.0	0.0	16.400	0.0	1-

Part Number	Part Name	QTY	Unit Price	Total Price	Notes
1030402	8 1 6 RYV COIL	1	0.00	0.00	
1030500	8 1 6 PITCH COIL	1	0.00	0.00	
1030700	8 1 6 R24 JML ASSY	1	0.00	0.00	
1030701	8 1 6 MOTOR ASSY	1	0.00	0.00	
1030702	8 1 6 INERTIA WML	1	0.00	0.00	
1030800	11 1 7 WML MOR SENS	1	0.00	0.00	
1030900	11 1 7 WFA SHIELD	1	0.00	0.00	
1040000	5 1 8 POWER	1	120.10	120.10	
1040100	11 1 7 UPPER SOL AR	1	0.00	0.00	
1040101	8 1 6 CELL MODULES	1	0.00	0.00	
1040102	8 1 6 SHUNT WIRING	1	0.00	0.00	
1040103	8 1 6 DIODES	1	0.00	0.00	
1040200	11 1 7 LOWER SOL AR	1	0.00	0.00	
1040201	8 1 6 CELL MODULES	1	0.00	0.00	
1040202	8 1 6 SHUNT WIRING	1	0.00	0.00	
1040203	8 1 6 DIODES	1	0.00	0.00	
1040300	11 1 7 BATTERIES	1	0.00	0.00	
1040301	3 1 6 BATT 1	1	0.00	0.00	
1040302	3 1 6 BATT 2	1	0.00	0.00	
1040400	11 1 7 P4 SUPPL EL	1	0.00	0.00	
1050000	5 1 8 CONNECTORS-B-	1	24.36	24.36	
1050100	3 1 6 TORSX XORDN	1	0.00	0.00	
1050300	11 1 7 XORDR CABLE	1	0.00	0.00	
1050500	3 1 6 LOG GAIN ANT	1	0.00	0.00	
1050600	3 1 6 W/2 GAIN ANT	1	0.00	0.00	
1050800	11 1 7 S4-FLY NTWRK	1	0.00	0.00	
1050900	11 1 7 PREMOD PROC	1	0.00	0.00	
1060000	5 1 8 C V WH	1	53.10	53.10	
1060100	11 1 7 CTP	1	0.00	0.00	
1060200	11 1 7 CNU	1	0.00	0.00	
1060300	11 1 7 RIV	1	0.00	0.00	
1060400	3 1 6 TAPE RECORDER	1	0.00	0.00	
1060500	3 1 6 S/C HARNESS	1	0.00	0.00	
1080100	10 1 6 UPPER HARN	1	0.00	0.00	
1080200	10 1 6 LOWER HARN	1	0.00	0.00	
1080300	10 1 6 GROUND BLOCK	1	0.00	0.00	
1080400	11 1 7 GROUND BLOCK	1	0.00	0.00	
1080500	11 1 7 POTTING	1	0.00	0.00	
1080600	11 1 7 CLAMPS	1	0.00	0.00	
1080700	11 1 7 WAT	1	0.00	0.00	
1080800	11 1 7 GRND STRAP	1	0.00	0.00	
1090000	5 1 8 SFE DE-B	2	150.92	301.84	
1090100	5 1 8 V-F	2	0.00	0.00	
1090101	10 1 6 TUBULAR ANT	2	0.00	0.00	
1090102	5 1 6 PREAMPS	2	0.00	0.00	
1090103	5 1 6 ELECTRONICS	2	0.00	0.00	
1090104	10 1 6 DISPENSER	2	0.00	0.00	
1090200	5 1 8 MAG	2	0.00	0.00	
1090201	10 1 6 SENSOR	2	0.00	0.00	
1090202	10 1 6 ELECTRONICS	2	0.00	0.00	
1090203	8 1 6 T-RML BLNKT	2	0.00	0.00	
1090300	5 1 8 ION	2	0.00	0.00	
1090301	8 1 6 ELECTRONICS	2	0.00	0.00	
1090302	8 1 6 SENSOR	2	0.00	0.00	
1090400	5 1 8 LAPT	2	0.00	0.00	
1090401	5 1 8 DETECTORS	2	0.00	0.00	
1090402	8 1 6 SCAN PLATE	2	0.00	0.00	
1090403	8 1 6 TYP PLATE	2	0.00	0.00	
1090405	8 1 6 MOVRE	2	0.00	0.00	
1090407	8 1 6 CABLING	2	0.00	0.00	

DYNAMICS EXPLORER DE-B
 WEIGHT SUMMARY BY LEVELS
 01 OCTOBER 1978

ID	NAME	PROPOSAL WEIGHT	CURRENT TARGET WEIGHT	CURRENT ESTIMATED ACT WT	QTY	DRWG NO	SOURCE
1000000	DE-B	617.38	696.70	797.391	1.	2294700-501	
1010000	STRUCTURE-B-	136.38	125.80	162.120	1.		AE-C
1010100	UPPER RP	0.0	0.0	23.400	1.		
1010200	LOWER BP	0.0	0.0	22.800	1.		
1010300	CEN COL/SH P	0.0	0.0	23.720	1.		
1010301	CENTER COL	0.0	0.0	9.200	1.		
1010302	S-R PNL 1	0.0	0.0	2.420	1.		
1010303	SHR PNL 2	0.0	0.0	2.420	1.		
1010304	SHR PNL 3	0.0	0.0	2.420	1.		
1010305	SHR PNL 4	0.0	0.0	2.420	1.		
1010306	SHR PNL 5	0.0	0.0	2.420	1.		
1010307	SHR PNL 5	0.0	0.0	2.420	1.		
1010500	SCP ATPT LVR	0.0	0.0	15.300	1.		
1010600	MAT UPPER	0.0	0.0	20.050	1.		
1010601	SIDES HU	0.0	0.0	15.700	1.		
1010602	EYD HU	0.0	0.0	4.350	1.		
1010700	MAT LOWER	0.0	0.0	20.850	1.		
1010701	SIDES HL	0.0	0.0	15.700	1.		
1010702	END HL	0.0	0.0	4.350	1.		
1010800	CENTER RING	0.0	0.0	16.000	1.		
1010801	RING	0.0	0.0	6.500	1.		
1010802	BRACKETS	0.0	0.0	9.500	1.		
1010900	VVA SUPPLY CO	0.0	0.0	3.400	1.		
1011000	HARDWARE	0.0	0.0	1.000	1.		
1011100	BRKTS-MISC	0.0	0.0	2.500	1.		
1011200	COVERS-SEALS	0.0	0.0	4.200	1.		
1011300	LIFTING MDJR	0.0	0.0	1.200	1.		
1011400	RF SCREENS	0.0	0.0	1.200	1.		
1011500	MDJRE BOX	0.0	0.0	2.000	1.		
1011600	ANTENNA SUPT	0.0	0.0	4.000	1.		
1011601	DUL 6N B/P	0.0	0.0	1.500	1.		
1011602	HY GN BRGTRY	0.0	0.0	2.500	1.		
1011700	ATC BRACKETS	0.0	0.0	1.340	4.		
1020000	THERMAL -R-	10.00	10.50	10.400	1.		
1020100	THR-UPR MAT	0.0	0.0	6.150	1.		
1020101	THR-UPR MAT	0.0	0.0	3.750	1.		
1020102	ATC-UPR MAT	0.0	0.0	2.400	4.	2271611-503	
1020300	THR-UPR M/S	0.0	0.0	8.240	1.		
1020301	TEMP SENS-UR	0.0	0.0	0.240	1.		
1020400	THR-LVR R/P	0.0	0.0	3.990	1.		
1020401	TEMP SENS-LB	0.0	0.0	0.240	1.		
1020402	THR-LVR B/P	0.0	0.0	3.750	1.		
1020500	TM HEATERS	0.0	0.0	0.100	1.		
1030000	ATT CONTR B	99.70	100.10	92.600	1.	2271623-501	
1030200	PITCH CON EL	0.0	0.0	8.400	1.		
1030300	SUN SENSOR	0.0	0.0	3.800	1.		
1030301	DETECTORS	0.0	0.0	1.600	2.		
1030302	ELECTRONICS	0.0	0.0	2.200	2.		
1030400	NUT DPR-COIL	0.0	0.0	28.400	1.		

1039401	MUT DAMPER	0.0	0.0	16.400	1.
1039402	ATT COIL	0.0	0.0	12.000	2.
1039500	PITCH COIL	0.0	0.0	3.000	1.
1039700	NON JHL ASSY	0.0	0.0	44.600	1.
1039701	MOTOR ASSY	0.0	0.0	22.300	1.
1039702	INERTIA W-L	0.0	0.0	22.300	1.
1039800	MHL HDR SEVS	0.0	0.0	2.000	1.
1039900	MMA SHIELD	0.0	0.0	2.400	1.
1040000	POWER	120.10	127.10	130.910	1.
1040100	UPPER SOL AR	0.0	0.0	29.860	1.
1040101	CELL MODULES	0.0	0.0	26.090	1.
1040102	SHUNT WIRING	0.0	0.0	2.850	1.
1040103	DIODES	0.0	0.0	0.920	1.
1040200	LOWER SOL AR	0.0	0.0	35.850	1.
1040201	CELL MODULES	0.0	0.0	30.620	1.
1040202	SHUNT WIRING	0.0	0.0	3.350	1.
1040300	DIODES	0.0	0.0	1.000	1.
1040301	BATTERIES	0.0	0.0	43.400	1.
1040302	BATT 1	0.0	0.0	21.700	1.
1040303	BATT 2	0.0	0.0	21.700	1.
1040400	PWR SUPPL EL	0.0	0.0	22.600	1.
1050000	CONVEYNS-B-	24.36	33.20	33.200	1.
1050100	TORSS XDRDR	0.0	0.0	15.900	1.
1051300	XPDRDR CABLE	0.0	0.0	2.300	1.
1050500	LOJ SAIN AVT	0.0	0.0	1.400	1.
1050600	MI. GAIN AVT	0.0	0.0	7.100	1.
1050601	SW+FLT MT-RK	0.0	0.0	2.100	1.
1050900	PREMOD PRCC	0.0	0.0	4.400	1.
1060000	C & DM	53.10	62.30	62.300	1.
1060100	CTP	0.0	0.0	9.100	1.
1060200	CUU	0.0	0.0	10.800	1.
1060300	PT4	0.0	0.0	6.400	1.
1060400	TAPE RECDRR	0.0	0.0	34.000	2.
1060600	S7C HARNESS	0.0	0.0	64.700	1.
1080100	UPPER HARN	0.0	0.0	27.500	1.
1080200	LOWER HARN	0.0	0.0	27.500	1.
1080300	GROUND BLOCK	0.0	0.0	0.400	1.
1080400	GROUND BLOCK	0.0	0.0	0.300	1.
1080500	POTTING	0.0	0.0	1.000	1.
1080600	CLAMPS	0.0	0.0	1.000	1.
1080700	HAT	0.0	0.0	5.500	1.
1080800	GRND STRAP	0.0	0.0	1.500	1.
1090000	GFL DE-B	150.32	122.10	172.348	1.
1090100	VCF	0.0	9.90	59.100	1.
1090101	TUPULAR AVT	0.0	0.0	10.716	6.
1090102	PREAMPS	0.0	0.0	3.300	6.
1090103	ELECTRONICS	0.0	0.0	6.600	1.
1090104	DISPENSER	0.0	0.0	38.484	6.
1090200	IAS	0.0	7.10	8.148	1.
1090201	SENSOR	0.0	0.0	1.610	1.
1090202	ELECTRONICS	0.0	0.0	6.538	1.
1090203	T-RHL BLNCT	0.0	0.0	0.0	1.
1090300	IDM	0.0	7.30	7.500	1.
1090301	ELECTRONICS	0.0	0.0	4.070	1.
1090302	SENSOR	0.0	0.0	3.430	1.
1090400	LAPI	0.0	30.00	30.000	1.
1090401	DETECTORS	0.0	0.0	9.300	1.
1090402	SCAN PLATE	0.0	0.0	2.300	1.
1090403	TOP PLATE	0.0	0.0	0.000	1.
1090406	MDVRE	0.0	0.0	0.500	1.

4.16.8-1

2294670-501
2294673-501
2294671-501

2295147-502
2294647-502
2294747-502

2295130-2
2295130-1

2295124-2
2295124-1

2295130-1
2295130-2
2295135-1

109387	CABLEING	0.0	0.0	11.500	1.
109388	PPS	0.0	0.0	4.000	2.
109389	MVS	0.0	0.0	2.400	2.
109390	EPD SYST	0.0	0.0	0.500	1.
109391	CEP	0.0	0.0	6.000	1.
109392	MV DISTR	0.0	0.0	1.000	1.
109393	1-1R BLKRY	0.0	0.0	0.200	1.
109394	MAG SENSOR	0.0	0.0	0.750	1.
109395	MAG DEPLOYER	0.0	0.0	0.750	1.
109396	MICS	0.0	+	17.000	1.
109397	ELECTRONICS	0.0	0.0	6.000	1.
109398	INSTRUMENT	0.0	0.0	10.100	1.
109399	COVER	0.0	0.0	0.892	1.
109400	FPI	0.0	+	19.000	1.
109401	ELECTRONICS	0.0	0.0	5.000	1.
109402	INSTRUMENT	0.0	0.0	12.625	1.
109403	CABLEING	0.0	0.0	0.200	1.
109404	COVER	0.0	0.0	0.375	1.
109405	WAYS	0.0	+	17.000	1.
109406	ELECTRONICS	0.0	0.0	8.000	1.
109407	SENSOR	0.0	0.0	8.100	1.
109408	COVER	0.0	0.0	0.692	1.
109409	LANG	0.0	+	6.000	1.
109410	SIG PROC	0.0	0.0	3.900	1.
109411	FILTER BOX	0.0	0.0	1.000	2.
109412	LATCH	0.0	0.0	0.400	2.
109413	PROBE	0.0	0.0	0.500	2.
109414	CABLEING	0.0	0.0	0.200	1.
109415	RPA	0.0	+	8.600	1.
109416	ELECTRONICS	0.0	0.0	4.800	1.
109417	SENSOR	0.0	0.0	3.800	1.
109418	BALANCE -9-	0.0	+	25.000	1.
109419	S/C BALANCE	0.0	0.0	20.810	1.
109420	MAG BAL	0.0	0.0	4.190	1.
109421	SUPPLY EQUIP	22.50	+	43.700	1.
109422	BOOMS	22.50	+	14.000	1.
109423	ASTRONAUT	0.0	0.0	2.325	1.
109424	ASTRO HOUR	0.0	0.0	11.677	1.
109425	HARNESS MAG	0.0	0.0	1.600	1.
109426	SEAN PLATFHM	0.0	+	28.100	1.
109427	MTG PLATE	0.0	0.0	9.400	1.
109428	DRIVE	0.0	0.0	9.400	1.
109429	IFCE ELECTN	0.0	0.0	3.500	1.
109430	DRIVE ELECTN	0.0	0.0	5.800	1.
109431	ENC REVISION	0.0	0.0	0.0	1.

2295131-2

2295131-1

2295133-1

2295132-1

2295132-3

2295137

2295134-1

2295134

DYANICS EXPLORER BE-3
 ZONE AND PHASE SUMMARY
 01 OCTOBER 1978

ZONE	PROPOSAL WEIGHT	CURRENT	
		TARGET WEIGHT	ESTIMATED WEIGHT
1	457.06	549.60	600.046
2	156.92	122.10	172.348
3	0.0	25.00	25.000

PHASE	PROPOSAL WT	CURRENT	
		TARGET WT	EST/ACT WT
TOTAL SYSTEM LAUNCH WEIGHT INCL BAL WT	617.98	696.70	797.394
SPACECRAFT HARDWARE WEIGHT INCL BAL	467.06	549.60	600.046
GF INSTRUMENTATION WEIGHT	150.92	122.10	172.348
TOTAL BALANCE WEIGHT	0.0	25.00	25.000

ORIGINAL PAGE IS
 OF POOR QUALITY

DIANIES EXPLORE DE-3
INPUT MOMENT OF INERTIA AND C.G. INFORMATION
31 OCTOBER 1978

NOMENCLATURE	ID.NO.	TP	NO	PA	LX/IXX	LY/IYY	LZ/IZZ	RAD.O	RAD.I	FBAR	YBAR	ZBAR	WEIGHT
UPPER RP	1010100	13	1	0	4145.9	4145.9	8291.0	0.0	0.0	0.0	0.0	-0.5	23.40
LOWER RP	1010200	13	1	0	4145.9	4145.9	8291.0	0.0	0.0	0.0	0.0	0.5	22.00
CENTER CGL	1010301	13	1	0	430.3	458.3	354.3	0.0	0.0	0.0	0.0	0.0	9.20
SMR PAWL 1	1010302	1	1	1	17.9	0.1	16.8	0.0	0.0	-15.2	0.0	0.0	2.42
SMR PAWL 2	1010303	1	1	0	18.9	0.1	16.8	0.0	0.0	-7.8	13.6	0.0	2.42
SMR PAWL 3	1010304	1	1	1	18.9	0.1	16.8	0.0	0.0	7.8	13.6	0.0	2.42
SMR PAWL 4	1010305	1	1	1	17.9	0.1	16.8	0.0	0.0	15.2	0.0	0.0	2.42
SMR PAWL 5	1010306	1	1	1	18.9	0.1	16.8	0.0	0.0	7.8	-13.6	0.0	2.42
SMR PAWL 6	1010307	1	1	1	18.9	0.1	16.8	0.0	0.0	-7.8	-13.6	0.0	2.42
SEP ATPT LWR	1010500	13	1	0	1346.2	1346.2	569.3	0.0	0.0	0.0	0.0	0.0	15.30
SIDES PU	1010601	9	1	0	0.0	0.0	20.9	26.6	26.2	0.0	0.0	-12.5	15.70
SIDES HL	1010701	9	1	0	0.0	0.0	0.5	26.6	26.2	0.0	0.0	-22.5	4.35
END HL	1010702	9	1	0	0.0	0.0	0.5	26.6	26.2	0.0	0.0	22.5	15.70
CENTER RING	1010800	9	1	0	0.0	0.0	3.0	26.5	26.4	0.0	0.0	0.0	16.00
VLA SUPPLY CO	1010900	13	1	0	59.1	59.1	73.6	0.0	0.0	0.0	0.0	-13.1	3.40
GRKTS-MISC	1011100	9	1	0	0.0	0.0	4.0	25.0	9.0	0.0	0.0	0.0	2.50
COVERS-SEALS	1011200	9	1	0	0.0	0.0	17.5	25.0	9.0	0.0	0.0	0.0	4.20
LIFTING MOWA	1011300	12	1	0	0.0	0.0	4.0	25.0	0.0	0.0	0.0	0.0	1.20
RF SCREENS	1011400	4	1	0	0.0	0.0	0.1	10.3	0.0	11.0	11.0	-22.5	0.30
RF SCREWS	1011400	4	1	0	0.0	0.0	0.1	10.3	0.0	-11.0	-11.0	-22.5	0.30
RF SCREWS	1011400	4	1	0	0.0	0.0	0.1	10.3	0.0	-11.0	-11.0	-22.5	0.30
NORE 60	1011500	9	0	0	0.0	0.0	20.0	25.0	9.0	0.0	0.0	0.0	2.00
DUL G4 BPD	1011601	13	1	0	378.1	378.1	264.7	0.0	0.0	0.0	0.0	-09.5	1.50
HI GN BRGY	1011602	1	1	0	3.0	1.0	6.0	0.0	0.0	0.0	-23.5	-25.5	2.50
ATC BRACKETS	1011700	4	1	0	0.0	0.0	0.7	1.5	0.0	11.0	11.0	-21.5	0.33
ATC BRACKETS	1011700	4	1	0	0.0	0.0	0.7	1.5	0.0	-11.0	-11.0	-21.5	0.33
ATC BRACKETS	1011700	4	1	0	0.0	0.0	0.7	1.5	0.0	-11.0	-11.0	-21.5	0.33
ATC BRACKETS	1011700	4	1	0	0.0	0.0	0.7	1.5	0.0	11.0	11.0	-21.5	0.33
TMB-UPR 1AT	1020101	9	1	0	0.0	0.0	20.9	25.0	24.9	0.0	0.0	-10.4	3.75
ATC-UPR MAT	1020102	4	1	0	0.0	0.0	0.7	10.3	0.0	11.0	11.0	-22.0	0.60
ATC-UPR MAT	1020102	4	1	0	0.0	0.0	0.7	10.3	0.0	-11.0	-11.0	-22.0	0.60
ATC-UPR MAT	1020102	4	1	0	0.0	0.0	0.7	10.3	0.0	-11.0	-11.0	-22.0	0.60
TEMP SENS-UB	1020301	1	1	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	-0.4	0.20
TEMP SENS-LR	1020401	1	1	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.24	0.24
TMB-LVR B/P	1020402	13	1	0	960.9	960.9	1509.1	0.0	0.0	0.0	0.0	17.5	3.75
TH HEATERS	1020500	1	1	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.10
PITCH CBN EL	1030200	1	1	1	8.3	5.9	7.9	0.0	0.0	7.4	19.1	-3.9	0.40
DETECTORS	1030301	1	1	0	2.0	2.0	2.0	0.0	0.0	24.0	12.0	21.0	0.00
DETECTORS	1030301	1	1	0	2.0	2.0	2.0	0.0	0.0	24.0	12.0	-21.0	0.00
ELECTRONICS	1030302	1	1	0	2.0	2.0	2.0	0.0	0.0	14.5	11.5	-9.8	1.10
ELECTRONICS	1030302	1	1	0	2.0	2.0	2.0	0.0	0.0	18.5	11.5	9.6	1.10
PITCH COIL	1030401	13	1	0	6732.7	3518.2	3512.9	0.0	0.0	-14.0	0.0	0.0	16.00
PITCH COIL	1030402	13	1	0	1950.7	1950.7	3501.5	0.0	0.0	0.0	0.0	7.5	6.00
PITCH COIL	1030500	13	1	0	1231.6	722.9	722.9	0.0	0.0	-14.0	0.0	0.0	3.00
MOTOR ARSY	1030701	4	1	0	0.0	0.0	12.0	3.3	0.0	0.0	0.0	-16.5	2.30
INERTIA HPL	1030702	13	1	0	1227.8	1227.8	2441.6	0.0	0.0	0.0	0.0	-20.0	22.30
HL MGR SEAS	1030800	4	1	0	0.0	0.0	12.0	3.3	0.0	0.0	0.0	-16.5	2.00
VLA SHILO	1030901	4	1	0	0.0	0.0	12.0	3.3	0.0	0.0	0.0	-16.5	2.00
UPPER SOL AR	1040100	9	1	0	0.0	0.0	21.0	26.4	26.3	0.0	0.0	-12.0	29.00
LOWER SOL AR	1040200	13	1	0	13067.9	13067.9	2016.5	0.0	0.0	0.0	0.0	10.0	35.00

BATT 1	1045301	1	1	0	5.4	11.3	4.8	0.0	0.0	-2.0	16.0	-5.4	21.78
BATT 2	1049372	1	1	0	11.3	5.4	4.4	0.0	0.0	-17.0	4.5	-5.4	21.78
PJR SUPPL EL	1049493	1	1	0	10.6	7.5	0.0	0.0	0.0	0.0	-20.0	-2.4	22.48
TDRSS XDRR	1050186	1	1	0	6.3	13.9	4.3	0.0	0.0	3.9	-17.5	-10.5	16.70
XPNOR CABLE	1050300	1	1	0	6.3	13.9	4.3	0.0	0.0	3.9	-17.5	-10.5	2.30
LOW GAIN ANT	1050500	4	1	0	0.0	0.0	3.0	1.3	0.0	0.0	0.0	-27.0	1.40
HI. GAIN ANT	1050600	1	1	0	28.0	7.0	2.0	0.0	0.0	0.0	-26.0	-25.3	7.10
SU-FLY TURN	1050800	1	1	0	6.3	13.9	4.3	0.0	0.0	0.0	-14.5	-10.5	2.10
PHMOD PROC	1053500	1	1	0	6.3	4.0	3.0	0.0	0.0	-0.3	20.9	-10.0	4.40
CTP	1060180	1	1	0	6.0	12.3	6.0	0.0	0.0	-11.3	2.9	-13.1	9.10
CPU	1060200	1	1	0	6.9	9.2	0.0	0.0	0.0	10.5	16.0	13.1	10.00
RTM	1061300	1	1	0	9.2	6.9	0.0	0.0	0.0	-3.5	10.5	13.1	6.40
TAPE RECORDER	1060400	1	1	0	9.0	13.0	6.0	0.0	0.0	12.5	0.0	11.0	17.00
TAPE RECORDER	1063400	1	1	0	9.0	13.0	6.0	0.0	0.0	-12.5	0.0	11.0	17.00
UPPER HARN	1043100	12	1	0	0.0	0.0	4.0	0.0	25.0	0.0	0.0	-10.6	27.50
LOWER HARN	1046200	12	1	0	0.0	0.0	4.0	0.0	25.0	0.0	0.0	0.0	27.50
GROUND CLOCK	1063500	9	1	0	0.0	0.0	4.0	0.0	25.0	0.0	0.0	-10.6	6.40
GROUND CLOCK	1063600	9	1	0	0.0	0.0	4.0	0.0	25.0	0.0	0.0	0.0	6.40
POTTING	1060500	9	1	0	0.0	0.0	4.0	0.0	25.0	0.0	0.0	-10.6	1.00
CLAMPS	1043500	9	1	0	0.0	0.0	4.0	0.0	25.0	0.0	0.0	0.0	1.00
HAT	1040700	9	1	0	0.0	0.0	4.0	0.0	25.0	0.0	0.0	0.0	5.50
GRND STRAP	1040800	9	1	0	0.0	0.0	4.0	0.0	25.0	0.0	0.0	-10.6	1.50
PREAMPS	1090102	1	1	0	3.0	2.5	1.3	0.0	0.0	-21.7	-5.2	9.4	0.55
PREAMPS	1090102	1	1	0	3.0	2.5	1.3	0.0	0.0	-21.7	-5.2	9.4	0.55
PREAMPS	1090102	1	1	1	3.0	2.5	1.3	0.0	0.0	10.5	11.5	7.1	0.55
PREAMPS	1090102	1	1	1	2.5	3.0	1.3	0.0	0.0	13.5	-10.4	-7.1	0.55
PREAMPS	1090102	1	1	1	3.0	2.5	1.3	0.0	0.0	-10.5	-11.5	7.1	0.55
PREAMPS	1090102	1	1	1	2.5	3.0	1.3	0.0	0.0	-10.5	-11.5	-7.1	0.55
ELECTRONICS	1090103	1	1	0	0.0	9.4	7.5	0.0	0.0	2.0	-10.5	12.5	6.60
DISPENSE	1090104	13	1	0	13.0	167.3	47.9	0.0	0.0	-21.0	0.0	-15.4	6.01
DISPENSE	1090104	13	1	1	13.0	167.3	47.9	0.0	0.0	-21.0	0.0	15.4	6.01
DISPENSE	1090104	13	1	1	76.7	196.5	140.9	0.0	0.0	11.0	-11.0	0.0	6.01
DISPENSE	1090104	13	1	1	76.7	196.5	140.9	0.0	0.0	-11.0	11.0	0.0	6.01
DISPENSE	1090104	13	1	1	76.7	196.5	140.9	0.0	0.0	11.0	11.0	0.0	6.01
SENSOR	1090201	1	1	0	3.0	6.7	6.7	0.0	0.0	-20.0	-6.2	0.0	1.61
ELECTRONICS	1090202	1	1	0	7.0	0.5	6.1	0.0	0.0	-7.5	-12.0	11.6	6.54
THRYL HLRY	1090203	1	1	0	7.0	0.5	6.1	0.0	0.0	-7.5	-12.0	11.6	0.0
ELECTRONICS	1090301	1	1	0	7.3	5.0	6.3	0.0	0.0	13.0	2.0	11.0	9.07
SENSOR	1090302	1	1	0	3.0	5.0	9.7	0.0	0.0	24.0	3.4	13.5	3.03
DETECTORS	1090401	0	1	0	0.0	0.0	6.5	0.0	0.0	0.0	0.0	20.0	9.30
SCAN PLATE	1090402	4	1	0	0.0	0.0	0.4	0.0	0.0	3.0	0.0	23.0	2.10
TOP PLATE	1090403	4	1	0	0.0	0.0	0.3	7.0	0.0	0.0	0.0	32.2	0.80
WJURE	1070405	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	0.50
CABLING	1050407	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	1.50
PPS	1090408	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	2.00
PPS	1090408	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	2.00
WUPS	1090409	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	2.00
WUPS	1090409	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	2.00
WUPS	1090409	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	2.00
EPD SYST	1090410	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	1.20
CEP	1090411	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	0.50
WV DISTR	1090412	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	6.00
THR BLKMT	1090413	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	1.00
YAG SENSOR	1090414	4	1	0	0.0	0.0	6.5	6.5	6.5	0.0	0.0	20.1	0.20
YAG DEPLEYER	1090415	12	1	0	0.0	0.0	12.0	0.0	0.0	0.0	0.0	32.5	0.75
ELECTRONICS	1090501	1	1	0	7.0	7.0	7.0	0.0	0.0	20.1	4.2	-4.2	6.00
INSTRUMENT	1090502	1	1	0	11.5	6.9	6.0	0.0	0.0	10.0	-3.6	-3.6	10.11
ELECTRONICS	1090601	1	1	0	7.0	5.0	6.0	0.0	0.0	0.0	22.6	-11.0	9.60
INSTRUMENT	1090602	13	1	1	405.3	950.0	932.9	0.0	0.0	10.5	12.7	-10.3	12.63
CABLING	1090603	1	1	0	7.0	5.0	6.0	0.0	0.0	0.0	22.6	-11.0	9.60

ELECTRONICS	1090701	1	1	0	7.0	7.0	7.0	0.0	0.0	11.3	11.0	-13.2	0.00
SENSOR	1090702	1	1	0	10.5	7.0	0.0	0.0	0.0	19.9	-2.6	-13.0	0.00
SIG PROC	1090801	1	1	0	6.0	5.5	0.0	0.0	0.0	11.3	-17.9	11.1	3.00
FILTER BOX	135-502	1	1	0	4.5	2.0	0.0	0.0	0.0	1.0	26.1	10.3	0.00
FILTER BOX	1090802	1	1	0	4.5	2.0	0.0	0.0	0.0	1.0	-26.1	10.3	0.00
LATCH	1090803	1	1	0	4.5	2.0	0.0	0.0	0.0	1.0	26.1	10.3	0.00
LATCH	1790803	1	1	0	4.5	2.0	0.0	0.0	0.0	1.0	-26.1	10.3	0.00
PROBE	1090804	4	1	0	0.0	0.0	0.0	0.0	0.0	0.0	26.1	0.0	0.00
PROBE	1090804	4	1	0	0.0	0.0	0.0	0.0	0.0	0.0	-26.1	0.0	0.00
CABLEING	1790805	1	1	0	6.0	5.5	0.0	0.0	0.0	-7.7	19.9	11.1	0.00
ELECTRONICS	1090901	1	1	0	9.1	5.0	0.0	0.0	0.0	16.5	-10.0	11.9	4.00
SENSOR	1092902	4	1	0	3.0	5.0	0.0	0.0	0.0	24.0	-3.4	13.5	3.00
MAG BAL	1160200	2	1	0	7.5	0.0	0.0	0.0	0.0	-26.5	-6.2	0.0	4.00
ASTRODAST	1300101	2	1	0	15.0	0.0	0.0	0.0	0.0	-18.0	-6.6	0.0	2.30
ASTRO MODR	1300102	2	1	0	15.0	0.0	0.0	0.0	0.0	-18.0	-6.6	0.0	11.00
YAGESS MAG	130-200	2	1	0	15.0	0.0	0.0	0.0	0.0	-18.0	-6.6	0.0	1.00
YIG PLATE	1300301	9	1	0	0.0	0.0	0.0	0.0	2.2	0.0	0.0	12.4	9.00
DRIVE	1300302	4	1	0	0.0	0.0	0.0	0.0	1.5	0.0	0.0	6.4	9.00
IFCE ELECTR	1300303	1	1	0	7.4	5.4	5.0	0.0	0.0	-13.0	10.3	11.3	3.00
CRIVE ELECTR	1300304	1	1	0	7.4	5.4	5.0	0.0	0.0	-13.0	10.3	11.3	3.00

DYNAMICS EXPLORER DE-3 MOMENT OF INERTIA CALCULATIONS BOX INERTIA VALUES

ITEM	TYR	TYV	TYZ	TYPE
UPPER OP	9195.879	9195.879	8291.800	13
LOWER OP	9195.879	9195.879	8291.800	13
CENTER CIL	128.340	128.340	359.320	13
SMA PAUL 1	56.921	121.246	64.330	1
SMA PAUL 2	56.920	129.932	72.116	1
SMA PAUL 3	56.920	129.932	72.116	1
SMA PAUL 4	56.921	121.534	64.619	1
SMA PAUL 5	56.926	129.832	72.116	1
SMA PAUL 6	56.926	129.832	72.116	1
SEP ATPT LMR	1396.290	1396.290	589.300	13
SIDES MU	6336.762	6336.762	10934.547	9
END HU	439.878	439.878	1653.181	9
SIDES ML	6336.762	6336.762	10934.547	9
END HL	534.690	534.690	1669.181	9
CENTER QTHS	5519.486	5519.486	11214.216	9
WA SUPPLY CO	59.124	59.124	75.610	13
BRKTS-MISC	999.593	999.593	882.500	9
COVERS-SEALS	148.487	148.487	1482.680	9
LIFTING-MOVM.	376.600	376.600	750.800	12
RF SCREWS	6.003	6.003	16.006	4
RF SCREWS	6.003	6.003	16.006	4
RF SCREWS	6.003	6.003	16.006	4
DORE HX	919.667	919.667	786.000	9
DUL IN OIPU	378.150	378.150	264.600	13
11 GN 4-17AY	7.708	7.708	2.883	1
ATC BRACKETS	0.202	0.202	0.377	4
ATC BRACKETS	0.202	0.202	0.377	4
ATC BRACKETS	0.202	0.202	0.377	4
ATC BRACKETS	0.202	0.202	0.377	4
TWO-UPR 4AT	1302.532	1302.532	2332.061	9
ATC-UPR 1AT	15.930	15.930	31.827	4
ATC-UPR 1AT	15.930	15.930	31.827	4
ATC-UPR 1AT	15.930	15.930	31.827	4
ATC-UPR 1AT	15.930	15.930	31.827	4
TEMP SECS-UB	0.0	0.0	0.0	1
TEMP SECS-LB	0.0	0.0	0.0	1
TWO-LVR 9/P	900.860	900.860	1509.100	13
TH HEATERS	0.0	0.0	0.0	1
PITCH CDN EL	60.034	91.910	72.590	1
DETECTORS	0.533	0.533	0.533	1
DETECTORS	0.533	0.533	0.533	1
ELECTRONICS	0.733	0.733	0.733	1
ELECTRONICS	0.733	0.733	0.733	1
NUT DAMPER	6732.695	3518.200	3672.000	13
ATT COIL	1750.750	1988.750	3901.560	13
PITCH COIL	1231.600	722.900	722.900	13
POTOM ASSY	326.312	326.312	121.024	4
INERTIA JML	1227.770	1227.770	2401.620	13
WHL HOR SEWS	29.005	29.005	16.890	4
W.A SHIELD	15.334	35.334	13.064	4
UPPER SOL AR	11495.109	11495.109	28795.516	9
LOWER SOL AR	13067.896	13067.896	28916.500	13

ELECTRONICS	72.788	65.333	72.788	1
SENSOR	57.432	73.141	81.428	1
SIG PROC	17.0.0	16.879	21.531	1
FILTER BOX	0.677	1.263	0.919	1
FILTER BOX	0.677	1.263	0.919	1
LATCH	0.271	0.505	0.368	1
LATCH	0.271	0.505	0.368	1
PROBE	16.131	16.131	0.001	4
PROBE	16.131	16.131	0.001	4
CAMMING	0.272	0.968	1.104	1
ELECTRONICS	25.625	49.841	43.416	1
SENSOR	37.872	32.805	10.767	0
MAG BAL	32.375	26.275	26.275	2
ASTROGRAPHY	29.637	56.075	56.075	2
ASTROGRAPHY	29.637	56.075	56.075	2
WARRNESS WAS	28.000	66.066	291.925	2
W6 PLATE	95.982	95.982	191.548	9
DRIVE	118.087	118.087	10.575	4
IFCE ELECTN	15.197	23.263	24.477	1
DAISE ELECTN	26.177	38.551	40.561	1

GYATICS EXPLORER DE-B
MOMENT OF INERTIA CALCULATIONS
BOX AXIS ROTATION FOR NONPARALLEL AXES

NAME	TX	TY	TZ	TX	TY	TZ	AM61	AM62	AM63	AM64
UPPER RP	4145.879	4145.879	8291.000							
LOWER RP	4145.879	4145.879	8291.000							
CENTER COIL	480.343	480.343	354.328							
SMR PAWL 1	56.921	121.246	64.330	0.000	-0.000	0.000	100.0	270.0	90.0	90.0
SMR PAWL 2	56.920	124.032	72.116							
SMR PAWL 3	111.084	74.948	72.116	31.225	0.000	-0.000	60.0	150.0	90.0	90.0
SMR PAWL 4	56.921	121.534	64.619	-0.000	0.000	0.000	0.0	90.0	90.0	90.0
SMR PAWL 5	46.486	139.464	54.067	-31.225	0.000	-0.000	300.0	60.0	90.0	90.0
SMR PAWL 6	111.084	74.946	72.116	31.225	-0.000	0.000	240.0	330.0	90.0	90.0
SEP ATTY LWR	1346.240	1346.240	589.300							
SIDES PU	6238.762	6038.762	10934.547							
END MU	834.658	834.658	1669.181							
SIDES ML	6238.762	6038.762	10934.547							
END ML	834.688	834.688	1669.181							
CENTER RING	5619.406	5619.406	11214.816							
KA SUPPLY CO	59.124	59.124	73.610							
SKTS-MISC	444.583	444.583	882.900							
COVERS-SEALS	448.487	448.487	1482.600							
LIFTING-ADJA	376.600	376.600	750.000							
RF SCREENS	8.003	8.003	16.006							
RF SCREENS	8.003	8.003	16.006							
RF SCREENS	8.003	8.003	16.006							
RF SCREENS	8.003	8.003	16.006							
ADJURE 204	419.567	419.567	746.000							
DUL G: RPD	378.150	378.150	264.680							
W1 GA BRSTRY	7.708	9.375	2.083							
ATC BRACKETS	0.202	0.202	0.377							
ATC BRACKETS	0.202	0.202	0.377							
ATC BRACKETS	0.202	0.202	0.377							
TH8-UPR -AT	1302.532	1302.532	2332.061							
ATC-UPR -AT	15.938	15.938	31.827							
ATC-UPR -AT	15.938	15.938	31.827							
ATC-UPR -AT	15.938	15.938	31.827							
ATC-UPR -AT	15.938	15.938	31.827							
TEMP SENS-UB	0.0	0.0	0.0							
TEMP SENS-LB	0.0	0.0	0.0							
TH8-LWR 3/P	360.860	360.860	1509.100							
TH HEATERS	0.0	0.0	0.0							
PITCH COV EL	84.062	75.502	72.590	11.289	0.000	-0.000	95.0	145.0	90.0	90.0
DETECTORS	0.533	0.533	0.533							
DETECTORS	0.533	0.533	0.533							
ELECTRONICS	0.733	0.733	0.733							
ELECTRONICS	0.733	0.733	0.733							
MUT DAMPER	6732.699	3518.280	3872.880							
ATT COIL	1950.750	1950.750	3901.500							
PITCH COIL	1231.600	722.900	722.900							
ACTON ASSY	328.312	328.312	121.425							
INERTIA JHL	1227.770	1227.770	2441.620							
JHL MOR SEMS	29.445	29.445	10.890							
JHL SHIELD	35.334	35.334	13.868							
UPPER SOL AR	11495.109	11495.109	20795.516							
LOWER SOL AR	13067.898	13067.898	20916.500							

ORIGINAL PAGE IS
OF POOR QUALITY

BATT 1	272.570	94.395	283.637			
BATT 2	94.395	272.570	283.637			
SWR SUPPL EL	251.793	347.296	307.309			
TURSS TENDR	280.845	76.600	307.761			
XPONOR CABLE	49.625	11.081	44.519			
LOW GAIN ANT	1.537	1.597	1.094			
MI. GAIN ANT	31.358	466.233	492.658			
SW+FLT TURK	37.259	10.117	40.794			
PREMOD PHOC	11.023	19.709	20.420			
CTP	173.434	93.791	149.794			
CDU	145.972	112.545	119.025			
RTM	47.535	113.456	92.575			
TAPE RECORDER	290.417	165.750	354.167			
TAPE RECORDER	296.917	165.750	354.167			
UPPER MAIN	8530.414	8530.414	17187.500			
LOWER MAIN	8530.414	8530.414	17187.500			
GROUND BLOCK	71.133	71.133	141.200			
GROUND BLOCK	53.350	53.350	105.900			
COFFIN	177.433	177.433	353.000			
CLAMPS	177.433	177.433	353.000			
MAT	378.093	378.093	1941.500			
SAND STRAP	266.750	266.750	529.500			
DEANPS	0.364	0.722	0.931			
DEANPS	0.364	0.722	0.931			
DEANPS	0.543	0.543	0.931	0.179	0.000	0.000
DEANPS	0.543	0.543	0.931	-0.179	-0.000	0.000
DEANPS	0.543	0.543	0.931	0.179	0.000	0.000
DEANPS	0.543	0.543	0.931	-0.179	-0.000	0.000
ELECTRONICS	79.535	65.137	83.792			
DISPENSE	193.800	167.300	47.900			
DISPENSE	193.800	167.300	47.900			
DISPENSE	136.600	136.600	140.900	-59.900	0.000	0.000
DISPENSE	136.600	136.600	140.900	59.900	0.000	0.000
DISPENSE	136.600	136.600	140.900	-59.900	-0.000	0.000
DISPENSE	136.600	136.600	140.900	59.900	0.000	0.000
SENSOR	12.045	7.230	7.230			
ELECTRONICS	59.537	46.979	66.061			
THML FLVKT	0.0	0.7	0.0			
ELECTRONICS	21.728	31.521	26.752			
SENSOR	34.040	29.467	9.718			
DETECTORS	110.957	110.957	156.426			
SCAN PLATE	20.206	20.206	56.350			
TOP PLATE	9.806	9.806	19.600			
TOURE	7.053	7.053	10.563			
CABLING	21.190	21.190	31.688			
PPS	28.254	28.254	42.250			
PPS	28.254	28.254	42.250			
WVPS	16.952	16.952	25.350			
WVPS	16.952	16.952	25.350			
EPO SYST	7.063	7.063	10.563			
CFP	84.761	84.761	126.750			
WV DISTR	14.127	14.127	21.125			
IMR BLNKT	2.825	2.825	4.225			
MAG SENSOR	1.000	1.000	1.500			
MAG DEPLOYER	9.211	9.211	0.422			
ELECTRONICS	49.000	54.531	54.531			
INSTRUMENT	65.913	141.723	146.987			
ELECTRONICS	29.483	41.063	35.767			
INSTRUMENT	545.637	409.702	932.890	24.738	-0.000	0.000
CABLING	1.017	1.417	1.233			

0.000 00.3 170.0 90.0 90.0

ELECTRONICS	72.708	65.335	72.708
SENSOR	57.432	73.141	81.925
SIG PROC	17.010	14.873	21.531
FILTER HOF	0.677	1.263	0.919
FILTER BOX	0.677	1.263	0.919
LATCH	0.271	0.505	0.369
LATCH	0.271	0.505	0.369
PROBE	14.131	14.131	0.001
PROBE	14.131	14.131	0.001
CABLING	0.672	0.968	1.104
ELECTRONICS	25.625	49.741	43.416
SENSOR	37.872	32.405	10.767
WAS BAL	52.375	26.275	27.275
ASTROMAST	29.037	59.075	58.075
ASTRO HOF	145.952	291.925	291.925
WARRNESS WAS	20.006	40.000	40.000
MTG PLATE	95.982	95.982	191.948
DRIVE	114.047	114.047	10.525
IFCE ELECTN	15.797	23.263	24.477
DRIVE ELECTA	26.177	34.551	40.561

DYATICS EXPLORER DE-B MOMENT OF INERTIA CALCULATIONS ABOUT S/C AXIS

IN A STEPWISE INDICATES THE TOTAL SUM OF THE MOMENTS OF BOX COMPONENTS

ID	NAME	IXX	IYY	IYY
1010100	UPPER BP	5628.5781	5028.5781	8291.0000
1010200	LOWER BP	5785.4336	5785.4336	8291.0000
1010301	CENTER COL	480.3401	480.3401	354.3281
1010302	SHR PAML 1	56.9212	680.3625	623.4470
1010303	SHR PAML 2	501.2360	277.3994	664.6010
1010304	SHR PAML 3	553.3214	223.3158	664.6010
1010305	SHR PAML 4	56.9212	680.6509	623.7354
1010306	SHR PAML 5	490.8059	287.8315	646.7720
1010307	SHR PAML 6	553.3214	223.3158	664.6010
1010500	SEP ATPT LUR	5537.2227	5537.2227	589.3000
1010601	SIDES MU	8491.8828	8491.8828	10934.5469
1010602	END MU	3036.8760	3036.8760	1669.1814
1010701	SIDES HL	8491.8828	8491.8828	10934.5469
1010702	END HL	3036.8760	3036.8760	1669.1814
1010800	CENTER RING	5619.4062	5619.4062	11214.8164
1010900	MVA SUPPT CO	647.0681	647.0681	73.6100
1011000	PRKTS MISC	444.5833	444.5833	882.5000
1011100	COVERS+SEALS	848.4873	848.4873	1482.5999
1011200	LIFTING MDWR	376.5996	376.5996	749.5995
1011300	RF SCREENS	196.1784	196.1784	28.5063
1011400	RF SCREENS	196.1784	196.1784	28.5063
1011500	RF SCREENS	196.1784	196.1784	28.5063
1011601	MDWR BOX	419.6665	419.6665	706.0000
1011602	DUL ON BIPD	4053.5249	4053.5249	264.6799
1011700	ATC BRACKETS	195.5908	195.5908	81.4469
1011701	ATC BRACKETS	195.5908	195.5908	81.4469
1011702	ATC BRACKETS	195.5908	195.5908	81.4469
1020101	THM-UPR HAT	1712.0417	1712.0417	2332.0605
1020102	ATC-UPR HAT	378.9380	378.9380	177.8270
1020103	ATC-UPR HAT	378.9380	378.9380	177.8270
1020104	ATC-UPR HAT	378.9380	378.9380	177.8270
1020301	TEMP SENS-DB	18.3750	18.3750	0.0
1020401	TEMP SENS-LB	18.3750	18.3750	0.0
1020402	THM-LWR B/P	2109.2976	2109.2976	1589.1801
1020500	THM WEYERS	0.0	0.0	0.0
1030200	PITCH CON EL	3276.2295	663.6497	3596.9761
1030301	DETECTORS	468.5332	814.1331	576.5332
1030302	DETECTORS	468.5332	814.1331	576.5332
1030303	ELECTRONICS	250.7771	481.7769	522.6831
1030304	ELECTRONICS	250.7771	481.7769	522.6831
1030401	MOT DAMPER	6732.6992	6732.6992	7887.2773
1030402	ATT COIL	2288.2500	2288.2500	3901.5000
1030500	PITCH COIL	1231.6001	1310.8999	1310.8999
1030701	MOTOR ASSY	6399.4844	6399.4844	121.4235
1030702	INERTIA WML	10147.7695	10147.7695	2441.6201
1030800	WHL HDR SENS	573.9448	573.9448	16.8200
1031900	MVA SHIELD	688.7336	688.7336	13.0680
1040100	JOPER SOL AR	15794.9453	15794.9453	20795.5156
1040200	LOWER SOL AR	20766.0039	20766.0039	20916.5000

ORIGINAL PAGE IS
OF POOR QUALITY

ORIGINAL PAGE IS
OF POOR QUALITY

1001301	BATT 1	7924.4687	832.3027	7401.2344
1001302	BATT 2	1154.9877	7164.9687	6594.3594
1001303	PWR SUPPL FL	9545.4182	888.9246	9547.3267
1001304	TRUSS RONDRA	6903.1914	2871.4136	5418.9687
1001305	HPONDR CABLE	998.5752	299.4382	743.0767
1001306	LOW GAIN ANT	4550.1914	4550.1914	1.0937
1001307	HI. GAIN ANT	9447.7365	5883.8039	5282.4531
1001308	SWIFT NTWK	710.2868	404.2659	644.9426
1001309	PRENO2 PROC	2429.7031	819.5437	2245.4968
1001310	CIP	1823.5749	2829.3625	1346.3032
1001311	CDU	4778.2395	3178.8064	4074.5249
1001312	RTM	4414.9766	1468.5045	3670.3742
1001313	TYPE RECORDER	2637.4790	5165.6225	3016.4165
1001314	TAPE RECORDER	2637.4790	5169.0625	3010.4165
1001315	UPPER WARM	11808.3428	11808.3828	17187.5800
1001316	LOWER WARM	11808.3828	11808.3828	17187.5800
1001317	GROUND BLOCK	117.3543	117.3583	141.2000
1001318	GROUND BLOCK	88.0187	88.0187	105.9020
1001319	POURING	293.3958	293.3958	353.8680
1001320	CLAMPS	293.3958	293.3958	353.8680
1001321	MAT	1613.6770	1613.6770	1941.5600
1001322	CHW STRIP	4400.6935	440.0935	529.5808
1001323	PREAMPS	63.8339	308.3091	274.7920
1001324	PREAMPS	91.5539	308.3091	302.5120
1001325	PREAMPS	101.8059	216.5059	261.9058
1001326	PREAMPS	222.6604	128.5059	295.5603
1001327	PREAMPS	101.8059	216.5059	261.9058
1001328	PREAMPS	161.8059	216.5059	261.9058
1001329	ELECTRONICS	3369.6355	1123.7874	2369.0479
1001330	DISPENSER	1714.9436	4517.0117	2876.4736
1001331	DISPENSER	1714.9436	4517.0117	2876.4736
1001332	DISPENSER	912.6936	912.6936	1693.0876
1001333	DISPENSER	912.6936	912.6936	1693.0876
1001334	DISPENSER	912.6936	912.6936	1693.0876
1001335	DISPENSER	912.6936	912.6936	1693.0876
1001336	SENSOR	73.9338	1289.4697	1331.3582
1001337	ELECTRONICS	1911.4604	1325.6835	1375.2954
1001338	THRL FLNKT	0.0	0.0	0.0
1001339	ELECTRONICS	918.1042	1916.9080	1675.1018
1001340	SENSOR	698.8879	2638.2642	2026.0486
1001341	DETECTORS	7824.7422	7824.7422	156.4259
1001342	SCAV PLATE	1512.0728	1512.0728	56.3500
1001343	TOP PLATE	839.2776	839.2776	19.2808
1001344	ADHRE	205.0684	209.0684	10.5625
1001345	CABLING	627.2051	627.2051	31.6875
1001346	PPS	836.2734	836.2734	42.2500
1001347	PPS	836.2734	836.2734	42.2500
1001348	PPS	501.7639	501.7639	25.3500
1001349	PPS	501.7639	501.7639	25.3500
1001350	EPD SYST	209.0684	209.0684	10.5625
1001351	CEP	2508.8208	2508.8208	126.7500
1001352	HW JSTN	418.1367	418.1367	21.3250
1001353	THR BLNKT	83.6273	83.6273	4.2250
1001354	WAS SENSOR	862.9867	862.9867	1.5800
1001355	WAS DEPLOYER	871.1179	871.1179	0.4239
1001356	ELECTRONICS	260.6797	2584.4307	2584.4307
1001357	INSTRUMENT	3547.9116	3547.9116	3552.9783
1001358	ELECTRONICS	3782.1753	3782.1753	2987.5950
1001359	INSTRUMENT	3921.3083	3921.3083	4361.0781
1001360	CABLING	130.4198	29.0291	103.0240

109J701	ELECTRONICS	1279.1879	2259.5715	1951.9880
109J702	SENSOR	1462.4934	4654.2344	3547.5776
109J801	SIG PROC	1691.9038	1015.1729	1731.6807
109J802	FILTER BOX	393.2913	55.4143	342.6223
109J803	FILTER BOX	393.2913	55.4143	342.6223
109J803	LATCH	157.3166	22.1637	137.0489
109J803	LATCH	157.3166	22.1637	137.0489
109J804	PROSE	182.1724	18.1308	170.0428
109J804	PROSE	182.1724	18.1308	170.0428
109J805	CABLEING	104.7162	37.4681	92.1640
109J901	ELECTRONICS	1185.3528	2035.5681	1630.2154
109J902	SENSOR	774.3494	2914.1530	2243.6939
1100200	MAG BAL	213.4385	2568.7017	3129.7651
130J101	ASTROMAST	130.2274	810.7268	911.9163
130J102	ASTRO MDNR	654.6123	4075.2727	4583.9141
130J200	WARYESS MAG	89.6960	556.3399	628.0957
130J301	MTG PLATE	1541.3252	1541.3252	191.9479
130J302	DRIVE	503.1111	503.1111	10.5750
130J303	IFCE ELECTN	834.0266	1061.6780	987.7910
130J304	DRIVE ELECTN	1362.1011	1759.3521	1636.0823

DYNAMICS EXPERIMENT DE-8
S/C MOMENTS OF INERTIA
01 OCTOBER 1978

THE TOTALS BEFORE BALANCING ARE--

SUM OF WEIGHTS = 0.7557033E+03
SUM OF WEIGHT * X DISTANCES = 0.34031036E+03
SUM OF WEIGHT * Y DISTANCES = 0.4744853E+02
SUM OF WEIGHT * Z DISTANCES = 0.1831871E+02
SUM OF WEIGHT * X * X DISTANCES = 0.10470796E+04
SUM OF WEIGHT * Y * Y DISTANCES = 0.57751936E+04
SUM OF WEIGHT * Z * Z DISTANCES = 0.49899731E+03
SUM OF WEIGHT * X * Y DISTANCES = 0.62911859E+05
SUM OF WEIGHT * Y * Z DISTANCES = 0.59424953E+05
SUM OF WEIGHT * X * Z DISTANCES = 0.121318919E+06

SUM OF IXX = 0.94977750E+05
SUM OF IYY = 0.91703562E+05
SUM OF IZZ = 0.15474437E+06

THE C.G. COMPONENTS ARE-- X = -0.449737E+00 Y = 0.627046E-01 Z = -0.242885E-01

SUM OF IXX = 0.9717233E+02
SUM OF IYY = 0.9
SUM OF IZZ = 0.0

DYANICS EXPLORER DE-8
S/C MOMENTS OF INERTIA
31 OCTOBER 1974

S/C MOMENTS OF INERTIA ARE-

* THE FOLLOWING VALUES HAVE UNITS OF LB.-IN²

IV = 0.27619137E+06
IV = 0.27583100E+06
IZ = 0.28230556E+06
IY = 0.1358408E+04
IVZ = 0.57763320E+04
IYY = 0.57936903E+03
IYX = 0.27661975E+06
IXY = 0.2758135E+06

* THE FOLLOWING VALUES HAVE UNITS OF IN-LBS-SEC²

IVX = 0.71562139E+03
IYY = 0.71456567E+03
IZZ = 0.73140092E+03
IYZ = 0.2491011E+01
IVZ = 0.14523034E+02
IYX = 0.15011625E+01
IXY = 0.7155544E+03
IXZ = 0.7134326E+03

INERTIA RATIO

I / I = 1.021
SPIN/ TRANSVERSE MAX

ORIGINAL PAGE IS
OF POOR QUALITY

APPENDIX D
DE-B DEPLOYED MASS PROPERTIES
COMPUTER OUTPUT

TBS

Design Note

REGA Astro Electronics

Originating Project or Group **DYNAMICS EXPLORER**

Note No. 2.4.4-003-DN

Title

DE RADIATION ENVIRONMENT ANALYSIS

Written by: G. Brucker/R. Ohanian

Date June 1, 1978

Approved by:

Date 6 June 78

This DN supplements (S), replaces (R) DN Nos.

Supersedes 2.4.4-001-DN, 9/9/77
Addition 9/27/78

REVISIONS

Letter	Description	Date	Author
A	Addition of Para. 6.0, Table 4, and Figure 5.	9/27/78	R. Ohanian
			Distribution: R. deBastos W. Fuldner G. Hogan W. Hord C. Hume S. Malyszka R. Ohanian D. Shipley

Distribution:
R. deBastos
W. Fuldner
G. Hogan
W. Hord
C. Hume
S. Malyszka
R. Ohanian
D. Shipley

1.0 INTRODUCTION

This design note supersedes 2.4.4-001-DN, an earlier radiation environment analysis submitted for Dynamics Explorer (1). The orbital parameters for the A and B missions have been modified and new environmental models have become available since the latter design note was issued. The current work incorporates all these changes and compares the new results with the previous results.

The environments for Dynamics Explorer A and B have been evaluated in a 1981 time frame (Solar Maximum conditions) utilizing the minimum drag orbit parameters ("Flux = 150" case) received from NASA. Minimum drag was chosen because it is a worst case condition by virtue of slower altitude decay. Results are presented here in a context of nominal mission life (13 months) and expected maximum life (97 weeks, after which the B orbit is expected to be fully decayed).

The data processing for this report is similar to that of previous work. First, the A and B orbits described in Reference (2) were constructed on an RCA orbit generating computer program by means of appropriate drag coefficients. Next, twenty-four hour "snapshots" of each orbit (two minute step size), corresponding to 16 week intervals, were placed on a disk file. Each snapshot was then processed in normal fashion using B-L conversion and radiation model programs originally obtained from E. Stassinopoulos (NASA/GSFC). Finally, the resulting snapshot environments were properly weighted, combined, and submitted to RCA's UNIDOSE and Solar Cell Damage Equivalence computer codes. It should be noted, however, that the present study utilized newly received maps for inner and outer zone trapped electrons; in particular the AEI7-HI map, which is a significant change for the outer zone, was used herein for worst case conservatism.

2.0 DOSE-DEPTH SHIELDING CURVES

Figures 1 and 2 contain the total worst case curves of ionization dose vs. equivalent aluminum thickness (spherical shield geometry) for the A and B spacecraft respectively. Note two solid curves in each figure (corresponding to the 97 week and 13 month durations of this present analysis), and a dashed curve which is taken from the worst case of the previous design note (2.4.4-001-DN).

To achieve a worst case for both A and B, the present study has applied a factor of two in uncertainty to the trapped proton contribution (AP8-MAX map), and has utilized the 99% confidence level for solar protons (solar alphas levels are approximated at 5% of the solar protons). However, for the trapped electrons, differing uncertainties were applied to the A and B spacecraft. In the case of DE-A, nearly the entire orbit falls within the outer zone, and because of the severe AEI7-HI environment, a factor of unity is adequate. On the other hand, owing to the large inner zone component, a factor of three was applied to the DE-B trapped electron (and accompanying Bremsstrahlung) contribution.

The resulting curves, coupled with a knowledge of spherical shielding geometry, enable one to design against the expected long-term dose encountered on-board the spacecraft. For simple or non-critical geometries, it may be possible to estimate the dose by hand. However, shielding geometry computer codes of excellent accuracy are available at RCA/AE if the need arises.

3.0 EQUIVALENT FLUENCE VS. SHIELDING CURVES

Figures 3 and 4 contain the worst case equivalent 1 MeV electron fluence -- vs. shield thickness curves for the A and B spacecraft respectively. These curves were produced under the same conditions as the dose-depth curves discussed above, and can be applied to spherical geometries to obtain long term bulk damage in semiconductor components (excepting solar cells - see below).

4.0 SOLAR CELL DEGRADATION PARAMETERS

The worst case equivalent 1 MeV electron fluences for evaluating end-of-life I_{sc} (short circuit currents) and P_{max} or V_{oc} (maximum power or open circuit voltage) for the A and B missions, along with the corresponding worst case results from 2.4.4-001-DN, are contained in Table 1. These results were calculated under the conditions outlined above, and are appropriate for a cover glass of 60 mils (fused silica) and infinite backshielding.

5.0 PEAK FLUXES

In general, the peak flux rate of a particle type at a given energy is about two orders of magnitude more severe than the long term average rate. Accordingly, Tables 2 and 3 contain a peak flux spectrum (a factor of 100 greater than the long-term average rate) for the A and B missions respectively. If interested, the reader may refer to 2.4.4-001-DN for the previous results, which were not presented in spectrum form and were obtained by using a slightly different criteria.

Peak rates are necessary when considering circuits which can be upset by short term (transient) conditions. However, one must be sure he is evaluating the correct transient mechanism. Tables 2 and 3 are useful if individual particle rates cause system upset (such as spurious counts in a sensor). On the other hand, peak rates for dose or equivalent 1 MeV electron fluence may be estimated from the information provided in the previous sections of this report: merely divide the long term dose (or fluence) by the appropriate time factor to obtain dose (or fluence) per second and multiply by 100 to achieve the two order of magnitude increase.

6.0 EXTENDED TABLE OF SOLAR CELL DAMAGE EQUIVALENCE

Table 4 and Figure 5 contain the results of a study which extends the results of paragraph 4.0 to cover glass thicknesses other than 60 mils.

REFERENCES:

- (1) G. Brucker and R. Ohanian, "DE Radiation Analysis", Dynamics Explorer design note 2.4.4-001-DN, September 9, 1977.
- (2) Letter from F. Carr (NASA/GSFC) to W. V. Fuldner, File #11128, May 12, 1978.

TABLE 1.
SOLAR CELL DAMAGE EQUIVALENCE (worst case total,
60 mil cover glass, infinite backshielding)

	I_{sc} (1 MeV electron fluence)	P_{max} or V_{oc} (1 MeV electron fluence)
A mission, 97 wks.	1.76×10^{14}	2.32×10^{14}
A mission, 13 mos.	9.56×10^{13}	1.25×10^{14}
A mission, 2.4.4-001-DN (1.8 yrs)	3.08×10^{14}	4.28×10^{14}
B mission, 97 wks.	2.93×10^{13}	3.49×10^{13}
B mission, 13 mos.	2.16×10^{13}	2.56×10^{13}
B mission, 2.4.4-001-DN (1.8 yrs)	8.76×10^{12}	1.06×10^{13}

TABLE 2.

Peak Flux Spectrum for DE-A

Energy (MeV)	Protons (p/cm ² /sec > Energy)	Electrons (e/cm ² /sec > Energy)
.1	1.90×10^9	1.52×10^9
1.0	1.39×10^8	9.90×10^7
5.0	3.39×10^6	7.94×10^5
10.0	6.29×10^5	0
50.0	2.61×10^4	0
100.0	1.05×10^4	0

TABLE 3.

Peak Flux Spectrum for DE-B

Energy (MeV)	Protons (p/cm ² /sec > Energy)	Electrons (e/cm ² /sec > Energy)
.1	3.65×10^6	6.84×10^7
1.0	2.98×10^5	9.21×10^5
5.0	9.19×10^4	9.25×10^3
10.0	7.04×10^4	0
50.0	1.87×10^4	0
100.0	8.29×10^3	0

DOSE VS. SHIELDING FOR DE-A




FIG. 1

DOSE VS. SHIELDING FOR DE-B




FIG. 2

EQUIVALENT FLUENCE VS. SHIELDING FOR DE-A




FIG. 3

EQUIVALENT FLUENCE VS. SHIELD THICK FOR DE-B




FIG. 4

TABLE 4.

EXTENDED TABLE OF SOLAR CELL DAMAGE EQUIVALENCE
(1 MeV Equivalent electrons/cm², Worst Case Total,
Infinite Backshielding)

Mission/Parameter	Cover Glass Thickness, Mils of Fused Silica				
	6	12	20	30	60
"A", 97 wks, I_{sc}	5.36×10^{15}	1.99×10^{15}	8.30×10^{14}	4.87×10^{14}	1.76×10^{14}
"A", 97 wks, P_{max} or Voc	1.25×10^{16}	4.17×10^{15}	1.46×10^{15}	7.99×10^{14}	2.32×10^{14}
"A", 13 mos, I_{sc}	3.08×10^{15}	1.06×10^{15}	4.43×10^{14}	2.61×10^{14}	9.56×10^{13}
"A", 13 mos, P_{max} or Voc	7.15×10^{15}	2.21×10^{15}	7.78×10^{14}	4.27×10^{14}	1.25×10^{14}
"B", 97 wks, I_{sc}	1.52×10^{14}	8.73×10^{13}	5.94×10^{13}	4.68×10^{13}	2.93×10^{13}
"B", 97 wks, P_{max} or Voc	2.91×10^{14}	1.44×10^{14}	8.47×10^{13}	6.37×10^{13}	3.49×10^{13}
"B", 13 mos, I_{sc}	1.26×10^{14}	6.98×10^{13}	4.58×10^{13}	3.53×10^{13}	2.16×10^{13}
"B", 13 mos, P_{max} or Voc	2.47×10^{14}	1.18×10^{14}	6.67×10^{13}	4.88×10^{13}	2.56×10^{13}

SOLAR CELL DAMAGE EQUIVALENCE FOR DYNAMIC EXPLORER

INFINITE BACKSHIELDING GEOMETRY

SOLID LINES FOR λ^* MISSION
DASHED LINES FOR λ^* MISSION

By J. O. Thomson
9/25/78

EQUIVALENT 1 MEV ELECTRON FLUENCE (E/CM^2)

10^{16}
 10^{15}
 10^{14}
 10^{13}

P_{max}
 V_{oc}
 I_{sc}
13 MS

P_{max}
 V_{oc}
97 WRS

I_{sc}
97 WRS

I_{sc}
13 MS

P_{max}
 V_{oc}
97 WRS

I_{sc}
97 WRS

I_{sc}
13 MS

ORIGINAL PAGE IS
OF POOR QUALITY

10 20 30 40 50 60 70
COVER GLASS THICKNESS (MILS OF GLASS)

4.0 THERMAL SUBSYSTEM DESIGN NOTES

TABLE OF CONTENTS

<u>Design Note</u>	<u>Title</u>
3.2.2-001-DN	DE-A Thermal Model Description
3.2.2-002-DN	DE-B Simplified Thermal Model Description
3.2.2-003-DN	DE-A Baseline Thermal Model Performance and Analysis
3.2.2-004-DN	DE-A Parametric Thermal Study
3.2.2-005-DN	DE-A Final Thermal Design Configuration
3.2.2-006-DN	DE-B Parametric Thermal Study and Performance
3.2.2-007-DN	LAPI/Scan Platform Thermal Model Description and Performance
3.2.2-008-DN	DE-A ATC Thermal Design Performance
3.2.2-009-DN	Thermal Interface for Booms and Antennas for the DE-A and DE-B Spacecraft
3.2.2-010-DN	DE-A and DE-B Thermal Design Hardware Summary

Design Note

PREMIER

Astro Electronics

Originating Project or Group	Note No.
	3.2.2-001-DN
Title	
DE-A THERMAL MODEL DESCRIPTION	
Written by	Date
C. Chhatpar <i>C. Chhatpar</i>	8/27/78
Approved by:	Date
W. V. Fuldner <i>W. V. Fuldner</i>	16 Oct 78
This DN supplements (S), replaces (R) DN Nos	
() _____ () _____	

Letter	Description	Date	Author
	Standard Distribution: R. deBastos W. Fuldner G. Hogan W. Hord C. Hume D. Shipley		

AE 1338 2 1/74

1. SUMMARY

A 24 node steady state thermal model has been developed to evaluate the parametric performance of the DE-A spacecraft. The model provides data to compute orbit-average temperatures as functions of sun angle and duty cycles of variable dissipating components. The program automatically computes variable radiation couplings of internal nodes to external surroundings as a function of ATC positions which are dependent upon the base-plate temperatures.

2. DETAILS

The details of the model are contained in the following tables:

<u>Item</u>	<u>Title</u>
Table 1	Node Identification
Table 2	External Sink Identification
Table 3	External Sink Thermophysical Properties
Table 4	Orbit Average External Sink Values
Table 5	Spacecraft Internal and External Couplings
Table 6	DE-A Thermal Power Configuration
Table 7	Shunt Power Distribution
Table 8	DE-A Nodal Power Distribution: 100% Duty Cycle
Table 9	DE-A Nodal Power Distribution: 67.5% Duty Cycle
Table 10	DE-A Nodal Power Distribution: 33.75% Duty Cycle
Table 11	DE-A Nodal Power Distribution: 0% Duty Cycle

TABLE 1. NODE IDENTIFICATION

<u>Node No.</u>	<u>Description</u>
1	Upper Baseplate - Equipment Complex
2	Lower Baseplate - Equipment Complex
3	Top - ATC Area
4	Top - Passive Area
5	Bottom - ATC Area
6	Bottom - Passive Area
7	Separation Adapter - Lower
8	PWI Lower
9	Thermal Shield Lower
10	Upper Side Array - Quadrant 1
11	Upper Side Array - Quadrant 2
12	Upper Side Array - Quadrant 3
13	Upper Side Array - Quadrant 4
14	Lower Side Array - Quadrant 1
15	Lower Side Array - Quadrant 2
16	Lower Side Array - Quadrant 3
17	Lower Side Array - Quadrant 4
18	S-band Antenna - Quadrant 1
19	S-band Antenna - Quadrant 2
20	S-band Antenna - Quadrant 3
21	S-band Antenna - Quadrant 4
22	Separation Adapter - Upper
23	PWI - Upper
24	Thermal Shield - Upper

TABLE 2. EXTERNAL SINK IDENTIFICATION

<u>Sink No.</u>	<u>Description</u>
1	Spacecraft Top
2	Upper Side Array - Quadrant 1
3	Upper Side Array - Quadrant 2
4	Upper Side Array - Quadrant 3
5	Upper Side Array - Quadrant 4
6	Lower Side Array - Quadrant 1
7	Lower Side Array - Quadrant 2
8	Lower Side Array - Quadrant 3
9	Lower Side Array - Quadrant 4
10	Spacecraft Bottom
11	S-band Antenna - Quadrant 1
12	S-band Antenna - Quadrant 2
13	S-band Antenna - Quadrant 3
14	S-band Antenna - Quadrant 4
15	Upper Baseplate - Experiment Ports
16	Lower Baseplate - Experiment Ports
17	Space

TABLE 3. EXTERNAL SINK THERMOPHYSICAL PROPERTIES

<u>Sink No.</u>	<u>Properties</u> <u>Solar Absorptance</u>		<u>IR Emittance</u>
	<u>BOL</u>	<u>EOL</u>	
1	.725	.763	.81
2	.622	.635	.722
3	.622	.635	.722
4	.622	.635	.722
5	.622	.635	.722
6	.622	.635	.722
7	.622	.635	.722
8	.622	.635	.722
9	.622	.635	.722
10	.725	.763	.81
11	.305	.455	.274
12	.305	.455	.274
13	.305	.455	.274
14	.305	.455	.274
15	.764	.764	.603
16	.857	.857	.732
17	1.0	1.0	1.0

TABLE 4. ORBIT-AVERAGE EXTERNAL SINK VALUES FOR DE-A SPACECRAFT
(HIGH-ALTITUDE MISSION)

Sink No.	Sink Equivalent Black-Body Radiation (Watts/Sq-In)											
	BOL - 10 rpm						EOL - 10 rpm					
	Apogee = 23918 km Perigee = 275 km						Apogee = 23918 km Perigee = 275 km					
	Orbit Sun Angle (deg)						Orbit Sun Angle (deg)					
	0	45	90	-45	-0		0	45	90	-45	-0	
1	0.004	0.006	0.008	0.578	0.812		0.002	0.003	0.005	0.604	0.852	
2	0.008	0.187	0.199	0.187	0.008		0.005	0.186	0.203	0.186	0.005	
3	0.008	0.187	0.199	0.187	0.008		0.005	0.186	0.203	0.186	0.005	
4	0.008	0.187	0.199	0.187	0.008		0.005	0.186	0.203	0.186	0.005	
5	0.008	0.187	0.199	0.187	0.008		0.005	0.186	0.203	0.186	0.005	
6	0.008	0.187	0.199	0.187	0.008		0.005	0.186	0.203	0.186	0.005	
7	0.008	0.187	0.199	0.187	0.008		0.005	0.186	0.203	0.186	0.005	
8	0.008	0.187	0.199	0.187	0.008		0.005	0.186	0.203	0.186	0.005	
9	0.008	0.187	0.199	0.187	0.008		0.005	0.186	0.203	0.186	0.005	
10	0.812	0.578	0.008	0.006	0.004		0.852	0.604	0.005	0.003	0.002	
11	0.008	0.24	0.255	0.24	0.008		0.005	0.347	0.379	0.347	0.005	
12	0.008	0.24	0.255	0.24	0.008		0.005	0.347	0.379	0.347	0.005	
13	0.008	0.24	0.255	0.24	0.008		0.005	0.347	0.379	0.347	0.005	
14	0.008	0.24	0.255	0.24	0.008		0.005	0.347	0.379	0.347	0.005	
15	0.008	0.272	0.289	0.272	0.008		0.005	0.266	0.29	0.266	0.005	
16	0.008	0.252	0.268	0.252	0.008		0.005	0.246	0.268	0.246	0.005	
17	0.000	0.000	0.000	0.000	0.000		0.000	0.000	0.000	0.000	0.000	

TABLE 5. SPACECRAFT INTERNAL AND EXTERNAL COUPLING - Continued

Internal Coupling						
From	To	Radiative Coupling (in ²)	Conductive Coupling (watts/°C)	From	To	Radiative Coupling (watts/°C)
7	9	6.2	--	14	15	--
7	14	13.0	--	14	15	--
7	15	13.0	--	14	18	--
7	16	13.0	--	15	16	--
7	17	13.0	--	15	19	--
8	9	3.0	--	16	17	--
10	22	13.0	--	16	20	--
10	11	--	.04	17	21	--
10	13	--	.04	18	19	--
10	18	--	.09	18	21	--
11	12	--	.01	19	20	--
11	19	--	.09	20	21	--
11	22	13.0	--	22	23	224.2
12	13	--	.04	22	24	6.2
12	20	--	.09	23	24	3.0
12	22	13.0	--			
13	21	--	.09			
13	22	13.0	--			

- NOTES: (1) Variable as a function of louver position and sun angle.
(2) Varied parametrically depending on configuration (with or without heat pipes or shear web thickness).

TABLE 5. SPACECRAFT INTERNAL AND EXTERNAL COUPLINGS

External Coupling					
From	To	Radiative Coupling (in ²)	From	To	Radiative Coupling (in ²)
Node	Sink		Node	Sink	
1	15	36.783	14	6	633.9
1	17	VAR (1)	15	7	633.9
2	16	62.519	16	8	633.9
2	17	VAR (1)	17	9	633.9
3	1	802.5	18	11	34.4
4	1	752.1	19	2	34.4
5	10	802.5	20	13	34.4
6	10	752.1	21	14	34.4
7	17	9.5	22	17	9.5
8	17	4.9	23	17	4.9
9	17	10.0	24	17	10.0
10	2	633.9			
11	3	633.9			
12	4	633.9			
13	5	633.9			

NOTE: (1) Varied as a function of cutouts in the end array for the ATC's.

TABLE 6. DE-A THERMAL POWER CONFIGURATION

Instrument/Box	Internal Power Distribution (Watts)									
	Continuous	Science	Playback	at 100% Duty Cycle Science (89%)		at 67.5% Duty Cycle Science (60%)	at 33.75% Duty Cycle Science (30%)	at 0% Duty Cycle Science	Playback	Duty Cycle Playback (3.75%)
				Science	Playback					
Upper Baseplate										
SAI		2.5		2.22		1.5	0.75			
EIC		7.0		6.23		4.2	2.1			
PWI		7.8		6.94		4.68	2.34			
PWI (Electronics)										
RIMS + RIMS (Electronics)		10.5		9.35		6.3	3.15			
MAG Electronics		3.5		3.12		2.1	1.05			
TR (TU + EU)		10.0	21.0	8.90	2.31	6.0	3.0	0.79		
Thermal	2.0									
SUBTOTAL	2.0	41.3	21.0	36.76	2.31	24.78	12.39	0.79	0	0
Lower Baseplate										
BHS	3.15									
RIMS (1 + 2)		6.0		5.34		3.6	1.8			
HAPI		10.0		8.90		6.0	3.0			
SAI + SAI		5.0		4.45		3.0	1.5			
Battery 1 & 2										
PSE	3.0									
PMP	1.6									
RTM	1.0									
CTP/CDU	2.5									
RTX-A	6.8									
Thermal	2.0		17.3		1.9			1.3	0.65	
SUBTOTAL	20.05	21.0	17.3	18.69	1.9	12.6	6.3	1.3	0.65	0
TOTAL	22.05	62.3	38.3							

TABLE 7. SHUNT POWER DISTRIBUTION

Node	Power Fraction
	Trans and Shunt
1	-
2	-
3	-
4	.16
5	-
6	.16
7	-
8	-
9	-
10	.079
11	.091
12	.091
13	.079
14	.079
15	.091
16	.091
17	.079
18	-
19	-
20	-
21	-
22	-
23	-
24	-

TABLE 8. DE-A NODAL POWER DISTRIBUTION
100% Duty Cycle [89% Science + 11% PB]

NODE	INTERNAL DISSIPATION		SHUNT POWER + BATTERY + PSE				ABSORBED HEAT FLUX NOT ACCOUNTED FOR				TOTAL Q			
	CONSTANT	SCIENCE	PB	11.67°	45°	90°	-45°	-11.67°	11.67°	45°	90°	-45°	-11.67°	11.67°
1	2.0	36.76	2.31	-	-	-	-	-	-	-	-	-	-	-
2	20.05	18.69	1.9	8.68	9.62	9.4	9.59	10.03	-	-	-	-	41.07	41.07
3				-	-	-	-	-	-	-	-	-	-	-
4				1.71	3.59	.45	2.96	.54	-	-	-	-	1.71	3.59
5				-	-	-	-	-	-	-	-	-	-	-
6				1.71	3.59	.45	2.96	.54	-	-	-	-	1.71	3.59
7				-	-	-	-	-	10.0	7.1	1.7	-	.2	10.0
8				-	-	-	-	-	4.9	3.5	.1	.1	.1	4.9
9				-	-	-	-	-	11.2	7.9	1.4	.1	.1	11.2
10				.84	1.77	.22	1.46	.27	-	-	-	-	.84	1.77
11				.97	2.04	.25	1.68	.31	-	-	-	-	.97	2.04
12				.97	2.04	.25	1.68	.31	-	-	-	-	.97	2.04
13				.84	1.77	.22	1.46	.27	-	-	-	-	.84	1.77
14				.84	1.77	.22	1.46	.27	-	-	-	-	.84	1.77
15				.97	2.04	.25	1.68	.31	-	-	-	-	.97	2.04
16				.97	2.04	.25	1.68	.31	-	-	-	-	.97	2.04
17				.84	1.77	.22	1.46	.27	-	-	-	-	.84	1.77
18				-	-	-	-	-	-	-	-	-	-	-
19				-	-	-	-	-	-	-	-	-	-	-
20				-	-	-	-	-	-	-	-	-	-	-
21				-	-	-	-	-	-	-	-	-	-	-
22				-	-	-	-	-	.2	.2	1.7	7.1	10.0	10.0
23				-	-	-	-	-	.1	.1	.1	3.5	4.9	4.9
24				-	-	-	-	-	.1	.1	1.4	7.9	11.2	11.2

TABLE 3. DE-A NODAL POWER DISTRIBUTION

67.5% Duty Cycle [60% Science + 7.5% PB]

3.2.2-001-DN
Page 13

NODE	INTERNAL DISSIPATION		SHUNT POWER + BATTERY + PSE				ABSORBED HEAT FLUX NOT ACCOUNTED FOR				TOTAL Q			
	CONSTANT	SCIENCE	PB	11.67°	45°	90°	-45°	-11.67°	11.67°	45°	90°	-45°	-11.67°	11.67°
1	2.0	24.78	1.58	-	-	-	-	-	-	-	-	-	-	-
2	20.05	10.38	1.3	6.46	7.19	9.32	9.26	9.05					28.36	28.36
3				-	-	-	-	-					38.19	38.92
4				5.17	7.11	.45	6.48	1.7					5.17	7.11
5				-	-	-	-	-					-	-
6				5.17	7.11	.45	6.48	1.7					5.17	7.11
7				-	-	-	-	-					-	-
8				-	-	-	-	-	10.0	7.1	1.7	.2	10.0	7.1
9				-	-	-	-	-	4.9	3.5	.1	.1	4.9	3.5
10				-	-	-	-	-	11.2	7.9	1.4	.1	11.2	7.9
11				2.55	3.51	.22	3.2	.84					2.55	3.51
12				2.94	4.04	.25	3.69	.97					2.94	4.04
13				2.94	4.04	.25	3.69	.97					2.94	4.04
14				2.55	3.51	.22	3.2	.84					2.55	3.51
15				2.55	3.51	.22	3.2	.84					2.55	3.51
16				2.94	4.04	.25	3.69	.97					2.94	4.04
17				2.94	4.04	.25	3.69	.97					2.94	4.04
18				2.55	3.51	.22	3.2	.84					2.55	3.51
19													-	-
20													-	-
21													-	-
22									.2	.2	1.7	7.1	10.0	10.0
23									.1	.1	.1	3.5	4.9	4.9
24									.1	.1	1.4	7.9	11.2	11.2

33.75% Duty Cycle [30% Science + 3.75% PB]

NODE	INTERNAL DISSIPATION			SHUNT POWER + BATTERY + PSE					ABSORBED HEAT FLUX NOT ACCOUNTED FOR					TOTAL Q				
	CONSTANT	SCIENCE	PB	11.67°	45°	90°	-45°	-11.67°	11.67°	45°	90°	-45°	-11.67°	11.67°	45°	90°	-45°	-11.67°
1	2.0	12.39	.79	-	-	-	-	-	-	-	-	-	-	15.18	5.18	15.18	15.18	15.18
2	20.05	5.19	.65	4.15	4.68	6.15	4.63	5.42						30.04	30.57	32.04	30.52	31.31
3				-	-	-	-	-						-	-	-	-	-
4				8.76	10.72	3.84	10.16	6.34						8.76	10.72	3.84	10.16	6.34
5				-	-	-	-	-						-	-	-	-	-
6				8.76	10.72	3.84	10.16	6.34						8.76	10.72	3.84	10.16	6.34
7				-	-	-	-	-	10.0	7.1	1.7	.2	.2	10.0	7.1	1.7	.2	.2
8				-	-	-	-	-	4.9	3.5	.1	.1	.1	4.9	3.5	.1	.1	.1
9				-	-	-	-	-	11.2	7.9	1.4	.1	.1	11.2	7.9	1.4	.1	.1
10				4.32	5.29	1.9	5.02	3.13						4.32	5.29	1.9	5.02	3.13
11				4.98	6.1	2.18	5.78	3.61						4.98	6.1	2.18	5.78	3.61
12				4.98	6.1	2.18	5.78	3.61						4.98	6.1	2.18	5.78	3.61
13				4.32	5.29	1.9	5.02	3.13						4.32	5.29	1.9	5.02	3.13
14				4.32	5.29	1.9	5.02	3.13						4.32	5.29	1.9	5.02	3.13
15				4.98	6.1	2.18	5.78	3.61						4.98	6.1	2.18	5.78	3.61
16				4.98	6.1	2.18	5.78	3.61						4.98	6.1	2.18	5.78	3.61
17				4.32	5.29	1.9	5.02	3.13						4.32	5.29	1.9	5.02	3.13
18														-	-	-	-	-
19														-	-	-	-	-
20														-	-	-	-	-
21														-	-	-	-	-
22									.2	.2	1.7	7.1	10.0	.2	.2	1.7	7.1	10.0
23									.1	.1	.1	3.5	4.9	.1	.1	.1	3.5	4.9
24									.1	.1	1.4	7.9	11.2	.1	.1	1.4	7.9	11.2

0% Duty Cycle

NODE	INTERNAL DISSIPATION			SHUNT POWER + BATTERY + PSE				ABSORBED HEAT FLUX NOT ACCOUNTED FOR				TOTAL Q			
	CONSTANT	SCIENCE	PB	11.67°	45°	90°	-45°	-11.67°	11.67°	45°	90°	-45°	11.67°	45°	90°
1	2.0	0	0	-	-	-	-	-	-	-	-	-	-	-	-
2	20.05	0	0	1.92	5.191	2.2	1.9	-	-	-	-	-	-	-	-
3				-	-	-	-	-	-	-	-	-	-	-	-
4				12.23	14.31	8.83	13.71	11.39	-	-	-	-	-	-	-
5				-	-	-	-	-	-	-	-	-	-	-	-
6				12.23	14.31	8.83	13.71	11.39	-	-	-	-	-	-	-
7				-	-	-	-	-	10.0	7.1	1.7	.2	10.0	7.1	1.7
8				-	-	-	-	-	4.9	3.5	.1	.1	4.9	3.5	.1
9				-	-	-	-	-	11.2	7.9	1.4	.1	11.2	7.9	1.4
10				6.04	7.06	4.36	6.77	5.62	-	-	-	-	-	-	-
11				6.95	8.14	5.02	7.8	6.48	-	-	-	-	-	-	-
12				6.95	8.14	5.02	7.8	6.48	-	-	-	-	-	-	-
13				6.04	7.06	4.36	6.77	5.62	-	-	-	-	-	-	-
14				6.04	7.06	4.36	6.77	5.62	-	-	-	-	-	-	-
15				6.95	8.14	5.02	7.8	6.48	-	-	-	-	-	-	-
16				6.95	8.14	5.02	7.8	6.48	-	-	-	-	-	-	-
17				6.04	7.06	4.36	6.77	5.62	-	-	-	-	-	-	-
18				-	-	-	-	-	-	-	-	-	-	-	-
19				-	-	-	-	-	-	-	-	-	-	-	-
20				-	-	-	-	-	-	-	-	-	-	-	-
21				-	-	-	-	-	-	-	-	-	-	-	-
22				-	-	-	-	-	.2	.2	1.7	7.1	.2	1.7	7.1
23				-	-	-	-	-	.1	.1	.1	3.5	.1	.1	3.5
24				-	-	-	-	-	.1	.1	1.4	7.9	.1	1.4	7.9

Design Note

DREAM

Originating Project or Group

Note No.

3.2.2-002-DN

Title

DE-B Simplified Thermal Model Description

Written by. P. Shang/O. Liu

Date October 2, 1978

Approved by:

C. Chhatpar

Date _____

16 Oct 78

This DN supplements (S), replaces (R) DN Nos.

REVISIONS

Letter	Description	Date	Author
	Standard Distribution: R. deBastos W. Fuldner G. Hogan W. Hord C. Hume D. Shipley		

1.0 Summary

A 21-node steady state thermal model has been developed to evaluate the parametric performance of the DE-B spacecraft. The model computes orbit average temperatures as functions of sun angle and duty cycles of various heat dissipating components. Radiative couplings, whose values vary as a function of ATC positions, are automatically computed by the model.

2.0 Contents

Figure

1. DE-B Thermal Configuration

Table

1. Node Identification
2. External Sink Identification
3. External Sink Thermophysical Properties
4. Orbit Average External Sink Values
- 5-1 Spacecraft Internal Couplings
- 5-2 Spacecraft External Couplings
- 6-1 Nodal Power Distribution for Various Sun
Angles: 50% Duty Cycle
- 6-2 Nodal Power Distribution for Various Sun
Angles: 40% Duty Cycle
- 6-3 Nodal Power Distribution for Various Sun
Angles: 30% Duty Cycle
- 6-4 Nodal Power Distribution for Various Sun
Angles: 20% Duty Cycle
- 6-5 Nodal Power Distribution for Various Sun
Angles: 10% Duty Cycle
- 6-6 Nodal Power Distribution for Various Sun
Angles: 0% Duty Cycle
- 7-1 DE-B Thermal Power Configuration
- 7-2 DE-B Shunt Power Distribution
- 7-3 DE-B Battery and PSE Dissipation on Node 1

Appendix 1. Calculation of the Effective Aperture Properties
for Nodes 15 and 16.

Appendix 2. Definition of Thermal Sink Value and Ris.




Figure 2 DE-B Thermal Configuration

ORIGINAL PAGE IS
OF POOR QUALITY

TABLE 1. NODE IDENTIFICATION

<u>Node No.</u>	<u>Description</u>
1	Upper Baseplate - Equipment Complex
2	Lower Baseplate - Equipment Complex
3	Top - ATC Area
4	Top - Passive Area
5	Bottom - Scan Platform
6	Bottom - Passive Area
7	Separation Adapter
8	LAPI
9	LAPI Thermal Shield
10	Upper Side Array - Quadrant 1
11	Upper Side Array - Quadrant 2
12	Upper Side Array - Quadrant 3
13	Upper Side Array - Quadrant 4
14	Lower Side Array - Quadrant 1
15	Lower Side Array - Quadrant 2
16	Lower Side Array - Quadrant 3
17	Lower Side Array - Quadrant 4
18	S-band Antenna - Quadrant 1
19	S-band Antenna - Quadrant 2
20	S-band Antenna - Quadrant 3
21	S-band Antenna - Quadrant 4

C - 3

TABLE 2. EXTERNAL SINK IDENTIFICATION

<u>Sink No.</u>	<u>Description</u>
1	Spacecraft Top
2	Upper Side Array - Quadrant 1
3	Upper Side Array - Quadrant 2
4	Upper Side Array - Quadrant 3
5	Upper Side Array - Quadrant 4
6	Lower Side Array - Quadrant 1
7	Lower Side Array - Quadrant 2
8	Lower Side Array - Quadrant 3
9	Lower Side Array - Quadrant 4
10	Spacecraft Bottom
11	S-band Antenna - Quadrant 1
12	S-band Antenna - Quadrant 2
13	S-band Antenna - Quadrant 3
14	S-band Antenna - Quadrant 4
15	Upper Baseplate - Experiment Ports
16	Lower Baseplate - Experiment Ports
17	Space

Table 3. External Sink Thermophysical Properties

Sink No.	Solar Absorptivity α		$\epsilon_{\text{BOL}}/\alpha_{\text{EOL}}$	IR Emissivity
	BOL	EOL		
1	.725	.763	1.052	.81
2	.660	.717	1.086	.74
3	.660	.717	1.086	.74
4	.660	.717	1.086	.74
5	.660	.717	1.086	.74
6	.631	.686	1.087	.757
7	.631	.686	1.087	.757
8	.631	.686	1.087	.757
9	.631	.686	1.087	.757
10	.725	.763	1.052	.81
11	.305	.455	1.492	.274
12	.305	.455	1.492	.274
13	.305	.455	1.492	.274
14	.305	.455	1.492	.274
15	.649	.693	1.068	.474
16	.25	.35	1.4	.560
17	1.0	1.0	1.0	1.0

Properties of nodes 1 through 14 are obtained from Electrodynamics Explorers Thermal Model Description, EE-DN-TH-1, dated 7 Sept. 1976. The properties of nodes 15 and 16 are taken from the effective Aperture properties, calculated as per Appendix 1.

TABLE 4. ORBIT-AVERAGE EXTERNAL SINK VALUES FOR DE-B SPACECRAFT

Sink No.	Sink Equivalent Black-Body Radiation (Watts/Sq-In)									
	BOL - 1 RPO					EOL - 1 RPO				
	Apogee = 1200 km Perigee = 275 km					Apogee = 1200 km Perigee = 275 km				
	Orbit Sun Angle					Orbit Sun Angle				
	0	30	90			0	30	90		
1	0.037	0.045	0.063			0.048	0.047	0.079		
2	0.091	0.256	0.234			0.104	0.278	0.245		
3	0.088	0.252	0.231			0.101	0.274	0.241		
4	0.003	0.125	0.239			0.007	0.136	0.273		
5	0.007	0.128	0.242			0.011	0.139	0.276		
6	0.091	0.245	0.225			0.104	0.266	0.236		
7	0.088	0.242	0.221			0.101	0.263	0.232		
8	0.003	0.117	0.223			0.007	0.127	0.255		
9	0.007	0.120	0.227			0.011	0.130	0.259		
10	0.856	0.754	0.063			0.909	0.793	0.079		
11	0.097	0.302	0.275			0.110	0.451	0.351		
12	0.088	0.293	0.266			0.101	0.437	0.341		
13	0.003	0.155	0.297			0.007	0.231	0.462		
14	0.012	0.164	0.307			0.016	0.245	0.471		
15	0.045	0.261	0.358			0.043	0.279	0.360		
16	0.021	0.101	0.091			0.053	0.141	0.250		
17	0.000	0.000	0.000			0.003	0.000	0.000		

TABLE 5.1 SPACECRAFT INTERNAL COUPLINGS

FROM	TO	INTERNAL COUPLING				CONDUCTIVE COUPLING (W/°C)	RADIATIVE COUPLING		CONDUCTIVE COUPLING (W/°C)	RADIATIVE COUPLING		CONDUCTIVE COUPLING (W/°C)	RADIATIVE COUPLING (IN ²)	CONDUCTIVE COUPLING (W/°C)	RADIATIVE COUPLING (IN ²)	CONDUCTIVE COUPLING (W/°C)	RADIATIVE COUPLING (IN ²)	CONDUCTIVE COUPLING (W/°C)
		RADIATIVE COUPLING (IN ²)	CONDUCTIVE COUPLING (W/°C)	FROM	TO		RADIATIVE COUPLING (IN ²)	CONDUCTIVE COUPLING (W/°C)										
1	2	787.0			2.5						2	21	0.4			0.65		
1	3	59.0									3	4						
1	4	44.9									3	10	4.175					
1	10	132.5			0.028						3	11	4.175					
1	11	132.5			0.028						3	12	4.175					
1	12	132.5			0.028						3	13	4.175					
1	13	132.5			0.028						4	10	1.5			0.1		
1	14	7.7									4	11	1.5			0.1		
1	15	7.65									4	12	1.5			0.1		
1	16	7.65									4	13	1.5			0.1		
1	17	7.65									5	6				0.65		
1	18	3.6									5	7	236.0			1.041		
1	19	3.6									5	8	184.32			7.6		
1	20	3.6									6	7	3.9			0.1		
1	21	3.6									6	8	29.81					
1	6	44.1									6	14	1.5			0.5		
2	7										6	15	1.5			0.5		
2	10	0.9			1.260						6	16	1.5			0.5		
2	11	0.9									6	17	1.5			0.5		
2	12	0.9									6	18	370.0			0.5		
2	13	0.9									7	9	6.2			0.2		
2	14	75.0									7	14	0.2					
2	15	75.0			0.024						7	15	1.5					
2	16	75.0			0.024						7	16	0.2					
2	17	75.0			0.024						7	17	0.2					
2	18	0.4									8	9				0.05		
2	19	0.4									10	11				0.04		
2	20	0.4									10	13				0.04		

TABLE 5.1 SPACECRAFT INTERNAL COUPLINGS (continued)

		INTERNAL COUPLING			
FROM	TO	RADIATIVE COUPLING (IN ²)	CONDUCTIVE COUPLING (W/°C)	FROM TO	RADIATIVE COUPLING (IN ²) CONDUCTIVE COUPLING (W/°C)
10	18		0.09		
11	12		0.04		
11	19		0.09		
12	13		0.04		
12	20		0.09		
13	21		0.09		
14	15		0.04		
14	17		0.04		
14	18		0.09		
15	16		0.04		
15	19		0.09		
16	17		0.04		
16	20		0.09		
17	21		0.09		
18	19		0.027		
18	21		0.027		
19	20		0.027		
20	21		0.027		

TABLE 5-2. SPACECRAFT EXTERNAL COUPLINGS

FROM	TO	RADIATIVE COUPLING (IN ²)	FROM	TO	RADIATIVE COUPLINGS (IN ²)
NODE	SINK		NODE	SINK	
1	15	8.234	11	3	662.0
1	17	(1)	12	4	662.0
2	16	0.01	13	5	662.0
3	1	686.48	14	6	544.0
4	1	537.6	15	7	544.0
6	10	874.8	16	8	544.0
7	17	9.5	17	9	544.0
8	17	252.0	18	11	33.5
9	17	10.0	19	12	33.5
10	2	662.0	20	13	33.5
			21	14	33.5

(1) Value variable, depending on the position of ATC position.

TABLE 6-1. NODAL POWER DISTRIBUTION FOR VARIOUS SUN ANGLES: 50% DUTY CYCLE

NODE NO.	INTERNAL DISSIPATION			SHUNT PWS + BAT + P.S.E.			ABSORBED HEAT FLUX NOT ACCOUNTED FOR			TOTAL Q		
	CON-STANT	SCIENCE	PLAY-BACK	SUN ANG 0°	30°	90°	0°	30°	90°	0°	30°	90°
1	31.35	9.25	1.37	14.2	13.42	7.42	-	-	-	56.17	55.39	49.39
2	2.38	23.55	1.31	-	-	-	-	-	-	27.24	27.24	27.24
3	-	-	-	-	-	-	-	-	-	-	-	-
4	-	-	-	1.824	3.326	.331	-	-	-	1.824	3.326	.331
5	-	2.64	-	-	-	-	-	-	-	2.64	2.64	2.64
6	-	-	-	1.824	3.326	.331	-	-	-	1.824	3.326	.331
7	-	-	-	-	-	-	10.0	8.66	1.7	10.0	8.66	1.7
8	-	7.2	-	-	-	-	9.37	29.8	27.07	16.57	37.0	34.27
9	-	-	-	-	-	-	11.2	9.7	1.4	11.2	9.7	1.4
10	-	-	-	.9	1.642	.164	-	-	-	.9	1.642	.642
11	-	-	-	1.04	1.892	.188	-	-	-	1.04	1.892	.188
12	-	-	-	1.04	1.892	.188	-	-	-	1.04	1.892	.188
13	-	-	-	.9	1.642	.164	-	-	-	.9	1.642	.164
14	-	-	-	.9	1.642	.164	-	-	-	.9	1.642	.164
15	-	-	-	1.04	1.892	.188	-	-	-	1.04	1.892	.188
16	-	-	-	1.04	1.892	.188	-	-	-	1.04	1.892	.188
17	-	-	-	.9	1.642	.164	-	-	-	.9	1.642	.164
18	-	-	-	-	-	-	-	-	-	-	-	-
19	-	-	-	-	-	-	-	-	-	-	-	-
20	-	-	-	-	-	-	-	-	-	-	-	-
21	-	-	-	-	-	-	-	-	-	-	-	-

ORIGINAL PAGE IS
OF POOR QUALITY

TABLE 6-2. NODAL POWER DISTRIBUTION FOR VARIOUS SUN ANGLES: 40% DUTY CYCLE

[illegible]

TABLE 6-3. NODAL POWER DISTRIBUTION FOR VARIOUS SUN ANGLES: 30% DUTY CYCLE

[illegible]

TABLE 6-4. NODAL POWER DISTRIBUTION FOR VARIOUS SUN ANGLES: 20% DUTY CYCLE

[illegible]

TABLE 6-6 NODAL POWER DISTRIBUTION FOR VARIOUS SUN ANGLES: 0% DUTY CYCLE

[illegible]

TABLE 7-1. DE-B THERMAL POWER CONFIGURATION

Instrument/Box	Continuous Load	Science	Playback	Internal Power Distribution (watts)									
				Duty Cycle									
				at 45%		at 33.75%		at 22.5%		at 11.25%		at 0%	
				SCI (40%)	PB (5%)	SCI (30%)	PB (3.75%)	SCI (20%)	PB (2.5%)	SCI (10%)	PB (1.25%)	SCI (0%)	PB (0%)
<u>Power Baseplate</u>													
FA		5.5											
FI		8.0											
FM		5.0											
FTK-B	10.1		21.9										
FTK	2.24												
FTK	3.5												
FTK	6.63												
FTK Torquer	0.375												
FTK DU	2.5												
FTK	1.0												
FTK	3.0												
FTK Thermal	2.0												
TOTAL	31.345	18.5	21.9	7.40	1.095	5.55	0.821	3.7	0.548	1.85	0.274	0	0
<u>Power Baseplate</u>													
FA		3.5											
FI		14.0											
FM		3.0											
FTK		4.0											
FTK		12.0											
FTK Torquer	0.375	10.6	21.0										
FTK Thermal	2.0												
TOTAL	2.375	47.1	21.0	18.84	1.05	14.13	0.788	9.42	0.525	4.71	0.263	0	0
TOTAL	33.72	65.6	42.9										
SCI = Science PB = Playback													

TABLE 7-2. DE-B SHUNT POWER DISTRIBUTION*

*FROM POWER RUN #127-#131

DUTY CYCLE	50%			40%			30%			20%			10%			0%		
	0°	30°	90°	0°	30°	90°	0°	30°	90°	0°	30°	90°	0°	30°	90°	0°	30°	90°
SUN ANGLE	11.42	20.79	2.07	11.42	20.79	2.07	25.91	5.29	2.07	40.81	50.2	2.07	56.15	65.53	5.0	70.33	80.0	19.0
TOTAL PRAC																		
1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4	.16	1.82	4.32	.33	1.82	4.32	.33	4.15	5.65	.33	6.53	8.03	.33	8.98	10.48	.8	11.25	12.8
5	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
6	.16	1.82	4.32	.33	1.82	4.32	.33	4.15	5.65	.33	6.53	8.03	.33	8.98	10.48	.8	11.25	12.8
7	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
8	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
9	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
10	.07	.9	1.64	.9	1.64	.16	2.05	2.79	.16	3.22	3.99	.16	4.44	5.18	.39	5.56	5.18	1.50
11	.09	1.04	1.89	1.04	1.89	.18	2.36	3.21	.18	3.71	4.57	.18	5.11	5.96	.45	6.4	5.96	1.72
12	.09	1.04	1.89	1.04	1.89	.18	2.36	3.21	.18	3.71	4.57	.18	5.11	5.96	.45	6.4	5.96	1.72
13	.07	.9	1.64	.9	1.64	.16	2.05	2.79	.16	3.22	3.97	.16	4.44	5.18	.39	5.56	5.18	1.50
14	.07	.9	1.64	.9	1.64	.16	2.05	2.79	.16	3.22	3.97	.16	4.44	5.18	.39	5.56	5.18	1.50
15	.09	1.04	1.89	1.04	1.89	.18	2.36	3.21	.18	3.71	4.57	.18	5.11	5.96	.45	6.4	5.96	1.72
16	.09	1.04	1.89	1.04	1.89	.18	2.36	3.21	.18	3.71	4.57	.18	5.11	5.96	.45	6.4	5.96	1.72
17	.07	.9	1.64	.9	1.64	.16	2.05	2.79	.16	3.22	3.97	.16	4.44	5.18	.39	5.56	5.18	1.50
18	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
19	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
20	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
21	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

TABLE 7-3
DE-B BATTERY AND PSE POWER DISSIPATION ON NODE 1

DUTY CYCLE	SUN ANGLE	BATTERY DISSIPATION	POWER S.E.	TOTAL POWER ON NODE 1
50%	0°	4.40	9.80	14.2
	30°	3.84	9.58	13.42
	90°	3.37	4.05	7.42
40%	0°	3.33	8.41	11.74
	30°	2.88	8.26	11.14
	90°	3.37	4.05	7.42
30%	0°	2.50	6.78	9.28
	30°	2.16	6.7	8.86
	90°	3.37	4.05	7.42
20%	0°	1.67	5.15	6.82
	30°	1.44	5.14	6.58
	90°	3.37	4.05	7.42
10%	0°	.83	3.52	4.35
	30°	.72	3.58	4.3
	90°	3.0	3.48	6.48
0%	0°	.08	2.05	2.13
	30°	.08	2.1	2.18
	90°	1.91	1.83	3.74

APPENDIX 1. CALCULATION OF EFFECTIVE APERTURE
PROPERTIES FOR NODE 15 AND 16

COMPONENTS	APERTURE AREA (A) (in ²)	ABSORPTIVITY (α)		ABSORPTIVITY*AREA $\alpha*A$		EMISSIVITY ϵ	$\epsilon*A$
		BOL	EOL	BOL	EOL		
Upper Baseplate Node 15							
RPA	2 x 1.95	0.25	0.35	0.975	1.365	0.055	0.215
FTI	4 x 2.5	0.96	0.96	9.6	9.6	0.8	8.
IDM	2 x 1.95	0.25	0.35	0.975	1.365	0.055	0.215
TOTAL	17.8			11.55	12.33		8.43
Effective Prop. For Node 15		0.649	0.693			0.473	
Lower Base P. for Node 16							
NACS	0.012	0.25	0.35	0.003	0.0042	0.56	0.00672
WAT	0.0123	0.25	0.35	0.0031	0.0043	0.56	0.00689
TOTAL	0.0243			0.0061	0.0085		0.0134
Effective Prop. For Node 16		0.25	0.35			0.56	

APPENDIX 2. Definition of Thermal Sink Value and RIS

Absorbed external flux to a node i (watt/in²)

= Solar flux + Albedo flux + Earth IR flux

$$= A_i \alpha_i [\text{solar intensity}] + A_i \alpha_i [\text{Albedo intensity}] + A_i \epsilon_i [\text{Earth IR}]$$

$$= A_i \epsilon_i \left[\frac{1}{\epsilon_i} (\text{solar} + \text{albedo}) + \text{Earth IR} \right]$$

Define $R_{is} = A_i \epsilon_i$ (see Table 5-2), and

$$I_i = \frac{q_i}{\epsilon_i} [\text{solar} + \text{albedo}] + \text{Earth IR (See Table 4)}$$

then, for a flat surface of a convex body, the absorbed external flux of node i is (R_{is}) (I_i).

Design Note

IREA Astro Electronics

Originating Project or Group

Note No. 3.2.2-003-DN

Title

DE-A Baseline Thermal Model Performance and Analysis

Written by: C. Chhatpar

Date 9/29/78

Approved by: **W. V. Fuldner**

Date 17 Oct 78

This DN supplements (S), replaces (R) DN Nos.

(S) 3.2.2-001-DN

REVISIONS

Letter	Description	Date	Author
	Standard Distribution: R. deBastos W. Fuldner G. Hogan W. Hord C. Hume D. Shipley		

SUMMARY

The DE-A mission imposes severe restraints on the spacecraft thermal design, since it will remain in a fixed orientation relative to the roll and yaw axes throughout the mission. This gives a possible sun angle range of 0° to 180° for the spacecraft. Since the power subsystem cannot supply required amount of solar array power at 0° sun angle for a minimum required duty cycle of the science payload, the minimum sun angle has been restricted to $\pm 18^{\circ}$. Nevertheless, the solar flux impinges on all sides of the spacecraft and the thermal design has to be able to maintain thermal balance during all sun angles.

A baseline configuration consists of active thermal control (ATC) louvers on the top and bottom surfaces of the spacecraft with no cutouts in the end panels for the ATC's. This configuration is the same as described in the DE Technical Proposal No. 102658-C, June 30, 1978.

DESIGN CONFIGURATION

The principal features of the DE-A thermal system design are illustrated in Figure 1. Simplified thermal model data for the DE-A spacecraft is described in DE design note 3.2.2-001-DN.

The upper-and-lower end substrates (arrays) serve as the principal sinks for the internal power dissipations, as one of the two end arrays will always be in the anti-sun side of the spacecraft. The radiation couplings from the baseplate equipment to these principal radiating surfaces are varied by a set of six 14.5-inch diameter, 4-double-blade pinwheel type, active-thermal-control louvers in each array. Radiation coupling from upper baseplate to upper ATC is varied from 69.0 in^2 (louvers fully closed) to 409.0 in^2 (louvers fully open) and likewise for the radiation coupling from lower baseplate to lower ATC. The design is symmetrical with respect to upper and lower compartments, and any differences in performance can be attributed to variations in power distribution, aperture areas, and equipment duty cycles unique to the particular baseplates.

The thermal program automatically computes variable radiation couplings of internal nodes to active thermal louver area as a function of active-thermal-control louver positions (fully open to fully closed) which are dependent upon the baseplate temperatures. Since there are no cutouts in the ends of both hats, the end solar arrays act as cold sinks for the ATC's, with the end solar arrays looking into space. This DE-A configuration is obviously less efficient than that of the DE-B spacecraft where the top-hat end array has cutouts through which the internal equipment views space as a function of louver position.




Figure 1: DE-A Thermal Configuration

All data for the simplified thermal model for this configuration is contained in 3.2.2-001-DN which also describes variable parameters that depend on design configuration. Table 1 provides data of variable parameters for this configuration. Appendix A provides computer printout of temperature prediction for a representative duty cycle.

3. THERMAL PERFORMANCE


The orbit-average temperatures of upper and lower baseplates as a function of instrument-payload duty cycles, sun angles, and BOL versus EOL variations in thermal properties are plotted in Figures 2 and 3. Data for the 0-percent and 69.75-percent duty cycles are replotted in Figures 4 and 5. Table 2 extracts the data from these two figures. The 0-degree sun angle, 0-percent duty cycle is a realistic flight case (initial maneuver, injection to prior-to-final orbital configuration) which drives the upper baseplate to a worst-case cold temperature of -16°C if no heaters are present. The dual TCE control will provide for the heater power when the thermistor senses the baseplate temperature below 1°C . Figures 2 and 3 show that the spacecraft-temperature sensitivity to power dissipation is about $0.35^{\circ}\text{C}/\text{watt}$. Therefore, about 46.0 watts of heater power will be required to maintain the baseplate at 0°C , with 0-percent duty cycle of the Science payload and with the spacecraft at 0-degree sun angle. This heater power, combined with the continuous load of 18.0 watts (22-4 watt thermal), results in a required power of 64.0 watts. Since the present DE-A end solar panel can provide only 52.0 watts, only 34.0 watts of power is available for the ATCE heater. The resulting upper-baseplate temperature of -4°C is considered acceptable baseline design for the short duration phase when all the Science payload is off and non-operational temperature specification limits would be applicable. However, since batteries and tape recorders have narrower specification limits, they will require special attention. The baseplate heaters may be placed strategically near the batteries to provide them with better thermal control. Similar arrangements may be provided for the tape recorders, or wider temperature specifications may be suggested for them. An alternate approach will be to increase the end-solar-array available power by the addition of cells to accommodate the heater requirements.

At the high-temperature end, nominal Science-payload duty cycle of 62-percent (69.75-percent duty cycle of Science and playback) and spacecraft in orbital configuration, a maximum EOL orbit-average steady-state temperature of 27.5°C is obtained on the lower baseplate (see Table 2). This steady-state temperature combined with the thermal transients ($\pm 2^{\circ}\text{C}$), gradients across the baseplates (of the order of $\pm 2^{\circ}\text{C}$) as well as the uncertainty factor of $\pm 3^{\circ}\text{C}$ applied to the analytical predicts, require that the upper temperature limit of the baseplates (component mounting interfaces) be set at $+35^{\circ}\text{C}$. Again for the 62-percent duty cycle of Science payload, the BOL minimum temperature of the lower baseplate is shown to be 5.5°C for the 90-degree sun angle.

TABLE 1. VARIABLE PARAMETRIC VALUES FOR THIS CONFIGURATION

FROM	TO	INTERNAL RADIATION COUPLING (IN ²)		COMMENTS (See Note 1)
NODE	NODE	LOUVERS FULLY CLOSED	LOUVERS FULLY OPEN	
1	3	69.0	408.97	Variable values for $\gamma < 90^\circ$; fully closed lvrs values for $\gamma > 90^\circ$.
1	22	646.5	536.5	Variable values for $\gamma < 90^\circ$; fully closed lvrs values for $\gamma > 90^\circ$.
2	5	69.0	408.97	Variable values for $\gamma > 90^\circ$; fully closed lvrs values for $\gamma < 90^\circ$.
2	7	646.5	536.5	Variable values for $\gamma > 90^\circ$; fully closed lvrs values for $\gamma < 90^\circ$.
3	10	0.85	5.0	Variable values for $\gamma < 90^\circ$; fully closed lvrs values for $\gamma > 90^\circ$.
3	11	.85	5.0	Variable values for $\gamma < 90^\circ$; fully closed lvrs values for $\gamma > 90^\circ$.
3	12	.85	5.0	Variable values for $\gamma < 90^\circ$; fully closed lvrs values for $\gamma > 90^\circ$.
3	13	.85	5.0	Variable values for $\gamma < 90^\circ$; fully closed lvrs values for $\gamma > 90^\circ$.
3	22	18.4	107.1	Variable values for $\gamma < 90^\circ$; fully closed lvrs values for $\gamma > 90^\circ$.
5	7	18.4	107.1	Variable values for $\gamma > 90^\circ$; fully closed lvrs values for $\gamma < 90^\circ$.
5	14	.85	5.0	Variable values for $\gamma > 90^\circ$; fully closed lvrs values for $\gamma < 90^\circ$.
5	15	.85	5.0	Variable values for $\gamma > 90^\circ$; fully closed lvrs values for $\gamma < 90^\circ$.
5	16	.85	5.0	Variable values for $\gamma > 90^\circ$; fully closed lvrs values for $\gamma < 90^\circ$.
5	17	.85	5.0	Variable values for $\gamma > 90^\circ$; fully closed lvrs values for $\gamma < 90^\circ$.
NODE	SINK	EXTERNAL RADIATION COUPLING (IN ²)		
1	17	0.0	0.0	Variable values for $\gamma < 90^\circ$; fully closed lvrs values for $\gamma > 90^\circ$.
2	17	0.0	0.0	Variable values for $\gamma > 90^\circ$; fully closed lvrs values for $\gamma < 90^\circ$.
1	2	CONDUCTIVE COUPLING (WATTS/°C)		This value is same as used in EE analysis.
		1.25		
NOTE 1. Fully closed louvers values are applicable for baseplate temperatures below 12°C; fully open louver values for temperature above 13°C. Program computes proportional values between 12°C and 13°C.				

FIGURE 2
DE-A TEMPERATURE RESPONSE VS SCIENCE & PB PAYLOAD
UPPER BASEPLATE NODE 1. NO ATCEHEATER POWER



ORIGINAL PAGE IS
OF POOR QUALITY




FIGURE 4
DE-A UPPER AND LOWER BASEPLATE TEMPERATURES, BOL VS EOL
0% DUTY CYCLE (NO ATCE HEATER POWER)




FIGURE 5
DE-A UPPER AND LOWER BASEPLATE TEMPERATURES, BOL VS EOL
69.75% DUTY CYCLE (SCIENCE AND PLAYBACK)




TABLE 2. DE-A THERMAL PERFORMANCE: ORBIT-AVERAGE
STEADY-STATE TEMPERATURE PREDICTIONS

Description	Duty Cycle of Science Payload (%)	Sun Angle (degree)	Temperature Predictions Without TCE Heater Power (°C)					Reference	Comments
			Upper Baseplate		Lower Baseplate				
			BOL	EOL	BOL	EOL	EOL		
Injection, prior to Final On-Orbit Configuration: Non- Operational for the Science Payload	0	0	-16.0	-15.0	3.0	4.0	Figure 4	With spacecraft sen- sitivity of 0.350/watts, this will require about 46.0 watts of heater power for 0% duty cycle at 0-degree sun angle to bring the baseplate temperature to 0°C.	
		90	-12.0	-11.0	-9.0	-8.4			
Nominal Power Dis- sipation: Operation for the Science Pay- load	62 (Maximum)	15	6.2	7.2	21.6	22.6	Figure 5	Thermal Transients and gradients as well as uncertainty factors are applied to the maximum temperature of 27.5°C to arrive at the upper limit estimate of 35°C.	
		45	12.4	13.2	27.0	27.5			
		90	7.2	8.0	5.5	6.4			
		-45	25.6	26.5	12.4	13.0			
		-15	14.0	15.2	7.0	7.7			


This minimum temperature combined with the same factors mentioned above, as well as the fact that the ATCE heater set-point will be set at 1°C (heater starting to turn-on) to 0°C (heater full-on), guarantees that the lower temperature of the mounting surfaces will not be allowed to go below 0°C. This combination of maximum EOL temperature and minimum BOL temperature on the lower baseplate then dictates the thermal performance of the mounting surfaces to be from 0°C to +35°C. Since the thermal switch in the PSE automatically switches off at $37\frac{1}{2} \pm 2\frac{1}{2}$ °C, the batteries will require special attention for DE-A. Proper strategic location and accurate thermal-gradient prediction will be required to optimize battery performance during the hot sun angle of +45 degrees (+5 degrees) during mission life. If that upper temperature cannot be reduced appreciably, reduced duty cycles may be suggested for the hot sun-angle periods.

3.1 Duty-Cycle Variations

Figure 6 shows DE-A Science payload duty cycles as function of sun angle for various mounting-surface interface high-temperature limits. These plots have been generated utilizing data from Figures 2 and 3 and have been corrected for thermal transients, gradients, and uncertainty factor. These plots indicate that as the upper allowable temperature limit of the mounting surfaces (baseplates) is lowered, the permissible duty cycle also has to be reduced. For the required 62-percent duty cycle of the Science payload, EOL 35°C curves meet the performance criteria. If for any reason higher duty cycles are demanded, the allowable temperatures of the mounting surfaces will also have to be higher than the present 35°C performance limit. Actual duty cycles as a function of power available as well as the upper temperature limit set by the thermal control will finally dictate the composite duty-cycle performance of the DE-A spacecraft.

FIGURE 6

DE-A DUTY CYCLE (SCIENCE + PLAYBACK) VS SUN ANGLE
FOR VARIOUS S/C INTERFACE TEMPERATURE SPECIFICATION LIMITS



3.2 Solar-Array Thermal Performance

The end solar array panels on the DE-A hats are continuous with no cutouts and have internal surfaces of different finishes, depending on whether the area is controlled by the ATC's or is passive. The ATC parts of the end solar array panels are called the top-ATC and bottom-ATC area. It is these areas that house the louver actuator housings. The temperature of the ATC part of the end solar array is of interest, because the ATC support configuration will have to be isolated from it. The data for the average duty cycle of 50% of Science payload is plotted in Figure 7 and significant points are listed in Table 3.

The orbit-average temperatures of side array as function of sun angle is shown in Figure 8. For the 90-degree sun angle, the day-time average temperature of the side array is computed to be $+13^{\circ}\text{C}$.

The effect of aerodynamic heating, significant at the 190-km minimum perigee altitude of the DE-A mission, has not been examined so far, but will be investigated in detail to arrive at optimum solar-array performance. At present, it is noted that since the DE-A (spinning mode) altitude is higher than that of the Atmosphere Explorer (despun) mission, the effect will be far less critical for the DE-A mission than that accommodated on Atmosphere Explorer.

FIGURE 7
DE-A TOP ATC (NODE 3) AND TOP PASSIVE AREA (NODE 4), BOL VS EOL
50% DUTY CYCLE OF SCIENCE PAYLOAD





TABLE 3. SOLAR ARRAY TEMPERATURE FOR ORBIT-AVERAGE
STEADY-STATE AT 50% DUTY CYCLE OF SCIENCE
PAYLOAD

Solar Array	Sun Angle (degree)	Orbit-Average Temperature (°C)		Reference
		BOL	EOL	
Top-ATC of End solar Array	15	-76	-85	Figure 7
	45	-50	-56	
	90	-80	-80	
	-45	70	80	
	-15	102	104	
Upper Side Array	15	-52	-50	Figure 8
	45	-10	-10	
	90	-10	- 8	
	-45	10	12	
	-15	-16	-16	

FIGURE 8
DE-A UPPER SIDE ARRAY
AVERAGE OF NODES 10, 11, 12 & 13 BOL & EOL
50% DUTY CYCLE OF SCIENCE PAYLOAD



4.0 DISCUSSION

Table 2 shows that the steady-state upper bulk temperature limit of 35°C is obtained after adding certain allowances for thermal transients ($+2^{\circ}\text{C}$), thermal gradients ($+2^{\circ}\text{C}$) and the uncertainty factor ($+3^{\circ}\text{C}$). This uncertainty factor accounts for several tolerance numbers, such as inaccuracy resulting from simplification of physical characteristics into thermal model, inadequate power dissipation data, inaccurate representation of actual conductive couplings, etc. Note that degradation of surface properties is accounted for by assuming BOL and EOL values. Whatever trade-off studies are to be undertaken, this total of $+7^{\circ}\text{C}$ will be applied to the maximum baseplate temperature obtained through the computer analysis. In an attempt to reduce the maximum bulk temperature of 35°C to 25°C , the steady-state computer maximum EOL baseplate temperature of 18°C will be the design goal. After the detailed model transient analysis is carried out, the first two factors, transients and gradients, can be dropped as the detail model will address to these effects; however, the uncertainty factor of $+3^{\circ}\text{C}$ will still be applicable.

Table 4 provides thermal specification limits for DE-A spacecraft. Several instruments as well as tape recorders have an upper operational temperature limit of 35°C . The batteries have upper operational limit of 40°C for limited depth of discharge and duty cycles only; it would be preferable to lower this limit. While the need for the SAI upper limit of 25°C is not apparent, attempts will be made to lower the spacecraft bulk temperature from 35°C to 25°C .

TABLE 4. DE-A THERMAL SPECIFICATIONS

ITEM	Allowable Temperature Limit Non-Operational Operational °C °C				COMMENTS
	MIN	MAX	MIN	MAX	
MAG Electronics Boom Heat Sink	-25 -60	50 60	-10 -40	40 40	External to spacecraft. Preferred temperature range is 0°C to 20°C Maximum operational limit is applicable for limited DOD and cycles only. Performance specification: GSFC-DE-100-21-0
PWI Electronics & Preamplifier Tubular & Wire Antenna	-40 -20	60 40	-20 0	50 30	
SAI	-25	45	-15	25	
HAPI	-35	40	0	35	
RIMS	-40	60	-20	40	
EICS	-40	55	0	35	
BHS	-5	45	0	35	
BATTERY	-5	40	0	40	
TR	-17	35	-17	35	
TRANSPONDER (NST)	-25	70	-15	50	

NOTES: 1. All limits are applicable on unit mounting interface.

2. Temperature limits of all GFE items have been obtained from the latest UNDOCS information.

To meet the temperature specification for the DE-A spacecraft following operating parameters will be considered:

- 67.5% duty cycle of science and playback load
- Sun angle = $\pm 45^{\circ}$ (hot case), $\pm 18^{\circ}$ and 90° (cold case)
- 14.5" diameter ATC louvers
- Maximum EOL bulk temperature = 25°C
- Maximum EOL computer baseplate temperature = 18°C
- Minimum BOL bulk temperature = 0°C
(obtained through use of baseplate heaters, if necessary)
- Design to have some positive louver margin, if possible (if louvered configuration is used) at hot end.
- Design to have some positive heater margin at cold end.

APPENDIX A
PRINTOUT OF COMPUTER PROGRAM OF
STEADY-STATE TEMPERATURE PREDICTIONS
FOR
33.75% DUTY CYCLE OF
SCIENCE AND PLAYBACK PAYLOAD

Table A-3. Conductive Coupling Between Nodes (w/°C)

1	2	1.250000	1	16	0.028000	1	11	0.028000	1	12	0.628000
1	13	0.028000	1	22	1.260000	2	7	1.260000	2	14	0.024000
2	13	0.028000	2	16	0.028000	2	17	0.028000	3	4	0.030000
4	17	0.030000	4	11	0.030000	4	12	0.030000	4	13	0.500000
4	22	0.030000	5	6	0.050000	5	7	0.100000	6	14	0.500000
1	11	0.040000	1	13	0.040000	8	17	0.050000	7	7	0.200000
1	13	0.040000	12	13	0.040000	10	18	0.050000	11	12	0.040000
14	17	0.040000	12	13	0.040000	12	20	0.060000	13	21	0.090000
14	17	0.040000	16	17	0.040000	14	14	0.060000	15	16	0.040000
1	17	0.040000	16	17	0.040000	14	26	0.050000	17	21	0.090000
1	17	0.040000	17	21	0.027000	19	20	0.027000	20	21	0.027000

Table A-4. Radiation Coupling from Node to Sink (in²)

1	1	50.783305	2	16	62.518997	3	1	602.560000	4	1	752.100698
1	1	0.000000	5	16	752.100698	7	17	9.500000	8	17	4.900000
17	1	0.000000	14	6	0.000000	11	3	633.899902	12	4	633.899902
17	1	0.000000	14	11	34.399994	15	2	633.899902	16	4	633.899902
17	1	0.000000	14	11	34.399994	15	2	34.399994	20	13	34.399994
17	1	0.000000	14	11	34.399994	15	2	4.900000	24	17	10.000000

Table A-4. Thermal Sink Value for Sun Angle = 0° (watts/ in²)

1	1	0.0000	3	4	0.0000	5	0.0000	6	0.0000	12	0.0000
1	1	0.0000	9	10	0.0000	11	0.8120	11	0.0000	12	0.0000
1	1	0.0000	15	16	0.0000	17	0.0000	17	0.0000	17	0.0000

Table A-5 Temperature Distribution ($^{\circ}\text{C}$) for Various sun angles at 33.75% Duty Cycle

BOL; 0° Sun Angle

1	-1.5125	2	9.2556	3	-107.6909	14	-100.5672	5	102.4017	6	73.4639
7	14.2103	8	20.4663	9	95.4712	10	-99.3896	11	-96.6295	12	-98.0295
13	30.5773	14	36.5773	15	36.5773	16	-38.5471	17	-38.5471	18	-72.7811
19	-70.4434	20	-70.4434	21	-70.7811	22	-14.6150	23	-15.8181	24	-54.8695

BOL; 45° Sun Angle

1	12.4342	2	20.4134	3	-57.4553	4	-41.6700	5	74.9661	6	61.3303
7	6.3727	8	31.0875	9	70.4895	10	-9.1966	11	-9.0396	12	-8.8730
13	11.1145	14	11.1145	15	11.1145	16	-11.4143	17	-11.1511	18	5.7380
19	1.1145	20	5.6835	21	6.5715	22	6.3223	23	4.9023	24	-30.2196

BOL; 90° Sun Angle

1	-3.0425	2	-0.9309	3	-79.6445	4	-47.3445	5	-79.1861	6	-47.0901
7	-4.0125	8	-5.0879	9	-14.2263	10	-10.0149	11	-10.0800	12	-9.9016
13	0.0000	14	0.0000	15	0.0000	16	-9.7593	17	-9.8387	18	-8.6380
19	-5.7131	20	-0.5769	21	-0.2651	22	-5.9661	23	-7.0371	24	-15.2749

BOL; -45° Sun Angle

1	12.4342	2	12.4636	3	74.4059	4	61.4808	5	-56.6942	6	-41.4489
7	6.3727	8	4.0050	9	-34.3868	10	10.8721	11	18.9883	12	11.1381
13	11.1145	14	11.1145	15	11.1145	16	-9.8483	17	-9.3383	18	35.3159
19	1.1145	20	5.6835	21	5.6449	22	27.6303	23	29.5256	24	77.8750

BOL; -90° Sun Angle

1	1.5272	2	-20.7576	3	102.4067	4	72.9072	5	-100.3736	6	-102.6524
7	-17.7744	8	-14.5015	9	-53.4184	10	-39.4511	11	-39.1986	12	-39.1985
13	11.1145	14	11.1145	15	11.1145	16	-101.1483	17	-101.1483	18	-73.8866
19	-73.8737	20	-73.8737	21	-73.8866	22	15.6182	23	28.4473	24	99.8913

E0°; 0° Sun Angle

RESULTS TABLE OF ITERATION FOR I												
1	1	16.4127	2	16.2372	3	-116.1873	4	-153.1809	5	106.5286	6	77.5680
7	17.7156	8	22.4180	9	100.3101	10	-102.1429	11	-101.5688	12	-101.5710	
13	18.2131	14	37.5544	15	37.5544	16	-37.5474	17	-38.3737	18	-75.8290	
19	13.5149	20	-73.5180	21	-74.0328	22	-13.4960	23	-15.1067	24	-54.3016	

EOL; 45° Sun Angle

Year	1	2	3	4	5	6
1950	12,4207	26,3401	59,4935	42,2375	78,3416	64,6309
1951	15,0174	32,1453	78,1736	51,1726	93,3428	84,8496
1952	17,1133	32,1410	11,9807	12,3732	11,9111	16,7979
1953	27,4225	15,9386	17,6967	6,1731	4,7549	36,3391

EOL: 90° Sun Angle

REGISTRATION NUMBER	DATE	TIME	LOCATION	TYPE	STATUS	REMARKS
1	12-1-68	10:30	100	1	1	1
2	12-1-68	10:30	100	1	1	1
3	12-1-68	10:30	100	1	1	1
4	12-1-68	10:30	100	1	1	1
5	12-1-68	10:30	100	1	1	1
6	12-1-68	10:30	100	1	1	1
7	12-1-68	10:30	100	1	1	1
8	12-1-68	10:30	100	1	1	1
9	12-1-68	10:30	100	1	1	1
10	12-1-68	10:30	100	1	1	1
11	12-1-68	10:30	100	1	1	1
12	12-1-68	10:30	100	1	1	1
13	12-1-68	10:30	100	1	1	1
14	12-1-68	10:30	100	1	1	1
15	12-1-68	10:30	100	1	1	1
16	12-1-68	10:30	100	1	1	1
17	12-1-68	10:30	100	1	1	1
18	12-1-68	10:30	100	1	1	1
19	12-1-68	10:30	100	1	1	1
20	12-1-68	10:30	100	1	1	1
21	12-1-68	10:30	100	1	1	1
22	12-1-68	10:30	100	1	1	1
23	12-1-68	10:30	100	1	1	1
24	12-1-68	10:30	100	1	1	1
25	12-1-68	10:30	100	1	1	1
26	12-1-68	10:30	100	1	1	1
27	12-1-68	10:30	100	1	1	1
28	12-1-68	10:30	100	1	1	1
29	12-1-68	10:30	100	1	1	1
30	12-1-68	10:30	100	1	1	1
31	12-1-68	10:30	100	1	1	1
32	12-1-68	10:30	100	1	1	1
33	12-1-68	10:30	100	1	1	1
34	12-1-68	10:30	100	1	1	1
35	12-1-68	10:30	100	1	1	1
36	12-1-68	10:30	100	1	1	1
37	12-1-68	10:30	100	1	1	1
38	12-1-68	10:30	100	1	1	1
39	12-1-68	10:30	100	1	1	1
40	12-1-68	10:30	100	1	1	1
41	12-1-68	10:30	100	1	1	1
42	12-1-68	10:30	100	1	1	1
43	12-1-68	10:30	100	1	1	1
44	12-1-68	10:30	100	1	1	1
45	12-1-68	10:30	100	1	1	1
46	12-1-68	10:30	100	1	1	1
47	12-1-68	10:30	100	1	1	1
48	12-1-68	10:30	100	1	1	1
49	12-1-68	10:30	100	1	1	1
50	12-1-68	10:30	100	1	1	1
51	12-1-68	10:30	100	1	1	1
52	12-1-68	10:30	100	1	1	1
53	12-1-68	10:30	100	1	1	1
54	12-1-68	10:30	100	1	1	1
55	12-1-68	10:30	100	1	1	1
56	12-1-68	10:30	100	1	1	1
57	12-1-68	10:30	100	1	1	1
58	12-1-68	10:30	100	1	1	1
59	12-1-68	10:30	100	1	1	1
60	12-1-68	10:30	100	1	1	1
61	12-1-68	10:30	100	1	1	1
62	12-1-68	10:30	100	1	1	1
63	12-1-68	10:30	100	1	1	1
64	12-1-68	10:30	100	1	1	1
65	12-1-68	10:30	100	1	1	1
66	12-1-68	10:30	100	1	1	1
67	12-1-68	10:30	100	1	1	1
68	12-1-68	10:30	100	1	1	1
69	12-1-68	10:30	100	1	1	1
70	12-1-68	10:30	100	1	1	1
71	12-1-68	10:30	100	1	1	1
72	12-1-68	10:30	100	1	1	1
73	12-1-68	10:30	100	1	1	1
74	12-1-68	10:30	100	1	1	1
75	12-1-68	10:30	100	1	1	1
76	12-1-68	10:30	100	1	1	1
77	12-1-68	10:30	100	1	1	1
78	12-1-68	10:30	100	1	1	1
79	12-1-68	10:30	100	1	1	1
80	12-1-68	10:30	100	1	1	1
81	12-1-68	10:30	100	1	1	1
82	12-1-68	10:30	100	1	1	1
83	12-1-68	10:30	100	1	1	1
84	12-1-68	10:30	100	1	1	1
85	12-1-68	10:30	100	1	1	1
86	12-1-68	10:30	100	1	1	1
87	12-1-68	10:30	100	1	1	1
88	12-1-68	10:30	100	1	1	1
89	12-1-68	10:30	100	1	1	1
90	12-1-68	10:30	100	1	1	1
91	12-1-68	10:30	100	1	1	1
92	12-1-68	10:30	100	1	1	1
93	12-1-68	10:30	100	1	1	1
94	12-1-68	10:30	100	1	1	1
95	12-1-68	10:30	100	1	1	1
96	12-1-68	10:30	100	1	1	1
97	12-1-68	10:30	100	1	1	1
98	12-1-68	10:30	100	1	1	1
99	12-1-68	10:30	100	1	1	1
100	12-1-68	10:30	100	1	1	1

EOL: -45° Sun Angle

1	23.6371	2	12.5044	3	70.5053	4	64.3699	5	-56.7312	6	-42.8207
7	5.5753	-	4.9188	9	-38.4972	10	11.6799	11	11.4458	12	11.6645
13	11.0419	14	-9.5122	15	-7.5169	16	-7.0151	17	-9.2783	18	16.5308
17	2.4305	21	16.5050	22	17.4807	23	27.8306	24	30.3920	25	78.1140

EOL; -0° Sun Angle

Iteration	Iteration for	4	5	6
1	10.0594	106.9810	77.3462	-110.9031
2	-4.5425	3	11	12
3	13.0694	9	10	-38.9332
4	-13.2461	15	16	-104.9470
5	10.0594	21	22	21.9368
6	-75.0277	26	27	21.9368
7	10.0594	31	32	21.9368
8	-13.2461	37	38	21.9368
9	10.0594	43	44	21.9368
10	-75.0277	49	50	21.9368
11	10.0594	55	56	21.9368
12	-13.2461	61	62	21.9368
13	10.0594	67	68	21.9368
14	-75.0277	73	74	21.9368
15	10.0594	79	80	21.9368
16	-13.2461	85	86	21.9368
17	10.0594	91	92	21.9368
18	-75.0277	97	98	21.9368
19	10.0594	103	104	21.9368
20	-13.2461	109	110	21.9368
21	10.0594	115	116	21.9368
22	-75.0277	121	122	21.9368
23	10.0594	127	128	21.9368
24	-13.2461	133	134	21.9368
25	10.0594	139	140	21.9368
26	-75.0277	145	146	21.9368
27	10.0594	151	152	21.9368
28	-13.2461	157	158	21.9368
29	10.0594	163	164	21.9368
30	-75.0277	169	170	21.9368
31	10.0594	175	176	21.9368
32	-13.2461	181	182	21.9368
33	10.0594	187	188	21.9368
34	-75.0277	193	194	21.9368
35	10.0594	199	200	21.9368
36	-13.2461	205	206	21.9368
37	10.0594	211	212	21.9368
38	-75.0277	217	218	21.9368
39	10.0594	223	224	21.9368
40	-13.2461	229	230	21.9368
41	10.0594	235	236	21.9368
42	-75.0277	241	242	21.9368
43	10.0594	247	248	21.9368
44	-13.2461	253	254	21.9368
45	10.0594	259	260	21.9368
46	-75.0277	265	266	21.9368
47	10.0594	271	272	21.9368
48	-13.2461	277	278	21.9368
49	10.0594	283	284	21.9368
50	-75.0277	289	290	21.9368
51	10.0594	295	296	21.9368
52	-13.2461	301	302	21.9368
53	10.0594	307	308	21.9368
54	-75.0277	313	314	21.9368
55	10.0594	319	320	21.9368
56	-13.2461	325	326	21.9368
57	10.0594	331	332	21.9368
58	-75.0277	337	338	21.9368
59	10.0594	343	344	21.9368
60	-13.2461	349	350	21.9368
61	10.0594	355	356	21.9368
62	-75.0277	361	362	21.9368
63	10.0594	367	368	21.9368
64	-13.2461	373	374	21.9368
65	10.0594	379	380	21.9368
66	-75.0277	385	386	21.9368
67	10.0594	391	392	21.9368
68	-13.2461	397	398	21.9368
69	10.0594	403	404	21.9368
70	-75.0277	409	410	21.9368
71	10.0594	415	416	21.9368
72	-13.2461	421	422	21.9368
73	10.0594	427	428	21.9368
74	-75.0277	433	434	21.9368
75	10.0594	439	440	21.9368
76	-13.2461	445	446	21.9368
77	10.0594	451	452	21.9368
78	-75.0277	457	458	21.9368
79	10.0594	463	464	21.9368
80	-13.2461	469	470	21.9368
81	10.0594	475	476	21.9368
82	-75.0277	481	482	21.9368
83	10.0594	487	488	21.9368
84	-13.2461	493	494	21.9368
85	10.0594	499	500	21.9368
86	-75.0277	505	506	21.9368
87	10.0594	511	512	21.9368
88	-13.2461	517	518	21.9368
89	10.0594	523	524	21.9368
90	-75.0277	529	530	21.9368
91	10.0594	535	536	21.9368
92	-13.2461	541	542	21.9368
93	10.0594	547	548	21.9368
94	-75.0277	553	554	21.9368
95	10.0594	559	560	21.9368
96	-13.2461	565	566	21.9368
97	10.0594	571	572	21.9368
98	-75.0277	577	578	21.9368
99	10.0594	583	584	21.9368
100	-13.2461	589	590	21.9368
101	10.0594	595	596	21.9368
102	-75.0277	601	602	21.9368
103	10.0594	607	608	21.9368
104	-13.2461	613	614	21.9368
105	10.0594	619	620	21.9368
106	-75.0277	625	626	21.9368
107	10.0594	631	632	21.9368
108	-13.2461	637	638	21.9368
109	10.0594	643	644	21.9368
110	-75.0277	649	650	21.9368
111	10.0594	655	656	21.9368
112	-13.2461	661	662	21.9368
113	10.0594	667	668	21.9368
114	-75.0277	673	674	21.9368
115	10.0594	679	680	21.9368
116	-13.2461	685	686	21.9368
117	10.0594	691	692	21.9368
118	-75.0277	697	698	21.9368
119	10.0594	703	704	21.9368
120	-13.2461	709	710	21.9368
121	10.0594	715	716	21.9368
122	-75.0277	721	722	21.9368
123	10.0594	727	728	21.9368
124	-13.2461	733	734	21.9368
125	10.0594	739	740	21.9368
126	-75.0277	745	746	21.9368
127	10.0594	751	752	21.9368
128	-13.2461	757	758	21.9368
129	10.0594	763	764	21.9368
130	-75.0277	769	770	21.9368
131	10.0594	775	776	21.9368
132	-13.2461	781	782	21.9368
133	10.0594	787	788	21.9368
134	-75.0277	793	794	21.9368
135	10.0594	799	800	21.9368
136	-13.2461	805	806	21.9368
137	10.0594	811	812	21.9368
138	-75.0277	817	818	21.9368
139	10.0594	823	824	21.9368
140	-13.2461	829	830	21.9368
141	10.0594	835	836	21.9368
142	-75.0277	841	842	21.9368
143	10.0594	847	848	21.9368
144	-13.2461	853	854	21.9368
145	10.0594	859	860	21.9368
146	-75.0277	865	866	21.9368
147	10.0594	871	872	21.9368
148	-13.2461	877	878	21.9368
149	10.0594	883	884	21.9368
150	-75.0277	889	890	21.9368
151	10.0594	895	896	21.9368
152	-13.2461	901	902	21.9368
153	10.0594	907	908	21.9368
154	-75.0277	913	914	21.9368
155	10.0594	919	920	21.9368
156	-13.2461	925	926	21.9368
157	10.0594	931	932	21.9368
158	-75.0277	937	938	21.9368
159	10.0594	943	944	21.9368
160	-13.2461	949	950	21.9368
161	10.0594	955	956	21.9368
162	-75.0277	961	962	21.9368
163	10.0594	967	968	21.9368
164	-13.2461	973	974	21.9368
165	10.0594	979	980	21.9368
166	-75.0277	985	986	21.9368
167	10.0594	991	992	21.9368
168	-13.2461	997	998	21.9368
169	10.0594	1003	1004	21.9368
170	-75.0277	1009	1010	21.9368
171	10.0594	1015	1016	21.9368
172	-13.2461	1021	1022	21.9368
173	10.0594	1027	1028	21.9368
174	-75.0277	1033	1034	21.9368
175	10.0594	1039	1040	21.9368
176	-13.2461	1045	1046	21.9368
177	10.0594	1051	1052	21.9368
178	-75.0277	1057	1058	21.9368
179	10.0594	1063	1064	21.9368
180	-13.2461	1069	1070	21.9368
181	10.0594	1075	1076	21.9368
182	-75.0277	1081	1082	21.9368
183	10.0594	1087	1088	21.9368
184	-13.2461	1093	1094	21.9368
185	10.0594	1099	1100	21.9368
186	-75.0277	1105	1106	21.9368
187	10.0594	1111	1112	21.9368
188	-13.2461	1117	1118	21.9368
189	10.0594	1123	1124	21.9368
190	-75.0277	1129	1130	21.9368
191	10.0594	1135	1136	21.9368
192	-13.2461	1141	1142	21.9368
193	10.0594	1147	1148	21.9368
194	-75.0277	1153	1154	21.9368
195	10.0594	1159	1160	21.9368
196	-13.2461	1165	1166	21.9368
197	10.0594	1171	1172	21.9368
198	-75.0277	1177	1178	21.9368
199	10.0594	1183	1184	21.9368
200	-13.2461	1189	1190	21.9368
201	10.0594	1195	1196	21.9368
202	-75.0277	1201	1202	21.9368
203	10.0594	1207	1208	21.9368
204	-13.2461	1213	1214	21.9368
205	10.0594	1219	1220	21.9368
206	-75.0277	1225	1226	21.9368
207	10.0594	1231	1232	21.9368
208	-13.2461	1237	1238	21.9368
209	10.0594	1243	1244	21.9368
210	-75.0277	1249	1250	21.9368
211	10.0594	1255	1256	21.9368
212	-13.2461	1261	1262	21.9368
213	10.0594	1267	1268	21.9368
214	-75.0277	1273	1274	21.9368
215	10.0594	1279	1280	21.9368
216	-13.2461	1285	1286	21.9368
217	10.0594	1291	1292	21.9368
218	-75.0277	1297	1298	21.9368
219	10.0594	1303	1304	21.9368
220	-13.2461	1309	1310	21.9368
221	10.0594	1315	1316	21.9368
222	-75.0277	1321	1322	21.9368
223	10.0594	1327	1328	21.9368
224	-13.2461	1333	1334	21.9368
225	10.0594	1339	1340	21.9368
226	-75.0277	1345	1346	21.9368
227	10.0594	1351	1352	21.9368
228	-13.2461	1357	1358	21.9368
229	10.0594	1363	1364	21.9368
230	-75.0277	1369	1370	21.9368
231	10.0594	1375	1376	21.9368
232	-13.2461	1381	1382	21.9368
233	10.0594	1387	1388	21.9368
234	-75.0277	1393	1394	21.9368
235	10.0594	1399	1400	21.9368
236	-13.2461	1405	1406	21.9368
237	10.0594	1411	1412	21.9368
238	-75.0277			

-Design Note

IREA Astro Electronics

- Originating Project or Group		Note No.
		3.2.2-004-DN
Title		
DE-A PARAMETRIC THERMAL STUDY		
Written by:		Date
C. Chhatpar <i>CC</i>		October 3, 1978
Approved by:		Date
W. V. Fuldner <i>W.V. Fuldner</i>		17 Oct 78
This DN supplements (S), replaces (R) DN Nos.		Send one copy of this Note to the DCC (Library) attached to a copy of Form AED 1488.
(S) 3.2.2-001-DN (S) 3.2.2-003-DN		

Letter	Description	Date	Author
	Standard Distribution: R. deBastos W. Fuldner G. Hogan W. Hord C. Hume D. Shipley		

Standard Distribution:
R. deBastos
W. Fuldner
G. Hogan
W. Hord
C. Hume
D. Shipley

1. Summary

As recommended in 3.2.2-003-DN, the upper temperature specification limit of 35°C obtained for the baseline thermal design has to be lowered to 25°C. This design note describes various design configurations and their performance, along with advantages and disadvantages of each. Following configurations are investigated in this parametric study:

1. Various cutouts in the end panel for ATC's to allow baseplate complement to directly view the space.
2. Lowering the operational active louver set points, thereby allowing the non-controlled baseplate to be coupled to a cooler controlled baseplate.
3. Increase conductive coupling between the baseplates by conventional means.
4. Incorporation of heat pipes ("Goddard Groove" Isothermalizer type) to conductively couple the two baseplates.

It is shown (see Section 3.5) that by combination of significant features of various configurations, it is possible to achieve upper maximum bulk temperature of 25°C. However, failure analysis as well as testing complexities make this configuration less attractive.

2. General

In discussing various configurations, the analysis concentrates on the following parameters:

- 67.5% duty cycle of science and playback payload. This is considered as maximum required duty cycle and is defined as the percent of every orbit time that the instruments with their playback stay on. The steady state temperature computations performed by the computer program consider this input as an orbit average internal power dissipation distributed between the upper and lower baseplates. No distinction is made as to which particular instruments are turned on and for how long. Only total bulk power dissipation is required to generate the bulk temperatures.

- Temperature predictions for $+45^{\circ}$ sun angle, EOL values are shown to be the maximum bulk temperatures and are primarily discussed whenever comparison to upper bulk temperature limit of 25° is considered.
- Thermal gradients ($+2^{\circ}\text{C}$), thermal transients ($+2^{\circ}\text{C}$) and uncertainty factor ($+3^{\circ}\text{C}$) are lumped together to give $+7^{\circ}\text{C}$ error margin on computer generated maximum steady state bulk temperatures. These factors require maximum analytical predictions of 18°C to give maximum bulk temperature of 25°C .

3.1 ATC Cutouts in End Array (Configuration 1)

The baseline configuration described in 3.2.2-003-DN consists of 6 louvers at each flat end of the spacecraft, with no cutouts in the end panels. The anti-sun facing end array acts as a radiator sink for the ATC's, with the controlled baseplate viewing radiator or insulator or a combination of the two segments of the inside of the end array. Under worst case hot use, say $\theta = +45^{\circ}$, the upper baseplate then effectively sees a -60°C end array, not quite an effective sink compared to space sink.

More efficient way of dumping heat through the louvers would be to provide cutouts in the end array to allow the baseplate to directly view the space. This, however, means that no solar cells can exist in the area cutout. Hence the degree of cutouts have to be compatible with the required number of solar cells to provide minimum power necessary at $\theta = 0^{\circ}$ during initial maneuver of the spacecraft.

Following constraints enter into overall consideration:

- a) Instrument payload accommodation, specifically ± 2 RIMS.
- b) S-Band antenna bracket accommodation.
- c) Conductive bare-metal area requirements (can be thermally acceptable by painting with Goddard 'Green').
- d) Mechanical interface requirements.
- e) Cold patches at center hubs of ATC's to locally cool the bi-metal housings under worst case hot sun angles to allow actuator to closely track the baseplate temperatures under control.
- f) Minimum number of solar cells required to meet $\theta = 0^{\circ}$ power requirements.
- g) Problems at hot end with solar flux impinging upon closed louvers.

A preliminary parametric study was conducted to evaluate the feasibility of using smaller diameter ATC's to accommodate RIMS. The study showed that the baseline ATC diameter of 14.5" was necessary to offer any appreciable performance improvements. The ATC diameter variation was dropped from further parameteric study. The RIMS has been accommodated by certain other rearrangements.

As pointed out earlier, 67.5% duty cycle, 45° sun angle, EOL bulk temperature of 25°C is the design goal. For a double bladed louver design, the maximum cutout per ATC segment can be 60°. Table 1 and 2 provide data for variable parameters for 20° and 40° ATC cutouts respectively. Other fixed parameter data for this simplified thermal model is given in DE design note 3.2.2-001-DN.

Temperature performance for 0°, 20° and 40° cutouts are plotted in Figure 1 and are extrapolated to full 60° cutouts. Note that 0° cutout data corresponds to no cutout in end array described in 3.2.2-003-DN. Also plotted on the same figure are number of solar array strings on end panels. Power subsystem requirements dictate that at least 8 strings be available, giving roughly 55° ATC cutout possibility.

Figure 1 shows that as the ATC cutouts are increased, there is an insignificant drop in the lower (hotter for $\gamma=+45^\circ$) baseplate temperature, for a 12°C louver setpoint on the upper baseplate. The louver margin increases significantly, meaning that not as much of louver rotation is required as provided. This is because the controlled baseplate (upper in this case) is always between 12°C and 13°C no matter how much additional heat dumping capability is provided. The hotter baseplate is always coupled to this 12°C-13°C sink, resulting in negligible drop in temperature.

If cooling of the hotter baseplate is required, then it will be necessary to couple it to a cooler controlled baseplate. This translates into a lower louver active set point.

Hence this parametric study indicates that merely providing ATC cutouts in end arrays does not meet the bulk temperature specification requirements of 25°C.

TABLE 1. Variable Parametric Values for 20° ATC Cutout Configuration

FROM		TO	INTERNAL RADIATION COUPLING (IN ²)		COMMENTS (see note 1)
NODE	NODE	NODE	LOUVERS FULLY CLOSED	LOUVERS FULLY OPEN	
1	3		69.0	280.05	Variable values for $\gamma < 90^\circ$; fully closed lvrs values for $\gamma > 90^\circ$ " " " " " $\gamma > 90^\circ$; fully closed lvrs values for $\gamma < 90^\circ$ " " " " " $\gamma < 90^\circ$; " " $\gamma > 90^\circ$ " " " " " " " " " " " " " " " " " $\gamma > 90^\circ$; " " $\gamma < 90^\circ$ " $\gamma > 90^\circ$; " " $\gamma < 90^\circ$ " " " " " " " " " " " " " " " "
1	22		646.5	536.5	
2	5		69.0	280.05	
2	7		646.5	536.5	
3	10		.85	5.0	
3	11		.85	5.0	
3	12		.85	5.0	
3	13		.85	5.0	
3	22		18.4	107.1	
5	7		18.4	107.1	
5	14		.85	5.0	
5	15		.85	5.0	
5	16		.85	5.0	
5	17		.85	5.0	
NODE	SINK	EXTERNAL RADIATION COUPLING (IN ²)		This value is same as used in EE analysis.	
1	17	0.0	136.88		
2	17	0.0	136.88		
		CONDUCTIVE COUPLING (WATTS/°C)			
1	2	1.25			


Note 1. Fully closed louver values are applicable for baseplate temperature below 120°C; fully open values for temperatures above 130°C. Program computes proportional values between 120°C and 130°C.

TABLE 2. VARIABLE PARAMETRIC VALUES FOR 40° ATC CUTOFF CONFIGURATION

FROM	TO	INTERNAL RADIATION COUPLING (IN ²)		COMMENTS (SEE NOTE 1)
NODE	NODE	LOUVERS FULLY CLOSED	LOUVERS FULLY OPEN	
1	3	69.0	156.86	Variable values for $\gamma < 90^\circ$; fully closed ltrs values for $\gamma > 90^\circ$
1	22	646.5	536.5	
2	5	69.0	156.86	
2	7	646.5	536.5	
3	10	.85	5.0	
3	11	.85	5.0	
3	12	.85	5.0	
3	13	.85	5.0	
3	22	18.4	107.1	
5	7	18.4	107.1	
5	14	.85	5.0	
5	15	.85	5.0	
5	16	.85	5.0	
5	17	.85	5.0	
EXTERNAL RADIATION COUPLING (IN ²)				
NODE	SINK			
1	17	0.0	273.75	Variable values for $\gamma < 90^\circ$; fully closed ltrs values for $\gamma > 90^\circ$
2	17	0.0	273.75	
CONDUCTIVE COUPLING (WATTS/°C)				This value is same as used in EE analysis.
1	2	1.25		

NOTE 1. Same as in Table 1.

FIGURE 1
DE-A END ARRAY CAPABILITY AND
UBP & LBP MAXIMUM TEMPERATURE, BOL VS EOL
67.5% DUTY CYCLE 45° SUN ANGLE
14.5" ϕ ATC, 12°C LOUVER SETPOINT



3.2 Louver Active Set Point (Configuration 2)


The louver active set point refers to a temperature of the controlled baseplate sensed by a thermistor that activates a heater on bimetallic actuator of ATC louver assembly. The set point is the temperature when louver first starts to open, with louver fully open at temperature 1°C higher. As long as there is sufficient heat dumping capability of the louver system, the controlled baseplate is always between its set point and 1°C higher. The other baseplate is likewise coupled to this almost constant temperature heat sink. All the variable parameter data as shown for the 40° ATC cutouts are applicable for this study, except that the louver control point is varied.

Figure 2 shows the results of 12°C , 5°C , and 0°C active louver set points for 67.5% duty cycle, 45° sun angle EOL values. Points on the figure for this parametric study correspond to K_{12} (conductive coupling between upper and lower baseplate) of $1.25 \text{ watts}/^{\circ}\text{C}$ (designated as EE coupling). While there is 4.5°C and 3°C drop in temperature for changing the set point from 12°C to 5°C and 5°C to 0°C respectively, the bulk temperature specification limit of 25°C is still not met with this design modification. $K_{12} = 1.25 \text{ W}/^{\circ}\text{C}$ pertains to conductive coupling as used in the EE design notes. More accurate computation of this coupling results in a slightly higher value. Note that increasing the cutouts to 50° doesn't gain much in performance.

This parametric study shows that by providing ATC cutouts in end arrays and lowering the louver set points doesn't meet the bulk temperature specification requirement of 25°C . As the Figure 2 shows, the parametric study with respect to K_{12} , the conductive coupling between the baseplates, seems to show promising results.

FIGURE 2

DE-A MAXIMUM BULK TEMPERATURE, EOL
67.5% DUTY CYCLE, 45° SUNANGLE
14.5" ϕ ATC



3.3 Conductive Coupling Between Baseplates (Configuration 3)

Figure 2 shows that for $K_{12} = 1.25 \text{ w/}^{\circ}\text{C}$ the maximum EOL bulk temperature is 27°C for a 0°C lower set point, still above the specification requirement of 25°C . As a result, parametric study was carried out to evaluate the effect of better conductivity coupling between the two baseplates by some means.

Figure 2 shows that for $K_{12} = 2.0 \text{ w/}^{\circ}\text{C}$ and 40° cutouts for ATC, the EOL bulk temperature of 25°C is obtained for a 0°C louver set point. This increase in conductive coupling can be accomplished in two conventional ways:

- a) Increase thickness of shear webs connecting the two baseplates and increase wall thickness of center column.
- b) Employ higher conductivity material to gain higher K_{ij} with minimum weight increase.

Since the center column material is magnesium ($K = 3.12 \text{ w/in}^{\circ}\text{C}$), any weight-effective increase in conductive coupling can be accomplished only by increasing the wall thickness. Changing the material to higher density aluminum does not contribute effectively. Hence increasing the conductive coupling by changing material and increasing thickness of shear webs is investigated. Table 4 shows candidate materials and their thermal conductivity values.

Keeping the joint conductances the same ($K = .3 \text{ w/in}^2/^{\circ}\text{C}$ for a dry joint), the increase in shear web thickness to obtain specific K_{12} results in certain weight increase, plotted in Figure 3 for three candidate materials. For a specific K_{12} from Figure 2, corresponding bulk temperature can also be obtained for a selected louver set point. This data is translated into Figure 4 which shows bulk temperature vs. total net weight change for the three candidate materials for 0°C louver set point, EOL data. This data is already corrected for weight saving obtained by eliminating doublerplates as shear web thickness increases. It appears that for a 25°C bulk operating specification limit, 6061-T6 for shear webs results in a net weight gain of approximately 3.5 lbs, which is considered quite acceptable.

TABLE 4.
THERMAL CONDUCTIVITY VALUES FOR CANDIDATE MATERIALS

Structure	Material		Thermal Conductivity w/in ^o C
Shear webs	Aluminum	2024-T4 (present)	3.0
		2014-T62	3.96
		6061-T6	4.22
Center Column	Magnesium ZK60A-T6		3.12

FIGURE 3

DE-A

CONDUCTIVE COUPLING BETWEEN BASEPLATES VS WEIGHT CHANGE
FOR DIFFERENT SHEAR WEB MATERIALS





FIGURE 4

DE-A MAXIMUM BULK TEMPERATURE, EDL VS SHEAR WEB
WEIGHT CHANGE FOR SOME CANDIDATE MATERIALS
40° ATC CUTOUTS
0°C LOUVER SET POINT



3.4 Heat Pipe Configuration (Goddard 'Groove') (Configuration 4)

Figure 2 shows that increasing the K_{12} between the two baseplates has considerable effect in reducing the maximum EOL bulk temperatures. As an extrapolation effort to further increase the conductive coupling between the two baseplates, heat pipes of isothermalizer type (Goddard 'Groove') were incorporated in the simplified thermal model.

The analysis deals with heat pipe on an overall bulk basis, in that the effective increase in conductive coupling is lumped into K_{12} which represents total conductive coupling between the upper and lower baseplates. Table 5 shows design data for two configurations; one with 40° ATC cutouts and one for no ATC cutouts.

Figure 5 illustrates the performance results for the two configurations considered. Note that analysis is carried out for the baseline 67.5% duty cycle of science and playback payload for +45° sun angle, for a 5°C louver set point. Only BOL data are plotted, because the intention is to discuss the overall trend of the effect of heat pipes. The actual EOL values can be obtained by adding another 1°C to the BOL values.

3.4.1 0° ATC Cutout with Heat Pipes


The curves show that as the conductive coupling is increased by adding more heat pipes, the two baseplates get clamped together with about 3°C asymptotic temperature differential between the two. However, the hotter of the two baseplates (lower in this case) does not cool off to 25°C bulk temperature until at least 4 heat pipes are incorporated. The upper baseplate (the ATC controlled one in this case), on the other hand, starts out with 9°C on the (computer) baseplate temperature while the louver set point was set at 5°C. This means that louvers will be wide open, with upper baseplate out of louver control range. Adding more heat pipes only makes the situation worse. It may, at first, appear that the final temperatures are acceptable, but without louvers maintaining control of the upper baseplate, the failure analysis of ATC's makes this configuration very undesirable.

Table 5. DE-A Thermal Model Description for Inclusion of Heat Pipes

Fixed Parameter Data	Ref. DE Design Note 3.2.2-001-DN				
Variable Parameter Data	40° ATC Cutouts	0° Cutout			
(Internal and External Radiation Couplings)	Table 2 of this Design Note	Table 1 of 3.2.2-003-DN			
Variable Parameter Data (Conductive Coupling)	No. of heat pipes	K ₁₂ of Heat Pipe W/°C	K ₁₂ of structure	Total K ₁₂ W/°C	
	0	0	1.25	1.25	
	1	6.375	1.25	7.625	
	2	12.75	1.25	14.0	
	3	19.125	1.25	20.375	
	4	25.5	1.25	26.75	

FIGURE 5

UBP AND LBP TEMPERATURES VS NO. OF HEAT PIPES (GOODARD GROOVE)
45° SUN ANGLE, BOL
67.5% Duty Cycle
5°C Lower Set Point



1.25 7.625 14.0 20.375 26.75
K12 - watts/°C

3.4.2 40° ATC Cutouts with Heat Pipes

Note that the initial part of these curves (up to $K_{12} = 4.5$ $\text{W}/^\circ\text{C}$) correspond to the curves shown in Figure 2. As would be expected, the heat pipes help to clamp the two baseplates together, with the upper baseplate always between $5^\circ\text{C} - 6^\circ\text{C}$ range, indicating that the upper baseplate is always under louver control. The lower baseplate (hotter of the two, in this case) bulk temperature drops to 25°C for a K_{12} of about $3.5 \text{ W}/^\circ\text{C}$, indicating that at least theoretically less than one Goddard groove heat pipe is necessary to achieve the desired performance.

The most important piece of information is obtained by observing that the greatest drop in bulk temperature is obtained for K_{12} up to $5.0 \text{ W}/^\circ\text{C}$ equivalent to less than one heat pipe. For across-the-baseplate-temperature-gradient reasons, it would be necessary to have at least four heat pipes, preferably six. All of which does not really contribute to improving the bulk temperature performance.


Figure 6 shows 0° sun angle BOL data for the two configurations. The heat pipes have almost the same clamping effect on the two baseplates for the two configurations.

Following comparison between the heat pipe configuration (Configuration 4) and Configuration 3 shows some interesting points:

FIGURE 6

UBP AND LBP TEMPERATURES VS NO. OF HEATPIPER'S (GODDARD GROVE)

0° SUN ANGLE, BOL
67.5% DUTY CYCLE
5°C LOUVER SET POINT



1.25 7.625 14.0 20.375 26.75
K₁₂ ~ Watts/q

Configuration 3.

Configuration 4.

ITEM	Conductive Coupling by Conventional Means	Heat Pipe
1. Weight Penalty	3.5 lbs. Refer to Figure 4	Each Goddard groove heat pipe including all hardware and support bracket = 2 lbs/heat pipe.
2. Gradient Problem	No such problem	For minimizing gradients, need 6 heat pipes. 12 lbs.
3. Manufacturing Complexity	Higher gage shear web will eliminate some doubler plates and simplify overall fabrication.	If one or more heat pipes should fail, then across gradients will develop. Probably should apply higher value for gradient tolerance factor.
4. Testing Complexity (component level)	No testing necessary.	Will require some layout and special hardware to integrate the heat pipes.
5. Testing Complexity (spacecraft level)	No such complexity experienced	Heat pipes will have to be fully qualified at component level prior to integrate with the spacecraft. Performance of heat pipes under zero g cannot be evaluated on spacecraft level. May require removing the heatpipes prior to spacecraft level testing. Performance in flight cannot be verified on ground.

It appears that increasing the conductive coupling by increasing the shear web thickness to provide $K_{12} = 2.0 \text{ w/}^{\circ}\text{C}$ is very cost-effective and weight-effective, compared to the other techniques.

Even though 40° ATC cutouts, 0°C louver set point provides acceptable bulk temperature performance, Figure 7 shows that for $K_{12} = 2.0 \text{ w/}^{\circ}\text{C}$, there is no louver margin at $\gamma=45^{\circ}$ for 67.5% duty cycle.

3.5 50° Cutout, 0°C Louver Set Point (Configuration 5)

As was pointed out in Section 3.1, up to 55° ATC cutout possibility exists without affecting the end solar array power. Therefore, analysis is carried out for a 50° cutout, 0°C louver set point which is also shown in Figure 7. Again, only BOL values are shown to make the design comparison. It can be seen that for 50° cutout, the upper baseplate is under active louver control for all values of K_{12} up to $4.5 \text{ w/}^{\circ}\text{C}$. For $K_{12} = 2.0 \text{ w/}^{\circ}\text{C}$ of interest, about 10% louver margin exists. This margin can be applied towards uncertainty in box internal power dissipations, failed louver case, etc. Following parameters constitute configuration 5:

14.5" $\varnothing$ ATC
 50° ATC cutouts in end panels
 0°C louver set point
 $K_{12} = 2.0 \text{ w/}^{\circ}\text{C}$ (wt. penalty of 3.5 lbs)


For 67.5% duty cycle of science and playback payload, 45° sun angle (hot case), this configuration provides upper EOL maximum temperature of 25°C , with approximately 10% on louver margin.

The above description would indicate that the design configuration has been evolved that meets the specification requirements, which is indeed the case. However, following two considerations throw some additional light on the situation:

- a) The cutouts in the end panels would indicate the need for a solar simulation test of the ATC assemblies to provide adequate data on louver performance under solar flux impingement. This test can be complex and costly.
- b) Failure analysis of louver assemblies indicates that if the louvers fail closed, the passive louver set point will eventually open up the louvers. However, if the louver happens to fail open, solar flux could penetrate the spacecraft. Depending upon which louver assembly fails open, some critical instruments could be directly illuminated by solar flux, possibly causing extensive damage.

FIGURE 7

DE-A UBP TEMPERATURE (BOL) AND LOUVER MARGIN
67.5% DUTY CYCLE, 45° SUN ANGLE
14.5" ϕ ATC, 0° LOUVER SET POINT



Hence these considerations make configuration 5 less attractive and point to the need for closing off the end array ATC cutouts.

Design Note

REAL Astro Electronics

Originating Project or Group	Note No. 3.2.2-005-DN
Title DE-A Final Thermal Design Configuration	
Written by: C. Chhatpar <i>CC Chhatpar</i>	Date Oct 6 1978
Approved by: W. V. Fuldner <i>W.V. Fuldner</i>	Date 17 Oct 78
This DN supplements (S), replaces (R) DN Nos. (S) 3.2.2-004-DN (S) 3.2.2-001-DN	Send one copy of this Note to the DCC (Library) attached to a copy of Form AED 1488.

Letter	Description	Date	Author
	Standard Distribution: R. deBastos W. Fuldner G. Hogan W. Hord C. Hume D. Shipley		

1. SUMMARY

Configuration No. 5 of 3.2.2-004-DN was shown to meet all DE-A specification requirements. However, the failed-open louver case of that configuration during orbital mission made the spacecraft susceptible to solar flux penetration upon some critical equipment. This catastrophic-type failure of some equipment as well as the fact that ATC cutout make it necessary to solar-simulate the spacecraft to evaluate the spacecraft performance made that configuration less attractive.

It was recognized that the baseplates were strongly coupled to their respective end arrays. Also, Section 3.1 of 3.2.2-004-DN indicates that 8 strings of solar cells on end array can provide sufficient power during $\gamma = +18^\circ$, which is the reason that up to 55° of ATC cutout were possible. The same area as allocated to ATC cutouts can be utilized to cool the end array, thereby lowering the maximum bulk temperatures.

2. DESIGN CONFIGURATION

In order to design in certain positive louver margin, the following parameters were selected to investigate the effect of end array temperatures on the baseplates:

67.5% Duty Cycle
45° Sun Angle
6°C Louver Set Points
 $K_{12} = 2.5 \text{ W/}^\circ\text{C}$

Three different white paints with different BOL and EOL surface properties were selected to carry out this parametric study. Table 1 shows the preliminary end array surface property breakdown, accounting for solar cells with coverglass, ATC cold patch to decouple the end array from the actuator housing, RIMS and antenna bracket accommodation, basemetal area requirement and different paint for the available radiator area.

TABLE 1. END SOLAR ARRAY SURFACE PROPERTIES

ITEM	Area in ²	Surface Finish	10 Mil Al/Teflon(1)						Goddard White NS43C						IITRIS-13GLO(1)					
			α			ε			α			ε			α			ε		
			MIN	MAX		MIN	MAX		MIN	MAX		MIN	MAX		MIN	MAX		MIN	MAX	
Solar cells .8" x .8" cell 156 cell/string 8 strings	798.72	Solar cells w/coverglass	.713	.737		.81	.81		.713	.737		.81	.81		.713	.737		.81	.81	
Cold Patch ATC 4"Ø (6)	75.4	10 Al/Teflon	.15	.2		.79	.83		.15	.2		.79	.83		.15	.2		.79	.83	
RIMS (78 cells)	49.92	Goddard White NS43C	.2	.3		.92	.92		.2	.3		.92	.92		.2	.3		.92	.92	
Antenna Bracket (50 cells)	32.0	Goddard White NS43C	.2	.3		.92	.92		.2	.3		.92	.92		.2	.3		.92	.92	
Baremetal (additional to separa- tion adapter)	225.49	Goddard White NS43C	.2	.3		.92	.92		.2	.3		.92	.92		.2	.3		.92	.92	
Radiator Area (Distributed Over Entire Area)	660.0	See (1)	.15	.2		.79	.83		.2	.3		.92	.92		.2	.4		.84	.88	
Total End Array	1841.53		.4025	.45		.82	.836		.42	.485		.867	.869		.42	.521		.838	.854	

Bare metal on end separation adapter=254.47

+Base metal on side

TABLE 2. Orbit Average External Sink Values for End Arrays
DE-A Spacecraft

Radiator Area Surface Properties	Sink No.	Sink Equivalent Black-Body Radiation (watts/sq.in)									
		BOL-10 rpm Apogee = 23918 km Perigee = 275 km					EOL - 10 rpm Apogee = 23918 km Perigee = 275 km				
		Orbit Sun Angle (deg)					Orbit Sun Angle (deg)				
		0	45	90	-45	-0	0	45	90	-45	-0
10 mil Al/Teflon	1	.004	.005	.006	.005	.004	.002	.003	.004	.003	.002
	10	.439	.312	.006	.312	.439	.497	.353	.004	.353	.497
NS43C Goddard White	1	.004	.005	.006	.005	.004	.002	.003	.004	.003	.002
	10	.440	.314	.006	.314	.440	.507	.359	.004	.359	.507
IITRIS-13 GLO	1	.004	.005	.006	.005	.004	.002	.003	.004	.003	.002
	10	.448	.319	.006	.319	.448	.563	.399	.004	.399	.563

TABLE 3. VARIABLE PARAMETRIC VALUES FOR FINAL CONFIGURATION

From	To	Internal Radiation Coupling (in ²)		COMMENTS (See Note 1)
Node	Node	Louvers Fully Closed	Louvers Fully Open	
1	3	69.0	408.97	Variable values for $\gamma < 90^\circ$; fully closed lvs values for $\gamma > 90^\circ$
1	22	646.5	536.5	" " " " " " " "
1	5	69.0	408.97	" " " $\gamma > 90^\circ$ " " " $\gamma < 90^\circ$
2	7	656.5	536.5	" " " " " " " "
3	10	.85	5.0	" " " $\gamma < 90^\circ$ " " " $\gamma > 90^\circ$
3	11	.85	5.0	" " " " " " " "
3	12	.85	5.0	" " " " " " " "
3	13	.85	5.0	" " " " " " " "
3	22	18.4	107.1	" " " " " " " "
5	7	18.4	107.1	" " " $\gamma > 90^\circ$ " " " $\gamma < 90^\circ$
5	14	.85	5.0	" " " " " " " "
5	15	.85	5.0	" " " " " " " "
5	16	.85	5.0	" " " " " " " "
5	17	.85	5.0	" " " " " " " "
Node	Sink	External Radiation Coupling (in ²)		
1	17	0.0	0.0	Variable values for $\gamma < 90^\circ$; fully closed lvs values for $\gamma > 90^\circ$
2	17	0.0	0.0	" " " $\gamma > 90^\circ$; " " " " $\gamma < 90^\circ$
1	2	Conductive Coupling (watts/°C)		Corresponds to about 7.0 lbs of weight increase in 6061-T6 shear webs.
		2.5		

NOTE 1. Fully closed louver values are applicable for baseplate temperatures below 6°C. Fully open louver values for temperatures above 7°C. Program computes proportional values between 6°C and 7°C.

Table 1 data translates into different external sink values for the three different materials, shown in Table 2. Table 3 shows all the variable parameter data applicable for this configuration. Note that all the fixed parameter data is given in 3.2.2-001-DN.

3.1 BASIC PERFORMANCE

Figure 1 shows the spacecraft bulk temperature for the three selected paints $\alpha S/\epsilon$ for the radiator part of the end array. It turns out that all three meet the specification requirement of 25°C on the hotter of the two baseplates. The controlled baseplate is under louver control with some positive louver margin.

Also plotted on the same figure is the maximum end array temperature for the 0° sun angle. The data arbitrarily includes 10°C uncertainty factor for conservatism.

The IITRIS-13GLO with the least of the three louver margins and highest end array temperature is selected for the detailed study, for the worst cold case will require maximum solar array (electrical as well as thermal) power to maintain temperatures within the spacecraft specifications.

3.2 DETAIL PERFORMANCE


The orbit-average temperatures of upper and lower baseplates as a function of instrument-payload duty cycles, sun angles, and BOL versus EOL variation in thermal properties are plotted in Figures 2 and 3. Data for the 0-percent, 67.5 percent and 100 percent duty cycles are replotted in Figures 4, 5, and 6. Table 4 extracts the data from these figures.

At the high-temperature end, nominal science payload duty cycle of 60 percent (67.5 percent duty cycle of science and playback) and spacecraft in orbital configuration, a maximum EOL temperature of 17°C is obtained on the lower baseplate (see Table 4). This steady-state temperature combined with the thermal transients (+2°C), gradients across the baseplates (+2°C) and the uncertainty factor of +3°C applied to the analytical predict gives a maximum EOL bulk temperature of 24°C, within the specification limit of 25°C. Note that for additional 4°C, i.e., 28°C of bulk temperature (steady state) up to 100 percent duty cycle can be allowed.

For short duration, this 100 percent duty cycle may be run by manipulating the time-constant of the spacecraft, as well as running earlier 0 percent duty cycle, thereby starting off with a cooler bulk temperature.

FIGURE 1

DE-A VBP AND LBP TEMPERATURES, EOL
 67.5% DUTY CYCLE 45° SUN ANGLE
 6°C LOWER SETPOINT
 K₁₂ = 2.5 W/°C



ORIGINAL PAGE IS
 OF POOR QUALITY

A conservative assumption will be made here that says that the DE-A spacecraft will go through a zero-degree sun angle after injection prior to achieving final orbital configuration. Since all the science instruments will be off during this maneuver, this 0° sun angle, 0 percent duty cycle represents a worst cold case. Data for this can be obtained from Figure 4, which shows that the worst case cold BOL temperature is -35.5°C . Note that this temperature (in fact, all the curves of Figure 4) are obtained with louvers operating logically; that is, if the temperature of the controlled baseplates happen to be below the louver set point, then the computer program automatically closes the louvers. As described earlier, the sunlit end of the louvers are normally commanded close by disabling the ATCE during the orbital configuration to prevent the sun heating up the already hot baseplate. The same sun, however, can be used to warm up the spacecraft when such solar flux becomes desirable.

When the sunlit-end louvers are commanded open by a set point change, the -35.5°C temperature of the upper baseplate warms up to -13.3°C . With the spacecraft sensitivity of $.484^{\circ}\text{C/watt}$ for 0° BOL curve (see Figure 2), this will require about 17.0 watts of heater power to bring the bulk temperature to -5°C (non-operational limit). This combined with 22.0 watts of continuous load gives a minimum required power of 39 watts. Figure 7 shows total BOL solar array available power during this initial turnaround maneuver. Note that the spacecraft will be turned at the rate of $6^{\circ}/\text{day}$. At all times there is some positive heater margin to keep the spacecraft within its specification (non-operational).

In addition, if need be, some battery power is available for short duration to supply the heater power. The time-constant of the spacecraft will also act favorably during this transient maneuver. For those critical items that require higher than -5°C , the ATCE heaters may be strategically located in order to gain advantage of the gradient characteristic.

The orbital minimum sun angle will be limited to $+18^{\circ}$. Again looking at Figure 4 for 0 percent duty cycle, it appears that the 90° sun angle is much colder than the $+18^{\circ}$. With the sensitivity of $.44^{\circ}\text{C/watt}$, there is plenty of power available at 90° sun angle to keep the spacecraft bulk at 0°C , within the specification.

Summarizing, this configuration has satisfied the specification limits of 25°C to 0°C (operational) on the bulk basis, and -5°C (non-operational) during the turnaround maneuver. Table 5 summarizes the performance.

FIGURE 2

DE-A TEMPERATURE RESPONSE VS. SCIENCE & PB PAYLOAD
FOR UPPER BASEPLATE (NODE 1) WITH NO ATCE HEATER POWER.




FIGURE 3

DE-A TEMPERATURE RESPONSE VS. SCIENCE $\frac{1}{2}$ -PB PAYLOAD
FOR LOWER BASEPLATE NODE 2. NO ATCE HEATER POWER.




FIGURE 4
DE-A UPPER AND LOWER BASE PLATE, TEMPERATURES (BOL & EOL)
VS. SUN ANGLE AT 0% DUTY CYCLE.




FIGURE 5
DE-A UPPER AND LOWER BASEPLATE TEMPERATURES (BOIL & EOL)
VS. SUN ANGLE AT 67.5% DUTY CYCLE.




FIGURE 6
DE-A UPPER AND LOWER BASE PLATE TEMPERATURES (BOL & EOL)
VS. SUN ANGLE AT 100% DUTY CYCLE.





TABLE 4. DE-A Thermal Performance: Final Configuration, Orbit-Average Steady-State Temperature Predictions

CASE	DESCRIPTION	DUTY CYCLE OF SCIENCE PAYLOAD	SUM ANGLE (DEG)	TEMPERATURE PREDICTIONS HEATER POWER (°C)				COMMENTS	THERMAL MARGIN	REFERENCE		
				WITHOUT ATCE		LOWER BASEPLATE						
				UPPER BASEPLATE	EOL	BOI	EOL					
HOT CASE	NOMINAL POWER DISSIPATION: OPERATIONAL SPECIFICATION LIMITS FOR THE SCIENCE PAYLOAD	60 PERCENT	18	-1.0	0.0	7.5	10.5	Thermal transients ($\pm 2^{\circ}\text{C}$), thermal gradients ($\pm 2^{\circ}\text{C}$) and uncertainty factor ($\pm 2^{\circ}\text{C}$) are applied to maximum EOL temperature prediction of 17°C to arrive at 24°C on the lower baseplate; within specification limit of 25°C .	15% ON LOUVER	FIGURE 4 AND FIGURE 1		
			45	6.4	6.8	15.2	17.0					
			90	5.5	5.8	6.0	6.4					
			-45	13.6	15.0	6.5	7.0					
			-18	-0.5	0.5	8.5	9.5					
COLD CASE	INJECTION: PRIOR TO FINAL ON-ORBIT CONFIGURATION: NON-OPERATIONAL SPECIFICATION LIMITS FOR THE SCIENCE PAYLOAD	0 PERCENT	0	-35.5	-29.0	-25.0	-16.0	With sunlit end louvers closed	5 WATTS ON HEATERS	FIGURE 2 AND FIGURE 7		
			0	-13.3	-	.7	-	By commanding sunlit-end louvers open, allows the lower baseplate to be coupled to the hot bottom end array bringing upper baseplate to -13.3°C . With spacecraft sensitivity of $.480^{\circ}\text{C}/\text{watt}$, this requires about 17.0 watts of heater power to bring the upper baseplate to -5°C . (Non-operational specification limit). Note that the lower baseplate at -7°C does not require any additional heat.				
			18	-6.0	-4.0	3.2	4.5	ATCE heaters will keep baseplates above 0°C .			Plenty heater margin	FIGURE 7
			90	-11.6	-10.4	-9.6	-8.4	" " " "				
			-18	1.0	5.2	-3.4	-3.0	" " " "				
ORBITAL CONFIGURATION	ORBITAL CONFIGURATION	0 PERCENT	18	-6.0	-4.0	3.2	4.5	ATCE heaters will keep baseplates above 0°C .	Plenty heater margin	FIGURE 7		
			90	-11.6	-10.4	-9.6	-8.4	" " " "				
			-18	1.0	5.2	-3.4	-3.0	" " " "				

FIGURE 7
DE-A INITIAL TURNAROUND MANEUVER
(WORST CASE)



3.3 Duty Cycle Variations

Figure 8 shows DE-A science and playback payload duty cycles as a function of sun angle for the specification temperature of 25°C for BOL & EOL variation. These plots have been generated utilizing data from Figures 2 and 3 and include the thermal transients, gradients and the uncertainty factor. Also plotted on this figure are the duty cycles, BOL and EOL as determined by the available power as a function of sun angle. The two, temperature limited and power limited, provide a composite duty cycle curve, also shown in Figure 8.

3.4 Solar Array Thermal Performance

The end solar arrays have been looked at in considerable design detail (Tables 1 through 3). Lowering their temperature has enabled the spacecraft bulk temperatures to be within specification, without any cutouts for the ATC's. The orbit-average temperatures of the end array for the 67.5% duty cycles are plotted in Figure 9.

The orbit average temperature of side array as function of sun angle is shown in Figure 10, which hasn't changed much from original design note 3.2.2-003-DN. Both end and side array temperatures for specific sun angles are extracted from these figures and tabulated in Table 5.

FIGURE 8
DE-A DUTY CYCLE PERFORMANCE VS SUN ANGLE
FOR 25°C BULK SPECIFICATION TEMPERATURE
COMPOSITE TEMPERATURE AND POWER LIMITED




FIGURE 9
DE-A TOP ATC AND TOP PASSIVE AREA TEMPERATURES VS. SUN
ANGLE FOR 67.5% DUTY CYCLE.




FIGURE 10

MEAN TEMPERATURE OF DE-A UPPER SIDE ARRAY (NODES 10, 11, 12, 13) VS
SUN ANGLE FOR 67.5% DUTY CYCLE.




Table 5. Solar Array Temperature for Orbit-Average
Steady-State at 67.5% Duty Cycle of Science and
Playback Payload

Solar Array	Sun Angle (degree)	Orbit-Average Temperature (°C)		Reference
		BOL	EOL	
Top-ATC of End Solar Array	18	-75	-72	Figure 9
	45	-57	-55	
	90	-80	-80	
	-45	30	45	
	-18	42	67	
Upper Side Array	18	-35	-35	Figure 10
	45	-10	-10	
	90	-10	- 8	
	-45	3	5	
	-18	-21	-16	

4. Discussion

In addition to satisfying the specification temperature limits, following advantages have been realized by this configuration:

1. Since no cutouts will be present in the end panel, this eliminates the need for solar simulation testing of the ATC configuration to verify the design and the thermal model.
2. Failed-open louver case can be handled easily by this configuration, with no solar flux impinging upon any critical equipment causing catastrophic failures.
3. Lowering the temperature of end array increases the solar cells efficiency, thereby reducing the required number of cells. This makes more area available for radiator purposes to further cool the end array. This 'self-feeding' effect is an important parameter that provides some control on the thermal design.
4. It has been discussed earlier that the passive set point of the louver bimetal housing require that the ATC housing be somewhat decoupled from the high end-array temperature. Lowering the end array temperature has made that decoupling design problem easier.

Design Note

TRCA

Astro Electronics

Originating Project or Group

Note No.

3.2.2-006-DN

Title

DE-B Parametric Thermal Study and Performance

Written by:

C. Chhatpar

OK Chbby

Date _____

October 13, 1978

Approved by:

W. Fuldner

M. Valda.

Date _____

October 13, 1978

This DN supplement (S), replaces (R) DN Nos.

(S) ~~3.2.2-002-DN~~

REVISIONS

Letter	Description	Date	Author
			Standard Distribution: R. deBastos W. Fuldner G. Hogan W. Hord C. Hume D. Shipley

Standard Distribution:

R. deBastos

W. Fuldner

G. Hogan

W. Hord

C. Hume

D. Shipley

1. SUMMARY

The DE-B presents less severe thermal conditions than the DE-A, since the variation in external thermal factors from worst-case cold to worst-case hot orbits will be smaller and the spacecraft will be rotated through 180° when the sun crosses the orbit plane to maintain the top of the spacecraft in anti-sun side. Like AE, the active louver control will not be required on the bottom surface.

It is assumed that the similar Active Thermal Control (ATC) configuration as used on the AE spacecraft will be used for this mission, with a 'fine tuning' improvement of performance to be accomplished as the detail design progresses.

2. DESIGN CONFIGURATION

The principal features of the DE-B thermal design are illustrated in Figure 1. This design is similar to that of the Atmosphere Explorer spacecraft.

The top array substrate serves as the principal sink for the internal power dissipation. This surface is on the antisun side of the spacecraft and has the least variation in external thermal factors. It serves to minimize the baseplate-temperature variation with changes in orbital power dissipation. The upper hat will include four 20-inch diameter active-thermal-control louvers, of the same double-blade pin-wheel type that was used on Atmosphere Explorer. These will be used to vary the radiative coupling from the upper baseplate equipment to cold space through cutouts in that substrate. Controlled radiation couplings from the side-array surfaces to the internal equipment are accomplished through the use of black paint and gold tape applied to the inside of the side arrays. The external thermal factors on these array surfaces have a direct relation to internal power dissipation and tend to magnify the temperature differences between worst-case hot and worst-case cold conditions.

The power dissipation from the internal equipment is distributed unequally between the upper and lower baseplates. The lower baseplate will carry about $1/3$ of the total power dissipation. This compensates for the smaller coupling between this baseplate and the top sink and equalizes the temperature levels for all internal equipment.

ATCE controlled heaters are provided on the upper and lower baseplates to prevent equipment temperatures from falling below the allowable minimum values during orbits when the instruments are not operated.

The shunt-limiter components are distributed over both the end and side arrays. The resistance section of the limiter is spread uniformly over the entire array surface using a serpentine resistance-wire layout. The transistors are placed on corner brackets between the end and side arrays to distribute the power in accordance with array temperatures. The relatively uniform distribution of power over the array surfaces minimizes the effect of shunt-limiter dissipation on internal equipment and array temperatures.

Simplified thermal model data for the DE-B spacecraft is described in DE design note 3.2.2-002-DN, which also describes variable parameters that depend on louver position. Table 1 provides variable parameters for this configuration. Appendix A contains a representative printout of computer program for a 50% duty cycle of science and playback payload.

3. THERMAL PERFORMANCE

Thermal performance of the baseline configuration as described in the DE Technical Proposal NO. 102658-C, June 30, 1978 dictated maximum EOL bulk temperature of 30°C , out of temperature specification limit of 25°C . The minimum BOL bulk temperature of 0°C for the orbital configuration was shown to meet the temperature specification limit.

As a result, parametric study was carried out to evaluate the effect of active louver setpoint on the maximum bulk temperature. Again, it should be noted that the analytical predictions have to be corrected for the thermal transients ($+2^{\circ}\text{C}$), thermal gradients ($+2^{\circ}\text{C}$) across the baseplates and the uncertainty factor of $+3^{\circ}\text{C}$, applied to the simplified steady-state temperature of the lower baseplate. Therefore, for the maximum bulk temperature specification limit of 25°C , the analytical prediction has to be below 18°C .

Orbit-average temperatures of lower and upper baseplates as function of louver setpoints, sun angles and BOL versus EOL variations, in thermal properties are plotted in Figure 2 and 3, respectively, for 50% duty cycle of science and playback payload. Figure 2 shows that the maximum EOL lower baseplate temperature for a 6°C louver setpoint is 17.8°C which corresponds to 24.8°C on bulk basis, below the 25°C specification limit. Figure 3 shows that both lower setpoints keep the upper baseplate under louver control for sun angles of 30° and 90° , but 0° sun angle is clearly out of the louver control range, requiring some heater power for BOL condition to bring the upper baseplate to 0°C .

TABLE 1 VARIABLE PARAMETRIC VALUES FOR THERMAL MODEL

FROM MODE	TO SINK	EXTERNAL RADIATION COUPLING(in ²)		COMMENTS (SEE NOTE 1)
		LOUVERS FULLY CLOSED	LOUVERS FULLY OPEN (See Note 3)	
1	17	0.0	569.0	Louver SetPoint = 12°C Baseline Configuration.
1	17	0.0	569.0	Louver Set Point = 6°C (Revised Configuration)
1	2	Conductive Coupling (WATTS/°C) 2.5		This value is increased from that used in baseline configuration of the Proposal of 1.25 Watts/°C resulting in about 6.0 lbs. weight penalty.


NOTE:1-Fully closed values are applicable for upper baseplate temperatures below setpoint. Fully open louver values for temperature 1°C higher than the setpoint. Program computes proportional values between these two temperatures.

2-Sun angle for this spacecraft varies from 0° to 90°.

3-The value considers blockage of space by MWA.

FIGURE 3

DEPENDENCE OF DE-B UPPER BASEPLATE TEMPERATURE ON
THE ATC LOWER SET POINT FOR 50% SCIENCE AND PLAYBACK
DUTY CYCLE WITH NO ATCE HEATER POWER.



ORIGINAL PAGE IS
OF POOR QUALITY

FIGURE 2

DEPENDENCE OF DE-B LOWER BASEPLATE TEMPERATURE ON
THE ATC LOWER SET POINT FOR 50% SCIENCE AND PAYBACK
DUTY CYCLE WITH NO ATC HEAT POWER.




FIGURE 4

DE-B UPPER BASE PLATE TEMPERATURE AS A FUNCTION OF
DUTY CYCLE FOR SCIENCE AND PLAYBACK PAYLOAD (NO ATCE POWER).





FIGURE 5
DE-2 LOWER BASEPLATE TEMPERATURE VS. SCIENCE AND
PLAYBACK DUTY CYCLE WITH NO ATCE HEATER POWER.



The orbit-average temperatures of upper and lower baseplates as function of instrument-payload duty cycles, sun angles, and EOL versus EOL variations in thermal properties are plotted in Figures 4 and 5. Data for the 0-percent and 50 percent cycles of the science payload are replotted in Figures 6 & 7. Table 2 extracts the data from these two figures and shows that for 0-degree sun angle and 0-percent duty cycle (representing injection into orbit, experiments-off condition), the upper baseplate reaches the cold temperature of -14.7°C if no heaters are present. The ATCE control provides for the heater power when the thermistor senses the upper baseplate temperature below 1°C . Figures 4 and 5 show that the spacecraft temperature sensitivity to power dissipation is about $.412^{\circ}\text{C}/\text{watt}$. This will require about 36 watts of heater power to maintain the upper baseplate at 0°C , for 0-percent duty cycle on the Science payload with the spacecraft at 0-degree sun angle. Assuming a 10 to 12 percent increase in solar array power from the EOL power value of 75.2 watts gives about 83.5 watts of total EOL available power. Since the required power, including continuous load, is 70 watts, there is adequate power margin to maintain spacecraft above 0°C during the initial injection. Figure 6 also shows that for the minimum sun angle of 18° , with the upper and lower baseplates are above 0°C , not requiring any heater power during nominal orbital configuration. ←


Table 2 shows that the maximum EOL upper baseplate temperature is 6.71°C , which correspond to a lower margin of about 29%. This margin can be applied towards the lower failure analysis or lowering the side end and array temperature by coupling them more to the baseplates. ←

TABLE 2. DE-B THERMAL PERFORMANCE: ORBIT-AVERAGE STEADY-STATE TEMPERATURE PREDICTIONS

Reference	Duty Cycle of Science Payload (Percent)	Description	Sun Angle (degrees)	Temperature Predictions Without ATCE Heater (°C)				Comments
				Upper Baseplate	Lower Baseplate	Upper Baseplate	Lower Baseplate	
Figure 6	0	Injection, prior to Final Orbital Configuration	0	NOA	NOA	NOA	NOA	With spacecraft sensitivity of 412 C/watt, this will require about 38.0 watts of heater power to bring upper baseplate temperature to 0°C.
			0	-14.7	-10.7	-7.8	-3.5	
		Non-operational for the Science Payload	90	6.0	6.2	2.0	3.5	
Figure 7	50	Orbital Configuration	18	4.8	5.7	14.5	16.0	Thermal gradient transients and uncertainty factors are applied to the maximum temperature of 17.8°C of lower baseplate to arrive at upper baseplate temperature of 24.8°C.
		Nominal Power Distribution	30	6.6	6.71	16.6	17.8	
		Operational for the Science Payload	90	6.32	6.47	6.44	7.9	

2-114

FIGURE 6
DE-B UPPER AND LOWER BASEPLATE TEMPERATURE
AS A FUNCTION OF SUNANGLE FOR 0% SCIENCE AND
PLAY BACK DUTY CYCLE (NO ATCE POWER)



ORIGINAL PAGE IS
OF POOR QUALITY

FIGURE 7

DE-B UPPER AND LOWER BASEPLATE TEMPERATURES Vs.
SUN ANGLE FOR 50% SCIENCE AND PLAY BACK DUTY CYCLE
WITH NO ATCE HEATER POWER.





FIGURE B
DE-B DUTY CYCLE PERFORMANCE VS SUN ANGLE
FOR 35°C BULK SPECIFICATION TEMPERATURE
COMPOSITE TEMPERATURE AND POWER LIMITED



C-4

ORIGINAL PAGE IS
OF POOR QUALITY

3.2 Duty Cycle Variations

Figure 8 shows DE-B science and playback payload duty cycles as a function of sun angle for the specification temperature of 25°C for BOL and EOL variation. These plots have been generated by utilizing data from Figures 4 and 5 and extrapolating from Figure 5. They include the thermal transient gradients and the uncertainty factor effects. Also plotted on this figure are the duty cycles, BOL and EOL, as determined by the available power from solar arrays as a function of sun angle. The two, temperature limited and power limited, provide a composite duty cycle curve, also shown in Figure 8.

4. DISCUSSION

It is shown that by lowering the active setpoint of the louver to 6°C and increasing the conductive coupling between the baseplates (to make them same as for DE-A), the upper maximum bulk temperature of 25°C has been achieved. In addition, about 29% additional louver heat dumping capability exists, some of which can be utilized to lower the end and side array temperatures which will ultimately result in a higher minimum duty cycle as dictated by the available power. At the cold end, both during injection as well as for orbital configuration, plenty of heater margin exists to maintain the spacecraft bulk temperature at 0°C.

Table 3 lists temperature specifications for instruments and selected components, which are all above the upper bulk temperature of 25°C. Those items with 0°C minimum operational limit may be provided with strategically located ATCE controlled heaters:

TABLE 3 DE-B THERMAL SPECIFICATIONS

ITEM	Allowable Temperature Limit Non-Operational Operational °C °C				COMMENTS
	MIN	MAX	MIN	MAX	
MAG	-25 -60	50 60	-10 -40	40 40	External to spacecraft. Prefers smaller transients
RPA	-30	75	-20	60	
WATS	-40	60	-10	40	
LANG	TBS	TBS	TBS	TBS	
VEFI	-30 -20	60 40	0 0	40 30	
FPI	-20	60	-10	30	
IDM	-30	75	-20	60	
LAPI	-30	40	0	35	
NACS	-40	60	-10	40	
MWA	-20	50	-5	40	
SCAN PLATFORM	-20	50	-5	40	Maximum operational limit is applicable for limited DOD and cycles only
BATTERY	-5	40	0	40	
TR	-17	35	-17	35	
TRANSPONDER	-25	70	-15	50	

- NOTES: 1. All limits are applicable on unit mounting interface.
2. Temperature limits of all GFE items have been obtained from the latest UNDOCS information.

APPENDIX A

COMPUTER PRINTOUT OF STEADY-STATE
TEMPERATURE FOR A REPRESENTATIVE
DUTY CYCLE FOR DE-B SPACECRAFT

Table A-1. Look-up Table of Radiation Coupling from Node 1 to Sink 17*

---DYNAMIC EXPLORER THERMAL MODEL 1.21 NGDE 180 DEGREE SUN ANGLE 80L-----									
1	4	1	3						
-160.0000	6.0000	7.0000	100.0000	0.0	0.0	0.0	0.0	0.0	1
0.0	0.0	564.0000	564.0000	0.0	0.0	0.0	0.0	0.0	2
0.0	0.0								
569.0000	569.0000								

*Corresponds to louver active set point of 12°C (louver start to open) to 13°C (louver fully open). Varies radiation coupling as a function of upper baseplate temperature.

Table A-2. Nodal Radiation Couplings (w/in²)

IN-UT MATRIX VALUES FOR RIJ											
1	2	767.00000	1	3	59.000000	1	4	44.899994	1	10	132.500000
1	11	132.500000	1	12	132.500000	1	13	132.500000	1	14	3.700000
1	15	7.650000	1	16	7.650000	1	17	7.650000	1	18	3.600000
1	19	3.600000	1	20	3.600000	1	21	3.600000	2	6	44.100000
2	10	6.300000	2	11	6.300000	2	12	0.550000	2	13	0.500000
2	14	75.000000	2	15	75.000000	2	16	75.000000	2	17	75.000000
2	18	0.400000	2	19	0.400000	2	20	0.400000	2	21	0.400000
3	16	9.175000	3	11	9.175000	3	12	9.175000	3	13	9.175000
4	10	1.500000	4	11	1.500000	4	12	1.500000	4	13	1.500000
5	7	236.00000	5	6	104.320000	6	7	3.500000	6	8	29.809996
6	14	1.500000	6	15	1.500000	6	16	1.500000	6	17	1.500000
7	9	373.00000	7	9	6.200000	7	14	0.200000	7	15	0.200000
7	16	0.200000	7	17	0.200000	8	9	29.500000			0.200000

Table A-3. Nodal Conductive Couplings (w/°C)

INPUT MATRIX VALUES FOR K1J												
1	2	2.500000	1	10	0.028000	1	11	0.028000	1	12	0.028000	0.028000
1	13	0.028000	2	7	1.260000	2	14	0.028000	2	15	0.028000	0.028000
2	10	0.028000	3	17	0.024000	3	4	0.050000	4	10	0.100000	0.100000
4	11	0.100000	4	12	0.100000	4	13	0.100000	5	6	0.650000	0.650000
5	7	1.000000	5	8	7.000000	6	7	0.100000	6	14	0.500000	0.500000
6	15	0.500000	6	16	0.500000	6	17	0.500000	7	8	0.200000	0.200000
7	4	0.050000	10	11	0.040000	10	13	0.040000	10	14	0.050000	0.050000
11	12	0.040000	11	15	0.050000	12	13	0.050000	12	20	0.040000	0.040000
13	21	0.090000	14	15	0.040000	14	17	0.040000	14	18	0.090000	0.090000
15	16	0.040000	15	19	0.090000	16	17	0.040000	16	20	0.050000	0.050000
17	21	0.090000	18	19	0.120000	18	21	0.020000	19	20	0.020000	0.020000
20	21	0.020000										

Table A-4. Radiation Coupling from Node to Sink (in²)

INPUT MATRIX VALUES FOR K1S												
1	15	0.230000	1	17	-1.001000 **	2	16	0.010000	3	1	0.010000	0.010000
4	1	0.000000	6	10	0.000000	7	17	0.000000	8	17	0.000000	0.000000
9	17	0.000000	10	2	0.000000	11	3	0.000000	12	4	0.000000	0.000000
13	5	0.000000	14	6	0.000000	15	7	0.000000	16	8	0.000000	0.000000
17	9	0.000000	18	11	0.000000	19	12	0.000000	20	13	0.000000	0.000000
21	14	0.000000										

**Refers to look-up Table A-1.

Table A-5. Thermal Sink Values for Sun Angle = 0° (watts/in²)

RESULTANT MATRIX OF 4 ITERATION FOR I												
1	0.0370	2	0.0910	3	0.0880	4	0.0030	5	0.0070	6	0.0910	0.0910
7	0.0880	8	0.0030	9	0.0070	10	0.0030	11	0.0070	12	0.0910	0.0910
13	0.0030	14	0.0120	15	0.0450	16	0.0210	17	0.0	18	0.0910	0.0910

Table A-6. Temperature Distribution ($^{\circ}\text{C}$) For Various Sun Angles; 50% Duty Cycle
BOL; 0 $^{\circ}$ Sun Angle

RESULTANT MATRIX OF 4 ITERATION FOR T											
1	-1.5791	2	5.5747	3	-77.7846	4	-74.3901	5	22.5840	6	77.5962
7	19.9324	8	18.5682	9	53.1812	10	-41.1778	11	-42.3417	12	-84.7361
13	-42.3216	14	-5.8491	15	-10.5469	16	-33.2177	17	-32.0975	18	-32.9247
19	-54.4895	20	-63.8492	21	-61.7283						

BOL; 30 $^{\circ}$ Sun Angle

RESULTANT MATRIX OF 6 ITERATION FOR Y											
1	6.6033	2	16.5742	3	-63.1441	4	-52.6764	5	31.8921	6	76.4236
7	29.3506	8	28.7222	9	58.5198	10	12.1350	11	11.3030	12	-22.6689
13	-21.6083	14	24.7463	15	24.2698	16	-0.7017	17	-0.1184	18	19.4534
19	18.3123	20	-9.9343	21	-8.6565						

BOL; 90 $^{\circ}$ Sun Angle

RESULTANT MATRIX OF 7 ITERATION FOR T											
1	6.3201	2	6.4390	3	-52.4507	4	-43.3256	5	-12.1377	6	-24.8421
7	-7.0467	8	-12.4924	9	-13.6770	10	7.8747	11	6.3616	12	6.2871
13	9.0055	14	0.2147	15	-0.0649	16	0.4410	17	1.3586	18	10.8569
19	9.6091	20	13.1179	21	14.4242						

EOL; 0 $^{\circ}$ Sun Angle

RESULTANT MATRIX OF 4 ITERATION FOR T											
1	2.0691	2	9.2715	3	-68.8762	4	-66.1214	5	26.1614	6	64.1541
7	23.5266	8	21.9283	9	55.3528	10	-18.5766	11	-15.6563	12	-79.1985
13	-77.1219	14	-4.7461	15	-5.4133	16	-29.5362	17	-28.4521	18	-27.1455
19	-24.6481	20	-59.4232	21	-57.3816						

EOL; 30 $^{\circ}$ Sun Angle

RESULTANT MATRIX OF 6 ITERATION FOR T												
	EOL: 30						SUN ANGLE					
1	6.7078	2	17.8015	3	-61.4162	4	-50.5393	5	34.8388	6	81.5156	
7	31.2839	8	30.7039	9	55.8652	10	17.5598	11	16.7508	12	-18.6444	
13	-17.7029	14	29.8647	15	29.3977	16	3.0881	17	3.6680	18	36.9922	
19	35.5073	20	1.9646	21	3.6572							

EOL; 90 $^{\circ}$ Sun Angle

RESULTANT MATRIX OF 6 ITERATION FOR T												
	LOW; 50						SWI Angle					
1	6.4734	2	7.9011	3	-43.9282	4	-35.5923	5	-9.5015	6	-18.5585	
7	-9.8171	8	-10.0466	9	-11.5916	10	18.3438	11	8.4688	12	16.8083	
13	17.4592	14	4.9441	15	4.0518	16	9.1611	17	9.9744	18	21.9656	
19	20.6567	20	34.1431	21	35.2568							

Design Note

RCAT Astro Electronics

Originating Project or Group	Note No.
	3.2.2-007-DN
Title	
LAPI/Scan Platform Thermal Model Description and Performance	
Written by:	Date
O. Liu <i>O. Liu</i>	October 13, 1978
Approved by:	Date
C. Chhatpar <i>C. Chhatpar</i>	16 Oct 78
This DN supplements (S), replaces (R) DN Nos.	

REVISIONS

Letter	Description	Date	Author
	Standard Distribution: R. deBastos W. Fuldner G. Hogan W. Hord C. Hume D. Shipley		

Standard Distribution:

R. deBastos
W. Fuldner
G. Hogan
W. Hord
C. Hume
D. Shipley

1. Summary

A 21-node thermal math model of Dynamics Explorer-B spacecraft LAPI (Low Altitude Plasma Instrument) and Scan Platform has been developed. The model has provided the temperature distribution in both cold case (90° sun angle) and hot case (30° sun angle) for various duty cycles. The model's geometry configuration, form factors, Radiation Couplings (RIJ's), view to space sink and orbit average external absorbed flux are generated by CDC TRASYS computer program. The steady state temperature distribution of two orbits are computed from RCA in-house TH014 steady-state thermal program. The nodal properties, conduction couplings (KIJ's) and power dissipations are supplied by GSFC. The spacecraft features simulated by this model are: magnetometer, LAPI stacks, scan platform, adapters, center column, driving motor housing, baseplate, and solar array.

The following data is contained in this report:

1. Plots and tables showing the nodal identification, properties and location.
2. Model's 3-dimension and orthographic view plots from TRASYS program.
3. Tables of absorbed nodal external flux.
4. Tables of data used in TH014.
5. Selected nodal temperature plots as function of instrument duty cycles.

2. Assumptions

1. The elliptical orbit has an apogee of 1200 km and a perigee of 275 km.
2. Heat is transferred by conduction and radiation.
3. Neglect the external flux incident through LAPI sensors slot openings.
4. Inside S/C is assumed as a sink of 25°C and 0°C for 30° sun angle and 90° sun angle respectively.
5. Magnetometer is in stowed position.
6. The scan platform (flower pot) has 75% see-through cutouts.
7. There is no wrap around the LAPI stacks.
8. Following design parameters are part of the model:
 - a) Motor is hard-coupled to the diaphragm adapter.
 - b) Diaphragm adapter is hard-coupled to the separation adapter.
 - c) All internal surfaces of separation adapter, diaphragm adapter, scan platform are painted with Z306 chemglaze black.

3. Thermal Model and Performance

Two nodal identification systems are used for the model. One consists of 43 nodes for a geometry model, used in TRASYS program to generate view factors, RIJ and external fluxes; the other one is a 21 nodes thermal model used in TH014 program to predict the temperature performance. The nodes and sinks are shown in Table 1 through Table 3.

Table 4 to Table 7 are the data input for TH014 program to obtain the temperature distribution.

The nodal absorbed external flux of two orbits for 30° and 90° sun angles are listed in Table 8 and 9 respectively.

Due to the fact that view factors to the space of some external nodes are less than 1, the inaccuracy will occur when calculating the external absorbed heat input. This has been compensated by adding the so called "S/C external nodal Absorbed Heat Input not accounted for with external sinks", as shown in Table 10, to the heat source data block in program TH014.

Table 11 lists the nodal heat input of various duty cycle for two different orbits.

The detail geometric configuration of the model are illustrated in Figure 1 through Figure 5.

The results of the analysis can be found in Table 12, Figure 6 and 7. The high voltage power supply and central electronic package will be operating at 39°C in hot case (30° sun angle and 100% duty cycle) and -9°C in cold case (90° sun angle and 0% duty cycle). The LAPI sensor stacks will be operating at 43°C in hot case and -6°C in cold case. The drive motor power dissipation of 6 watts is included in this analysis.

4. Discussion

Latest information from GSFC indicates that the most probable duty cycle of LAPI and scan platform will be 25% to 40%. The analysis has indicated that in this duty cycle, the HVPS (Node 17) and CEP (Node 18) will be operating at 31°C in hot case and -1°C in cold case. These are computer generated steady state temperature predictions which do not include uncertainty factor and thermal transients. The LAPI sensor stacks operational temperature, 38°C in hot case, is considerably high. Therefore, a thermal shielding wrap around LAPI stack is recommended in order to reduce external flux impingement. Some fine-tuning of external properties may also be investigated, taking into account BOL vs EOL variation.

TABLE 1. NODAL IDENTIFICATION (for TH014)

TH14 Nodes	Description	Material	Corresponding TRASYS Nodes
1	Magnetometer		1-6
2	LAPI Stack #1	Mg Az 31 BH24	7
3	LAPI Stack #2	"	8
4	LAPI Stack #3	"	9
5	Magnetometer holding platform	"	10-11
6	Flower Pot Top Platform	"	16-17
7	Flower Pot Side	AL2024-T6	18-19
8	Adapter Top Spring Holder (Disc)	AL7075-773	34-35
9	Flower Pot bottom	AL2024-T6	20-21
10	Driving Motor Housing Adapter	AL6061-T6	22
11	Driving Motor Housing	"	23-25
12	Diaphragm adapter	MgAz31B	30-31
13	Driving motor housing bottom	A16061-T6	25
14	S/C Center Column	MgAz31BH24	36-37
15	Adapter (conical part)	A17075-773	38
16	Adapter (cylinder part)	"	32-33
17	High Voltage Power Supply	MgAz31B	45-49
18	Central Electronic Package	MgAz31B	51-55
19	Sun Shield (cylind	Stainless Steel	26
20	Solar Array	-	40-41
21	Inside S/C Environment	-	-

MODEL=SCALPI CONFIG=U08LPJ STEP=-1
PROCESSING OPERATIONS DATA

-----DE-B LAPI 3 SCNPLTFM EXTERNAL FLUX, SUR ANG=30.-----

NODE	BOS	AREA	ALPHA	FMISS	SURF. TYPE	ACTIVE	COMMENTS	THICK	NAME	SURF
1	WNTIME	123333	382	690	RECTANGLE	TOP	MAGNETOMETER			
2	WNTIME	033333E-01	382	690	RECTANGLE	TOP	MAGNETOMETER			
3	WNTIME	133333	382	690	RECTANGLE	TOP	MAGNETOMETER	1		1
4	WNTIME	033333E-01	382	690	RECTANGLE	TOP	MAGNETOMETER			
5	WNTIME	133333	382	690	RECTANGLE	TOP	MAGNETOMETER			
6	WNTIME	143333	382	690	RECTANGLE	TOP	MAGNETOMETER			
7	LAPI08	273522	652	860	CYLINDER	OUTSIDE	LAPI NO.2 STACK	2		2
8	LAPI08	273542	650	860	CYLINDER	OUTSIDE	LAPI NO.2 STACK	3		3
9	LAPI08	273542	650	860	CYLINDER	OUTSIDE	LAPI NO.3 STACK	4		4
10	LAPI08	111927	312	690	DISC	TOP	MAGNETOMETER HOLDER	5		5
11	LAPI08	111974	310	690	DISC	TOP	MAGNETOMETER HOLDER	6		6
12	SKNPLF	111974	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
13	SKNPLF	111974	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
14	SKNPLF	273508	1003	860	CYLINDER	INSIDE	SCAN PLATFORM HOUSING	7		7
15	SKNPLF	273527	1000	860	CYLINDER	OUTSIDE	SCAN PLATFORM HOUSING			
16	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	9		9
17	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
18	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	10		10
19	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
20	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	11		11
21	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
22	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	12		12
23	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
24	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	13		13
25	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
26	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	14		14
27	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
28	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	15		15
29	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
30	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	16		16
31	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
32	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	17		17
33	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
34	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	18		18
35	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
36	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	19		19
37	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
38	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	20		20
39	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
40	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	21		21
41	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
42	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	22		22
43	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
44	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	23		23
45	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
46	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	24		24
47	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
48	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	25		25
49	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
50	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	26		26
51	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
52	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	27		27
53	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			
54	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM	28		28
55	SKNPLF	273527	203	860	DISC	TOP	TOP OF SCAN PLATFORM			

ADJUSTING FIELD LENGTH TO 101108 FOR THE FF SEGMENT

Table 2. Geometric Thermal Model Modal Identification

Table 3. Sink Identification

<u>Sink #</u>	<u>Description</u>
1	Magnetometer
2	LAPI Stack #1
3	LAPI Stack #2
4	LAPI Stack #3
5	Magnetometer holding platform
6	Flower Pot Top Platform
7	Adapter top spring holder
8	Adapter (cylinder part)
9	Sun shield
10	Solar Array
11	Inside S/C environment

Table 4. Orbit Average External Sink Value I_s (watts/in²)

Sink #	Apogee = 1200 Km Perigee = 275 Km	
	Sun Angle	
	30°	90°
1	.268	.122
2	.125	.142
3	.092	.147
4	.122	.142
5	.448	.207
6	.077	.017
7	.154	.043
8	.085	.062
9	.071	.063
10	.738	.066
11	.0	.0

Table 5. Internal Radiation Couplings (in²)

INPUT MATRIX VALUES FOR K1J		1		2		3		4		5		6		7		8		9		10		11		12		13		14		15		16		17		18		19		20		21		22		23		24		25		26		27		28		29		30		31		32		33		34		35		36		37		38		39		40		41		42		43		44		45		46		47		48		49		50		51		52		53		54		55		56		57		58		59		60		61		62		63		64		65		66		67		68		69		70		71		72		73		74		75		76		77		78		79		80		81		82		83		84		85		86		87		88		89		90		91		92		93		94		95		96		97		98		99		100		101		102		103		104		105		106		107		108		109		110		111		112		113		114		115		116		117		118		119		120		121		122		123		124		125		126		127		128		129		130		131		132		133		134		135		136		137		138		139		140		141		142		143		144		145		146		147		148		149		150		151		152		153		154		155		156		157		158		159		160		161		162		163		164		165		166		167		168		169		170		171		172		173		174		175		176		177		178		179		180		181		182		183		184		185		186		187		188		189		190		191		192		193		194		195		196		197		198		199		200		201		202		203		204		205		206		207		208		209		210		211		212		213		214		215		216		217		218		219		220		221		222		223		224		225		226		227		228		229		230		231		232		233		234		235		236		237		238		239		240		241		242		243		244		245		246		247		248		249		250		251		252		253		254		255		256		257		258		259		260		261		262		263		264		265		266		267		268		269		270		271		272		273		274		275		276		277		278		279		280		281		282		283		284		285		286		287		288		289		290		291		292		293		294		295		296		297		298		299		300		301		302		303		304		305		306		307		308		309		310		311		312		313		314		315		316		317		318		319		320		321		322		323		324		325		326		327		328		329		330		331		332		333		334		335		336		337		338		339		340		341		342		343		344		345		346		347		348		349		350		351		352		353		354		355		356		357		358		359		360		361		362		363		364		365		366		367		368		369		370		371		372		373		374		375		376		377		378		379		380		381		382		383		384		385		386		387		388		389		390		391		392		393		394		395		396		397		398		399		400		401		402		403		404		405		406		407		408		409		410		411		412		413		414		415		416		417		418		419		420		421		422		423		424		425		426		427		428		429		430		431		432		433		434		435		436		437		438		439		440		441		442		443		444		445		446		447		448		449		450		451		452		453		454		455		456		457		458		459		460		461		462		463		464		465		466		467		468		469		470		471		472		473		474		475		476		477		478		479		480		481		482		483		484		485		486		487		488		489		490		491		492		493		494		495		496		497		498		499		500		501		502		503		504		505		506		507		508		509		510		511		512		513		514		515		516		517		518		519		520		521		522		523		524		525		526		527		528		529		530		531		532		533		534		535		536		537		538		539		540		541		542		543		544		545		546		547		548		549		550		551		552		553		554		555		556		557		558		559		560		561		562		563		564		565		566		567		568		569		570		571		572		573		574		575		576		577		578		579		580		581		582		583		584		585		586		587		588		589		590		591		592		593		594		595		596		597		598		599		600		601		602		603		604		605		606		607		608		609		610		611		612		613		614		615		616		617		618		619		620		621		622		623		624		625		626		627		628		629		630		631		632		633		634		635		636		637		638		639		640		641		642		643		644		645		646		647		648		649		650		651		652		653		654		655		656		657		658		659		660		661		662		663		664		665		666		667		668		669		670		671		672		673		674		675		676		677		678		679		680		681		682		683		684		685		686		687		688		689		690		691		692		693		694		695		696		697		698		699		700		701		702		703		704		705		706		707		708		709		710		711		712		713		714		715		716		717		718		719		720		721		722		723		724		725		726		727		728		729		730		731		732		733		734		735		736		737		738		739		740		741		742		743		744		745		746		747		748		749		750		751		752		753		754		755		756		757		758		759		760		761		762		763		764		765		766		767		768		769		770		771		772		773		774		775		776		777		778		779		780		781		782		783		784		785		786		787		788		789		790		791		792		793		794		795		796		797		798		799		800		801		802		803		804		805		806		807		808		809		810		811		812		813		814		815		816		817		818		819		820		821		822		823		824		825		826		827		828		829		830		831		832		833		834		835		836		837		838		839		840		841		842		843		844		845		846		847		848		849		850		851		852		853		854		855		856		857		858		859		860		861		862		863		864		865		866		867		868		869		870		871		872		873		874		875		876		877		878		879		880		881		882		883		884		885		886		887		888		889		890		891		892		893		894		895		896		897		898		899		900		901		902		903		904		905		906		907		908		909		910		911		912		913		914		915		916		917		918		919		920		921		922		923		924		925		926		927		928		929		930		931		932		933		934		935		936		937		938		939		940		941		942		943		944		945		946		947		948		949		950		951		952		953		954		955		956		957		958		959		960		961		962		963		964		965		966		967		968		969		970		971		972		973		974		975		976		977		978		979		980		981		982		983		984		985		986		987		988		989		990		991		992		993		994		995		996		997		998		999		1000		1001		1002		1003		1004		1005		1006		1007		1008		1009		1010		1011		1012		1013		1014		1015		1016		1017		1018		1019		1020		1021		1022		1023		1024		1025		1026		1027		1028		1029		1030		1031		1032		1033		1034		1035		1036		1037		1038		1039		1040		1041		1042		1043		1044		1045		1046		1047		1048		1049		1050		1051		1052		1053		1054		1055		1056		1057		1058		1059		1060		1061		1062		1063		1064		1065		1066		1067		1068		1069		1070		1071		1072		1073		1074		1075		1076		1077		1078		1079		1080		1081		1082		1083		1084		1085		1086		1087		1088		1089		1090		1091		1092		1093		1094		1095		1096		1097		1098		1099		1100		1101		1102		1103		1104		1105		1106		1107		1108		1109		1110		1111		1112		1113		1114		1115		1116		1117		1118		1119		1120		1121		1122		112	
-----------------------------	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	-----	--

Table 8. S/C External Nodal Absorbed Heat
Input Not Accounted for with
External Sinks (Watts)

Node #	Apogee = 1200 Km Perigee = 275 Km	
	Sun Angle	
	30°	90°
1	0	.0
2	6.014	6.599
3	4.33	6.78
4	4.83	5.401
5	9.769	1.476
6	2.16	.626
7	0	0
8	1.97	0.553
9	0	0
10	0	0
11	0	0
12	0	0
13	0	0
14	0	0
15	0	0
16	2.19	1.601
17	0	0
18	0	0
19	1.43	1.243
20	0	0
21	0	0

Table 9. Nodal Absorbed External Heat Flux - Sun Angle = 30°

DATE 10/04/74 TIME 09:14:33 THERMAL RADIATION ANALYSIS SYSTEM (TPRAYS) CDC6300/SCOPE 3.0 PAGE 68

MODEL=SCALP1 CONFIG=SCALP1 ST-PRINT=0
 ABSORBED Q OUTPUT COMPUTATION LINK. -----DE-B LAPI 3 SCALP1M E-TERNAL FLUX, SUN ANG=30.-----

AVERAGE INITIAL HEATING FLUX AND AREA CARDS PUNCHED

VALUES ARE: FLUX = INPUT (UNITS) * EXPR WHERE EXPR = .10330E+01
 VALUE AND AREA = INPUT (UNITS) * AMPE WHERE AMPE = .10000E+01

0	1	1.00000000E+00	1.00000000E+00
0	2	1.00000000E+00	1.00000000E+00
0	3	1.00000000E+00	1.00000000E+00
0	4	1.00000000E+00	1.00000000E+00
0	5	1.00000000E+00	1.00000000E+00
0	6	1.00000000E+00	1.00000000E+00
0	7	1.00000000E+00	1.00000000E+00
0	8	1.00000000E+00	1.00000000E+00
0	9	1.00000000E+00	1.00000000E+00
0	10	1.00000000E+00	1.00000000E+00
0	11	1.00000000E+00	1.00000000E+00
0	12	1.00000000E+00	1.00000000E+00
0	13	1.00000000E+00	1.00000000E+00
0	14	1.00000000E+00	1.00000000E+00
0	15	1.00000000E+00	1.00000000E+00
0	16	1.00000000E+00	1.00000000E+00
0	17	1.00000000E+00	1.00000000E+00
0	18	1.00000000E+00	1.00000000E+00
0	19	1.00000000E+00	1.00000000E+00
0	20	1.00000000E+00	1.00000000E+00
0	21	1.00000000E+00	1.00000000E+00
0	22	1.00000000E+00	1.00000000E+00
0	23	1.00000000E+00	1.00000000E+00
0	24	1.00000000E+00	1.00000000E+00
0	25	1.00000000E+00	1.00000000E+00
0	26	1.00000000E+00	1.00000000E+00
0	27	1.00000000E+00	1.00000000E+00
0	28	1.00000000E+00	1.00000000E+00
0	29	1.00000000E+00	1.00000000E+00
0	30	1.00000000E+00	1.00000000E+00
0	31	1.00000000E+00	1.00000000E+00
0	32	1.00000000E+00	1.00000000E+00
0	33	1.00000000E+00	1.00000000E+00
0	34	1.00000000E+00	1.00000000E+00
0	35	1.00000000E+00	1.00000000E+00
0	36	1.00000000E+00	1.00000000E+00
0	37	1.00000000E+00	1.00000000E+00
0	38	1.00000000E+00	1.00000000E+00
0	39	1.00000000E+00	1.00000000E+00
0	40	1.00000000E+00	1.00000000E+00
0	41	1.00000000E+00	1.00000000E+00
0	42	1.00000000E+00	1.00000000E+00
0	43	1.00000000E+00	1.00000000E+00
0	44	1.00000000E+00	1.00000000E+00
0	45	1.00000000E+00	1.00000000E+00
0	46	1.00000000E+00	1.00000000E+00
0	47	1.00000000E+00	1.00000000E+00
0	48	1.00000000E+00	1.00000000E+00
0	49	1.00000000E+00	1.00000000E+00
0	50	1.00000000E+00	1.00000000E+00
0	51	1.00000000E+00	1.00000000E+00
0	52	1.00000000E+00	1.00000000E+00
0	53	1.00000000E+00	1.00000000E+00
0	54	1.00000000E+00	1.00000000E+00
0	55	1.00000000E+00	1.00000000E+00

TOTAL TIME TO COMPUTE ABSORBED Q OUT .29

ADJUSTING FIELD LENGTH TO 035.00 FOR THE 00 SEGMENT

Table 10. Nodal Absorbed External Heat Flux, - Sun Angle = 90°

DATE 10/ 5/77 TIME 15.30.37 THERM RADIATION ANALYSIS SYSTEM (TRACYS) CDC6500/SCOFF 3.4 PAGE 109

MODEL=SCALPI CONFIG=DUHLEPI STEPI 100
 ABSORBED 1 OUTPUT COMPUTATION LINK.

AVERAGE INITIAL HEATING FLUX AND AREA CARDS PUNCHED

VALUES ARE FLUX = INPUT (UNITS) * EMF WHERE EMF = .10000E+01
 VALUES ARE AREA = INPUT (UNITS) * AMPF WHERE AMPF = .10000E+01

1	1	1.00000E+00	1.00000E+00
2	2	1.00000E+00	1.00000E+00
3	3	1.00000E+00	1.00000E+00
4	4	1.00000E+00	1.00000E+00
5	5	1.00000E+00	1.00000E+00
6	6	1.00000E+00	1.00000E+00
7	7	1.00000E+00	1.00000E+00
8	8	1.00000E+00	1.00000E+00
9	9	1.00000E+00	1.00000E+00
10	10	1.00000E+00	1.00000E+00
11	11	1.00000E+00	1.00000E+00
12	12	1.00000E+00	1.00000E+00
13	13	1.00000E+00	1.00000E+00
14	14	1.00000E+00	1.00000E+00
15	15	1.00000E+00	1.00000E+00
16	16	1.00000E+00	1.00000E+00
17	17	1.00000E+00	1.00000E+00
18	18	1.00000E+00	1.00000E+00
19	19	1.00000E+00	1.00000E+00
20	20	1.00000E+00	1.00000E+00
21	21	1.00000E+00	1.00000E+00
22	22	1.00000E+00	1.00000E+00
23	23	1.00000E+00	1.00000E+00
24	24	1.00000E+00	1.00000E+00
25	25	1.00000E+00	1.00000E+00
26	26	1.00000E+00	1.00000E+00
27	27	1.00000E+00	1.00000E+00
28	28	1.00000E+00	1.00000E+00
29	29	1.00000E+00	1.00000E+00
30	30	1.00000E+00	1.00000E+00
31	31	1.00000E+00	1.00000E+00
32	32	1.00000E+00	1.00000E+00
33	33	1.00000E+00	1.00000E+00
34	34	1.00000E+00	1.00000E+00
35	35	1.00000E+00	1.00000E+00
36	36	1.00000E+00	1.00000E+00
37	37	1.00000E+00	1.00000E+00
38	38	1.00000E+00	1.00000E+00
39	39	1.00000E+00	1.00000E+00
40	40	1.00000E+00	1.00000E+00
41	41	1.00000E+00	1.00000E+00
42	42	1.00000E+00	1.00000E+00
43	43	1.00000E+00	1.00000E+00
44	44	1.00000E+00	1.00000E+00
45	45	1.00000E+00	1.00000E+00
46	46	1.00000E+00	1.00000E+00
47	47	1.00000E+00	1.00000E+00
48	48	1.00000E+00	1.00000E+00
49	49	1.00000E+00	1.00000E+00
50	50	1.00000E+00	1.00000E+00
51	51	1.00000E+00	1.00000E+00
52	52	1.00000E+00	1.00000E+00
53	53	1.00000E+00	1.00000E+00
54	54	1.00000E+00	1.00000E+00
55	55	1.00000E+00	1.00000E+00

ORIGINAL PAGE IS
 OF POOR QUALITY

TOTAL TIME TO COMPUTE ABSORBED 2.707 2A

ADJUSTING FIELD LENGTH TO 23630 FOR THE ON SEGMENT

Table 11-1 - Nodal Internal Power Dissipation

Node #	Description	Power Dissipation (watts)
1	Magnetometer	.1
2-3-4	LAPI Sensor	6.3
11,13	Driving Motor	6.0
17	High Voltage Power Supply	4.2
18	Central Electronics Package	7.3

Table 11-2 LAPI/Scan Platform Total Nodal Power Distribution

[illegible]





Figure 1. LAPI/Scan Platform Schematic and Nodal Identification

ORIGINAL PAGE IS
OF POOR QUALITY


DEB LAP1 AND SCAN PLATFORM THERMAL ANALYSIS



VIEW - 3-0
SCALE - 0.650
VIEW NUMBER - 1

Figure 2.


DE-8 LAP1 AND SCAN PLATFORM THERMAL ANALYSIS



VIEW - Y-AXIS
SCALE - .0050
VIEW NUMBER - 1

Figure 3.


DE-B LAM AND SCAN PLATFORM THERMAL ANALYSIS



VIEU • X-AXIS
SCALE • .0050
VIEU NUMBER • 1

Figure 4.

DEB LAPI AND SCAN PLATFORM THERMAL ANALYSIS




VIEW = Z-AXIS
SCALE = .0050
VIEW NUMBER = 1

Figure 5.

Figure 6.


DEPENDENCE OF TEMPERATURE ON DUTY CYCLE FOR
COMPONENTS OF LAPI + SCAN PLATFORM AT 30° SUN ANGLE



ORIGINAL PAGE IS
OF POOR QUALITY

Figure 7.

DEPENDENCE OF TEMPERATURE ON DUTY CYCLE FOR COMPONENTS
OF LAP1 & SCAN PLATFORM AT 90° SON ANGLE



ORIGINAL PAGE 1
OF POOR QUALITY

Table 12. Temperature Distribution of all Cases

RESULTANT MATRIX OF 4 ITERATION FOR T									
SUN ANG = 30°, DUTY CYC = 50%									
1	40.5461	2	40.7146	3	34.1551	4	37.7132	5	55.6533
7	30.5269	8	32.4202	9	29.3135	10	28.2431	11	31.2411
13	29.5658	14	27.5215	15	26.1533	16	24.5693	17	30.5783
19	7.9978	20	100.9293	21	25.0330				33.2227
32	32.3926								36.4643
33	33.1184								39.9709

RESULTANT MATRIX OF 4 ITERATION FOR T									
SUN ANG = 30°, DUTY CYC = 50%									
1	39.7070	2	34.9741	3	36.9050	4	36.5364	5	54.7471
7	25.0741	8	32.1300	9	28.5184	10	27.5483	11	26.5483
13	27.7354	14	26.7156	15	25.0443	16	24.7563	17	30.4259
19	7.9370	20	100.9222	21	25.0210				31.2541
32	31.2666								36.1630
33	31.2541								39.9709

RESULTANT MATRIX OF 4 ITERATION FOR T									
SUN ANG = 30°, DUTY CYC = 50%									
1	39.0950	2	37.3330	3	34.5543	4	34.6177	5	53.4297
7	22.7212	8	31.4245	9	26.7120	10	26.1548	11	25.4051
13	25.0167	14	25.0480	15	24.7774	16	23.8413	17	27.6421
19	7.4451	20	100.4534	21	25.0051				28.2156
32	29.7955								35.4327
33	28.2156								39.9709

RESULTANT MATRIX OF 4 ITERATION FOR T									
SUN ANG = 30°, DUTY CYC = 50%									
1	39.0950	2	37.3330	3	34.5543	4	34.6177	5	53.4297
7	22.7212	8	31.4245	9	26.7120	10	26.1548	11	25.4051
13	25.0167	14	25.0480	15	24.7774	16	23.8413	17	27.6421
19	7.4451	20	100.4534	21	25.0051				28.2156
32	29.7955								35.4327
33	28.2156								39.9709

RESULTANT MATRIX OF 4 ITERATION FOR T									
SUN ANG = 30°, DUTY CYC = 50%									
1	39.0950	2	37.3330	3	34.5543	4	34.6177	5	53.4297
7	22.7212	8	31.4245	9	26.7120	10	26.1548	11	25.4051
13	25.0167	14	25.0480	15	24.7774	16	23.8413	17	27.6421
19	7.4451	20	100.4534	21	25.0051				28.2156
32	29.7955								35.4327
33	28.2156								39.9709

RESULTANT MATRIX OF 4 ITERATION FOR T									
SUN ANG = 30°, DUTY CYC = 50%									
1	39.0950	2	37.3330	3	34.5543	4	34.6177	5	53.4297
7	22.7212	8	31.4245	9	26.7120	10	26.1548	11	25.4051
13	25.0167	14	25.0480	15	24.7774	16	23.8413	17	27.6421
19	7.4451	20	100.4534	21	25.0051				28.2156
32	29.7955								35.4327
33	28.2156								39.9709

RESULTANT MATRIX OF 4 ITERATION FOR T									
SUN ANG = 30°, DUTY CYC = 50%									
1	39.0950	2	37.3330	3	34.5543	4	34.6177	5	53.4297
7	22.7212	8	31.4245	9	26.7120	10	26.1548	11	25.4051
13	25.0167	14	25.0480	15	24.7774	16	23.8413	17	27.6421
19	7.4451	20	100.4534	21	25.0051				28.2156
32	29.7955								35.4327
33	28.2156								39.9709

RESULTANT MATRIX OF 4 ITERATION FOR T									
SUN ANG = 30°, DUTY CYC = 50%									
1	39.0950	2	37.3330	3	34.5543	4	34.6177	5	53.4297
7	22.7212	8	31.4245	9	26.7120	10	26.1548	11	25.4051
13	25.0167	14	25.0480	15	24.7774	16	23.8413	17	27.6421
19	7.4451	20	100.4534	21	25.0051				28.2156
32	29.7955								35.4327
33	28.2156								39.9709

Design Note

REAR Astro Electronics

Originating Project or Group	Note No. 3.2.2-008-DN
Title DE-A ATC THERMAL DESIGN AND PERFORMANCE	
Written by: C. Chhatpar <i>CC Chhatpar</i>	Date: Oct. 13, 1978
Approved by: W. V. Fuldner <i>W. V. Fuldner</i>	Date: Oct. 13, 1978
This DN supplements (S), replaces (R) DN Nos.	

Letter	Description	Date	Author
	Standard Distribution: R. deBastos W. Fuldner G. Hogan W. Hord C. Hume D. Shipley		

AE 1338-2 1/74

1. SUMMARY

Because of sun impingement on all sides of the DE-A spacecraft, the hot end solar array causes high temperature problems for the louver actuator design. The bimetallic actuator needs to be cooled to reasonably low temperature levels so that a louver passive set point can be selected which results in acceptable normal louver operation. This note presents a design configuration that incorporates an insulating structural block between the bimetallic housing and the end solar array substrate. Additionally, there is a cold patch concentric with and larger than the housing diameter to locally cool the structural block. Both design changes help achieve acceptable temperature ranges for the bimetallic spring and the housing.

Only the hot end problem is analyzed here. It is assumed that the cold end (normal louver operation) design is substantially the same as for the Atmosphere Explorer louver design.

2. DESIGN REQUIREMENTS

The active-thermal-control hardware required for the DE-A spacecraft includes louvers on both ends of the spacecraft. The louvers (either end) are used in their normal mode (i.e., like DE-B) when they are not sun-illuminated. Since DE-A will not perform a 180-degree rotation when the sun crosses the orbit plane, the sun will be incident on each side of the spacecraft at some point in the mission. Figure 1 shows the louver configuration when sun-illuminated. The ATC portion of the end solar array will achieve an average temperature of 80°C when normally illuminated with the louvers closed. The primary design concern is one of effective isolation and cooling of the bimetal housing when its side of the spacecraft is illuminated. One design approach is to cover a portion (preferably a diameter concentric with larger than the housing) of the hat with a low α/ϵ surface that will reduce the maximum temperature of the hat section immediately adjacent to the bimetal housing, resulting in a more desirable operating environment. This technique also relies on a relatively low conduction from the solar-cell-covered portion of the ATC part of the end solar array to the low α/ϵ covered portion via locally reduced skin thickness or low thermal-conductivity materials as shown in Figure 2.

The end solar array achieves a maximum temperature of 80°C for +18° sun angle. This is the assumed design case for which the Bimetal coil will be designed. The sunlit louvers will be commanded close by disabling the ATCE bimetallic heater. This puts the ATC under the passive operation whereby the passive set point (the temperature where bimetallic heater starts to open, without being supplied external heater power, by being radiatively coupled to the hot end array) of the bimetallic heater should be higher than the actual temperature achieved.

3. DESIGN CONFIGURATION

The louver actuator housing design shown in Figure 2 is the same as that of AE spacecraft, except for the following additions:

a) There is a bimetal-housing-support block of low-conductivity material. This structural block provides isolation of the bimetal housing from the hot end array substrate. Two different materials are investigated to carry out the parametric study to evaluate the effect of conductivity on the bimetallic coil temperature.

b) There is a cold patch concentric with and larger than the actuator housing diameter. This patch 10 mil Al/Teflon, bonded on space facing side of the structural block, will provide a local cooling effect of the structural block, thereby assisting the block to isolate the actuator housing from the substrate.

The dynamic loads and stress analysis of this configuration will have to show that addition of this structural block can be accomplished by the two selected or other available materials. Any design change dictated by the stress analysis can be incorporated without altering the major thermal assumptions. Table 1 shows the mechanical and thermal properties of the two selected materials.

TABLE 1. CANDIDATE STRUCTURAL BLOCK MATERIAL PROPERTIES

Material	Thermal Conductivity watts/in/°C	Tensile Ult. Strength (psi)
Polycarbofil G50/40	.00136	23,000
G11	.0074	40,000




Figure 1. DE-A Louver Assembly Configuration




Figure 2. Bimetal Housing Mounted on Structural Support Block

ORIGINAL PAGE IS
OF POOR QUALITY

4. THERMAL MODEL AND PERFORMANCE

A 7-node simplified thermal model of the ATC assembly is described in Table 2 and Figure 2. Table 2 also lists the external sinks, of which the equivalent black body radiation values are given in Table 4. Table 3 lists all the internal and external radiation couplings and conductive couplings between the nodes. Two materials for the isolating structural block are considered to evaluate the parametric effect of conductance on the bimetallic coil temperatures. These two materials - Polycarbofil G50/40 and G11 Fiberglass/Epoxy - have different mechanical properties (See Table 1). The selection of one or the other (or similar other material) will be determined by thermal and mechanical requirements.

Assuming end solar array substrate (Honeycomb Hat) at 80°C and spacecraft-baseplate at 25°C (constant temperature nodes), the simplified thermal model predictions show that the bimetallic coil can be adequately cooled to about 31°C by higher strength G11 epoxy-fiberglass. Applying an uncertainty factor of $\pm 5^\circ\text{C}$ results in a maximum coil temperature of 36°C.

If the louver passive set point is set at 40°C (above 36°C), then applying ΔT of 30°C to fully open the louver actively requires that the bimetallic coil be heated up to about 70°C which is an acceptable temperature of the bimetallic coil.

The data for the two materials of the structural block are plotted in Figure 3. Even though this is a simplified model of the ATC assembly, this model has indicated that it is possible to cool the bimetallic actuator housing and the coil to acceptable levels. The extended model will address to the following details:

- a) Gradients through the structural block;
- b) Accurate values of conductive couplings across the joint between substrate and housing;
- c) Heater requirements for the normal louver operation.

FIGURE 3
DEPENDENCE OF ATC ELEMENTS TEMPERATURE ON THE
CONDUCTANCE OF THE SUPPORTING STRUCTURAL BLOCK




TABLE 2. IDENTIFICATION OF NODES
AND EXTERNAL SINKS

NODE	DESCRIPTION
1	Honeycomb Hat
2	Upper Structural Block
3	Bimetal Housing
4	Bimetal Coil
5	Louver Support Hub
6	Baseplate
7	Lower Structural Block
SINK	DESCRIPTION
1	ATC Cold Patch
2	Space

TABLE 3. ATC COUPLINGS

From	To	Internal Couplings				From	To	External Coupling Radiative Coupling (in ²)
		Radiative Coupling (in ²)	Conductive Coupling					
			G50/40	Structural Block (w ^o /C)				
				G50/40	G11 Structural Block			
1	2	.016	.001	.001	1	2	1000. (1)	
1	7		.023	.125	2	1	9.927	
2	3	.022	.002	.002	6	2	1000. (2)	
2	7		.0085	.046				
3	4	.112	.002	.002				
4	5	.001	.002	.002				
5	6	5.500						
5	7	.010						

(1) Together with $Q_1 = 568.9W$ to keep $T_1 = 80^\circ C$ (Constant Temperature Node)

(2) Together with $Q_6 = 289.3W$ to keep $T_6 = 25^\circ C$ (Constant Temperature Node)

TABLE 4. EXTERNAL SINK VALUES

SINK	SINK EQUIVALENT BLACK BODY RADIATION Watts/in ²
	BOL. 18 DEGREE SUN ANGLE
1	.222
2	0

TABLE 5. THERMAL PERFORMANCE OF ATC
18° SUN ANGLE, BOL

TEMPERATURE ~°C

NODE	STRUCTURAL BLOCK MATERIAL		COMMENTS
	G50/40	G11	
1	80°C	80°C	Constant Temp Node
2	18.4	41.0	
3	20.7	35.7	
4	22.6	31.2	
5	24.9	25.7	
6	25.0	25.0	Constant Temp Node
7	64.4	69.4	

5. DISCUSSION

It is shown that the louver bimetallic spring can be cooled to 36°C by incorporating a structural block between the actuator housing and the end solar array substrate, along with a cold patch on the block facing the space to locally cool the area. Following scenarios for the DE-A louver operation are offered:

a) When sun is incident on a louver side, the louver heater on that side will be deactivated by ground command and the louver will be closed. This type of operation requires that the passive opening point (set-point) of the louver be set at a temperature higher than the housing's maximum equilibrium temperature. The bimetal housing achieves a maximum equilibrium temperature of 36°C for worst-case conditions, then, to remain closed, the passive opening temperature must be set higher than 36°C . The passive set-point is an important parameter in the louver design, since it dictates the amount of heater power required to open the louvers when louver operation is desired (the higher the passive set-point, the higher the required power to open the louvers). Also, since the bimetal must be elevated to a temperature higher than the set-point ($\sim 30^{\circ}\text{C}$ higher) to fully open the louver, the actuator housing and the bimetal will be qualified to temperatures up to 80°C .

b) When the sun is not incident on a louver side, the louver on that side will operate normally as a function of the base-plate temperature. To open, TCE will activate the bimetal heater, elevating the bimetal temperature until the louver is in a full-open position. This operation is similar to the Atmosphere Explorer louver-system operation. Since the passive set-point is set to satisfy scenario (a), the louver heater will have to drive the bimetal to a temperature approximately 30°C higher than the passive set-point while in a worst-case cold (no sun on hat) environment.

The emittance characteristic of the outside of ATC assembly facing the space has not been substantially altered by the design change. Although not analyzed here, the cold case simulation of the nominal louver operation will not result in much too different temperatures for the actuator housing than that for the Atmosphere Explorer. If anything, the situation is better with a structural insulating block between the actuator housing and the cold end array substrate, which will maintain the housing and the bimetal temperatures higher than those achieved for the Atmosphere Explorer design.

Hence, even though the passive set point of the louver dictated by scenario (a) may be higher than that for the Atmosphere Explorer louver design, the total temperature differential required to fully rotate the bimetal would be about the same, resulting in similar heater power requirements.

Design Note

ROE Astro Electronics

Originating Project or Group	Notes No. 3.2.2-009-DN
Title Thermal Interfaces for Booms and Antennas for the DE-A and DE-B Spacecraft	
Written by: C. Chhatpar <i>CC Chhatpar</i>	Date Oct. 13, 1978
Approved by: W. V. Fuldner <i>W.V. Fuldner</i>	Date Oct. 13, 1978
This DN supplements (S), replaces (R) DN Nos.	

Letter	Description	Date	Author
	Standard Distribution: R. deBastos W. Fuldner G. Hogan W. Hord C. Hume D. Shipley		

1. Summary

Current status of the boom and antenna designs are in the preliminary stage where only overall location information is available. The mechanical design has not progressed enough to yield a reasonable thermal model. However, preliminary thermal analysis has been carried out that specifies certain interface temperature requirements, external surface finish requirements and auxiliary heater requirements when the design is biased towards a cold operational performance.

2. Assessment of Design Requirements

2.1 MAG on Astromast Boom (DE-A and DE-B) Interface at MAG

Memo of Jim Marshburn, GSFC/NASA, dated July 3, 1978 specifies a .3 watt custom design heater bonded to the inside of the magnetometer mounting plate to maintain the MAG-A between 18°C and 27°C and MAG-B between 18°C and 35°C with booms between -40°C and +40°C respectively. This design also requires that the Mag mounting plate be isolated from the magnetometer base by use of titanium spacers and Delrin washers.

Since the magnetometer shadows the mounting plate for all the sun angles, a VDA finish for the mounting plate is recommended to minimize the radiation coupling between the two.

2.2 Astromast Interface at Spacecraft (DE-A and DE-B)

The Astromast housing is recessed inside the spacecraft. When fully deployed, the housing will form a cavity susceptible to all external fluxes. The spacecraft baseplate interface will be running at 25°C (at 45° sun angle for DE-A) and 0°C (at 90° sun angle for DE-A). In the 90° sun angle case, this cavity could form a significant heat-leak which will be minimized by following design recommendations:

- a) Backside of magnetometer housing will be fully blanketed.
- b) The inside of the housing will be coated with specular VDA to minimize external flux absorption.

2.3 PWI on Astromast Boom (DE-A and DE-B)

The PWI and the stub boom on the Astromast do not shadow the mounting plate as much as the magnetometer does. In order to minimize the heat exchange across the mounting plate, the mounting plate will be covered with low α , high ϵ surface finish, in addition to it being isolated from the boom itself.

2.4 S-Band Antenna (DE-A)

The bracket hinge supporting this antenna will undergo following environment:

- a) Antenna will be deployed prior to 70 rpm spin-up. As a result, it may see the initial sun angle of 108° .
- b) In orbit, the bracket will see the extreme temperature swings of the end solar array from -110°C to $+80^{\circ}\text{C}$.
- c) The hinge and the damper, while antenna is being deployed, should be between 0°C and 20°C .
- d) After antenna deployed, the bracket hinge and the damper temperature should not exceed 50°C (40°C preferably).

These environment and temperature requirements dictate that the hinge-damper design will be biased towards cold end, with a small heater to keep the assembly near 0°C under extreme cold conditions. The external finish configuration will consist of Goddard-white (NS43C) paint ($\alpha = .3$, $\epsilon = .92$) in addition to certain areas with low ϵ finish.

EOL BOL

3. Discussion

These conceptual thermal designs for the booms and the antennas are provided as guide lines for when the mechanical design starts to address to these details.

Design Note

FROM

Astro Electronics

Originating Project or Group	Note No.
	3.2.2-010-DN
Title	
DE-A and DE-B Thermal Design Hardware Summary	
Written by	Date
C. Chiatpar and P. Shang	10/6/78
Approved by	Date
W. V. Fuldner	17 Oct 78
This DN supplements (S), replaces (R) DN Nos.	

Letter	Description	Date	Author
	Standard Distribution: R. deBastos W. Fuldner G. Hogan W. Hord C. Hume D. Shipley		

1.0 Summary

To achieve temperature control of the spacecraft components during the DE missions, both Passive Thermal Control Elements and Active Thermal Control Elements are used. Because of the differences in the spacecraft operational modes and external thermal factors, individual designs are necessary to meet the mission requirements. This design note summarizes the design of thermal hardware, requirements for new hardware, areas of design difficulty for new hardware. Detailed descriptions of the thermal performances of the spacecrafts are given in 3.2.2-003 thru 006-DN.

2.0 Passive Thermal Control

Passive Thermal Control is obtained through careful selection of surface coatings, surface finishes, thermal conductive materials, thermal blankets, and thermal shields. Tables 1 and 2 list various coatings and finishes, and their application for DE-A and DE-B spacecrafts, respectively. Table 3 provides the characteristics of different thermal conduction control materials and locations at which they are used.

Thermal shields are used where protection from solar or aerodynamic heating is required. The thermal shields provided are a single layer of 2-mil second-surface aluminized Teflon, used to cover the separation-adaptor open structure between the PWI booms and the separation ring at both ends on DE-A and at the bottom end on DE-B. These shields provide sun-shielding of the +z and -z end during on-orbit operation.

TABLE 1 DE-A THERMAL-CONTROL FINISHES AND COATINGS

Coating/Finish	Application	α		ϵ	
		Minimum	Maximum	Minimum	Maximum
Black Paint (Chemglaze Z-306)	Upper & Lower baseplate, shear webs, center-column, separation adapter external (except 4-in. wide polished aluminum section adjacent to hat flange), internal-equipment surfaces, transistor brackets, separation-adapter-well equipment surfaces inside well.	0.93	0.96	0.85	0.9
White Paint (Chemglaze Z-202)	Center-band antenna bracket	0.25	0.6	0.84	0.88
White Paint (IITRI S-13 GLO)	Upper-hat out-board finish except solar cells, lower-hat outboard finish except solar cells.	0.2	0.4	0.84	0.88
Second-surface aluminized Kapton sheet (0.05 mil) reinforced with Dacron Cloth	Upper-hat side in-board, lower-hat side in-board insulation blanket.	0.32	0.37	0.5	0.55
Buffed Aluminum	Separation ring, edges of ATC opening.	-	-	-	-
Polished Aluminum	Separation-adapter-well equipment exposed surfaces.	0.08	0.15	0.02	0.05
Second-surface aluminized Teflon sheet (2 mil)	Separation adapter well equipment exposed surfaces, thermal shield external.	0.13	0.2	0.62	0.67
Second-surface aluminized Teflon sheet (10 mil)	ATC cold patches	0.15	0.2	0.79	0.83
Goddard White Goddard Green	RIMS Ground Plane S-Band Antenna Bracket, bare-metal ground planes and areas*	0.2 to 0.6	0.3 to 0.7	0.92	0.92

* Electrically conductive paint to satisfy bare-metal area requirements with acceptable thermal properties.

TABLE 2 DE-B THERMAL-CONTROL FINISHES AND COATINGS

Coating/Finish	Application	α		ϵ	
		Minimum	Maximum	Minimum	Maximum
Black Paint (Chemblaze Z-306)	Upper and lower baseplates, shear webs, center-column, separation adapter external (except 4-inch wide polished aluminum section adjacent to hat flange), internal-equipment surfaces, lower-hat bottom in-board, transistor brackets, separation-adapter-well equipment surfaces inside well.	0.93	0.96	0.85	0.9
White Paint (Chemglaze Z-202)	Center-board antenna bracket.	0.25	0.6	0.84	0.88
White Paint (IITRI S-13-GLO)	Upper-hat outboard finish except solar cells, lower-hat outboard finish except solar cells.	0.2	0.4	0.84	0.88
Alternate black-chemglaze and gold-tape stripes	Upper-hat side in-board, lower-hat side in-board.	Controlled		Controlled	
Gold-tape/gold finish	Upper-hat top in-board, except ATC, ATC actuator housing outside.	0.19	0.25	0.02	0.05
Buffed Aluminum	Separation ring, edges of ATC opening.	-	-	-	-
Polished Aluminum	Separation-adapter-well equipment exposed surfaces.	0.08	0.15	0.02	0.05
Second surface aluminized Teflon sheet (2 mil)	Separation-adapter-well equipment exposed surfaces, thermal shield external.	0.13	0.2	0.62	0.67
Goddard White Goddard Green	Bare-metal ground planes, Astromast housing outside and areas.*	0.2 to 0.6	0.3 to 0.7	0.92	0.92

*Electrically conductive paint to satisfy bare-metal area requirements with acceptable thermal properties.

TABLE 3 THERMAL-CONDUCTION-CONTROL MATERIALS

Material Type	Thermal Characteristics	Use Location
G11 Epoxy Fiberglass	Provides high thermal resistance to heat flow and high strength.	Bushings between separation adapter and bottom hat. Actuator housing support between top and bottom array and actuator housing on DE-A.
G50/40 Poly carbofil	Provides high thermal resistance.	Bushings between base-plates and hats.
Unprimed RTV	Improves thermal conductivity across high-power equipment mounting interface.	At mounting interfaces of transponder to base-plate.

Thermal Blankets

The application and construction of thermal-insulation blankets used on the spacecraft are given below. Blanket assembly and attachment to spacecraft surfaces are accomplished using urethane "button tacks", Velcro zippers, and tapes.

- Spacecraft-Side Outer Layer
 - Second-surface aluminized Kapton, 0.5 mil reinforced with Dacron cloth.
 - Inner Layers (10 layers).
 - Double-sided aluminized Mylar, 0.25-mil thick.
 - Separators (11 layers).
 - Dacron net, 1/8-inch honeycomb weave.
- Anti-Spacecraft-Side Outer Layer
 - Second-surface aluminized Kapton, 0.5 mil reinforced with Dacron cloth.

3.0 Active Thermal Control

Active Thermal Control Elements consist of heaters, louvers, and ATCE units. It is through the usage of these elements that the cooling and heating spacecraft components are achieved. In this section the heating elements and louvers used on the DE spacecrafts are briefly described.

Active Control Louvers

Four 20-inch diameter, double bladed, rotating vane, and bimetal actuated louvers (Figs. 1 and 2) which are similar to those on the AE spacecraft, are mounted on the antisun side of the spacecraft (Fig. 3), providing a radiation coupling to space which is variable. The louvers are actuated by a heating element located on the bimetal element housing. A sensor, located on the upper baseplate, is set to turn on the heater at a preselected temperature, driving the louver open. A louver system design almost identical to the AE spacecraft is applicable to the DE-B spacecraft.

The active thermal control hardware required for the DE-A spacecraft includes louvers (Fig. 4) on both ends of the spacecraft. The louvers (either end) are used in their normal mode (i.e., like DE-B) when they are not sun-illuminated, since DE-A will not perform a 180-degree rotation when the sun crosses the orbit plane; however, the sun will be incident on each side of the spacecraft at some point in the mission. Figure 5 shows the louver configuration when sun-illuminated. The ATC portion of the end solar array will achieve an average temperature of 80°C when normally illuminated with the louvers closed. The primary design concern is one of effective isolation and cooling of the bimetal housing when its side of the spacecraft is illuminated. One design approach is to cover a portion (preferably a diameter concentric with the housing) of the hat with a low α/ϵ surface that will reduce the maximum temperature of the hat section immediately adjacent to the bimetal housing, resulting in a more desirable operating environment. This technique also relies on a relatively low conduction from the solar-cell-covered portion of the ATC part of the end solar array to the low α/ϵ covered portion via locally reduced skin thickness or low thermal-conductivity materials as shown in Figure 6. A preliminary thermal analysis shows that temperature of the isolated hat section surrounding the housing will be lower than 40°C when the hat is at 80°C. The scenarios for DE-A louver operation are as follows:

- (1) When sun is incident on a louver side, the louver heater on that side will be deactivated by ground command and the louver will be closed. This type of operation requires that the passive opening point (set-point) of the louver be set at a temperature higher than the housing's maximum equilibrium temperature. For example, if the bimetal housing achieves a maximum equilibrium temperature of 40°C for worst-case conditions, then, to remain closed, the passive






Figure 1. Louver Blade Configuration (From AE)



RE-PROD SECTION A-A
WITH 1/2" SCALE INDICATED IN LINE OF SECTION



SECTION B-B

Figure 2. Bimetal/Housing Configuration (From AE)

ORIGINAL PAGE IS
OF QUALITY




Figure 3. DE-B Thermal Configuration




Figure 4. DE-A Thermal Configuration




Figure 5. DE-A Louver Assembly Configuration




Figure 6. Bimetal Housing Mounted on
Structural Support Block

ORIGINAL PAGE IS
OF POOR QUALITY

opening temperature must be set higher than 40°C. The passive set-point is an important parameter in the louver design, since it dictates the amount of heater power required to open the louvers when louver operation is desired (the higher the passive set-point, the higher the required power to open the louvers). Also, since the bimetal must be elevated to a temperature higher than the set-point ($\approx 30^\circ\text{C}$ higher) to fully open the louver, the activator housing and the bimetal will be qualified to temperatures up to 80°C.

- (2) When the sun is not incident on a louver side, the louver on that side will operate normally as a function of the baseplate temperature. To open, TCE will activate the bimetal heater, elevating the bimetal temperature until the louver is in a full-open position. This operation is similar to the Atmosphere Explorer louver-system operation. Since the passive set-point is set to satisfy scenario one, the louver heater will have to drive the bimetal to a temperature approximately 30°C higher than the passive set-point while in a worst-case cold (no sun on hat) environment. If a louver design similar to the Atmosphere Explorer design is used, the required louver heater power will be higher than the Atmosphere Explorer louver power. A decrease in louver heater power is possible by employing a current TIROS-N design in the bimetal/heater area. The design consists of bonding the heating element directly to the bimetal coil rather than the housing surrounding the coil as was done for Atmosphere Explorer. The advantages of this design are increased-temperature response of the louver and more direct heating of the bimetal coil with reduced bimetal heater-power requirements.

Active Control Heaters

Heater elements characteristics are summarized in Table 4. This thin film strip-type heater has been successfully used for body heating as well as for the louver bimetallic drive.

TABLE 4 THERMAL-CONTROL-HEATER CHARACTERISTICS

Parameter	Characteristics
Insulation Materials	Kapton/FEP
Heater Element	Non-inductive, nichrome or cupronickel
Heater Leads	24 or 30 AWG stranded, Kapton insulated*
Heater Thickness	0.010 inch maximum, except 0.065 inch maximum over leads
Lead Length	12.00 inches minimum
Lead Pull Strength	3.0 pounds minimum
Heater Bend Radius	0.1-inch radius or greater
Insulation Resistance	1000 Megohms minimum at 500 Vdc
Temp Range: Operating	-200°C to 232°C
Non-Operating	-200°C to 260°C
Power Density	Up to 70 watts/square-inch when properly heat sunk
Weight	Less than 0.25 gram per square-inch
Finish	Aluminum foil on bonded side
Heat Distribution	Uniform
*Bimetal heaters have Teflon insulation.	

**5.0 POWER SUBSYSTEM
DESIGN NOTES**

TABLE OF CONTENTS

<u>Design Note</u>	<u>Title</u>
3.4.2-005-DN	DE Array Design Considerations
3.4.2-006-DN	Shadowing of Solar Cells

Design Note

REAT Astro Electronics

Originating Project or Group	Note No. 3.4.2-005-DN
Title DE Array Design Considerations	
Written by: P. Nekrasov <i>Paul Nekrasov</i>	Date
Approved by: W. Fuldner <i>W. Fuldner</i>	Date 13 Oct 78
This DN supplements (S), replaces (R) DN Nos.	

REVISIONS

Letter	Description	Date	Author
			Distribution: C. Chhatpar K. Johnson R. deBastos D. Shipley G. Hogan W. Hord R. Horner C. Hume

Distribution:
C. Chhatpar K. Johnson
R. deBastos D. Shipley
G. Hogan
W. Hord
R. Horner
C. Hume

CONTENT

- 1.0 Introduction
- 2.0 Tentative Conclusions and Future Effort
- 3.0 Assumptions and Ground Rules
- 4.0 Nomenclature and Numerical Assumptions
- 5.0 Analysis and Discussion
 - 5.1 The NOVA Cell
 - 5.1.1 Description
 - 5.1.2 Characteristics
 - 5.1.3 Radiation Effects
 - 5.1.4 Cell Performance Analysis
 - 5.1.4.1 Series String Voltage Requirement
 - 5.1.4.2 Solar Cell Equations
 - 5.1.4.3 Solar Cell Performance Plots
 - 5.1.5 Confidence Level
 - 5.2 Cover Glass Thickness
 - 5.2.1 Summary
 - 5.2.2 Analysis
 - 5.3 Array Design Analysis
 - 5.4 Series Cell Requirements and Protection Against Shadowing
 - 5.5 DE-B Side Array Preliminary Layout Considerations
- 6.0 References

Appendix: Amount of Power Lost if Elements of a String of Series-Connected Solar Cells are Placed on Adjacent Panels of a n-Sided Configuration.

1.0 Introduction

This Design Note covers preparatory work necessary to begin solar cell layout and, ultimately, to determine the required number and size of solar cells as well as the solar array power.

Solar cell analysis performed for the DE program to date has been updated to reflect the NOVA cell technology. Series cell requirements and cell current availability have been computed for the radiation regime of the DE orbits. The 30-mil fused silica glass thickness has been found to offer nearly as much protection as the 60-mil thickness considered previously, with the added benefit of a sizable weight reduction. Preliminary layout considerations concentrate on preservation of the 2 X 2 cm cell size as a potential manufacturing cost advantage and to preserve legacy established on another RCA program; further work, however, is required in this area. The side array of the DE-B spacecraft has been used as the "driver" in the tradeoff analyses as the array portion most in need of power enhancement.

Shadowing loss protection analysis has been limited to an allowance for an increased number of series solar cells as in prior analyses.

2.0 Tentative Conclusions and Future Effort

Use of the NOVA solar cell with a non-optimized cell layout results in an end-of-life minimum Science ON Time duty cycle of 16 percent. An increase in the DE-B side array power of approximately eight percent raises the minimum duty cycle value to just above the required 19 percent minimum value (Table III, text). A potential increase of in excess of the required eight percent is possible if the DE-B side array maximum temperature, particularly the top "hat" portion, can be reduced from +67°C to +58°C or lower and if the elements of certain series cell strings are mounted on adjacent panels of the "B" array; the 2 x 2 cm cell size would be preserved in that case (part 5.5, text).

Immediate future plans include the performance of a cell layout, particularly on DE-B, to verify and finalize the tentative conclusions reached thus far as well as to define the cell quantity and characteristics (if different from the NOVA program) to initiate procurement.

3.0 Assumptions and Ground Rules


3.1 Nominal solar cell performance characteristics will be used in DE solar array design.

- (a) solar intensity seasonal variation is neglected; during the summer and winter solstices, the solar cell current will be lower than presently reported by approximately 3.4 percent; during equinoxes, it will be higher by a like amount.
- (b) prediction and measurement uncertainties, of the order of a total of +2%, are neglected.

- 3.2 Shadowing losses due to antennas, booms, and other appendages are fully compensated in DE solar arrays provided that the number of series cells is at least 10% greater than that required if no shadows were present.
- 3.3 The side array portion of the DE-B bottom array "hat" is not subject to shadowing by appendages.
- 3.4 Pending further solar cell layout work on DE arrays, present analysis is based on cell layout which is essentially the same as reported in References (5) and (8), except:
- (a) the number of series cells is generally lower due to either the improved performance characteristics of the NOVA cell, or reduced temperatures (e.g., DE-A flat-end arrays), or both,
 - (b) minor re-adjustment in the number of paralleled series strings, e.g., reduced number of strings on DE-A flat-end arrays and two additional series strings on DE-B side; Table III, text.
- 3.5 Maximum solar cell steady-state temperatures are:
- DE-A: side, $+13^{\circ}\text{C}$
end array, $+75^{\circ}\text{C}$
- DE-B: side, $+67^{\circ}\text{C}$
end array $+110^{\circ}\text{C}$
- 3.6 The solar cell is identical to that specified in Reference (1), except as modified for cell thickness in this part 5.1.2(c) and with the addition of the palladium passivation layer, as per later quote (10/2/78) from the cell vendor.
- 4.0 Nomenclature and Numerical Assumptions
- k_v solar cell voltage-temperature coefficient over linear range, in millivolts per $^{\circ}\text{C}$ rise. For NOVA cell (unirradiated), $k_v = -2.23 \text{ mv}/^{\circ}\text{C}$; reference (3)(a).
- F_v factor applied to k_v to account for a change in its value as a function of irradiation level; Figure 1.
- k_i solar cell current-temperature coefficient over linear range, in percent per $^{\circ}\text{C}$ rise. For NOVA cell (unirradiated) $k_i = +0.063\%$ per $^{\circ}\text{C}$; Reference (3)(a).

F_i	factor applied to k_i to account for a change in its value as a function of irradiation level; Figure 1.
T	temperature, $^{\circ}\text{C}$
$V_{mp}(T)$	maximum-power-point solar cell voltage at temperature T .
d_v	non-time-variant degradation factor applied to solar cell voltage, with cell installed in a solar array; $d_v = 0.99$ (cell-to-cell wiring loss).
d_{rv}	time-variant degradation factor applied to solar cell voltage, e.g., Figure 2.
$i_{mp}(T)$	maximum-power-point solar cell current at temperature T .
d_i	non-time-variant degradation factor applied to solar cell current; for present purposes, the UV damage (0.97) and coverglass charged particle loss (0.97) will both be considered as fixed degradations. Product, $d_i = 0.94$.
d_{ri}	time-variant degradation factor applied to solar cell current, e.g., Figure 2.
ΔV_{da}	array blocking diode drop, 1.0 volt; Figure 3.
ΔV_{wi}	array harness drop, 0.5 volts; Figure 3.
ΔV_{ch}	charge regulator drop, 1.5 volts; Figure 3.
V_{BC}	battery charge voltage assuming 1.45 volts per cell and 24 series storage cells; $V_{BC} = 34.8\text{V}$. Reference (5).
V_s	voltage level (charge controller input) at which solar array power is computed, presently as well as in the DE Power Analysis Computer Program, Reference (7). $V_s = 36.3$ volts. Part 5.1.4.1.

**Fig. 1 Factors Applied to Solar Cell Temperature Coefficients
to Reflect Changes in Their Value with Irradiation Level**



Note: plots are approximations
based on Fig-5 3.14
and 3.15, Reference (6),
for $T_{amb} = 25^\circ C$

ORIGINAL PAGE IS
OF POOR QUALITY

5.0 Analysis and Discussion

5.1 The NOVA Cell

5.1.1 Description

The solar cell most strongly considered for DE at the present time is the NOVA cell manufactured by OCLI. The DE cell, therefore, will be identical to that specified in Reference (1), with the possible exception of the cell dimensions which may have to be altered somewhat from the present 2 X 2 cm size to optimize the packing factor on DE, particularly on DE-B side. The cells would be ordered bare and coverglass bonded at RCA as under the NOVA program.

5.1.2 Characteristics

Given the 2 X 2 cm size, major characteristics of the NOVA-DE cell are:

- (a) minimum average solar cell output, paragraph 3.11.2, Reference (1): 151 milliamperes at 0.49 volts, at +25°C AMO.
- (b) base resistivity: 1-3 ohm-cm.
- (c) cell thickness: 10 $\pm$ 2 mills (OCLI quote 2L78-78, Mod 2, 10/2/78).
- (d) temperature coefficients, Reference (3)(a) unirradiated (see also Figure 1):

$$k_v = -2.23 \text{ mv/}^{\circ}\text{C}$$

$$k_i = +0.063\% \text{ per } ^{\circ}\text{C}$$

The above numerical characteristics form the basis for the analyses reported in this Design Note.

5.1.3 Radiation Effects

We are considering three different effects of space radiation on the power output of the NOVA solar cell. These are:

- (1) Change in the values of the voltage and current temperature coefficients. The magnitude of the change in the values of cell voltage and current per unit temperature change is generally higher with increasing radiation levels. The approximate relationship used presently is given in Figure 1.
- (2) Loss of light transmission through coverglass. A fixed 3% loss in cell current is assumed and included in the fixed current loss factor "d_i", part 4.0.
- (3) Reduction in cell voltage and current. Figure 2 is a summary of the irradiation data examined to arrive at the cell degradation factors to be used in DE. Test data provided by OCLI in Reference (3) has been performed specifically for the RCA-NOVA program. Information plotted from Reference (4) is for a solar cell thought to be most nearly equivalent to the NOVA cell in performance; note that it is slightly on the pessimistic side as compared to the OCLI data.

Degradation factors chosen as design points for DE on the basis of the data examined are also shown in Figure 2.

5.1.4 Cell Performance Analysis

5.1.4.1 Series String Voltage Requirement

Ultimate objective is to connect a sufficient number of solar cells in series to assure 1 battery recharge. Reference is made to Figure 3. Voltage level V_s at the solar bus (charge controller input) must be equal to, or exceed slightly, the sum of the charge controller drop ΔV_{ch} and the voltage of a fully charged battery. The solar cell string voltage, "V(solar cells)" in Figure 3, must therefore equal

$$\begin{aligned} V(\text{solar cells}) &= \Delta V_{da} + \Delta V_{wi} + \Delta V_{ch} + V_{BC} \quad (1) \\ &= 1.0 + 0.5 + 1.5 + 34.8 \\ &= 37.8 \text{ volts} \end{aligned}$$




Fig. 2 Radiation Effects Information

- I_{MP} ratio, Reference (3) (a), 7.6-8.8 mil cells, +25°C AMO, 1-3 ohm-cm
- V_{MP} ratio, Reference (3) (a)
- x I_{MP} ratio, Reference (3) (b), 12-mil cells, +25°C AMO, 1-3 ohm-cm
- △ V_{MP} ratio, Reference (3) (b)
- I_{MP} ratio, Reference (4), shallow-junction cell, 2 Ohm-cm, 8-12 mils thick, +30°C AMO
- V_{MP} ratio, same cell as in Reference (4) above

● Design points chosen for DE

I-Max Electron Fluence, g/cm²

9/24/72

For future reference, note that the solar array output power P_s watts is computed at voltage V_s , which is

$$V_s = \Delta V_{ch} + V_{BC} = 36.3 \text{ volts} \quad (2)$$

5.1.4.2 Solar Cell Equations

Location of the solar cell maximum power point at any temperature T within linear range, $V_{mp}(T)$, $i_{mp}(T)$, is given by

$$V_{mp}(T) = \left[V_{mp}(+25) + (T-25)F_v \cdot k_v \right] d_{rv} d_v \quad (3)$$

and

$$i_{mp}(T) = i_{mp}(+25) \left[1 + \frac{k_i}{100} F_i (T-25) \right] d_{ri} d_i \quad (4)$$

where, for the NOVA cell, part 5.1.2(a),

$$V_{mp}(+25) = 0.490 \text{ volts,}$$

$$i_{mp}(+25) = 151 \text{ ma,}$$

and F_i , F_v , d_{ri} , and d_{rv} are quantities dependent on the irradiation level.

5.1.4.3 Solar Cell Performance Plots

Quantities $v_{mp}(T)$, $i_{mp}(T)$ are computed using expressions (3) and (4) over a wide temperature range, and using irradiation level dependent quantities as tabulated in Table I.




Fig.3 Solar Cell Series String Voltage Requirements

Fluence 1-MeV e/cm ²	d _{rv} (*)	F _v (Fig. 1)	d _{ri} (*)	F _i (Fig. 1)
10 ¹³	0.99	1	0.98	1
10 ¹⁴	0.97	1.06	0.93	1.35
3 x 10 ¹⁴	0.94	1.10	0.88	1.7
10 ¹⁵	0.91	1.15	0.81	1.9

(*) These factors are the "Design Points Chosen for DE",
Figure 2.

Table 1. Irradiation Level Dependent Cell Parameters

Other numerical values used in eq-ns (3) and (4) as well as the meaning of all symbols are provided in part 4.0.

Computed quantities of $v_{mp}(T)$ are divided into 37.8 volts (part 5.1.4.1) and the result, the required number of series cells, is plotted in Figure 4 vs. solar cell temperature with the irradiation level retained as a parameter; computed quantities of $i_{mp}(T)$ are plotted directly in Figure 5. Using the latter two sets of plots, a set of "working curves" is plotted for DE in Figure 6; here, we can see exactly what the cell voltage and current will do on various parts of DE arrays, depending on what degree of protection (mils glass thickness, resulting in one or another value of "1 MeV e/cm²") we choose to provide.

5.1.5 Confidence Level

The RCA NOVA cell specification, Reference (1), sheet 14, includes a plot of the radiation resistance requirement of that cell. We want to ascertain that our cell analysis performed thus far reflects performance which compares reasonably well with the specified minimum performance requirement.

We note that the curve on sheet 14 of the RCA specification is prepared for the condition of a bare cell at $+60^{\circ}\text{C}$. Let one of our data points, say, at 10^{14} e/cm^2 (Figures 4 and 5) be reduced to the condition of the curve plotted in the spec:

- (a) from Fig. 4, volts/cell at $+60^{\circ}\text{C}$ @ 10^{14} e/cm^2 equals $37.3/96.4 = 0.392 \text{ v}$.
- (b) similarly, from Figure 5, $\text{ma/cell} = 135.8 \text{ ma}$
- (c) $\text{mw/cell} = (0.392 \text{ v}) \times (135.8 \text{ ma})$; reducing this by 1% as is the case in an un-glassed cell, $\text{mw/cell} = 52.7 \text{ mw}$. Reference (1), part 3.11.2.
- (d) $d_v = 1.00$ (cell is not yet series-connected and as such has no "wiring drop"); $52.7/0.99 = 53.2 \text{ mw}$.
- (e) $d_i = 1.00$ ("fixed" current loss, acquired only after launch, is zero); $53.2/0.94 = 56.7 \text{ mw}$.

The latter value, 56.7 mw, compares well with 55 mw which is the minimum acceptable cell power at 10^{14} e/cm^2 1-MeV fluence. This and three other computed values are plotted on the curve from the RCA cell spec which is reproduced here in Figure 7. It is evident that the cell parameters being used presently for DE are based on cell performance which is just barely above the minimum acceptable procurement level and, as such, are reasonably "safe".

5.2 Cover Glass Thickness

5.2.1 Summary

As pointed out in Reference (6), significant weight savings can be achieved if the fused silica cover glass thickness could be reduced from 60 to 30 mils on both DE spacecraft. Results of the analysis of the radiation environment in DE orbits, Reference (2), and the NOVA cell analysis reported in this part 5.1 provided the means for a cover-glass thickness tradeoff study as a result of which we find that the DE-B side array power suffers a loss of only one percent or less in going from 60 to 30 mils.

Discussion of the tradeoff analysis detail follows in part 5.2.2 below.

46 1513


14-Σ 10 X 10 TO THE CENTIMETER 8 X 25 CM
KLUFFEL & ESSER CO. MADE IN U.S.A.

NOVA Solar Cell

Fig. 4. Series Cells Required vs. Cell Max. Steady-State Temperature

No provisions for shading


Solar Cell Voltage = 37.8 v.



ORIGINAL PAGE IS
OF POOR QUALITY

46 1513

Fig. 5. Nova Solar Cell Current
2x2 cm cell



9/22/78

Fig. 6: NOVA Solar Cell Radiation Degradation in DE





Figure 7. Confidence Level



(Reference (1), Figure 1, Radiation Resistance Requirement Curve - Unglassed Cells at 60°C)

Size	Code Ident No.	2285464
A	49671	
		Sheet 14

5.2.2 Analysis

Results of the glass thickness effects analysis are presented graphically in Figures 9 and 10. Most significantly, Figure 10 shows that increasing the glass thickness on the side array of DE-B beyond 30 mils does not produce an appreciable increase in EOL power.

Mechanics of the analysis is best described by reference to various columns (1 thru 12) in Table II. Let it be noted that this analysis is intended to be accurate only in a relative sense, and that great accuracies in the absolute numbers of watts per pound or per square foot quoted in Table II or in either Figures 9 or 10 are not to be expected.

Further discussion of the cover glass thickness as an array design parameter appears in part 5.3. Presently, reference is made to Table II:

<u>Column</u>	<u>Rationale</u>
1 and 2	Self-explanatory.
3	Maximum steady-state solar cell temperature.
4	Fused silica cover glass thickness.
5	Equivalent 1-MeV electron fluence for 13-month life, Reference (2).
6	From Figure 6.
7	Equivalent 1-MeV electron fluence for 13-month life, Reference (2).
8	From Figure 6.

ColumnRationale

9

Series cells required to locate the 13-month EOL maximum power point at 37.8 volts using per-cell voltage of Column 8. Plotted in Figure 8.

10

Using current and voltage given in columns 6 and 8, respectively, and assuming 204 2 x 2 cm cells per sq. ft. in a typical solar panel, the calculation becomes

$$\text{watts/sq. ft.} = 204 \frac{\text{cells}}{\text{sq.ft}} \times \frac{(\text{volts})(\text{ma})}{\text{cell}} \times 10^{-3} \frac{\text{W}}{\text{mW}}$$

Note that with discrete bypass diodes mounted on array surface the number of cells per sq. ft. will be somewhat less than 204; for glass thickness trade-off purposes, however, consistency rather than absolute accuracy of the calculated watts/sq. ft. numbers is of primary importance.

Column

Rationale

The calculated numbers are plotted in Figures 9 and 10.

11

Using fused silica coverglass areal density of 0.335 grams/cm² of 60-mil thickness, reference (4), Appendix A, page A-1, 204 2 x 2 cm cells per sq. ft. as in Column 10, 3.918 cm² coverglass area per 2 x 2 cm cell, and 0.45 pounds per sq. ft. of assembled solar cells exclusive of any cover glass, the pounds per sq. ft. calculation becomes

$$\frac{\text{pounds}}{\text{sq. ft.}} = 0.45 \frac{\text{lb}}{\text{ft}^2} + 204 \frac{\text{covers}}{\text{ft}^2} \times \\ \times (0.335 \frac{\text{gm}}{\text{cm}^2}) (\frac{\Delta t}{60 \text{ mils}}) (3.918 \frac{\text{cm}^2}{\text{cover}}) (\frac{1}{453 \frac{\text{gm}}{\text{lb}}})$$

$$\frac{\text{pounds}}{\text{sq. ft.}} = 0.00985 \Delta t + 0.45$$

where Δt = glass thickness, mils

Note that the fixed quantity 0.45 lb/ft² is not precise, will vary with each array, and is not intended to include the substrate; for glass thickness tradeoff purposes, however, consistency rather than absolute accuracy of the calculated pounds/sq.ft. numbers is of primary importance.

12

The watts/pound numbers are calculated using columns 10 and 11, and plotted in Figures 9 and 10.

1	2	3	4	5	6	7	8	9	10	11	12
DE Flight	Array	Temp. °C	mils, glass	Cell Current		Cell Voltage		Series cells req'd	Watts sq.ft	Pounds sq.ft.	Watts pound
				1 MeV e/cm ²	ma/cell	1 MeV e/cm ²	volts/cell				
A	side	+13	6	3 x 10 ¹⁵	103.5	7 x 10 ¹⁵	0.447	84.6	9.44	0.509	18.54
			10	1.4 x 10 ¹⁵	109.4	3.3 x 10 ¹⁵	0.455	83.2	10.16	0.548	18.54
			20	4.5 x 10 ¹⁴	120	8 x 10 ¹⁴	0.473	80	11.58	0.647	17.9
			40	1.9 x 10 ¹⁴	127	2.7 x 10 ¹⁴	0.485	78	12.57	0.844	14.89
			60	9.5 x 10 ¹³	130.7	1.3 x 10 ¹⁴	0.495	76.4	13.2	1.041	12.68
B	top/bot.	+75	6	3 x 10 ¹⁵	110	7 x 10 ¹⁵	0.30	126	6.73	0.509	13.22
			10	1.4 x 10 ¹⁵	118.5	3.3 x 10 ¹⁵	0.31	122	7.5	0.548	13.68
			20	4.5 x 10 ¹⁴	128.5	8 x 10 ¹⁴	0.33	114.5	8.65	0.647	13.37
			40	1.9 x 10 ¹⁴	134.3	2.7 x 10 ¹⁴	0.343	110.2	9.4	0.844	11.14
			60	9.5 x 10 ¹³	137.7	1.3 x 10 ¹⁴	0.352	107.3	9.89	1.041	9.5
B	side	+67	6	1.3 x 10 ¹⁴	135.3	2.5 x 10 ¹⁴	0.364	103.8	10.05	0.509	19.74
			10	8.1 x 10 ¹³	137.3	1.5 x 10 ¹⁴	0.372	101.6	10.42	0.548	19.01
			20	4.6 x 10 ¹³	139.1	6.9 x 10 ¹³	0.381	99.2	10.81	0.647	16.71
			40	3 x 10 ¹³	140.2	4 x 10 ¹³	0.385	98.2	11.01	0.844	13.04
			60	2.2 x 10 ¹³	141	2.6 x 10 ¹³	0.387	97.7	11.21	1.041	10.77
B	bottom	+110	6	1.3 x 10 ¹⁴	140.5	2.5 x 10 ¹⁴	0.265	142.6	7.6	0.509	14.93
			10	8.1 x 10 ¹³	142	1.5 x 10 ¹⁴	0.273	138.5	7.91	0.548	14.43
			20	4.6 x 10 ¹³	143.5	6.9 x 10 ¹³	0.283	133.6	8.28	0.647	12.8
			40	3 x 10 ¹³	144.5	4 x 10 ¹³	0.288	131.3	8.49	0.844	10.06
			60	2.2 x 10 ¹³	145.1	2.6 x 10 ¹³	0.291	129.9	8.61	1.041	8.27

Table II. Cover Glass Thickness Tradeoffs

Fig. 8. DE Series Cells vs. Glass Thickness

No shadowing effects

13-mo. Life

2/28/81 Launch

NOVA Cell




Fig. 9. DE-A Glass Thickness Effects

13-mo. life

2/22/81 launch

NOVA Cell

— Watts/pound

- - - Watts/sq. ft

Side

+13°C

Top/Bottom

+75°C

ORIGINAL PAGE IS
OF POOR QUALITY

M/S, Fused Silica

461513

100% MAX. TO THE CENTER OF A




Fig. 10. DE-B Glass Thickness Effects

13-mo. life

2/28/81 Launch


NOVA Cell

— watts/pound

- - - watts/sq. ft

46 1513

IN FEET TO THE CENTIMETER



5.3 Array Design Analysis

Ten different solutions are summarized in Table III. Duty cycle values tabulated in Column 5 for DE-A and DE-B have been computed under identical load profile conditions for each respective spacecraft as reported in the RCA Proposal, Reference (5).

The first two solutions are those of the DE solar arrays as proposed in Reference (5); the Proposal includes the details of the numerical analysis performed to arrive at the numbers tabulated.

Solutions 3 and 4 were obtained subsequent to the Proposal submission assuming a 12.5% power increase over the proposed solar cells and some adjustment in the number of series string quantities as given in Column 10.

Solutions 5 through 10 are based on the NOVA (OCLI) solar cell and, as such, are the primary object of the remainder of this discussion; the first four solutions are included in the table primarily for their historical significance and will not be discussed any further.


Rationale used in preparing Table III is discussed below.

Columns 1 and 2 identify the DE flight, A or B, and the solar cell data used in each solution.

Column 3 of Table III identifies the fused silica glass thickness applicable to each solution. Thirty and sixty mil thicknesses were considered: sixty, since our baseline designs to date were based on that thickness; thirty, since, relative to sixty, the EOL array power reduction in DE-B appears to be of the order of only one percent or less (Figure 10) while offering an overall weight reduction of approximately 26.8 pounds considering both DE spacecraft; Reference (6).

Column 4 identifies the Power Analysis Computer Program run number leading to the solution of the duty cycles given in Column 5. Computer runs for the 60 mil glass thickness solutions (No. 5 and 8) using the NOVA cell have not been made due to the small difference in the EOL side array power in DE-B as discussed in the preceding paragraph; specifically, in column 11, note that the increase is only 0.8 watts with 60 mils relative to the side power with 30 mils. The beginning-of-life (BOL) solutions (No. 7 and 10) have no practical significance other than to illustrate the increased amounts of array power available initially (Column 11). Note also that, given the BOL array power throughout lifetime (zero radiation damage), the 19% minimum duty cycle requirement in DE-B would be met. Computed Science On-Time Duty Cycle variation with life in orbit for solutions 6, 7, 9, and 10 is given in Figures 11-14.

DYNAMIC EXPLORER FLIGHT A




DAYS FROM LAUNCH

RUN 183E0L

DYNPLT FILE1

Fig. 11. DE-A Duty Cycle Variation, End-of-Life Array Throughout and 30-mil Coverglass
Reference: Table III, Solution 6

DYNAMIC EXPLORER FLIGHT A




DAYS FROM LAUNCH

RUN 184B01

DYNPLT FILE1

Fig. 12. DE-A Duty Cycle Variation, Beginning-of-Life Array Throughout
Reference: Table III, Solution 7

DYNAMIC EXPLORER FLIGHT B




DAYS FROM LAUNCH

RUN 185E01

DYNPLT FILE1

Figure 13. DE-B Duty Cycle Variation, End-of-Life Array Throughout and 30-mil Coverglass
Reference: Table III, Solution 9

DYNAMIC EXPLORER FLIGHT B



DAYS FROM LAUNCH

RUN 186B0L

DYNPLT FILE1

Figure 14. DE-B Duty Cycle Variation, Beginning-of-Life Array Throughout
Reference: Table III, Solution 10

Column 6 lists the total fluence in terms of the number of damage-equivalent 1-MeV electrons per sq. cm. for a thirteen-month life throughout (except where a BOL solution is identified) as applicable to solar cell current. (Reference (2)).

Columns 7 and 8 identify the portion of the solar array and the maximum steady-state solar cell temperature currently predicted for that portion.

Column 9, the solar cell current in milliamperes per cell, is based on the broken-line curves in Figure 6, except that the BOL cell current of the NOVA cell solutions is computed as in this part 5.1.4.2, eq-N (4), but using:

$$\begin{aligned} d_{ri} &= 1.0 \text{ (no radiation damage)} \\ F_i &= 1.0 \text{ (unirradiated cell)} \\ d_i &= 0.97 \text{ (UV damage only)} \\ i_{mp}(+25) &= 151 \text{ ma as per Reference (1)} \\ T &= \text{as in Column 8, this Table} \end{aligned}$$

Column 10 is self-explanatory. Column 11 is the maximum power at voltage V_s , Figure 3, computed for each portion of the array in each solution (sun vector normal to the spin axis for the side array, or normal to a flat-end array). In the NOVA cell solutions (No. 5 through 10), the computation is made as follows:

- (a) From Sec. 5.1.4.1, eq-N(2), the voltage level V_s is 36.3 volts
- (b) Assuming that the number of series cells is indeed 10% greater than that indicated in Figure 8 (refer to Part 5.4), then, in keeping with the assumption made in Part 3.2, there will be no loss of power due to shadowing. If so, the total maximum side array current is:

$$(\text{ma/cell, side, Column 9}) \cdot \frac{\text{No. of series strings, side, Col. 10}}{\pi}$$

For example, in solution 9, that would be

$$139.9 \cdot \frac{63}{\pi} = 2810 \text{ ma max. side array current}$$

Solution No.	DE Flight	2	3	4	5		6	7	8	9	10	11
					Min	Ave						
		Origin of Cell Data	Mils Glass	Run No.	Duty Cycle Percent		1-MeV c/cm ² Fluence (Current)	Array	Temp °C	Cell Current Ma/Cell	No. of Series Strings	Max. Power Watts
1	A	TIROS N	60	132	38	57.6		Side Ends	+13 +110	111.6 124.9	57 12	70.5 51.75
2	B	TIROS N	60	137	11	28.4		Side End	+67 +110	126 136	61 16	87.8 75.2
3	A	TIROS N + 12.5% Power	60	170	40	55.9		Side Ends	+13 +110		57 8	79.31 38.81
4	B	TIROS N + 12.5% Power	60	180	16	35.3		Side End	+67 +110		63 16	101.73 85
5	A	NOVA, this DN	60	None			9.5 x 10 ¹³	Side Ends	+13 +75	131.2 137.7	57 8	86.4 40
6	A	NOVA, this DN	30	183	40	62.3	2.7 x 10 ¹⁴	Side Ends	+13 +75	124.2 132.2	57 8	81.8 38.39
7	A	NOVA, this DN		184	51	79.3	BOL	Side Ends	+13 +75	145.36 151.08	57 8	95.74 43.87
8	B	NOVA, this DN	60	None			2.2 x 10 ¹³	Side End	+67 +110	141 145.1	63 16	102.64 84.27
9	B	NOVA, this DN	30	185	16	34.9	3.6 x 10 ¹³	Side End	+67 +110	139.9 144.1	63 16	101.84 83.69
10	B	NOVA, this DN		186	20	41.5	BOL	Side End	+67 +110	150.35 154.31	63 16	109.45 89.62

TABLE III. SUMMARY OF ARRAY DESIGN SOLUTIONS

Similarly, the total maximum end array current would be:

(ma/cell, Column 9) (No. of series strings, end, Column 10)

Once again using solution 9 as an example, the bottom ("end") array current is

$$144.1 \times 16 = 2310 \text{ ma maximum "end" current}$$

- (c) Therefore, the maximum power numbers tabulated in Column 11 for solution 9 are:

$$36.3 \text{ volts (2.81 amp.)} = 101.84 \text{ watts, side}$$

$$36.3 \text{ volts (2.31 amp.)} = 83.69 \text{ watts, "end"}$$

5.4 Series Cell Requirements and Protection Against Shadowing

Table IV summarizes the series cell requirements. Given the 2 x 2 cm cell size, it is seen that the series cells needed with the NOVA cell, including those additional series cells thought to be required to overcome the shadowing loss, are well within the numbers developed in Reference (8) using the TIROS N-vintage cell.

5.5 DE-B Side Array Preliminary Layout Considerations

For the present, we will limit the cell layout discussion to the DE-B side array as the most critical portion of the power-limited "B" array needed to provide an adequate Science On Time duty cycle. Discussion will be further limited to the 2 x 2 cm cell size, and only to those panels on the DE-B side array which have no cutouts which is assumed to be the case in the majority of those panels.

Given a "clean" side panel, up to 258 2 x 2 cm cells can be accommodated on such a panel allowing for six cells "lost" due to baseplate pickup holes.

From Table IV, it is seen that 99 cells in series are needed on the bottom hat portion of the DE-B side array where no shadowing is presumed to occur. A "clean" panel, therefore, can accommodate a single string of 99 two-cell modules plus one-half of an additional single-cell-module string:

$$2 \times 99 + 50 = 248 < 258 \text{ cells,}$$

with the other half of the single-cell string mounted on an adjacent panel. Given a 17% cell current loss in the "split" string (Appendix to this DN), the power increase of the side panel in question as compared to a straight 2 x 99 - cell layout (no "split" string) would be

$$\frac{2 + 0.5 (1-0.17)}{2} = 1.21, \text{ or } 21 \text{ percent}$$

On the side panels of the top "hat" where shadowing occurs, 109 series cells are required. With the 258-cell maximum limitation, the split-string approach is not possible,

$$2 \times 109 + 55 = 273 > 258 \text{ cells,}$$

unless the string "size" is reduced from 109 to 103 cells:

$$2 \times 103 + 52 = 258 \text{ cells}$$

Such a reduction can be implemented if the temperature of the DE-B side cells on the top "hat" can be reduced from +67 to +58°C maximum (as determined by proper reference to Figure 4), in which case a 21% power gain can also be obtained from the top hat portion of this side array.

TABLE IV. DE SERIES CELL REQUIREMENTS

DE Flight	Number of Series Cells								Remarks
	Side Array				Flat-End Array			(3)	
	Need		If No Shadows (1)		+10% (2)				
	If No Shadows (1)	10% (2)							
A	78	86	86	112	123	156	Bottom "Hat" Top "Hat"		
B	99	(4)	121	132	145	156			
B	99	109	121	-	-	-			

NOTES: (1) Figure 8, with 30-mil glass.
(2) To get rid of all shadowing loss, Part 3.2.
(3) References (5) and (8), 2 x 2 cm cells (series cells proposed, TIROS N cell data).
(4) "+10%" not required; Part 3.3.

6.0 REFERENCES

1. NOVA Solar Cell Specification, RCA 2285464, Dash One, Rev. Ltr. E.
2. Figure 5, DE Radiation Environment Analysis, G. Brucker/R. Ohanian, Rev. A, DE File 2.4.4-003-DN.
3. Letter, Dieter K. Zemmrich (OCLI) to R. Devaux, RCA, June 21, 1978, with enclosures:
 - (a) Quality Assurance Engineering Report 010, June 14, 1978, OCLI High-Efficiency Solar Cell. (Includes temperature coefficient and NRL electron irradiation data).
 - (b) Irradiation data, dated March 31, 1978, performed at Hughes A/C with OCLI Solar Simulator, as implied in referenced letter. OCLI High Efficiency Cells with fluences corrected for bare-cell exposure.
4. Solar Cell Radiation Handbook, JPL Publication 77-56, November 1, 1977.
5. RCA Proposal No. 102658-C, June 30, 1978, Dynamics Explorer (DE)-A and -B Spacecraft, Part 2, Book 1, Section 3.2.
6. R. G. Horner, Preliminary Tradeoff of 60 mil vs. 30 mil Solar Cell Covers, September 5, 1978, DE File 3.4.7.2-006.
7. DE Power Analysis Computer Programs, DE File Numbers 2.4.2-005 and 2.4.2-007-DN.
8. W. Fuldner, Considerations Affecting the Implementation of Solar Cell Bypass Diodes and Resulting Solar Array Output Noise, May 15, 1978, DE File 2.3.3-023-DN.

APPENDIX

Amount of Power Lost if Elements of a
String of Series-Connected Solar Cells
Are Placed on Adjacent Panels of a
n-Sided Configuration.

APPENDIX

Major assumption is that the instantaneous magnitude of the string current of a "split" string is limited to the magnitude of the maximum-power-point current generated by the cell which is subject to the lowest solar incidence angle (furthest off normal incidence). Thus, with the sun vector location as shown in the attached sketch, the current of the series string split between the adjacent sides "a" and "b" (the dotted line) would equal essentially that of the cells on side "b". An added assumption is that the maximum-power-point current of an off-normally illuminated solar cell obeys the cosine law.

Referring to the attached sketches, let the sun vector be placed along the -90° position in the sketch at the top of the page, and let the spacecraft be rotated clockwise as shown. Over each 2π rotation of the angle α , each independent string located on sides "a" and "b" would generate instantaneous power proportional to the cosinusoids shown at the bottom of the page. The split string, however, would produce power proportional to the shaded area, that is, area shared by both cosinusoids. Fraction of power generated by a split string as compared to a normal string (whose cells are all in one plane) is therefore given by

$$\int_{-90 + \frac{360}{2n}}^{\frac{360}{2n}} \cos\left(\alpha - \frac{360}{n}\right) d\alpha + \int_{\frac{360}{2n}}^{+90} \cos \alpha d\alpha$$

Fraction =


$$\int_{-90}^{+90} \cos \alpha d\alpha$$

$$= 1 - \sin \frac{180^\circ}{n}$$

or, for a 18-sided configuration such as DE ($n = 18$),


$$\text{Fraction} = 0.8264,$$

which represents about a 17% loss in a "split" string relative to a "normal" one.




C-5

ORIGINAL PAGE IS
OF POOR QUALITY



Design Note



Letter	Description	Date	Author
			Standard Distribution: R. deBastos D. Shipley G. Hogan W. Hord C. Hume

AE 1338 2 1/74

The shadowing analysis reported in this note has been performed as a possible aid in the on-going solar cell layout effort on DE Spacecraft. In particular, a significant portion of the layout work will consist of identifying those selected locations on the solar arrays where the bypass diodes are required to protect against shadowing losses.

Shadowing loss is most severe in the umbra region, that is, where complete shadow of an opaque body such as a boom results in a complete cutoff of light. In the partial shadow region of penumbra where the source of light is only partially cut off, the loss of solar cell power is not as severe. Given an opaque body of a fixed size, its distance from the cells is the critical parameter which determines the umbra configuration.


Results are provided in the attached plot. It is seen, for instance, that the 0.166-inch-dia. tip of the 22-inch long LANG boom will not produce an umbra in DE-B (the 0.182-inch-dia. base of the boom, however, will cast a complete shadow of up to approximately 10 to 20% of a 2x2 cm solar cell's area). Similarly, the attached plot shows that any opaque elements mounted on the stub boom at the end of the 5.9-meter long Astromast will not produce an umbra in DE-A unless the dimensions of the opaque parts exceed about two inches.

Details of the supporting analysis follow.

inches
meters
300
250
200
150
100
50
0

Beam-to-Cell Distance (L)

Effect of Beam Distance "L" from a 2x2 cm
Solar Cell on Size of Umbra Falling on the Cell
(Size of Umbra expressed as a fraction of cell's dimension)



Supporting Analysis

SYMBOLS: L distance to which umbra extends
 ℓ distance from opaque object to solar cell
 S solar cell dimension, e.g., 2 cm as in 2 x 2 cm cell
 p fraction of solar cell dimension "S" covered by umbra
 d dimension of opaque body, e.g., boom diameter
 α angle subtended by solar disc
 (0.5331° at mean distance to sun)

By reference to the attached sketch, basic relationships (1) and (2) are written. Substituting for " α " into (1) and solving for "L",

$$L = 107.47583 d \quad (3)$$


From eq-n (2),

$$\ell = L \left(1 - \frac{sp}{d} \right) \quad (4)$$




Substituting for "S" of a 2 x 2 cm cell and for "L" from eq-n (3) into eq-n(4),

$$\ell = 107.47583 \left(d - \frac{p}{1.27} \right) \text{ inches} \quad (5)$$

Equation (5) is plotted in the attached figure for p=0 (no umbra), 0.1, 0.25, 0.5, and 1.0.



boom, dia. "d" solar cell, dimension "s"



$$\frac{d}{2L} = \tan \frac{\alpha}{2} \quad (1)$$

$$\frac{d}{sp} = \frac{L}{L-l} \quad (2)$$

**6.0 COMMUNICATIONS SUBSYSTEM
DESIGN NOTES**

TABLE OF CONTENTS

Design Note

Title

3.5.2-004-DN	Antenna Test Plan
3.5.2-005-DN	Antenna Coverage During DE-A Spin-Precession Maneuver

Design Note



Originating Project or Group
Dynamics Explorer

Note No. 3.5.2-004-DN

Title

Antenna Test Plan

Written by: D. McGiffney

Date _____

Approved by:

D. Shipley

Date _____

This DN supplements (S), replaces (R) DN Nos.

REVISIONS

Letter	Description	Date	Author
			Distribution: H. Curtis R. deBastos W. Fuldner G. Hogan W. Hord C. Hume H. Rickert D. Shipley

Distribution:
H. Curtis
R. deBastos
W. Fuldner
G. Hogan
W. Hord
C. Hume
H. Rickert
D. Shipley

Testing of the brass-board and protoflight models of the three DE antennas will be as described below. The attached table summarizes the sequence of tests.

I. Brass-board Model Tests

Brass-board models of each of the DE antennas will undergo bench tests and pattern measurements at the AE antenna range. After these tests, the brass-board antennas will be shipped to GSFC where they will be mounted on an RF mock-up of the DE spacecraft. The mock-up will be able to simulate both DE-A and DE-B. Pattern measurements will be made to determine the effect of the spacecraft body and appendages on antenna performance. After the mock-up tests the brass-board antennas can be returned to AE if needed.

II. Protoflight Tests

The protoflight antennas will undergo bench tests and pattern measurements at the AE antenna range. These tests will verify that the protoflight antennas are within specification and that there is good correspondence between the protoflight and brass-board performance. Afterwards, the protoflight units will be shipped to GSFC for tests with the RF mock-up. The protoflight antennas then will be returned to AE for the remainder of the component level test cycle. Also, the RF mock-up will be sent to AE for use in calibrating the integration area antenna range.

At AE the protoflight units will undergo thermal tests to verify VSWR performance over temperature, and then will be subjected to vibration. Afterwards, the antennas will undergo bench tests and abbreviated pattern measurements to verify that their performance has not been altered by the environmental exposure. The final component level test will be an RF breakdown test, which will check for ionization breakdown at critical pressure and multipactor breakdown in hard vacuum.

After the component level tests, the protoflight antennas will be integrated onto their respective spacecraft and tested at the integration area antenna range. These tests will consist of EIRP measurements (transmitters ON) at a few selected angular coordinates, and partial patterns of the high gain antenna beam. The purpose of these tests is to provide a data reference for the post-environmental spacecraft level tests and to establish the validity of the RF mock-up tests. After this pre-environmental test, the spacecraft will be subjected to the required environmental exposures, and the pre-environmental tests will be repeated to verify that the exposures did not alter spacecraft performance. After the post-environmental test, each antenna will be removed from its spacecraft and undergo a bench test to verify that its VSWR is still within specification.

When the antennas are re-integrated onto the spacecraft, a go/no-go check of EIRP will be performed using a near-field coupler ("sniffer") or equivalent. This test will verify that the antenna has been correctly installed and is still functioning properly.

DE ANTENNA TEST PLAN

SPECIFICATION DESCRIPTION	PARA. NO.	BRASS-BOARD				PEPORE INTEGRATION								TESTED FROM S/C		ALL-TEST ON S/C
		BLNCH TEST	AT AE PATTERN MEAS.	AT GSPC ON PEPORE-UP PATTERN MEAS.	PATTERN MEAS.	AT GSPC ON PEPORE-UP PATTERN MEAS.	THERMAL TEST	VIBRA- TION(1)	POST ENV. BLNCH TEST	ABREV. PATTERN MEAS.	RF BALANCE DOWN TEST(2)	INTEGRATED ON S/C			POST- ENV. BLNCH TEST	DE/NO GO TEST (4)
												ANTENNA RANGE TEST PRE- ENV. (3)	S/C ENV. TESTS	ANTENNA RANGE TEST POST ENV. (3)		
INPUT POWER	3.1.1.1.1	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL
GAIN	3.1.1.1.2	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL
AXIAL RATIO	3.1.1.1.3	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL
RF POWER HANDLING	3.1.1.1.4	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL
SWR	3.1.1.1.5	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL	REL

R - DE-A MEDIUM GAIN ANTENNA
L - DE-B LOW GAIN ANTENNA
B - DE-C HIGH GAIN ANTENNA

- (1) TESTED ON PICTURE WHICH SIMULATES SPACECRAFT MOUNT.
- (2) TESTED IN 10" BELL JAR AT 25°C. CRITICAL PRESSURE AND 10⁻⁵ TORR.
- (3) PATTERN PATTERNS AND SELECTED POINTS MEASURED TO VERIFY VALIDITY OF RF POWER-UP TESTS AND TO VERIFY THAT ENV. TESTS DID NOT CHANGE PATTERNS.
- (4) TESTED WITH NEAR FIELD ANTENNA COUPLER OR EQUIVALENT.

ORIGINAL PAGE IS
OF POOR QUALITY

Design Note



Astro Electronics

Originating Project or Group Dynamic Explorer	Note No. 3.5.2-005-DN
Title Antenna Coverage During DE-A Spin Precession Maneuver	
Written by D. McGiffney <i>D. McGiffney</i>	Date 28 Sept 78
Approved by: W. Fuldner <i>W. Fuldner</i>	Date 28 Sept 78
This DN supplements (S), replaces (R) DN Nos.	

Letter	Description	Date	Author
			Distribution: H. Curtis R. deBastos W. Fuldner G. Hogan W. Hord C. Hume D. McGiffney

H. Curtis
R. deBastos
W. Fuldner
G. Hogan
W. Hord
C. Hume
D. McGiffney
H. Rickert
D. Shipley

The DE-A spacecraft will be injected into its final orbit while spinning at 70 rpm with its spin axis lying in the orbital plane. The spin axis then will be precessed until it reaches the desired orientation, i.e., normal to the orbital plane. Afterwards the spin rate will be decreased and the medium gain antenna will be deployed. Before deployment the antenna will not be able to provide reliable coverage and therefore some other means must be found to provide ground station contact when the antenna is in the stowed position.

A possible solution to the problem would consist of mounting two antennas with hemispheric coverage patterns on opposite ends of the spacecraft, as shown in Figure 1. The antennas would be circularly polarized, with opposite sense. A power splitter and RF switch are also required. After the final spin axis orientation is attained and the medium gain antenna is erected, the switch position would be reversed. The presence of a switch between the antenna and the command receiver raises a serious reliability question, since a switch failure could result in the inability to command the spacecraft. However, this point will not be discussed further, other than to point out that the switch would need to be operated only once during the mission.

The antennas would be of quadrifilar construction with a pattern as shown in Figure 2, based on measured data. While operating with these antennas it would be necessary for the ground station to switch its polarization sense twice each orbit, i.e., when the X-Y plane of the satellite passes through the ground station.

Taking into account blockage and reflection due to the top and bottom surfaces of the spacecraft, undesired coupling from the opposite sense antenna, and assuming a 26-meter ground station, the resulting antenna performance would be adequate for commanding and ranging throughout the orbit. The HEW data channel, however, could not be supported over the entire orbit. Figure 3 shows the portion of the orbit during which adequate HEW margin would be obtained with the ranging channel off. Between 31% and 72% of the orbit period would be serviceable, depending on the precession angle. Note that the link performance would be better at the beginning of the precession maneuver than at the end.

Figure 3 was derived assuming that the HEW channel modulation index is 0.3 radian per the current baseline. However the index could be changed to 1.4 radians by command (this index is normally used with the real-time data channel). The higher index would provide adequate HEW margin throughout the entire orbit, for any precession angle. During ranging, however, it would be necessary either to turn off the HEW modulation or switch back to the low index.






FIGURE 3 - DE-A WITH HEMISPHERIC COVERAGE ANTENNAS

FIGURE 2 - QUADRIFILAR ANTENNA PATTERN





**7.0 PLASMA WAVE INSTRUMENT INTERFACE
DEFINITION DESIGN NOTES**

TABLE OF CONTENTS

Design Note

Title

4.5.3-034 PWI Testing and Calibration



Astro Electronics Division

Originating Project or Group Dynamics Explorer	File # 4.5.3-034
Title PWI Testing and Calibration	
Written by: Paul S. Updegrave	Date 28 Aug 78
Approved by: W. V. Fuldner	Date 28 Aug 78

REVISIONS

Letter	Description	Date	Author

V. TESTING AND CALIBRATION

Instruments similar to the PWI Instrument previously described have historically required more spacecraft testing and calibration than most other types of instruments. The following section will attempt to describe the Why's and the How's of that testing and calibration, the equipment used, the support required, and those requirements which conflict or differ with those of the Dynamics Explorer Test Plan for Evaluation and Certification of Instruments (TEC).

1.0 SENSOR STIMULATION AND SPACECRAFT CONNECTIONS

The PWI AGE requires sync signals from the spacecraft for proper operation. These signals will preferably be hardline from the Spacecraft Umbilical. A less desirable method would be to buffer them in the experiment and feed them through the experiment test connector. This latter method requires access to the experiment test connector for all tests requiring AGE stimulation. Assuming the signals are available at the spacecraft umbilical, the only connections between the AGE and the spacecraft will be via the sensor inputs as described below.

1.1 Electric Field Antennas

1.1.1 E_x

These sensors will be driven differentially via the RF test connector located on the antenna housing. This connector should be accessible on a fully configured (Solar Panels, Thermal Blankets, etc.) spacecraft.

1.1.2 E_z

These antennas should also have an accessible RF connector on each unit similar to E_x .

1.1.3 Short Electric Antenna

This antenna is driven differentially via cables that clip to each wire cage. No external shielding of the spheres appears to be necessary due to the low impedance provided by the 40 db attenuators to be described later.

1.2 Magnetic Field Sensors

Both the Loop and Search Coil require magnetic field stimulation and shielding from external interference (60 Hz etc.). To avoid these interference problems, the Loop and Search Coil are calibrated separately and the majority of the spacecraft and subsystem level testing will bypass these sensors themselves and instead will drive their respective differential amplifiers in the main electronics via the boom cabling. This connection is accomplished via a relay circuit that connects either the output of the sensor or the output of the 40 db attenuators to the differential amplifiers. A more detailed discussion of the 40 db attenuators and the sensor bypass relays follows.

1.3 40 db Attenuators

External programmable 40 db attenuators are required on all sensors to attenuate external noise pickup on the sensor stimulus lines at low level signal input. After the input signal level has increased sufficiently (≈ 10 mV) the attenuation is switched out and the input level decreased by 40 db by control pulses from the AGE stimulus unit. Teledyne magnetic latching relays are used to enable to attenuators to hold state after the power has been removed. Electrically the units appear as either a short from input to output or a 5K - 50 Ω resistive divider trimmed to give $40 \pm .2$ db attenuation. Attenuators for the E_x and E_z antenna inputs have an additional state which presents a high impedance (1 Meg - 220 pf) to the antenna input during testing of the internal calibration signal. Physically the units are built in aluminum boxes (5.5 x 2.8 x 3.3 cm), with the input and

output stamped into the lid as well as an identifying number. E_x and E_z units have an "S" following the identifying number.

Signal connections are made through Female BNC connectors and control connections through a UMI-5F connector on the side of each box. All units were built to thermal-vacuum specifications and all units to be used for DE project have been through Thermal Vacuum at least twice.

A 40 db attenuator is required on all ten stimulus lines and must be located as close as feasible to the sensor (6" - 12"). The attenuators are small and in the case of the E_x and E_z sensors will necessarily be separated. On previous spacecraft these were tied or taped close to the sensor. In the case of the 40 db attenuators for the boom mounted units, which may be mounted on a plate along with the Magnetic Sensors Bypass Relays described below, provision should be made for rigidly attaching the plate somewhere -- preferably to the boom. Details of this plate will be provided at a later date.

1.4 Magnetic Sensors Bypass Relay

These relays allow the experiment differential input to be driven from either the sensor output or the AGE stimulus output. Switching is done with latching relays, controlled by a manual switch to be located at the AGE equipment rack. The possibility of making the relay control automatically controllable from the AGE computer is under consideration.

Since both magnetic sensors are located on the boom, the Bypass Relays will be mounted on a plate with the 40 db attenuators, and will use the common return for the control ground. This technique cuts down the number

of lines required. Configuration of the plate is TBD.

Prior to any major testing the Bypass Relays adapter cable will be connected between the loop or search coil and their respective cables. A small harness will connect power and thermistor lines continuously, while the signal lines will be brought out to the relay box. The sensors are thus powered at all times during testing, and the experiment input can be switched from sensor drive to stimulus drive and back without shutdown of the experiment to configure the cables manually.

2.0 AGE DESCRIPTION FOR THE DE PWI (see enclosed Block Diagram)

The AGE for the PWI falls into two categories: experiment control for bench level testing and experiment stimulus for all levels of testing.

2.1 Bench Level Testing

The experiment control section will contain the equipment necessary to command and power the unit and display all digital parameters coming from the experiment. Analog multiplexing will allow any single analog channel to be displayed.


The design of this section is not expected to be fundamentally different from that of the ISEE-A/B or Voyager PWS systems, control being selectable for either manual operation or automatic. Automatic operation will be controlled by an HP-9830 calculator system.

2.2 Experiment Stimulus

The experiment stimulus will be adapted as much as possible from the existing ISEE equipment. Calibration and checkout of the PWI experiment requires the ability to drive an accurately known frequency in the range 1 Hz to 2.040 MHz at a known amplitude (+10 db to -120 db where 0 db = 1V rms), and the capability of producing a known phase difference between two antennas in the frequency range of 1 Hz to 400 kHz.

1. Added comments and designation no. 3/1/77

ORIGINAL PAGE IS
OF POOR QUALITY



DO NOT SCALE PRINT	DATE	10/10/77	UNIVERSITY OF ICMA
UNLESS OTHERWISE SPECIFIED, DIMENSIONS ARE IN INCHES WITH TOLERANCES ON FRACTIONS DECIMALS ANGLES .XX .01 2 0 15' 21/64 XXX 2.00R	DESIGNED BY	D. McAdams	DEPT OF PHYSICS & ASTRONOMY
MATERIAL	DATE	10/10/77	PROPOSED DE PWI-AGE for S/C Level Testing
FINISH	DATE	10/10/77	Block Diagram
USED ON	SCALE	83 C 1900	HEIGHT
CALLED FOR ON	SCALE	83 C 1900	HEIGHT

ALL COMMAND AND DATA HANDLING WILL BE DONE
BY THE DE COMPUTER SYSTEM (SIGMA 5).

UNLESS OTHERWISE SPECIFIED,

NOTE:

To meet the basic amplitude-frequency requirements, the ISEE GSE was developed. This system uses a programmable frequency synthesizer driving programmable attenuators which can be set at 1 db steps in the range of 0 to 110 db. The output of these attenuators is transformer isolated and fed differentially to any one or combination of 5 antennas. Common mode drive is also available by driving both inputs of an antenna from one side of the differential transformer winding.

To achieve lower noise levels, an outboard programmable 40 db attenuator is placed in each antenna line. Ideally these are placed as close to the antenna inputs as possible. To avoid loading the internal calibration signal the outboard attenuators can be switched to and open state where the Ω signal drive is disconnected and the antenna is switched to a high impedance load. On the magnetic antennas provision is being made to be able to either drive the differential amplifier directly or switch to the sensor to observe the calibration signal.

Since a single stimulus unit cannot provide the needed phase differences between antennas, two units will be used for phase calibration, one driven by the reference port and the other by the variable output port of a Wavetek Programmable Variphase generator. Since the stimulus unit outputs will be connected in parallel with no lockout, it is possible to connect both stimulus unit outputs to the same sensor. Assuring the antennas are driven separately will be the responsibility of the operator or the software.

The equipment for the AGE will be contained in two (2) movable racks each about 5 x 2 x 2 ft. During normal testing the racks must be close enough to the S/C to allow the coax signal harness and 40 db attenuator control harness to be properly connected (~ 10 ft.). During environmental testing enough bulkhead connections must be reserved to allow all of these lines into the chamber. Required are:

10 separate coax lines shields must be isolated

21 control harness lines

If feasible we may want to include an optional drive capability for the magnetic sensors. This would create the need for another two coax lines into the chamber and two more control lines.

All AGE hardware with the exception of the following off the shelf or previously purchased items

- a. HP9830 Programmable Calculator
- b. Exact Mod 602 Programmable Frequency Synthesizer
- c. Wavetek Mod 152 Programmable Variphase Generator

are fabricated by the University of Iowa.

2.3 Automated Testing

For on-spacecraft and qualification program testing we propose to use a system similar to that used for ISEE. In this system, a program in the DE computer system will configure the experiment via Major and Minor Mode Command and then send a stimulus command to the PWI AGE calculator. This stimulus command will call a preprogrammed test sequence in the calculator. While the sequence runs, the DE computer system will collect data from the experiment and print it out

along with AGE status information which will be fed back at the same time. When the calculator sequence is completed it will signal the DE computer which will go to the next step of its test sequence.

A minimum AGE interface requires the 1/sec, 64 wd and 128 wd pulses to be buffered and made available to the AGE. This would allow manual operation of the AGE as a stand alone system. Testing efficiency will be greatly increased, however, if the AGE calculator can be controlled directly from the Sigma 5 as described in the previous paragraph.

An 8-bit Transmit and separate 8-bit Receive buss is required as a minimum to implement the Stimulus Command and Feedback System. Data transfer will be simplified, however, if provision is made for additional lines from the AGE to the Sigma 5.

2.4 During the course of normal testing and for certain special testing, we will require access to the analog output of the telemetry receiver for wideband receiver testing. This output will be monitored with several pieces of portable equipment (spectrum analyzer, demodulator, etc.) and does not have to be available at the stimulus racks. Frequently during analog testing we will require a tape recording of the analog output, the recording requirements are TBD.

A separate portable piece of AGE will be developed to monitor the output of the WAVE receiver. This unit will contain a gain state decoder plus a demodulator for the mode when both the WBR and LWR share the analog transmitter.

3.0 TESTING

The following refers to the Dynamics Explorer Test Plan for Evaluation and Certification of Instruments (TEC).

3.1 EPET

An instrument such as the PWI that performs the number of functions (DC and AC electric field measurement to 400 kHz, and AC magnetic field measurement to 400 kHz, plus Phase determination, along with wideband information to 2 MHz, and Linear wideband measurement), with the number of sensors (3 Electric field, 2 Magnetic field), and the number of modes (Automatic or Manual selection of 1 to 5 antennas to 1 of 4 different subsystems in combination with Automatic or Manual selection of 136 different frequencies) cannot receive a complete electric performance evaluation test in one hour as suggested in the TEC document. A comparable experiment on the ISEE A spacecraft never received what could be considered a complete EPET during the six-hour periods allotted it.

We believe the PWI unit, however, can receive a thorough checkout in a 3-hour period assuming no hardware or software malfunctions and a fully automated test procedure. This requires PWI antenna and mode selection, Real time data display, and PWI AGE program call all under Sigma 5 Program Control. A feedback link from the PWI AGE to the Sigma 5 with the feedback information on both the real time display or on-line printout and subsequent off line printout is considered

essential. Absence of any of the above capabilities will significantly increase the required test time.

The instrument cannot be checked solely from the FWI test connector* as there is no provision for commanding through the test connector. In addition all the required Analog and Digital outputs are not available at the Test Connector and even assuming that they were, the AGE is incapable of displaying a full data frame and has no data storage capability. Much of our EPET procedure will utilize the fact that two or more sections of the instrument can be tested simultaneously assuming the entire data frame is being collected and displayed or stored for later printout.

APT -- An abbreviated performance test utilizing the calibration feature of the instrument could be done in ~ TBD.

3.2 Testing Sequence

We would prefer a testing sequence that differs somewhat from that in the TEC. Traditionally our instruments are temperature tested at Iowa and then taken to GSFC for EMI and Magnetics and perhaps preliminary weight checks. The instrument is then returned to Iowa for final conformal coat prior to vibration at Iowa. Following vibration, it is returned to GSFC for Thermal Vacuum. The rationale for this is that we do not have the facilities at Iowa for either EMI or Magnetic preliminary testing. This means we do not know until the tests at Goddard if we are out of spec. If rework is required, it is much simpler to do it on a unit with subsystems that are relatively accessible. Thermal vacuum testing does not present this problem as vacuum has

*Recent conversations with M. Lidston modify this statement somewhat. During unit level tests at GSFC the instrument can be tested when the simulator is disconnected as this is no different than a bench test configuration with possibly longer cables. The statement concerning data display and storage is still valid and the paragraph still holds for on-spacecraft testing.

little effect on the operation of the instrument and the unit will have been thoroughly temperature tested at this point.

Our preferable sequence would then be

Mechanical Interface	}	GSFC
EMI		
Magnetics		
Vibration	-	Iowa
Weight -	}	GSFC
Pyro Shock		
Acceleration		
Thermal Vacuum		

3.3 Further Comments

- A. The 3' x 3' chamber will not accommodate the loop antenna. A chamber of at least 4' x 4' or more will be required.
- B. A thermal balance test of the boom mounted units will be required.
- C. If an extendible type boom is to be used, some sort of stub boom for mounting the loop, search coil and short electric antenna must be developed. This unit must be designed to fold to meet the shroud profile and to orient the sensors in their proper position when deployed. If the decision is to fund the University to design and build this stub boom, some sort of deployment test will be required that most likely will have to be done at GSFC.

D. We believe that from both a cost and schedule standpoint the PWI vibration testing should be done at Iowa. A listing of the vibration facility's instrumentation follows. This facility was used for testing experiments for the Injun V, Hawkeye, IMP H, IMP I, IMP J, Helios, MJS, and ISEE programs.

U OF I PHYSICS DEPARTMENT
VIBRATION FACILITY

GENERAL DESCRIPTION:

The U of I facility provides for sine vibration testing as follows:

Frequency Control	- 5 - 2000 Hz
	- servo with constant displacement, velocity or acceleration.
Maximum displacement	- .8 in D.A.
Maximum Force	- approx. 2500 lb.
Maximum Acceleration	- 100 g
Table Weight	- 21 lb.

The random facility is as follows:

Frequency	- 20 - 2000 Hz
Equalization	- Manual, 45 channels
Analysis	- PSD with single channel sweeping analyzer (BW = 10 Hz and 50 Hz)
Display	- PSD on X-Y recorder

EQUIPMENT LISTING:

- 1 - B & K 1025 servo/sine oscillator
- 4 - U - D, D11 series charge accelerometer preamps
- 1 - U - D, MAC-6C multifunction averaging control
- 1 - S - D, SD101A analyzer/tracking filter
- 1 - Ballantine 320 RMS voltmeter
- 1 - HP 7562A Log voltmeter
- 1 - HP 7005B X-Y recorder
- 1 - U - D, E109 spectrum equalizer
- 1 - Krohn-Hite, 330M B.P. filter
- 1 - GR, 1390-B noise generator
- 1 - Ling, PP-7/8-C power amp, 7 KVA
- 1 - U - D, 203 AMA shaker

Manufacturer Abbreviations

B & K	-	Bruel & Kjaer
U - D	-	Unholtz - Dickie
S - D	-	Spectral Dynamics
H - P	-	Hewlett Packard
GR	-	General Radio

4.0 CALIBRATION

Calibration of the instrument is normally done during spacecraft Thermal Vacuum Testing due to the fact that only at that time are all the factors present that can affect the system end output. These are

- 1) loading of the sensor outputs by interconnecting harnesses,
- 2) temperature variations,
- 3) spacecraft generated interference,
- 4) analog to digital conversion quantization errors.

Calibration is a time consuming process and depending on the extent could require 24 hours or more at each temperature.

Other options with their associated drawbacks are being considered:

- A. Part of the calibration is done at one temperature soak and the remainder at ambient and the opposite temperature extreme.
- B. The calibration is done on the spacecraft but not necessarily during thermal vacuum. This would require a 24-30 hour period where PWI calibration had highest priority. In the case of 8-hour days only, 3-5 days. I would assume this would be in the evening.
- C. The calibration is done during subsystem Thermal Vacuum.
- D. Calibration is done at Iowa and only selected channels, levels, etc. to verify those previous calibrations or perhaps determine where loading occurs would be done during spacecraft thermal vacuum testing.

In addition to routine testing and calibration, certain one-time-only tests are required to insure proper operation, tolerable interference levels, etc. Following is a description of those tests.

PWI (Plasma Wave Investigation)

INSTRUMENT UNIQUE TESTS

The following is a description of the special one-time-only or infrequently run tests that we feel are necessary to insure tolerable interference levels and proper operation and understanding of the PWI instrument and related spacecraft systems. Similar tests have been carried out within the Injun, IMP, Hawkeye and ISEE programs. It is very likely that most of these tests can be phased in with the spacecraft integration and check-out.

1. EMI VERIFICATION TEST

This test is intended to locate radiated and/or conducted electrical interference from the spacecraft systems or other instruments that might not have been detected at the unit or spacecraft EMI test level. The test must be conducted in a shielded room. The capability of physically removing all 60 Hz input from the room either by removing fuses or throwing knife switches, etc. is important. We have found in the past that it is necessary to operate the spacecraft on external batteries to achieve the noise level required for meaningful testing. In its final version the test requires a fully configured and completely buttoned up spacecraft such as it would be for the spacecraft EMI test, but a modified test earlier in the program

(a preliminary conducted interference test could be run in the clean room or an open spacecraft) would point out problem areas. The standard procedure in this type of test is to power down to only essential spacecraft systems for a baseline and then sequentially turn on all instruments and spacecraft systems in their most noisy mode and look for an increase in the PWI instrument noise level. This test could be conducted in conjunction with the standard EMI tests.


2. SOLAR ARRAY NOISE MEASUREMENT

High level noise present on the solar array buss due to regulator switching and the inherent ripple as the panels come into sunlight could conceivably be coupled to the PWI antennas. Since this noise, especially in the case of the regulator, is a function of the illuminated array impedance which is difficult to simulate, the only accurate means of knowing it is to measure the noise on the solar array buss of a fully configured spacecraft spinning in sunlight. We would do so by capacitively coupling the buss to one of the electric preamps using the PWI instrument then as a spectrum analyzer. If a spinning test is impossible we would at least want to run the test on a stationary illuminated spacecraft.

3. SETTING OF MODULATION INDEX

The purpose of this test is to accurately adjust the wideband output peak-to-peak signal level to obtain maximum deviation of the carrier without distortion as determined by observing the real time

demodulated signal after it has passed through the entire system as shown below.



Our PWI instrument will be constructed to make the gain adjustment easily available through an access hole on the main electronics box front plate. When this adjustment was made on previous experiments the spacecraft was located in building 22 and the demodulator at the output of the STADAN receiver at NTF so it will require a certain amount of coordination such as communication between the two areas, etc. The test does not require a fully configured spacecraft but only those systems essential for wideband transmission.

4. LOW FREQUENCY MAGNETIC EMI

The purpose of this test is to locate any magnetic field interference generated by spacecraft subsystems or other experiments. This test can only be done at the Magnetic Test Facility and requires all AC power in the area be shut down. This power restriction also applies to the S/C power and any support equipment. This requirement can be met by powering the S/C from internal or external batteries and transmitting the data to a suitable receiver tied into the EE data handling system. The test requires a fully configured spacecraft. The

standard procedure is to power down to only essential spacecraft systems to obtain a baseline and then sequentially turn on all instruments and spacecraft systems in their most noisy mode and look for an increase in the baseline readings from the FWI instrument print out.

5. FWI PHASE/AMPLITUDE CALIBRATION

This test is required to determine the phase differences, as a function of frequency and amplitude, between each pair of antennas -- loop, search coils and electric dipoles. Measurements are made from the antennas through the data handling system. The spacecraft must be in a magnetically quiet area such as the Magnetic Test Site. The test does not require a fully configured spacecraft but only the FWI experiment and associated spacecraft data handling systems -- transmitter, receiver and Sigma 5 computer. The power needed will most likely require the use of automobile storage batteries. The batteries should be fused and placed in battery boxes in such a way that it is impossible to short them out. The University can supply these batteries but with the shipping etc. required it would be more economical if they were supplied by GSFC. All electrical power in the area must be off or DC operated including spacecraft support equipment as in the low frequency EMI Test (#4). A battery powered signal generator will drive all of the antennas and the phase variations between antenna pairs as a function of frequency and amplitude will be read out from the FWI Instrument data output.

6. COMPRESSOR TIME CONSTANT CALIBRATION

- A. Purpose--To calibrate the phase shift of signals through the compressors (for radio source direction finding corrections).
- B. Location and Configuration--The Clean Room environment will be sufficient for this test as the Magnetic Sensors will be bypassed. The test does not require a fully configured spacecraft but only the essential subsystems: data handling, power, etc.
- C. Special Equipment Needed--Will be furnished by Iowa.
- D. Special Timing Signals Needed--We will require a Nadir pulse to our AGE and to the S/C to simulate optical aspect data (this pulse must be at $\approx$ the S/C spin rate but not an exact multiple of any telemetry clock rate).
- E. Procedure--The input signal to the experiment will be AM modulated by a sine wave derived from the sun pulse and uniquely correlated to it (say the signal minimum occurs at sector 0). Plotting the compressor output against sector will then give the phase shift of the compressors. This test should require $\approx$ 4 hr. exclusive of setup and check out.
- F. Frequency--The test should be run 2 separate times for comparison and accuracy check. The test will take $\approx$ 4 hours.

Dr. Helliwell's group at Stanford may also require special testing for the LWR but such test requirements will be supplied and supported by them and do not appear in this document.