General Disclaimer

One or more of the Following Statements may affect this Document

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.

- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.

- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.

- This document is paginated as submitted by the original source.

- Portions of this document are not fully legible due to the historical nature of some of the material. However, it is the best reproduction available from the original submission.

Produced by the NASA Center for Aerospace Information (CASI)

Temp #83-417338

SSD 83-0094-2

DEVELOPMENT OF DEPLOYABLE STRUCTURES FOR LARGE SPACE PLATFORM SYSTEMS

Design Development Volume II

### NASA/MSFC CONTRACT NAS8-34677
OCTOBER 1983

Shuttle Integration & Satellite Systems Division

Rockwell International

Development of Deployable Structures for Large Space Platforms

Design Development
Volume II

Submitted by

H.S. GREENBERG
Study Manager

Approved

E.E. ENGLER
Study Cor, NASA / MSFC

Prepared for:

National Aeronautics and Space Administration
George C. Marshall Space Flight Center

Marshall Space Flight Center
Alabama 35812

Rockwell International

FOREWORD

Thi.s volume describes the major achievements of Parts 1 and 2 of the study titled "Development of Deployable Structures for Large Space Platform Systems." An executive summary of the Part 1 and 2 study is presented in Volume I, SSD 83-0094-1. An appendix containing the developed design drawings and supporting stress analysis is contained in Volume III, SSD 83-0094-3.

This study was managed by Marshall Space Flight Center (MSFC) and was performed by the Shuttle Integration and Satellite Systems Division personnel of Rockwell International Corporation located at Downey and Seal Beach, California. The study COR was Mr. Erich E. Engler. The study manager was Mr. H. Stanley Greenberg.

The Part 1 study was initiated on October 16, 1981 and was completed nine months later on July 16, 1982. The Part 2 study was started August 6, 1982 and was completed fourteen months later on October 7, 1983.

The major contributors to this study are listed below:

o Design - R. Hart (Lead, Part 1)
            R. Barbour (Lead, Part 2)
            B. Mahr
            A. Perry
            J. Keech
            W. Wiley
            C. Lang
            G. Buhler
            P. Buck
            T. Clegg

o Stress Analysis - G. Lesieutre
                     W. Bateman

o Thermal Analysis - T. Tysor

o Materials Analysis - R. Long
                        C. Brownfield

o Mass Properties - C. Griesinger
                     W. Morgan

o Electrical Power/Date Management - A. Gordon

o Electrical Utilities Integration - A. LeFever

o Guidance and Control - R. Olgevie

o Technology Development - A. M. Pope

CONTENTS

PRECEDING PAGE BLANK NOT FILMED

ILLUSTRATIONS

TABLES

INTRODUCTION

This volume describes the major achievements of the Parts 1 and 2 study activities related to deployable structures for large space platforms. These activities included development of a building-block design for the automatic construction of deployable platforms such as those shown in Figure 1, and the development of deployable volumes for manned modules and OTV hangars identified for potential Space Station configurations.

Since the recent accomplishments of Part 2 are of greater interest to the large space structures community the Part 2 study accomplishments are presented first.

The preponderance of the study effort was devoted toward the deployable platform systems study which has culminated (Part 2) in a "fabrication ready" detailed design of a ground test article for future development testing. This design is representative of a prototype square-truss, single-fold building-block design that can construct deployable platform structures in the manner suggested in Figure 2.

This prototype design was selected (Part 1) through a comprehensive and traceable selection process applied to eight competitive designs. The selection process compared the competitive designs according to seven major selection criteria, i.e., design versatility, cost, thermal stability, meteoroid impact susceptibility, reliability, performance predictability, and orbiter integration suitability.

In support of the foregoing, a materials data base, and the development needs for platform systems technology were established (Part 1).

In the deployable volumes study an erectable design of an OTV hangar was selected (Part 2) and recommended for further design development. This design was selected from five study-developed competitive single and double-fold designs including hard-shell and inflatable designs. Also, two deployable manned module configurations, i.e., a hard-shell and an inflatable design were each developed (Part 2) to the same requirements as the composite of two Space Station baseline manned modules. For each of these deployable module designs, atmospheric sealing suitability was of sufficient concern to offset the potential launch cost savings. Hence, no further activity was recommended pertinent to deployable manned modules.

Figure 1.   Focus Mission Platform Systems Configurations

Figure 2.   Potential Construction Application of Building Block

2

1. DEPLOYABLE PLATFORM SYSTEMS

1.1 DESIGN EVOLUTION

1.1.1 Part 1 Selected Design

The Part 2 study activities were directed toward the establishment of a detailed design of a ground test article that is representative of the Part 1 selected design (Figure 1.1-1).

At this stage of development the deployment mec': anism was not defined but visualized to be a reciprocating design requiring guide rails to maintain root strength during deployment. The potential problems of such a design were recognized during the Part 1 study efforts toward constructing and deploying the generic platforms with each of the competitive building block concepts.

The potential problem associated with the use of guide rails arises during extension of a truss which has a payload or module sufficiently wide that the guide rails cannot straddle the module (Figure 1.1-2) and, therefore, cannot be unfolded until the truss has extended and moved the large payload out of the way. Obviously, if the guide rails are not in position when the truss/payload is moving, there is no root strength developed. While several solutions to minimize this problem were established during the Part 1 study, the mechanism design estab'.shed in Part 2 was developed to completely avoid this problem.

1.1.2 NASA/MSFC Requirements

The design development was also directed to satisfy the NASA/MSFC requirements derived from the McDonnell Douglas SASP study (Reference 1). The test article configuration was to proximate the SASP deployable structure configuration shown in Figure 1.1-3. Further, the following additional requirements were stipulated by NASA/MSFC.

o Provide automatic retraction in addition to deployment

o Use 1.4 m x 1.4 m truss cross section

o Provide mounting for two 3636 kg simulated payload carriers at each of 2 stations each having an attachment bolt pattern of 1.09 m x 1.31 m (43 x 51.5 in.)

o Provide a design with a minimum natural frequency of 0.10 Hz

o Provide a design that can sustain a 0.04 g load factor applied at the c.g. of one payload at each station.

o Provide trays in two bays to accommodate four No. 1/0 cables, two No. 8 AWG, four No. 12 AWG, twenty No. 22 twisted pairs shielded, and four each coax lines.

- ALL MEMBERS ARE ROUND TUBES
- LONGERONS WITH CENTER HINGE JOINTS
- TELESCOPING DIAGONALS
- NO OFFSET LOADS AT JOINT
- BATTENS CROSS BRACED BY TENSION STRAPS

MAIN HOUSING

TRUSS

ADAPTER

DEPLOYMENT RAILS

LONGERONS

UTILITY TRAY

END VIEW FOLDED

DETAIL OF JOINT

UTILITIES INSTALLATION

Figure 1.1-1. Selected Design

P/L

HOUSING

RAILS
STOWED

RAILS IN
POSITION

Figure 1.1-2. Deployment Problem with Guide Rails

Figure 1.1-3. SASP Deployable Ground Test Structure

The requirement to mount the 3636 kg (8000 lb) simulated payload carriers at two stations was satisfied by using the housing as one of the bases with the deployable truss providing the second base. This solution is cheaper than placing both bases on the deployable truss and represents the reality of potential platform systems, wherein payloads or major subsystems will be mounted onto the housing. With the payload carriers placed as described, the test article was then designed to be supported, during ground testing, by an end adapter at the end opposite the main housing.

1.1.3 Major Goals and Design Philosophy

The major goals and design philosophy to be used in the development of the test article were agreed upon between NASA/MSFC and Rockwell. The major goal and design philosophy are as follows:

Major Goal: To design the structure and mechanism to support demonstration of the suitability of the prototype building-block design to automatically deploy and retract, to have predictable dynamic behavior, and lastly to sustain specified limit loads.

Design Philosophy: Minimum test article cost with minimal to no compromise of the major goals delineated above.

Major Design Implications:

o Members of the truss and joints are aluminum and steel (composite designs to be developed later).

o Test article will be a representative design, but not an optimum design.

o Near minimum weight approach to structural design only when sensitive to structural performance otnerwise cost governs.

o Design for NASA/MSFC test facility environment i.e., no provision for in-space environmental requirements on lubricants, materials, or positioning equipment.

o Positioning system components are not designed for orbiter launch survival

o Trays to be provided for future utilities integration and to accommodate electrical lines with standard insulation and fluid bellows (uninsulated).

The foregoing directed the test article configuration and detailed design to that described herein and by the top assembly and detailed design drawings contained in the appendix of Volume III.

1.2 SUMMARY OF TEST ARTICLE DESIGN

A summary of the test article design is provided herein. The test article design is described in further detail in Section 1.3 and by the set of drawings and supportive structural analysis in the appendix of Volume III. Figure 1.2-1 illustrates the test article configuration. The major components of this test article are as follows:

1. The square truss (Figure 1.2-2) containing folding utilities trays in Bays 4 and 5 with provisions for future installation of power, data, and fluid lines.

2. A mechanization system (Figure 1.2-3) consisting of (a) a batten deployment/retraction jackscrew system which translates the battens one at a time, (b) a diagonal latch unlocking system, and (c) a longeron latch unlocking system.

3. A jackscrew support frame assembly that supports the cantilevered ends of the batten deployment/retraction jackscrews (Figure 1.2-3).

4. A positioning system to precisely control the bay-by-bay deployment and retraction operations (Figure 1.2-6).

5. A precompression system to eliminate structure joint backlash (Figure 1.2-8).

6. An end adapter at the end of the truss with provisions for attachment to a NASA/MSFC test fixture (Figure 1.2-1).

7. An aluminum skin and frame main housing (Figure 1.2-9). The housing and payload carrier frames shown contain inserts for attachment of the NASA/MSFC simulated payload carriers.

A brief summary of the overall design is presented to enhance an understanding of the individual components detailed designs.

Figure 1.2-2 illustrates the deployable truss major design features. The deployable truss contains square battens stabilized by compression diagonal braces. Each batten contains a half-nut at each of the four corners. Through engagement with each of the four batten deployment/retraction jackscrews, counterclockwise rotation of the jackscrews imparts outward linear motion to the batten (deployment), while the opposite rotation imparts inward motion to the batten (retraction). With the exception of the first bay, deployment or retraction is respectively accomplished by holding the aft batten with detents while deploying or retracting the forward batten. During deployment, each of the four longerons is unfolded and each of the four telescoping diagonals is extended. The longerons and diagonals each have spring-activated locking pins in latches at their center joints that, upon unlocking, provide axial and moment structural continuity. Both designs have end rod fittings with spherical bearings and turnbuckles for precise member length adjustment. The aforementioned spring-activated pins in the center joints must be unlocked to permit retraction. This is accomplished with each of the diagonal and longeron unlocking systems (Figure 1.2-4) that contain tripping devices that rotate exterior cammed surfaces on the latch mechanisms to depress the locking pins.

Figure 1.2-1. Test Article Design Configuration

Figure 1.2-2. Deployable Truss and Utilities Trays Concept

The truss design also contains trays for Bays 4 and 5 onto which a generous complement of electrical power, data, and fluid lines can be mounted. Specifically, space is available for six No. 1/0 cables, three No. 8 AWG, six No. 12 AWG, six coax, twenty-eight No. 22 twisted pairs shielded, and four 12.5 mm flexible coolant tubes. The trays are hinged from the batten frames and fold as shown at the lower right (Figure 1.2-2). During the Shuttle launch of a prototype design the trays would provide lateral support to the folded longerons. Longitudinal support of the lorgerons is provided by tight packaging and appropriate end transverse beams in the adapter and main housing.

Figure 1.2-3 illustrates (in the deployed configuration) the major features and orientation of the test article mechanization system. For clarity, the ten-bay truss structure is not shown. This system provides fully controlled bay-by-bay deployment/retraction capability with maintenance of root strength throughout all phases of deployment. The mechanisms include the batten deployment/retraction jackscrew system, the longeron unlocking system, and the diagonal unlocking system. The batten deployment/retraction system (Figure 1.2-4) consists of four asemblies of guide rail, splined shaft, and jackscrew mounted in a slide carriage. These assemblies are located at each of the four corners of the main housing. In the first stage of deployment, i.e., Bay 1, clockwise rotation of each of the spline shafts advances the slide carriage and jackscrews out of the housing into the configuration shown. Concurrently, the jackscrew support frame assembly is advanced to the configuration shown with the automatic locking of the telescoping diagonals. A controller-driven single motor, slaved to a chain and sprocket system, drives all four assemblies. The longeron unlocking system (Figure 1.2-4) consists of four assemblies of guide rail, jackscrew, carriage, and tripping device. These systems are located adjacent to the individual batten deployment/retraction assemblies. Each of the four diagonal unlocking assemblies are the same as that of each longeron unlocking system, except for the tripping devices, and are each located at the center of the housing sidewalls. The longeron and diagonal unlocking assemblies are each controller-driven by a single motor slaved to a chain and sprocket system to drive all four assemblies.

Figure 1.2-4 further describes the deployment/retraction mechanism. The batten deployment/retraction jackscrew shown illustrates one of the four jackscrew assemblies. The jackscrew, carriage, and spline assemblies are cradled within a rigid rail. A splined bushing at the aft end of the 50.8-mm-diameter jackscrew encircles a splined shaft that extends nearly the entire length of the jackscrews. The jackscrew splines extend beyond the aft end of the rails where a chain and sprocket are attached.

Encircling the rotating jackscrew is a carriage fitting that has external ea⁻s that engage matching grooves running the length of the rails. The carriage is pulled forward with the jackscrew, during deployment of Bay 1 (Figure 1.2-3), until a hole in the side of the carriage is engaged by a spring-operated pin mounted near the forward end of each rail, thereby locking the carriage. During retraction of this final bay the pin is manually retracted from the carriage, thus allowing the jackscrew to be retracted into the housing.

One of the longeron and one of the diagonal unlocking assemblies is each shown (Figure 1.2-4) in the partially deployed configuration. In the stowed configuration the carriages are entirely within the main housing.

Figure 1.2-3. Deployment/Retraction Mechanism Concept

Figure 1.2-4. Deployment/Retraction Mechanism Details

The separate longeron and diagonal unlocking systems are activated only during retraction and are respectively used to unlock the longeron and diagonal center joint latches prior to the start of the batten retraction. The diagonal and longeron center joint latches are unlocked by forward motion of the trip lever pins and tripping probes mounted on the deployable/retractable carriages installed within rails and driven by the 25.4-mm-diameter jackscrew.

The positioning system requirements for this program are a version of standard motion control (robotics) used in industrial machine control applications.

Motion profiles are built up as sequenced indexes. Each index consists of a direction, acceleration time, deceleration time, feed rate, and travel distance. The controller calculates acceleration rates, deceleration rates, and the position to begin deceleration. The mechanization uses encoder and tachometer sensing with overrated motors and mechanization to ensure precise position control without overshoot in the presence of varying output loads. The motion profiles for the test article are shown in Figure 1.2-5.

The three-axis system selected will allow totally separate positioning of (1) the batten deployment/retraction system, (2) the longeron unlocking system, and (3) the diagonal unlocking system.

The batten deployment/retraction axis controller will use a direct-drive dc servo motor rated at 27 Nm (240 lb-in.) continous operation up to 225 rpm. The motor will be driven with a standard pulse-width modulated drive. Positioning resolution will be within 0.001 revolution which is equivalent to a longitudinal accuracy of 0.0064 mm (0.00025 in.) on the 6.35 mm pitch jackscrew. The deployment/retraction profile will be achieved as a series of ten indexes entered into a specific program.

The diagonal and longeron unlocking controllers will be configured with identical hardware and software. Again, direct-drive dc servo motors will be used rated at 3.7 Nm (33 lb-in.) continuous up to 2400 rpm. The motor contains an integrally mounted encoder and tachometer. Each of the motors will have its own pulse-width modulated drive and dc drive power supply. These controllers will be to within 0.0025 revolution which is equivalent to a longitudinal accuracy of 0.127 mm (0.0005 in.) on the 5.08 mm pitch jackscrew to which they will be mounted. Figure 1.2-6 shows an illustration of the typical components

Figure 1.2-7 illustrates the key discrete stages of deployment and retraction. Starting from the stowed package (View 1) the end adapter, which is the foward batten of Bay 1, is forward of the jackscrew support frame. The first stage of deployment positions and locks the jackscrews and the jackscrew support frame diagonal struts, and develops (View 2) Bay 1. At this point, the Batten 1 (Figure 1.2-1) half-nuts are engaged with the aft end of the jackscrew thread. The batten deployment/retraction system jackscrews are reversed to start the deployment of Bay 2 (View 3).

Figure 1.2-5. Positioning System Motion Profile

3 Required

Figure 1.2-6. Positioning System Components

Batten 2 (Figure 1.2-7) is held in place by spring-loaded detents until Bay 2 is fully extended and locked, and is later overwhelmed by the jackscrew starting the deployment of Bay 3. In this manner, each of the bays is deployed one at a time until the fully deployed truss configuration is achieved (View 4).

At this point, precompression of the longerons can be applied and removed by manual activation of the precompression system.

In the retraction phase the longeron and diagonal unlocking carriages are initially positioned such that each of the tripping probes is 25.4 mm away from the longeron and diagonal latch trip levers. The four diagonal and four longeron latches in Bay 10 are tripped after ten clockwise revolutions of the unlocking system jackscrews. After a number of milliseconds (to be determined in the future ground tests) the batten deployment/retraction system motors are rotated clockwise until Batten 9 (Figure 1.2-1) is placed on the rail. As each bay is retracted, the carriages on the unlocking systems are advanced to the next unlocking position (Figure 1.2-5). This proceeds from Bay 10 through unlocking of Bay 1 (View 6). Upon unlocking the longerons and diagonals of Bay 1, the batten deployment/retraction jackscrews are rotated counter-clockwise 32 revolutions. The extended diagonal and longeron unlocking systems are then retracted into the housing to permit the final retraction of Bay 1.

Figure 1.2-8 describes the major features of the precompression system provided to eliminate joint backlash in both the longerons and diagonals. A cable/bungee system, with a cable pretension of 1780 N (400 lb), will apply up to 1425 N of compression in each of the four truss longerons. This compression load will, through compatible strain, provide up to 260 N of precompression in the diagonals.

The precompression system consists of two spring bungee assemblies mounted on the aft end of the main housing. From either end of each bungee, threaded rods are extended that mate with a turnbuckle. From the opposite end of each turnbuckle is another threaded rod swagged to a long cable. The two from each turnbuckle traverse laterally until they engage a pulley near the axes of the longerons. The cables wrap around the pulleys 90 degrees and extend forward where they enter the longerons located at the four corners of the truss. The cables continue forward through the longerons of all ten bays. The cables exit the longerons of Bay 1 and engage another pair of fairleads mounted within the adapter. These fairleads are canted in such a way that the cables continue toward the geometric center of the adapter within its diagonal braces. Swagged balls on the cables attach to fittings whose mounting locations are adjustable within the adapter.

The bungees are supported on the rear of the housing by two pairs of brackets that partially encircle the cylindrical body and still allow the body to move along its axis as the turnbuckles are utilized to pretension the cables to their final 1780 N load.

Figure 1.2-9 illustrates the major parts of the main housing which is a combination welded, riveted, and bolted assembly into which all other major assemblies are installed. A welded frame consisting of 50.8 mm square aluminum 6061-T6 tubing has numerous skin and stringer subassemblies riveted to it.

① STOWED PACKAGE

② DEPLOYMENT OF
  • ADAPTER
  • JACKSCREW SUPPORT FRAME ASSY
  • FIRST BAY (BAY 1)

③ PARTIAL DEPLOYMENT, BAY 2

④ DEPLOYMENT OF BAYS 2 THROUGH 10

⑦ LONGERON & DIAGONAL TRIPPING DEVICES RETRACTED

⑤ LONGERON & DIAGONAL UNLOCKING DEVICES TRIP BAY 10—BATTEN DEPLOYMENT/RETRACTION SYSTEM RETRACTS BAY 10

⑥ ALL BAYS EXCEPT BAY 1 RETRACTED—

Figure 1.2-7. Deployment/Retraction Major Phases

3.1 mm DIA (7 X 19) CABLE

LONGERON

CABLES EXTEND FORWARD THROUGH LONGERONS & ATTACH TO ADAPTER

PRECOMPRESSION SYSTEMS

HOUSING

MANUAL ADJUSTMENT OF TENSION CABLE PERMITS TEST DATA FROM 0 TO 1780 N

SPRING PROVIDES 1780 N NOMINAL PRELOAD. (SPRING CONSTANT 87.5 N/cm)

TURN BUCKLE

BUNGEE

CABLE ASSY

SUPPORT BRACKETS

GSE WRENCH

Figure 1.2-8. Precompression System to Eliminate Joint Slop

Figure 1.2-9. Main Housing Structure

Panels on the aft side of the housing are removable to provide access to the precompression system and the three chain-and-sprocket drive systems located near the center of the housing. Access holes along the four sides of the housing align with the batten retaining detents to provide adjustment capability.

A rectangular pattern of threaded inserts is provided on the four sides of the housing for the future attachment of the NASA/MSFC simulated payload carrier structures.

The foregoing described test article design is representative of a square-truss, single-fold prototype building-block design from which potential space platforms (Figure 1) or Space Station structures can be constructed.

The protoype building block has the following significant design characteristics:

o Automatic bay-by-bay deployment and/or retraction to facilitate identification of problem (in the event this occurs)

o Maintenance of root strength during deployment/retraction operations which can permit orbiter VRCS firing (if necessary)

o Longitudinal deployment/retraction within the housing cross-section envelope

o All inter-building-block electrical connections in olace prior to orbiter installation

o In-space Inter-building-block structural connections made automatically without a fixture.

o Square-shaped truss which is most suitable for inter-building-block attachments; mounting of payloads, docking ports, and propulsion modules; and redundancy for meteoroid impact

o Circular tubes for all truss members which is the minimum cost construction for graphite composite construction

o Wide trays for mounting of a large complement of utilities with ease of initial installation, repair, replacement during the total ground fabrication period, and with minimum truss structural design constraints

o Narrow trays for minimal complement of utilities with a longeron fold angle of 40 to 45°

o Payloads and propulsion modules can be attached using the RMS

o A precompression system to eliminate joint backlash

o Unlocking systems (for retraction) that are easily removable for applications in which retraction is not required

1.3 TEST ARTICLE DESIGN

This section contains a detailed discription of each of the major sub-assemblies that comprise the test articles major components (1.3.1), a listing of the test articles major deviations from the prototype design (1.3.2), a description of the test article assembly procedure (1.3.3), and a detailed description of the method of deployment and retraction (1.3.4).

1.3.1 Major Subassemblies Design Description

The major subassemblies that comprise the major components summarized in Section 1.2 are described in further detail in this section.

1.3.1.1 Deployable Truss

Each of the major subassemblies that comprise a bay of the deployable truss are described as follows:

Diagonal Assembly (Drawing 42712-110) - Figure 1.3-1 illustrates the major design features of the diagonal assembly. The outer part of this telescoping design consists of, from left to right, a rod end threaded to a turnbuckle which is threaded to a transition fitting that is blind riveted to a 50.8-mm-diameter 6061-T6 aluminum tube that is adhesive bonded to an outer center fitting. The unlocking latch mechanism is attached to this fitting. The inner sliding part, from right to left, consists of an identical rod end threaded to a transition fitting that is blind riveted to a 44.5-mm-diameter tube also adhesive bonded to an inner center f tting. The rod ends are stainless steel, the transition fittings CRES 304 steel, and center fittings (Figure 1.3-2) 6061-T6 aluminum.

Within this inner center fitting is a pair of opposing spring-loaded locking pins oriented 90° to the axis of the tube. These pins have blunt points machined on them that are aligned with holes on opposite sides of the inner and outer center fittings. A spring between the two pins exerts a separating force on them. In all but the extended position, the pins are prohibited from protruding outside the inner tube because of the encircling wall of the outer tube. During truss deployment, the two tubes are extending with the spring loaded pins of the inner tube pressing on the inner wall of the outer tube. At within 6 mm of complete diagonal extension the spring-load pins come into axial alignment with the two opposing holes in the outer tube. The spring forces the pins into the matching holes of the outer tube, thus locking the two tubes in that position. The longitudinal force provided by the pair of springs is 82.8 N. This operation is automatic and occurs in each of the four diagonals of each bay.

The two shear pins provide the axial load path between the inner and outer center fitting. The pins also provide capability to sustain bending moments acting in a plane containing the axis of the pins. A bending moment acting in a plane perpendicular to the axis of the pins is sustained by bearing between the inner and outer fittings at the stations reinforced by rings (Figure 1.3-2). The tolerances between the mating diameters of the two fittings have been limited for this reason (Section 1.5). The diagonals will be fabricated to the dimensional length tolerances shown on the drawings. Upon final assembly, as described in Section 1.3-3, the diagonals will be adjusted to the length compatible with trouble-free deployment and retraction by micro-adjustment of the turnbuckle provided.

Figure 1.3-1. Telescoping Diagonal Joint

Figure 1.3-2. Telescoping Diagonal Center Joint

For the retraction operation, an external cam lever is provided (Figure 1.3-2) and is actuated by the diagonal unlocking trip lever pin as follows: The trip lever pin on the carriage is extended by the jackscrew until it contacts and causes the diagonal's external cam lever to rotate. The rotating lever causes the cam to partially depress the protruding spring-loaded pins. Subsequently, the batten jackscrew begins moving the batten toward the housing. This motion induces bearing on the pin holes of the outer tube which completely compresses the tapered pins inside the center fitting. Continued batten retraction permits total telescoping of the diagonal. In the stowed configuration the diagonal nests between the batten assembly members (Figure 1.2-2).

Longeron Assembly (Drawing 42712-120) - Figure 1.3-3 illustrates the major design features of the longeron assembly. Each longeron is comprised of two identical halves (except for provisions for attachment of the latching mechanism). Each half consists of a rod end (identical to that provided in the diagonal assembly) threaded to a turnbuckle which is threaded to a CRES 304 transition section which is blind riveted to the 50.8 mm (2 in.) diameter 6061-T6 tubes which are blind riveted to a 2024 aluminum center fitting (Figure 1.3-4). The center fitting on each half, in conjunction with the side plates, comprise the center hinge mechanism required to fold the longerons to the configuration shown in Figures 1.2-2 and 1.3-5. This design was developed to prevent the increase and subsequent decrease in longeron length that occur in an over-center latch pivot design at the stage of deployment shown in Figure 1.3-6. The added complications to the aforementioned diagonal telescoping tube locking and the positioning system motion profile would be prohibitive.

Longeron axial loads are transferred from the left center fitting to the pivot pin into the pair of side plates and then into the right center fitting through the pivot pin. Bending moments acting in a plane perpendicular to the planes of the the side plates are similarly transferred across the joints. Bending moments acting in the plane of the side plates are transferred by bearing in the pivot pins and the 9.5 mm (3/8 in.) diameter locking pins. Shear stiffness in the plane perpendicular to the side plates is provided by the web shown in Figure 1.3-4.

Two sector gears are installed on either side of the hinge to eliminate the instability of the four pivot points of the longeron during deployment. These sector gears anchor the two pivots of the longeron halves together causing them to rotate in a singular controlled manner. The result is to make the two pivots act as one hinge on the center line of the longeron.

Locking of the longeron in the fully deployed position is accomplished by a pair of spring-loaded pins (similar to those in the diagonal) in the fold mechanism. The aforementioned side plates extend beyond their pivot pins a short distance and provide a pair of holes that are aligned to receive the spring-loaded pins when the two rotating arms arrive at their fully deployed position. The engaging pins and pivot pins lock each half of the longeron to the side plates and, since the plates are continuous across the hinges, the hinge becomes rigid in the fully extended position.

Figure 1.3-3. *Folding Longeron Assembly*

Figure 1.3-4. *Longeron Center Joint Details*

SECTOR GEARS

SIDE PLATES

PLUNGER LOCATIONS

LONGERONS STOWED
(TRIP LEVERS OMITTED)

TRIP LEVER

TRIP MECHANISM

127 mm

SPRING LOADED PLUNGERS

SIDE PLATE 3.2 mm - 2024 AL

CAM RETURN SPRING

A-A

CAM (304 CRES)

A

A

6.4 mm DIA SCREW & NUT (2)

TRIP LEVER

LONGERON DEPLOYED

50.8 mm O.D. X 2.1 mm WALL AL TUBE

SIX - 4.8 mm DIA AL BLIND RIVETS

Figure 1.3-5.   Longeron Center Joint Additional Details

DESIGN REQUIRES LONGERON HINGE TO BE ON SIDE OF TUBE TO PROVIDE 180 DEG FOLD DURING STOWAGE

1.3 mm FOR TYP BAY; 1.7 mm FOR CARRIER BAY

● ACCOMMODATION OF LENGTH INCREASE WOULD COMPLICATE TELESCOPING JOINT, AND POSITIONING SYSTEM DESIGN

PARTIALLY OPEN

Figure 1.3-6.   Problem with Over-Center Latch Design

1-19

Like the diagonal struts, there is a taper on the end of the spring-loaded pins that assists in the final degrees of longeron deployment. This is accomplished by the points of the tapered pins engaging the edge of the holes in the side plates with the resulting camming action forcing the two arms of the longerons into their final deployed position.

After the spring-loaded pins have fully engaged their respective holes in the side plates, their aforementioned conical ends extend outside the plates. To unlock the longeron and allow it to fold into its retracted position, a pivot hole is added to the side plates. A rotating shaft is inserted through the pivot hole and a cam plate is installed on each end of the shaft. The cams are located so as to depress the extended cones of the spring-loaded locking pins in a manner similar to the aforementioned diagonal. A lever arm is added to one of the cams. A probe extending from the carriage of the longeron retraction jackscrew assembly engages this lever and rotates it enough to unlock the latch by causing the cams to depress the spring-loaded pins (Figure 1.3-5) and also exerts a side force on the hinge that causes the hinge to fold off "dead center" as the outboard batten is retracted by the batten jackscrew assembly. As the batten continues to move toward the housing, the longeron folds at an angle of 35° inboard from the plane of the truss. This out-of-plane fold angle provides clearance for the telescoping diagonal struts to be stowed along side the batten members.

Upon final assembly (Section 1.3.3) each of the longeron halves will be micro-adjusted to the lengths compatible with trouble-free operation by the turnbuckles located at either end. Dual turnbuckles are necessary so the folding hinge is always located at the center of the longeron to prohibit binding during the fold sequence. The turnbuckle shown, compared to conventional turnbuckle designs, provides a more direct load path and, because of the reduced length, results in a stiffer member for column applications.

Typical Batten Assembly (Drawing 42712-190) - Figure 1.3-7 illustrates the major design features of the typical batten assembly that, in conjunction with four longerons and four diagonals, comprise a typical bay of the deployable truss (Figure 1.2-2). This batten assembly is not to be confused with the payload carrier batten assembly (Drawing 42712-220).

The batten is comprised of four 35 mm (1-3/8 in.) diameter 6061-T6 tubes that define the truss square frame, stabilized by a compression-carrying diagonal brace of the same size and material. The brace contains tapered end fittings to preclude interference with the stowed longerons. The four frame members are joined together by blind riveting to the four corner fittings shown. The corner fittings contain integral clevises for attachment of the diagonal and longron rod ends, and the threaded half-nuts that engage the batten deployment/retraction system jackscrews. The corner fittings also provide gussets for mechanical fastening of the diagonal brace. Each of the corner fittings contains a pair of pockets into which ball detents, mounted in the deployment/retraction system rails, enter to retain the stowed batten. The corner fittings also contain openings, through which the precompression system tension cables are routed.

The batten corner fitting clevises (for the rod ends of the diagonal and longeron members) contain shoulders on the inner surfaces to minimize the axial rotation of the members to $\pm 1.5°$. This restriction is necessary to preclude the possibility of the latch release levers rotating out of the plane of their respective tripping probes mounted on the diagonal and longeron unlocking system carriages.

The half-nut corner fittings are coated with teflon (TFE) to reduce friction while in contact with the rotating jackscrews during deployment and retraction.

Payload Carrier Batten Assembly (Drawing 42712-220) - The payload carrier batten assembly overall configuration and design features are shown in Figure 1.3-8. There are two of these battens onto which the NASA/MSFC simulated payload carriers will be mounted. The 1/2-20 threaded inserts provided 1.31 m (51.5 in.) apart along the batten and 1.09 m (43.0 in.) apart between the pair of battens are the attachment interface for the simulated payload carriers. This attachment interface is provided on each of the four batten faces.

This batten is designed to locally support installation of a 3636 kg (8000 lb) simulated payload carrier, for modal survey tests, without detrimental deformation provided the frame itself is supported by a pair of vertical tension cables attached at the bottom of the frame or at points "A" and "B" (Figure 1.3-8). Therefore, the batten is comprised of 50.8 mm 6061-T6 square tube members. Further, the square tubing can permit future installation of electrical feedthrough plates.

The corner fittings are configured to accommodate blind riveting for attachment of the square tubes and to provide threaded inserts for installation of the payload carriers. It also provides clevises with rotation-limiting features for the longerons and diagonals, pockets for the ball detents, threaded half-nuts, and holes for the routing of the precompression system tension cables.

Like the corner fittings on the regular battens, the half-nuts are also coated with teflon.

Utilities Support Trays (Drawing 42712-230) - The deployable truss design includes utilities support trays. For this ground test article the utilities trays are provided in only Bays 4 and 5. The trays provide support for the required complement of four No. 1/0 cables, two No. 8 AWG, four No. 12 AWG, four coax, twenty No. 22 twisted pairs shielded, and four 12.5 mm flexible coolant tubes. There is additional space available for two No. 1/0 cables, one No. 8 AWG, two No. 12 AWG, two coax, and eight No. 22 twisted pairs shielded.

The tray assembly in each bay consists of two half-trays hinged to each other at the tray edges in the center of the bay. Each tray half attaches to hinge fittings mounted on the batten tube frame.

Each half-tray assembly has a machined aluminum base containing the four hinge points, tray sides and stiffeners. Three epoxy glass block clamp sets and a machined aluminum cover are bolted to the base. The block clamp sets provide support of the utilities and ample separation of power and data lines. The base and cover contain cutouts to reduce weight.

One half-tray assembly base in each bay has provisions for four bolt-on longeron supports. These supports provide lateral stability for the longerons in their stowed position and have capture guides that assist the longeron during retraction.

1-21

Figure 1.3-7. Typical Batten Assembly

Figure 1.3-8. Payload Carrier Structure

When stowed, each utility tray will nest between the diagonal braces of
adjacent battens. Each tray base has two pads that can transmit longitudinal
support from the folded tray to the adjacent tray. For a truss containing
trays throughout, the longitudinal load can be transferred to the support
beams provided in the main housing and adapter.

The length of the utility tray assembly is slightly longer than the
distance between adjacent batten hinges so that the trays center hinges will
be approximately 50 mm (2 in.) above the batten hinge centerline when   .
deployed. This is to prevent a locking condition on retraction.

1.3.1.2 Deployment/Retraction Mechanism

Each of the major subassemblies that comprise the deployment/retraction
mechanism is described as follows:

Batten Deployment/Retraction System (Drawing 42712-130) - Figure 1.3-9
illustrates the major design features of one of the four batten deployment/
retraction system assemblies. Each assembly consists of a jackscrew,
carriage, and spline assembly cradled within a rigid rail that is attached to
a pair of main housing frames. The jackscrew threads and rails match similar
features on the half-nuts of the batten and carrier assemblies (Figure
1.3-10). A splined bushing at the aft end of the jackscrew encircles a
splined shaft that runs nearly the entire length of the jackscrew. The
jackscrew spline extends beyond the aft end of the rail where a chain and
sprocket is attached. One of the four spline shafts is coupled to a drive
motor mounted on the aft end of the housing. A chain encircling the four
sprockets drives all of the jackscrews simultaneously. (Figure 1.2-4)

Encircling the rotating jackscrew is a carriage fitting with external ears
that engage matching grooves running the length of the rails. The carriage is
pulled forward with the jackscrew, during deployment of the first bay, until a
hole in the side of the carriage engages a spring-operated pin (Figure 1.3-10)
mounted near the forward end of each rail. During jackscrew retraction, the
spring-loaded pin is manually retracted from the carriage, thus allowing the
carriage and jackscrew to be subsequently retracted into the housing.

At the cantilevered forward end of the spline is attached a sleeve whose
outside diameter is slightly smaller than the inside diameter of the
jackscrew. The purpose of this sleeve is to maintain concentricity of the
splined shaft with the jackscrew.

At the forward end of the jackscrew (Figure 1.3-9) a probe is provided
that supports the jackscrew support frame and the end adapter in the retracted
position. The jackscrew support frame is attached by a plate on the frame
engaging an annular groove in the probe. The end adapter is retained on the
probe by an adjustable spring-loaded ball detent in each probe engaging a
matching groove within each of the four drogues located at the corners of the
adapter.

At eight places along each rail are adjustable spring-loaded detents that
are utilized to offer resistance to deployment of battens stowed along with
the rails while a bay is being formed along the extended jackscrews. Once the
bay is formed by fully extending the longeron and diagonal struts, sufficient

Figure 1.3-9.   Batten Deployment/Retraction System Mechanism

Figure 1.3-10.   Carriage Locking Detail and
Half-Nut to Rail Matching Features

force can be exerted on the restrained batten by the jackscrew to overwhelm
the resistance of the detents and, thereby, deploy the batten. The same
procedure is repeated for deployment of each bay until the entire truss is
deployed.

Attached approximately midway to the rails are truss attachment fittings
that interface with the aft ends of the longeron and diagonal struts that
comprise the last bay. These anchor fittings replace a batten that is
normally used elsewhere in the truss. When the truss is completely deployed
the fittings transfer longeron and diagonal loads to the rails, and to the
housing through the rail attachment to the housing. This frame is adjacent to
the fittings and is stiffened by the shear web shown in Figure 1.2-9.

Longeron and Diagonal Unlocking Assembly (Drawing 42712-140) - Figure
1.3-11 illustrates the major design features of the longeron and diagonal
unlocking assemblies. The figure at the upper left represents the partially
deployed configuration. The diagonal unlocking assembly is identical except
for the difference in the tripping device.

There are four longeron unlocking assemblies (one for each of the four
longerons) and four diagonal unlocking assemblies (one for each of the four
diagonals). These assemblies are located as shown on Figure 1.2-3

Each of these eight assemblies consists of a 6061-T6 guide rail, 25.4 mm
(1 in.) diameter 304 CRES steel jackscrew, 6061-T6 carriage, and appropriate
latch tripping device. The jackscrew has an ACME thread with a 5.08 mm pitch
(0.20 in.). The guide rail is fastened through adjustable shims to the main
housing frames. Sprockets mounted on the aft-extended end of the threaded
carriage rods are interconnected by a chain encircling the sprockets. A drive
motor is attached to one of the extended threaded carriage rods, and the
interconnecting chain drives the three remaining assemblies within each
system. (Figure 1.2-4).

The separate longeron and diagonal unlocking systems are activated only
during retraction and are respectively used to unlock the longeron and
diagonal center joint latches just prior to the start of the batten
retraction. The diagonal and longeron center joint latches are unlocked by
forward motion of the trip lever pins and tripping probes mounted on the
deployable/retractable carriages installed within rails and driven by the
jackscrews. This is accomplished as follows:

At the center of each telescoping diagonal strut and folding longeron are
internal spring-loaded pins that automatically lock each strut in its fully
extended position In this locked position, tapered ends of the spring-loaded
pins are extended through the walls of the struts beyond their exterior
surfaces. Lever operated cams, mounted on the exterior of the members depress
the spring loaded pins, thus unlocking the struts and thereby permitting them
to be folded or telecoped to the stowed position.

A motor controller is programmed to rotate each carriage jackscrew,
thereby extending probes, (mounted on the forward ends of each carriage)
enough to engage the cam levers on each strut and to cause them to rotate
until the cams depress the spring-loaded pins within the members. The

forward batten of that bay can then be moved toward the main housing, causing the diagonals to compress and the longerons to fold into their fully-stowed position. Because the stowed thickness of a typical bay is 101.6 mm (four inches), the carriage must be advanced this distance to center the carriage trip probe with the lever cam latches in the subsequent bay. After the latches of the final bay are tripped, the motor controller is programmed to retract the extended carriages back into the housing to permit subsequent retraction of the jack-crew support frame and the truss end adapter.

At first glance one would think that the mechanization of a tripping system for the diagonals would be identical to one of the longerons because they both simply rotate levers on the respective latches. A closer analysis of the two systems kinematics reveals the initial rotation of the latch lever depresses the locking pins of the latches. In the case of the diagonals, once the pins are retracted, the extended bay batten can be retracted into the housing. This action causes the telescoping diagonals to shorten. In the case of the longerons, however, just retracting the locking pins will not necessarily allow the longeron to fold. A friction lock could still inhibit the longeron from folding. An additional force perpendicular to the axis of the longeron pivots is required to displace the pivot off-center simultaneously with the retraction of the extended bay batten. Thus it can be seen that a single unlocking system to perform all these functions was not appropriate.

1.3.1.3 Jackscrew Support Frame Assembly (Drawing 42712-170)

Figure 1.3-12 illustrates the major features of the jackscrew support frame assembly. This assembly, consisting of four telescoping diagonals and a frame, provides a "deep truss" stiffness to the cantilevered ends of the four batten deployment/retraction system jackscrews during all operations excepting the deployment/retraction of Bay 1 (Figure 1.2-3). During deployment/retraction of this bay the four jackscrews and frame behave as a Vierendeel truss. This is expected to be adequate during the initial stages of deployment of the truss since the length is small; hence, on-orbit moments and stiffness requirements should be minimal. The frame itself also minimizes any relative lateral separation between the jackscrews compatible with maintaining thread engagement.

The assembly consists of the support frame (View A-A) and four telescoping diagonals. The diagonals are identical to the typical diagonals in the deployable square truss except for length. The ends of the diagonals are attached to clevis fittings on the main housing forward frame and to the frame as shown in detail "A".

The frame is comprised of four 6063-T52 rectangular tubes riveted together through the fittings shown on Details "A" and "B". The dog-legs in the fittings are required to permit clearance during the traverse of the deployable truss longeron latch mechanisms and the batten corner fittings half-nuts. The dog-leg and requirements of compact stowage directed the design to have offsets between the jackscrew, diagonal, and frame member centerlines. This has been accounted for in the design (Volume III).

Figure 1.3-11.   Longeron/Diagonal Unlocking Mechanisms

Figure 1.3-12.   Jackscrew Support Frame

1.3.1.4 Positioning System Design

During the early part of this study Rockwell obtained the assistance of PMI Motors (Division of Kollmorgen Corporation) to determine the positioning system design characteristics. The resulting design is documented in Reference 10. At the conclusion of this study, PMI Motors deferred the positioning system responsibility to the Kiowa Corporation. The following positioning system description has been provided by the Kiowa Corporation.

The positioning system requirements for this program are a version of a standard motion control (robotics) used in industrial machine control applications.

Motion profiles are built up as sequenced indexes. Each index consists of a direction, acceleration time, deceleration time, feed rate, and travel distance. The controller calculates acceleration rates, deceleration rates, and the position to begin deceleration. The mechanization uses encoder and tachometer sensing with overrated motors and mechanization to ensure precise position control without overshoot in the presence of varying output loads. The motion profiles for the test article are shown in Figure 1.2-5.

The three-axis system selected will allow totally separate positioning of (1) the batten deployment/retraction system, (2) the longeron unlocking system, and (3) the diagonal unlocking system.

In addition, the system includes a programmable output option that allows the batten deployment axis to sequence the longeron and diagonal unlocking axes. The system consists of a standard main frame chassis with three standard motor control modules, position feedback modules, and digital input/ output modules. In addition, three machine logic simulators are included for all motion fuctions on any axis; for example, jog, run, hold, and high or low speed.

The batten deployment/retraction axis controller will use a direct-drive dc servo motor rated at 27 Nm (240 lb-in.) continuous operation up to 225 rpm. The motor will be driven with a standard pulse-width modulated drive. Positioning resolution will be to within 0.001 revolution which is equivalent to a longitudinal accuracy of 0.0064 mm (0.00025 in.) on the 6.35 mm pitch jackscrew. The deployment/retraction profile will be achieved as a series of ten indexes entered into a specific program.

The diagonal and longeron unlocking controllers will be configured with identical hardware and software. Again, direct-drive dc servo motors will be used rated at 3.7 Nm (33 lb-in.) continuous up to 2400 rpm. The motor contains an integrally mounted encoder and tachometer. Each of the motors will have its own pulse-width modulated drive and dc drive power supply. These controllers will be to within 0.0025 revolution which is equivalent to a longitudinal accuracy of 0.0127 mm (0.0005 in.) on the 5.08 mm pitch jackscrew to which they will be mounted.

The controller is an Intel-8085 based eight-bit microcomputer with 2K of random access memory (RAM), 16K of eraseable programmable read-only memory (EPROM), and 1K of electrically alterable read-only memory (EAROM). For extended programming capability, the EAROM may be expanded to 5K. EAROM is nonvolatile, having at least ten years of storage life for the user input parameters. Operating system software integral with the controller simplifies the task of user programming. The configuration is arranged through a prompting routine displayed from an alphanumeric display requiring simple command input from a keyboard.

Interface between the controller, motors, and sensor feedback is done through 24 input/output lines defined for specific functions.

All of the hardware, except the motors, the remote programming panel and cabling will be mounted in a standard 914 mm by 914 mm by 305 mm enclosure.

Figure 1.2-6 shows an illustration of typical components, and Figures 1.3-13 and -14 show they key dimensions for the selected motors.

1.3.1.5 Precompression System Assembly (Drawing 42712-150)

Figure 1.3-15 illustrates the major design features of the precompression system provided to eliminate the slop in the 280 pivots of the ten-bay deployable truss.

The system consists of a pair of spring bungee assemblies mounted on the aft end of the main housing. From either end of each bungee threaded rods are extended that mate with a turnbuckle. From the opposite end of each turnbuckle is another threaded rod swagged to a long cable. The two 3.2 mm (1/8 in.) diameter wire rope (7 x 19 strands) from each turnbuckle traverse laterally until they engage a pulley aligned with the axes of the longerons. The cables wrap around the pulleys 90 degrees and extend forward where they enter the longerons located at the four corners of the truss. The cables continue forward through the longerons of all ten bays. The cables exit the longerons of Bay 1 and engage fairleads mounted within the adapter. These fairleads are canted in such a way that the cables continue toward the geometric center of the adapter within its diagonal braces. About midway to the center of the adapter, swagged balls on the cables attach to fittings whose mounting locations are adjustable within the adapter.

The bungees are supported on the rear of the housing by two pairs of brackeᵥ (Figure 1.3-15) that partially encircle the cylindrical bodies (6061-T) and still allow the body to move along its axis as the turnbuckles are uti zed to pretension the cables to their final 1780 N load.

The cable pretension is accomplished by utilizing a GSE tool (described on the drawings) as follows. Slots located in each leg of the tool's yoke that straddle the turnbuckles are engaged with the flats on the cable terminal and the rods extending from either side of the bungee into the turnbuckles. A 25.4 mm crescent wrench is simultaneously engaged with the center of the turnbuckle to turn it to shorten the effective length of the cable and thereby, compress the spring within the bungee. The same procedure is applied to the other turnbuckle to totally foreshorten each cable 101.6 mm (4 in.), for a total cable pretension of 1780 N (400 lb).

C

Figure 1.3-13.   27 Nm DC Servomotor Dimensions

Figure 1.3-14.   3.7 Nm DC Servometer Dimensions

The bungee utilizes a 79.4 mm (3-1/8 in.) O.D. compression spring fabricated from 8.7 mm (.343 in.) diameter 17-7 PH wire. The compression spring is stabilized by the inner wall of the bungee cylinder body. The spring is designed to provide a spring constant of 87.5 N/cm (50 lb/in.) to minimize pretension cable load fluctuations that could occur in a space article. Figure 1.3-16 illustrates the routing of the tension cables between adjacent longerons through the batten corner fitting guide openings, and the routing through the longeron rod end transition fittings past the center joint mechanism. The openings provide adequate clearance for bending of the cable, to permissible bend radii, during folding of the structure. The openings at the longeron center joints also permit bending to adequate radii and confine cable excursions to an acceptable envelope.

1.3.1.6 End Adapter Assembly (Drawing 42712-180)

Figure 1.3-17 illustrates the major design features of the end adapter which is the forward batten for the first bay and has provisions for attachment to a NASA/MSFC test fixture for stiffness, modal survey, and limit load strength testing (Figure 1.3-18). The end adapter also is the mounting for the swagged balls on the four tension cables of the precompression system. Representative of future flight article needs, during orbiter launch, the diagonals stabilize the main housings forward frame and vertical beams provide rigid longitudinal support for the folded longerons and trays.

The end adapters square configuration is constructed from four 50.8 x 76.2 mm (2 x 3 in.) 6061-T6 rectangular tubes mechanically fastened together by corner jackscrew drogue fittings (View A-A). The drogue is shaped to capture the ball detents mounted on the end of the batten deployment/ retraction jackscrew probes. The corner fittings provide the clevis fittings to receive the rod ends of the diagonals and longerons. The corner fittings also contain two inserts shown (Figure 1.3-17 - right view) for attachment of eight brackets that are mounted to the outside face of the main housing forward frame. The forward face of this corner fitting (View B-B) each contains threaded inserts for attachment to the NASA/MSFC test fixture. The inserts are centered on the projected longeron axis.

A pair of back-to-back 76.2 mm (3 in.) deep extruded channel sections are provided for each of the adapter diagonals. The spacing between the channels is used for routing the precompression system tension cables, and provisions for the adjustable fittings to which the swagged end of the cables are attached. Each end of the diagonals are attached to the corner fittings by a pair of shear clips and a pair of gussets as shown in Figure 1.3-17. The same type of structural attachment is provided at the diagonal crossings at the vertical beams, and at the inersection of the diagonals.

The square tube 6061-T4 beams are attached to the adapter square frame with shear clips and gussets.

1.3.1.7 Main Housing Assembly (Drawing 42712-160)

The main housing structure, Figure 1.3-19, is a combination welded, riveted and bolted assembly into which all other major assemblies are installed.

3.2 mm DIA (7 X 19) CABLE

LONGERON

CABLES EXTEND FORWARD
THROUGH LONGERONS &
ATTACH TO ADAPTER

PRETENSIONING
SYSTEMS

HOUSING

MANUAL ACTIVATION OF
TENSION CABLE SYSTEM
PERMITS TEST DATA FROM
0 TO 1780 N

SPRING PROVIDES
1780 N NOMINAL
PRELOAD. (SPRING
CONSTANT 87.5 N/cm

BUNGEE
SUPPORT FTG

CABLE ASSY

BUNGEE

TURNBUCKLE

GSE WRENCH

Figure 1.3-15. Pretension System to Eliminate Joint Slop

LONGERON

CABLE PORTS
IN END FITTINGS

CLEAR CABLE PATH
THRU CENTER FITTINGS

TENSION
CABLE

A

BATTEN

VIEW A-A

VIEW A-A

A

Figure 1.3-16. Tension Cable Routing Through Longerons

1-32

Figure 1.3-17. Adapter Assembly

Figure 1.3-18. Model Survey Potential Test Set-up

DRIVE
MOTOR
SUPPORT
FRAME

FRAME ADJACENT TO
ATTACH FITTING

2.3 mm ALUMINUM
SKIN PANELS
ALL SIDES

ACCESS
PANELS

STIFFENERS TO
PROVIDE MINIMUM
FREQUENCY TO 10 Hz

HOUSING
MAJOR
FRAMING

BATTEN
DETENT
ADJUSTMENT
HOLES (TYP)

Figure 1.3-19.   Main Housing Structure

A weld assembly of three frames and connecting stringers form the housing framing structure. The frames are made of 50.8 mm (2 in.) square, 6061-T6 aluminum tubing. The corners are braced with a 9.5 mm (.375 in.) thick 6061-T6 aluminum gussets welded in place. The forward and center frames provide the mounting for the rails of the four batten jackscrew assemblies, and the four diagonal unlocking and four longeron unlocking assemblies. Two insert mounts welded in each external frame side provide the 1/2-20 threaded insert pattern for payload carrier mounting. The center frame has two 76.2 mm (3 in.) square tube 6061-T4 aluminum members to accept longeron and utility tray longitudinal loads when stowed. The center frame also has a mounting structure for the precompression system. The aft frame provides mounting structure for the three drive motors and three chain drive idlers.

The center frame is closed out with two 2.3 mm (.090 in.) thick 6061-T6 aluminum sheets riveted in place. The sides of the main housing and aft drive motor frame are covered with 2.3 mm thick 6061-T6 aluminum skin panels that are bolted in place. All large skin panels have 44.5 x 44.5 x 3.2 mm 6061-T6 aluminum angle stiffners spot-welded in place to provide a minimum modal frequency no less than 10 Hz (Volume III). Access holes are provided in the skin for batten detent adjustment and jackscrew carriage release.

The 1/2-20 threaded insert pattern on each side of the main frames are also used for accepting eye bolts to attach support structures during ground handling and deployment/retraction operations. The forward inserts are used to secure the adapter to the housing during shipping.

1.3.1.8 Corrosion Protection

Corrosion protection on all components is in accordance with the standard industry practice, i.e., anodize for aluminum, cad plating for low carbon steel parts, TFE and dri lube for sliding and rotating surfaces.

1.3.1.9 Dimensional Accuracy

Dimensional accuracies with regard to detail fabrication are in accordance with specification ANSl Y14.5-1973. In addition, adjustments have been designed into minor and major assemblies via turnbuckles and shims.

1.3.2 Ground Test Article Deviations from Prototype

The ground test article design is "fabrication ready" and, hence, clearly defined. The prototype building-block design that is represented by the ground test article has not been designed in detail, and is not as clearly understood. However, to aid reviewers interested in future space applications the known ground test article deviations from the protype design are delineated as follows:

o Adapter-to-Housing Retention Mechanism - The test article is presently secured in the stowed position by four S-fittings connecting the end adapter to the main housing forward frame. Unlocking is done manually by removal of the four fittings. A prototype design will require substitution of a remotely controlled latch system.

o   Batten Jackscrew Carriage Locking Pins Assembly - Prior to retraction
    of Bay 1, the current design requires manual release of each of the
    four batten deployment/retraction jackscrew carriages locking
    assemblies. In the prototype design a remote motorized system is
    required.

o   Jackscrew Support Frame Diagonal Unlocking - Prior to retraction of Bay
    1 the test article requires manual release of each of the four tele-
    scoping diagonal latches that position and support the jackscrew
    support frame assembly. For the prototype design a remotely operated
    unlocking system will be required.

o   Positioning System Motors, Tachometers, Encoders - The test article
    servo motors, encoders, and tachometers are heavy-duty commercial
    designs. The prototype design will require flight-qualified designs,
    i.e, thermal, vacuum, radiation, Shuttle launch.

o   Precompression System Cable Tensioning - The test article tension is
    applied/removed manually with GSE wrenches. For the prototype design
    the tension will be applied/removed by a remotely controlled motor.

o   Motor Redundancy - The test article contains no redundancy. For the
    prototype, redundancy is required for all the motorized components.

o   Deployable Curtain - Reliable deployment/retraction operations on-orbit
    may require a curtain around the four open faces of Bay 1 (Figure
    1.2-3) The curtain can minimize fluctuation in the temperatures of the
    batten deployment/retraction jackscrews and in the longerons and
    diagonals during deployment, and with time permitting, during
    retraction. The curtain can be foldable in the same manner as that
    shown in Figure 2.1-7 for the Concept 4 OTV hangar. The need for a
    curtain depends on the range of temperatures that would occur in the
    affected members during deployment without it.   The desirability of a
    coarser ACME thread in the jackscrew which would provide an increased
    tolerance for thermal induced length changes is also dependent on
    thermal analysis results (Section 1.5.2.5).

    Depending on the particular future system-imposed requirements, the
    following design modifications may be necessary for a prototype design.

o   Main Housing and End Adapters - The ground test article design may be
    modified for the unique end attachment applications, and stowage in the
    orbiter.

o   Mass Critical Designs - A mass critical design would require modifi-
    cations such as reduced housing skin gauges, more extensive machining
    of the batten deployment/retraction rails, and reduced gauges on the
    longerons, diagonals, battens, jackscrew support frames, and end
    adapter.

o   Stringent Figure Control Design - Stringent dimensional stability
    requirements may require the use of low coefficient of thermal
    expansion (CTE) longerons, diagonals, and battens. Such a design in
    conjunction with an invar deployment/retraction jackscrew and a low CTE
    main housing would preclude the need for a curtain or the concerns of
    Section 1.5.2.5.

Finally, thermal coatings may be required on all non-rubbing surfaces of the truss structure.

1.3.3 Assembly Description

The assembly of the ground test article (Figure 1.3-20) is to be accomplished in the following manner:

1. Support the completed main housing assembly and orient as shown on Figure 1.3-21 and remove the aft skins. The aft face of the housing is to be approximately 1.5 m above the floor. (There are 16 handling lugs that will screw into the housing payload/carrier attachment inserts.)

2. Install the four batten deployment/retraction jackscrew assemblies and position (with shims) to satisfy the dimensional requirements shown on the top assembly drawing.

3. Install the four longeron and four diagonal unlocking jackscrew assemblies and position (with shims) to satisfy dimensional requirements shown on the top assembly drawing.

4. Install the jackscrew support frame assembly such that the underside of the frame rests on the housing and attach the four telescoped diagonals to the clevices on the housing and frame. This represents the stowed condition of the jackscrew support frame assembly.

5. Manually extend together the jackscrew support frame assembly and four batten deployment/retraction jackscrews and carriage to the deployed configuration shown on the top assembly drawing. Secure the four carriages to the housing by installing the four carriage locking pins through each rail into each carriage. Adjust the turnbuckle on each of the four diagonal tubes to the required dimensions shown on the top assembly to achieve squareness on all planes.

6. Support (as required) the jackscrew support frame assembly to permit removal of the four carriage locking pins and remove the assembly together with the jackscrews, splined shafts and carriages. During removal, protect flexible parts with wood bracing or equivalent.

7. Install the seven typical battens and two payload carrier support battens in the proper sequence into the housing, one on top of the other. (Batten 9 is supported by the four clevis fittings attached to the batten deployment/retraction jackscrew rails.) Partially lower the assembly removed in Item 6 into place until the aft ends of the four batten deployment/retraction jackscrew threads contact the forward faces of the four Batten 1 half-nuts. Orient the lead thread on each of the four batten jackscrews with its corresponding lead thread on the four batten half-nuts. Lower the entire assembly by simultaneously and manually rotating the four jackscrews clockwise until the holes in the carriage line up with the corresponding holes in the rails. Reinstall the four carriage locking pins.

Figure 1.3-20. Test Article Bay and Batten Identification

Figure 1.3-21. Test Article Assembly Configuration

8. Install the drive sprockets, and chain assemblies and shaft collars as shown on the top assembly drawing. Pretension the chains as specified. While installing and pretensioning the chains be sure to maintain the thread indexing of the batten jackscrews with the Batten 1 half-nuts. Upon completion of chain pretensioning, tighten the setscrews that secure the sprockets to the splined shafts.

9. Install the end adapter on the four jackscrew probes.

10. Install all four Bay 1 longerons and diagonals to complete Bay 1. Any length adjustment of the longerons is to be shared equally between each of the two turnbuckles per longeron.

11. Provide external vertical support that will permit retraction of Bay 1. Remove the four carriage locking pins and manually unlock the four jackscrew support frame diagonals, and the four longeron and four diagonal latches. (The sprockets have spanner wrench holes. A spanner wrench detail is provide on the top assembly drawings.) Use the spanner wrench to manually rotate the batten jackscrews until the jackscrew support frame rests on the main housing. Deploy and retract Bay 1 until trouble-free operation is achieved.

12. Using the spanner wrench, manually redeploy Bay 1. Continue counterclockwise revolutions until the forward face of the Batten 1 half-nuts are flush with the aft face of the jackscrew support frame. Position Batten 2 so that the forward faces of its half-nuts are contacting and radially aligned with the aft face of the batten jackscrew threads. Manually rotate the batten jackscrews counter-cockwise eight revolutions to obtain a 50.8 mm (2 in.) engagement of the Batten 2 half-nuts.

13. Install all Bay 2 longerons and diagonals. As before, any length adjustment of the longerons is to be equally shared by each of the two turnbuckles on each longeron.

14. Manually unlock all four diagonals and longerons of Bay 2. Retract and deploy Bay 2 until trouble-free operation is achieved.

15. Install Bays 3 and 4 longerons and diagonals in the same manner as Bay 2 until trouble-free operation is achieved.

16. Redeploy Bay 4. Continue manual counterclockwise rotation of the batten jackscrews until the forward faces of the Batten 4 half-nuts are 25.4 mm (1 in.) below the aft face of the jackscrew support frame. Position Batten 5 (payload carrier support frame) so that the forward faces of its half-nuts are contacting and radially aligned with the jackscrew threads. Manually rotate the jackscrew 12 revolutions counterclockwise.

17. Install the Bay 5 longerons and diagonals and adjust as described in Item 13.

18. Repeat Item 14 for Bay 5.

19. Redeploy Bay 5. Continue manual counterclockwise rotation until the forward face of the Batten 5 half-nuts are 254 mm (10 in) below the aft face of the jackscrew support frame. Position Batten 6 (payload carrier support frame) so that the forward faces of its half-nuts are contacting and radially aligned with the jackscrew threads. Manually rotate the jackscrews 32 revolutions counterclockwise which is a 203.2 mm (8 in.) travel.

20. Install the Bay 6 longerons and diagonals and adjust as in Item 13.

21. Repeat Item 14 for Bay 6.

22. Redeploy Bay 6. Continue manual counterclockwise rotation until the forward faces of the Batten 6 half-nuts are 25.4 mm above the aft face of the jackscrew support frame. Position Batten 7 so that the forward faces of its half-nuts are contacting and radially aligned with the jackscrew threads. Manually rotate the jackscrews 8 revolutions counterclockwise.

23. Install the Bay 7 longerons and diagonals and adjust as in Item 13.

24. Repeat Item 14 for Bay 7.

25. Install Bays 8 and 9 in the same manner as Bay 2.

26. Redeploy Bay 9. Continue deployment until the forward faces of the Batten 9 half-nuts are 1.35 m (53 in.) from the forward face of the rail attach fittings.

27. Perform Item 13 for Bay 10.

28. Perform Item 14 for Bay 10.

29. Manually retract Bay 10 through Bay 1 and record the relative longitudinal and lateral contact points for each longeron and diagonal retraction probe in each bay. Adjust each of the eight probes for best compromise. Redeploy and retract to verify suitability of probe adjustment.

30. Redeploy the entire structure Bays 1 through 10.

31. Manually and concurrently, using spanner wrench, rotate clockwise ten revolutions the diagonal and longeron retraction jackscrews, thereby unlocking the latches in each longeron and diagonal for Bay 10. Manually rotate the batten deployment/retraction system jackscrews clockwise to retract Bay 10.

32. Manually and concurrently rotate the unlocking system clockwise 20 revolutions, thereby unlocking Bay 9. Retract Bay 9.

33. Repeat Item 32 for Bays 8 and 7, except prior to retraction of Bay 7; manually and concurrently rotate the unlocking system counterclockwise five revolutions.

34. Manually and concurrently rotate the unlocking system five revolutions clockwise, thereby tripping the longerons and diagonals of Bay 6. Retract Bay 6.

35. Rotate the unlocking system 60 revolutions clockwise, thereby unlocking the Bay 5 diagonals and longerons. Retract Bay 5.

36. Repeat same procedure for Bays 4, 3, and 2 as for Bays 9 and 8, ending with retraction of Bay 2.

37. Rotate unlocking system 20 revolutions clockwise, thereby unlocking the Bay 1 longerons and diagonals. Manually unlock the four jackscrew support frame diagonals and pull the four carriage locking pins. Retract Bay 1 through 32 counterclockwise revolutions of the jackscrew systems. Retract the unlocking system by rotating the jackscrew system through 210 revolutions counterclockwise. The retraction probes should be in the initial stowed position. Complete the retraction of Bay 1 by rotating the unlocking assembly jackscrews counterclockwise through an additional 164 revolutions.

38. Deploy Bays 1 through 10 and install the precompression system as shown on the top assembly drawing.

39. Manually deploy and retract all bays to assure tension system cables do not interfere with deployment and retraction.

40. Deploy Bay 1. At Batten 2, using GSE wrench No. VW62 inserted through detent access holes in the housing skin, advance all eight detents (two at each batten corner half-nut) until contact with the half-nut is made. Note the depth of insertion of the wrench. Advance all eight detents 1.52 to 1.65 mm (0.060 - 0.065 in.). This position of the detent will impart a total of approximately 445N (100 lb) force resistance to the batten before the detents are compressed, thereby allowing the batten to move. If this amount of force appears to be too little or too great, the detents can be readjusted until the desired batten resistance is achieved.

41. Install the three drive motor assemblies.

42. Perform positioning system motor and computer adjustments.

43. Upon completion of Item 42, deploy Bays 1 through 5 and install the tray assemblies in Bays 4 and 5, respectively.

44. Retract and deploy Bays 4 and 5 to assure trouble-free operation. Retract the remaining structure and install the adapter/housing four "S" fittings.

The following further defines the assembly operations requirments:

(a) During deployment and retraction the truss structure weight exerted upon the jackscrews shall be counterbalanced to within ± the weight of one bay. Appropriate lateral support safety guides shall be provided.

(b) The assembly of the test article is to be performed in an environ-
ment in which temperatures are controlled to 27 $\pm$ 10°C (75° $\pm$ 18°F).

(c) The manual deployment and retraction operations will be performed
by applying torque to a spanner wrench that attaches to any one of
the four batten deployment/retraction jackscrew sprockets. A
torque wrench attached to the end of the spanner wrench will
permit measurement of the system's required torques prior to
installation of the positioning system.

In the event the vertical deployment is restricted such as shown in Figure
1.3-22, the following assembly variations relative to the foregoing are
imposed.

(a) Pertinent to operations 15 through 37, the upper bays can be
manually folded, provided the aforementioned counterbalancing
requirement is satisfied during deployment and retraction,
adequate support is provided for the bay being manually folded,
and upon retraction the folded bays are manually redeployed prior
to retraction with adequate support provided.

(b) Folding will be accomplished by manual tripping of the diagonal
and longeron latches, with latch retention maintained by a
suitable GSE device that will free the technicians for other tasks.

38. Deploy Bays 1 through 5 and install the tray assemblies in Bays 4 and
5, respectively.

39. Retract and deploy Bays 4 and 5 to assure trouble-free operation.

40. Perform item 40 as previously described pertaining to adjustment of the
detents.

41. Reorient the stowed configuration and manually deploy Bays 1 through 10
to the configuration shown in Figure 1.3-23.

42. Install the precompression system and manually deploy and retract all
bays to assure tension system cables do not interfere with deployment
and retraction.

43. Install the three drive motor assemblies. Reorient the configuration
to that shown in Figure 1.3-21.

44. Perform the positioning system motor and computer adjustments. Upon
completion retract the remaining structure and install the
adapter/housing four "S" fittings.

Figure 1.3-22. Test Article Assembly Configuration with Headroom Restructions

Figure 1.3-23. Precompression System Installation Configuration

1.3.4 Deployment/Retraction Operations

This section provides a detailed description of the means by which the previously described design accomplishes controlled, automatic, bay-by-bay deployment and retraction. While much of the forthcoming figures illustrate the test article in a horizonal attitude for drawing convenience, the deployment and retraction are most easily accomplished in the vertical mode as suggested in Figure 1.3-24.

1.3.4.1 Stowed Configuration

Figure 1.3-25 illustrates a section through the test article in the stowed position. The adapter is nested to the jackscrew support frame which is captured between the adapter and housing. The adapter is fastened to the housing with eight eye-bolts into the four "S" fittings. Battens 1 through 9 are captured (Figure 1.3-10) between the four rails as shown at the right, with each of the four half-nut threads engaged with each of the four stowed jackscrews. Battens 2 through 9 (all except Batten 1), have the eight detents per batten engaged. Finally, Battens 1 through 9 are positioned fore and aft such that they bear against each other, with Batten 9 bearing against the truss attach fitting.

1.3.4.2 Deployment of Bay 1

The deployment operation starts with removal of the eight eye-bolts and the start of clockwise rotation of the drive motor that rotates the four batten deployment/retraction system spline shafts which rotate the threaded jackscrews. The kinematics is best explained by the analogy of a bolt and nut (Figure 1.3-26). Clockwise rotation of the bolt with the nut constrained from moving aft will result in forward motion of the bolt. Since the batten half-nuts are constrained from moving aft the jackscrew and attached carriage are pushed outward, i.e., to the left (Figure 1.3-25). Continued rotation will continue to drive the jackscrew and carriage to the left. At $196 + .001$ revolutions, the carriage locking pin, for each of the four carriages will be automatically engaged locking the carriages fore and aft. Concurrently, the jackscrew support frame and adapter have been driven forward. The forward motion of the adapter unfolds the four longerons and extends the four telescoping diagonals attached to it. The forward motion of the jackscrew support frame assembly extends the four telescoping tubes attached to it. At carriage locking, through the adjustments described in the assembly operations, the 12 members previously described will all be locked. The configuration is as shown in Figure 1.3-27 with Bay 1 developed, and the jackscrew support frame assembly rigidized. It is pertinent to note that the jackscrew threaded length is such that the Batten 1 half-nuts are on the aft 101.6 mm (4 in.) of the jackscrews. This phased development is noted as (1) on Figure 1.3-31.

VARIABLE
WEIGHT

SUPPORT
FIXTURE

Figure 1.3-24. Deployment/Retraction
Operations Configuration

BATTEN

HOUSING

STOWED CONFIGURATION

BATTENS

HALF NUT

ADAPTER

FOLDED LONGERONS

RAIL

SPROCKET

CARRIAGE LOCKING PIN

JACKSCREW
SUPPORT
FRAME
ANNUALR GROOVE IN JACKSCREW

HOUSING FRAME

CARRIAGE

SPLINED
SHAFT

Figure 1.3-25. Test Article Packaged Configuration

Figure 1.3-26. Bolt/Nut Analogy at Batten Deployment/Retraction System

Figure 1.3-27. Configuration at Deployment of Bay 1

1.3.4.3 Deployment of Bay 2

The analogy of the bolt and nut can also illustrate the deployment of Bay 2. For this stage of deployment the analogy consists of the bolt restrained longitudinally. A counterclockwise rotation of the bolt will advance the nut forward. The carriage locks restrain the jackscrews; however, there is no constraint against forward motion of Batten 1 which is engaged with the jackscrew. Batten 2 is held in place by the eight detents. Deployment of Bay 2 commences, therefore, by the commuter commanded drive motor rotating the four jackscrews counterclockwise. This rotation and the engagement with Batten 1 drive Bay 1 forward overwhelming the ball detents (on the drogue) that previously restrained the adapter. Batten 2, however, is held in place by the detents. The rotation is continued until 196 + .001 revolutions are counted by the encoder. It is pertinent to note that the encoder counting accuracy of + .001 revolution represents a longitudinal positioning accuracy to .0064 mm (.00025 in). At completion of the 196 + .001 revolutions the longerons and diagonals are locked completing the deployment of Bay _ to the configuration shown in Figure 1.3-28. This phase of deployment is represented as (2) in Figure 1.3-31. In this configuration Batten 1 is fully engaged with 101.6 mm (4 in) of the jackscrew forward end. Specifically, the forward face of the half-nuts is at the forward face of the jackscrew thread. The forward face of the four half-nuts on Batten 2 is at the aft edge of the jackscrew.

1.3.4.4 Deployment of Bays 3 and 4

The deployment of Bay 3 starts with the counterclockwise rotation of the four Batten deployment/retraction jackscrews. Through engagement of Batten 1 with the jackscrew, as in Bay 2, the rotation drives the completed Bay 2 forward by overwhelming the eight detents restraining Batten 2. The total restraining force (longitudinal component) of the detents can be set to vary from 180 to 1780 N. Since the half-nuts are 101.6 mm (4 in) wide during the first 16 revolutions both Batten 1 and 2 half-nuts are engaged with the jackscrew. After 16 revolutions only Batten 2 is engaged. Upon completion of the 196 + .001 revolutions Bay 3 is complete and is designated by (3) on Figure 1.3-31. At completion the Batten 2 and Batten 3 (held by detents) are located as shown in Figure 1.3-32

1.3.4.5 Deployment of Bays 4 through 10

The deployment of Bays 4 through 10 is accomplished in the same manner except that the completed bay is located further and further aft, i.e., closer to the aft attach fitting. This is because the aft Batten at any completed bay is located as shown in Figure 1.3-33. The only other exception is that the carrier bay being 1.09 m (43 in), i.e., center to center of the Battens and containing 152.4 mm (6 in) half-nuts needs to advance only .94 m (37 in) to deploy. Hence, the number of revolutions shown on Figure 1.3-31 for phase (6) is 148 revolutions.

1.3.4.6 Precompression System Operations

Upon completion of deployment the precompression system can be manually activated to apply and deactivated to remove the precompression loading.

1.3.4.7 Retraction of Bay 10

The retraction operation starts with activation of each of the diagonal and longeron unlocking systems (Figure 1.3-29). Since the tripping devices are set 25.4 mm aft of the bay longeron and diagonal latch faces, rotation of the jackscrews with a pitch of 5.08 mm (.20 in.) advances the probes to contact the latches. Continued rotation advances the tripping devices which rotate the latch mechanisms that depress the locking pins. At the proper phasing (to be determined during the ground test deployment/ retraction operations) the batten deployment/retraction jackscrews will be rotated clockwise (Figure 1.3-31). The rotation through engagement of the four half-nuts of Batten 9 will drive Batten 9 aft towards the housing. In the initial stages the batten closure further depresses the locking pins. The rotation continues until Batten 9 is driven into the housing and over the detents and repositioned. The spring activated detents again retain the batten. At 225 rpm the retraction of Bay 10 will occur in approximately 52 seconds. During the first 16 seconds (approximately) the unlocking systems continue to advance forward until 20 revolutions are completed and the tripping devices are 25.4 mm from the face of the Bay 9 longeron and diagonal latch mechanisms.

1.3.4.8 Retraction of Bays 9 and 8

The retraction of Bays 9 and 8 is accomplished in the same manner as Bay 10.

1.3.4.9 Retraction of Bays 7 and 6

The retraction of Bay 7 is the same as Bays 8, 9, and 10, except as shown in Figure 1.3-31, the unlocking systems are returned to the same position as at the start of retraction. This is due to the difference in length of the next bay, i.e., the carrier bay, and the Batten 6 half-nut length of 157.4 mm (6 in). This is illustrated by Figure 1.3-34, and the following calculations for Δa which represents the required advancement of the tripping devices. The advancement from the start of Bay 7 to the start of Bay 6 retraction is determined from the equations:

$$\Delta a = \frac{H_6}{2} + \frac{H_7}{2} + \frac{\ell_7}{2} - \frac{\ell_6}{2}$$

$$\Delta a = 50.8 + 76.8 + 495.3 - 622.9 = 0$$

The advancement from the start of the Bay 6 retraction to the start of the Bay 5 retraction is similarly determined as:

$$\Delta a = 76.8 + 76.8 + 622.9 - 495.3 = 281.2 \text{ mm (11 in)}$$

The 55 revolutions shown in Figure 1.3-31 accomplishes the required 281.2 mm (11 in) of travel.

1.3.4.10 Retraction of Bay 5, 4, 3 and 2

The retraction of these bays is accomplished in the same manner as that described for Bay 10.

Figure 1.3-28. Configuration at
Deployment of Bays 1 and 2

Figure 1.3-29. Configuration at
Start of Bay 10 Retraction

Figure 1.3-30. Configuration at
Start of Retraction of Bay 1

Figure 1.3-31. Positioning System Motion Profile

Figure 1.3-32.   Batten 2 and 3 Positions
at End of Bay 2 Deployment

Figure 1.3-33.   Location of Battens 1 through 7

Figure 1.3-34. Description of Unlocking Systems Required Advancement

1.3.4.11 Retraction of Bay 1

The retraction of Bay 1 is unlike that of the other bays. The retraction starts with manual unlocking of the four carriage locking pins and four jackscrew support frame diagonals and advancement of the unlocking systems to unlock the Bay 1 four longerons and four diagonals. At the proper phasing (to be determined in the ground tests) the deployment/retraction batten system motors are rotated counterclockwise 32 revolutions thereby retracting Bay 1 203.2 mm (8.0 in). Any further retraction is delayed until the extended unlocking system carriages are retracted back into the housing (210 revolutions). At the appropriate phase the remaining 164 batten system jackscrew revolutions are accomplished thereby completing the retraction of the structure. At this point insertion of the eight eye-bolts can reattach the adapter frame to the housing.

1.4 TEST ARTICLE MASS PROPERTIES

To support the planning of a future ground test program and future space applications studies a mass properties analysis was performed. The results of the analysis are summarized in Table 1.4-1. The masses shown were determined by detailed mass properties analyses of all the drawings, except for the adapter, utilities tray, and jackscrew support frame assembly which were estimated from the original layouts. The values shown represent the calculated masses with no allowance for tolerances.

It is also pertinent to note that minimum cost of the test article was regarded as more significant than minimum mass, provided there was no compromise in the represantation of concept performance. For example, the four rails in the batten deployment/retraction system are heavier than necessary to minimize machining cost without any deleterious impact on performance. The same is true for the main housing structure which is fabricated with 2.3 mm skins to minimize the addition of stringers for panel stiffness.

Table 1.4-1 also illustrates the potential mass reduction associated with removal of the systems required for retraction. Figure 1.4-1 illustrates the scope of those reductions.

1.5 STRUCTURAL ANALYSIS

The structural analyses performed during the Part 2 phase of this contract directed the subject ground test article's conceptual and detailed design. This section describes the structural requirements concept reviews, and an overview of the major analyses performed to assure design compliance with the requirements. A copy of the detailed structural analyses, performed to support the drawing production, is contained in the Volume III Appendix.

1.5.1 Requirements

Figure 1.5-1 illustrates the major limit-loads location and orientation that established the design internal loads. These are the loads that will be applied to the ground test article at the conclusion of deployment/retraction, stiffness, and modal survey tests.

Table 1.4-1. Test Article Predicted Mass (kg)

COMPONENT	NO. OF PARTS	TOTAL MASS	MASS WITHOUT RETRACTION SYSTEM
DEPLOYABLE TRUSS	1	384	349
•LONGERONS	40	138	114
•DIAGONALS	44	133	122
•BATTENS	9	83	83
•CARRIER	2	30	30
ADAPTER *	1	47	47
DEPLOYMENT/RETRACTION SYSTEM	4	185	185
JACKSCREW SUPPORT FRAME ASSEEMBLY *	1	26	26
MAIN HOUSING & EQUIPMENT	1	315	233
•STRUCTURE	1	200	199
•UNLOCKING SYSTEMS	8	55	0
•PRETENSION SYSTEM	1	14	14
•MOTORS & EQUIPMENT	3	46	20
UTILITIES TRAYS *		21	21
•CARRIER	1	10	10
•TYPICAL	1	11	11
TOTAL		978	861

DIAGONAL UNLOCKING SYSTEM

LONGERON UNLOCKING SYSTEM

REMOVABLE SYSTEM

SHADED AREA DENOTES DELETED PARTS

ASSOCIATED MOTORS, ENCODERS, TACHOMETERS, MICROMOTION MOUNTS, CHAIN & SPROCKETS NOT REQUIRED

Figure 1.4-1. Retraction System Equipment Deletion
for Design Without Automatic Retraction

The significant structural requirements are listed as follows:

o The structure shall sustain without detrimental deformation:

    (1) The loads occurring during deployment in the vertical or horizontal mode (with appropriate supports during deployment).

    (2) The worst combination of the internal loads derived from the loading shown in Figure 1.5-1 in conjunction with limit precompression system loads.

    (3) The placement of the 3636 kg simulated payload carriers supported as shown in Figure 1.3-18.

    (4) A 6g acceleration applied to the stowed configuration along any of the three major axes (one axis at a time). This is representative of the Shuttle quasi-static launch load environment.

o The structure shall sustain the above conditions upon application of ultimate load. The ultimate loading is the above described limit loading mutiplied by a factor of 1.5.

o Provide a minimum natural frequency, in the stowed configuration, of 10 Hz. This requirement is to provide frequency separation with the orbiter to minimize quasi-static loads to no more than 6 g.

o Provide a design minimum natural frequency, in the deployed configuration shown in Figure 1.3-18, of .10 Hz. This requirement is applicable to the configuration with the precompression system cables tensioned to 1780 N.

o Perform trouble free deployment/retraction operations in a controlled environment, i.e., room temperature ± (10°C)

1.5.2 Concept Reviews

The significant concept structural analysis reviews that directed the design to its present form are described herein.

1.5.2.1 Truss Configuration

The selected truss member arrangement was determined from consideration of the two major options shown in Figure 1.5-2. Configuration (a) represents a design in which the member arrangement permits all the joints to be identical. This configuration also has all the diagonals oriented in the same sense with regard to the approach of the diagonal unlocking tripping devices. These two advantages, however, were less significant than the advantages of the selected configuration (b). The most significant advantage, and alone sufficient to favor selection of configuration (b), is that precompression of the longerons, by the precompression system, will also induce compression in the diagonals. In configuration (a) there can be no precompression of the diagonals since it would create an unbalanced torque. In this case the shortening of the longerons is accommodated by torsional rotation of the batten frames. The selected configuration also experiences reduced longeron loads due to torsional moment. For the applied limit loads shown in Figure 1.5-1, the total longeron load is reduced by 17%.

Figure 1.5-1. Major Structural Requirements

Figure 1.5-2. Candidate Truss Arrangements

With the selected configuration no loads are imposed on the batten members by the diagonals, which, in conjunction with the reduced longeron loads, provide increased torsional stiffness and hence a higher torsional frequency.

The arrangement and configuration of the diagonals within the battens were also studied, particularly in relation to the development of precompression of the major truss diagonals. A pair of X-braced tension cables, as configured in the Part 1 selected design, does not provide the required AE to develop sufficient precompression in the truss major diagonals. The phenomenon is illustrated in Figure 1.5-3. The development of precompression in the diagonals is dependent on the extensional stiffness of the batten since any induced compression in the diagonals would have the resultant loads shown in Section A-A. The most direct approach is to place the diagonal along the line of the resultant load, thereby negating the flexibility of members 1-2, 2-3, 3-4, and 4-1. Hence, placement of the batten diagonal along the lines of the resultant force is the selected design for each batten frame. The sensitivity of the developed diagonal compression force to variations in the design are shown in the table of Figure 1.5-3.

1.5.2.2 Precompression System Concept

A precompression system utilizing a pair of bungees and tension cables was chosen as the method to remove joint slop because it is current technology, and, hence compatible with the goal of FY 1986 technology readiness. The removal of joint slop is required not only to preclude a loss of stiffness but also, and most important, because a structure with slop is dynamically unpredictable. Another significant advantage of the precompression system is that it permits joint slop during deployment. This is very advantageous to the in-space deployment of the prototype design, which is indeterminate, since it can accommodate the member length changes (graphite composite members) during deployment. An indeterminate structure with no joint slop during deployment, experiencing thermal-induced length changes, will not deploy unless adequate force is used to accommodate the dimensional changes by internal load induced deformation. A determinate structure can deploy with tight joints, provided there is no binding, without any forces required.

The precompression system is designed to induce and maintain sufficient precompression in the longerons and diagonals, throughout the application of control system loadings, in systems for which precise control is required. Rockwell's large space structures studies (References 2 and 3) have indicated these forces generally result in longeron and diagonal loadings below 1600 and 200 N respectively. A simple example that illustrates this is that of a cantilevered square truss 50 m long and 1.25 m deep. RCS thruster forces can be 4.45 N (1.0 lb) or at most 44.5 N (10 lb). A 44.5 N force shear exerted at the end of this beam would result in a longeron load of 890 N (neglecting shear relief due to acceleration of the payload mass). The worst diagonal forces would be due to torsion. To exceed the 200 N precompression, two equal and opposing thrusters of 44.5 N would have to be 7.90 m apart. The exception to the foregoing are loads incurred during hard docking. The control requirements for hard docking, feasibility of berthing, or attenuation is beyond the scope of this study. Assuming that the control requirements during hard docking do not require precompression throughout the structure, a tension in the precompression system cable of 1780 N was established. This does not mean that higher values are not possible. However, higher precompression loads result in higher total longeron and diagonal design loads.

The system contains a pair of compression springs that each have a spring constant of approximately 88 N/cm. The low spring constant will minimize variations in the precompression of a future flight article despite differential strains between the longeron and cable due to either load, thermal variations or creep. For example, a 30°C uniform temperature change in an aluminum longeron (worst case) would cause a total length change of 9.5 mm, and a load change of 83 N which is a percentage change of 4.6, which is certainly acceptable.

1.5.2.3   Concept Suitability-Launch Loading

Figure 1.5-4 illustrates the pertinent features of the prototype design in the stowed configuration. Any of the three orientations relative to the orbiter are possible. Referring to the references axes shown in the figure, the following comments are appropriate to the support of the components for loads directed along the X-axis.

o   For a prototype design the adapter will be latched to the main housing with latches designed for the peak X-axis loading.

o   The jackscrew support frame is captured between the adapter and main housing.

o   The screwjacks and carriage are constrained by the pawl (Fig 1.5-4).

o   The battens are constrained (forward) by the half-nut engagement with the screwjack and (aft) by bearing on the truss attachment fittings. The half-nuts of all the adjacent battens are in contact during launch.

o   The longerons are constrained by bearing on each other with transfer of load to the transverse beams on the adapter (forward) or on the transverse beams (aft) on the housing.

o   With a full complement of utilities trays, the trays are constrained by bearing on each other with transfer to the same end beams used to support the longerons.

o   The diagonals and battens are constrained by their end clevis attachments to the half-nuts and each acts as simple beams between the ends.

The following comments are appropriate to the support of the components for loads directed along the Y and Z axes.

o   For a prototype design Y and Z directed loads will be transferred from the adapter to the jackscrew support frame and into the main housing through bearing on suitable shoulders between the components.

o   The jackscrews are constrained at their ends by bearing on the adapter and attachment to the carriage which is laterally supported by the guide rail. The jackscrew acts as a beam between these two ends.

o   The battens are constrained by the half-nuts bearing on the faces of the rails (Figure 1.3-10).

MINIMUM DIAGONAL COMPRESSION (N)
DUE TO 1780 N PRETENSION

BATTEN DIAGONAL	1.52 mm WALL	3.05 mm WALL
AT 1-3	147 N	—
AT 2-4	258 N	320 N

Figure 1.5-3. Batten Diagonal Load Paths

Figure 1.5-4. Potential Launch
Configuration Features

o   The longerons are constrained by the fittings provided on the utilities
    trays (Figure 1.2-2).

o   The trays are constrained by the support provided by the batten members
    (Figure 1.2-2).

o   The diagonals and batten individual members are constrained by their
    end clevis attachments to the half-nuts and each act as simple beams
    between their ends. The longeron halves act as simple beams between
    their end clevis attachment and the attachment to the utilities trays.

1.5.2.4 Root Strength During Deployment and/or Retraction

    Figure 1.5-5 illustrates the load path during deployment operations
subsequent to deployment of the jackscrew support from assembly. (The load
paths during deployment of the jackscrew support frame assembly were discussed
in Section 1.3.1.3.) Bending moments about the pitch or yaw axes are
transferred from the truss longerons of the last deployed bay to the half-nuts
and onto the jackscrews through bearing on the engaged threads. This results
in axially applied loads to the jackscrew which are transferred to the
carriage and into the rails through the carriage locking pins. The rails
transfer the load into the housing through attachment to the frames. Lateral
shear, or torsion induced shears, are transferred from the diagonals of the
last deployed bay to the jackscrews through bearing from the half-nuts. The
lateral load is transferred through bending of the jackscrew to the carriage
and to the jackscrew support frame. The lateral load at the carriage is
transferred into the rails through bearing on the carriage ears. The lateral
load at the jackscrew support frame is transferred to the housing frames
through the diagonal braces. During retraction operations, prior to
retraction of the jackscrew support frame assembly, the same load paths are
available.

1.5.2.5 Dimensional Compatibility - Spacing of Adjacent Batten Half
         Nuts/Pitch o. Jackscrew Thread

    A critical requirement of the mechanization system is the maintenance of
the longitudinal distance between the corresponding points on the half-nut
threads of adjacent battens (for each of the four pairs of half-nuts) with the
mating threads on the jackscrews. Failure to satisfy this requirement would
preclude engagement of the aft batten half-nuts during deployment, and
engagement of the forward batten half-nuts during retraction. The requirement
and the design solution are illustrated in Figure 1.5-6. The thread of the
half-nuts has a radius 1.57 mm (.063 in) larger than the jackscrew. The
larger radius with a 1.57 mm radial separation will provide a 0.76 mm (.030
in) longitudinal clearance when assembled as described in Section 1.3.3. This
is accomplished through adjustment of the longeron and diagonal turnbuckles.
This assembly will be accomplished in a room temperature environment of 24 $\pm$
10°C (75 $\pm$ 18°F).

Figure 1.5-5. Load Paths During Deployment/Retraction

Figure 1.5-6. Adjacent Half-Nut to Jackscrew Clearances

Deployment and retraction operations should be performed in the same environment. The three potential future deviations from the assembled condition can be due to length changes from differential thermal expansion, jackscrew pitch variation as the battens move along the jackscrew, and longeron joint slop affects on longeron length.

o The worst case for thermal expansion would ˑ assemble at 34°C and deploy/retract at 14°C or the opposite extreme ndition. A 20°C temperature change will result in a 0.30 mm (0.012 in) differential length change over the 1.35 mm length.

o For the typical bay of 1.35 m the half-nuts adjacent battens are both engaged for a length of 50.8 mm (2 in) while for the carrier bay this length is 203.2 mm (8 in). In both cases this ..s half the full travel length but representative of the deviation from the assembled condition (Section 1.3.3). Reference 4 indicates the maximum jackscrew pitch variation across 203.2 mm is 0.018 mm (0.007 in).

o The potential change in length, of the longeron, due to joint slop at the two end clevises and two center pivots pins (4 pins, 8 holes) is 0.16 mm. This was determined by calculating the maximum gap between each smallest pin and the two largest holes and taking the square root of the sum of all the squared values of the gaps.

Numerical addition of the 0.30 mm, 0.018 mm, and 0.16 mm deviations results in a total of 0.48 mm, which is less than the initial value of 0.76 mm and acceptable.

From the foregoing discussion, however, it is evident that it is critical to maintain the radial separation of 1.57 mm between the threads of the half-nut and jackscrew. A closer view of this problem indicated a small increase (0.34 mm) in the radial separation is permissible since it does not decrease the longitudinal clearance of 0.76 mm, and engagement is maintained at the sides and most of the half-nut. A decrease in the radial separation of the threads does decrease the longitudinal clearance.

During deployment this concern is applicable at the aft face of the jackscrew thread, where the aft batten comes onto the jackscrew. During retraction this concern is applicable at the forward face of the jackscrew thread, where the forward batten must mate with the jackscrew.

For the aft region, during assembly, the rails can be shimmed laterally 0 to 0.05 mm of true position. Arithmetic additions of the tolerances between the rail to the carriage and the carriage to the jackscrew add up to ± 0.175 mm (laterally). For the forward end the jackscrew support frame, ferrule locations (Figure 1.3-12) and ferrule to jackscrew thread tolerances arithimetically add up to 0.165 mm laterally. The batten half-nut location thread tolerances add up to ± 0.30 mm (lateral). A statistical calculation of the resultant radial (not lateral) deviation is 0.34 mm (0.0136 in).

Since all the structure affecting the lateral stability of the ground test
article is aluminum, no significant differential thermal distortions are
anticipated. For a prototype flight article using low CTE materials the same
conclusion applies.
However for a flight article with an aluminum housing and truss, a detailed
thermal analysis is required to determine the magnitude of differential
thermal distortions. This will determine whether it is necessary to decrease
the pitch of the jackscrew thread to 9.5 or 12.7 mm (0.5 in.) to achieve a
thread depth up to 6.35 mm. This would permit an increased radial separation
and longitudinal thread gap up to 1.5 mm. This does not preclude the need for
a thermal curtain (Section 1.3.2).

A radial closure of 0.34 mm will result in a reduction of the 0.76 mm
longitudinal gap by 0.14 mm to 0.62 mm. Since the foregoing analysis
indicated a total longitudinal closure of 0.48 mm, the design is adequate.

1.5.2.6 Torque Requirement for Deployment/Retraction System

The output torque required for the batten deployment/drive system of the
test article was determined for vertical deployment without any ballast. The
torque requirement was determined to lift a truss mass of 454 kg and overcome
a batten detent resistance of 1780 N. The equivalent force is 6230 N (1400
lb). The classical jackscrew analysis equations extracted from Reference 5
defines the required torque as

$$T = Wr \tan (\phi + \theta) \quad \text{where} \quad \tan \theta = \text{pitch}/2\pi r$$

and W is equal to 6230 N, r is the jackscrew radius of 25.4 mm, and ϕ is
determined from the coefficient of friction ($\tan \phi = .14$). Based on the
foregoing a peak torque requirement of 26 Nm was determined. The use of a
coefficient of friction of 0.14 is considered to be conservative. The
determination of the required output torque for the unlocking systems is
presented in Volume III.

1.5.2.7 Drive Chain Deformation Implications

The drive chain used is a Browning No. 35 (3/8 in. pitch) stainless-steel
roller chain. The tensile strength capability of this chain is 9345 N (2100
lb), with a life of 15000 hours. These capabilities are greatly in excess of
the requirements. Of concern was the magnitude of chain slop and axial
deformation in regard to its affect on the relative accuracy of the position-
ing of the jackscrews. The slop will be eliminated by a chain pretension from
223 N (50 lb) to 446N (100 lb). The peak maximum load in a chain due to the
maximum output torque is 845 N (Volume III). This is less than the chain
allowable working load of 934 N.

A total axial deformation of 0.467 mm was deter ined for the loads
developed in the chain due to the applied torque. This deformation, and an
additional 0.24 mm for wear (100 operations), will cause a deviation between
the longitudinal position of the worst jackscrew relative to the motor-driven
jackscrew of 0.014 mm (0.0006 in) which is acceptable.

1.5.2.8 Chain Drive Considerations

During operation of the three chain drive configuration shown on the top assembly drawings, it is essential that adjacent chains do not touch. Hence, any dynamic amplification must be limited to the clearance envelope provided. The forcing frequency of the chain is determined by NS/60 where N is the number of teeth on the sprocket and S is the sprocket revolutions per minute. The frequency at 225 rpm is 131 Hz and at 75 rpm is 44 Hz. A chain pretension of 445 N provides a minimum chain frequency of 12.8 Hz, i.e., an order of magnitude below that of the forcing frequency. Therefore, it is not practical to provide a chain frequency above the forcing frequency.

It is expected that buildup and decay of the shaft rpm will occur in no more than 2 seconds. This will result in a forcing frequency of 8 to 18 Hz for .15 second, i.e., the time for two cycles of chain vibration at 12.8 Hz. This is not expected to cause any significant amplification, in the presence of the 1g static loading. However, if the amplication is significant guide supports can easily be added during the assembly and checkout stage of the test article.

1.5.2.9 Test Article Internal Loads

A NASTRAN model of the ground test article from which the internal loads were established is presented in Figure 1.5-7. The model represents the configuration of Figure 1.2-1 and the loading shown in Figure 1.5-1 plus the addition of four 1780 N end loads representative of the precompression system loading. The design limit compression loads, obtained directly from the program are delineated as follows. The ultimate design values used are also shown.

Longerons	13,800 N limit, 20,700 N (4650 lb) ultimate
Diagonals	6,750 N limit, 10,125 N (2275 lb) ultimate
Typical Batten Members	0, 2,140 N (480 lb) ultimate
Batten Diagonal Brace	0, 1,000 N (225 lb) ultimate
Payload Carrier Batten	0, 13,350 N (3000 lb) ultimate

The 13,350 N column load capability is provided to permit use of a spreader beam (if necessary) below the truss to support the simulated payload carrier. It is derived from 1/4 the 3636 kg mass, and a safety factor of 1.5.

The model also indicated a peak lateral deflection of 43 mm (1.7 in), at point A (Figure 1.5-7) in the direction of the applied loads. The angle of twist, of the plane at point A, about the longitudinal axis was 0.9 degree. Further, for future ground test planning, the predicted spring constant is 400 N/cm.

1.5.2.10 Modal Analysis

A modal analyses was performed using the NASTRAN model shown in Figure 1.5-7. The 3636 kg simulated payload carrier c.g. was located as shown in Figure 1.3-18. The first, second, and third modal frequencies were 0.40, 0.405, and 1.4 Hz.

The first mode exhibited a combination of lateral bending and torsion. An analyses t, determine the sensitivity of the first mode value to payload . carrier moment of inertia variations indicated the following:

I_{xx}	I_{yy}	I_{zz}	First Mode Frequency Hz
3320 nm^2	3018 nm^2	1210 nm^2	0.410
6640 nm^2	6036 nm^2	2420 nm^2	0.408
13280 nm^2	12072 nm^2	4840 nm^2	0.400

1.5.2.11 Internal Loads - First Mode Behavior Modal Survey

For future test planning the internal loads anticipated for the longerons and diagonals during a modal survey are summarized in Table 1.5-1. The magnitude of the precompression in the longerons and diagonals depends upon the initial compression induced by the precompression system and the amplitude of steady state modal excitation. It is assumed that during the modal test only the lowest cantilevered mode of the truss will be excited. In order not to introduce any non-linearity in the system, i.e., sloppy joints, it is required that the longeron and the diagonals should always be in compression. The NASTRAN math model of Figure 1.5-7 gave the internal load distributions for cantilevered deflections of the truss. From this various amplitudes of excitation were selected, such that the longeron and the diagonal always remained in compression during the test. The mass of the truss was considered to be neglible compared to the mass of the payload.

A review of the table indicates all the members are in compression if the peak deflection at point A does not exceed 6.25 mm.

1.5.2.12 Diagonal Assembly Structural Analysis Issues

The diagonal assembly structural analysis reviews contained the following significant structural analyses and design concerns.

(1) During deployment, how much spring force is required during the last 6 mm of stroke to ensure full deployment of the spring activated locking pins?

(2) How much outward spring force can be tolerated by t . outer tube wall design?

(3) What are the load implications of the radial tolerance between inner and outer tube walls and the associated local tube stiffness affects?

(4) Was a room temperature cured adhesive joint suitable for attachment of the telescoping tube to the center joint fittings?

NASTRAN MODEL

Figure 1.5-7.   Test Article NASTRAN Model

Table 1.5-1.   Predicted Loads During Modal Survey

CONTROL MODAL DISPLACEMENT	CABLE PRECOMPRESSION (N)			
	0	450	900	1800
	ELEMENT MINIMUM AND MAXIMUM LOADS			
CRITICAL ELEMENTS				
• 1.56 mm				
1. LONGERON	±289	-645 -67	-1000 -423	-1713 -1135
2. DIAGONAL	±42	-106 -23	-171 -87	-300 -216
• 6.25 mm				
1. LONGERON	±1157	-1513 +801	-1869 +445	-2580 -267
2. DIAGONAL	±167	-232 +102	-296 +38	-425 -91

1-66

These questions were resolved as follows:

(1) A conservative estimate of the potential force required during the last 6 mm of stroke was determined a follows:

The major concern \ as applicable to a potential flight article using a low CTE diagonal of graphite composite. [(An aluminum design is expected to require a deployable curtain on the jackscrew support frame assembly (Section 1.3.2)]. The concern is generated from the potential thermal-induced change in one diagonal members length during on-orbit deployment. For a 60°C change, the change in length is estimated to be 0.13 mm (0.005 in.). For all other components being as-built the force capability in the diagonal needed to overcome this length variation was determined for the following NASTRAN Models (assuming no joint slop).

1st bay deployed	0 (structure is determinate)
In 2nd bay with 2 bays deployed	49 N
In 9th bay with nine bays deployed	73 N
In 10th bay with 10 bays deployed	124 N

The larger force in the 10th bay is due to the rigidity of the housing.

In the foregoing section, a potential longeron length change, due to joint slop was determined to be 0.16 mm. Using only 0.04 mm a virtual work analysis indicates that such a slop can accommodate the entire 0.13 mm variation. Therefore, the 124 N value was considered too high. A design goal of 73 N appeared more reasonable and was established (See Volume III). Friction effects are expected to be small by comparison.

(2) Analysis of an outer tube wall of 1.75 mm (0.068 in.) exposed to a force of 90N indicated a stress level of 1310 N/cm^2 (1900 psi). A gauge of half that value would experience four times that stress (still acceptable even for a composite construction design). The analysis was accomplished with a NASTRAN model. THe 90 N force represents the outward load of the compressed spring (Figure 1.5-8). The plunger head is rounded to reduce friction and contact stresses.

(3) Figure 1.5-9 illustrates the main features of the analysis to determine the implication of tolerance between the inner and outer center fittings and local stiffness affects on the strength of the diagonal tube. The concern is the potential magnification of the initial deflection as ultimate load is approached. The initial center deflection due to a radial gap of 0.125 mm (0.005 in.) between the inner and outer sleeve is 1.27 mm (.05 in). With provision of rings at the bearing lines, and accounting for ring local deflection, a peak deflection at ultimate load of 5.3 mm (.21 in) was obtained. The acceptable stresses compatible with this deflection are illustrated in Volume III.

(4) Figure 1.5-10 illustrates the test configuration and results of development tests performed upon three simulated bonded joints. The lowest developed strength was 5.3 times greater than the ultimate diagonal load.

17-7PH SPRING
15.7 mm DIA.
1.70 mm WIRE DIAMETER

82 N

82 N

Figure 1.5-8. Telescoping Diagonal
Spring Activated Plunger

10124 N

1.27 mm

10124 N

1793 mm

END RING LOADING

SYMM
AS ℄

P

P

Figure 1.5-9. Telescoping Diagonal
Column Loading Considerations

1-68

NOTE: APPLY MB0120-008 BOND PER
MA0105-305 GRADE A TO
TAPERED AREA OF PLUG AND TUBE

RESULTS

SPECIMEN 1 - 54735 N
SPECIMEN 2 - 64970 N
SPECIMEN 3 - 53400 N

(DESIGN BOND ALLOWABLE-
1' 9.2 N/cm² - ACTUAL STRESS
1 0 N/cm² TO 2207.2 N/cm²)

VENDOR WILL DO SAME
TESTS ON SAME SPECIMENS
PROVIDED BY ROCKWELL

*Figure 1.5-10. Telescoping Diagonal Adhesive
Joint Test Results*

1.5.2.13 Longeron Assembly (Drawing 42712-120)

The longern assemblies structural analysis reviews contained the following significant structural analysis concerns.

(1) During deployment are the spring forces provided during the last 1/2 degree of longeron rotation adequate to ensure side plate locking?

(2) Does the center joint side plate design, in conjunction with the reduced flexural stiffness in the rod ends, provide sufficient rigidity compatible with the required ultimate load?

(3) How much initial deflection is associated with the tolerances of the center joint design, and what are the consequences at ultimate load?

These questions were resolved as follows:

(1) The spring force in the plungers provide a lateral force of 47.9 N (10.7 lb). The couple arm is 110 mm (Figure 1.5-11) hence, a torque capability of 527 n cm is provided. The two major sources of opposing friction torque are the two rod end clevises and pivot pins. An upperbound estimate of the friction torque at each source is provided by the torque breakaway data in rod end bearings (Reference 6). For the rod ends used this value is 170 N cm thus requiring a total for breakaway of 680 N cm. Since the longerons are already in motion, the 527 n cm provided is expected to be adequate.

(2) Figure 1.5-12 summarizes the analysis method performed to verify the column suitability of the longeron design. A NASTRAN model of the center splice joint was made and used to join two halves of a constant moment-of-inertia tube. The column capability determined was used to define an equivalent flexural stiffness E_2I_2 as shown in the figure.

E_1I_1 represents the equivalent flexural stiffness of the earlier rod-end turnbuckle design. This hand analyses was performed using the equation shown where P is the critical column load. A value of 29,700 N was obtained. This analysis is based on the improved rod end to turnbuckle design which provides an increased E_1I_1 and a shorter effective length ℓ_1 (Figure 1.5-12).

(3) Figure 1.5-11 illustrates the tolerances upon which an analysis of the worst possible initial deflection, at the center of the longeron, was made. The initial deflection calculated was 3.63 mm by assuming the pivot pins and spring plungers have the minimum values and the sleeves the maximum values. Using an ultimate column capability of 29,700 N the magnified deflection at an ultimate load of 20,700 N was determined to be 11.95 mm from

$$\Delta_E = \Delta \left[\cfrac{1}{1 - \cfrac{P_{ult}}{P_{cr}}} \right]$$

BOLT DIA 6.299 +0.000
          -0.051 mm

20693 N

PIN DIA 17.435 +0.000 mm
              -0.015
HOLE DIA 17.475 +0.025 mm
              -0.000

110 mm

6675 N

6675 N

20693 N

6675 N

20693 N

9.7 mm

20693 N

6675 N

LOADS FOR TOTAL LONGERON

3338 N

+.000
PIN DIA 9.484 -.013 mm
HOLE DIA 9.525 .023 mm
             -0.000

10346 N   10346 N

3338 N

HOLE DIA 6.312 +.023 mm
              -0.000

3338 N   3338 N

LOADS FOR EACH OF 2 SPLICE PLATES

*Figure 1.5-11. Longeron Center Joint
Column Loading Considerations*

NASTRAN COLUMN STABILITY ANALYSIS

ℓ_1 ℓ_2 ℓ_2 ℓ_1

$E_1 I_1$ $E_2 I_2$ $E_1 I_1$

$(TAN \sqrt{P/E_1 I_1} \ell_1)$ $(TAN \sqrt{P/E_2 I_2} \ell_2)$ $\cdot\sqrt{E_2 I_2/E_1 I_1}$

HAND ANALYSIS

*Figure 1.5-12. Folded Longeron Column
Analysis Considerations*

where P_{ult} and P_{cr} are respectively the applied ultimate load and Euler column critical load and Δ_i is the initial deflection. The stress analysis based upon this condition is presented in the appendix of Volume III.

1.5.2.14 Diagonal to Batten Attachment Stiffness Analysis

While all the center lines of the longerons, diagonals, batten members, and batten diagonal braces intersect at a common point, the clevis to which the main diagonals are attached sustains shear and bending deformation during transfer of diagonal loads (Figure 1.5-13). The clevis configuration is as shown to provide clearance for the longerons. To assure that no significant loss of torsional stiffness would be incurred due to the aforementioned local effects the vertical deflection due to vertical sh   as determined as shown on the figure.

The percentage due to local affects (i.e., the last three terms) was less than 10% which is certainly acceptable.

PER BAY VERTICAL DEFLECTION DUE TO SHEAR IS

$$= \frac{SuL}{AE} + \int \frac{Mmdx}{EI} + 2\int \frac{Mmdx}{EI} + 2\int \frac{Vvdx}{GA}$$

(BASIC DIAGONAL)	(POST BENDING)	(LUG BENDING)	(LUG SHEAR)
= .556	+ .023	+ .015	+ .020 = .614 mm

REGION CONTRIBUTING TO DEFORMATION

LUG NOT ADJACENT TO LONGERON

LUG ADJACENT TO LONGERON

PREDICTED REDUCTION IN STIFFNESS
10%

Figure 1.5-13. Diagonal Clevic Deformation Implications

2. DEPLOYABLE VOLUMES

Space Station configurations developed in NASA and industry studies have depicted OTV hangars and manned modules (Figure 2.0-1). The OTV hangars are too large to be packaged into the orbiter, hence, the need for either a deployable cr erectable design. The size (approximately 8 m in diameter and 12.2 m long), however, does not invite the use of a space-fabricated design. Each of the manned modules presently configured is approximately 4.5 m in diameter and 12.5 m long and, therefore, can be placed into the orbiter without folding. This is accomplished at a significant increase in launch cost compared to a deployable manned module. For example, two manned modules, such as previously described, require two Shuttle launches compared to only one Shuttle launch of an equivalent deployable module. However, the deployable modules structural systems are more complex, require additional specific sealing techniques, and will require on-orbit installation of partitions and systems.

The goals of this deployable volumes study, for an OTV hangar, therefore, were:

o To establish the major design driver requirements for the OTV hangar design

o To develop candidate deployable and erectable OTV conceptual designs, that satisfy these requirements, utilizing hard shell and inflatable constructions

o To select for future development the most suitable of the developed designs. The selection was to be accomplished through a systematic/traceable process, similar to that used in Part 1.

The goals of this deployable volumes study for manned modules were:

o To obtain from the Rockwell Space Station study (Reference 7) and the NASA study documentation (Reference 8) the major design driver requirements.

o To define, through collection and collation of Rockwell's Space Station study, definition of a manned module, a description of a baseline non-deployable (conventional) manned module design.

o To develop a hard-shell deployable and an inflatable design that provide the same combined capability as the two baseline modules shown in Figure 2.0-1.

o To compare the developed deployable designs with the baseline design and to select the most suitable design through a systematic/traceable selection process similar to that used in the Part 1 study.

The OTV hangar concept development utilized the following information obtained from the Part 1 study:

o   The concept, developed in Part 1. of providing a Space Station docking port structure with ingress/egress between the station and hangar, with integral provision of an astromast for OTV ingress/egress, and integral umbilicals for fueling the OTV, was maintained.

o   Concepts 1, 3, and 6 developed in Part 1 (Figure 2.0-2) were developed in further detail.

o   The OTV hang:r unpressurized, deployed configuration concept was maintained in which with the aft end is open and oriented toward earth.

o   The pertinent questions raised in the Part 1 study concerning unpressurized inflatable structures were presented to Goodyear Aerospace Corporation for resolution (Reference 9).

The manned module development utilized the following information obtained from the Part 1 study:

o   The concept of a large rigid strongback, onto which either a deployable hard-shell or an inflatable shell is to be mounted, was maintained. Within this strongback are mounted the conglomeration of ECLSS air revitalization, humidity control, water reclamation, waste management, food preparation, electrical power, thermal control, and crew systems equipment.

o   Concepts 3 and 5, developed in Part 1 (Figure 2.0-3), were developed in further detail.

The study was directed by the following major goals:

o   Development of a design for the early 1990's i.e., a design requiring a minimum of technology development that can satisfy the requirements

o   Strive for minimum usage of orbiter cargo bay length

o   Utilize EVA where complexity can be significantly reduced

2.1   OTV HANGAR DEVELOPMENT

The development of OTV hangar design concepts was directed by the established requirements shown in Figure 2.1-1. These requirements represent the best information available at the time, which was during the early months of the series of Space Station contracts.

The drawings describing the concepts developed are contained in the appendix of Volume III.

All the concepts have an integrated central hub which contains the Space Station docking port with egress/ingress between the Space Station and hangar, an astromast, and OTV refueling probes. Upon OTV approach the astromast is extended outward to the forward edge of the hangar. Three extendible struts stored in the docking device, mounted at the forward end of the astromast

2-2

Figure 2.0-1. Potential Space Station
Configuration

Figure ... -2. Part 1 OTV Hangar Concept

• DEPLOYABLE SECTIONS SHOWN SHADED

Figure 2.0-3. Part 1 Manned Module Concepts

• LIFE OF 20 YEARS
• DOCKING PROVISIONS FOR ATTACHMENT TO SPACE STATION
• PERMIT CREW INGRESS/EGRESS FROM SPACE STATION
• PROVIDE FOR OTV BERTHING OR DOCKING, AND INGRESS/EGRESS
• PERMIT CAPABILITY OF ATTACHMENT OF OTV SERVICING, LIGHTING,
  ELECTRICAL POWER EQUIPMENT
• PROVIDE WORK PLATFORMS AND CLEARANCE (1 TO 1.5 m) FOR WORK SPACE
• PROVIDE CAPABILITY TO STORE SERVICE EQUIPMENT AND/OR SPARE PARTS
• PROVIDE DEBRIS/MICROMETEOROID PROTECTION FOR OTV
• PROVIDE RADIATION SHIELDING FOR CREW AND STORAGE EQUIPMENT
• PACKAGE WITHIN ORBITER DYNAMIC ENVELOPE AND SUSTAIN LAUNCH ENVIRONMENT

Figure 2.1-1. Baseline OTV Characteristics

2-4

extend radially to the inner face of the hangar platforms until bearing on the platform is developed. The astromast is laterally supported and therefore has sufficient flexural stiffness to sustain OTV docking. Upon completion of the docking maneuver the astromast draws the OTV into the hangar for servicing.

All the OTV platforms require longitudinal bracing and in-plane structural attachments to develop frame behavior in the platforms. In all the concepts this structural continuity of the frames is accomplished by EVA. In all the concepts, excepting only Concept 3, the longitudinal bracing is installed by EVA.

A detailed description of each of the concepts developed is as follows:

2.1.1 Concept 1 - Double-Folded Hard-Shell (Drawing 42712 - 1)

Figures 2.1-2 through 2.1-4 describe the major design features of Concept 1. Figure 2.1-2 illustrates the fully deployed configuration. The central hub fixture described above in this case also contains six telescoping braces used to laterally deploy the stowed configuration (Figure 2.1-3) to the first stage of deployment. The braces also provide longitudinal support to the OTV hangar shell. The shell is comprised of twenty-four 50 mm-deep graphite composite faced honeycomb sandwich panels packaged as shown in Figure 2.1-3. The panels utilize graphite composite face sheets to minimize thermal distortions for assurance of post-deployment locking of the latches shown in Figure 2.1-4.

In the folded configuration, which has a length of 5.6m, platform panels A and B are in different planes to permit folding. Platforms are provided at the two ends and as shown in Figure 2.1-2. To accomplish the folding shown and permit deployment, the panels in Bays 2 and 3, during deployment, are attached only along the common circumferential edges. Hence, the latched details are provided as shown on Figure 2.1-4. Details 1, 2 and 4 present the concept of the latches required for structural continuity of the shell. Detail 3 presents a concept for EVA installation of the struts as shown in Figure 2.1-3. The configuration is supported in the orbiter by the fittings shown. A band clamp is also provided.

2.1.2 Concept 2 - Double-Folded Curtain Shell (Drawing 42712-2)

Figures 2.1-5 through 2.1-7 describe the major design features of Concept 2. The deployed configuration is shown on Figure 2.1-5. Eight double-ended continuous longeron astromasts are used as the longerons to deploy the curtain shell construction shown in Figure 2.1-7 which uses 6.25 mm deep aluminum panels. The astromasts are laterally stabilized by sidewall frames at the ends and at the middle. During deployment the frames unfold radially as shown in Figure 2.1-5. A system of 16 sets of X-bracing is provided between the astromasts and frames to provide a trussed configuration. The X-bracing cables are tensioned by the final stages of astromast deployment. Discussions with AstroResearch personnel confirmed the feasibility of this approach. During and subsequent to deployment, the curtains span circumferentially to tension cables attached to storage reels mounted on the frames. Three sets of work platforms are attached to the folding frames as shown in Figure 2.1-6. Continuity of the frames is provided by self-latching devices or the frames. Installation of the longitudinal bracing supports requires EVA.

Figure 2.1-2.   OTVH Concept 1—Hard Shell Double Fold
(Fully Deployed Configuration)

Figure 2.1-3.   OTVH Concept 1—Hard Shell Double Fold
(Stowed and First Phase of Deployment)

Figure 2.1-4. OTVH Concept 1—Details

Figure 2.1-5. OTVH Concept 2—Curtain
Shell Double Fold Configuratior

Figure 2.1-6. OTVH Concept 2—Curtain Shell
Double-Fold (Stowed Configuration)

Figure 2.1-7. OTVH Concept 2—Curtain Shell Details

Similar to Concept 1, extendable Struts (telescopic braces) are provided to first laterally extend the packaged structure as shown in Section B-B of Figure 2.1-5. For this design eight struts are required, i.e., one for each astromast. Upon completion of this phase, and locking of the frame joint latches, the astromasts are mechanized to longitudinally deploy the structure.

The packaged configuration length as shown in Figure 2.1-6 is 3.6 m. A cradle is provided as shown in Figure 2.1-6 for support during orbiter launch. Fittings are also provided on the hub structure.

2.1.3 Concept 3 - Single-Fold Hard-Shell Design (Drawing 42712-3)

Figures 2.1-8 and 2.1-9 illustrate the major design features of Concept 3. This concept is primarily the simplification of Concept 1 achievable by deleting the longitudinal folding requirement at the cost of a significant increase in orbiter stowage length (14.5 m). While the significant launch cost penalty is appreciated, if a significant part of the available space shown can be used to place OTV spare parts, or other Space Station equipment, that penalty may be acceptable in consideration of the significant reduction of hangar complexity. In this concept the entire outer shell is monolithic except for the longitudinal hinges that permit the lateral folding shown. The panels are 50-mm-deep aluminum faced honeycomb sandwich structure panels. Thermal distortion in this design can be tolerated by the design of the common longitudinal hinges.

The platform panels A, are folded up against the flat outer shell panels to permit folding as shown in Section A-A, Figure 2.1-9. In the deployed configuration these panels A and B are in the same plane. Longitudinal braces can be ground-installed; however, EVA is required for on-orbit attachment of panels A to B, and adjacent panels A to each other.

As in the Concept 1 design six telescopic braces are provided for lateral deployment. The stowed configuration is shown in Figure 2.1-9 with provision for orbiter attachment.

2.1.4 Concept 4 - Erectable Hard-Shell (Drawing 42712-4)

Figures 2.1-10 through 2.1-12 describe the major features of this design. The outer shell of this design is built up from eighty-eight 18.8 mm (0.75 in.) deep by 1.2 m x 2.9 m graphite composite faced honeycomb sandwich panels. Here too, graphite composite construction is used to ensure minimal thermal distortion during the erection process. The deployed shell is stabilized by work platforms at the ends and center of the configuration built up from frame panels as shown in Figure 2.1-11 (Stage 6). All the panels are stowed into the storage container space within the work platform enclosure, as shown in Figure 2.1-12.

The construction is accomplished in the manner shown in Figures 2.1-10 and 2.1-11, Stages 1 through 7. Extension of the platform for construction is accomplished by the astromast shown, which also is used to provide ingress/egress for an OTV.

The construction is accomplished by two astronauts and will proceed as follows:

Referring to Stage 1, the platform container is extended to the position

Figure 2.1-8. *OTVH Concept 3—Hard Shell Single Fold*
(Fully Deployed Configuration)

Figure 2.1-9. *OTVH Concept 3—Hard Shell Single Fold*
(Stowed Configuration)

Figure 2.1-10. OTVH Concept 4—Erectable
Hard Shell Configuration Construction

Figure 2.1-11. OTVH Concept 4—Erectable
Hard Shell Configuration Construction

shown in Stage 2. The end-hinged stowed panels are deployed as shown in Stage 3 and joined to each other. The periphery of the end panels have provision for mounting of the first set of side panels as shown in Stage 4. The panels are fastened together by the studs shown in Figure 2.1-11 that are mounted onto a cable prior to attachment to the panels. Numerous other means for attachment are possible. The construction continues as shown in Stage 5. The placement of the panels is assisted by the guides and tabs shown in Figure 2.1-11. In Stage 6 the installation of the platforms is shown.

This construction has been conservatively estimated to require 105 man-hours for each of the two astronauts for a total of 210 man-hours. This includes 18 man-hours for the work platform deployments. The estimate is composed of a nominal time plus a 30% contingency time to account for delays and uncertainties. A total of five hours nominal time for suit donning and doffing is included for each six hours of EVA (or less when breaks seemed advisable in the sequence). With the eight-psi pressure suit, such don-doff time may be reduced to two hours or less per six hours of EVA. The preliminary concept for procedures and assembly hardware could probably be significantly reduced (perhaps by 25% to 50%) following further study and application of concepts using simple rods, tools, and latches, which would reduce the need for some crew relocation activity during assembly. Assuming a labor rate of $15,000 per man-hour the approximate cost for the worst case would be $3,150,000. With the use of a rotating platform, it is quite possible that this time can be reduced to 48 man-hours each, i.e., construction in six eight hour days. The cost would be reduced to $1,440,000.

This concept results in the smallest packaged length, i.e., 3.0 m. Support in the orbiter is provided at attachment fittings on the docking port and platform container.

2.1.5 Concept 5 - Inflatable Design (A drawing was not developed)

A drawing was not developed since adequate design definition is provided by Figures 2.1-13 to 2.1-15. This design was developed by the Goodyear Aerospace Corporation (GAC) under contract to Rockwell (Reference 9). The construction recommended by GAC is shown in Figure 2.1-14 and further defined by the following table.

ITEM	MATERIAL WEIGHT	
	GM/CM^2	LB/FT^2
Outer Cover (With Thermal Coating)	0.034	0.068
Interlayer Adhesive	0.005	0.010
Two Plies of Fiberglass	0.036	0.071
Interlayer Adhesive	0.005	0.010
Gelatin - Impregnated Scott Foam (64 mm)	0.375	0.750
Interlayer Adhesive	0.005	0.010
Two Plies of Fiberglass	0.036	0.071
Inner Coating	0.020	0.040
TOTAL	0.516	1.030

Figure 2.1-12. OTVH Concept 4—Erectable
Hard Shell (Stowed Configuration)

Figure 2.1-13. OTVH Concept 5—Inflatable
Concept Stages at Deployment

RADIAL SUPPORT ARMS
ROTATE AS HANGER IS
DEPLOYED

THICKNESS

64 mm

TWO PLIES OF
FIBERGLASS

HANGER SHELL
DURING RADIAL
DEPLOYMENT

STABILIZATION
STRAPS INSTALLED
BY EVA

POLYURETHANE MESH
CORE IMPREGNATED WITH
GELATIN RESIN FOR
RIGIDIZATION

TWO PLIES OF FIBERGLASS
WITH THERMAL COATING

CONSTRUCTION

⑤

⑥

COMPLETED
OTV HANGER

CIRCUMFERENTIAL
WORK PLATFORMS

Figure 2.1-14. OTVH Concept 5—Inflatable
Concept Stages at Deployment

PLATFORMS
STOWED

A

TOROIDAL TANK
AIR SUPPLY

DOCKING PORT
COVER

INFLATABLE
HANGER
STOWED

DOCKING PORT

HANGER
END RIBS

ASTROMAST
CANISTER

A

4.0 m

HINGE (8 PLACES)

RIB (8 PLACES)

STOWED
HANGER

4.6 m CLR DIA

SECTION A-A

Figure 2.1-15. OTVH Concept 5—Inflatable
Concept Stowed

2-14

The packaging and development of this structure are complex. The following concept is the result of a very preliminary study and should be considered as such. Inflation is used for controlled deployment and a gelatin system is proposed for rigidization. The work platforms are one meter wide and held in place axially by straps. Open areas are provided in the platform areas to permit suited astronauts to move axially in the hangar. Velcro, snaps, hooks, and straps can be installed as required to enhance maintenance operations. Rigid subsystems can be added once the hangar is deployed. Deployment of the structure will proceed as follows from the stowed configuration (Figure 2.1-15). The stowed configuration, which is best visualized as a "rolled-up sock," is pushed out of the stowage container by extension of the astromast which drives the covered docking port against the folded configuration (Figure 2.1-13 Stages 1 and 2). The air supply system (toroidal tanks) shown is used to inflate the "Chinese Whistle" longitudinal tube (Stages 3, 4, and 5). At this stage, continued inflation of the 64 mm sandwich develops the configuration to Stage 6. Subsequent to completion of Stage 6 the chemical process of the gelatin system provides final reigidization of the shell. EVA is required to connect the tension straps that stabilize the work platforms.

A potential problem is posed by the process used to package the structure into the container. A vacuum bag is positioned over the sandwich structure of the hangar shell. The vacuum bag is used to compress the foam sandwich. This may be the least understood part of the process. The rigid radial support arms are stretched along the hangar axis while the hangar skin is pleat-folded into a diameter compatible with the storage container. The inflatable tube is added to the pleated skin. The collapsed hangar skin is now rolled up like a window shade in the direction of the storage container. The rolled material is placed into the container and the rigid radial support arms are folded into position to hold the stored hangar in the rigid can. The potential problem is how to get rid of the vacuum bag after hangar deployment. A further unknown is what is the best way to initiate the rigidization process.

A major concern is the lifetime of such a structure. However, GAC (hence most likely any other firm) does not have sufficient test data to predict the lifetime of the proposed hangar materials in the LEO environment. Past projects have indicated a 5 to 10 year terrestrial storage and service life for these flexible structures; however, until actual on-orbit test data are evaluated it is rather difficult to predict a 20 year lifetime.

Stowage in the orbiter is accomplished as shown in Figure 2.1-15. Supports can be provided on the docking port and the stowage container. The packaged length is 4 m.

2.2 OTV HANGAR CONCEPT ANALYSIS

The analyses performed to support the concept evaluation process are briefly described herein.

2.2.1 Micrometeoroid/Space Debris Shielding

Figures 2.2-1 and 2.2-2 illustrate the significant issues pertinent to OTV shielding from the meteoriod and space debris environments. Figure 2.2-1 illustrates the vulnerable areas computed for the surface of the OTV. For the environments and probabilities of no impact the particle sizes, for which shielding is required, are shown. Unquestionably, there is great uncertainty in the validity of the debris model. Also, many Space Station system engineers believe advanced detection of such large debris particles and avoidance is preferable to attempts at shielding. The prediction of required shielding has the additional uncertainty illustrated by Figure 2.2-2, Section A-A. For one m wide platforms, the OTV shell is approximately 1.2 m away from the hangar wall. All the existing ballistic data for micrometeoroid particles are based on constructions in which the shielding is appreciably closer than 1.2 m, i.e., 0.05 to 0.1 m. There is no data at all for debris. In view of all the foregoing uncertainties, no analyses for debris was attempted.

For the micrometeoroid environment, the following analysis results are pertinent.

o The aluminum single-sheet thickness for Po = 0.99; for no penetration by a 7.4 mm diameter micrometeoroid, is 21.6 mm

o The combined effective sheet thickness of the OTV expected space-based construction shown is 3.2 mm

o For the total hangar wall construction the required bumper ballistic efficiency is 21.6/3.2 = 6.74

o The current ballistic efficiency for 50 mm spacings is 5; hence for 1.2 m, a value of 6.74 is readily achievable

The implications of the above are as follows:

o It is expected that all designs can be suitable for micrometeoroid protection

o The outer-shell mass required to provide protection may be less for designs with the greatest construction depth, thus providing greater cargo bay location flexibility. This is demonstrated as follows:

o A linear mass variation of 1078 to 2156kg/m satisfies the lauch envelope

o A T-bar comparable to 1078 to 2156 kg/m stowed in 3 m varies from 3.6 to 7.2 mm (0.28 in.).

Hence lightweight designs such as a T-bar of 3.6 mm can be placed anywhere.

Figure 2.2-1. OTV Hangar Man-Made Debris
and Micrometeoroid Design Implications

SECTION A-A

Figure 2.2-2. Micrometeoroid/Debris Model
Uncertainties for OTVH

2.2.2 Stress Analysis Review

All of the described designs were reviewed to satisfy structural design suitability. It is apparent the OTV hangar, during operation has minimal strength and stiffness requirements that are achievable with all the designs. The main output of the review was the inclusion, in the design, of all necessary structural components to satisfy astronaut foot loads, hard loads, placement of lighting and black box equipment, and OTV docking loads. The most stringent structural requirements occur during launch. A loads and stress analysis of the configurations was obviously beyond the study scope. However, during the development of each concept, the design was reviewed and driven to provide assurance of launch suitability. For example, Concept 2 required a retention cradle.

2.3 OTV CONCEPT SELECTION

Table 2.3-1 illustrates the selection process criteria used to evaluate the relative suitability of the five concepts developed. Tables 2.3-2 through 2.3-6 present the actual evaluations performed for each of the major and subselection criteria listed in Table 2.3-1. Table 2.3-7 provides a normalized summary of the major criteria 1 through 5.

Concept 4, the erectable design was selected on the basis of the data contained in Table 2.3-7 and the following judgmental observations:

o While Concept 1 is close (343) in total point value, its cost is $8.8 million higher

o In comparison with Concept 1, the erectable design has the highest potential technology transfer to other large deployable volumes

o While the inflatable design has great growth potential, the suitability of the proposed rigidization system is uncertain with no apparent potential for on-orbit remedial action in the event of a problem. Further the on-orbit life of the inflatable construction is not known.

It is also pertinent to mention the following additional observations.

o The current erectable design demonstrated the advantage of an erectable OTV hangar, but may not necessarily be the best erectable design.

o The on-orbit estimated construction time of 210 hours, with an EVA cost of $3.15 million, can be reduced through use of automatic latches and a rotating platform.

o A future study to resolve the above, directed toward development of a point design, represents the next logical step

Table 2.3-1. OTV Hangar Selection Process Criteria

```
(1) RELATIVE COSTS ($ MILLIONS)
    • LAUNCH          • TECHNOLOGY DEVELOPMENT
    • FABRICATION     ◆ EXTRA VEHICULAR ACTIVITY

(2) DESIGN VERSATILITY
    • CAPABILITY FOR
        - GROUND INSTALLATION OF EQUIPMENT
        - ON-ORBIT INSTALLATION OF EQUIPMENT ON SHELL
        - ON-ORBIT INSTALLATION OF EQUIPMENT ON PLATFORMS
        - ADDED PLATFORMS
    • POTENTIAL FOR SIZE GROWTH

(3) ORBITER INTEGRATION
    • CONSTRUCTION SUITABILITY
    • CRADLE COMPLEXITY
    • LAUNCH LOCATION FLEXIBILITY

(4) RELIABILITY OF STRUCTURAL RIGIDIZATION
    • SIMPLICITY OF JOINING
    • CAPABILITY OF REMEDIAL EVA
    • CONTROL DURING CONSTRUCTION
    • NUMBER OF MOVING PARTS/FUNCTIONS
    • CONFIDENCE FROM GROUND TESTS

(5) DESIGN/EVA/TECHNOLOGY DEVELOPMENT/LIFE RISKS
    • LEAST DESIGN RISK
    • MINIMUM EVA RISK
    • MINIMUM TECHNOLOGY DEVELOPMENT RISK
    • MINIMUM STRUCTURE LIFE RISK
```

Table 2.3-2. Relative Costs ($ Millions)

CONCEPT	LAUNCH		FAB.	TECH. DEV.	Δ EVA	TOTAL	TOTAL POINTS
	PACKAGE LENGTH (m)	COST*					MAXIMUM 100
①	5.6	23.5	2.0	-	0.5	26.0	81
②	3.6	15.0	2.0	-	0.8	17.8	99
③	14.5	60.8	1.5	-	0.3	62.6	0
④	3.0	12.5	1.0	0.5	3.2	17.2	100
⑤	4.0	16.8	0.5	2.5	0.5	20.3	93

*Launch cost for FY 1984 is $77 million.

Table 2.3-3. Design Versatility

CONCEPT	CAPABILITY— GRND INSTALLATION OF EQUIPMENT		CAPABILITY— ON-ORBIT INSTALL. OF EQUIP ON SHELL		CAPABILITY— ON-ORBIT INSTALL. OF EQUIPMENT ON PLATFORMS		CAPABILITY FOR ADDED PLATFORMS		POTENTIAL FOR SIZE GROWTH		TOTAL POINTS
	RANK	POINTS	RANK	POINTS	RANK	POINTS	RANK	POINTS	RANK	POINTS	
	MAX. POINTS 10		MAX. POINTS 20		MAX. POINTS 20		MAX. POINTS 10		MAX. POINTS 20		MAXIMUM 80
1	2	6	2	16	1	20	4	4	3	0	47
2	3	0	6	4	3	16	5	2	3	0	22
3	1	10	1	20	1	20	1	10	3	0	60
4	3	0	3	16	3	16	2	6	2	14	52
5	3	0	4	14	3	16	2	6	1	20	56

Table 2.3-4. Orbiter Integration

CONCEPT	CONSTRUCTION SUITABILITY		CRADLE COMPLEXITY		LAUNCH LOCATION FLEXIBILITY*		TOTAL POINTS
	RANK	POINTS	RANK	POINTS	RANK	POINTS	
	MAX. POINTS 10		MAX. POINTS 10		MAX. POINTS 30		MAXIMUM 50
1	1	10	1	10	1	30	50
2	5	3	5	3	4	10	16
3	1	10	1	10	5	0	20
4	1	10	1	10	2	20	40
5	1	10	1	10	1	30	50

*Due to weight implication from meteoroid shielding requirements.

Table 2.3-5.   Reliability of Structural Rigidization

CONCEPT	SIMPLICITY OF JOINING MAX. POINTS 10		CAPABILITY OF REMEDIAL EVA MAX. POINTS 30		CONTROL DURING CONSTRUCTION MAX. POINTS 10		NO. OF MOVING PARTS/FUNCTIONS MAX. POINTS 20		CONFIDENCE FROM GROUND TESTS MAX. POINTS 30		TOTAL POINTS MAXIMUM 100
	RANK	POINTS	RANK	POINTS	RANK	POINTS	RANK	POINTS	RANK	POINTS	
①	5	2	2	24	5	2	4	10	2	26	64
②	2	8	4	18	1	10	5	6	2	26	68
③	2	8	2	24	1	10	3	10	1	30	68
④	4	6	1	30	1	10	2	18	2	26	90
⑤	1	10	5	0	4	7	1	20	5	10	47

Table 2.3-6.   Design, EVA, Technology Development,
and Life Risks

CONCEPT	LEAST DESIGN RISK MAX. POINTS 10		MINIMUM EVA RISK MAX. POINTS 20		MIN. TECHNOLOGY DEVELOPMENT RISK MAX. POINTS 20		MIN. STRUCTURE LIFE RISK MAX. POINTS 30		TOTAL POINTS MAXIMUM 80
	RANK	POINTS	RANK	POINTS	RANK	POINTS	RANK	POINTS	
①	4	5	1	20	1	20	3	26	71
②	4	5	1	20	1	20	1	30	75
③	1	10	1	20	1	20	1	30	80
④	1	10	5	0	1	20	3	26	56
⑤	3	8	1	20	5	5	5	10	43

Table 2.3-7. Normalized Summary of
the Major Criteria

CONCEPT	COST	DESIGN VERSATILITY	ORBITER INTEGRATION	RELIABILITY	RISK	TOTAL POINTS
	MAX. POINTS	MAX. POINTS	MAX. POINTS	MAX. POINTS	MAX. POINTS	MAXIMUM
	100	100	50	100	100	450
①	81	59	50 ✓	84	89	343 ✓
②	99 ✓	28	16	68	94 ✓	305
③	0	75 ✓	20	88 ✓	100 ✓	283
④	100 ✓	65	40	90 ✓	70	365 ✓
⑤	93	70 ✓	50 ✓	47	54	314

✓ DENOTES CONCEPT HAS FIRST OR SECOND HIGHEST POINT VALUE

2.4 MANNED MODULE DEVELOPMENT

The manned module development consisted of definition of the two baseline modules portrayed in the Rockwell Space Station Configuration Studies (Reference 7) and the development of hard shell and inflatable designs that each accomplish the total functions of the two baseline modules. This approach was taken since it is compatible with the study goals, and ensures that the developed concepts could indeed be used in a Space Station configuration such as is shown in Figure 2.4-1. This approach also assures a proper comparison of the designs. For example, the two baseline modules equipment (as best defined) was placed into the two deployable concepts. The major requirements were, of course, the same as tabulated in Table 2.4-1. Attention is directed to the two goals listed in the table which are extracted from Reference 8. Both of these goals are satisfied by the two deployable concepts developed. Figure 2.4-2 illustrates a potential Space Station scenario utilizing the deployable modules. This scenario and the designs developed were coordinated with Space Station project and design personnel to assure satisfaction of the major requirements.

2.4.1 Baseline Space Station Conventional Modules (Drawing 42712-6)

Figure 2.4-3 illustrates the major design features of the baseline manned module design. Figure 2.4-4 illustrates the distribution of ECLSS, water purification, power, and hygiene systems equipment.

The baseline module is a classical welded aluminum cylindrical shell containing at each end a toroidal transition section to a conical shell. Each end of the conical shell contains a docking port. A horizontal floor is provided that is constructed of integrally machined floor plates and supported by longitudinal beams that span to three transverse beams. The three transverse beams are attached to three external frames that are welded or mechanically fastened (bosses) to the shell. The floor plates will be fastened to the shell to provide a shearflow path for the longerons that attach to the Orbiter. The pair of longerons are provided at the floor level and attach to the extension of the floor plates.

The outer shell construction is as shown in Figure 2.4-3. The array of equipment mounted above and below the floor is shown in Figure 2.4-4. One of the major design goals is essentially a smooth inner surface of the module wall to permit inspection and repair of micrometeoroid punctures. Therefore, much of the equipment, 1 to 2 m above the floor, may have to be supported by temporary bracing down to the floor. This remains a future problem area since the scope of the Space Station design has not evolved to that level of detail as yet. A summary of the preliminary mass properties prepared for the baseline module is presented in Table 2.4-2.

2.4.2 Deployable Hard Shell Manned Module (Drawing 42712-7)

Figures 2.4-5 through 2.4-7 illustrate the major features of the hard shell manned module conceptual design that is equivalent to two conventional baseline modules. For design commonality with an energy module, and for docking requirements, a pair of conical shells using toroidal transition sections are provided at each end of a central deployable section. If necessary, side docking ports can be installed on these end structures to

INITIAL

• 3 TO 4 MAN CREW

ALL UP

• 8 TO 12 MAN CREW

*Figure 2.4-1. Evolution of Initial to Growth
Space Station Configuration*

Table 2.4-1. Manned Module Major Requirements

• LEO	• 20 years
• LAUNCH/PACKAGING	• Compatible with the orbiter
• CREW	• 4 to 8 crewmen for 90 days + 21 days emergency
• ENVIRONMENT	• $10.5 \, n/cm^2$ and 18 to 24°C
• REDUNDANCY	• Two separate pressurized compartments • Two routes for ingress/egress
• MAXIMUM LEAKAGE RATE	• 0.22 Kg/day
• EQUIPMENT	• Life support equipment • Command Control Center • Two docking ports
• METEOROID PROTECTION	• 1990 Kessler space debris and NASA SP8013 micrometeoroid model
• RADIATION PROTECTION	• $0.50 \, gram/cm^2$
• Manned module design commonality (design goal)	
• Compatibility with evolution from initial to growth configuration	

DEPLOYABLE MODULE
DOCKED

BASELINE ENERGY MODULE
WITH SOLAR ARRAYS,
RADIATOR & DOCKING
MODULE DEPLOYED

DEPLOYABLE MODULE
(DEPLOYED)

ADDITIONAL
DEPLOYABLE MODULE
BERTHED

LOGISTICS MODULE
BERTHED TO DEPLOYABLE MODULE

*Figure 2.4-2. Potential Space Station Evolution
Scenario with Deployable Manned Modules*

MANNED MODULE

DESIGN COMMONALITY

RADIATORS

HABITAT MODULE - 12.2 m LONG

COMMAND MODULE - 12.2 m LONG

CONSTRUCTION

MLI

BUMPER
SUPPORT

25 mm MULTI-LAYER
INSULATION (MLI)

.125 mm
KAPTON

FRAME COVER
ENVIRONMENTAL SHIELD

.77 mm AL BUMPER/RADIATOR
SUPPORT

HEAT PIPE

PRESSURE SKIN
(3.6 mm ALUMINUM)

50 mm

ENERGY MODULE - 6.1 m LONG

Figure 2.4-3. Manned Modules Baseline Design Summary

Figure 2.4-4. Manned Module Conventional
Design Equipment Arrangement

Table 2.4-2. Baseline Conventional
Manned Module Mass (kg)

SYSTEM	MASS (Kg)
BODY STRUCTURE	4375
INDUCED ENV. PROTECT.	657
LAUNCH, RECOVERY & DOCK.	222
ORIENT, CNTLS/SEP, & ULLAGE	44
PRIME POWER	0
PWR, CONV. & DIST.	159
GUIDANCE & NAVIGATION	0
INSTRUMENTATION	207
COMMUNICATION	41
ENVIRONMENTAL CONTROL	2048
PERSONNEL PROVISIONS	1263
CREW STATION CNTLS & PNLS	88
RANGE SAFETY & ABORT	TBD
WEIGHT GROWTH ALLOW.	1682
PERSONNEL	TBD
CARGO	0
BALLAST	TBD
RESIDUAL PROP. & SERV. ITEMS	TBD
RESERVE PROP. & SERV. ITEMS	TBD
INFLIGHT LOSSES	TBD
TOTAL GROSS MASS (Kg)	10,786

Figure 2.4-5. Deployable Hard Shell
Manned Module Concept

Figure 2.4-6. Deployable Hard Shell
Manned Module Concept Details

accommodate the Space Station configuration shown in Figure 2.4-7 (bottom).
The deployable central section is comprised of a 1.8 m high x 4.2 m wide x 9.2
m long strongback structure onto which the pair of deployable cylindrical
shells is mounted as shown. The radius of the shells are equal to 2.08 m with
hinge lines A, B, C, and D oriented along the entire cylinder length. The
folding of the cylinder to suit the orbiter cargo bay diameter envelope is
shown in Section A-A. The four end bulkheads that provide closure at each end
of the pair of cylinders are shown in View B-B. Folding of the flat bulkheads
is accomplished such that each pair of flip-out panels is folded inward about
the vertical hinge line and then together with the fold-down panels are folded
inward and tucked under the ceiling. Upon completion of all four bulkheads
the cylindrical shells can be folded downward through rotation about the hinge
lines A, B, C, and D. Deployment would be conducted in the reverse manner,
with deployment of the cylindrical shells accomplished by a pair of jackscrews
for each shell mounted in a non-obstructing area of the floor. Fold-down and
flip-out of the panels and locking are accomplished by astronauts standing on
the strongback floors, securing latches such as shown in Section C-C and D-D
of Figure 2.4-8.

    The structural design of such a structure to withstand pressure induced
loads appears entirely feasible. The structural behavior of the cylindrical
section is essentially that of a double-bubble pressure vessel. As such, the
cylindrical shell experiences essentially PR loads, except at the ends where
local discontinuity moments will exist. The flat bulkhead design presents no
foreseeable unsurmountable problems. There will be, of course, a need to
extend the strongback structure into the transition conical shell. The
strongback structure must be designed to sustain any combination of loss of
pressure. Hence, the flat surfaces of the strongback are designed to sustain a
peak 1... atmospheric pressure differential. It is expected that numerous
transverse bulkheads will be used to permit satisfaction of this requirement.
The launch attachment fittings will also be mounted onto the strongback
structure.

    The construction used for the outer shell is identical to that defined for
the baseline design, and is shown in Figure 2.4-6. The end bulkhead panels
and strongback will be integrally machined panels stiffened by mechanically
fastened beams similar to the flat bulkhead of the STS orbiter crew module.

    Figure 2.4-7 illustrates the packaging of all the identified baseline
configuration equipment. Much of the equipment is packaged in the volumes
between the ceiling and cylindrical shell and between the two floors, i.e., in
the strongback. No problems pertinent to packaging of this equipment in these
regions was uncovered. However, it is apparent from Section A-A that equip-
ment can only be packaged between the ceiling and strongback as shown on
Figure 2.4-7. This equipment must be rearranged and secured after deployment
by astronauts.

    Any of the foregoing design concerns all appeared to have acceptable
potential solutions. However, the requirement of maintaining the total module
leakage to no more than 0.44 kg/day (Reference 8) appears most difficult in
view of the following comments.

*Figure 2.4-7. Manned Module—Deployable
Hard Shell Equipment Arrangement*

*Figure 2.4-8. Deployable Module—Hard
Shell Alternate Seal Concepts*

o The STS orbiter crew module structure measured leakage rate is 4.9 kg/day, i.e., more than 10 times the requirement. While it is appreciated that the crew module has a large number of electrical penetrations and many large area windows the minimization of leakage to 0.44 kg/day represents a significant challenge.

o The magnitude of the challenge can be visualized by noting that the total equivalent leakage area in a module at atmospheric pressure cannot exceed 0.12 mm (0.0047 in) in diameter to maintain a leakage. rate of no more than 0.44 kg/day. Some of this may be used up at the docking port seals.

During the concept development several concepts to seal the cylindrical hinge lines, end bulkhead hinge lines, and fold-out panel to cylinder mating surfaces were investigated. These concepts are summarized in Figure 2.4-8. These designs, however, cannot satisfy the above discussed requirements at the intersection of two hinge lines. Therefore, the seal recommended is the design shown in Figure 2.4-6. This seal consists of a continuous polypropylene membrane across the flat bulkhead and ends of the cylindrical shell as shown at the left and in detail as shown in Section B-B. The cylindrical hinge lines A, B, C, and D are sealed by the hinge sideseal shown. This seal concept nevertheless involves EVA installation of the membrane after deployment of the structure.

An alternative seal configuration that would be in place during launch would have to accommodate the inward motion of the fold out panels, i.e., be sufficiently oversized. This may be the best solution yet, but is beyond the scope of this study.

2.4.3 Inflatable Manned Module Design (Drawing 42712-8)

The major features of this design concept are summarized by Figure 2.4-9 and 2.4-10. The same concept as that of the hard shell structure previously described is used in regard to the end conical shells and center section strongback. However, in this design the center structure consists of a pair of inflatable shells attached to each side of the strongback by an end attachment such as shown in Section B-B. The configuration of the center structure is a pair of cylindrical shells capped by an ellipsoidal dome. The cylinder radius is 2.08 m, and the dome depth is 63% of the shell diameter. The construction, recommended by GAC is a fabric consisting of Nomex unidirectional cloth coated with a Viton B-50 elastomer. Goodyear has qualified this material to the requirements of the NASA Space Shuttle orbiter crew cabin and Spacelab module.

An even number of multiple layers of the Nomex/Viton B-50 qualified material will be laminated together until adequate strength is obtained. the aluminum foil layer was defined as a flame barrier in earlier GAC studies.

Figure 2.4-9. *Manned Module Inflatable
Design Concepts*

Figure 2.4-10. *Manned Module Infla   ｀e Design
Equipment and Living Space Arrar.   ,t*

The mass distribution of this construction is shown below.

ITEM	MATERIAL MASS	
	GM/CM^2	LB/FT^2
ALUMINUM FOIL LAYER	0.002	0.0041
ADHESIVE	0.005	0.0102
STRUCTURAL LAYER	1.370	2.810
TASLAN INTERLOCKIN LAYER & ADHESIVE	0.024	0.049
ONE INCH POLYURETHANE FOAM	0.080	0.164
ADHESIVE	0.005	0.0102
OUTER COVER AND THERMAL COATING	0.031	0.064
TOTAL	1.52	3.11

Figure 2.4-9 also illustrates the deployable radiator configuration which serves as a meteoroid bumper. This is necessary since radiators cannot be mounted on the flexible structure.

Figure 2.4-10 illustrates the mounting of the miscellaneous equipment into the module. While less space is available in this module than the foregoing hard-shell design because of the domes, all the baseline equipment identified was packaged.

Pertinent to the inflatable design the issues of crew protection from radiation material flammability and offgassing, construction life, crack prevention propagation, and sealability are discussed as follows.

2.4.3.1 Radiation Protection

Since the inflatable shell material is projected to have a mass of 1.52 gm/cm^2, its mass is considerably above the 0.50 gm/cm^2 considered adequate for radiation protection of the crew.

2.4.3.2 Flammability and Offgassing

Since fluorocarbons have been tested successfully in the past for flammability and offgassing, it was believed that Viton was a good choice for an elastomer. The above items, in conjunction with the fact that the early development units made by McDonnell Douglas had used Viton and had been approved by NASA, led to the selection of Viton as the elastomer for the Goodyear flex element. Due to processability the specific Viton selected was Viton B-50. Several combinations of elastomer and cloth were submitted to NASA via MDTSCO for evaluation. The results showed that the Viton B-50

2-32

elastomer and Nomex cloth would pass the flammability and offgassing test as called out in NHB8060.1A (Reference 9) by being subjected to an autoclave cure, post cure and vacuum bakeout. Therefore, it is anticipated that all flammability and offgassing requirements of the program can be met.

2.4.3.3 Lifetime

None of the environmental conditions which the Spacelab tunnel flex element must withstand were very severe compared to that of a Space Station module. Most elastomers could survive the operational environment imposed on the flex element. There were, however, two significant requirements that led to the selection of Viton as the elastomer: 10-year life and offgassing/flammability requirements. Viton is known for its long life at elevated temperatures; and, since there was no elevated temperature requirements on the flex element, the life would be well in excess of ten years. (Elevated temperature is used for accelerated aging testing of rubbers.) Characteristic dry heat resistance of volcanizates of Viton in continuous service is considered to be greater than three years at 230°C.

For comparison, conventional elastomers would be brittle after one day at 230°C.

Other characteristics of Viton which make it an excellent selection are its weatherability and fungus resistance.

GAC quotes their elastomeric products as being good for ten years under reasonable, uncontrolled terrestrial storage conditions. This includes such items as diaphragms, seals, pillow type tanks, fuel cells, flotation bags, uprighting bags, impact attenuators and similar structures. After this storage, these products can provide five years of service, generally. Diaphragms and seals usually provide 18 to 20 years of service.

Obviously, further tests are required for on-orbit life but it is believed that the Viton B-50 elastomer has the best chance to meet the desired 20-year lifetime.

2.4.3.4 Crack Propagation Prevention

GAC has conducted pressure tests on the flex section for the Spacelab transfer tunnel to verify the constructions stability in the presence of detectable damage. That same construction is proposed for this manned module but with more plies since the limit circumferential loading is 2100 N/cm (1200 lb/in). With the increased number of plies in this manned module the stress levels should be comparable. For a damage totally through the construction the crack propagation resistance should be similar to that of the tested design.

The purpose of the leak-before-burst test was to demonstrate that the design of the flex element is stable under limit conditions with readily detectable damage.

The leak-before-burst test involved inducing a 12.5 mm cut completely through the flex element while at an internal pressure of 11 N/cm^2. The cut was oriented perpendicular to the yarns of the ply that was loaded.

The blade used was double edged, 12.5 mm wide, and came to a point. It was mounted on a pneumatic actuator such that once the blade penetrated the unit, it could be withdrawn and the pressure maintained for four minutes. The leak-before-burst test was filmed for documentation. Visual examination of the cut after the test revealed that the cut did not grow beyond the initial cut length.

The design was stable under limit pressure and displacement conditions when a readily detectable damage consisting of a 12.5 mm slit through both plies was intentionally inflicted on the unit. This represented a successful completion of the leak-before-burst test.

From the foregoing the suitability of the construction to sustain micrometeoroid punctures is quite likely (particularly over the surface shielded by the radiators. The suitability to resist space debris particles, as for the metals, is not known.

2.4.3.5 Sealability

The two potential sources of leakage are through the basic construction and/or at the flexible seal. While GAC has demonstrated by test the leakage of the flex section of the Spacelab transfer tunnel to be no more than 0.050 kg/day that structure has a surface area approximately 1/100 that of the manned module. In its favor this construction has an increased number of plies. On the other hand this capability after 5, 10, 15, or 20 years in space is not known. While the perimeter ratio of the flexible seal is only 1/6 that of the manned module the radial deformation tending to cause leakage is (for the same stress) approximately 20 times greater. The uncertainty is apparent. What is certain is that the requirement of 0.44 kg/day is representative of a total integrated hole size no larger than 0.12 mm (.0047 in.) if no leakage occurs elsewhere (at the access hatches). Until development tests are accomplished that are directly related to this application the leakage rate is an unknown.

2.4.3.6 Meteoroid/Space Debris Issue

It was stated earlier that a micrometeoroid puncture is not expected to precipitate a catastrophic failure. Figure 2.4-11 illustrates the pertinent data concerning the potential for puncture and repair of the shell. Since the radiator configuration serves as a bumper over most of the projected area (Figure 2.4-9) the analysis is performed on that basis.

For the surface area quoted, and a 20-year exposure, there is a probability of 0.99 that no impact will occur for a particle size greater than 9.9 mm in diameter. This particle, for no puncture, requires an aluminum single sheet thickness of 29.5 mm. For a bumper ballistic efficiency of 5, the equivalent thickness required of this construction is 5.9 mm (0.23 in.). The polyurethane foam, having a density of 0.031 gm/cm^3 (2 lb/ft^3), behaves like an aluminum sheet 4.3 mm thick. This is based on the following data provided by GAC.

"Based on hypervelocity particle impact tests conducted by Goodyear Aerospace and on tests conducted at the micrometeorite testing facility at Wright-Patterson AFB, flexible foam with a .015 gm/cm^3 (1.0 lb/ft^3) density has been selected as a suitable barrier material. The tests at Wright-Patterson were conducted with a particle that had an average mass of 0.005 g, traveling at 8232 m/sec (27,000 ft/sec).

Figure 2.4-11. Manned Module Man-Made Debris
and Micrometeoroid Design Implications

Both series of tests indicate that a foam barrier has the same effectiveness as a single sheet of aluminum with 15 times the mass per unit area."

It is expected that provision of a foam with increased density can provide the required stopping power. Based on this it can be said that for a life of 20 years the probability of a puncture occurring that requires repair is 0.01. Such a puncture can be repaired.

The problem of space debris for this structure as the hard shell, is ill-defined. To assure that no catastrophic crack propagation would be initiated by impact of a space debris particle, the size, density, and speed properties of the particle must be explicitly defined and ballistic tests must be performed upon candidate constructions in pressurized configurations.

A brief summary of the foregoing is as follows:

o There is no on-orbit data to a confirm 20-year-life suitability of t e wall construction utilizing a Viton B-50 elastomer.

o GAC prior test data do not resolve the question of the 10 to 20 year seal capability of the basic wall construction (maximum leakage requirement of 44. kg/day).

o Micrometeoroid impact is not expected to be a problem with the use of radiators as a bumper.

o The construction suitability for space debris is not known.

o Crew radiation shielding, material outgassing, and nonflammability requirements are satisfied by construction.

2.5 DEPLOYABLE MODULE MISCELLANEOUS COMMENTS

The following general comments are applicable to both deployable module designs.

o Both deployable configurations can satisfy the manned module crew safety, volume requirements, design commonality, and growth evolution requirements.

o Each configuration requires 16 m of cargo bay, compared to 25.3 m for the two modules. The potential launch cost savings is $39.0 million (1984 dollars).

o An extrapolation of the Space Station baseline manned module mass (Table 2.4-2) results in a potential mass of the deployable modules of 23 kg to 25 kg.

o For the c.g. at orbiter Station 982, the maximum cargo launchable mass is 19 kg, but an aftward shift of the c.g. of 0.89 m can be accomplished with 4 to 5 kg ballast or additional equipment. This permits the launch of a 29.5 kg mass.

o Both designs require additional on-orbit cost of installation of partitions and systems at a rate of $15,000/hour.

2.6 MANNED MODULE SELECTION

o The capability of either hard-shell or inflatable deployable designs to
   satisfy the minimum leakage requirement is very questionable. A 2.2
   kg/day additional leakage amounts to 16,600 kg over 20 years which
   alone negates the initial launch savings.

o While the inflatable design has the best potential, with technology
   development, to satisfy the leakage requirements, no data exist to
   confirm a 20-year life of the construction.

o Any launch cost savings will be reduced by increased structural
   complexity, seal technology development, and on-orbit cost of EVA for
   equipment installation.

Hence, it is recommended that the conventional baseline design be
maintained until the technology development of seals can provide assurance
that the requirement of .44 kg/day can be satisfied. Also, no further
conceptual effort is recommended until Space Station configurations,
requirements, and criteria are more accurately defined.

3. REFERENCES

1. SASP Deployable structure Ground Test Project, Test Article Design Requirements, prepared by MSFC Preliminary Design Office, Program Development, January 1980.

2. Satellite Power Systems (SPS), Final Report (Exhibit E Report), LSST Systems Analysis and Integration Task for SPS Flight Test Article, Rockwell Report, SSD 80-0102, dated August, 1980.

3. Space Construction Systems Analysis, Part 2, Final Report, Platform Definition, NAS9-15718, Rockwell International, April 1980.

4. Federal Standard FED-STD-H28/12, Screw Thread Standards for Federal Services, August 31, 1978.

5. Engineering Mechanics, Ferdinand L. Singer, Harper and Brothers, 2nd Edition.

6. SD&P Mechanical Systems Design and Parts, Rockwell Volume III Publication 543-G-25, April 1983.

7. Space Station Needs, Attributes, and Architectural Options Study, SSD83-0032, April 22, 1983, Contract NASW 3683.

8. Space Station Program Description Document, System Requirements and Characteristics, Book 3, JSC, November 1982.

9. Preliminary Study to Adapt Inflatable Structures to a Space Station Habitat and OTV Hangar, GAC 19-1585, February 1983.

10. Midterm Review - Development of Deployable Structures for Large Space Platform Systems, SSD 83-0004, January 28, 1983.

CONTENTS

I, II, III, IV

ILLUSTRATIONS

TABLES

INTRODUCTION

During the next decade, a revolution in spacecraft design will occur, resulting in large space platforms that will accommodate multiple payloads. Cost savings to users will occur through sharing of spacecraft utilities, ease of servicing, and the ability to change payloads. In addition, for geosynchronous communication payloads, platforms will reduce the crowding of this important orbital location.

The development of deployable platform systems is the most significant technology step in the direction of realizing these platform capabilities. Although the Shuttle allows payloads with much larger dimensions than other launch systems, the large dimensions of the platforms will, nevertheless, require extensive structural deployment to package it within the orbiter.

Much of the previous industry effort in large structures concentrated on orbital construction or erection. A recent Rockwell study, Space Construction System Analysis Study (NAS9-15718), developed the detail necessary to understand the difficulty of joining machine-made beams and integrating spacecraft utilities in orbit from the Shuttle. These studies pointed up the difficulty of erecting or constructing large platforms from the Shuttle. Consequently, ground integration of utilities into a deployable structure was selected by NASA as the first logical approach to platforms. NASA/MSFC has prepared a five-year plan to achieve technology readiness of deployable platform systems by FY 1986. Phase I of that plan is to identify the one or two most suitable deployable platform systems (Part I) and establish all the information necessary to plan and execute a follow-on-hardware development test program (Part II). On October 16, 1981 Rockwell initiated the study activities in support of Part I, with completion 9 months later - on July 16, 1982. Sections 1 through 4 of this interim report describe the pertinent study accomplishments for Part I.

Future missions such as the manned space platform require both pressurized and unpressurized volumes, respectively, for crew quarters and manned laboratories, and maintenance hangars. Deployable volume enclosures can minimize launch costs and enable use of volumes greater than those which can be transported by the Space Shuttle orbiter. On April 16, 1982, Rockwell initiated a 3-month add-on study of Deployable Volume Enclosures with the objective of identifying generic concepts for manned habitats, tunnels and OTV hangars. The accomplishments of that study are described in Section 5 of this interim report.

During the course of this conceptual study, 31 drawings were completed. The drawings are provided in a separate document, i.e., Volume II, SSD 82-0121-2, August, 1982.

1

DESIGN APPROACH

The design approach employed in this study of deployable platform systems is developed to satisfy the objectives and guidelines as follows:

Objectives

- o Development and evaluation of generic deployable platform system concepts applicable to the focus mission LEO/GEO applications and foreseeable applications for the 1990 to 2000 time period

- o Establishment of a materials data base for structures and utilities systems compatible with LEO/GEO applications

- o Identification of the new technology development needs, schedules, and costs

- o Systematic/traceable selection of the one or two most suitable generic concepts

Guidelines

- o Automatic deployment - minimum EVA

- o Platform system - not just a structure

- o FY 1986 technology readiness - test-proven hardware

- o Generic - not a basepoint design

- o Versatility - can be used to build spacecraft of different configurations; "building block" approach (self-contained modules)

- o Distinction between LEO and GEO designs

- o Adaptable for a wide range of payloads

Of the above, the guideline of automatic deployment was the major design driver.

The entire concept development is directed toward automatic deployment of the entire platform system without use of a construction fixture or EVA. This approach is illustrated in Figure 1. The deployable platform system is comprised of several building blocks which are preassembled before flight to provide the defined spacecraft confi iration. Each building block contains the deployable truss; integrated power, data, and fluid lines; a main housing; adapter; and deployment mechanization system. Attachments for payloads, reaction control system (RCS) modules and docking ports are provided on the main housings or adapters. The packaged platform system can be integrated into the orbiter with a pallet that serves as a control system module and contains batteries and telemetry, tracking, and command (TT&C) equipment. The system can be removed from the orbiter by the remote manipulator system (RMS) and placed on a handling and positioning aid (HAPA) or, depending on configuration, size, and shape, utilize both RMS and HAPA during the initial

2

deployment stages and during control system checkout. Subsequent to control
system checkout, the platforms can be translated away from the orbiter (100 to
200 meters) for completion of the automatic deployment phase.

Figure 1. Deployable Platform Systems Concept

A major factor in the study approach is the requirements. Unquestionably, the
regime of strength, stiffness, and utilities requirements is a major
consideration. The requirements are extracted directly from the three focus
missions (Figure 2, References 1, 2 and 3) and supplemented by Rockwell
analysis and recognition of other potential applications.

Figure 2. Focus and Miscellaneous Configurations

The study approach was directed according to the study plan shown in Figure 3.

C

Figure 3. Study Logic—Part I

SUMMARY

This section briefly summarizes the major study accomplishments.

Figure 4 summarizes the deployable platform system acccomplishments. In Subtask 1.1, the strength, stiffness, electrical, and fluid utilities requirements and additional requirements encompassing structural temperature limits, guidance and control, pointing accuracy, and propulsion were established. In Subtask 1.2, the generic configuration (to serve as a study tool) consisting of linear members was configured depicting the platform size, general arrangement, utilities distribution and docking ports. Also, investigation of an area platform constructed in such a manner that plate behavior is developed, resulted in termination of that concept for the reasons

5

Figure 4. *Summary of Deployable Platform System Accomplishments*

delineated in Section 1.2. In Subtasks 1.3 and 1.4, eight candidate structure concepts with integration of utilities, and concepts for deployment mechanisms, housings to contain the mechanisms and structure, and adapters for payloads were developed.

All the concepts were integrated into eight building-block concepts. The eight building blocks were compared on the basis of packaging the generic platform into the orbiter, with supporting parametric structural, thermal, mass properties, meteoroid impact, and cost analyses. The results of these analyses are tempered by the consideration that the generic platform and requirements represent one design condition in the spectrum of platform applications. In fact, the generic platform and adopted strength, stiffness, and utilities requirement are at the upper end of the spectrum of foreseeable requirements for most platforms.

In Task 2, candidate materials most suitable for the deployable platform system components were identified, with establishment of a data base for these candidates. The data base is comprised of 10 tables of mechanical and physical properties.

In Task 3, new technology development needs were identified, prioritized, and scheduled, including the development cost estimates. Of the 16 new technology items identified, no show-stopper is apparent.

The foregoing data were used in the concept selection process of Task 4. The concept analyses compared the designs on the basis of design versatility, cost, thermal stability, meteoroid impact suitability, reliability, performance predictability, and orbiter integration suitability. This selection process methodology, in conjunction with judgmental evaluations, resulted in the selection of Concept 6A, (Figure 5). The major features of Concept 6A are summarized as follows:

o   Building-block approach for automatic deployment of platform systems

o   Square shaped truss - most suitable for inter-building-block attachments; mounting of payloads, docking ports, and propulsion modules; and provides redundancy for meteoroid impact.

o   Circular tubes for all truss members -- minimum cost construction for graphite composite construction

o   Minimal complement of utilities mounted on longerons

o   Trays for mounting of large complement of utilities - ease of initial installation, repair, replacement during total ground fabrication period - minimum truss structural design constraints imposed by utilities integration.

o   Square-shaped housing with reciprocating deployment mechanism

o   Bay-by-bay deployment (to facilitate identification of deployment problem, if it occurs)

7

- ALL MEMBERS ARE ROUND TUBES
- LONGERONS WITH CENTER HINGE JOINTS
- TELESCOPING DIAGONALS
- NO OFFSET LOADS AT JOINT
- BATTENS CROSS BRACED BY TENSION STRAPS

Figure 5. Square Truss with Modified Longerons (Concept 6A)

o   Rail system for root strength during bay-by-bay deployment - permits
     orbiter berthing and orbiter vernier reaction control system (VRCS)
     firing (if necessary).

o   Adapters for mounting of payloads with automatic electrical
     connector interface

o   Payloads and propulsion modules attached using RMS

An example of a possible configuration achievable with this concept that is
constructed of 1.75 and 2.75 m deep trusses is shown in Figure 6.

The major conclusions drawn in this study of deployable platforms systems are
as follows:

o   Deployable platform systems technology readiness for FY 1986 period
     is quite feasible (with appropriate funding)

o   The building-block concept utilizing Concept 6A can effectively be
     used to construct LEO/GEO platforms

o   Deployment is accomplished with orbiter RMS and/or HAPA without use
     of construction fixture

o   NASA/MSFC goal of automatic deployment of platform system (not
     including payloads, RCS modules) is achievable

Figure 6. Possible Configuration (Concept 6A)

o   All candidate building-block concepts, applied to generic platform,
    are packageable into one orbiter and are well within 20,000 kg
    launch capability (28.5° inclination, 210 nmi)

o   The selected concept accommodates the upper regime of platforms size,
    utilities, and adopted strength requirements and is applicable to
    large range of reduced requirements

o   commodation of adopted stiffness requirements is dependent on the
    resolution of "Joint Slop" issue (most platform applications will
    have stiffness requirements well below adopted values)

o   No foreseeable unresolvable technology development requirements

o   Major extent of technology development for selected concept is
    applicable to alternate candidate concepts

Figure 7 summarizes the major accomplishments of the Add-on Deployable Volume
Enclosures Study. The Space Station studies currently being performed at
Rockwell are used for the establishment of requirements and applications for
manned habitats and OTV hangars. Eight habitat and seven OTV hangar candidate
configurations were developed. Three preferred configurations were identified
for the manned habitats and developed in further detail (Section 5). Three

9

Figure 7. Summary of Deployable Volume Enclosures Accomplishments

10

OTV hangars were also developed in further detail. Further, the major design issues and new technology development requirements were identified.

The major conclusions drawn from this study are as follows:

o The application to habitats appears attractive - large useful volumes are achievable

o Metallic structures (can be sealed) can provide ample meteoroid, radiation protection, and equipment mounting surfaces, but are constrained by pressure loads/packaging requirements

o Inflatables alone are not sufficient - hard structure is required for mounting of consoles, orbiter and space station integration, and heat rejection

o Inflatables in conjunction with rigid core module provide a variety of feasible large volume designs provided

     Materials are suitable to crew safety/space environment; foam micrometeoroid stopping power is comparable to existing data; repair of punctures or use of meteoroid bumper is feasible; and adequate protection of the crew from radiation can be provided.

o Hangar requirements are ill-defined - OTV meteoroid protection alone is not sufficient justification

o Most attractive OTV hangar concepts appear to be metallic deployable/erectable or inflatable with foam core (provided stiffness is adequate)

1. CONCEPT DEVELOPMENT

This section describes the study concept development accomplishments which
include establishment of platform system requirements (1.1), development of a
generic spacecraft configuration (1.2), development of the building-block
component concepts (1.3), and integration of these components into eight
candidate building blocks (1.4). Section 1.4 also describes the application
of tne building blocks to the generic platform; packaging of the platform into
the orbiter; and the comparative structural, thermal, mass properties, and
cost analysis performed for the Concept Selection Trade Study (4).

1.1 DEPLOYABLE PLATFORM SYSTEMS REQUIREMENTS

This section describes the generic platform system requirements extracted
either directly from the three focus mission studies (References 1, 2, 3
and 4) or determined by supplemental analysis from the data provided therein.
In the course of performing the supplementary analysis pertaining to the ASASP
and GSP requirements, the study managers of these studies were contacted for
additional information and/or clarification.

The three focus mission studies provide four platform configurations as shown
in Figure 1.1-1. Since Geostationary Space Platform (GSP) Alternative 1

215 m

SPS TEST ARTICLE

160 m

ASASP

30 m

125 m

GSP ALTERNATIVE 1

GSP ALTERNATIVE 4

*Figure 1.1-1. Four Configurations Extracted from
Three Focus Mission Studies*

represents a configuration entirely cons . table with either astromasts or
supermasts, emphas: was placed upon the GSP Alternative 4 configuration which
represents the high ... of the spectrum in terms of size, strength and
stiffness requirements. This configuration is comprised of three modules
individually transferred to and joined together in GEO. Two of the largest of
these three modules are shown in Figure 1.1-2. The information shown in
Figure 1.1-2 ,.d mass distribution data were extracted from the several books
of Volume II, Reference 5.

*Figure 1.1-2. Modules 1 and 2 of
GSP Alternative 4 Configuration*

Additional to the supplementary analysis required to completely define the
requirements for the missions, it was necessary to understand the derivation
of the most severe requirements in order to assess the applicability of these
requirements. The assessment was tempered by the consideration that this
study is a technology development contract, with extension of the technology,
as practicable, being a major goal. Further, many of the requirements stem
from conditions where two equally possible alternatives to the design can
exist and are dependent on the particular spacecraft configuration and systems
trades. For example, thermal control of payloads can be accomplished with
dedicated radiators at each payload or with the use of a central radiator and
coolant lines integrated into the deployable structure. In such cases, in the
the absence of any other information, the alternative requirement that
advances the technology (in this case, integration of coolant lines into the
structure) is included.

1.1.1 Strength and Stiffness Requirements

Table 1.1-1 summarizes the strength and stiffness requirements for the focus
mission spacecraft configurations. The data shown were obtained by a
combination of direct extraction from the focus mission documents and
supplemental hand calculations. The data directly extracted are identified
with a subscript "d".

Table 1.1-1. Focus Mission Limit Strength and Stiffness Requirements

PARAMETER / PLATFORM	SPS	ASASP	GSP ALT. 1	GSP ALT. 4
DEPLOYABLE STRUCTURE MODULE				
• FLEXURAL STIFFNESS (Nm^2)	$17.3 \times 10^6{}_d$	$\checkmark 6.0 \times 10^8{}_d$	$2.8 \times 10^6{}_d$	$\checkmark 2.6 \times 10^8{}_d$
• TORSIONAL STIFFNESS (Nm^2)	$4.4 \times 10^4{}_d$	$\checkmark 1.1 \times 10^7$	8.2×10^4	$\checkmark 1.1 \times 10^7{}_d$
• BENDING MOMENT (Nm)	808_d	$\checkmark 9000$	6570_d	$\checkmark 1.0 \times 10^5{}_d$
• TORSIONAL MOMENT (Nm)	18_d	$\checkmark 4900$	3500	$\checkmark 1.8 \times 10^4$
• AXIAL LOAD (N)	200	500	$\checkmark 4660$	3700
• SHEAR (N)	400	200	660	$\checkmark 5400$
PAYLOAD INTERFACE				
• BENDING MOMENT (Nm)	1600	$\checkmark 4900$	NEGLIGIBLE	90
• TORSIONAL MOMENT (Nm)	NEGLIGIBLE	$\checkmark 4900$	NEGLIGIBLE	110
• AXIAL LOAD (N)	200	375	NEGLIGIBLE	90
• SHEAR LOAD (N)	100	500	NEGLIGIBLE	110
PROPULSION MODULE INTERFACE				
• BENDING MOMENT (Nm)	1200	1080	6190	$\checkmark 1.3 \times 10^4$
• AXIAL LOAD (N)	200	1780	1.05×10^4	$\checkmark 1.1 \times 10^4$
• SHEAR LOAD (N)	400	250	1050	$\checkmark 7850$

1. Attachment of orbiter to platform accomplished by berthing.
2. Berthing loads are: bending moment - 1630_d (Nm), axial load - 1800_d (N).
3. Subscript "d" denotes data obtained directly from focus mission documents.
4. $\checkmark$ Denotes maximum values.

The strength requirements are very sensitive to configuration and payloads size, shape, and mass distribution; and locations of propulsion modules for LEO stationkeeping or transfer to GEO.

The stiffness requirements are not only dependent on the payload and configuration size, shape and mass distribution but also the interplay between pointing system requirements, attitude control system (ACS) thruster levels, and control system design. For a basepoint design, trades between these systems can be made along a wide variation of parameters. Since this study is generic, such trades are not possible. However, the implications are recognized in the establishment of the requirements.

1.1.1.1 ASASP Flexural and Torsional Stiffness Requirements

The flexural stiffness value of 6×10^8 Nm^2 for the ASASP (Advanced Science and Applications Space Platform) configuration is extracted directly from Reference 4 as shown in Figure 1.1-3 and was determined to provide a minimum first modal frequency of 0.10 Hz. Since no information was available reqarding the required torsional stiffness, a hand calculation resulted in a value 1.1×10^7 Nm^2 for the same first modal requirement of 0.10 Hz. The total mass of the platform was 80,553 kg. The individual payloads, and mass moments of inertia were extracted from Reference 2.

Figure 1.1-3. Flexural Stiffness
Vs. Frequency (Hz) for ASASP

It is pertinent to note that during the orbiter packaging investigations, a NASTRAN modal analysis using an EI = 2×10^8 Nm^2, and GJ = 0.5×10^7 Nm^2, i.e., stiffnesses respectively 1/3 to 1/2 of the above quoted values, resulted in a first modal frequency of 0.043 Hz. Since flexural stiffness is the main driver, a frequency of 0.057 Hz would correspond exactly. However, within the broad context of this study, and the derived generic requirements, the model sufficiently confirms the validity of the stated requirements.

1.1.1.2 ASASP Strength Requirements

The ASASP strength requirements of 9000 Nm (bending) and 4900 Nm (torsion) occur during stationkeeping maneuvers. The propulsion module thrust of 890 N, directed as shown in Figure 1.1-4, induces the above specified loads. It is pertinent to note the relatively large torsional moment results from the large offset of the center of mass of the payloads.

Figure 1.1-4. ASASP Configuration
—Stationkeeping Thrust

1.1.1.3 GSP Alternative 4 Flexural and Torsional Stiffness Requirements

The stiffness data shown in Table 1.1-1 are extracted directly from Table 3-6 of Reference 3. The requirements shown in Table 1.1-1 are the maximum requirements for members B and E (Figure 1.1-5). The requirements are based upon a restriction of the relative lateral displacement between the reflector and feed of 0.20 m due to RCS thruster induced loads. A hand calculation of the deflection due to inertial loads directed as shown compatible with an "approximate acceleration of .0003 g" (from Reference 3) indicated a deflection of 0.14 m (using amplification factor of 2). This proximity between 0.14 m and 0.20 m is quite adequate for this study. Of primary importance is the fact that the torsional induced portion of the deflection was more than 95% of the total deflection.

*Figure 1.1-5. Module 1 (Alternative 4)
Attitude Control Thrust*

Consideration was also devoted to the stiffness requirements to provide frequency separation with the control system. The following is an extraction from Reference 3 pertinent to this concern.

"A NASTRAN finite element model was generated for the Alternative No. 4 platform based on the individual module orbit transfer strength requirements. The model was comprised of 65 grid points, 64 structural elements, and 390 structural degrees of freedom. Natural modes and corresponding natural frequencies were determined for the system. The fundamental natural frequency of the system based on strength requirements is 0.019 Hz. A similar analysis of the Alternative No. 4 platform resized to comply with stiffness

requirements would yield significantly higher natural frequencies. Again,
caution must be exercised to ensure that the lower frequency vibration modes
do not interact with the RCS and cause instability. As noted previously,
control techniques can obviate this possibility."

1.1.1.4 GSP Alternative 4 Strength Requirements

The maximum bending moment extracted from Table 3-5, Reference 3 is 101,427 Nm
for member H of Module 2 (Fig. 1.1-6). Torsional moments are not provided in
Reference 3. The bending moment results from the GEO orbit transfer thrust of
6000 N directed as shown. The data presented in Reference 5 were used to
construct a mass distribution model of Module 2 from which hand calculations
confirmed the specified moment of 101,427 Nm, or more approximately stated,
provided confidence in the mass distribution model used. A hand calculation
of the torsional moment resulted in a value of 18,000 Nm. Both calculations
include a factor of 2 for dynamic amplification.

*Figure 1.1-6. Module 2 (Alternative 4)
Attitude Control Thrust*

Table 1.1-2 illustrates the strength and stiffness requirements adopted for the concept development and structural analyses to be performed in this study. One set of requirements, i.e., the adopted requirements, is used to size the structure for the concept development drawings. However, the implication of order of magnitude variations of these requirements is studied in Section 4.

Table 1.1-2. Adopted Loads (Limit) and Stiffness Requirements

PARAMETER / PLATFORM	SPS	ASASP	GSP ALT. 1	GSP ALT. 4
DEPLOYABLE STRUCTURE MODULE				
• FLEXURAL STIFFNESS (Nm^2)	17.3×10^6 d	2.0×10^8 d	2.8×10^6 d	2.0×10^8 d
• TORSIONAL STIFFNESS (Nm^2)	4.4×10^4 d	$.50 \times 10^7$	8.2×10^4	0.5×10^7 d
• BENDING MOMENT (Nm)	808 d	9000	6570 d	$.35 \times 10^5$ d
• TORSIONAL MOMENT (Nm)	18 d	7050	3500	1.0×10^4
• AXIAL LOAD (N)	200	500	4660	3700
• SHEAR (N)	400	200	660	5400
PAYLOAD INTERFACE				
• BENDING MOMENT (Nm)	1600	4000	NEGLIGIBLE	90
• TORSIONAL MOMENT (Nm)	NEGLIGIBLE	4900	NEGLIGIBLE	110
• AXIAL LOAD (N)	200	375	NEGLIGIBLE	90
• SHEAR LOAD (N)	100	500	NEGLIGIBLE	110
PROPULSION MODULE INTERFACE				
• BENDING MOMENT (Nm)	1200	1060	6190	1.3×10^4
• AXIAL LOAD (N)	200	1780	1.05×10^4	1.1×10^4
• SHEAR LOAD (N)	400	250	1050	7650

☐ DENOTES ADOPTED STRENGTH AND STIFFNESS

The adopted stiffness requirements are based upon the following rationale:

o   The highest EI value listed for the ASASP of 6×10^8 Nm^2 is quite arbitrary, i.e., to achieve a first modal frequency of .10 Hz for a platform mass of 80,553 kg. It is unlikely a platform in excess of 40,000 kg will be required. Further, a first modal frequency of .03 Hz is still 100 times the LEO orbit disturbance frequencies.

o   Of the values (from GSP 4 Module 1) of EI = 2.6×10^8 and GJ = 1.1×10^7 Nm^2, only the GJ is the major requirement to limit the required deflection. That requirement is due to placement of the feeds for the 60 m reflector as shown in Fig. 1.1-5. Antennas with their own feed columns would preclude this requirement.

o   In view of the foregoing, and the technology advancement goals of developing designs up to the maximum practical/realistic requirements, the adopted stiffness values of 2×10^8 and $.5 \times 10^7$ Nm^2, respectively, for EI and GJ were selected.

The adopted strength requirements were based on the following:

o   The values of $1x10^5$ and $1.8x10^4$ Nm, respectively, for the
    bending and torsional moment obtained from the GSP alternative 4,
    Module 2, are regarded as unnecessarily high since the module is
    20,600 kg (payloads to GEO by the year 2000 are not expected to
    exceed 6000 kg). Further, the loads can be reduced by reduction of
    the orbit transfer T/W (thrust to weight ratio), and/or minimization
    of dynamic amplifications. The latter two items are technology
    development needs, for antennas as well as platforms. The potential
    reduction of T/W from 0.035 to a possible 0.0137 is discussed as
    follows:

Low-thrust liquid propellant systems are indicated for orbit tranfer
applications for current and future missions to GEO as the need for
maneuvering, start-stop operations and especially low thrust levels
predominate as desirable characteristics.

Low thrust and the resultant long burn times can mean larger gravity
losses and increased propellant weight (Figure 1.1-7) for single
burns. However, multiple perigee burns minimize gravity losses by
reducing the burning arc and theta (Θ), the angle between the
velocity vector and the local horizontal in the gravity loss term,
$g_c t \sin\Theta$ (simplified).

Figure 1.1-7. GEO Transfer T/W and Number of
Perigee Burn Implications on Propellant Mass

The use of multiple burns to minimize gravity loss (2% for eight burns versus 14% for single burn) is attractive in exchange for a somewhat longer transfer coast time (22 hours for 8 burns versus 6 hours for single burn). In many cases, this will be an acceptable compromise. The reduction in propellant requirements with multiple perigee burns at low T/W is dramatic, as shown for the payload indicated. Generally, propellant requirements increase as T/W decreases below the value of one, due to the aforementioned gravity loss effects. The propellant weight is decreased, however, as the number of perigee burns is increased above a nominal of one perigee burn. Eight perigee burns provide a substantial reduction in propellant requirement at low T/W; the maximum reduction occurring in the vicinity of T/W (final) from 0.01 to 0.02. These savings are sharply reduced, however, at T/W (final) values below 0.008.

o   In view of the foregoing, and the technology advancement goals of developing designs up to the maximum practical and realistic requirements, the strength values of .25x10^5 and 1x10^4 Nm, respectively, for bending and torsional moments were used.

In summary, the rationale for establishment of the adopted strength and stiffness requirements is presented above. In consideration of the overall range of requirements throughout the focus missions shown on Figure 1.1-1, the justifiable departure from the maximum values is minimal. Hence, it may be stated that the adopted requirements are at the high end of the total requirements spectrum.

1.1.2 Power and Data Utilities

Table 1.1-3 summarizes the adopted power and data utilities alongside of the corresponding data extracted from the focus mission studies. This requirement is used throughout the concept development.

Table 1.1-3.   Generic Power and Data Utilities Requirements

SYSTEM FUNCTION	ASASP	GPS	SPS	ADOPTED	COMMENTS
POWER (Kw)	50	10	490	50	SPS DEFINED AS SPECIAL CASE
DATA	20 MBPS (D) 50 KBPS (D) 25 KBPS (C) 4.2 MHz (A)	NOT DETERMINED	50 MBPS (D) 216 KBPS (C)	20 MBPS (D) 50 KBPS (D) 25 KBPS (C) 4.2 MHz (A)	(SCIENTIFIC) (HOUSEKEEPING) (TV)
INTERFACES POWER	6 NO. 0 28 NO. 2 4 NO. 14	6 NO. 3 4 NO. 13 20 NO. 13	396 NO. 10	6 NO. 0 16 NO. 2 4 NO. 14	
DATA	35 F.O.	34 NO. 13 TSP 58 NO. 26 TSP 144 F.O.	4 NO. 22 TSP	90 NO. 22 TSP 2 COAX 8 F.O. 100 F.O. (OPTION)	TO BE ACCOMMODATED BY DEPLOYABLE STRUCTURAL ELEMENTS

The power lines are based upon a 50 kw total spacecraft power requirement and
distribution system. The data utilities are based upon the scientific,
housekeeping, and TV data needs as shown in Table 1.1-3 and discussed herein.

The power and signal distribution requirements are based upon analysis of
possible payload combinations and altitudes. Table 1.1-4 presents a summary
of the payloads considered. Included in the table are various physical
characteristics and interfaces required to support the selected payloads. In
a general sense, the distribution system is required to accommodate two
classes of signals. The first is power at a relatively high level approaching
20 kW. The major power capability is distributed at 124-164 VDC, with lower
loads at 30 VDC and 110 VAC, 400 Hz. The second class of signals are at
fairly low levels and consist of command and data signals, digitally coded
data transfer and low level closed-circuit TV (CCTV). The digital and video
signal bandwidths are estimated to be 1 Mbps and 6.0 MHz, respectively.

Table 1.1-4. Reference Payload Group

PAYLOAD GROUP	MASS (KG)	DEPL. SIZE (M)	ALTITUDE (KM)	ORBIT (DEG)	POWER	DATA MGMT		NOTES
						COMMAND (KBPS)	DATA (KBPS)	
1. ATMOSPHERIC GRAVITY WAVE ANTENNA	3,000	100 (D)	>250	56-90	33 (kWh)	<25	10	SEE ①
2. PARTICLE BEAM INJECTION	3,000	100 x 100 (SQUARE)	400	56-90	3.3 (kWh)	<25	200 + 4.2 MHz (TV)	SEE ①
3. ASTROMETRIC TELESCOPE	4,500	2(D) x 18	400	28	1,000 (W)	<25	1,000	SEE ②
4. LARGE AMBIENT DIS-PLAY IR TELESCOPE	16,000	15(D) x 35	400-700	28-56	1,000 (W)	<25	7,000	SEE ③

NOTES ① EVA FOR MAINTENANCE AND DEPLOYMENT
② VIBRATION AND GAS PARTICLE SENSITIVE
③ VIBRATION AND GAS PARTICLE SENSITIVE + EVA

1.1.2.1 Power Utilities

The power utilities requirements are based upon the distribution system shown
in Figure 1.1-8 and line lengths compatible with the generic platform (Section
1.2).

The wire size selection was conservatively based upon the worst case
conditions at an operating temperature of 200°C, and line losses of
approximately 5%. (Refinements in the analysis made at a later date to
account for reduction of the operating temperatures to 20°C are discussed
later.)

The 16 No. 2 requirement shown in Table 1.1-3 was derived from provision of
124 VDC at 290 A. For this condition, the primary path wire bundle was chosen
to be eight No. 2 gauge (stranded) for power input plus eight No. 2 gauge
(stranded) for returns.

Figure 1.1-8. Platform Power Distribution Subsystem

Six No. 0 for the 30 VDC lines, and four No.14 for the 110 VAC, 400Hz lines
were similarly determined. Later in the study, as part of an evaluation to
determine the significance to the power utilities requirements of a 250 kW
total spacecraft power requirement, refinements in the above analysis were
made. The essence of this analysis was reduced electrical wire sizes due to
replacement of the 30 VDC by 124-164 VDC, or replacement of both 30 and
124-164 VDC by 110 VAC, with converters and inverters at each port. For this
reason and since the adopted requirement could be integrated into the designs,
the adopted requirement was maintained. The investigation for a total
spacecraft power load of 250 kW indicated essentially the same total circular
mils as that of the adopted values provided the selected power lines operate
at 460 VAC.

The basis for the foregoing conclusions is discussed in the following
paragraphs.

The original evaluation assumed that the 30 VDC and the 110 VAC voltages were
derived at a common location, located some distance from the solar array
module. The effect of this assumption was to require that the deployable
truss be capable of accommodating both the entire 50 kW at 124-164 VDC as well
as accommodating 5.6 kW at 30 VDC and 0.4 kW at 110 VAC. In this original
evaluation it was also assumed that the primary 124 VDC wire bundle
temperature could rise to 200°C. Subsequent analysis indicated that a 20°C
design limit could be maintained and, therefore, it was decided to redo the
analysis of the basic concepts as well as all the other distribution concept
options at the 20°C design point.

The result of the revised basic analysis (summarized in Table 1.1-5) is to reduce the number of No. 2 AWG wires to eight. However, in the re-evaluation of the original analysis, the number of No. 0 AWG wires is increased to eight. Both numbers include their respective return wires or grounds. The total cross-sectional area of the wire bundle was reduced from 1,707,000 circular mils (in the original analysis) to 1,384,000 circular mils - a reduction of 18.4%.

An alternate to the basic wiring layout was also evaluated. In this case, the conversion to 30 VDC was accomplished within the solar power module with the resulting reduction in the power handling requirement of the 124-164 VDC wire bundle to 36 kW. At the same time, it was noted that the 30 VDC circuit may be required to accommodate 9.6 kW rather than 5.6 kW, so this increase in power level was also considered. The results of these changes are shown in the second column of Table 1.1-5. In this approach, the number of No. 2 AWG wires is reduced to six, reflecting the lowered power level, but the identified increase in 30 VDC power increases the number of No. 0 AWG wires to 12. The end result is a net increase in wire area of 21.5%. If the 5.6 kW requirements at 30 VDC are retained, a wire cross-sectional area of 9.5% is realized..

Four new options were considered during this study. Two of these options, Option A at 45.6 kW and Option C at 250 kW, assumed that all of the energy was provided at 124-164 VDC. The other two options considered the power is to be delivered at 460 VAC. Option B was rated at 50 kW while Option D provided 250 kW. The wire sizes for the ac power analyses were taken from a standard ac power handbook and adjusted for the voltage and current levels identified.

Table 1.1-5. Effects of Differing Power Load Assumptions
Upon Wire Count

		OPTIONS				
		BASIC	BASIC (ALT)[1]	A [2]	B [3]	C [4]	D [5]
WIRE SIZE (AWG)	POWER LOAD REQMTS	50 kW @ 124-164 VDC	36 kW @ 124-164 VDC	45.6 kW @ 124-164 VDC	—	250 kW @ 124-164 VDC	—
		5.6 kW @ 30 VDC	5.6/9.6 kW @ 30 VDC	—	—	—	—
		0.4 kW @ 110 VAC	0.4 kW @ 110 VAC	0.4 kW @ 110 VAC	50 kW @ 460 VAC	0.4 kW @ 110 VAC	250 kW @ 460 VAC
14		4	4	4	—	4	—
4		—	—	—	8 [6]	—	38
2		8 (WAS 16)	6	8	—	58	
0		8 (WAS 6)	8/12	0	—		

[1] Electronics located in power module.
[2] Requires 124 to 30 VDC converters at each port, or responsibility of users.
[3] Requires inverters & radiators (n = 90%) in power module, and rectifiers (n = 90%) at each port or within users' equipment. Losses of 10% at inverter will increase effective size of solar arrays (increase to 55 kW)
[4] 5% line voltage drop permitted.   (T = 20°C)

The spacecraft configuration applied to all of the new options considered that the derivation of any voltage other than the primary distribution voltage, with the exception of the relatively low-powered ac in Options A and B, is to be accomplished at the user port or within the experiment system. Thus, in Options A and C the deployable truss must accommodate only two voltage levels, 124-164 VDC and 110 VAC. In Options B and D, only high voltage (460 V) ac must be accommodated. The advantage of eliminating the low-voltage distribution system is apparent, but it does require the addition of more equipment at each port.

The question of utilizing an ac distribution concept at a higher voltage was addressed in Option B. Again, it is possible to further reduce the total number of wires within a deployable truss at the expense of additional equipment, specifically rectifiers and transformers, utilized to provide the lower ac voltages and the various dc voltages. A further cost factor that should be appreciated, when using the ac concept, is the need to compensate for the additional losses introduced by the added equipment. With an estimated efficiency of 90% or less, the option will require a 10-15% increase in solar array to generate the necessary power.

Options C and D were evaluated to determine the impact of increasing the spacecraft experiment support power to 250 kW. Specifically, the ac distribution power level was increased to 250 kW at 124-164 VDC, while the ac system power level is specified at 250 kW at 460 VAC.

The effects of the higher power levels will, as expected, result in a larger number of wires. Total cross-sectional area of the wires varies from approximately 3,870,000 circular mils (in the case of Option C) to approximately 1,619,000 circular mils (Option D). In the case of the ac distribution system, it will again be necessary to appreciate the additional losses in the system caused by the port-located conversion equipment.

A final point of discussion is to examine the reasons why, if higher dc voltage will reduce loss effects, a higher dc primary distribution voltage (greater than 124-164 VDC) was not selected for the basic concept and for Options A and C. The major rationale for not selecting a higher voltage distribution system is the state of switching technology, particularly at the relatively high power levels specified. Switch devices capable of switching high dc voltages at high power levels are not yet available to the confidence levels needed to assure reliable operation. These switching devices include those simply used to control the power distribution as well as those used in dc-dc converters supplying the various lower voltages required. Several attempts at initiating technology programs to develop these equipments have been made with various degrees of success, but none have been completed. Accordingly, no hardware is available at the present time nor in the immediate future.

The second reason for not selecting a higher voltage is the impact upon the solar array. Solar arrays are comprised of many small solar cells interconnected in a series-parallel matrix to provide the needed power/voltage combination. Increased voltage levels increase the complexity of the solar array with the attendent reduction in reliability, life, and in poorer operating characteristics resulting from increased internal losses.

1.1.2.2 Data Utilities

The data management, control path, and the CCTV paths are essentially low power and are provided using three different forms of signal paths. Discrete signals or commands are routed utilizing 22 gauge, twisted, shielded pairs (TSP). Ninety pairs are included in the design of deployable structural elements; sixteen of which are preassigned as emergency control originating in the subsystem control module. The remaining 74 pairs are unassigned and may be used to provide interconnections between berthing stations.

The placement of these, or any signal wires, immediately adjacent to power cables is to be avoided. If the designs do not permit the separation of these cable groups, it is necessary to provide metallic separation (shields) to avoid electromagnetic interference caused by power switching.

The data management concept selected for this study presumes the use of an integrated, on-board data processing approach that uses a data bus design to minimize the overall number of discrete paths between satellite or platform communications interfaces. The proposed data bus link consists of four pairs of fiber optic cables. Each pair consists of an independent command and data channel. Four pairs are provided to accommodate reliability concerns (e.g., redundant paths in the event of channel failure) as well as providing for possible requirements calling for independent links to selected payloads. It is recommended that provisions to add up to 100 additional fiber optic cables to permit future system expansion be included in the element design.

The final requirement identified in prior studies is the need to provide at least two channels for routing of CCTV or high bit rate data to the satellite downlink communications system. The suggested coaxial is type RG-303/U.

In summary, it is pertinent to note that the data requirements delineated above are considered to be a generous complement of number and sizes. It is generally, however, consistent with the ASASP and GPS requirements. Further, spacecraft data needs during any program always press to the limit the ability of the structure to accommodate data needs. Hence, again, the generous complement of data utilities in the adopted requirements.

1.1.3 Fluid Utilities

The adopted fluid utilities requirement established for this study is two 2.0 cm coolant lines. Propellant lines are not a requirement for the reasons discussed subsequently.

1.1.3.1 Coolant Lines

Provision of fluid coolant lines is imposed as a requirement since location of radiators adjacent to a heat source may not always be practical. The requirement of two 2.0 cm lines was determined from the payload requirements of Table 1.1-4, which were extracted from Reference 2. For these payloads, the maximum power level was 25 kW.

The use of a central radiator system would require that fluid lines be run
along the structure between the heat source and the radiator and return. The
pumping power required to circulate the coolant varies directly with length
and power dissipation level and inversely with line diameter. For the
reference mission payloads, a practical line diameter is 2 cm. Figure 1.1-9
presents the pump power to circulate Freon coolant through a 2 cm line over 40
meters and return for a range of power dissipation levels. As shown, a
pumping power of less than 0.2 kW is required to circulate coolant to reject
25 kW of payload power.

Figure 1.1-9. Pump Characteristics

Insulation will be required for fluid lines used on the deployable platform to prevent freezing of the coolant during quiet periods. A quantitative estimate of the thermal control system (TCS) requirements for fluid lines is summarized in Table, 1.1-6 for a range of typical TCS coating techniques. These calculations assume the heat transfer area to be that of a 2-cm-diameter straight tube. The calculations show that a radiation barrier insulation ($\epsilon \approx 0.04$) is required to keep the drop in fluid temperature, due to line heat losses, at reasonable levels. A bare metal, such as aluminum, is unacceptable. These materials have high solar absorptance compared to its emittance. This would result in high tube surface temperatures that could cause localized boiling in the fluid line. A multi-layer insulation (MLI) blanket of about 5 to 6 layers would provide the proper emittance. The blanket could consist of concentric wraps of embossed metallized foil. A non-metallic outer layer may be desirable.

Table 1.1-6. TCS Requirements for 2-cm Fluid Lines

SURFACE COATING	EMIT-TANCE	LOSS OF TEMPERATURE (°C) FOR 40-m LINE HEAT LOAD			TIME TO FREEZE FLUID	HEAT LOSS AT FREEZ. TEMP.	TEMPERATURE (°C) SUN LOAD	
	ϵ	1 kW	5 kW	25 kW	HR	W/m	AVERAGE	PEAK
PAINT	0.9	52	10.4	2.0	0.5	3.3	24	122
COATING	0.5	28	5.6	1.2	1.3	2.0	24	122
BARE METAL	0.1	6	1.2	0.3	6.4	0.3	24	122
POLISHED METAL ($\alpha = 0.3$)	0.04	2.4	0.5	0.1	13	0.15	219	381
MLI ($\alpha = 0.4$)	0.04	2.4	0.5	0.1	13	0.15	-37	42

An alternate to the fluid coolant system is a heat pipe system. The heat pipe is a sealed heat transport device and does not require a pump to maintain its operation. A typical installation would use a 2 cm line to transport vapor and a 0.63 cm line to transport liquid. The technology of high capacity heat pipes is developing rapidly. Pipes with the capacity to transport heat loads of a few kilowatts over distances of a few meters are currently in development.

1.1.3.2 Propellant Lines

Integration of propellant lines into the deployable structure was not included as a requirement, although the use of distributed thrusters for either GEO orbit transfer or active modal control was considered.

The use of distributed thrusters has been suggested to reduce the bending loads imposed on the structure during orbit transfer. This advantage is not regarded as sufficient to offset the numerous disadvantages discussed below:

    o   Since the design must provide for failure of a thruster, each of the thrusters lines of force must pass through the platform center of mass for the engine out condition. For the sizes of GEO platforms

this would be applicable to possibly 2 to 4 thrusters. (Concepts utilizing more than 10 distributed thrusters as shown for solar power satellite (SPS) structures are not applicable.) Provisions for this condition would require excessive propellant.

o   The additional cost of providing and installing the additional thrusters, and integrating the cross-feed propellant lines would be excessive. In particular, the folding and thermal control of propellant lines is a significant technology problem.

o   The reduction of the bending and possibly torsional moments, while reducing the individual member loads, may not represent any significant weight reduction for stiffness-critical designs. The weight savings, if any, may be limited to the joints. The reduced loads on the joints and individual members could permit increased packaging efficiency. However, the loads can be reduced by stowage, which appears to be a simpler task.

It is pertinent to note the Large Spacecraft Systems/Propulsion Interaction Work Shop, held on October 22 and 23 in 1981, recommended the use of a single orbital transfer vehicle (OTV) with clustered thrusters for orbit transfer of GEO platforms. For the range of platform mass up to 6000 kg, a single OTV has the capability.

The use of distributed control thrusters is not considered appropriate for platform control in view of the following:

o   The major spectrum of LEO/GEO mission requirements is achievable without special distributed actuators. Sufficient stability is attainable without distributed thrusters.

o   For the special cases where unique payload precision pointing and high levels of stability are required special mounts such as initial pointing system (IPS) or annular suspension pointing system, gimbal system (AGS) will be provided.

If for some reason, distributed control is required, the preferred location for rotary or linear actuators is at the attachments between building blocks. Since the payloads are mounted only at the main housing or adapters, shaping of the basic truss is not required.

1.1.4   Control System

Control system requirements can be satisfied without the mounting of control system equipment directly onto the deployable truss. A control system module is provided to contain control system equipment other than that located at the payloads.

This review examined the three focus mission requirements with the basic platform functions and control philosophy as follows:

o   The platform provides a general-purpose base to support
    special-purpose (and multidisciplinary) payloads whose pointing and
    control requirements can be quite diverse.

o   The platform provides gross stabilization and pointing control.
    Nominal attitude will be a local level and/or inertial orientation
    selected to minimize the platform disturbance torques and the
    resulting control system requirements.

o   Payload precision pointing and high levels of stability will be
    provided by special pointing mounts (such as IPS and AGS).

o   Specialized passive or active control for structural dynamic or
    figure control augmentation can be located at the housings or
    adapters (rather than on the deployable truss).

o   The control system is designed to meet the most common recurring
    control problems - not rare or ill-defined special situations.

As evident from Table 1.1-7, it is feasible to locate all attitude control
system equipment either in the control system module, the payload package, or
at the building-block-to-building-block interfaces. Much of the equipment
listed as mountable on the "control system module or payload package" can
probably be mounted in the control system module for most NASA missions in
which structural deformations are well within pointing requirements.

Table 1.1-7.   Control System Equipment Requirements

COMPONENT	S/C USED ON				POSSIBLE LOCATIONS		
	ASASP	GSP	SPS	GENERIC ONLY	DEPLOY. STRUCTURE	CONTROL SYSTEM MODULE OR P/L PKG.	BUILDING-BLOCK INTERFACE
● SOLAR TRACKERS (ST)	X		X			X	
● SOLAR ASPECT SENSORS (SAS)	X	X	X			X	
● FINE SUN SENSORS (FSS)	X					X	X
● COARSE SUN SENSORS (CSS)				X		X	
● HORIZON SENSOR (HS)	X	X				X	
● INERTIAL REF. UNIT (GYROS)—(IRU)	X	X	X			X	
● MOMENTUM & REACTION WHEELS (MW)		X				X	
● CONTROL MOMENT GYROS (CMG)	X		X			X	
● COMPUTER (COMP.)	X	X	X			X	
● INSTRUMENT POINTING SYSTEM (IPS)	X					X	
● MISC. ROTARY JOINTS (RJ)	X	X	X				X
● INTERFACE ELECTRONICS UNIT (IEU)				X		X	
● MAGNETIC TORQUERS (MT)				X		X	
● MAGNETOMETER (M)				X		X	
● INERTIAL MEASUREMENT UNIT (IMU)				X		X	
● REACTION CONTROL SYSTEM (RCS)		X	X			X	X
● STRUCTURAL ALIGNMENT MEASUREMENT DEVICES				X		X	X

CONCLUSION: ALL ACS COMPONENTS ARE LOCATED ON ADAPTERS OR IN CONTROL SYSTEM MODULE.

1.1.5 Structural Temperatures

Peak structural temperatures range from -100° to 80°C for LEO and -200° to 80°C for GEO. Figure 1.1-10 presents the peak temperatures calculated for the materials shown for an end of life (α/ϵ =1).

Figure 1.1-10. Maximum and Minimum Temperatures

The materials considered were aluminum, beryllium, magnesium, and several graphite and metal matrix composites. The peak maximum and minimum orbital temperatures depend upon the density times specific heat product for a particular material. For a given material thickness, the smallest density specific heat product will yield the largest maximum-to-minimum temperature range. Since a large number of materials is being considered, the materials were ranked according to this product. Beryllium had the largest value of this product, and graphite epoxy the smallest. Therefore, the properties of these materials were used in the analysis. Aluminum is used currently in spacecraft construction; therefore, data for aluminum are presented for comparison.

The member shapes considered were round, square, rectangular tubes and I-sections. The hottest structural temperatures occur when the member shape exposes its largest projected area toward the sun. A measure of this peak heating condition is the ratio of the solar projected area to the radiation area; therefore, the member shapes were ranked according to this ratio. For the member shapes considered, this ratio differs only slightly; therefore, only one or two shapes need to be analyzed. The square tube and the I-section

were selected for analysis. The data presented are for the square tube. The coldest structural temperatures occur during eclipse and are independent of member shape.

Individual truss members may be oriented at various angles with respect to the orbit plane and the sun. The orientation which exposes the largest solar projected area was selected for analysis.

Orbital temperatures were computed with a thermal math model (TMM). This model, for the square tube, consists of four nodes which are connected together by conduction and internal radiation. The nodes are connected to the external environment by radiation to space and by heat flow rates (QDOT's) for the incident solar, albedo, and earth emission fluxes.

1.1.6 Servicing

Servicing is assumed to be at one-year intervals, and consists mainly of replacing consumables or equipment with limited life. Changeout of payloads may be required from time to time because of "state of the art" or completion of mission.

The vehicles used for servicing are the orbiter for LEO and a teleoperator for GEO. It is expected that the teleoperator will use the same docking interface as the orbiter and will have a similar set of RMS.

The design of the platform, therefore, has to include docking provisions at strategic locations, near to payloads and service centers such as the control module. All items likely to be replaced must be designed for disconnect/removal/replacement using the RMS and/or EVA. Factors such as crew visibility, TV coverage, RMS reach, RCS plume effects and orbiter/platform interference need to be considered when designing for servicing.

1.1.7 Orbiter Integratio

The orbiter is obviously an item of major concern in the design of a deployable platform. The orbiter is called upon to perform several functions:
- o Transport the packaged platform to LEO
- o Serve as a base for adding payloads, modules, etc.
- o Checkout and troubleshooting the platform and systems
- c Continued servicing and maintenance for a period of 10-20 years.

In performing these functions, the following factors are of importance:
- o Docking/berthing clearances
- o EVA capabilities and safety
- o RCS plume effects
- o RMS reach and capability
- o TV & crew visual coverage
- o Orbiter power available for platform
- o Payload bay volume, c.g. and weight
- o Mounting in the payload bay, cradles/pallets, trunnion and keel fitting location and loads
- o Orientation during platform deployment, solar thermal, radiators
- o Orientation, free drift, control authority
- o Cost

1.1.8 Environment

Materials for the deployable platform systems must have a minimum life of ten
years in either LEO or GEO environments. Since transfer time to GEO is
expected to be less than 24 hours with the use of chemical propulsion, the
more severe LEO-to-GEO environment effects will be negligible.

Space environment effects are due to a combination of environments, some of
which act at the surface and others which act throughout the volume (mass).
Solar radiation, vacuum, and micrometeoroids are examples of environments
which act primarily on exposed surfaces, while Van Allen Belt particles, solar
flare particles, and the electron-produced Bremsstrahlung are examples of
environments which act throughout the volumes of objects in space. Figure
1.1-11 illustrates the nuclear radiation components at GEO as a function of
aluminum shielding thickness (the curves are similar for other materials) and
Figure 1.1-12 illustrates the altitude dependence of the natural Van Allen
Belts.

Figure 1.1-11. Radiation Dose Rates at GEO
— Functions of Shield Thickness

0° INCLINATION

Re = EARTH RADIUS
GM/CM² = ALUMINUM

ALTITUDE (NMI)

DOSE RATE, RADS (SI)/DAY

0.5 GM/CM²

1 GM/CM²

2 GM/CM²

8 HR
(3.17 Re)

12 HR
(4.15 Re)

24 HR
(6.6 Re)

*Figure 1.1-12. Natural Van Allen Belt
Dose Rates, 0° Inclination Orbit*

1-23

The solar spectrum and vacuum are well known and are not included herein.
Several materials can be severely impacted by both of these environmental
properties, but thin protective coatings from other materials (such
as thermal control coatings) can and do readily negate any excessive adverse
effects.

Particulate or meteoroid flux can and does get significant as satellites
increase in size and required service life. Figure 1.1-13 shows a
time-averaged meteoroid flux at 1 AU from the sun. This meteoroid flux was
obtained directly from Reference 6 and is sufficiently accurate for both LEO
and GEO platform applications.

Figure 1.1-13. Natural Time Averaged Meteoroid Flux
at 1 AU from the Sun

1.1.9 Payloads, Propulsion Modules, ACS Modules

Generally speaking, the linear platform is deployed without payloads,
propulsion modules, ACS modules, or other large items which are not part of
the basic platform. It is expected that they are added by the RMS to suitable
interfaces subsequent to deployment of the platform structure. There are,
however, possibilities of building some modules into the deployment system;
depending on the size/shape of the module and the size/shape of the platform.
If the circumstances are favorable, the module may be treated as another
housing similar to a building block, and be incorporated onto the end of a

truss. Some items may be mounted directly onto an existing control module or truss housing. If the module is to be added to the platform subsequent to platform deployment, an interface is provided complete with alignment features and all the structural/mechanical/electrical/fluid interconnects required for RMS berthing.

1.1.10 System Pointing Accuracy

The most stringent pointing requirement is delineated in Table 6 of Reference 4 for the GSP application. A value of 0.05 to 0.10° is listed.

Discussion with electronics specialists at Rockwell indicate pointing accuracies of 0.05 to 0.10° will be representative of most applications for the 1990 to 2000 time period, although a small number of applications will require accuracies of 0.03 to 0.02°.

1.1.11 Requirements Perspective

The design approach and requirements presented in Sections 1.1 through 1.10 are the basis for the generic platform development (Section 1.2); deployable truss, utilities folding/deployment, housing, and adapter concepts developed (Sections 1.3 and 1.4) and concept selection (Section 4). A perspective on these requirements are summarized below:

o   The adopted strength and stiffness requirements are at the upper limits of the spectrum of requirements for the 1990 to 2000 time period.

o   The generic platform represents the largest size of platform foreseeable for the 1990 to 2000 time period.

o   The adopted complement of power utilities is representative of the maximum number and size of lines consistent with a 50 kW spacecraft (30 VDC and 124-164 VDC lines).

o   The adopted complement of power utilities is also representative of a 250 kW spacecraft (460 VAC).

o   The adopted complement of data utilities is quite extensive, but can vary considerably with payloads.

o   During the platform design phase, the magnitude of data utilities is generally driven toward the maximum the structure can accommodate.

o   The two 2-cm fluid lines requirement is representative of the maximum coolant fluid line diameter.

o   A pointing accuracy of 0.05 to 0.10 degree is representative of a majority of systems for 1990 to 2000 time period.

This perspective is applicable to the focus missions (Figure 1.1-1) and to the spacecraft configurations shown in Figure 1.1-14.

*Figure 1.1-14. Rockwell Communications Configurations
and SASP*

1.2 GENERIC DEPLOYABLE SPACECRAFT CONFIGURATIONS

The generic linear platform (Figure 1.2-1) is based on the requirements established in this study. The purpose of developing such a platform is not to suggest that this is the best or only configuration available, but to display and understand the many problems encountered in designing a deployable system. Without such a configuration to study, there is a tendency to concentrate on the truss structure and overlook such important points as orbiter integration/packaging, deployment sequence and attachment of one section to another.

The configuration of the deployed platform is similar to the ASASP. The overall dimensions of the structure are 146 meters by 73 meters. The payloads shown (i.e., the reference payload system) are the atmospheric gravity-wave antenna, particle beam injection experiment, astrometric telescope, and IR telescope. Each of the four payloads is mounted at a "hard point" and not on the deployable truss itself. The design goal is to avoid mounting equipment on the deployable truss unless it is absolutely necessary. This policy has been followed throughout all the drawings. The electrical power for the reference payloads, ₋nd spacecraft systems, with allowances for line losses is 50 kW. The solar array is suitably sized and has the necessary rotary joints for two degrees of freedom. A radiator is shown mounted adjacent to the solar array module.

Although the reference payloads are LEO payloads, an orbit transfer vehicle is mounted on the aft end of the platform. Four reaction control system (RCS) modules are shown, of which two are mounted on short booms deployed from the control module, and two are mounted on structural hard points.

The control module (CM) serves three functions, i.e., it is a cradle or pallet for mounting equipment in the orbiter, a building platform for deploying the platform, and it is a part of the spacecraft platform and functions as the control center and houses equipment such as batteries, communications, data storage, and power conversion and control.

Provisions for docking/berthing of the orbiter are shown at the control module, at the solar array module, and at hard points on the structure, suitable for servicing payloads or propulsion units.

The structure consists of building blocks, arranged in such a fashion that they deploy sequentially or in unison to form the configuration shown. There is no "erection" or EVA involved, and there is no requirement for a building fixture or jig.

In the development of the several concepts for the trusses and building blocks, the generic platform was modified slightly to incorporate needs as they arose: for instance, sometimes there are two control modules and sometimes two trusses are joined into one building block.

Subsequent to the development of the generic linear platform, a generic area platform was studied in which the structural assembly behaves as a plate rather than as a number of beams connected together. The advantages expected to be gained of such a structure are:

146 M

36 M — 37 M — 37 M — 36 M

⑧ IR TELESCOPE ⑥ ⑤ ⑦

ASTROMETRIC
TELESCOPE
4500 KG

TEE JUNCTION

②

ATMOSPHERIC GRAVITY
WAVE ANTENNA
100 M DIA
3000 KG

④ ③

48 M

PARTICLE BEAM
INJECTION

RCS 4 PLACES

①

25 M

SOLAR ARRAYS 50 KW TOTAL

SOLAR ARRAY
MODULE

Figure 1.2-1.   Generic Linear Platform

o   A significant increase in stiffness provided payload and equipment
    attachments span to three node points.

o   A significant decrease in torsional-type, thermal-induced
    deflections.

o   Both of the above advantages may permit simplification of the
    control system, depending on the specifics of the design.

o   Significant reduction in GEO orbit transfer-induced member loads,
    particularly for thrust in the plane of the platform. This is
    particularly favorable to joint designs.

o   Significant increase in number of paths for routing of power and
    data lines.

The disadvantages of an area platform such as the Generic Area Platform
Figure 1.2-2 are:

o   A large area platform has drawbacks as compared with a linear
    platform when payload servicing/replacement is considered. The
    platform shown is about 1.5 meters deep. If the depth is increased,
    the accessibility problem is aggravated. This is a problem which is
    common to all large area platforms regardless of the type of
    structure or deployment method.

o   Deployable area structures which deploy in two directions (i.e.,
    length and width) possess certain drawbacks which are not present in
    other concepts:

    -   Difficulty of controlling and holding the platform while it is
        deploying.

    -   All bars deploy simultaneously in both directions, with root
        strength not achievable until full deployment.

Rockwell Inc. is not aware of the need for such an area platform application
for the time period 1990-2000 other than solar arrays and antennas being
developed in other study contracts. Therefore, with the concurrence of
NASA/MSFC, the design of a deployable area platform was discontinued.

RCS (4 PLACES)

ASTROMETRIC
TELESCOPE
6500 KG

SOLAR ARRAYS
50 KW TOTAL

PAYLOAD WITH
RADIATOR

PAYLOAD ATTACH PORTS

SOLAR ARRAY MODULE

SOLAR
ARRAY

96 M
(315 FT)

PAYLOAD
INTERFACE

IR TELESCOPE
16,000 KG

AVAILABLE FOR
DOCKING/BERTHING,
PAYLOAD, RADIATOR,
ETC

30.5 M
(100 FT)

Figure 1.2-2.   Generic Area Platform

1.3 DEPLOYABLE PLATFORM SYSTEMS CONCEPTS

This section describes the individual component concepts developed that, in total, comprise the basic building block (Figure 1) from which automatically deployable platform systems can be constructed. The basic components (Figure 1.3-1) are the deployable truss, utilities integration system, deployment mechanization and rail system, the main housing into which the foregoing systems are folded during launch, and the end adapter.

The candidate designs for each of the aforementioned components are discussed in this section. In Section 1.4, the candidate components are integrated into total building blocks. Also, in Section 1.4, the integrated building-block designs were used to construct the generic spacecraft configuration, starting with packaging in the orbiter and ending with the fully deployed basic platform system.

The following section discusses the candidate designs developed for each of the building-block components discussed above.

1.3.1 Deployable Trusses

The establishment of the candidate deployable truss concepts gave serious consideration to the applicability of existing concepts. The search included review of in-house documents, the applicable documents listed in the four Large Space Systems Technology (LSST) bibliographies (Reference 12), and reviews of reports and discussions with the associated study managers of concepts recently developed/documented. Figure 1.3-2 illustrates most of the designs that were compiled as a result of that effort. Barring unseen proprietary designs, there is no deployable structure panacea, i.e., a structure that can be doubly folded into a very compact configuration (with utilities integration) that can be integrated into an automatically deployable platform system.

Figure 1.3-2 encompasses flight-proven designs, designs for which demonstration models have been made, and proposed concepts. These designs were reviewed on the basis of their suitability to satisfy the adopted strength and stiffness requirements and complement of utilities; compatibility with the total building-block approach; and compatibility with the single bay at a time deployment approach with maintenance of root strength during deployment. The designs using X-braced tension cables such as designs A, B, G, H, and K represent single-folded structures that are not compatible with the adopted GJ stiffness requirements.

The same comment is applicable to Concept F. A demonstration model of this concept was observed at the AIAA symposium in Long Beach, California, held on May 14, 1981. The design is a box truss containing circular longerons and I-section battens into which the longerons nest during stowage. The diagonal system uses X-braced tension straps preadjusted on the ground, so the preload is induced upon extension/locking of the longerons. Strap tension is approximately 45 N. No evidence of utilities integration was present in the model cell, which was approximately 4.6 m on its side. Demonstration of the model was presented by a series of staged slides. The basic deployment

BASIC BUILDING BLOCK

DEPLOYABLE
TRUSS

END
ADAPTER

MAIN
HOUSING

UTILITIES
INTEGRATION SYSTEM

DEPLOYMENT MECHANIZATION
AND RAIL SYSTEM

Figure 1.3-1.   Deployable Platform System Components
—Basic Building Block

1-32

Ⓐ AstroResearch	Ⓔ Vought	Ⓘ Rockwell
CONTINUOUS LONGERON MAST	DOUBLE-CELL, DOUBLE-FOLD TRUSS	WARREN TRUSS— TRANSVERSE FOLD
Ⓑ AstroResearch	Ⓕ Martin	Ⓙ Rockwell
ARTICULATED LONGERON MAST	BOX TRUSS WITH X-BRACING	CABLE CROSS-BRACED— TRANSVERSE FOLD
Ⓒ AstroResearch	Ⓖ Harris	Ⓚ Rockwell
EXTENDIBLE SUPPORT STRUCTURE FOR SEASAT	TOWER SEGMENT	CABLE CROSS-BRACED— LONGITUDINAL FOLD
Ⓓ General Dynamics	Ⓗ Lockheed	ⓁⓂ Rockwell
TETRAHEDRAL TRUSS	TAPERED TUBE	K-BRACES— LONGITUDINAL FOLD

INCORPORATE INTO CANDIDATE CONCEPTS

Ⓓ TETRAHEDRAL TRUSS	Ⓕ MECHANIZATION SYSTEM

Figure 1.3-2. Review of Applicability of
Industry Existing and Rockwell IR&D Designs

concept (obtained from Reference 8), however, for one bay at a time deployment utilizing stored strain energy (with retention of the remaining structure) was used initially in the development of Concepts 4 and 6.

Concept E has been successfully tested in the Neutral Buoyancy Tank at MSFC (References 9 and 11). This design has a limited length storable in the Shuttle cargo bay, since the longerons are not folded. This concept is regarded as essentially an erectable concept, and was not considered further, since no apparent method was foreseeable to use this concept in an automatically deployable platform system. The Rockwell-proposed designs (I and J) were not considered further for the same reason despite the attractive feature of non-folding longerons.

Concepts L and M were not pursued further because of poor packaging characteristics. Concept C (Reference 10) was not significantly different from Concept 1 (Figure 1.3-4).

Concept D represents a very efficient double-folded structure. The basic structure mechanization is quite simple (in the context of the complexity of double folding). Examination of the demonstration model (courtesy of General Dynamics) revealed well designed joints (concentric load paths and a minimum of material). This concept was therefore included (as Concept 3) in the candidate designs, although difficulty with integration into an automatically deployable spacecraft configuration was anticipated. Unquestionably, the design is extremely attractive in an erectable platform system that, through use of a fixture, joins together numerous deployable truss modules.

1-33

The development of new truss concepts resulted in the matrix of truss designs
shown in Figure 1.3-3. This matrix of designs was derived to include the
scope of single and double-folded designs, a design with X-braced tension
cables that could satisfy the GJ stiffness requirements, and designs using
triangular and square cross-sections. The matrix of these design variations
is shown in Table 1.3-1.

Figure 1.3-3. Candidate Deployable Platform Structure Concepts

All of the designs shown (Figure 1.3-3) satisfy the requirements in Section
1.1, with emphasis placed upon:

o   One bay at a time deployment to maintain root strength during all
     phases of deployment. A rail system is provided on the
     building-block main housing for root strength. Upon completion of
     deployment, the main load path from truss to truss is through the
     adapters and main housing (Section 1.3.4).

o   Satisfaction of the adopted strength and stiffness requirements in
     Section 1.1.1.

o   Capability to be integrated into the building block concept shown in
     Figure 1. For example, the matrix of design variations (Table 1.3-1)
     includes no designs that have only a lateral fold despite the signif-
     icant advantage of such a design. Such a design could have clevis
     joints in the longerons approximately 17 m apart.

Table 1.3-1.
Matrix of Truss Variations

GEOMETRIC SHAPE	LONGITUDINAL FOLD COMPRESSION-TYPE MEMBERS	LONGITUDINAL AND LATERAL FOLD COMPRESSION-TYPE MEMBERS	LONGITUDINAL AND LATERAL FOLD TENSION CABLES
	①		
	②		
		③	
	④	⑦	⑤
	⑥ ⑧		

• The eight truss concepts shown in Figure 1.3-3 are discussed in detail in Section 1.4. The structural drawings are presented in Volume II. The main features in the development of each of these trusses are as follows:

o Concept 1 (Figure 1.3-4) utilizes the kinematic advantage of the General Dynamics (GD) tetrahedral truss (for a single-folded design), the folding advantages of nesting the longerons and diagonals into the pyramidal members, and provision of clear space for utilities support trays.

o Concept 2 (Figure 1.3-5) utilizes the high packaging efficiency of the offset longerons and shear panel as shown. The design requires only the diagonals shown in the top plane. Redundancy for meteoroid impact can be provided by addition of lower plane diagonals. The shear panel was used to provide lateral stiffness to the hinge line member to minimize deflection due to the offset longerons.

o Concept 3 (Figure 1.3-6) is included for the reasons discussed previously.

o Concept 4 (Figure 1.3-7) places emphasis on structural simplicity (in contrast to the designs of Concepts 2, 3, 5, 7, and 8), both in regard to member shape and kinematics. All the structural members are circular tubes, with folding of the longerons and telescoping of the diagonals as shown.

PYRAMIDAL MEMBERS

DIAGONAL

LONGERONS

LATERAL

SECTION A-A
SHOWING LONGERONS NESTING IN
THE PYRAMIDAL MEMBERS

Figure 1.3-4. Concept 1—Pentahedral Truss

DIAGONAL

HINGELINE
MEMBER

SHEAR
PANELS

LONGERON

Figure 1.3-5. Concept 2—Warren Truss

Figure 1.3-6. Concept 3—Tetrahedral Truss

Figure 1.3-7. Concept 4—Truss

o   Concepts 5 and 7 (Figure 1.3-8) utilize the advantages of double
     folding (increased structure depth, fewer members and joints, and
     increased packaging efficiency) with provision of a rigid main
     housing structure. Both concepts utilize telescoping battens to
     deploy laterally to the larger cross-section shown. The increased
     depth provided by the double-fold permitted consideration of
     X-braced tension cables (Concept 5). However, in view of the ever
     present concern for maintaining cable tension throughout the thermal
     variation spectrum, a design with compression diagonals was
     considered (Concept 7).

Figure 1.3-8.   Concepts 5 and 7—Truss

o   Concept 6 (Figure 1.3-9) establishes a square truss version of
     Concept 4, i.e., the same emphasis upon structural simplicity.
     The square truss can be either statically determinate (battens
     braced at end bays only) or redundant (all batten bays braced).

Figure 1.3-9. Concept 6—Truss

o   Concept 8 (Figure 1.3-10) has the advantages of the square truss
(redundancy, ease of building-block to building-block attachment,
accommodation of payloads), but with the high packaging efficiency
achieved through nesting of the longerons into the battens, and
the availability of the total area inside the batten for mounting
utilities in trays.

Figure 1.3-10. Concept 8—Truss

1.3.2 Utilities Installations

1.3.2.1 Requirements/Objectives

The requirements/objectives for installation of the utilities into the deployable structure are as follows:

o   Incorporate the adopted requirements for power, data, signal and fluid lines established in Sections 1.1.2 and 1.1.3.

o   Growth capability is desirable.

o   Automatic deployment, as part of the building block, in space and on the ground with manual or ground support equipment (GSE) assistance if necessary.

o   Retraction in space is not necessary, but on the ground retraction is required with manual or GSE assistance if necessary.

o   Minimum number of joints/connections along a truss with no joints preferred.

o   Minimum number of in-space connections with none being preferable. This depends as much on the method of integrating the building blocks into the platform, as it does on integrating the utilities into the building block.

o   On the ground end-to-end checkout is highly desirable including all building blocks and possibly small payloads with no break/remake connections between ground checkout, loading in the orbiter, and final deployment.

o   Protection from adverse environments (thermal, radiation, vibration during launch)

o   High reliability

o   Weight - not a big driver for LEO but important for GEO.

o   Separation of power and data/signal lines (minimum electrical interference)

o   Accessibility - ease of installation, maintenance and replacement, and accommodations of design changes

1.3.2.2 Installation Methods

Four general methods for installation of utilities were investigated;

o   In trays

o   In coils or loops of several configurations

o   On the outside of structural members; for example, secured
    to the outside of longerons

o   Inside structural members such as the longerons

The results of a design review are shown in Table 1.3-2.   The conclusions to
be drawn from this review are:

o   No one method of utilities installation is best for every
    configuration and mission.

o   If room is available, the tray method is preferred for
    integration of a large quantity of utilities.

o   For a limited number of utilities, installation on the outside
    of longerons is preferred.

1.3.2.3   Fluid lines

The fluid lines are nominally two centimeter diameter flexible lines
containing Freon for cooling purposes. Other sizes and shapes are available
to suit the specific requirements of the various configurations investigated.
The two main problems encountered in using such lines are the bend radius and
associated bending moment, and temperature control.

The bend radius required in any truss installation depends on the pitch
distance between batten frames in the packaged configuration. The designer
naturally attempts to keep this distance as small as possible to obtain a high
packaging ratio, hence the importance of bend radius. If it is necessary to
maintain the folded line in one plane the best bend radius obtainable is equal
to the pitch distance less half the diameter (Figure 1.3.-11). If it is
possible to overlap the lines out of plane, the bend radius can be increased
(Figure 1.3-12).

The acceptable bend radius of a 2-centimeter-diameter flexible fluid line is 3
centimeters with an associated bending moment of 7 Nm (courtesy of Metal
Bellows Corp.). In the event that a 2-centimeter-diameter line cannot be
installed, there is always the alternative of using a greater quantity of
smaller lines i.e. four 1.4 centimeters diameter lines. Another interesting
possibility is the "race-track" shape (Figure 1.3-11) which permits a small
bend radius. Table 1.3.-3 lists some characteristics of utilities installed
on the Rockwell building blocks. In cases where the permissible bend radius
of the installation falls below that which is recommended for a 2 centimeters
diameter line, the system uses smaller lines.

Fluid lines require thermal insulation to prevent the Freon from freezing
during eclipse periods. Six layers of MLI (multi-layer insulation) is
estimated to be sufficient protection (Section 1.1.3). The MLI is retained on
the outside of the flexible line by a loosely woven nylon jacket which will
not interfere with the flexing of the line.

Table 1.3-2. Comparison of Utilities Installation

METHOD	PRO	CON
TRAYS	• SIMPLE INSTALLATION—PERMITS STRUCTURAL ASSEMBLY, RIGGING, AND TESTING PRIOR TO UTILITIES INSTALLATION • ACCESSIBLE FOR DESIGN CHANGES • EASE OF MAINTENANCE & REPLACEMENT • GOOD GROWTH POTENTIAL • METEOROID IMPACT PROTECTION • SEPARATION OF POWER AND DATA • GOOD SUPPORT FOR LAUNCH • DISPERSED AGAINST METEOROID IMPACT • GOOD HEAT DISSIPATION FOR ELECTRIC POWER LINES	• EXTRA COST • EXTRA WEIGHT (GEO) • EXTRA SPACE
COILS & LOOPS	• SIMPLE INSTALLATION—PERMITS STRUCTURAL ASSEMBLY, RIGGING, AND TESTING PRIOR TO UTILITIES INSTALLATION • ACCESSIBLE FOR DESIGN CHANGES • EASE OF MAINTENANCE & REPLACEMENT • LIGHTWEIGHT, LOW-COST INSTALLATION • FAIRLY GOOD HEAT DISSIPATION FOR ELECTRIC POWER LINES • GOOD SEPARATION OF POWER AND DATA • LARGE BEND RADII OF LINES	• GROUND CHECKOUT—INCREASED FOLDING TIME • LIMITED GROWTH POTENTIAL • NO METEOROID IMPACT PROTECTION • NOT DISPERSED AGAINST METEOROID IMPACT • LAUNCH SUPPORT COULD BE PROBLEM
OUTSIDE OF LONGERONS	• SIMPLE INSTALLATION • ACCESSIBLE FOR DESIGN CHANGES • EASE OF MAINTENANCE & REPLACEMENT • GOOD SUPPORT FOR LAUNCH • GOOD HEAT DISSIPATION FOR ELECTRIC POWER LINES • LOW-COST, LIGHTWEIGHT INSTALLATION	• LIMITED NUMBER OF UTILITY LINES • MAY NOT BE ABLE TO SEPARATE POWER AND DATA • NO METEOROID IMPACT PROTECTION • NOT DISPERSED AGAINST METEOROID IMPACT
INSIDE OF STRUCTURAL MEMBERS	• METEOROID IMPACT PROTECTION • GOOD SUPPORT FOR LAUNCH • LIGHTWEIGHT INSTALLATION	• SMALL BEND RADII OF LINES (NEW TECHNOLOGY) • MAY REQUIRE INCREASED LAY ANGLE (INCREASED WEIGHT & LOSSES) • DIFFICULT TO INSTALL—INSTALLATION DURING PIECE-BY-PIECE STRUC. ASSY. • NOT ACCESSIBLE FOR DESIGN CHANGES • DIFFICULTY OF MAINT. & REPLACEMENT • GROWTH POTENTIAL POOR • MAY NOT BE ABLE TO SEPARATE DATA AND POWER • NOT DISPERSED AGAINST METEOROID IMPACT • POOR HEAT DISSIPATION FOR ELECTRIC POWER LINES • NOT SUITABLE FOR SMALL MEMBERS (SMALL PLATFORMS)

1-42

RACETRACK CROSS-SECTION
SHAPE PERMITS REDUCED
BEND RADII

Figure 1.3-11.   Utilities in One Plane

Figure 1.3-12.   Utilities with Overlap and
Increased Bend Radius

Table 1.3-3. Electrical and Fluid Utilities Characteristics

| CONCEPT | ELECTRICAL | | FLUID | |
	METHOD	BEND RADIUS (cm)	METHOD	BEND RADIUS (cm)
1	TRAYS	6.3	TRAYS	12
2	TRAYS	3.3	OVERLAP FOLDS	20
3	COILS	24.0	OVERLAP FOLDS	20
4	OVERLAP FOLDS	22.3	OVERLAP FOLDS	14
5	TRAYS	2.9	TRAYS	4
6	OVERLAP FOLDS	22.3	OVERLAP FOLDS	14
7	TRAYS	2.9	TRAYS	4
8	TRAYS	2.5	TRAYS	3.1
8	LONGERONS	20.3	LONGERONS	20

1.3.2.4 Electrical Utilities

The electrical utilities consist of power lines; twisted shielded pairs for both
signal and data lines; and for data lines, fiber optics and coaxial.

The twisted shielded pairs and coaxial lines are of small diameter and are
flexible and pose no problems pertinent to folding in the trays or into loops
as required. The type of overall platform design envisioned by Rockwell
avoids the problems of multiple coaxial connectors. There are no coaxial
connectors on the trusses where flexing occurs and, since the entire platform
is packaged and deployed as a unit witnout piece-by-piece assembly, there are
very few connectors in a line which may run from one end of the platform to
the other, traversing several building blocks in the process.

Fiber optics are sensitive to radiation degradation and to cracking caused by
thermal cycling. Also, at low temperature some fiber optics cease to
transmit. The present drive in the industry is to improve fiber optic
materials and to develop shielding to overcome these problems. This is listed
as a line item in the technology development section. In the event fiber
optics are not ready for 1986, copper lines can be used instead.

Power lines for space platforms do not need the heavy insulation commonly
found on electrical cables for earth applications. There is no moisture
problem in space and no requirement for "idiot proof ruggedness".
Consequently, a light, loosely woven insulation is recommended. Such
insulation will save weight, provide flexibility, and avoid cracking when
folded.

The acceptable bend D/d ratios associated with the sizes of power cables
selected are shown in Table 1.3-4.

Table 1.3-4. Permissible Electrical Conductor D/d Bend Ratios

CABLE SIZE	D/d	BEND RADIUS (cm)
0	6	2.45
2	6	1.96
4	6	1.55
WIRE BUNDLES	10	23

The actual bend D/d ratios (Table 1.3-3) all exceed these acceptable values.

The permissible D/d shown in Table 1.3-4 were obtained by review of the parametric data (Figures 1.3-13 through 1.3-16) furnished by Tension Member Technology (TMT). The review used a maximum permissible strain of 2.5% based on upward adjustment of the strain data shown in Figure 1.3-18 since the data shown are for cyclic reversal of strain which does not occur in the bending of the cables. Further, the value of 2.5% is regarded as reasonable since the following analysis includes the strain imposed during fabrication of the cable which occurs only once. The basis of the 40 cycles of strain shown in Figure 1.3-17 comes from the assumption of 10 cycles of folding (during installation, checkout, and final deployment) multiplied by a scatter factor of 4.

The analyses are all based upon the use of a 15-degree lay angle (essentially standard cable fabrication practice).

o   For a No. 2 conductor a maximum strain of 1.5% is determined from Figure 1.3-13 for D/d = 6. The D/d = 6 is conservative.

o   For a No. 0 conductor a maximum strain of 1.1% is determined from Figure 1.3-14 for D/d = 6. The D/d = 6 is conservative.

o   For a 1 x 7 wire bundle comprised of No. 2 conductors, from Figure 1.3-15, the curvature ratio for bending to a D/d = 10 is 19, the initial wrap curvature is 32. From Figure 1.3-13 the maximum possible strains are respectively 1.2 and 1.15%, or a total of 2.35%. A 1 x 7 bundle of No. 0 conductors is less critical. It is pertinent to note the cyclic strain is less than half of the total strain.

o   A 1 x 19 wire bundle to a D/d = 10 will have less strain.

The bending moments associated with bending these cables, to the D/d ratios discussed herein, are not significant to the concept development. For example, the limit bending moment incurred in bending a No. 0 cable to a D/d = 6 is 0.7 Nm.

The background for the foregoing analysis is based upon the additional documentation (and discussions) provided by TMT as follows:

The bending of a helically wound cable produces bending, extensional, and torsional strains in the individual cable elements. The bending strain is a result of the change of curvature of the elements as the cable is bent.

Figure 1.3-13. Maximum Bending Strain
—No. 2 Conductor

Figure 1.3-14.   Maximum Bending Strain
—No. 0 Conductor

Figure 1.3-15.   Minimum Bending Curvature Ratio
—1 x 7 Structure

Figure 1.3-16. Minimum Bending Curvature Ratio
—1 x 19 Structure

Figure 1.3-17. Copper Filament
Fatigue Data

Extensional strain occurs when the elements of the cable are prevented from axial movement due to friction forces among them, thus requiring the elements to elongate or foreshorten to comply with changes in their local path length as the cable is bent. This friction-induced extensional strain of the cable elements is in addition to any strain which may exist due to tensile loading and elongation of the complete cable assembly. Torsional strains are the result of twisting of the individual elements due to bending distortions of their helical paths.

Both the bending and torsional strains induced in individual cable elements become smaller for decreasing element size relative to the total cable size. Extensional strains due to bending become smaller with reduced values of internal cable friction.

The analysis described in this report assumes that both the extensional and torsional strains are negligible and that only bending strains are significant. This assumption is valid for a frictionless cable wherein the elements are free to move axially with respect to each other. The known techniques for approximating this frictionless condition are the utilization of ample cable lubrication and/or a "loose pack" cable design. For some applications, low cable friction can be achieved by enclosing the cable assembly within a loose-fitting tube or hose which contains a lubricant such as a liquid fluoropolymer. Of course, such a design is not suited for deployable space structures. However, a "loose pack" cable design is quite appropriate. In such a cable, the individual elements ideally are helically wound and held loosely together with some average spacing among them. The result is a nearly frictionless cable which provides for minimum strain on the individual elements during cable bending.

The No. 2 (19 x 35) and No. 0 (19 x 55) cable constructions are defined as "cables" which consist of 19 "strands," each of which consists of a number of "elements" (35 and 55, respectively). The 19 strands are arranged with one strand in the center of the assembly, a layer of six strands around the center strand, and a layer of twelve strands around that. The 1 x 7 and 1 x 19 constructions are defined as "cables" (or "strands") which consist of a number of "elements" (7 and 19, respectively). In each case, the "elements" are the smallest subunits of the construction.

The numerical analysis included computation of the bending strains induced in the individual cable elements both during original manufacture of the cable assembly and as a result of bending this assembly to various ratios of bending diameter to cable diameter. Figures 1.3-13 and -14 show the results of this analysis for the No. 2 and No. 0 cable constructions. For this analysis, it was assumed that the helical direction of the elements within the individual strands was opposite that of the strands in the complete cable assembly. It was also assumed that the 19 strands were manufactured as a "bunched" strand configuration. Furthermore, the analysis required that the lay angle of the elements within the strands be equal to the lay angle of the strands within the cable assembly. Without this restriction, the analysis would have required an additional plotting dimension.

The curves in Figures 1.3-13 and -14 are dimensionless and can be applied to any size cable made with the indicated configurations. On each of these curves, the reference angle Θ defines the location of the strand within the cable ($\Theta = 0$ corresponds to the strand furthest from the center of curvature of the entire cable assembly). Similarly, the reference angle $\emptyset$ defines the location of an individual element within that strand ($\emptyset = 0$ corresponds to the element which is furthest from the cable centerline). The combinations of Θ and $\emptyset$ indicated in these figures correspond to the locations of the maximum element bending strain (minimum radius of curvature).

The curve for D/d = infinity corresponds to a straight cable assembly and indicates the maximum bending strain (minimum radius of curvature) in individual elements as the result of the elements being formed into a double helix during the cable manufacturing process. The location of this maximum bending strain corresponds to $\emptyset = 0$ for all values of Θ. In other words, for a straight cable, this maximum bending strain occures in the cable elements which are furthest from the cable centerline.

The remaining curves for various values of D/d indicate the maximum bending strain (minimum radius of curvature) in the individual elements after bending the entire cable assembly. In all cases, this maximum bending strain is that which is produced as a cable element, which is initially straight, and assumes some final radius of curvature in the bent cable assembly. Not included in this analysis is any initial state of strain which the individual elements may have had as the result of wire drawing or heat treating processes occurring prior to the elements being formed into the cable.

Note that the location of the maximum bending strain changes as a function of both the element lay angle and the ratio of the bending diameter to the cable diameter. The reader is cautioned against attempting to take the difference between the D/d = infinity curve and any other curve to determine the change in element bending strain due to bending the entire cable assembly. This procedure will not yield accurate results in all cases, since the site of maximum bending strain within a straight cable may be different than the site of maximum bending strain within a bent cable. Furthermore, even if the sites of maximum bending strain are identical in both the straight and bent cable, it is possible that for some cable geometries and bending diameters, the radius of curvature of an individual element may pass through infinity as the cable is bent, thereby producing a change in strain due to bending which is greater than the net bending strain which exists either before or after the cable is bent.

Figures 1.3-15 and -16 for the 1 x 7 and 1 x 19 configurations indicate the minimum bending curvature ratio, which is the minimum radius of curvature of an outer layer element divided by the radius of that element. Again, these curves are dimensionless, and they can be applied to any size cable made with the indicated configuration. The curve for D/d = infinity can be used to describe the minimum radius of curvature of one of the outer elements in a straight cable. The remaining curves indicate the minimum radius of curvature of one of the outer cable elements after the cable is bent.

All the four curves have been corrected to take into account the fact that the
diameter of the complete cable assembly increases with increasing lay angle of
the individual elements and strands. In other words, for a D/d ratio of 10, a
larger bending diameter is required for a cable assembled with 20-degree lay
angles than is required for a cable assembled with 10-degree lay angles.

The curves in 1.3-13 and -14 may be used directly to determine the maximum
bending strain produced in an individual element of a No. 0 or a No. 2
conductor as the result of the original cable manufacturing process or as a
result of bending the cable to a specified bending diameter. It is important
to note, however, that when establishing a value for D/d, the "d" applies to
the outside diameter of a bare conductor. Any insulating jacket which is
applied over the conductor must be ignored for purposes of determining the
maximum strain.

All the curves require that the lay angle of the cable component be specified
in order to determine the maximum bending strain or the minimum bending
curvature ratio. For a cable component which follows a simple helical path,
the lay angle is defined as:

$$\text{Lay angle} = \text{Arctan } \frac{2\pi r}{\ell}$$

where

- r = the pitch radius of the cable component as measured
  from the axis of the helix to the center of that
  component, and

- ℓ = the lay length of the cable component (the distance
  measured along the axis of the helix corresponding
  to one helical pitch of the cable component).

1.3.3 Deployment Mechanization Concepts

The requirements for the deployment mechanism are:

- o Automatic deployment - in space, on the ground manual or GSE
  assistance is permissible.

- o Retraction is nice but not a firm requirement.

- o One bay at a time deployment.

- o Controlled rate of deployment. Sometimes it may be necessary to
  synchronize several trusses being deployed.

- o Root strength of truss maintained throughout deployment.

- o Suitable for use with the building block approach for deployment of
  a platform.

- o Compact or foldable.

o   Low power consumption.

o   High reliability.

o   Suitable and safe for EVA operations in the event of a malfunction.

o   Able to generate extra force in the event of a "hang-up" or jam.

The following sections describe the deployment techniques considered in this study.

1.3.3.1 Pressurization

Pressurization systems were investigated but no suitable applications were discovered.

1.3.3.2 Cable Deployment Systems

Cable systems are sometimes used for deployment and/or retraction of trusses and similar structures. They may be used as the prime motive source or in conjunction with deployment springs, in which case the cable may function as a restraining device. Cable systems tend to deploy all the bays of a truss simultaneously or in a random fashion. This may be acceptable for a single truss but is not acceptable for a system with many trusses. A remedy for this uncontrolled deployment is to tie all of the batten frames together by latches which are released sequentially. Alternatively a "hold-back" sequencing mechanism can be incorporated in the main housing. Another and more complex method is to have a separate cable system for each bay.

Depending on the truss being used, a cable system will probably not develop root strength of the truss unless it is aided by auxiliary guide rails.

Although cable systems were investigated, the truss concepts developed herein were not appropriate for the use of cables.

1.3.3.3 Stored Energy Deployment Systems

Of the stored energy devices available, mechanical springs are the most suitable for truss deployment. Other devices such as gas cylinders are more complex and bulky and less reliable. Mechanical springs used may be tension, torsion, compression, leaf or any of the other forms available.

Spring deployment systems have many of the same characteristics as cable systems; simultaneous bay deployment, lack of accurate control over deployment rate, and lack of root strength development. These drawbacks can be overcome by the addition of other devices, such as restraining cables, sequenced latches and guide rails.

Concepts 4 and 6 were initially designed for torsion spring deployment using sequenced mechanisms as shown in Figure 1.3-18. This is a mechanism which holds adjacent battens together as part of the truss stowed stack. Upon receipt of a command signal, a fuse wire which holds together the two halves of a nut is melted. The nut and bolt separate and the batten is free to deploy under the influence of torsion springs (not shown).

Latching mechanism
between No. 1 & No. 2
battens. Shown in the
open configuration.

NO. 3 BATTEN   NO. 2 BATTEN

NO. 1 BATTEN
DEPLOYED

*Figure 1.3-18.   Latching Mechanisms
between No. 2 and No. 3 Battens*

Spring deployment is usually not as positive as a mechanical drive. It is
sometimes difficult to obtain a reserve of force without inducing unwelcome
accelerations in the item being deployed. For longerons which unfold and
move to an over center or "in line" configuration, light springs located at
the longeron center hinge are very useful. They can provide a kick over the
last few degrees of movement which is difficult to obtain by other means.
Such springs were used in the design of longeron latches as shown in
Figure 1.3-19.

● LONGERON: OFFSET HINGE WITH HOOK LATCH

● LONGERON: IN LINE HINGE

● LONGERON: OVER CENTER LINKAGE HINGE   ● LONGERON: CENTER LATCH

Figure 1.3-19.   Longeron Latching Mechanisms

1.3.3.4 Mechanical Deployment System

The mechanical deployment system used is the same or equivalent to the recipro-
cating tape and pulley with integral guide rails developed by General Dynamics
for their tetrahedral truss (Figure 1.3-20).

*Figure 1.3-20. Deployment Rails
and Mechanism*

The system consists of two guide rails (Figure 1.3-21), each carrying a tape
and pulley arrangement which advances to deploy one bay, then returns to
deploy the next bay. To completely control the motion of the truss and to
develop root strength, the guide rails need to extend a distance of two
deployed bays from the front of the stowed truss stack. The mechanism needs
to extend only half way along that distance. The pulleys are motor driven
and are controlled electronically. A method of folding the guide rails and
mechanism is shown on Drawing 42712-016, sheet 4 (Volume II).

Figure 1.3-21. Detail of Deployment Rail

For a truss whose profile changes during deployment (Concepts 1, 2 and 3) the
two rail system just described is used. However, for trusses whose profile
does not change during deployment (Concepts 4, 5, 6, 7 and 8) a variation is
available. It is possible to use 3 or 4 guide rails, (depending on whether
the truss is triangular or square) the length of the rails being equal to only
one bay in front of the stowed truss stack. The operation of the rails and
mechanism remains essentially unchanged.

The reciprocating mechanical deployment system is the design selected for the
deployable platform. It meets all of the requirements and does not suffer
from the drawbacks of the other systems considered.

1.3.3.5 Payload Deployment

One problem associated with the use of guide rails arises when extending a
truss which has a payload or module so wide that the guide rails cannot
straddle it, (Figure 1.3-22) and therefore cannot be unfolded until the truss
has extended and moved the large payload out of the way. Obviously, if the
guide rails are not in position when the truss/payload is moving, there is no
root strength developed.

Figure 1.3-22. Deployment Rail Issue

The·e are several possible sol·tions.

Solutior.]: Use fixed rails (Figure 1.3-23). This design uses more stowage
length in the orbiter and the large payload is not supported
directly from the main housing.

Figure 1.3-23.   Fixed Rail Method

Solution 2: Penetrate the module (Fig·~e 1.3-24). It is not likely that the
rails would be allowed +ʊ penetrate an actual payload but it is
quite possible that t'ey could ponetrate a structural module.

Figure 1.3-24.   Penetration Method

Solution 3: Spar booms (Figure 1.3-25). This appears to be the most feasible
solution to the stated problem for situations with payloads and
modules as well.

RAILS IN POSITION

2 SPAR BOOMS   RAILS STOWED   BOOMS RELEASED
EXTENSIONS   & RETRACTED

Figure 1.3-25.   Spar Boom Method

1.3.4 Main Housings and Adapters

This section describes the array of main housings and adapter designs (Figure 1.3-26) developed for the candidate concept trusses (discussed in Section 1.3.1) that are compatible with the building-block concept. Additional information is provided in the drawings listed in Volume II.

Emphasis in the drawing development was placed upon conceptual rather than detailed design. Of primary concern was the overall concept integration with the truss, rail system, accommodation of docking ports and payloads, and suitability for inter-building-block attachments. Sufficient detail was presented to support the weights and cost analyses (Section 1.4).

The primary functions of the housings are as follows:

o   Attachment of the deployable truss, mechanization, and rail system components.

o   Attachment of electrical, data, and fluid utilities feed-through connections (as required).

o   Provisions for mounting of docking port support rings for orbiter berthing or payload attachment.

o   Provision for structural attachment with adjacent building-block housings and/or adapters with accommodation of the variations in the building blocks orientation.

o   Provision for structural attachments for orbiter installation.

The structural concept for all the main housings shown is expected to be built up from numerically controlled integrally machined aluminum panels (2219-T6 or equivalent) to a truss or skin-stiffened construction depending on the specific design conditions. Thermal gradients can be greatly minimized to reduce the local thermal distortion (if required). If aluminum is not adequate, (depending on the pointing accuracy requirement) the main housing can be constructed of composite materials, but with increased cost.

The adapter functions are as follows:

o   Provision of attachments to mount onto the extremity of the basic deployable truss.

o   Provision of all hardware to permit subsequent RMS attachment of payloads, RCS modules, and/or orbiter berthing ports.

o   Provision of automatic electrical and fluid line connectors.

o   Provision of structural stability to the main housing during orbiter boost.

1-58

TRUSS CONCEPT	HOUSING CONCEPT	ADAPTER CONCEPT
① ④		
② ⑥ ⑧		
③		
⑤ ⑦		

Figure 1.3-26. Candidate Housing and Adapter Concepts

While three concepts are shown for the adapter, the most likely construction
is that of a numerically controlled, integrally machined aluminum design
(thermal stability permitting). The machined panel permits the greatest
flexibility for mounting of latches, connectors, etc.

1.4   DEPLOYABLE PLATFORM SYSTEMS CONCEPT INTEGRATION

This section describes the integration of the specific deployable truss
concepts (1.3.1), utility folding concepts (1.3.2), deployment mechanization
concepts (1.3.3) and main housings and adapters (1.3.4) into 8 candidate
building block concepts that are subsequently compared in the concept
selection study of Section 4.

Unquestionably, a comparison of these diverse designs for satisfaction of a
specific platforms unique configuration and performance requirements
represents an ample challenge but is possible within the scope of this study.
Comparison of the 8 concepts for more than one platform of different size,
strength, stiffness, and utilities accommodations needs, while preferable, was
beyond the scope of this study. The best compromise therefore, was to perform
the comparison in detail (production of drawings) for one baseline platform
designed to one set of baseline requirements and, to the maximum extent
possible, analyze and/or review the implications associated with departure of
size and requirements from the baseline.

The generic platform described in Section 1.2 was the baseline platform, with
the adopted strength, stiffness, and utilities accommodations representing the
baseline requirements. All 8 concepts were constrained in size to permit
packaging of the generic platform in the orbiter as schematically shown in
Figure 1.4-1. Additional details pertinent to packaging are shown on Drawing
42712-020 (Volume II). The resulting deployable truss dimensions are shown on
Figure 1.4-2. It is recognized that other options for each concept are
possible. The options shown were the most likely at that point in the study.
In fact, Concepts 2, 6, and 8 were subsequently (after completion of
structural and thermal analyses) packaged as shown in Figure 1.4-3, permitting
an increase in the truss width and depth. Hence, the data shown in Section 4
for these concepts are slightly pessimistic.

Figure 1.4-1. Concepts for Packaging of
Generic Platform

NOTE: All dimensions are in meters.

Figure 1.4-2. Structural Concept Dimensions

CONCEPT 2   CONCEPT 6, 8

*Figure 1.4-3. Final Concept for Packaging
(Concepts 2, 6, and 8)*

Referring to Figure 1.4-2, it is pertinent to note that the largest truss
dimensions compatible with orbiter space available, were used for the
following reasons:

o   Packaging efficiency is increased with increase in truss depth

o   Best accommodation of utilities

o   Fewest structural members and joints (reduced cost and minimum
     weight)

The following sections describe the structural sizing method and approach, the
8 integrated candidate building-block designs, the packaging of the generic
platform utilizing these designs, and the thermal, mass properties, and
fabrication cost data developed for use in the concept selection. Finally, a
discussion of significant miscellaneous issues is presented.

1.4.1 Structural Sizing Method and Approach

A summary of the design ultimate compression load, shape, and structural sizes
for the 8 deployable truss individual longeron, batten, diagonal and/or
pyramidal members is presented in Table 1.4-1. The generation of these data
are described as follows:

o   The individual compression loads were obtained by computer analysis
     of each truss (dimensions shown in Fig. 1.4-2) for the concurrent
     adopted limit bending and torsional moments of respectively,
     2.5×10^4 and 1×10^4 Nm. An ultimate safety factor of 1.5 was
     used. The computer used equations developed from hand analyses
     which are sufficiently accurate for the purposes of this study.

o   The individual compression load in conjunction with the member
     length and specified material properties was input (automatically)
     into a column analyses subroutine. A CRT plot for each member is
     obtained such as that shown in Figure 1.4-4 for either longeron,
     batten, diagonal, or pyramidal members of circular, square,
     rectangular or I shape. The material properties used for the
     T300/934 graphite composite design was $E_L=143,000$ and $E_T =$
     17,250 mpa and for the P75S/934 $E_L = 231,000$ and $E_T = 28,000$ mpa.

Table 1.4-1. Structural Sizes to Adopted Strength and Stiffness Requirements

CONCEPT	CHARACTERISTIC	LONGERON	PYRAMIDAL	DIAGONAL	BATTEN **
①	ULT. LOAD (KN)	28.8 ✓	12.0	15.3	5.4
	SHAPE	R	I	C	I
	DIMENSIONS (CM)	5.0, 0.43, 2.5, 0.43	5.5, 0.1, 5.3, 0.18	4.7, 0.15	5.4, 0.09, 4.6, 0.13
②*	ULT. LOAD (KN)	24.3 ✓		19.6	
	SHAPE	R	—	C	—
	DIMENSIONS (CM)	3.8, 0.43, 2.5, 0.43		3.2, 0.26	
③	ULT. LOAD (KN)	12.5	4.3		2.1
	SHAPE	C	C	—	C
	DIMENSIONS (CM)	4.4, 0.26	2.8, 0.31		2.8, 0.18
④	ULT. LOAD (KN)	36.0 ✓		14.4	10.3
	SHAPE	C	—	C	C
	DIMENSIONS (CM)	3.75, 0.51		4.7, 0.16	3.1, 0.19
⑤	ULT. LOAD (KN)	2 @ 12.5		5.2	6.9
	SHAPE	R	—	TENSION STRAPS	I
	DIMENSIONS (CM)	4.75, 0.13, 2.5, 0.15			8.1, 0.15, 5.1, 0.15
⑥	ULT. LOAD (KN)	22.4 ✓		9.5	5.9
	SHAPE	C	—	C	C
	DIMENSIONS (CM)	3.5, 0.5		4.5, 0.09	2.0, 0.33
⑦	ULT. LOAD (KN)	2 @ 12.5		10.4	5.9
	SHAPE	R	—	R	I
	DIMENSIONS (CM)	4.75, 0.13, 2.5, 0.15		4.8, 0.13, 4.8, 0.13	10.5, 0.15, 5.1, 0.15
⑧	ULT. LOAD (KN)	2 @ 11.9 ✓		10.7	5.9
	SHAPE	R	—	R	I
	DIMENSIONS (CM)	3.5, 0.22, 2.4, 0.22		3.3, 0.48, 2.5, 0.23	8.7, 0.10, 4.6, 0.1

KEY TO DATA

SHAPE DENOTED BY C
DIMENSIONS:
5.0 × 0.125 CM

SHAPE DENOTED BY R
DIMENSIONS: 5.0, 0.5, 2.5, 0.4 CM

SHAPE DENOTED BY I
DIMENSIONS: 4.0, 0.3, 2.0, 0.4 CM

NOTES:

*SHEAR WEB FOR CONCEPT 2 —2.5-CM-DEEP ALUMINUM CORE, 0.005 CM GRAPHITE EPOXY FACE SHEETS

**BATTEN OR LATERAL

● DATA OF TELESCOPING MEMBERS REFER TO INNER MEMBER.

● MATERIAL IS T300/934 GRAPHITE EPOXY COMPOSITE UNLESS NOTED BY ✓ (ADJACENT TO LOAD) WHICH DENOTES T75S/934.

● SIZING IS TO ADOPTED STRENGTH AND STIFFNESS REQUIREMENTS.

Figure 1.4-4. Example of Column Sizing Data

o   For the longerons, data such as shown in Figure 1.4-4 were compared
    with the AE requirement compatible with the adopted flexural (EI)
    stiffness requirement of $2x10^8$ nm^2. For example, for Concepts
    1, 2, 4, 6 and 8, the AE requirement was more critical than the
    column stability requirement. For these cases the higher modulus
    material was used to maintain good packaging efficiency and/or avoid
    solid members. Note that for an EI requirement equal to half the
    adopted value, the T300/934 would be used. The cost penalty with
    use of the P75S/934 was accounted for in the fabrication cost
    analyses. For all the longerons the sizes were based upon the best
    compromise, through discussion with the designer, in regard to
    packaging, suitability of end joint attachment, and space for the
    folding joint.

o   For the diagonal, battens, and/or pyramidal members, the data such
    as shown in Figure 1.4-4 were developed with sizes determined based
    upon the best compromise with the designer as described above. The
    sizes obtained were checked (excepting Concepts 2 and 5) for
    satisfaction of the adopted torsional stiffness (GJ). For Concepts
    1, 3, 4, 6, 7, and 8 the designs satisfied the adopted torsional
    stiffness of $5x10^6$ Nm^2 (Concept 3 in fact had a GJ five times
    greater than that required). For Concept 5 the X-bracing members
    AE values were sized to satisfy the GJ requirement. For Concept 2,
    NASTRAN analysis was used. The NASTRAN analysis included elastic
    stability analysis and shear stiffness analyses of the individual
    panel, including the cutouts (reinforcing around cutouts). Further,

since the total Warren truss design included an offset between
the longerons and diagonal braces, a two-bay model of the
structure was made.

The data of Table 1.4-1, as determined by the above discussion, are shown on
the structural drawings of the eight candidate concepts. Additional discrete
analyses were performed to support the concept development and mass properties
data tabulated in Section 1.4.5. These analyses encompassed the housings,
adapters, utilities support trays, and launch support cradles.

1.4.2 Eight Candidate Building-Block Concepts

1.4.2.1 Concept 1

The structure (Figure 1.4-5) is a pentahedral truss formed essentially from
one-half of the General Dynamics tetrahedral truss, but with three differences:

o   The concept folds only in the axial direction.
o   A telescopic diagonal is provided across the base of the
    pyramid-shaped bay.
o   Members of various cross-sections (e.g., [＿＿] or I) are used which
    nest one within another, thus permitting a higher packaging ratio.

Figure 1.4-5.   Concept 1

The folded truss is stowed in a rigid triangular housing from which it is
deployed one bay at a time along a pair of guide rails by means of a recipro-
cating mechanism. To enable the truss to develop root stiffness while deploy-
ing, the rails must be a minimum length of two bays plus the stack length. The
guide rails may be folded back alongside the housing for ease of stowing in the
orbiter.

Subsequent to full deployment, root stiffness is developed by attachment of the
truss to the rear face of the housing.

The adapter is a rigid assembly which attaches to, and moves with, the far end
of the truss. It is the interface for payloads or modules and contains mechan-
ical/structural latches, electrical/fluid interfaces and an alignment system.

1-65

ORIGINAL PAGE IS
OF POOR QUALITY

Space Operations/Integration &
Satellite Systems Division

Rockwell
International

The electrical utilities are mounted in trays which are attached to the truss
pyramidal members and pivot about the tray centerline (Figure 1.4-6). There
is ample room for the full complement of utilities. The fluid lines are
installed on the square face of the truss in a series of pivoting trays.

The packaging ratio is 15 to 1.

Figure 1.4-6. Installation of Utility Trays
(Concept 1)

1.4.2.2 Concept 2

This concept is a deployable Warren truss, as shown in Figure 1.4-7. The
truss is supported in a housing during orbiter launch and is deployed from
it along a pair of rails by a reciprocating mechanism. The length of the
housing is dependent on the number and size of the bays to be packaged. For
the truss to be under control during deployment, the minimum length of the
rails is equivalent to the length of two bays plus stack length. This will
usually provide fairly long rails which need to be folded for convenient
packaging in the orbiter. During deployment, the root strength of the truss
is developed by the truss attachments rolling in the deployment rails.
Subsequent to full deployment, the truss root strength is developed by the
attachment of the truss to the housing structure. The truss consists of
folding longerons, telescoping diagonals and rigid sandwich panels that form
the shear panels. Because the panels are rigid, there is a choice of design
such as machined waffle or honeycomb panel.

Each longeron is hinged at the middle, and the two half-longerons fold one
inside the other. There is an offset between the axes of the diagonals and
the longerons.

The adapter is a square, rigid assembly which also acts as the last shear
panel in the truss. It is the interface for payloads and other modules and
contains all of the elements necessary for alignment, berthing and utility
interfacing.

The design of the shear panels is particularly suitable for the installation
of utilities in trays (Figure 1.4-8). The electrical power and the
signal/data cables are in two separate trays, pivoting in slots cut in the
shear panels. The fluid lines which use elbow fittings, to avoid small bend
radii, are mounted in similar fashion in other slots in the shear panels.

The packaging ratio is 21.6 to 1.

- DEPLOYS FOLDS AXIALLY
- PLATE TYPE SHEAR MEMBERS
- ROUND SECTION TELESCOPIC DIAGONALS
- ⌐⌐ SECTION LONGERONS
- LONGERONS ARE OFFSET

MAIN
HOUSING

ADAPTER

DEPLOYMENT
RAILS

DETAIL OF JOINT

Figure 1.4-7.   Concept 2

FLUID LINES

DATA LINES
POWER LINES

Figure 1.4-8.   Installation of Utilities
(Concept 2)

1.4.2.3 Concept 3

Concept 3, the tetrahedral truss, is the General Dynamics design used in its
entirety (Figure 1.4-9). It is a good, practical design of a deployable truss
which has been demonstrated as a working model on many occasions. The truss
is a double-fold system which packages into a small volume. All of the
members are round tubes which converge without offset at the joints. Springs
are used at the joints to assist in the final deployment of struts and to lock
them in position.

Figure 1.4-9. Concept 3

The deployment mechanism is the same as in Concepts 1 and 2, i.e., a
reciprocating mechanism with folded guide rails.

During deployment the truss develops root strength through its interface with
the guide rails. Subsequent to deployment, root strength is developed through
the attachements between the truss longerons and the main housing, or between
the truss longerons and a subsidiary structure (Section 1.4.3.3) which is
deployed for that purpose.

The adapter consists of folded plates attached to the truss. It is
automatically erected as the first fold of the truss is deployed. The erected
adapter contains the same type of alignment, berthing and interface devices as
do the rigid adapters previously described for other concepts.

The double folding of the truss causes some problems with the utilities
installation (Figure 1.4-10). To install the full complement of utilities,
the electrical cables are mounted on the exterior of the pyramidal members in
a looped configuration. They will extend easily but must be retracted and
re-looped manually. The fluid lines are mounted on the lateral members in a
series of folds.

The packaging ratio is 20 to 1 (along the length).

Figure 1.4-10. Installation of Utilities
(Concept 3)

● ALL MEMBERS ARE ROUND TUBES
● DOUBLE-FOLD SYSTEM
● NO OFFSET LOADS AT JOINTS

1.4.2.4 Concept 4

This concept (Figure 1.4-11) is a triangular truss which deploys/retracts
axially without changing its end profile. Each bay consists of a rigid
triangular frame, three folding longerons, and three telescopic diagonals.
The three longerons folded into the stowed configuration are shown in
Figure 1.4-12. It is recognized that there will have to be a support in the
middle of the triangular frame to brace the longerons during launch. All of
the truss members are round tubes which converge at the corner fittings
without offset. The folding of the longerons toward the middle instead of in
line with the batten tubes and diagonals is necessary to achieve a high
packaging ratio.

The main housing is a conventional rigid framework which contains the folded
truss and deployment mechanism, and carries the loads from the truss into the
rest of the deployable platform. The selected deployment mechanism is a
reciprocating device which deploys and rigidizes the truss one bay at a time.
Initially, torsion springs were used but were replaced by a reciprocating
mechanism for better packaging. During truss deployment, root strength is
developed by guide rails which are stowed alongside the housing when not in
use.

Because the truss does not change its triangular end profile dimensions while
deploying, there is a choice of using either two or three guide rails, i.e.
with two-guide rails a rail length equal to 2 bays plus the stack length is
required; with three guide rails a rail length equal to 1 bay plus the stack
length is required.

1-69

* Deploys/folds axially
* All members are round tubes
* Longerons with center hinge joints
* Telescoping diagonals
* No offset loads at joints

Figure 1.4-11. Concept 4

Figure 1.4-12. End View of
Folded Configuration

The adapter is a rigid triangular assembly which can be identical to that described for Concept No. 1.

Utilities cannot be mounted in trays because the longerons are folded into the center. Therefore, they are mounted directly onto the batten frames in a series of folds (Figure 1.4-13). For the full complement of utilities they are installed on both the inside and outside of the battens.

With the use of the reciprocating deployment system, a packaging ratio of 20.2 to 1 was achieved.

ONLY ONE CABLE IS SHOWN.
THE INNER & OUTER SURFACES
OF ALL THREE SIDES ARE
USED TO MOUNT UTILITIES

*Figure 1.4-13. Utilities Installation
(Concept 4)*

1.4.2.5   Concepts 5 and 7

Concepts 5 and 7 are the same except that Concept 5 is a tension X-braced
structure, while Concept 7 uses compression diagonals for shear and torsion
capability.   Concept 5 will be described (Figure 1.4-14).

Concept 5 is a triangular section truss which deploys along two axes. First,
the triangular section expands to approximately 170% of its original size;
then, the truss deploys along its longitudinal axis. A high ratio of deployed
length/stowed length is achieved by all of the cross-bracing and longerons
nesting inside the batten frames when stowed.

* CONCEPT 5 CROSS BRACED WITH TENSION STRAPS AS SHOWN
* CONCEPT 7 BRACED WITH COMPRESSION DIAGONAL
* TRIANGULAR BATTEN FRAME
  * EXPANDS 70%
  * H SECTION MEMBERS
* ⊓⊔ LONGERON SECTION
* LONGERONS & DIAGONALS
  NEST IN THE BATTENS
* NO OFFSET LOADS AT JOINTS

MAIN HOUSING

DEPLOYMENT RAILS

ADAPTER

JOINT DETAIL

Figure 1.4-14.   Concepts 5 and 7

The expanding triangular batten frame is of H-section construction. The longerons are a channel cross-section with a hinge and a latch at the mid length. The cross-braces are rectangular section tension straps, constructed of a graphite/rubber composite or similar material which has a low CTE and is flexible enough to behave as a strap instead of a rigid bar. The cross-braces are pretensioned by deploying the truss bays. The longerons serve as natural over-center tensioning devices to apply load to the cross-braces which are accurately fabricated to a predetermined length.

The expanding triangular truss is stowed in an expanding triangular housing. As the housing expands it pulls the truss with it. The housing which is made in three sections is expanded/contracted by a number of powered screw jacks. The expanding force from the housing to the truss is via the guide rails attached to the housing and the guide wheels which are attached to the truss battens. As in Concept 4 the number of guide rails can be either two or three. The longitudinal deployment mechanism is a "standard" reciprocating system using the guide rails.

Concept 7 is shown in Figure 1.4-15. Because of the double fold nature of the truss, the compression diagonal has two folding joints in addition to a telescoping joint which is considered to be a significant disadvantage.

Figure 1.4-15. Concep

The full complement of utilities can be integrated iuto Concepts 5 and 7. The electrical cables are installed inside the truss triangle in trays which are pivoted at their ends from clevises mounted on the battens (Figure 1.4-16). The fluid lines are outside the truss triangle on shallow trays which are pivoted at their end from the battens.

A packaging ratio of 27.5 to 1 was achieved.

1.4.2.6 Concept 6

Concept 6 (Figure 1.4-17) is a linearly deployable truss with a square cross-section consisting of rigid batten frames joined to each other by folding longerons and telescoping diagonals pin-connected at corner fittings integral with the frames.

The longerons (Figure 1.4-18) fold toward the middle of the truss at a 45-degree angle, have self-aligning spherical ball end fittings, and hinge/lock fittings in the center of the longeron length. The telescoping diagonals have a lock mechanism and self-aligning end fittings.

X-braced tension cables can be provided for all the interior batten frames for redundancy.

All of the truss members (round tubes for the longerons, battens, and diagonals, and rectangular straps for the lateral bracing) are loaded along their centroids and converge without offsets at the batten frame corner fittings.

The stowed truss is contained in a square rigid housing to which the guide rails and deployment mechanism are attached. The number of guide rails may be 2, 3, or 4. For 2 guide rails, the rail length is equal to 2 bays plus the stack length. For 3 or 4 guide rails, the rail length is equal to 1 bay plus the stack length.

The folding guide rails and the reciprocating deployment mechanism are the same as in the concepts described previously. Initially, torsion springs were considered. The method of deployment is "one bay at a time," with root stiffness developed by the guide rails during deployment. The longerons attachment to the rear of the main housing provides the load capability subsequent to deployment.

The adapter is a square rigid assembly at the far end of the truss. It contains all of the electromechanical latches, alignment features and connections required for a payload/module interface.

The full complement of utilities is attached to the batten frames in figure-8 loops (Figure 1.4-19). Both the inside and the outside of the batten frames can be used (Figure 1.4-18).

With the use of the reciprocating mechanism, a packaging ratio of 20.4 to 1 was achieved.

UTILITES INSTALLATION

Figure 1.4-16. Utilities Installation
(Concepts 5 and 7)

- All members are round tubes
- Longerons with center hinge joints
- Telescoping diagonals
- No offset loads at joints
- Battens braced by tension straps

MAIN HOUSING

TRUSS

ADAPTER

DEPLOYMENT RAILS

Figure 1.4-17. Concept 6

UTILITIES

DETAIL OF JOINT

Figure 1.4-18.   End View Stowed

FOR CLARITY, ONLY TWO LINES ARE SHOWN

Figure 1.4-19.   Utilities Installation
(Concept 6)

1.4.2.7 Concept 8

Concept 8 (Figure 1.4-20) consists of square rigid batten frames connected together by folding longerons and telescoping diagonals. The batten frames are H-section, cross-braced by thin tension straps (as required in the interior bays for redundancy). Each longeron consists of two rectangular section members with locking hinges at their centers. The diagonals are rectangular sections which telescope within each other. The diagonals and longerons stow within the confines of the H-section battens. In the deployed configuration all the members converge at a common point.

The housing, rails, deployment system and end adapter are the same as in the square truss of Concept 6.

Concept 8 has the advantage of utility trays which can extend the whole width of the interior of the batten frames if desired, permitting a large separation between power and data lines plus the advantage of growth in the number of lines (Figure 1.4-21).

A packaging ratio of 22 to 1 was achieved.

Figure 1.4-20. Concept 8

*Figure 1.4-21. Utilities Installation
(Concept 8)*

1.4.3 Orbiter Packaging

This section describes the studies and results applicable to the packaging of the generic platform (Section 1.2), constructed from the eight candidate building blocks, into the orbiter. The packaging is based upon the packaging efficiencies shown in the preceding section.

1.4.3.1 Concepts 1 & 4

Concepts 1 and 4 are axially folding trusses of triangular cross-section. Because of its better packaging ratio, Concept 4 uses less space (7.5 M) in the Payload Bay than does Concept 1 (9.0 M), Figure 1.4-22. Apart from this, the two concepts are identical in packaging and deployment. The figures and description apply only to the generic platform, although many other configurations can be built/deployed by following the approach outlined in this report.

Figure 1.4-22. Orbiter Packaging
—Concepts 1 and 4

The platform system deployment is 100% automatic without resort to EVA, RMS assembly or to building fixtures. All of the necessary modules, orbiter supports and cradles are incorporated in the design.

There are eight triangular building blocks and two cradles. The cradles are structures which interface with the orbiter trunnion and keel fittings, join some of the building blocks together at their hinge points, and provide mounting surfaces for the spacecraft systems.

Each of the building blocks is a single truss design, i.e., only one truss is deployed from each housing.

The platform is assembled and checked out on the ground before it is folded and placed in the orbiter. All of the utility connections from end to end of the platform are made on the ground and are not broken during stowage or deployment.

The stowed platform is removed from the orbiter by using the RMS, and remains
in the grasp of the RMS and/or is attached to the HAPA during the initial
stages of deployment. If continuous operation and a low deployment rate of
3/cm per second are assumed, the platform could be deployed in about 72
minutes. Some trusses deploy simultaneously. There are three basic
operations involved in deploying the platforms, i.e., reorienting the building
blocks, extending the trusses, and latching.

One sequence of operations to deploy the platform is shown in Figure 1.4-23.
Several other sequences are possible in achieving the same configuration. The
solar array is not shown as an integrated deployable item in this design,
although it is quite possible that it could be incorporated. Items such as
large payloads, modules, etc., are added to the deployed platform by the RMS,
using the interfaces provided.

Figure 1.4-23. Platform Deployment—Concepts 1 and 4

1.4.3.2 Concepts 2, 6 and 8

This section discusses the packaging and deployment sequence for axially
deploying building blocks, of square cross-section of which Concepts 2, 6, and
8 are typical examples. The three concepts are identical in packaging and
deployment with the exception of the slight difference of their lengths in the
payload bay (Figure 1.4-24.).

*Figure 1.4-24. Orbiter Packaging
—Concepts 2, 6, and 8*

There are five building blocks and two modules in the assembly
(Figure/1.4-25). Of the five building blocks two are "singles", i.e., one
truss from a main housing, and three are "doubles", i.e., two trusses, one
from each end of a main housing.

   o   Module 1 mounts three of the building blocks and is a cradle which
       supports them in the orbiter. It forms part of the deployed
       platform and is used to mount spacecraft systems and equipment.
   o   Module 2 mounts the remaining two building blocks and is the cradle
       which supports them in the orbiter. It too is deployed with the
       rest of the platform and is used to mount spacecraft systems.

The complete package is removed as a unit from the payload bay using the RMS
and is retained on the RMS (or mounted onto the HAPA) for the initial stages
of deployment. The stages of the deployment sequence are:

   o   Reorient four of the building blocks by rotating them until all five
       building blocks are in the same plane.
   o   Extend the trusses as shown to form the vertical of the T shape of
       the platform.
   o   Rotate the building blocks which form the diagonals and extend the
       trusses to complete the T shape of the platform.

The platform is automatically deloyable without the assistance of EVA,
building/assembly fixtures or piece-by-piece assembly using the RMS. There is
no requirement to make electrical or fluid connections in flight except where
separate units such as payloads are added subsequent to deployment by the RMS.

1.4.3.3 Concept 3

Although this concept was successfully packaged (Figure 1.4-26) and deployed,
this study does point up the difficulties with the use of a double-fold
structure. The advantages gained from the dense volumetric packaging of the
structure are largely illusory when one turns from a simple truss to a
complete deployable platform system. Some of the problems which contribute
are:

1-79

- ORBITER PAYLOAD BAY

- USE RMS TO REMOVE STOWED PLATFORM FROM THE ORBITER

- EXTEND THESE TRUSSES

- DIAGONAL TRUSSES ROTATE ABOUT THE HINGE POINTS ON THE HOUSINGS

- REORIENT THE BUILDING BLOCKS

- EXTEND THE TRUSSES SHOWN

Figure 1.4-25. Platform Deployment—Concepts 2,6, and 8

13.562 M

PAYLOAD BAY

OMS KIT

9.1 M

- DOCKING MODULE

*Figure 1.4-26. Orbiter Packaging
—Concept 3*

o   The stowed double-fold truss is difficult to support in the
     orbiter with provision of stiffness compatible with frequency
     separation (10 Hz) from the orbiter.
o   The methods of joining truss to truss, or truss to module,
     are more complex. It is sometimes necessary to erect a sub-
     sidiary structure for structural continuity.
o   The end adapter cannot be a simple plate to support latches,
     interfaces, etc.
o   Mounting of the adopted complement of utilities is difficult
     because of limited space.

In spite of these difficulties, the generic platform can be built using
Concept 3. It is an automatic deployable platform which requires no EVA, no
building/assembly fixture and no part-by-part erection. The electric/fluid
utilities are installed and checked out on the ground from end to end of the
platform. There are no connections broken/reconnected between stowage into
the orbiter and final deployment.

The platform consists of five building blocks and one module. Of the five
building blocks, three are "double building blocks," i.e., a truss deploys out
of each end of the housing. The module is an integral part of the platform,
is deployed along with the building blocks, is intended to mount spacecraft
systems, join three of the truss together, and serves as a base for deploying
subsidiary structure for reacting truss loads.

The packaged platform (Figure 1.4-27) is removed from the orbiter by means of
the RMS. While it is in the grasp of the RMS (or HAPA) the initial stages of
platform deployment are made. There are several stages in the deployment
sequence.

Figure 1.4-27.   Platform Deployment—Concept 3

o   Unfold the building blocks.
o   Deploy the subsidiary structure on the module. This includes a
     docking port and attach points for reacting truss loads.
o   Erect the first fold of the trusses.
o   Extend the trusses part way.
o   Make the joints at the module attach points.
o   Extend the trusses completely.

This completes the deployment of the platform. Payloads/solar array/RCS pods
may be added, as required, by a second launch or by using the empty portions
of the payload bay of the first launch.

1.4.3.4 Concepts 5 and 7

Concepts 5 and 7 are stowed in the orbiter (Figure 1.4-28) and deploy to the
final configuration in identical fashion. The stowage and deployment shown
are for the generic platform only. It is a completely automatic deployable
system which requires r EVA and no assembly or erection by RMS. The
deployable platform inc des six buiding blocks and two modules.

Figure 1.4-28. Orbiter Packaging
—Concepts 5 and 7

o   Module 1 mounts three of the building blocks and is a cradle which
     supports the whole of the stowed platform in the orbiter. It forms
     part of the deployed platform and is used to contain spacecraft
     systems.
o   Module 2 mounts the remaining three building blocks. It does not
     interface directly with the orbiter, but is attached to Module 1.
     It too forms part of the deployed platform and is used to mount
     spacecraft systems.

The complete package is removed from the orbiter in its stowed form by using
the RMS. While it is in the grasp of RMS (or HAPA) automatic deployment is
initiated. There is no requirement for a building/assembly fixture to hold
the platform while the RMS attache, trusses or modules section by section. As
in all of the Rockwell platform deployment concepts, the utilities are
installed and checked out on the gound and not disturbed thereafter.

Because of the high packaging efficiency, it is possible to stow some of the building blocks with their lengths normal to the major axis of the payload bay, i.e., stow them "across" the ship instead of lengthwise. This permits arrangements such that the building-blocks do not have to be reoriented to achieve the deployed configuration.

There are only two stages in the deployment sequence (Figure 1.4-29), i.e., expand the triangle shapes of the building blocks and extend the trusses.

Of all the concepts which were studied, Concepts 5 and 7 proved to be the most suitable for packaging and deploying the Generic Platform. They stowed in the shortest length of the payload bay and required the least reorientation of the building blocks.

ORBITER
PAYLOAD
BAY

• USE TO REMOVE
STOWED PLATFORM
FROM ORBITER

• DIAGONAL TRUSSES
ROTATE ABOUT THEIR
HINGE POINTS AS
THE TRUSSES EXTEND

• EXTEND THE TRUSSES

• NO REORIENTATION OF
BUILDING BLOCKS IS
REQUIRED

• EXPAND THE
TRIANGLES OF
ALL THE BUILDING
BLOCKS

Figure 1.4-29.   Platform Deployment—Concepts 5 and 7

1.4.4 Thermal Analysis

A thermal analysis provided a prediction of the thermal gradients across the candidate deployable trusses (Table 1.4-2). The temperatures shown are the average over the length of each member. These gradients were determined for the structural arrangement/geometry shown in Figure 1.4-30 and for GEO applications. LEO applications have lower gradients due to earth and albedo heating.

Table 1.4-2. Thermal Gradients between Longerons

CONCEPT	d (m)	DIAGONAL PRESENT	LONGERON TEMPERATURE (°C)		ΔT (°C)	FIGURE OF MERIT d/(ΔT)
			SUN SIDE	SHADE SIDE		
1	1.6	YES	21.6	-13.5	35.1	0.046
2	1.3	YES	20.7	-11.6	32.3	0.040
		NO	24.0	4.8	19.2	0.067
3	3.0	NO	24.0	2.7	21.3	0.140
4	1.7	YES	21.7	-7.4	29.1	0.058
5	2.5	YES (TS)*	23.8	-36.0	59.8	0.041
6	1.3	YES	22.5	-22.6	45.1	0.029
7	2.5	YES	23.6	-56.7	80.3	0.031
8	1.3	YES	22.5	-17.5	40.0	0.031

*(TS) = TENSION STRAP

The thermal gradients are due to shadowing when one or more structural members pass between another member and the sun during orbit.

For analysis, each configuration can be represented as a Z-section (Figure 1.4-31) or as two parallel members if a diagonal is not present in the plane. A thermal math model of the Z-section is used for the analysis. It consists of 24 nodes and provides for conduction between nodes. The construction material is graphite composite. The surface radiation properties were assumed to be nearly black. Emmittance and absorptivity values of 0.85 were used. The thermal model for the two parallel member cases is a single node heat balance.

Two important assumptions in the analysis are the estimate of the shadow time and the view factor for solar impingement during shadow. The shadow time t_s (minutes) is estimated by the following expression. For two parallel members,

$$t_s = 8(0.2566 + \sin^{-1} D/S)$$

where D = member diameter
      S = distance between members

Figure 1.4-30. Structure Arrangement for Thermal Gradient Analysis
(Dimensions in Meters)

Figure 1.4-31. Thermal Analysis
Configuration

This expression accounts for the size of the shadowing member, the distance between members, and the included angle of the sun. For the Z-section, a modified form of this expression was used. The distance between members was allowed to vary with nodal position.

The view factor for solar impingement of the shadowed member was approximated by the following cosine function,

$$F = \cos^2 (180\ t/t_s)$$

This function has a value of unity at the extremes and a value of zero at the center of the time interval.

Table 1.4-2 also illustrates the parameters to evaluate the relative merit of each concept for thermal stability. The end rotation of a beam θ is determined by

$$\theta = \frac{\alpha(\Delta T)\ell}{d}$$

For beams of equal length and the same material, then θ is proportional to $(\Delta T/d)$ or the figure of merit is proportional to $(d/\Delta T)$ with high values being best. The foregoing data were based upon the structural design sizes as determined by the strength/stiffness characteristics, packaging, minimum weight, and joint design considerations. The design was not adjusted for reduction of the thermal gradients. For example, for Concept 6 the thermal gradient can be reduced by reduction of the diagonal diameter (reduced shadow) with a small weight impact (of no consequence to LEO platforms). Also, since the data are based upon $\alpha/\epsilon = 1.0$ with ϵ and $\alpha = 0.85$, if reduction of the thermal gradients is required, initial values of $\alpha = 0.10$ can be realized by wrapping the graphite composite structure with silver teflon tape. Though α will increase over the life of the structure, particularly in the GEO environment, the end of life value will be less than 0.85.

A perspective on these thermal gradients is appropriate. For a 40-meter cantilever using concept 6, the end will have a thermal induced rotation of 0.028° ($\alpha = 0.36 \times 10^{-6}$ m/mC) due to the specified gradient of 45°C across a design with a 1.26 m depth. (The 40 m length is used since precision antennas would be mounted closest to the center of the configuration). Section 1.1-10 indicates the desired pointing accuracies should be 0.05 to 0.10 degree (based on statistical analyses). If necessary, a value of 0.28° can be reduced by many of the techniques delineated above. In addition, placement of the square cross-section as shown in Figure 1.4-32 can reduce the 0.028° rotation to approximately 0.020°. If necessary, larger trusses (Figure 6) can further reduce the end rotation. The use of composites with negative coefficients of expansion and metal fittings can also reduce these rotations.

In the light of the foregoing, it is also appropriate to note that a 22.2 N shear on the end of a 40 m cantiliver will induce an end rotation of 0.005° for the adopted flexural stiffness, or for 4.45 N induce an end rotation of 0.001°. Hence, RCS induced distortions are small by comparison.

Figure 1.4-3`. Approach to Reduce
Thermal-Induced Truss Rotation

1.4.5 Mass Properties Analysis

The results of the deployable platform systems mass properties analysis of the generic platform contructed from Concepts 1 through 7 are shown in Table 1.4-3. These masses are determined by a combination of detailed calculations where specific structure sizing was avail`ble (deployable trusses, for example), and standard preliminary design mass estimation techniques (housings, for example). The generic platform mass is based upon the adopted strength, stiffness, and complement of utilities delineated in Section 1.1.

Table 1.4-4 illustrates the major differences in the masses for Concepts 1 through 8. The data for Concept 8 are estimated from the data provided for Concept 6 in Table 1.4-3. The data shown are used in the orbit transfer cost data described in Section 4. The data in Table 1.4-4 were also used as a basepoint for extrapolation of the weight differences for a generic platform designed to 1/10 the adopted strength/stiffness requirement (Table 4.3-5).

A review of Table 1.4-3 illustrates all of the candidate deployable platform systems, including a 20% growth allowance, are launchable to a 210 nmi orbit 28.5° inclination (Figure 1.4·33) without use of an OMS kit. The balance of mass between the values shown and an allowable 20,000 kg is available for payloads, RCS propulsion modules, etc. An addditional 2500 kg is launchable if an OMS kit is provided. The 210 Nmi orbit is considered suitable, since for the generic platform, decay to 150 nautical miles would not occur until 60 days after insertion into orbit. This is considered ample time for deployment, installation of payloads, checkout, etc.

1.4.6 Cost Analysis

Consideration was devoted, in support of the Concepts Selection Trade, to the establishment of the relative costs associated with the design, development, testing, special technology needs, fabrication, shuttle launch, and orbit transfer of GEO platforms. The design, development, and testing costs were not included since they are dependent on the number, types of application and

Table 1.4-3. Candidate Concepts Generic Platform Mass Summary

ITEM	MASS (KG)						
	CONCEPT 1	CONCEPT 2	CONCEPT 3	CONCEPT 4	CONCEPT 5	CONCEPT 6	CONCEPT 7
1. BASIC TRUSS STRUCTURE	1,924	3,193	1,946	1,802	1,616	1,810	2,192
2. BASIC TRUSS JOINTS	1,325	890	965	1,652	623	1,890	1,264
3. UTILITIES INSTALLATION EQUIPMENT	813	202	118	283	749	199	749
4. UTILITIES	2,554	2,569	2,544	2,559	2,557	2,554	2,557
5. HOUSINGS	675	540	354	599	597	559	597
6. ADAPTERS	52	65	95	60	89	73	89
7. MECHANISMS	476	377	803	572	549	789	548
8. HOUSING-TO-HOUSING ATTACH. MECH.	127	156	178	128	98	156	98
9. SEPARATE DEPLOYABLE STRUCTURES	-	-	66	-	102	-	102
10. DOCKING PORTS	409	409	409	409	409	409	409
11. CONTROL MODULE EQUIPMENT	2,004	2,004	2,004	2,004	2,004	2,004	2,004
12. MISCELLANEOUS	23	91	91	23	29	91	29
SUBTOTAL	10,382	10,496	9,575	10,091	9,422	10,534	10,638
13. ORBITER INTEGRATION WEIGHT	2,240	2,547	3,440	2,154	1,130	2,774	1,130
SUBTOTAL	12,622	13,043	13,015	12,245	10,552	13,308	11,768
14. GROWTH (20%)	2,525	2,608	2,604	2,445	2,110	2,662	2,353
TOTAL	15,147	15,651	15,619	14,669	12,662	15,970	14,121

Figure 1.4-33. Orbiter Payload Ma.. —Launch/Landing Constraints

Table 1.4-4. Comparative Mass $(kg \times 10^{-3})$ —Generic Platform

ITEM	CONCEPT							
	1	2	3	4	5	6	7	8
BASIC TRUSS ELEMENTS	1.9	3.2	2.0	1.8	1.6	1.8	2.2	1.8
ALL JOINTS	1.3	0.9	1.0	1.6	0.6	1.9	1.3	1.9
UTILITIES INSTALLATION SYSTEM	0.8	0.2	0.1	0.3	0.7	0.2	0.7	0.7
HOUSING AND ADAPTERS, HOUSING-TO-HOUSING ATTACH.	0.9	0.9	0.6	0.8	0.8	0.9	0.8	0.6
DEPLOYABLE STRUCTURES FOR DOCKING PORTS	-	-	0.1	-	0.1	-	0.1	-
TOTAL	4.9	5.2	3.8	4.5	3.8	4.8	5.1	5.0
Δ MASS	1.1	1.4	0.0	0.7	0.0	1.0	1.3	1.2

ALL DESIGNS, INCLUDING DEPLOYMENT MECHANISMS, UTILITIES LINES, DOCKING PORTS, CONTROL MODULE
EQUIPMENT, AND CRADLE WEIGHT (WITH 20% GROWTH)—LESS THAN 16,600 KG.

requirements of future platforms which are not defined. The special
technology development costs (as subsequently shown in Section 3) are
primarily the same across all the candidate concepts, with the few exceptions
resulting in negligible cost impacts (particularly if spread across
several platforms).

The analysis, therefore, determined the recurring fabrication cost, Shuttle
launch and for GEO platforms, the cost of orbit transfer. All the cost
analysis data are expressed in terms of FY 1981 dollars and are relative,
i.e., applicable only to items which are different. The costs of items that
are the same across all concepts are not included. For example, the cost of
the basic power, data and fluid utilities themselves, docking ports, etc., is
not included.

1.4.6.1 Fabrication Cost Data

The component fabrication costs to construct the generic platform are shown in
Table 1.4-5. These data are incorporated directly into Table 4-4-1. These
data were derived by a combination of material and fixture costs (as
appropriate) and manufacturing hours to which a composite cost rate was
applied. The composite cost rate includes direct labor, overhead, and general
and administrative (G&A).

The materials, fixture, and manufacturing hours data presented were determined
from estimates by advanced manufacturing personnel using drawing details.
Where detailed information was not available, in-house Rockwell parametric
cost model techniques were used.

Table 1.4-5.   Fabrication Cost Data ($ Million)

COST ITEM	CONCEPT						
	1	2	3	4	5	6	7
BASIC TRUSS MEMBERS (COMPOSITE)	2.2	5.0	1.0	1.7	2.0	1.9	2.3
TRUSS JOINTS AND FITTINGS	2.2	1.7	1.5	2.1	1.2	3.0	1.9
TRUSS ASSEMBLY AND CHECKOUT	0.4	0.6	0.3	0.5	0.3	0.6	0.6
UTILITIES SUPPORT SYSTEM (FABRICATION AND INSTALLATION)	0.4	0.2	0.1	0.1	0.8	0.1	0.8
INSTALLATION OF UTILITIES AND CHECKOUT	0.1	0.1	0.1	0.1	0.1	0.1	0.1
END ADAPTERS AND MAIN HOUSINGS	0.4	0.3	0.3	0.3	0.4	0.3	0.4
BUILDING BLOCK TO BUILDING BLOCK ATTACH MECHANISMS	2.3	2.9	3.5	2.2	1.7	2.8	1.7
TOTAL ($M)	8.0	10.8	6.8	7.0	6.5	8.8	7.8
Δ ($M)	1.5	4.3	0.3	0.5	0	2.3	1.3

NOTE: CONCEPT 8 ESTIMATED FROM EXISTING DATA FOR CONCEPT 6

It is pertinent to note that Table 1.4-5 does not include the costs of deployment mechanisms since the building blocks can utilize either a reciprocating device (GD design or equivalent) or a stored strain energy system. The differences between the same type mechanism across the single folded designs were regarded as negligible. In retrospect, the additional cost of the mechanisms for the double folding of Concepts 3, 5, and 7 should be included into the last cost item in the table. To do so would only enhance the conclusions and decisions made in Section 4. and require extensive numerical change throughout the tables for the sake of consistency. Hence, this item is not included.

1.4.6.2 Shuttle Launch Cost

The Shuttle launch cost data for use in Table 4.4-1 are based upon a cost of $2.6M/meter of Shuttle cargo bay length. It is derived from an FY 1982 total cost of $48M for 18.3 m of bay length. The $48M is the FY 1981 cost extrapolated from the baseline FY 1975 launch cost of $32M and is for a medium traffic model (40 launches per year). A significant reservation on the use of this total value is that for a dedicated mission the system cost is incurred regardless of the usage of the bay. This reservation is reflected in the allocation of points in the totaling of the major criteria.

1.4.6.3 GEO Orbit Transfer Cost

The Rockwell space station studies have identified a cost (in FY 1981 dollars) of $8,800 per kg of mass delivered to GEO orbit including the launch to LEO by the shuttle. This cost is also based on a medium mission model.

1.4.7 Miscellaneous Design Issues

During the concept development discussed throughout this section , three design concerns surfaced as follows:

o   Extension of a truss which has a large payload while maintaining the deployable truss root strength with the guide rails

o   Implication of building block to building-block structural attachments that are not fully fixed about all three axes

o   Potential significance of "joint slop"

The first issue has been resolved as discussed in Section 1.3.3.5. The second issue has been investigated and resolved as follows:

A configuration such as the generic or ASASP platform can have joints without full structural continuity at places, such as joints 1 and 2 of Figure 1.4-34, with acceptable reductions in effective stiffness.

A sensitivity analysis of platform overall stiffness variations associated with different end joint design characteristics was performed. The analysis was performed with a NASTRAN model that simulates the ASASP platform configuration and mass distribution. The construction platform was not included. The ASASP was used since the mass distribution was more readily available and the generic platform was fashioned after the ASASP. The adopted stiffness values were used.

Since the overall variation in platform stiffness is most easily defined by the resulting modal frequencies, modal analyses are performed for the expected diagonal member end joint variations. At all other joints, flexural and torsional moment continuity is maintained.

The table on Figure 1.4-34 illustrates the first four modal frequency variations relative to that of the baseline design. For all of the four cases shown, the stiffness reductions were acceptable.

For other possible configurations:

o   Moment and torsion capability of cantilevered members can be provided by fixed joints or appropriate self-locking latches (Figure 6)

o   In worst case, EVA attachment of strut or pair of struts is feasible, if necessary.

| CASE | FREQUENCY (Hz) | | | | COMMENTS FOR JOINTS 1 & 2 |
	FIRST	SECOND	THIRD	FOURTH	
BASE-LINE	0.0431	0.0703	0.0823	0.1181	FULLY FIXED
1	0.0361	0.0658	0.0686	0.1129	Z-AXIS PINS
2	0.0359	0.0651	0.0683	0.1120	Z-AXIS PINS AND 1/10 OF EI, GJ, AE
3*	0.0361	0.0658	0.0686	0.1152	Z-AXIS PINS WITH OFFSET FROM DIAGONAL CENTERLINE
4	0.0351	0.0628	0.0680	0.1085	BALL JOINTS

*OFFSET = 1.5 m

Figure 1.4-34. ASASP Modal Frequency Variation
with Diagonal End Joint Design

The third design concern has not been resolved in this study and is applicable to the concepts studied which all utilize clevis joints, folding and/or telescoping joints.

Consider the following illustrative example (Refer to Figure 1.4-35):

o   Consider a cantiliver member 60 m long (38 bays)

o   Suppose ACS thruster shear = 4.5 N

o   Limit longeron load = 2.8 N (one bay from RCS thruster)

o   Limit longeron load = 107 N (38 bays from RCS thruster)

o   For the adopted EI = 2 x 10^8 Nm^2, and truss depth of 1.26 m the longeron AE = 1.26 x 10^8 N

o   Elongation of longeron for load of 2.8 N = 0.0000035 cm

o   Elongation of longeron for load of 107 N = 0.00013 cm

o   For a design to twice the depth (same EI), the above values of 0.0000035 and .00013 cm are multiplied by 4, i.e., elongation is 0.000014 and 0.00052 cm

Figure 1.4-35. Model for "Implication of Joint Slop" Analysis

o   For both depths, the elongations are very small compared to conventional clevis/pin clearances

o   Problem is increasingly more severe with reduced RCS thrust

Hence, for future resolution: (1) To what extent does friction preclude "joint slop?" and (2) What is statistical implication of joint slop in actual design with numerous joints?

The potential implications of "joint slop" to the control system design are:

o   It will be of increasing concern in figure control applications where "joint slop" alone results in structural deflections approaching total allowable deflection

o   "Joint slop" is highly non-linear phenomenon with strong potential for destabilization and limit cycling

o   It will be of increasing concern if "equivalent frequency" (f_e) (Figure 1.4-36) approaches control system bandwidth

The resulting potential control system design implications are:

o   Develop accurate "joint slop" model to facilitate controller design

o   Typical controller enhancement - nonlinear gain scheduling, compensation and limiters to enhance performance

*Figure 1.4-36. Equivalent Structure
Frequency due to "Joint Slop"*

The primary problem is that joint slop introduces a series of distributed non-linearities in the spacecraft dynamics. In general, this will degrade control system performance. It is destabilizing and a potential cause of limit cycling. Special control enhancements can be used to minimize the detrimental effects of joint slop, as indicated above. In general, the problem is tractable if the magnitude of the joint slop can be eliminated or made small relative to the control system pointing accuracy requirement. Also, the control problems are eased with increasing friction levels at the joints.

The preferred solution is to eliminate or negate joint slop by mechanical means (eccentric clevis pin or bolt with an expanding sleeve) or with thermosetting materials at the joints (one bay at a time deployment enhances this possibility). Another alternative is to increase joint friction providing it is not detrimental to deployment.

2. MATERIAL DATA BASE

The material requirements for the manufacture of structural members for large
deployable platforms include those needed to produce tension/compression
members, tension members only, fittings, hinges, bearings and springs. The
materials selected for the data base to satisfy these requirements are those
currently available in present technology and those which could be available
in the technology for point design by 1986. This philosophy permits the
consideration of not only metals and organic composites, but metal matrix
composite materials.

This material data base is not intended to permit the detailed optimization
needed for the ultimate point designs to be made by 1986. It is intended to
supply a sufficiency of general information to allow the material trades
required for the generation of preliminary designs. These trades will specify
the direction of the ultimate designs for deployable space structures.

All materials selected are suitable for the temperature fluctuations
(-200 to 80C) that will be encountered in service in either a low earth or
geosynchronous orbit. These temperature excursions can be reduced by the
judicious application of thermal control coatings and insulations.
Temperature resistance of the materials is, therefore, not a critical
consideration. The radiation resistance of the material is important only in
the case of geosynchronous orbit. Using a radiation criterion of a dose rate
of 6×10^2 rads (Si) per day as the maximum anticipated in geosynchronous
orbit, the materials have life expectancies in excess or 5 to 500 years
(Reference 13). Since only a few of the materials have low damage
thresholds and these are usually restricted to low radiation exposures in the
interior of spacecraft, a minimum of thirty-year life is expected for any
platform system designed using the materials in the data base.

The data base is contained in Tables 2.2-0 through 2.0-11. Table 2.0-1
provides a glossary of terms. Tables 2.0-2 through 2.0-11 present candidate
materials and their pertinent material properties.

Tension and Compression Members

Some typical metals such as aluminum 2219 and beryllium (Table 2.0-2) are
included in the data base for comparison with the more advanced materials such
as the organic and metal matrix composite materials (Table 2.0-3).
Considering the design parameters of low thermal distortion, low cost, and
high modulus, the most attractive candidate materials within the state of the
art are the epoxy/graphite composites. The metals have a high coefficient of
thermal expansion which contributes to excessive thermal distortion of the
structure. The polyimide/graphite is state of the art, but it is used only
for high temperature applications because it is excessively expensive for
general use. The metal matrix composites have all the right properties, but
are at present very expensive and the technology is in the experimental stage
and may not be available for production by 1986. Therefore, they may have to
be relegated to specialty applications where no other material can reasonably
suffice. Some new materials that will very probably be available for general
application to point designs in 1986 are the very high modulus graphite
fibers. These fibers permit the production of structures with a lower

Table 2.0-1. Glossary of Terms for Data Base

MAIN CHARACTER			
A	ACCEPTABLE	M	MEMORY
B	ACCEPTABLE WITH SPECIFIC COUPONS	L	LOSS FACTOR
B_e	BEARING STRENGTH	N/A	NOT APPLICABLE
C	ACCEPTABILITY MUST BE DEMONSTRATED BY TEST OR ANALYSIS	NR	NOT RATED
		R	REFLECTANCE
D	DUCTILITY	σ	SURFACE RESISTIVITY
d_{He}	DIFFUSION OF HELIUM	S	SET POINT
D_{ie}	DIELECTRIC CONSTANT	Sp	SPECIFIC HEAT
D_{is}	DISSIPATION FACTOR	TML	TOTAL MASS LOSS
E	MODULUS	U	UNAVAILABLE
e	ELONGATION	VCM	VOLATILE CONDENSIBLE MATERIAL
F	STRESS	$1/\gamma$	VOLUME RESISTIVITY
f	FATIGUE PROPERTIES	X	UNACCEPTABLE
G	SHEAR MODULUS	α	ABSORPTIVITY
H	HARDNESS	ϵ	EMISSIVITY
K	COEFFICIENT	μ	POISSON's RATIO
k	THERMAL CONDUCTANCE	ρ	DENSITY

SUPERSCRIPT			SUBSCRIPT	
c	COMPRESSION		C	TEMPERATURE
E	MODULUS		e	THERMAL EXPANSION
t	TENSILE		f	FRICTION
u	ULTIMATE		L	LONGITUDINAL
s	SHEAR		T	TRANSVERSE

DIMENSIONS	
MPa	- MEGA PASCALS
GPa	- GIGA PASCALS
J/kgK	- JOULES/KILOGRAM-DEGREE KELVIN
W/mK	- WATTS/METER-DEGREE KELVIN
m/mK	- METER/METER-DEGREE KELVIN
kg/m^3	- KILOGRAM/CUBIC METER
$m^2/sec\text{-}ATM$	- SQUARE METERS/SECOND-ATMOSPHERE

coefficient of thermal expansion, a higher thermal conductivity and a high
specific rigidity. The two more prominent contenders in the field of high
modulus fiber composites are the P75S/934 and P100S/934 graphite/epoxy
composites listed in Table 2.0-3.

Fittings

In addition to the conventional materials used in the manufacture of fittings
for spacecraft, such as the metals in Table 2.0-4, more unconventional
materials (Table 2.0-5) are being considered to obtain both a closer thermal
expansion match to the basic structure and a closer match to the modulus.
Another major advantage for the use of composite fittings is that it permits
the molding of fittings directly into structural members. The type of organic
materials most amenable to this type of processing are the thermoplastic
composites such as the polysulfone/graphites. There is some development work,
however, that needs to be accomplished between now and FY 1986 to reduce the
direct molding to structural member process to common everyday practice.

Table 2.0-2.   Metallic Materials for Structural Members

MATERIALS ② PROPERTIES ① ②	ALUMINUM 2219	BERYLLIUM
MECHANICAL		
F_L^{tu} (MPa)	427.8	276.0
F_L^{cu} (MPa)	331.0	207.0
F_L^{su} (MPa)	248.4	172.0
E_L^{t} (GPa)	72.5	289.0
E_L^{c} (GPa)	74.5	289.0
G_L (GPa)	27.6	138.0
μ	0.33	0.10
B_e (MPa) $\begin{array}{l}e/D = 1.5\\ e/D = 2.0\end{array}$	655.0 835.0	N/A
PHYSICAL		
Sp (J/kgK)	848.0	1825.0
k (W/mK)	12.1	8.4
K_e (m/mK x 10^{-6})	22.0	12.3
ϵ	0.05	0.10
α	0.10	0 55
R	0.90	0.45
ρ (kg/m^3)	2830.0	1850.0
APPLICATIONS	TENSION & COMPRESSION BEARINGS	TENSION & COMPRESSION
① ALL PROPERTIES MEASURED UNDER AMBIENT CONDITIONS ② ALL MATERIALS LISTED MEET SP-R-0022 FOR VCM AND TML		

Table 2.0-3. Structural Member Candidate Composite Materials

PROPERTIES	MATERIAL ①②③ GRAPHITE/EPOXY ①			POLYIMIDE/ GRAPHITE ①	ALUMINUM/ GRAPHITE ①	MAGNESIUM/ GRAPHITE ①
	T300/934	P75S/934	P100S/934			
MECHANICAL						
F_L^{tu} (MPa)	1482.0	999.0	1140.0	863.0	483.0	635.0
F_T^{tu} (MPa)	48.0	32.0	37.0	20.7	48.0	35.0
F_L^{cu} (MPa)	1276.0	328.0	311.0	538.0	642.0	621.0
F_T^{cu} (MPa)	186.0	119.0	U	89.0	104.0	104.0
F_L^{su} (MPa)	69.0	44.0	48.0	41.0	48.0	48.0
F_T^{su} (MPa)	33.0	21.?	23.0	20.0	55.0	U
E_L^{t} (GPa)	145.0	368.0	428.0	304.0	207.0	324.0
E_T^{t} (GPa)	10.0	6.0	U	6.2	35.0	21.0
E_L^{c} (GPa)	133.0	246.0	428.0	254.0	U	U
M (%)	5.0	4.9	U	4.83	24.1	17.3
PHYSICAL						
Sp (J/kgK)	980.0	U	U	879.0	962.9	962.9
k (W/mK)	N/A	N/A	N/A	N/A	233.0	1030.0
k_L (W/mK)	9.0	157.0	520.0	77.83	N/A	N/A
k_T (W/mK)	0.7	1.8	U	1.21	N/A	N/A
K_{aL} (m/mK x 10^{-6})	0.23	-1.04	-1.6	-0.99	1.33	0.55
K_{aT} (m/mK x 10^{-6})	25.2	25.6	26.9	28.8	26.6	28.2
E	0.85	0.85	0.85	0.85	0.45	0.45
a	0.80	0.80	0.80	0.80	0.45	0.45
R	0.20	0.20	0.20	0.20	0.55	0.55
ρ (kg/m³)	1600.0	1765.0	1820.0	1580.0	2410.0	1880.0

① ALL COMPOSITE PROPERTIES ARE BASED ON 0° FIBER ORIENTATION
② ALL PROPERTIES MEASURED UNDER AMBINET CONDITIONS
③ ALL MATERIALS LISTED MEET SP-R-0022 FOR VCM AND TML

Table 0-4. Metallic Materials for Fittings and Springs

PROPERTIES[1]		CRES 304L-1/8H	MAGNESIUM AZ31B	STEEL 4340	ALUMINUM 2219	BERYLLIUM	TITANIUM (6AL-4V)	302 STAINLESS STEEL	17-7PH STAINLESS STEEL
MECHANICAL									
F_L^{tu}	(MPa)	518.0	235.0	1790.0	427.5	276.0	1000.0	587.0	1830.0
F_L^{cu}	(MPa)	370.0	110.0	1655.0	331.0	207.0	1034.0	414.0	1103.0
F_L^{su}	(MPa)	345.0	159.0	1080.0	248.4	172.0	621.0	366.0	793.0
E_L^t	(GPa)	200.0	448.0	200.0	72.5	289.0	116.0	193.0	200.0
E_L^c	(GPa)	200.0	448.0	200.0	74.5	289.0	113.0	193.0	206.0
G_L	(GPa)	79.4	16.6	75.9	27.6	138.0	42.8	79.4	75.9
μ		0.28	0.35	0.32	0.33	0.10	0.31	0.28	0.28
PHYSICAL									
Sp	(J/kgK)	502.0	1004.8	477.0	848.0	1825.0	544.0	502.0	460.5
k	(W/mK)	176.0	76.0	38.0	12.1	8.4	7.0	16.25	16.1
K_e	(m/mK x 10^{-6})	17.2	25.3	11.3	22.0	12.3	5.4	17	10.4
ρ	(kg/m³)	8030.0	1770.0	7840.0	2830.0	1850.0	4430.0	8030.0	7760.0
APPLICATIONS		FITTINGS	FITTINGS	FITTINGS	FITTINGS	FITTINGS	FITTINGS SPRINGS	SPRINGS	SPRINGS

NOTES: (1) ALL PROPERTIES MEASURED UNDER AMBIENT CONDITIONS.
(2) ALL MATERIALS LISTED MEET SP-R-0022 FOR VCM AND TML.

Table 2.0-5. Non-Metallic Materials for Fittings and Springs

(3) PROPERTIES (2) \ MATERIALS	GRAPHITE/EPOXY (1)			POLYIMIDE/ GRAPHITE (1)	POLYSULFONE/ GRAPHITE (1)
	T300/934	P75S/934	P100S/934		
MECHANICAL					
F_L^{tu} (MPa)	1482.0	999.0	1140.0	863.0	1323.0 (4)
F_T^{tu} (MPa)	48.0	32.0 (4)	37.0 (4)	20.7	43.0 (4)
F_L^{cu} (MPa)	1276.0	328.0	311.0	538.0	1139.0 (4)
F_T^{cu} (MPa)	186.0	119.0	U	89.0	166.0 (4)
F_L^{su} (MPa)	69.0	44.0 (4)	48.0	41.0	54.0 (4)
F_T^{su} (MPa)	33.0 (4)	21.0 (4)	23.0 (4)	20.0 (4)	26.0 (4)
E_L^{t} (GPa)	145.0	368.0	428.0	304.0	119.0 (4)
E_T^{t} (GPa)	10.0	6.0	U	6.2	4.3 (4)
E_L^{c} (GPa)	133.0	246.0	428.0	254.0 (4)	U
G_{LT} (GPa)	5.3	4.9	U	4.82	U
μ_{LT}	0.29	0.365	U	0.30	U
PHYSICAL					
S_p (J/kgK)	880.0	U	U	879.0	U
k_L (W/mK)	9.0	157.0	520.0	77.83	9.0 (4)
k_T (W/mK)	0.7	1.8	U	1.21	U
K_{aL} (m/mK x 10^{-6})	0.23	-1.04	-1.6	-0.99	0.23 (4)
K_{aT} (m/mK x 10^{-6})	25.2	25.6	26.9	28.8	U
ϵ	0.85	0.85	0.85	0.85	0.85
α	0.80	0.80	0.80	0.80	0.80
R	0.20	0.20	0.20	0.20	0.20
ρ (kg/m³)	1600.0	1765.0	1820.0	1580.0	1490.0
APPLICATIONS	FITTINGS SPRINGS			FITTINGS SPRINGS	SPRINGS

NOTES: (1) ALL COMPOSITE PROPERTIES ARE BASED ON 0° FIBER ORIENTATION

(2) ALL PROPERTIES MEASURED UNDER AMBIENT CONDITIONS

(3) ALL MATERIALS LISTED MEET SP-R-0022 FOR VCM AND TML

(4) CALCULATED VALUE FROM BASIC MATERIAL PROPERTIES

Springs

Table 2.0-4 presents the conventional spring materials normal.y used in spacecraft. These materials are metallic and have the same shortcomings of excessive thermal expansion as metals proposed for other applications on the deployable platform systems. To obtain a close match of the coefficient of thermal expansion to a graphite composite structure, it is desirable to manufacture the spring out of the same basic materials. Some of the new organic composite materials being considered for the production of springs are presented in Table 2.0-5. These composite springs may not be commercially available by 1986. However, titanium springs can be considered as the closest compatible compromise in the event commercial availability of composites lags the need date.

Flexible Tension Members

Flexible tension members usually consist of metal cables such as the 17-7PH stainless steel presented in Table 2.0-6. This type of construction has two major deficiencies for this application. One, the high coefficient of thermal expansion of the metals makes these cables incompatible with the contemplated graphite/epoxy structure. To further aggravate this condition, the twist in the material can exaggerate the dimensional mismatches that occur with thermal excursions. To reduce, if not eliminate this problem, graphite fiber tapes of monofilaments with flexible organic binders are proposed. A sample of one of these materials is RTV566/graphite and is presented in Table 2.0-6. Most of the properties of the individual components of the composites are known but significant work remains to confirm the potentials of these materials in a combined form as flexible cables.

Table 2.0-6. Materials for Tension Cables

(2) MATERIALS (3) PROPERTIES	RTV 566/ GRAPHITE (1)	17-7PH STAIN- LESS STEEL
MECHANICAL		
F_L^{tu} (MPa)	U	1830.0
E_L^t (GPa)	U	200.0
PHYSICAL		
S_p (J/kgK)	U	460.5
k (W/mK)	U	16.1
K_e (m/mKx10^{-6})	U	10.4
ϵ	0.90	0.30
α	0.85	0.10-0.25
R	0.15	0.90-0.75
ρ (kg/m^3)	U	7760.0
APPLICATIONS	TENSION	TENSION

NOTES: (1) ALL COMPOSITE PROPERTIES ARE BASED ON 0° FIBER ORIENTATION

(2) ALL PROPERTIES MEASURED UNDER AMBIENT CONDITIONS

(3) ALL MATERIALS LISTED MEET SP-R-0022 FOR VCM AND TML

Electrical Conductors

The primary criterion for electrical conductors, apart from the obvious properties such as specific electrical conductivity, is the ability to coil and uncoil the conductors several times through very tight radii for stowage and deployment in a deployable structure. To this end, copper with its smaller radius of wire for equivalent electrical conductivity, surpasses aluminum. Its superior mechanical properties for like wire gauges surpass silver for this application (Table 2.0-7).

Table 2.0-7. Materials for Electrical Conductors

① PROPERTIES / MATERIALS ②	ALUMINUM 1100	COPPER	SILVER
MECHANICAL			
F_L^{tu} (MPa)	165.0	207.0	138.0
E_L^t (MPa)	68.2	117.0	73.0
PHYSICAL			
Sp (J/kgK)	958.8	385.2	238.6
k (W/mK)	222.0	7.11×10^5	427.0
K_e (m/mK $\times 10^{-6}$)	23.86	16.74	19.0
ρ (kg/m³)	2710.0	8920.0	10,500.0
1/γ (ohm-cm $\times 10^{-6}$)	2.6548	1.6730	1.50
APPLICATIONS	FLUID LINES ① ELECTRICAL CONDUCTOR	ELECTRICAL CONDUCTOR	ELECTRICAL CONDUCTOR
① ALL PROPERTIES MEASURED UNDER AMBIENT CONDITIONS			
② ALL MATERIALS LISTED MEET SP-R-0022 FOR VCM AND TML			

Diffusion Barriers for Fluid Lines

Fluid diffusion barriers (Table 2.0-8) are one application where only a metal can perform effectively for long exposure times. There are a number of candidate materials with little to choose between. The possible exception is the use of the metal matrix composites which technically provide the best of all worlds, low coefficient of thermal expansion, high resistance to gas diffusion, high modulus and low weight. The drawbacks are extreme high cost and the commercial availability by 1986.

Table 2.0-8. Diffusion Barriers for Fluid Lines

PROPERTIES (3) / MATERIALS (4)	17-7PH STAINLESS STEEL	ALUMINUM/ GRAPHITE (3)	ALUMINUM 5052	ALUMINUM 5056	ALUMINUM 1100	TITANIUM (6AL-4V)
MECHANICAL						
F_L^{tu} (MPa)	1630.0	483.0	289.8	414.0	165.0	1100.0
E_L^t (GPa)	200.0	207.0	70.4	71.1	68.2	116.0
PHYSICAL						
Sp (J/kgK)	460.5	962.9	962.9	921.0	966.8	544.0
k (W/mk)	16.1	233.0	138.0	116.6	222.0	7.0
K_e (m/mK x 10^{-6})	10.4	L 1.33 T 26.6	24.1	24.1	23.86	9.4
d_{He} (m²/sec-ATM)	NEGLIGIBLE	NEGLIGIBLE	NEGLIGIBLE	NEGLIGIBLE	NEGLIGIBLE	NEGLIGIBLE
ρ (k/m³)	7760.0	2410.0	2690.0	2640.0	2710.0	4430.0
CHEMICAL						
HYDRAZINE	A	A	A	A	A	A
HELIUM	A	A	A	A	A	A
FREONS AS A CLASS	A	A	A	A	A	X (5)
NITROGEN TETROXIDE	A	A	A	A	A	A
APPLICATIONS	FLUID LINES (1)	FLUID LINES (1)	FLUID LINES (1)	FLUID LINES (1)	FLUID LINES (1)	FLUID LINES (1)

NOTES:
(1) THE FLUID LINES MAY BE OVERWRAPPED HYBRIDS OR SINGLE MATERIALS
(2) ALL COMPOSITE PROPERTIES ARE BASED ON 0° FIBER ORIENTATION
(3) ALL PROPERTIES MEASURED UNDER AMBIENT CONDITIONS
(4) ALL MATERIALS LISTED MEET SP-R-0022 FOR VCM AND TML
(5) CHLORIDES AND CHLORINATED HYDROCARBONS OTHER THAN FREON TF ARE UNACCEPTABLE

Diffusion Barriers-Bellows

Considering the extended exposure times anticipated for flexible portions of the fluid lines the only materials reasonable to consider for this application are metal bellows. The two primary materials currently in use are presented in Table 2.0-9. It is not anticipated that any significant new material will be available for point design by FY 1986.

Table 2.0-9. *Diffusion Barriers for Bellows*

PROPERTIES*	MATERIALS	
	321 STAINLESS STEEL	INCONEL 718
MECHANICAL		
F_L^{tu} (MPa)	586.0	1240.0
F_T^{tu} (MPa)	N/A	N/A
F_L^{cu} (MPa)	N/A	N/A
E_L^{t} (GPa)	193.0	200.0
E_T^{t} (GPa)	N/A	N/A
μ	0.28	0.31
PHYSICAL		
S_p (J/kgK)	502.0	418.7
d_{He} (sec/m^{2}s)	NEGLIGIBLE	NEGLIGIBLE
ρ (kg/m^3)		
$1/\gamma$ (ohm-cm x 10^{-6})	N/A	N/A
CHEMICAL		
HYDRAZINE	A	A
HELIUM	A	A
FREONS AS A CLASS	A	A
NITROGEN TETROXIDE	A	A
APPLICATIONS	BELLOWS	BELLOWS
*ALL PROPERTIES MEASURED UNDER AMBIENT CONDITIONS		

Vibration Damping Materials

Currently, there are primarily two significant space-rated materials for vibration damping. These materials are presented in Table 2.0-10. It is not anticipated that any unusual developments will require any unique materials development in this area.

*Table 2.0-10. Vibration
Damping Materials*

MATERIALS PROPERTIES	SMERD G.E.	SYNTACTIC FOAM D AIRCRAFT
MECHANICAL		
F_L^{tu} (KPa)	2760.0	2208.0
e (%)	100.0	55.0
Torsional Shear (KPa)	U	1035.0
G (KPa)	U	41,400.0
Tear Strength (N-M)	U	11.3
H (Shore A)	50.0 min.	70.0-85.0
D_{la}	0.162 (1 KHz)	0.12 (1 MHz max.)
PHYSICAL		
VCM (%)	0.02	0.10
TML (%)	0.19	0.22
Glass Transition (°K)	U	227.0
APPLICATIONS	VIBRATION DAMPING	VIBRATION DAMPING

Thermal Control Coatings

Some typical space-rated thermal control coatings currently available are presented in Table 2.0-11. This area requires some extended development not only for deployable space structure, but for all spacecraft. Very few materials serve in this capacity and meet the outgassing contamination requirements of NASA specification SP-R-0022. These materials have some problems with adhesion and general in-space deterioration from causes not fully understood.

Table 2.0-11. Thermal Control Coatings

C

MATERIALS PROPERTIES	BLACK CHEM-GLAZE Z306	WHITE S13G/LO (IITRI)
MECHANICAL Adhesion (1)	NO EVIDENCE OF LIFTING	NO EVIDENCE OF LIFTING
PHYSICAL		
α	0.94	0.22
ε	0.86	0.85
VCM (%)	0.01 (3)	0.03 (2)
TML (%)	0.56 (3)	0.47 (2)
APPLICATIONS	THERMAL CONTROL COATING	THERMAL CONTROL COATING

NOTES: (1) TESTED PER ASTM D-522
(2) FULLY CURED (30 DAYS OR LONGER) AT ROOM TEMPERATURE
(3) CURED 30 DAYS AT ROOM TEMPERATURE

Lubricants

Several space-rated lubricants exist for most of the typical applications that are anticipated. For solid film lubricant applications, there are the molybdenum disulfides such as Molykote 3402 which conforms to MIL-L-3937 and Adrecolube 13 which conforms to MIL-L-46010. There is also a tungsten disulfide solid film lubricant Microseal. Where greases are needed there is a fluorinated material, Braycoat 3L-38RP; and for an oil, a fluorinated material, Brayco 815Z. All these materials meet the requirements for outgassing in SP-R-0022. The materials listed are typical of the many available and are presented for illustration only.

3. IDENTIFICATON OF TECHNOLOGY DEVELOPMENT NEEDS

Table 3.0-1 presents the special technology needs summary. It summarizes the estimated cost of resolving each new technology need, as well as the estimated calendar time.

Table 3.0-1. Special Technology Needs Summary

POTENTIAL TECHNOLOGY REQUIREMENT (LISTED BY RATING)	ESTIMATED TOTAL COST ($)	SCHEDULE TO ACCOMPLISH (YR)	PRIORITY
• DAMPING CHARACTERISTICS PREDICTION TECHNIQUE	350-400,000	4.0	
• ORBITAL TRANSFER THRUSTER (1335-2225 N THRUST)*	780-960,000	3.5	
• SPACE CHARGE DISSIPATION TECHNIQUES	124-150,000	4.0	HIGHEST
• JOINTS WITHOUT "SLOP"	190-220,000	1.5	
• MINIMIZE STRUCTURAL LOAD AMPLIFICATION	295-340,000	3.5	
• RADIATION-RESISTANT FIBER OPTICS	120-150,000	1.0	
• LIGHTWEIGHT, LOW CTE, HIGH-STRENGTH CLUSTER FITTING	210-240,000	1.7	
• PASSIVE STRUCTURAL DAMPING TECHNIQUES	100-125,000	2.0	MEDIUM
• MICROMETEOROID STRUCTURE DAMAGE	100-150,000	1.5	
• RADIATION-RESISTANT THERMAL CONTROL COATING	95-115,000	0.8	
• HIGH-CAPACITY HEAT PIPE	600-800,000	3.5	
• ACTIVE STRUCTURAL CONTROL TECHNIQUES	300-350,000	3.3	
• ADAPTIVE CONTROL TECHNIQUES	340-385,000	2.7	LOWEST
• LIGHTWEIGHT, HIGH-STRENGTH MEMBER (MALE) FITTING	155-175,000	1.7	
• INSULATED FLEXIBLE COOLANT LINES	190-240,000	2.5	
• LOW CTE, HIGH MODULUS, FLEXIBLE TENSION MEMBER	100-130,000	1.0	
TOTAL	4,930,000 (HIGHEST)	4.0 (LONGEST)	

*THIS TECHNOLOGY REQUIREMENT IS INVALID IF EARTH STORABLE PROPELLANTS ARE CHOSEN FOR THE ORBIT TRANSFER FUNCTION.

The technology needs are presented in three priority groups. The groups are based upon consideration of net effect on performance, hardware level of the problem, type of logic for resolution, level of test simulation required, development test approach, and required hardware interfaces. There is no significance to the order of the items listed within each priority group.

It is pertinent to note that numerous development tests need to be performed pertaining to electrical cable bending, fatigue data, suitability of folding joints, telescoping joints, etc. These were not considered new technology items since the technical approach is based on known methodologies.

The logic diagram shown in Figure 3.0-1 indicates the approach Rockwell used to identify, validate, and estimate the cost of the special technology needs.

ORIGINAL PAGE I
OF POOR QUALITY

Space Operations/Integration &
Satellite Systems Division

Rockwell
International

Figure 3.0-1.   Logic Diagram—Special Technology Needs

Table 3.0-2 summarizes the 23 potential technology items identified, along with the rationale used to reject seven of the items. As might be expected, the greatest number of items are identified for structures and materials, as well as dynamics and control.

Each of these potential technology requirements was validated by asking the four questions shown in Table 3.0-3. The Technical Review Board (TRB), representing in-depth knowledge in each of the disciplines covered, was able to identify solutions/ongoing R&D activities for seven of the 23 items discussed. The remaining 16 items, which passed Gate 1, were scrutinized further as the TRB collected confirming data. The data were reviewed at the second gate, with confirmation of the 16 primary technology candidates.

Most of the requirements apply to all the structural concepts generated, not just to individual concepts. As an example, radiation-resistant fiber optics apply to all the concepts generated—not just one or two. For this reason, the output of this task is deemed to be inappropriate for inclusion in the selection criteria, but will be a direct input to the Preliminary Test Plan of the Part II study.

A fiscal year schedule for each identified task, including major milestones, was completed for each technology deficiency. Estimated costs were established through discussions with each responsible engineer in each discipline, using a checklist which includes the costs for design and analysis, manufacturing, laboratory testing, major ground tests, flight tests, and (outside) consultation fees.

Table 3.0-2. Summary of Potential Technology Requirements

POTENTIAL ITEMS	RATIONALE FOR SELECTION
STRUCTURES AND MATERIALS • MICROMETEOROID IMPACT STRUCTURE DAMAGE • RADIATION-RESISTANT FIBER OPTICS • SPACE CHARGE DISSIPATION TECHNIQUES • RADIATION-RESISTANT THERMAL COATING • LOW CTE, HIGH MODULUS, FLEXIBLE TENSION MEMBER • LOW CTE, HIGH MODULUS, COMPOSITE MATERIAL FOR DEPLOYABLE STRUCTURAL ELEMENTS • LIGHTWEIGHT, LOW CTE HIGH-STRENGTH CLUSTER FITTING • LIGHTWEIGHT, HIGH-STRENGTH MEMBER (MALE) FITTING • COMPOSITE MATERIAL CARPENTER'S HINGE • ZERO-BACKLASH JOINTS	CURRENTLY UNDER DEVELOPMENT BY G.E. AND CONVAIR SHORT-TERM DEVELOPMENT EFFORT
THERMAL CONTROL • INSULATED FLEXIBLE COOLANT LINES • LONG-LIFE FLUID PUMP • HIGH-CAPACITY HEAT PIPE • HEAT PIPE INTERCONNECTION TECHNIQUE • ROTATING FLUID JOINT FOR ARTICULATING RADIATOR	ORBITER'S RADIATOR FREON PUMP CAN RESOLVE BY DESIGN TECHNIQUES DESIGN APPROACH DEMONSTRATED DURING FLYING LUNAR EXCURSION EXPERIMENTAL PLATFORM CONTRACT (NAS1-9516, 1970)
UTILITIES • TECHNIQUES TO REDUCE BEND RADIUS OF ELEC. CABLES • TECHNIQUES TO REDUCE BEND RADIUS OF NON-POWER CABLES	DESIGN SOLUTIONS ARE WITHIN CURRENT TECHNOLOGY REALM
PROPULSION • ORBITAL TRANSFER THRUSTER (1335-2225 N THRUST)	
DYNAMICS AND CONTROL • DAMPING CHARACTERISTICS PREDICTION TECHNIQUE • ADAPTIVE CONTROL TECHNIQUES • ACTIVE STRUCTURAL CONTROL TECHNIQUES • PASSIVE STRUCTURAL DAMPING TECHNIQUES • MINIMIZE STRUCTURAL LOAD AMPLIFICATION	

Table 3.0-3. Validation Questions

1. IS COMPARABLE WORK BEING CONDUCTED NOW (OR CONTEMPLATED) BY NASA, DOD, OR INDUSTRY? 2. COULD THE REQUIRED NEED DATE BE SATISFIED BY THE ON-GOING TECHNOLOGY RATE/TREND LINE? 3. ARE THERE VIABLE ALTERNATIVES IF THE TECHNOLOGY NEED IS NOT SATISFIED? 4. IS THE SOLUTION TO THE PROBLEM PRIMARILY A SHORT-TERM EFFORT (LESS THAN ONE YEAR)?

The final products of this task are provided at the end of this section. The individual tasks also lend themselves to more accurate milestone schedules and time-phased cost estimates.

The 16 technology items were then prioritized according to the criteria described in Table 3.0-4.

The use of criteria is a method of measuring the impact of a new technology need on deployable platform system performance. The first criterion is a direct measure, while the remaining five are indirect measurements based on the relative difficulty of solving a particular technology deficiency.

The results of the rating are summarized in Table 3.0-5, which indicates that the point count ranges from a high of 4.75, down to 2.00. In those cases where two or more technology deficiencies receive the same numerical total, the same priority rating is assigned. Although this technique is rather arbitrary, the ratings are relative to each other, and a difference of one or two positions is not critical.

Because these rating criteria have only one direct measurement of the impact of a new technology need on system performance, a sensitivity analysis is conducted. The results of this analysis are shown in Table 3.0-6. The upper limit of the first criterion is raised to 3.00 (rather than 1.00) and each priority rating value in this column is multiplied by 3.00 to intensify the first criterion. The results (Table 3.0-6) indicate that roughly half the technology requirements do not change position and the other half moves only one or two positions, i.e., the change is negligible.

Table 3.0-4. Priority Rating Criteria

---

1. NET EFFECT ON PLATFORM PERFORMANCE — AN OVERALL MEASURE OF THE IMPACT THAT A TECHNOLOGY DEFICIENCY HAS ON AN OPERATIONAL DEPLOYABLE PLATFORM DESIGN IS THE NET EFFECT ON PERFORMANCE; AND, BECAUSE THE NET EFFECT INCLUDES ALL TYPES OF TECHNOLOGY DEFICIENCIES, THE TERMS USED TO DESCRIBE THE IMPACT ON THE SYSTEM ARE RATHER GENERAL. OUR NUMERICAL RATING ASSIGNS A VALUE OF 1.00 FOR *SEVERE PERFORMANCE LIMITATION*, WHILE *NO IMPACT* IS ASSIGNED A VALUE OF ZERO.

● SEVERE PERFORMANCE LIMITATION	1.00
● CONSIDERABLE DEGRADATION	0.75
● MILD IMPACT	0.50
● MEASURABLE DEGRADATION	0.25
● NO IMPACT ON PERFORMANCE	0

---

2. HARDWARE LEVEL OF PROBLEM — ONE INDIRECT MEASURE OF THE SYSTEM IMPACT OF A TECHNOLOGY DEFICIENCY IS THE LEVEL (SIZE/COMPLEXITY) OF THE HARDWARE REQUIRED TO RESOLVE THE PROBLEM. GENERALLY SPEAKING, A COMPONENT (SUCH AS A PUMP) REPRESENTS A MUCH LOWER COST IMPACT TO RESOLVE A PROBLEM, COMPARED TO A COMBINED SUBSYSTEMS OR INTEGRATED SYSTEM TEST PROGRAM. THE LATTER NORMALLY REQUIRES MANY ITEMS OF GROUND SUPPORT EQUIPMENT AND KNOWLEDGEABLE TECHNICAL PERSONNEL IN A VARIETY OF DISCIPLINES TO SUCCESSFULLY DIAGNOSE AND CORRECT A SYSTEMS-LEVEL DEVELOPMENT TASK. A COMPONENT, ON THE OTHER HAND, USUALLY REQUIRES A MUCH SMALLER TEAM WITH MORE IN-DEPTH TECHNICAL TRAINING AND A FEW ITEMS OF GROUND SUPPORT EQUIPMENT. OUR NUMERICAL RATING ASSIGNS A VALUE OF 1.00 FOR A SYSTEM-LEVEL PROBLEM BECAUSE OF THE RELATIVELY GREATER COMPLEXITY OF A SYSTEM VERSUS A COMPONENT. A COMPONENT-LEVEL PROBLEM HAS A VALUE OF 0.25.

● COMBINED SUBSYSTEMS/INTEGRATED SYSTEMS	1.00
● SYSTEM/SYSTEM CRITICAL INTERFACE	0.75
● SUBSYSTEM	0.50
● COMPONENT	0.25
● MATERIAL OR METHODS	0

---

3. TYPE OF LOGIC FOR RESOLUTION — THE TYPE OF (COMPUTATIONAL) LOGIC REQUIRED TO RESOLVE A TECHNOLOGY DEFICIENCY IS ALSO AN INDIRECT MEASURE OF SYSTEM IMPACT. CUT-AND-TRY LOGIC IS A FORM OF CURVE FITTING IN A REGION WHERE RELATIONSHIPS ARE NOT WELL DEFINED. THIS METHOD IS TIME-CONSUMING AND REQUIRES EXPERIMENTATION. AN EXAMPLE WOULD BE THE KNOWLEDGE OF FLUID BEHAVIOR IN ZERO GRAVITY IN 1960. AT THE OTHER EXTREME, ANALYSIS OF A PROBLEM USING PROVEN FORMULAS/RELATIONSHIPS AND/OR COMPUTER-STORED PROGRAMS IS RELATIVELY SIMPLE (LEAST COST IMPACT).

● CUT AND TRY	1.00
● DATA EXTRAPOLATION	0.75
● STATISTICAL/EMPIRICAL	0.50
● ANALYSIS/SYNTHESIS	0.25

---

4. LEVEL OF TEST/SIMULATION REQUIRED — TEST LEVELS REQUIRED TO FIND SOLUTIONS TO A PROBLEM ARE ALSO INDICATIVE OF RELATIVE SYSTEM IMPACT. A MAJOR FLIGHT TEST, FOR INSTANCE, IS VERY COSTLY BUT IS SOMETIMES JUSTIFIED AS THE ONLY TEST LEVEL WHICH WILL CREATE ACTUAL COMBINED TEST ENVIRONMENTS WHICH ARE NECESSARY FOR HIGH-CONFIDENCE RESOLUTION. LABORATORY TESTING, ON THE OTHER HAND, TENDS TO BE LESS COSTLY BECAUSE THE TEST TEAM IS GENERALLY SMALL AND THE TEST ENVIRONMENT, EVEN IF CONSIDERED COSTLY, DOES NOT LAST VERY LONG (APPLIED INTERMITTENTLY).

● MAJOR FLIGHT TEST	1.00
● MAJOR GROUND TEST	0.75
● FLIGHT/GROUND PASSENGER	0.50
● LABORATORY	0.25

---

5. DEVELOPMENT TEST APPROACH — THE DEVELOPMENT TEST APPROACH REFERS TO THE PRIMARY METHOD TO BE USED TO OBTAIN THE DESIRED TEST RESULTS. AS AN EXAMPLE, COMBINED TEST ENVIRONMENTS ARE GENERALLY PREFERRED, FROM A TEST POINT OF VIEW, BECAUSE THEY STRESS THE TEST ARTICLE SIMILAR TO ACTUAL USE CONDITIONS AND THEREBY ELIMINATE SOME OF THE UNKNOWNS (THE ADDITIVE EFFECT OF INTERNAL STRESS LEVELS CAUSED BY DIFFERENT ENVIRONMENTS). COMBINED TEST ENVIRONMENTS ARE DIFFICULT TO ACHIEVE AND ARE, THEREFORE, COSTLY TO SIMULATE. A DEMONSTRATION TEST, HOWEVER, IS USUALLY STRAIGHTFORWARD AND, FROM A COST IMPACT STANDPOINT, REPRESENTS RELATIVELY LOW TEST COSTS.

● COMBINED ENVIRONMENTS TESTING	1.00
● DETERMINE SAFETY MARGINS	0.75
● DETERMINE FAILURE MODES	0.50
● DEMONSTRATION	0.25
● GATHER DATA	0

---

6. OTHER HARDWARE INTERFACES REQUIRED — OTHER HARDWARE INTERFACES REQUIRED TO CONTROL, MONITOR, SIMULATE, RECORD, COOL, SUPPORT, POINT, OR TRACK THE TEST ARTICLE ARE ALSO AN INDIRECT MEASURE OF THE IMPACT OF A TECHNOLOGY DEFICIENCY. OTHER HARDWARE INTERFACES REPRESENT CONSIDERABLE COST TO OBTAIN AND OPERATE, OR TO SIMULATE THE EFFECT OF THE INTERFACE. FOR THESE REASONS, *COMBINED SUBSYSTEMS/INTEGRATED SYSTEMS* (AS A HARDWARE INTERFACE) IS THE MOST COSTLY AND, THEREFORE, HAS THE HIGHEST PRIORITY RATING VALUE OF 1.00. *OTHER SUBSYSTEM INTERFACES* REPRESENTS THE LEAST COST IMPACT AND HAS THE LOWEST PRIORITY RATING VALUE OF 0.25.

● COMBINED SUBSYSTEMS/INTEGRATED SYSTEMS	1.00
● OTHER COMPLETE SYSTEMS	0.75
● OTHER PARTIAL SYSTEMS	0.50
● OTHER SUBSYSTEM INTERFACES	0.25

Table 3.0-5. Priority Rating Results

POTENTIAL TECHNOLOGY REQUIREMENTS	PRIORITY RATING CRITERIA						TOTAL	RATING
	NET EFFECT ON PLATFORM PERFORMANCE	HARDWARE LEVEL OF PROBLEM	TYPE OF LOGIC FOR RESOLUTION	LEVEL OF TEST/ SIMULATION REQUIRED	DEVELOPMENT TEST APPROACH	OTHER HARDWARE INTERFACES REQUIRED		
1. RADIATION-RESISTANT FIBER OPTICS	0.75	0	0.75	0.25	0.75	0.25	2.75	5
2. SPACE CHARGE DISSIPATION TECHNIQUES	1.00	0	0.50	0.50	0.75	0.25	3.50	3
3. RADIATION-RESISTANT THERMAL CONTROL COATING	0.25	0	0.50	0.50	0.75	0.25	2.25	6
4. LOW CTE, HIGH MODULUS, FLEXIBLE TENSION MEMBER*	0.0	0.25	1.00	0.25	0.50	0.50	N/A	8
5. LIGHTWEIGHT, LOW CTE, HIGH-STRENGTH CLUSTER FITTING	0.50	0.25	0.75	0.25	0.50	0.50	2.75	5
6. LIGHTWEIGHT, HIGH-STRENGTH MEMBER (MALE) FITTING	0.25	0.25	0.50	0.25	0.50	0.25	2.00	7
7. ZERO-BACKLASH JOINTS	0.75	0.25	0.50	0.25	0.75	0.50	3.00	4
8. INSULATED FLEXIBLE COOLANT LINES	0.25	0.25	0.50	0.25	0.50	0.25	2.00	7
9. HIGH-CAPACITY HEAT PIPE	0.0	0.25	0.50	0.25	0.50	0.25	N/A	8
10. ORBITAL TRANSFER THRUSTER (1335-2225 N THRUST)	0.75	0.50	0.75	0.50	1.00	0.75	4.25	2
11. DAMPING CHARACTERISTICS PREDICTION TECHNIQUE	0.75	0.75	0.50	1.00	0.75	1.00	4.75	1
12. ADAPTIVE CONTROL TECHNIQUES	0.0	0.50	0.50	0.25	0	0.25	N/A	8
13. ACTIVE STRUCTURAL CONTROL TECHNIQUES	0.0	0.75	0.50	0.25	0.50	0.75	N/A	8
14. PASSIVE STRUCTURAL DAMPING TECHNIQUES	0.50	0.25	0.75	0.25	0.75	0.25	2.75	5
15. MINIMIZE STRUCTURAL LOAD AMPLIFICATION	0.50	0.50	0.50	0.50	0.50	0.50	3.00	4
16. MICROMETEOROID IMPACT	0.75	0.25	0.25	0.75	0.25	0	2.25	6

NOTE: A VALUE OF 0.0 IN THE FIRST COLUMN AUTOMATICALLY PLACES THE REQUIREMENT IN LAST PLACE.

* NOT A SELECTED CONCEPT.

Table 3.0-6. Sensitivity Trade Results

POTENTIAL TECHNOLOGY REQUIREMENTS	PRIORITY RATING CRITERIA						TOTAL	RATING
	NET EFFECT ON PLATFORM PERFORMANCE	HARDWARE LEVEL OF PROBLEM	TYPE OF LOGIC FOR RESOLUTION	LEVEL OF TEST/ SIMULATION REQUIRED	DEVELOPMENT TEST APPROACH	OTHER HARDWARE INTERFACES REQUIRED		
1. RADIATION-RESISTANT FIBER OPTICS	2.25	0	0.75	0.25	0.75	0.25	4.25	5
2. SPACE CHARGE DISSIPATION TECHNIQUES	3.00	0	0.50	0.50	0 75	0.25	5.00	3
3. RADIATION-RESISTANT THERMAL CONTROL COATING	0.75	0	0.50	0.50	0.75	0.25	2.75	8
4. LOW CTE, HIGH MODULUS, FLEXIBLE TENSION MEMBER	0.0	0.25	1.00	0.25	0.50	0.50	N/A	11
5. LIGHTWEIGHT, LOW CTE, HIGH-STRENGTH CLUSTER FITTING	1.50	0.25	0.75	0.25	0.50	0.50	3.75	7
6. LIGHTWEIGHT, HIGH-STRENGTH MEMBER (MALE) FITTING	0.75	0.25	0.50	0.25	0.50	0.25	2.50	10
7. ZERO-BACKLASH JOINTS	2.25	0.25	0.50	0.25	0.75	0.50	4.50	4
8. INSULATED FLEXIBLE COOLANT LINES	0.75	0.25	0.50	0.25	0.50	0.25	2.50	9
9. HIGH-CAPACITY HEAT PIPE	0.0	0.25	0.50	0.25	0.50	0.25	N/A	11
10. ORBITAL TRANSFER THRUSTER (1335-2225 N THRUST)	2.25	0.50	0.75	0.50	1.00	0.75	5.75	2
11. DAMPING CHARACTERISTICS PREDICTION TECHNIQUE	2.25	0.75	0.50	1.00	0.75	1.00	6.25	1
12. ADAPTIVE CONTROL TECHNIQUES	0.0	0.50	0.50	0.25	0	0.25	N/A	11
13. ACTIVE STRUCTURAL CONTROL TECHNIQUES	0.0	0.75	0.50	0.25	0.50	0.75	N/A	11
14. PASSIVE STRUCTURAL DAMPING TECHNIQUES	1.50	0.25	0.75	0.25	0.75	0.25	3.75	7
15. MINIMIZE STRUCTURAL LOAD AMPLIFICATION	1.50	0.50	0.50	0.50	0.50	0.50	4.00	6
16. MICROMETEOROID IMPACT	2.25	0.25	0.25	0.75	0.25	0	3.75	7

NOTE

A VALUE OF 0.0 IN THE FIRST COLUMN AUTOMATICALLY PLACES THE REQUIREMENT IN LAST PLACE.

NEW TECHNOLOGY NEED

TASK TITLE:
Damping Characteristics Prediction Technique

JUSTIFICATION:

A highly damped structural system will minimize any requirement to aug-
ment motion with the attitude control function. A low damped structural
system may require augmented attitude control (to meet pointing accuracy)
as well as a variable gain function. The latter situation would be
more complicated (less reliable) and weigh more than the first situation.
The ability to accurately predict the degree of damping may alleviate
a complicated attitude control function and avoid an overkill with passive
damping techniques.

TECHNICAL OBJECTIVES:

Develop a method of analysis (verified by test data) which will predict
the damping characteristics of deployable structures containing extensive
utility lines and cables in zero gravity.

TASK DESCRIPTIONS:

1. Develop a modeling technique for utility lines and cables which
   are secured to basic structure in a variety of ways (various
   damping coefficients).

2. Verify the above modeling characteristics by free-free modal
   testing of representative structures and utilities.

3. Verify the above modeling characteristics by space flight testing
   representative structures and utilities (zero-gravity mode).

4. Update the analysis technique as required.

Space Operations/Integration &
Satellite Systems Division

Rockwell
International

NEW TECHNOLOGY NEED

TASK TITLE: ORBITAL TRANSFER THRUSTER (1335 TO 2225 N THRUST)*

Justification

Many light-weight structure concepts will be constrained to very low
acceleration forces (thrust to weight ratio) during transfer to
geosynchronous orbit. A new thruster, in the 1335 to 2225 N thrust
range, utilizing liquid oxygen and liquid hydrogen, needs to be
developed for this application.

Technical Objective

Design and demonstrate reliable operation of an orbital transfer
thruster in the 1335 to 2225 N thrust range, pump fed.

Task Description

Conduct detail design, analysis, manufacture, and development tests to
verify performance and reliable operation of an orbital
transfer thruster in the 1335 to 2225 N thrust range. A soft thrust
buildup transient is a key requirement (5 to 15 second rise time), which
may require a variable area injector, a sequenced injector design, or
variable-speed, motor-driven pumps.

---

*This technology requirement is invalid if earth storable propellants
are chosen for the orbital transfer function.

NEW TECHNOLOGY NEED

TASK TITLE: SPACE CHARGE DISSIPATION TECHNIQUES

JUSTIFICATION

The space environment, particularly at geosynchronous altitudes, is known to cause a spacecraft to accumulate a differential charge as high as 20 kilo-volts when a magnetic disturbance (called a substorm) occurs in its vicinity. Large arcs, or the corona discharge so produced, radiate large-amplitude fast-rise-time electromagnetic pulses that can be detrimental to circuits and circuit piece-parts.

While there are active mechanisms to reduce surface charging (electron gun, heated filament, or a plasma source), long-term, high-reliability requirements suggest a high secondary electron emission material. This area has not been fully explored to date and holds the promise of a passive, long-life, highly reliable method to minimize surface charging of the system.

TECHNICAL OBJECTIVES

● Investigate and recommend, based on simulated environmental testing, a surface coating which will produce secondary electron emissions (or luminescence) at relatively low-voltage spacecraft charging levels.

● Develop a suitable application process for the above recommended coating, based on laboratory testing and verification methods.

● Verify, by space testing, that the basic theory of reducing charge voltage levels, through secondary yield or photon emission of the coating, actually works.

TASK DESCRIPTION

Part I will investigate, by means of laboratory testing, various coating materials which electroluminesce or produce high secondary yields at relatively low-voltage platform charging levels.

The purpose of this task is to demonstrate the above effect by subjecting a test structure, coated with a suitable material, to a simulated electro-static charge.

Part II will concentrate on developing a suitable method of applying the recommended coating. Laboratory application tests will be conducted, and methods will be developed which verify uniformity and adhesion.

Part III will verify the basic theory of the new coating by space testing. A spacecraft (an ATS geosynchronous vehicle) will be coated with the new material and be suitably instrumented (a harness noise monitor and high-voltage-charge-accumulation monitor) to detect possible static charge buildup and arcing.

NEW TECHNOLOGY NEED

TASK TITLE: Joints without Slop

JUSTIFICATION:

Stiffness of the deployable platform structure will be lost if backlash
is present in the joints. Also, the predictability of structural
performance characteristics will be imperiled.

TECHNICAL OBJECTIVES:

Develop a zero-backlash joint, suitable for deployable platform designs
and operational environments.

TASK DESCRIPTIONS:

1. Perform design and analysis to investigate and select several promising
   approaches, both passive and active concepts.

2. Manufacture several joints of each design selected above.

3. Perform laboratory test program to verify zero backlash for all
   operational (load) conditions and environments. Select the design
   approach which best meets the performance requirements.

NEW TECHNOLOGY NEED

TASK TITLE: Minimize Structural Load Amplification

JUSTIFICATION

Several approaches are possible which will reduce load amplification
factors for lightweight structures, namely: (1) soft transient thrust
buildup of RCS thrusters (0.1 to 0.25 lb thrust, 10-20 second rise time);
and (2) optimum pulsing of RCS thrusters to deadbeat the structural
response of the system. The most cost-effective approach must be defined
and demonstrated because a structural load amplification of two
will require structural members with greater stiffness (more weight) for
the deployable platform system.

TECHNICAL OBJECTIVES

Select the most cost-effective approach to minimize structural load ampli-
fication for lightweight deployable space platform structures.

TASK DESCRIPTIONS

Two approaches are p:esented. The optimum pulsing approach is shown to
be the most cost-effective method and will be adopted as the baseline
method to minimize load amplification.

1.   Develop and demonstrate an RCS thruster (0.1 to 0.25 lb
     thrust level) which has a 10-20 second rise time.

2.   Define a suitable method (hardware and mechanization) for
     optimum pulsing of current design RCS thrusters, such that
     the structural response of the system does not lead to
     appreciable load amplification factors. Include verifica-
     tion testing using representative structure and utilities
     in a space flight mode.

NEW TECHNOLOGY NEED

TASK TITLE: RADIATION RESISTANT FIBER OPTICS

JUSTIFICATION:

Quartz fiber optics are subject to color center formations, called opaquing (degrading effect to light transmission), caused by radiation impingement in a vacuum. The Quartz fiber space lattice is composed of silicon and oxygen atoms which have a one-to-one correspondence (single bond) between each element. Double bonds are formed within the lattice structure (color is added) when radiation (electrons, protons, or photons) displaces an oxygen molecule, thereby destroying one of the single bonds.

Shielding would add considerable mass. The high density material required would be a source of secondary emissions (Bremsstrahlung radiation, produced by the impact of electrons, protons, or photons) which can be more damaging (because these are harder to shield against) than the original radiation.

Two approaches to resolve this problem are presented. The approach which shows the most promise, at the end of the development period, will be adopted as the baseline method for fiber optic applications.

TECHNICAL OBJECTIVES:

1. Determine the possibility that organic materials (such as Acrylic), with higher energy linkage between bonds, are more resistant to galactic radiation and will maintain high transmissibility of light.

2. Determine a suitable method of annealing the Quartz fibers with heat, applied intermittently.

TASK DESCRIPTIONS:

1. Select the most promising organic materials which possess suitable light transmission characteristics.

   Conduct a laboratory testing program to determine the amount of resistance to simulated galactic radiation of each material selected above.

   Based on the above test results recommend an organic material suitable for 10-year life in geosynchronous orbit.

2. Investigate possible methods of annealing Quartz fibers with heat. Conduct laboratory tests to verify that annealing restores the single bonds between elements (no degradation).

NEW TECHNOLOGY NEED

TASK TITLE: Lightweight, low CTE, High-Strength Cluster Fitting

JUSTIFICATION:

Without a low CTE cluster fitting, the effective CTE for the overall
deployable platform design could be appreciably higher and result in
increased thermal deformation.

TECHNICAL OBJECTIVES:

Develop a technique for producing multi-directional cluster fittings
which have the following characteristics: (1) low CTE in each ^f the
projected (longitudinal) directions; (2) close-tolerance clevis pin holes;
(3) high bearing allowables at the clevis pin holes; (4) low overall
weight; and (5) high strength across the fitting.

TASK DESCRIPTIONS:

1. Manufacture several cluster fittings using different ratios of resin to
    fiber, different fibers, mixes of fibers (glass/carbon), as well as
    combination techniques (partial hand layup, partial injection mold).
    Consider metal inserts for clevis pin holes.

2. Perform a laboratory test program to evaluate longitudinal CTE,
    bearing stress limits, weight, load capacity across the fitting.
    Select the manufacturing methods and material which best meet the
    characteristics desired.

3. Develop a process specification to be used tc produce multi-directional
    cluster fittings.

```
┌────────────────────────────────────────────────────────────────┐
│        NEW TECHNOLOGY NEED—CONTINUATION SHEET                    │
├────────────────────────────────────────────────────────────────┤
│ TASK TITLE:   PASSIVE STRUCTURAL DAMPING TECHNIQUES             │
└────────────────────────────────────────────────────────────────┘
```

JUSTIFICATION. The visco-elastic material currently used to attenuate structural response is very heavy and, therefore, would not be suitable for application to the entire deployable platform. A judicious application to each pinned joint, to cause the joint to respond more like a cantilevered beam, needs to be investigated and design solutions verified by testing.

TECHNICAL OBJECTIVES. Develop passive structural damping techniques suitable for the pinned joints of large deployable space platform structures.

TASK DESCRIPTIONS

1. Design studies to determine best means of applying visco-elastic material to pinned joints.

2. Laboratory test program to verify attenuation of structural response (pinned joints respond more like cantilevered beam).

3. Establish a design standard for applying visco-elastic material to pinned joints for deployable space platforms.

NEW TECHNOLOGY NEED

TASK TITLE: Micrometeoroid Impact Structure Damage

JUSTIFICATION

The probability of micrometeoroid impact upon the structural members in a
deployable truss is sufficiently significant to be of concern to the
structural integrity. Presently, there is virtually no data descriptive
of the impact damage upon structural tubes of circular, square, or rectang-
ular cross sections fabricated from composite materials.

TECHNICAL OBJECTIVE

To develop analytical method (confirmed by testing) for prediction of
micrometeoroid impact damage to circular, square, and rectangular tubes
of graphite epoxy and aluminum construction.

(1) Develop analytical methodology, using existing techniques to
    maximum extent possible, to predict structural damage of cand-
    idate constructions.

(2) Manufacture nine representative sections of graphite epoxy tubing
    and nine representative sections of aluminum tubing. Two tubing
    shapes will be made (nine round, and nine square).

(3) Characterize each different tubing shape (round, square) for
    compressive strength.

(4) Test six sections of each different tubing shape for hypervelocity
    impact, using glass beads with a mass of one gram (or less) to
    produce velocities of 7 km/sec or more. Three sections are to be
    hit on centerline, and three sections hit one inch off centerline.

(5) Retest each tubing section (which was penetrated) for strength
    characteristics as described in item (2) above.

(6) Correlate analytical predictions with test data and mobility
    prediction techniques, as required.

NEW TECHNOLOGY NEED

TASK TITLE: Radiation-Resistant Thermal Control Coating

JUSTIFICATION

The white pigments used in thermal control coatings (such as zinc oxide
and titanium dioxide) tend to increase in solar absorptivity in the space
environment. The cause is believed to be a combination of ultra violet
and entrapped radiation, causing the loss of a small percentage of oxygen
or water in the pigment. Most white paints will slowly discolor because
of color centers formed (caused by the loss of oxygen or water). This
phenomenon causes spacecraft temperature to increase and could imperil the
operation of temperature-sensitive components using structure as a heat
sink.

TECHNICAL OBJECTIVE

Verify that a new pigment (such as zinc orthotitanate), with an appropriate
binder, will not degrade significantly over the ten-year life of the space
platform in geosynchronous orbit.

TASK DESCRIPTION

Conduct laboratory tests on new pigments (such as zinc orthotitanate), with
an appropriate inorganic binder, to determine the amount of degradation to
be expected in a space environment over a ten-year period. Recommend a new
pigment and binder combination for long-term space applications.

NEW TECHNOLOGY NEED

TASK TITLE: HIGH CAPACITY HEAT PIPE

Justification

High capacity heat pipes, in the range of 20 KW-meters and above, have
not been developed and demonstrated.

Technical Objective

Develop and demonstrate a high capacity heat pipe

Task Description

Develop and demonstrate a high capacity heat pipe design (20 KW-meters
and above), suitable for space platform application.

NEW TECHNOLOGY NEED

TASK TITLE: Active Structural Control Techniques

JUSTIFICATION:

This technology will permit system performance requirements to be achieved in the presence of relaxed structural stiffness, frequency, damping, and alignment requirements.

TECHNICAL OBJECTIVES:

Develop an active structural control technique for vibration suppression and shape control (including use of distributed sensors and actuators) in order to reduce requirements for structural stiffness, frequencies, and damping.

TASK DESCRIPTIONS:

1. Develop methodology.

2. Synthesize active structural control approach for space platform.

3. Simulate and evaluate sensitivity to "real world" errors and develop hardware requirements.

4. Develop sensor and actuator requirements.

5. Verify sensor and actuator performance by space flight-testing representative structure and utilities.

NEW TECHNOLOGY NEED

TASK TITLE: Adaptive Control Techniques

JUSTIFICATION

Large tolerances on structural dynamic parameters, from preflight analytical estimates, will not permit achievement of a high-performance controller. Ground testing of very large structures is difficult and expensive. Classical frequency separation criteria impose unnecessarily severe structural dynamic requirements.

TECHNICAL OBJECTIVES

Development of an in-flight dynamic mode identification technique in order to reduce tolerances of structural dynamic parameters. These data will permit adaptive readjustment of the controller to achieve higher stability/performance and/or reduction in structural bending stiffness and frequency requirements.

TASK DESCRIPTIONS

(1) Develop methodology.

(2) Synthesize adaptive approach for space platform application.

(3) Simulate system and evaluate sensitivity to "real world" errors.

(4) Formulate new criteria for structural dynamic design requirements.

(5) Verify in-flight dynamic mode identification technique by ground testing representative structure and utilities.

NEW TECHNOLOGY NEED

TASK TITLE: Lightweight, High-Strength Member (Male) itting

JUSTIFICATION:

Separate (male) fittings will weigh more (and require more volume) than a fitting which is integral with the structural member. Packaging efficiency of the deployable platform may be degraded.

TECHNICAL OBJECTIVES:

Develop a technique for producing lightweight, high-strength member (male) fittings as an integral part (extension) of the structural compression member.

TASK DESCRIPTIONS:

1. Manufacture several member (male) fittings by a layup technique, transitioning from a circular (tube) member to a flat tongue. Consider the addition of different fibers in the male fitting, as well as metal inserts for the clevis pin hole.

2. Laboratory test program to evaluate compression/tension limits and bearing stress limits. Select the manufacturing methods and materials which best meet the desired characteristics.

3. Develop a process specification to be used to produce integral (male) member fittings.

NEW TECHNOLOGY NEED

TASK TITLE: INSULATED FLEXIBLE LINES

Justification

Insulated fluid lines, currently on the market, are not flexible enough
to bend to a small radius. Those designs available which will bend to
a small radius are quite bulky and require too much room when stowed
in a deployable structure.

Technical Objective

Develop a new concept for insulated flexible lines.

Task Description

Design and develop a new concept for an insulated flexible line which is
not bulky and will permit bending to a small radius.

NEW TECHNOLOGY NEED

TASK TITLE: Low CTE, High Modulus, Flexible Tension Member

JUSTIFICATION:

The only high-strength tension member which is quite flexible and currently
available is stranded wire cable. Wire cable, however, has a substantially
higher coefficient of thermal expansion compared to the anticipated
composite structure. Net result would be a loss of tension in sunlight
and excessive tension in the earth's shadow. The structure's shape,
pointing accuracy, and load-carrying capacity would be severely degraded.

TECHNICAL OBJECTIVES:

Develop a high-strength tension member which will bend to a small radius,
have an extremely small coefficient of thermal expansion, and not
degrade in the space environment.

TASK DESCRIPTIONS:

Laboratory test program to determine the best composite material (such as
P100S graphite fibers, imbedded in an elastomeric matrix material) which
will bend to a small radius, have an extremely small coefficient of
thermal expansion, and will not degrade in a space environment.

4. CONCEPT SELECTION

This section describes the process used to select the most suitable concept from the eight candidate building block designs, described in Section 1. This process identified Concepts 6 (Figure 1.4-17) and 8 (Figure 1.4-20) as together being the designs that best satisfy the major criteria tabulated in Table 4.1-1. The major reasons for identification of Concepts 6 and 8 are enumerated as follows:

o   The open-square shape of Concept 8 has the best growth potential for utilities and can accommodate (in trays) up to twice the adopted study requirements (increased utilities requirements are typical with program maturity).

o   For significantly reduced utilities requirements (mountable on longerons) Concept 6 is adequate and is a simpler structural design than Concept 8.

o   The two designs together can satisfy the LEO/GEO platform requirements with common concepts of housing, adapter, deployment mechanization and building-block to building-block attachment designs.

o   Redundancy for meteoroid impact survival (if necessary) is available.

o   The square housing is most suitable for mounting of payloads, subsystems, propulsion modules, and mounting ports.

o   The square housing is most amenable to support in the orbiter cargo bay.

The identification of Concepts 6 and 8 was accomplished through review of summary tables (4.10-1 through 4.10-5). These tables encompass the major criteria of Table 4.1-1.

At the conclusion of this selection process, the best features of Concepts 6 and 8 were configured into a new concept called 6A, (Figure 4.11-2). Concept 6A is the same design as Concept 6 except the longerons are folded at 30° rather than 45° (Drawing 42712-29, Volume II), clearing the center of the square frame for installation of utility trays such as are shown for Concept 8 (Drawing 42712-025, Volume II). The overall features of this design are summarized as follows:

o   Building-block approach for automatic deployment of platform systems.

o   The square-shaped truss is most suitable for inter-building-block attachments; mounting of payloads, docking ports, propulsion modules, etc.

o   Circular tubes for all truss members provide minimum cost construction with use of graphite composite construction.

4-1

o   Trays for mounting of adopted complement of utilities provide ease
    of initial installation, repair, and replacement during total ground
    fabrication period with minimum truss structural design constraints
    imposed by utilities integration

o   Small complements of utilities can be mounted directly onto the
    longerons (design reduces to Concept 6).

o   Square-shaped housing with reciprocating deployment mechanism

o   Bay-by-bay deployment to facilitate identification of deployment
    problem (in the event this occurs).

o   Rail system for root strength during deployment permits orbiter
    berthing and orbiter VRCS firing, if necessary.

o   Adapters for mounting of payloads with automatic electrical
    connector interface.

o   Payloads and propulsion modules attached using RMS.

Further detail concerning the selection process is provided in the remainder
of this section.

4.1 MAJOR CRITERIA

The criteria used in the selection are listed in Table 4.1-1. Many other criteria were included and then rejected, since there was no difference among the concepts insofar as these criteria are concerned. For example, one early criterion was the ability to deploy in a straight line. All of the concepts have this characteristic, hence that particular criterion was eliminated.

An explanation of each criterion together with the approach to grading the concepts is provided in Sections 4.3 through 4.9.

Table 4.1-1. Major Criteria Used in
the Selection Process

1. DESIGN VERSATILITY (WITH DISTINCTIONS BETWEEN LEO AND GEO) OF STRUCTURAL CONCEPT
   - Accommodation of adopted power and data utilities requirements
   - Accommodation of reduced power and data utilities requirements
   - Accommodation of fluid utilities: Two 2-cm lines (or equivalent)
   - Satisfaction of adopted strength and stiffness requirements
   - Satisfaction of strength and stiffness requirements that are each 1/10 of the adopted values
   - Satisfaction of the adopted strength requirement and 10 times the adopted stiffness requirement
   - Platform construction
   - Accommodation of aluminum and graphite composite materials

2. COST OF TOTAL BUILDING BLOCK IN GENERIC PLATFORM
   - Launch cost
   - Fabrication cost
   - Orbit transfer to GEO
   - Technology development differential (negligible)

3. THERMAL STABILITY OF STRUCTURAL CONCEPT

4. METEOROID IMPACT SUITABILITY OF STRUCTURAL CONCEPT

5. RELIABILITY OF DEPLOYMENT (BUILDING BLOCK)
   - Basic truss structure
   - Docking port structure
   - Housing
   - Materials variation
   - Adapter
   - Mechanization

6. PREDICTABILITY OF PERFORMANCE OF STRUCTURAL CONCEPT

7. INTEGRATION SUITABILITY OF BUILDING BLOCK

4.2 METHODOLOGY

The eight concepts are graded by an allocation of points. Points are allocated to the concepts in two ways:

- o   Qualitative data are converted to points judgmentally.

- o   Quantitative data are converted to points using a linear system as shown in Figure 4.2-1. Regarding the line marked "baseline evaluation" the most desirable concept is awarded 100% points and the least desirable concept is awarded 50% points. The other concepts are graded on a linear basis between the two extremes. This method was used for all the tables shown up to and including Tables 4.10-1 and -2.

Figure 4.2-1.   Point Evaluation Methodology

Another approach is shown on Figure 4.2-1, but uses the line marked "sensitivity study". The only difference is that zero % points are awarded to the least desirable concept instead of 50%. This method was used in compiling summary tables (4.10-3 and -4). Both the "baseline study" and the "sensitivity study" are incorporated into this selection process.

There is only one important distinction between LEO and GEO in terms of concept selection, and that is mass. Other differences between LEO and GEO are listed below, but do not affect concept selection:

- o   Transfer to GEO introduced a somewhat higher loading regime, but not sufficient for distinction in trade

- o   No significant differences observed in flexural and torsional stiffness requirements

4-4

o   No differences (significant to concept selection) observed in
    - Utilities requirements (function of payloads)
    - Meteoroid environment
    - Thermal environment
    - Servicing and maintenance

4.3 DESIGN VERSATILITY OF STRUCTURAL CONCEPT

The grading of the eight buiding-block concepts for this criterion is shown on seven tables:

o   Table 4.3-1 - Electrical Accomodations (GEO)

o   Table 4.3-2 - Electrical Accomodations (LEO)

o   Table 4.3-3 - Fluid Utilities Accommodations (LEO and GEO)

o   Table 4.3-4 - Structural Materials Variation (LEO and GEO)

o   Table 4.3-5 - Strength & Stiffness Accommodations (GEO)

o   Table 4.3-6 - Strength & Stiffness Accommodations (LEO)

o   Table 4.3-7 - Platform Construction (LEO and GEO)

The following notes are intended to explain the rationale behind the grading and points allocation of Tables 4.3-1 through 4.3-7.

For Tables 4.3-1 through 4.3-3:

o   Mass implications apply to the mass of trays, clips, and shoes, etc., necessary to support utilities.

o   The high electrical requirement is the baseline adopted requirement.

o   The low electrical requirement consists of eight No. 4 lines and 1/8 the complement of adopted data lines.

o   The values assigned are based on accommodation of utilities by the utilities installation designs tabulated as follows:

CONCEPT	LOW REQUIREMENT	HIGH REQUIREMENT	FLUIDS
1	TRAYS	TRAYS	TRAYS
2	TRAYS	TRAYS	LOOPS
3	COILED	COILED	LOOPS
4	LONGERONS	LOOPS	LOOPS
5	TRAYS	TRAYS	TRAYS
6	LONGERONS	LOOPS	LOOPS
7	TRAYS	TRAYS	TRAYS
8	TRAYS	TRAYS	TRAYS

Tables 4.3-1 and 4.3-2 address the comparative capability of the designs to accommodate the electrical utilities, respectively, for GEO and LEO applications. The following clarification of the evaluation parameters is presented:

o   Reliability for Space Deployment

This parameter addresses the likelihood of successfully moving the electrical lines from the stowed to the deployed position. Retraction is not a factor. Lines which are mounted on trays or on the longerons are thought to be the most reliable. Looped lines are similarly reliable for small quantities of lines, but slightly less reliable for large bundles. Coiled lines are judged to be the least reliable.

o   Ease of Ground Deployment and Checkout

This section addresses the ease/difficulty of extending and retracting the electrical utilities several times in a 1-g environment. Factors included in the assessment are accessibility and the necessity for manual resetting of the lines for retraction.

Table 4.3-1. Electrical Accommodations (GEO)

CONCEPT	LOW REQUIREMENT								HIGH REQUIREMENT								TOTAL LOW AND HIGH REQUIREMENT
	RELIABILITY SPACE DEPLOYMENT		EASE OF GROUND DEPLOYMENT & CHECKOUT		SUITABILITY TO LAUNCH ENVIRONMENT		MASS* IMPLICATION		TOTAL LOW REQUIREMENT	RELIABILITY SPACE DEPLOYMENT		EASE OF GROUND DEPLOYMENT & CHECKOUT		SUITABILITY TO LAUNCH ENVIRONMENT		MASS* IMPLICATION		TOTAL HIGH REQUIREMENT	
	RANK	PTS	RANK	PTS	RANK	PTS	MASS	PTS		RANK	PTS	RANK	PTS	RANK	PTS	MASS	PTS		
	MAX POINTS 20		MAX POINTS 10		MAX POINTS 20		MAX POINTS 20		MAX POINTS 70	MAX POINTS 20		MAX POINTS 10		MAX POINTS 20		MAX POINTS 20		MAX POINTS 70	MAX POINTS 140
1	1	20	3	9	3	18	.14	10	57	1	20	1	10	1	20	.68	10	60	117
2	1	20	3	9	3	18	0	20	67	1	20	1	10	1	20	0.1	19	69	136
3	8	15	8	4	8	10	0	20	49	8	15	8	4	6	12	0	20	51	100
4	1	20	1	10	1	20	0	20	70	6	18	6	6	7	6	.15	18	48	118
5	1	20	ᴗ	7	3	18	.14	10	55	1	20	4	8	1	20	.64	11	59	114
6	1	20	1	10	1	20	0	20	70	6	18	6	6	7	6	0.1	19	49	119
7	1	20	6	7	3	18	.14	10	55	1	20	4	8	1	20	.64	11	59	114
8	1	20	5	8	3	18	0.0	20	66	5	19	3	9	1	20	0.3	15	63	129

NOTES:

* KG X 10^{-3}

Table 4.3-2. Electrical Accommodations (LEO)

CONCEPT	ELECTRICAL UTILITIES ACCOMMODATION													
	LOW REQUIREMENT							HIGH REQUIREMENT						TOTAL LOW AND HIGH REQMT
	RELIABILITY SPACE DEPLOYMENT		EASE OF GROUND DEPLOYMENT & CHECKOUT		SUITABILITY TO LAUNCH ENVIRONMENT		TOTAL LOW REQMT	RELIABILITY SPACE DEPLOYMENT		EASE OF GROUND DEPLOYMENT & CHECKOUT		SUITABILITY TO LAUNCH ENVIRONMENT		TOTAL HIGH REQMT	
	RANK	PTS	RANK	PTS	RANK	PTS		RANK	PTS	RANK	PTS	RANK	PTS		
	MAX POINTS 20		MAX POINTS 10		MAX POINTS 20		MAX PTS 50	MAX POINTS 20		MAX POINTS 10		MAX POINTS 20		MAX PTS 50	MAX PTS 100
1	1	20	3	9	3	18	47	1	20	1	10	1	20	50	97
2	1	20	3	9	3	18	47	1	20	1	10	1	20	50	97
3	8	15	8	4	6	10	29	8	15	8	4	6	12	31	60
4	1	20	1	10	1	20	50	6	18	6	6	7	6	30	80
5	1	20	6	7	3	18	45	1	20	4	8	1	20	48	93
6	1	20	1	10	1	20	50	6	18	6	6	7	6	30	80
7	1	20	6	7	3	18	45	1	20	4	8	1	20	48	93
8	1	20	4	8	3	18	46	5	19	3	9	1	20	48	94

o   Suitability to Launch Environment

This parameter subjectively accounts for the degree of support
provided to the utilities during launch by the utilities
installation systems (longerons, trays, clips, shoes). Electrical
utilities mounted on the longerons are best, with trays second, and
the remaining concepts last. The points allocated are a judgmental
estimate of the relative difference between the designs.

o   Mass Implication

This parameter quantitatively accounts for the GEO transfer cost
implication of the utilities support system mass. The masses shown
represent the delta mass above that of the minimum value.

Table 4.3-3 compares the comparative capability of the designs to accommodate the fluid utilities. The following clarification of the evaluation parameters is presented.

o   Minimum Bend Radius

A large bend radius in the fluid lines is judged to be better than a small bend radius. A small bend radius has higher stress and takes more force to fold.

o   The notes for Tables 4.3-1 and 4.3-2 apply to the other parameters shown.

Table 4.3-3.   Fluid Utilities Accommodation
(LEO and GEO)

CONCEPT	FLUID UTILITIES ACCOMMODATION							
	RELIABILITY SPACE DEPLOYMENT		EASE OF GROUND DEPLOYMENT & CHECKOUT		SUITABILITY TO LAUNCH ENVIRONMENT		MINIMUM BEND RADIUS		
	RANK	PTS	RANK	PTS	RANK	PTS	RADIUS (CM)	PTS	TOTAL
	MAX POINTS 20		MAX POINTS 10		MAX POINTS		MAX POINTS 20		MAX PTS 70
1	1	20	1	10	1	20	12	15	65
2	5	19	5	8	5	18	20	20	65
3	8	10	6	7	6	16	20	20	53
4	5	19	8	7	7	6	14	14	46
5	1	20	3	9	1	20	4	10	59
6	5	19	6	7	7	6	14	18	50
7	1	20	3	9	1	20	4	10	59
8	1	20	1	10	1	20	3.1	10	60

Table 4.3-4 compares the versatility of the candidate structural designs to use either aluminum or composite materials (graphite epoxy or metal matrix). The judgemental evaluation is based upon the degree of static determinacy of the structure. The maximum points are assigned to statically determinate structures. A pure statically determinate structure can experience thermal gradients between members with no loads incurred and no resistance to closure just prior to locking at the end of the deployment phase.

*Table 4.3-4. Structural Materials
Variation (LEO and GEO)*

STRUCTURAL MATERIAL VARIATION*—20 POINTS		
CONCEPT	RANK	POINTS
1	1	20
2	1	20
3	6	8
4	1	20
5	6	8
6	1	20
7	1	20
8	6	8
NOTES: *COMPOSITE MATERIALS OR ALUMINUM		

Tables 4.3-5 and 4.3-6 compare, for GEO and LEO platforms, respectively, the candidate concept trusses accommodation of varied strength and stiffness requirements. The three ranges of strength and stiffness requirements are defined in Table 4.1-1, (Major Criteria used in the Selection Process). The accommodation of strength and stiffness is described by packaging efficiency and structure mass; hence, these parameters are the basis for this assessment. Clarification of each of the parameters is as follows:

o   Packaging Efficiency

     The packaging efficiency is the ratio of deployed length to stowed length. This is a quantitative evaluation with linear distribution of points between the maximum and minimum values. Consideration was devoted to use of a volumetric efficiency term. The linear efficiency is used because the study of packaging (Section 1.4.3) the concepts indicates that it is the most significant factor.

o   Mass Implication

     This parameter represents the estimated weight difference between the concepts as used in the generic platform. A detailed breakdown of the designs for the adopted strength and stiffness requirements is presented in Table 1.4-3. The concern here is the implication on GEO transfer cost.

Table 4.3-5. Strength and Stiffness Accommodation (GEO)

CONCEPT	REDUCED STRENGTH AND STIFFNESS					ADOPTED STRENGTH AND STIFFNESS					INCREASED STIFFNESS					TOTAL ACROSS ALL REQMTS.
	PACKAGING EFFICIENCY (PE)		MASS IMPLICATION			PACKAGING EFFICIENCY (PE)		MASS IMPLICATION			PACKAGING EFFICIENCY (PE)		MASS IMPLICATION			
	PE	PTS	Δ MASS	PTS	SUBTOTAL	PE	PTS	Δ MASS	PTS	SUBTOTAL	PE	PTS	Δ MASS	PTS	SUBTOTAL	
	MAX POINTS 10		MAX POINTS 20		30	MAX POINTS 20		MAX POINTS 30		50	MAX POINTS 10		MAX POINTS 10		20	100
1	22	5	1.0	12	17	16	10	1.1	17	27	8	5	10	0	5	49
2	32	10	1.2	10	20	21.6	17	1.3	15	32	8	5	14	0	5	
3	26	7	0.0	20	27	20	15	0.0	30	45	20	9	0	10	19	91
4	26	7	0.2	19	26	20	15	0.7	22	37	10	6	10	0	6	69
5	25	6	0.9	13	19	25	20	0.1	29	49	25	10	3	3	13	81
6	31	9	0.6	15	24	20	15	1.0	18	33	10	6	12	0	6	63
7	25	6	1.3	?.	16	25	20	1.3	15	35	25	10	3	3	13	64
8	26	8	0.6	15	23	22	17	0.9	18	35	14	7	12	0	7	65

NOTES: MASS DATA (KG × 10⁻³) BASED ON GENERIC PLATFORM (WITHOUT MECHANIZATION SYSTEM).

Table 4.3-6. Strength and Stiffness Accommodation (LEO)

CONCEPT	REDUCED STRENGTH AND STIFFNESS		ADOPTED STRENGTH AND STIFFNESS		INCREASED STIFFNESS		TOTAL ACROSS ALL REQMTS
	PACKAGING EFFICIENCY (PE)		PACKAGING EFFICIENCY (PE)		PACKAGING EFFICIENCY (PE)		
	PE	POINTS	PE	POINTS	PE	POINTS	
	MAXIMUM POINTS 10		MAXIMUM POINTS 20		MAXIMUM POINTS 10		40
1	32	5	15	10	8	5	20
2	32	10	21.6	17	8	5	32
3	26	7	20	15	20	9	31
4	26	7	20	15	10	6	28
5	25	6	25	20	25	10	36
6	31	9	20	15	10	6	30
7	25	6	25	20	25	10	36
8	28	8	23	17	14	7	32

Table 4.3-7 compares the candidate concepts' bui.ding-block platform
construction versatility. The following discussion clarifies the comparison
parameters.

Table 4.3-7. Platform Construction (LEO and GEO)

CONCEPT	EASE OF JOINING BUILDING BLOCKS		BEST ACCOMMODATION OF PAYLOADS AND DOCKING		MINIMUM DESIGN CONSTRAINTS— RAIL DEPLOYMENT		
	RANK	POINTS	RANK	POINTS	RAIL LENGTH (METERS)	POINTS	TOTAL
	MAX. POINTS 20		MAX. POINTS 20		MAX. POINTS 20		MAX. PTS 60
1	4	14	4	18	3.2	17	49
2	1	20	1	20	2.5	18	58
3	8	6	8	6	6.0	10	22
4	4	14	4	18	1.6	20	52
5	6	10	6	10	2.8	17	37
6	1	20	1	20	1.6	20	60
7	6	10	6	10	2.8	17	37
8	1	20	1	20	1.9	19	59

o   Ease of Joining Building-Blocks

This section ranks the ease and versatility of joining building blocks
together to form platforms of many configurations. Building blocks are joined
to each other or to other modules via the main housing or adapter. Rigid
square housings/adapters are the best, followed by rigid triangular shapes.
Expanding triangular shapes, such as Concepts 5 and 7, pose difficulties
because of the change in dimension of the housings/adapters. Concept 3
offers the most difficulty because of the flat shape of the housing/
adapter, and because only two of the longerons are tied into the main
housing. The other two longerons must be tied into another structure
(subsequent to truss deployment) to maintain structural integrity.

o   Best Accommodation of Payloads and Docking

Payloads/docking accommodations are provided by the main housings and the
adapters. Adapters which do not change shape are judged superior to those
which expand (Concepts 5 and 7) or to those which unfold (Concept 3). Rigid
square main housings are best for mounting interfaces, closely followed by
rigid triangular housings. Concepts 5 and 7 have expanding triangular
housings which pose obvious difficulties. The mounting of an interface on the
main housing of Concept 3 requires a deployable substructure.

o   Minimum Design Constraints—Rail Deployment

The length of the deployment/guide rails poses some design
constraints. If the rail is to be folded for stowing, a longer rail
may require multiple folds. If the rail is to be moved into
operating position subsequent to a partial deployment of the
truss/payload, a longer rail requires a longer "partial deployment"
which in turn implies a longer "partial deployment mechanism".
Finally, if a fixed rail system is to be used, a longer rail implies
that more of the orbiter payload bay is required for stowage.

4.4 COSTS FOR GENERIC PLATFORM (LEO AND GEO)

The grading of the eight building-block concepts is shown on Table 4.4-1.
Additional information is provided on Tables 1.4-4, and 1.4-5

The following notes are intended to explain the rationale behind the grading,
points allocation of Tables 4.4-1.

Table 4.4-1 presents the comparative costs determined for the candidate
concepts as used in the generic platform and sized for the adopted
strength/stiffness requirements and adopted complement of utilities.   The

Table 4.4-1.   Costs for Generic Platform (LEO and GEO)

CONCEPT	Δ LAUNCH COST ①		Δ FAB. COST (SM)	TOTAL Δ COST FOR LEO (SM)	EQUIV. POINTS FOR Δ COST FOR LEO	Δ OTV COST FOR GEO TRANSFER ②		EQUIV. POINTS FOR Δ COST FOR GEO
	Δ PKG. LENGTH (METERS)	Δ (SM)			MAX PTS 20	Δ MASS	Δ (SM)	MAX PTS 20
1	2.25	5.9	1.5	7.4	11	1.1	9.7	12
2	1.5	3.9	4.3	8.2	10	1.3	11.5	10
3	2.3	6.0	0.3	6.3	12	0.0	0.0	20
4	0.75	1.8	0.5	2.3	17	0.7	6.2	14
5	0.0	0.0	0.0	0.0	20	0.0	0.0	20
6	2.1	5.5	2.3	7.8	11	1.0	8.8	12
7	0.0	0.0	1.3	1.3	18	1.3	11.5	10
8	1.5	3.9	3.0	6.9	12	1.2	10.6	11

NOTES:
① BASED ON $2.6M PER METER OF PACKAGED LENGTH
② BASED ON $8.8K PER KG

difference in packaged lengths is determined from the packaging arrangements shown in Section 1.4.3. The recurring fabrication costs are extracted from Table 1.4-5. The use of the unit Shuttle launch cost of $2.6M/meter is based upon a FY 1981 launch cost of $48M divided by the 18.3 m bay length. A significant reservation on the use of this value is that for a dedicated mission the $48M cost is incurred regardless of the length of the bay actually used.

The differences in platform mass are obtained from the data shown on Table 1.4-4. A significant reservation pertaining to the OTV transfer costs is that it is representative of only the adopted strength/stiffness requirements and for the generic platform. For this reason, and the reservations noted above, the point allotment of the cost criteria on the final summation charts is no more than 40. Further, the maximum cost differences shown are very small compared to the total system cost.

4.5 THERMAL STABILITY OF STRUCTURAL CONCEPT

The grading of the eight concepts for thermal stability is shown in Table 4.5-1. This table is a summary of the thermal data shown on Table 1.4-2.

Table 4.5-1. Thermal Stability of Structural Concept

CONCEPT	d (m)	DIAGONAL PRESENT	LONGERON TEMP. (°C)		ΔT (°C)	FIGURE OF MERIT, d/(ΔT)	POINTS
			SUN SIDE	SHADE SIDE			
1	1.6	YES	21.6	-13.5	35.1	0.046	11
2	1.3	YES NO	20.7 24.0	-11.6 4.8	32.3 19.2	0.053	12
3	3.0	NO	24.0	2.7	21.3	0.140	20
4	1.7	YES	21.7	-7.4	29.1	0.058	12
5	2.5	YES (TENSION STRAP)	23.8	-36.0	59.8	0.040	11
6	1.3	YES	22.5	-22.6	45.1	0.029	10
7	2.5	YES	23.6	-56.7	80.3	0.031	10
8	1.3	YES	22.5	-17.5	40.0	0.031	10

4.6 METEOROID IMPACT SUITABILITY OF STRUCTURAL CONCEPT

This section discusses the issue of potential meteoroid impact and structural survival. The data in Table 4.6-1 were derived using the meteoroid model stipulated in Reference 6. The model is sufficiently accurate for the GEO environment. Man-made debris was less critical (Reference 15).

The size of the meteoroid particles and associated probabilities are shown for two sizes of platform and for a 10-year exposure. The projected area applies to the totality of truss members. Little to no recent information exists pertinent to the size of holes resulting from the meteoroid strike, particularly for graphite composites. From discussions with Materials personnel and reviews of meteoroid impact damage (Reference 7), it is estimated that the hole size may be 2 to 4 times the diameter of the particle. Considering the low levels of stress and low number of cycles associated

with RCS systems, and the negligible impact of the hole on local or Euler
stability, it is likely that the structural damage will be acceptable.
However, since this needs to be verified, redundancy in the structural
design is an advantage; hence the grading of the eight concepts is based
on that consideration and is shown in Table 4.6-2.

C

Table 4.6-1. Probability of Meteoroid Damage

GENERIC PLATFORM (220 m²)		
PROBABILITY OF HIT IN 10 YR (%)	METEOROID DIAMETER (cm)	POTENTIAL HOLE DIA. (cm)
1	0.60	1-1/4 TO 2-1/2
2	0.48	1 TO 2
5	0.38	3/4 TO 1-1/2
SMALLER PLATFORM (70 m²)		
PROBABILITY OF HIT IN 10 YR (%)	METEOROID DIAMETER (cm)	POTENTIAL HOLE DIA. (cm)
1	0.42	3/4 TO 1-1/2
2	0.36	3/4 TO 1-1/2
5	0.30	1/2 TO 1-1/4

Table 4.6-2. Meteoroid Impact Suitability

CONCEPT	METEOROID IMPACT SUITABILITY—20 POINTS	
	RANK	POINTS
1	5	10
2	4	16
3	1	20
4	5	10
5	5	10
6	1	20
7	5	10
8	1	20

4.7 RELIABILITY OF DEPLOYMENT OF BUILDING BLOCK

This section compares the candidate building-blocks for reliability of deployment based on the parameters which are explained in detail below. The grading of the eight concepts is listed in Table 4.7-1.

o   Basic Truss Based on Number of Joints.

This evaluation is based on the number of joints in the length of truss required to build the generic platform. The joints included are sliding joints in diagonals and battens, and folding/rotating joints in the longerons and pyramidal members. There is an inverse linear relationship between the number of joints and the number of points awarded. Table 4.7-2 describes in detail the numbers of joints for each of the eight concepts.

o   Basic Truss Based on Complexity.

This is an assessment based on the type of joints/ movements used in deploying the basic truss structure. Sliding joints in diagonals are judged to be more complex than folding joints. The I-section sliding battens of Concepts 5 and 7 are judged to be the most complex.

Table 4.7-1. Reliability of Building-Block Deployment

CONCEPT	BASIC TRUSS BASED ON NUMBER OF JOINTS		BASIC TRUSS BASED ON COMPLEXITY		THERMAL EFFECTS— GRAPHITE COMPOSITE TRUSS		THERMAL EFFECTS— ALUMINUM TRUSS		HOUSING STRUCTURE		ADAPTER STRUCTURE		DOCKING PORT SUPPORT STRUCTURE		TOTAL
	NO. OF JOINTS	PTS	RANK	PTS	RANK	PTS	RANK	PTS	RANK	PTS	RANK	PTS	RANK	PTS	
	MAX POINTS 10		MAX POINTS 10		MAX POINTS 15		MAX POINTS 5		MAX POINTS 20		MAX POINTS 20		MAX POINTS 10		MAX POINTS 90
1	848	9	2	8	1	15	1	5	1	20	1	20	1	10	87
2	1350	8	2	8	6	12	6	4	1	20	1	20	1	10	82
3	1368	8	1	10	7	12	7	3	1	20	8	12	8	4	69
4	1242	8	2	8	1	15	1	5	1	20	1	20	1	10	86
5	732	10	6	5	7	12	7	3	7	8	6	16	6	6	60
6	1660	7	2	8	1	15	1	5	1	20	1	20	1	10	85
7	1464	8	6	5	1	15	1	5	7	8	6	16	6	6	63
8	2208	5	6	5	1	15	1	5	1	20	1	20	1	10	80

Table 4.7-2. Number of Joints in Basic Structure for Generic Platform

CONCEPT	NUMBER OF BAYS	NUMBER OF LONGERON FOLDED JOINTS	NUMBER OF DIAGONAL TELESCOPING JOINTS	NUMBER OF DIAGONAL FOLDED JOINTS	NUMBER OF BATTEN TELESCOPING JOINTS	NUMBER OF PYRAMIDAL JOINTS	TOTAL JOINTS
1	212	636	212	—	—	—	848
2	270	1080	270	—	—	—	1350
3	114	456	—	—	—	912	1368
4	207	621	621	—	—	—	1242
5	122	366	—	—	366		732
6	215	830	830	—	—	—	1660
7	122	366	366	732	366	—	1464
8	184	1472	736	—	—	—	2208

NOTES: COUNT DOES NOT INCLUDE BASIC CLEVIS JOINTS BECAUSE THEY ARE SIGNIFICANTLY LESS COMPLEX THAN FOLDING AND TELESCOPING JOINTS. THE NUMBERS ARE BASED ON APPROXIMATELY 340 METERS OF TRUSS, WHICH IS THE LENGTH REQUIRED TO BUILD THE GENERIC PLATFORM.

o   Thermal Effects, Graphite Composite Truss or Aluminum Truss

These parameters account for the reduced reliability of deployment inherent in the structures that are indeterminate for the materials shown. The values are judgmental between the maximums and minimum shown.

o   Housing Structure

Concepts 1, 2, 3, 4, 6, and 8 are ranked equal because they are rigid with no mechanisms required. Concepts 5 and 7 are ranked last, because they require a mechanism for lateral extension.

o   Adapter Structure

Concepts 1, 2, 4, 6, and 8 are ranked first because they are rigid structures which require no mechanisms. Concepts 5 and 7 are judged as having less reliability because they are expanded by a mechanism. Concept 3 is ranked last because it requires a separate mechanism to unfold it.

o   Docking Port Structure

A docking port interface mounted to a rigid main housing is the most reliable. Concepts 5 and 7 have expanding main housings which degrade the reliability of the interface. Concept 3 requires a separate substructure to be deployed to obtain a docking port interface. This requires additional mechanization, which is the reason for its being ranked 8th.

4.8 PREDICTABILITY OF PERFORMANCE OF STRUCTURAL CONCEPTS

The grading for the eight concepts is listed in Table 4.8-1.

The features of the eight structural concepts which affect the accurate prediction of structural performance are:

- o   A determinate structure is better than an indeterminate structure for analytical purposes

- o   The difficulty of maintaining the tension in "X" braced structures which is essential to performance predictability

- o   The disadvantages of designs with offset load paths at the joints

While NASTRAN analysis and development testing during a program can deal with these effects, Table 4.8-1 judgmentally and qualitatively accounts for these additional requirements.

Table 4.8-1. Predictability of Performance

CONCEPT	COMPOSITE MATERIALS					ALUMINUM					TOTAL FOR BOTH MATERIALS
	PREDICTION OF INTERNAL LOADS		PREDICTION OF EFFECTIVE STIFFNESS			PREDICTION OF INTERNAL LOADS		PREDICTION OF EFFECTIVE STIFFNESS			
	RANK	POINTS	RANK	POINTS	TOTAL	RANK	POINTS	RANK	POINTS	TOTAL	
	MAX POINTS 10		MAX POINTS 10		MAX PTS 20	MAX POINTS 10		MAX POINTS 10		MAX PTS 20	
1	1	10	1	10	20	1	10	1	10	20	40
2	6	9	8	5	14	6	9	7	5	14	28
3	8	6	1	10	16	7	4	1	10	14	30
4	1	10	1	10	20	1	10	1	10	20	40
5	6	6	7	8	14	8	4	8	2	6	20
6	1	10	1	10	20	1	10	1	10	20	40
7	1	10	1	10	20	1	10	1	10	20	40
8	1	10	1	10	20	1	6	1	10	16	36

4.9 ORBITER INTEGRATION SUITABILITY

This section compares the candidate designs in regard to their orbiter integration suitability.

The grading of the eight concepts is shown on Table 4.9-1.

Table 4.9-1. Orbiter Integration Suitability

CONCEPT	① HOUSING LAUNCH ENVIRONMENT SUITABILITY		① EASE OF PACKAGING INTO ORBITER		② EASE OF PACKAGING INTO ORBITER		① CRADLE STRUCTURE Δ MASS (KG x 10⁻³)		① COMPLEXITY, PACKAGED CONFIGURATION TO DEPLOYED		SPARE VOLUME		
	RANK	POINTS	RANK	POINTS	RANK	POINTS	Δ MASS	POINTS	RANK	POINTS	RANK	POINTS	TOTAL
	MAX POINTS 10		MAX POINTS 10		MAX POINTS 10		MAX POINTS 10		MAX POINTS 10		MAX POINTS 10		MAX PTS 60
1	1	10	8	5	1	10	0.9	8	3	8	7	5	46
2	1	10	5	6	1	10	1.4	7	5	7	4	7	47
3	8	3	4	7	1	10	2.3	5	8	6	1	10	41
4	1	10	3	8	1	10	1.0	8	3	8	7	5	49
5	1	10	1	10	6	8	0	10	1	10	2	8	56
6	1	10	5	6	1	10	1.6	6	5	7	4	7	46
7	1	10	1	10	6	8	0	10	1	10	2	8	56
8	1	10	5	6	1	10	1.4	7	5	7	4	7	47

NOTES: ① APPLICABLE TO GENERIC PLATFORM
② APPLICABLE TO PLATFORM SMALLER THAN GENERIC
③ BASIC BUILDING BLOCK CONCEPT

A discussion of each of the design parameters, listed above, is as follows:

o   Housing Launch Environment Suitability

This parameter judgmentally accounts for the relative capability of the candidate housing designs to sustain the launch/inertia induced loads and also to provide (in conjunction with the cradle structure) a minimum natural frequency above that of the orbiter (say, 10 Hz).

o   Ease of Packaging into Orbiter (Generic Platforms)

The rankings of this section are based on the studies and drawings made for the generic platform only. Factors which influence the package are:

o   Packaging ratio = $\dfrac{\text{expanded length}}{\text{stowed length}}$ of a truss

o   The shape of the truss section

o   The size of the truss section

4-18

Concepts 5 and 7 gain first due to their high packaging ratio. Triangular-shaped trusses generally fit together in a circle (such as the orbiter payload bay) better than square-shaped trusses. If the packaging can be arranged so that the building blocks fit across the payload bay instead of along the longitudinal axis, it is an advantage. This is reflected in the ranking of Concept 3.

o   Ease of Packaging into Orbiter (Smaller than Generic)

No drawings of packaging "smaller than generic" platforms into the orbiter were made. As the platforms become smaller, so does the differential between them, until the point is reached for <u>very</u> small platforms when there is generally little significant advantage of one concept over another. It is judged that small platforms can probably be packaged across the width of the payload bay. Concepts 5 and 7 are ranked slightly lower because of the need for clearance around the expanding main housings.

o   Cradle Structure Delta Weight.

This quantitative assessment describes the delta weight additional to each concept as packaged in the orbiter. The delta weight represents cradle structure, trunnions and, where required, reinforcement of the housing structure. No distinction is made between LEO and GEO designs at this stage of the investigation.

o   Complexity of Configuration—Packaged to Deployed

This evaluation addresses the difficulty and complexity of moving the building blocks from the packaged configuration to the final deployed configurations. For each concept, a count was made of the number of mechanisms/movements required to unlock, rotate, relock each building-block housing and adapter, and the unfolding of the deployment/guide rails. The concept with the least number of mechanisms/movements, etc., was awarded first place with the other concepts graded accordingly. This assessment is applicable only to the generic platform.

o   Spare Volume

In the length of the orbiter payload bay which is occupied by the packaged generic platform, a certain percentage of the volume is available for other purposes. The concept with the maximum space is awarded first place, and the other concepts are ranked accordingly. This assessment applies only to the generic platform.

4.10 SUMMARY OF POINTS AND GRADING

The results of the points allocation and grading of Sections 4.3 through 4.9 are presented in five tables:

o   Table 4.10-1, Total of Normalized Points (LEO)

o   Table 4.10-2, Total of Normalized Points (GEO)

-o   Table 4.10-3, Total of Normalized Points (LEO)-Sensitivity Trade

o   Table 4.10-4, Total of Normalized Points (GEO)-Sensitivity Trade

o   Table 4.10-5, Summary of Points (LEO and GEO)

Table 4.10-1 (LEO) presents the total points in each of the seven major selection criteria for each building-block concept. The point values shown for each concept are obtained from the total point value determined in the individual preceding criteria sheets multiplied by the appropriate factor to be compatible with the maximum point allocations shown on this chart for each criterion. For example, for Concept 1, the total points for "Reliability of Building-Block Deployment" (obtained from Table 4.7-1) is 87 out of a total possible 90 points. The 97 points shown on Table 4.10-1 is obtained by 100/90 x 87 = 96.66 or 97. The "Design Versatility" criterion includes the points obtained from Tables 4.3-2, 4.3-3, 4.3-4, 4.3-6 and 4.3-7, normalized in the same manner as shown above.

Table 4.10-1. Total of Normalized Points (LEO)

CONCEPT	(1) DESIGN VERSATILITY MAX POINTS 100	(2) COST MAX POINTS 40	(3) THERMAL STABILITY MAX POINTS 20	(4) METEOROID IMPACT SUITABILITY MAX POINTS 40	(5) RELI-ABILITY MAX POINTS 100	(6) PREDICT-ABILITY MAX POINTS 20	(7) ORBITER INTEGRATION MAX POINTS 60	TOTAL MAX POINTS 380
1	87 ✓	22	11	20 ·	97 ✓	20 ✓	46	303
2	94 ✓	20	12	32	91	14	47 ✓	310 ③
3	60	24	20 ✓	40 ✓	77	15	41	277
4	78	34 ✓	12	20	96 ✓	30 ✓	49	309 ④
5	80	40 ✓	11	20	67	10	56 ✓	284
6	83	22	10	40 ✓	94 ✓	20 ✓	46	315 ②
7	84	36 ✓	10	20	70	20 ✓	56 ✓	296
8	86 ✓	24	10	40 ✓	89	18	47 ✓	316 ①

NOTES:

CIRCLED NUMBERS IN TOTALS COLUMN DENOTE RANKING.
✓ FOR TOP 3 VALUES IN EACH CATEGORY

The assignment of maximum points of 100 to "design versatility" and "reliability" represents the greater importance of these criteria. The rationale for reduced emphasis on cost is discussed in Section 4.4. It is important to note that this generic requirements point allocation would be different for a very specific mission, depending on constraints. For example, suppose the available orbiter length is a constraint, or suppose subsequent test data indicate meteoroid impact to be more critical than expected. These parameters and/or criteria take on an increased significance. The total points are shown to the right for each concept, with Concepts 8, 6, 2, and 4 representing the most suitable design for a LEO platform.

Table 4.10-2 (GEO) is compiled in the same fashion as Table 4.10-1. The table indicates Concepts 6, 8, 4, 3, and 2 to be most suitable.

Table 4.10-2. Total of Normalized Points (GEO)

CONCEPT	(1) DESIGN VERSATILITY MAX POINTS 100	(2) COST MAX POINTS 40	(3) THERMAL STABILITY MAX POINTS 20	(4) METEOROID IMPACT SUITABILITY MAX POINTS 40	(5) RELI- ABILITY MAX POINTS 100	(6) PREDICT- ABILITY MAX POINTS 20	(7) ORBITER INTEGRATION MAX POINTS 60	TOTAL MAX POINTS 380
1	77	24	11	20	97 ✓	20 ✓	46	295
2	86 ✓	20	12	32	91	14	47 ✓	302 ⑤
3	89	40 ✓	20 ✓	40 ✓	77	15	41	302 ④
4	78	28 ✓	12	20	96 ✓	20 ✓	49	303 ③
5	75	40 ✓	11	20	67	10	56 ✓	279
6	80 ✓	24	10	40 ✓	94 ✓	20 ✓	46	314 ①
7	75	20	10	20	70	20 ✓	56 ✓	271
8	81 ✓	22	10	40 ✓	89	18	47 ✓	307 ②

NOTES:
    CIRCLED NUMBERS IN TOTALS COLUMN DENOTE RANKING.
    ✓ FOR TOP 3 VALUES IN EACH CATEGORY

Tables 4.10-3 and 4 describe the corresponding sensitivity data derived as described in Section 4.2. The results are summarized in Table 4.10-5. The sensitivity study data, however, is not considered on an equal basis with that of the baseline.

Table 4.10-3. Total of Normalized Points (LEO)—Sensitivity Trade

CONCEPT	(1) DESIGN VERSATILITY MAX POINTS 100	(2) COST MAX POINTS 40	(3) THERMAL STABILITY MAX POINTS 20	(4) METEOROID IMPACT SUITABILITY MAX POINTS 40	(5) RELIABILITY MAX POINTS 100	(6) PREDICTABILITY MAX POINTS 20	(7) ORBITER INTEGRATION MAX POINTS 60	TOTAL MAX POINTS 380
1	78	4	⌐	20	93 ✓	20 ✓	44	258
2	90 ✓	0	4	32	85	14	44	269
3	53	8	20 ✓	40 ✓	71	15	36	243
4	70	28 ✓	5	20	91 ✓	20 ✓	47 ✓	281 ①
5	76	40 ✓	1	20	62	10	56 ✓	265
6	79	0	0	40 ✓	89 ✓	20 ✓	43	271 ⑤
7	80 ✓	34 ✓	0	20	64	20 ✓	56 ✓	274 ②
8	82 ✓	6	0	40 ✓	83	16	44	273 ③

NOTES:

Circled numbers in totals column denote ranking.
✓ For top 3 values in each category.

Table 4.10-4. Total of Normalized Points (GEO)—Sensitivity Trade

CONCEPT	(1) DESIGN VERSATILITY MAX POINTS 100	(2) COST MAX POINTS 40	(3) THERMAL STABILITY MAX POINTS 20	(4) METEOROID IMPACT SUITABILITY MAX POINTS 40	(5) RELIABILITY MAX POINTS 100	(6) PREDICTABILITY MAX POINTS 20	(7) ORBITER INTEGRATION MAX POINTS 60	TOTAL MAX POINTS 380
1	58	6	2	20	93 ✓	20 ✓	44	243
2	76 ✓	0	4	32	85	14	44	255
3	85	40 ✓	20 ✓	40 ✓	71	15	36	287 ①
4	69 ✓	18 ✓	5	20	91 ✓	20 ✓	47 ✓	270 ③
5	66	40 ✓	1	20	62	10	56 ✓	255
6	73 ✓	10	0	40 ✓	89 ✓	20 ✓	43	275 ②
7	61	0	0	20	64	20 ✓	56 ✓	221
8	69 ✓	4	0	40 ✓	83	18	44	258 ④

NOTES:

Circled numbers in totals column denote ranking.
✓ For top 3 values in each category.

Table 4.10-5 summarizes the data obtained from the preceding tables. The number of criteria for each concept that are within the top three is indicated.

The major result is that there is little difference in the total points obtained for the top four designs. Hence, the decision between these is judgemental, but based on the knowledge gained from the details of the study and tabulation of the selection process data.

*Table 4.10-5. Summary of Points and Grading,
LEO and GEO*

| CONCEPT | LEO PLATFORM | | | | | | GEO PLATFORM | | | | | |
| | BASELINE DATA | | SENSITIVITY DATA | | NO. OF CRITERIA IN TOP 3 | | BASELINE DATA | | SENSITIVITY DATA | | NO. OF CRITERIA IN TOP 3 | |
	PLACE	POINTS	PLACE	POINTS	BASE	SENS.	PLACE	POINTS	PLACE	POINTS	BASE	SENS.
8	1	316	3	273	3	2	2	307	4	256	3	2
6	2	315	4	271	3	3	1	314	2	275	4	4
4	4	309	1	281	3	4	3	303	3	270	3	5
2	3	310	5	269	4	1	4	302	5	255	2	1

4.11 CONCEPT SELECTION

A review of the selection process of Sections 4.1 through 4.10 and Table 4.10-5 leads to the following general conclusions:

o   Concept selection between the first four designs is judgmental, but based on knowledge obtained f om selection process study.

c   Specific mission critical requirements will impose special emphasis on particular parameters and concept selection.

o   No clear concept choice distinction for LEO or GEO application is represented by the data.

o   The major difference in concept selection will result from extent of payload power and data requirements.

o   No one design is best on the basis of satisfaction of every requirement - improvement toward one requirement almost always results in degradation of another requirement.

o   The thrust of the program for the next 4 years should be to resolve the major design & technology issues pertinent to deployable platform systems.

o The major design and technology issues are essentially the same across the candidate designs.

o The open-square shape of Concept 8 has best growth potential for utilities since it can accommodate in trays up to twice the baseline study requirements (increased utilities requirements typical with program maturity).

o For significantly reduced utilities requirements (mountable on longerons), Concept 6 is adequate and is a simpler structural design than Concept 8.

o Concepts 8 and 6 together present the most promising combinations of top four designs (Figure 4.11-1).

CONCEPT
⑧

CONCEPT
⑥

Figure 4.11-1.   Concepts 6 and 8

Subsequent to the identification of Concepts 6 and 8 as the two designs best suited for LEO/GEO platforms, it became evident that the best features of both can be combined into one. This concept, known as 6A, is shown in Figure 4.11-2, and further discussed as follows:

o Concept 6A is the best utilization of the advantages of Concept 8 (utilities accommodation) and Concept 6 (structural simplicity).

o Concept 6A permits full accommodation of the adopted utilities requirement with a 0.5-meter-wide tray. The longerons are folded at 30°.

o Concept 6A has an acceptable packaging efficiency of 18 for the adopted requirements, and a 1.26-m-deep truss. Increased packaging efficiency is achievable with increased truss depth and reduced loads.

o   The technology development of Concept 6A is applicable to a
     family of designs ranging from Concept 6A to Concept 6.

- ALL MEMBERS ARE ROUND TUBES
- LONGERONS WITH CENTER HINGE JOINTS
- TELESCOPING DIAGONALS
- NO OFFSET LOADS AT JOINT
- BATTENS CROSS BRACED BY TENSION STRAPS

MAIN HOUSING

TRUSS

ADAPTER

DEPLOYMENT RAILS

LONGERONS

UTILITY TRAY

END VIEW FOLDED   DETAIL OF JOINT

UTILITIES INSTALLATION

Figure 4.11-2.   Concept 6A

4-25

5. DEPLOYABLE VOLUME ENCLOSURES

This section describes several applications of deployable volumes for a
typical Space Station (Figure 5.0-1). The three specific applications are
habitat modules, an orbit transfer vehicle (OTV) hangar, and crew transfer
tunnels.

Figure 5.0-1. Deployable Volume Enclosures

Current designs for Space Station modules typically visualize rigid bodies
which are approximately the same size as the orbiter payload bay. With the
advent of deployable volumes there arises the possiblity of launching much
larger modules without the problems associated with assembly in space. This
section examines these possibilities and demonstrates that in many cases they
are more than just possibilities - they are eminently feasible.

5.1 HABITAT MODULES

5.1.1 Habitat Requirements

The requirements for the design of the habitat module are:

o A life of 10 to 20 years in LEO.

o Compatiblity with the orbiter for transportation to LEO.

o Compatiblity with existing designs and concepts for manned space
stations.

o   Accommodation of crew of up to 8 for 90 days + 90 days emergency.

o   Normal pressurization of 14.7 psi (limit); 8 psi for an emergency.

o   Provision of two separate pressurized compartments.

o   Provision of two routes for ingress/egress.

o   Automatic deployment to maximum extent feasible, EVA assist if
    advantageous.

o   Incorporation of all the equipment normally associated with habitat
    modules, including life support equipment, command control center etc.

o   Provision of two docking systems.

o   Minimum of one airlock.

o   Exterior mounting of equipment such as fuel cells, toxic items etc.

o   Radiation protection of 0.50 gram/cm^2 (1.0 lb/ft^2).

o   Adequate meteoroid protection (discussed subsequently).

5.1.2 Radiation/Meteoroid Shielding Review

The suitability of a potential habitat wall design concept (gratuitously
furnished by Goodyear Aircraft Corp.) for radiation shielding has been eval-
uated (Figure 5.1-1). The basic 2.5-cm-thick design with a foam density of
0.032 gm/cc^3 is adequate for precluding skin damage, but not for protection
of the astronauts' eyes. An additional 0.24 gm/cc^2 needs to be provided by
either increasing the bladder thickness, foam thickness or density, a combin-
ation of the foregoing, or other means. The implication on packaging needs
to be assessed (in subsequent studies).

The associated probabilities of meteoroid puncture of the inner wall using
two different foam densities are shown. These data are based upon the
meteoroid model specified in Reference 6 and the man-made debris model of
Reference 15. The analyses assume an effective stopping power of 15 for
the foam, i.e., the foam is as effective as 15 times the same mass per unit
area of a sheet of aluminum. This information was obtained from documented
tests performed by Goodyear, and is consistent with predictions by Rockwell
researchers.

The probabilities shown indicate that with development of a leak-detection
system and repair capability, the inflatable wall design shown can be suitable
insofar as meteoroid impact is concerned (propagation of the puncture is not
expected to occur).

| ELASTIC RECOVERY CONCEPT* | |

FOR PROJECTED AREA OF 100 m²

0.016 GM/CM³ FOAM (2.5 cm THICK)

- 1% PROBABILITY OF PUNCTURE IN 3 DAYS
- ON AVERAGE, ONE PUNCTURE EVERY 9 MONTHS TO BE REPAIRED

0.032 GM/CM³ FOAM (2.5 cm THICK)

- 1% PROBABILITY OF PUNCTURE IN 27 DAYS
- ON AVERAGE, ONE PUNCTURE IN 7.5 YEARS TO BE REPAIRED

DETAIL WEIGHTS OF EXPANDABLE MATERIALS*	
CONSTRUCTION	(gm/cm²)
• ALUMINUM INNER LAYER	0.002
• ADHESIVE	0.005
• PRESSURE BLADDER	0.080
• ADHESIVE	0.005
• STRUCTURAL LAYER	0.031
• TASLAN INTERLOCKING LAYER AND ADHESIVE	0.024
• POLYURETHANE FOAM	0.080
• ADHESIVE	0.005
• OUTER COVER AND COATING	0.031
TOTAL	0.263

ADDITIONAL MATERIAL REQUIRED TO SATISFY RADIATION REQMT.

*Courtesy of Goodyear Aerospace (for Expandable Airlock Technology Experiment)

Figure 5.1-1. Habitat Radiation/Meteoroid Implications

5.1.3 Habitat Design Approach

A review of the habitat requirements and logistics associated with delivery of habitats to LEO resulted in the following design approach.

o The habitat module should be large as compared to conventional modules to significantly offset the reduced cost and higher reliability of a conventional design.

o For habitats with inflatables, use combination of hard (fixed) structure and inflatables.

o Design to accommodate equipment in its correct locations (on the hard structure) during Shuttle launch to minimize work/rearrangement on orbit.

o Separate the crew quarters from the equipment not in regular use with placement of heavy equipment on hard structure and crew quarters in the deployable structure.

o Divide the crew quarters into large volumes for communal use and into smaller private volumes.

o Build radiators into the exterior of the hard structure.

o Provide capability to repair inflatables from the inside.

o A meteoroid bumper is desirable for inflatables.

o Utilize the crew inside the Habitat Module for relocation of minor
equipment, final stages of deployment such as locking joints and
removal of temporary deployment mechanisms.

5.1.4 Candidate concepts for Habitat Modules

Eight concepts for deployable Habitat Modules were considered (Figure 5.1-2).
Three were selected for further study (Section 5.1.5).

Figure 5.1-2. Candidate Deployable Habitat Module Concepts

Concept 1 expands axially from a central airlock/docking port and two hard
decks on which equipment is mounted. The stowed module occupies most of the
orbiter bay and the deployed volume is minimal. The inflatable sections are
supported by light deployable internal structures.

Concept 2 is a derivative of Concept 1 but has spherical end bulkheads.

Concept 3 has a rigid central floor which acts also as a strongback for
launch. There are two docking ports and an airlock. The two inflatable
sections are shown as approximately 4.5 meters in diameter but can be larger.
They can be subdivided into wardroom, sleeping quarters, etc., as desired.

Concept 4 consists of a nearly "standard" rigid habitat module with an
inflatable torus attached. It has excellent capability for mounting
equipment, good radiator area and a large inflatable volume for crew
quarters. The arrangement for airlocks and docking is the same as for
"standard" rigid habitat modules.

5-4

Concept 5 is a "standard" rigid habitat module with two deployable hard sections. The deployable sections can be sealed either by large internal bags or by sealing around individual joints (or both). The volumes available for equipment and crew quarters are excellent. This concept has the further advantages of all-hard structure, large radiator area, standard docking, and no unusual structures.

Concept 6 consists of Concept 4 with the addition of a hard deployable shell which serves as a meteoroid bumper for the habitat module and as an OTV hanger. The system is deployable and is packaged for a single launch.

Concept 7 is a rigid module with two inflatable sections deployed from it. It is somewhat similar to Concept 4 but the deployed volume is probably not as useful.

Concept 8 is a variation of Concept 7, as shown.

5.1.5 Preferred Concepts

The three preferred concepts are shown in Figure 5.1-3. The drawings are contained in Volume II. These concepts were selected for further investigation for the following reasons:

o Representation of a wide variety of designs

o A good ratio of deployed volume/stowed volume is provided

Figure 5.1-3. Preferred
Habitat Module Concepts

o High growth potential

o Adequate hard structure for mounting equipment

o Safety (redundant volumes available)

o The crew quarters can be subdivided into large and small rooms as
desired

-o No technology development of an unusually difficult nature is required

5.1.5.1 Habitat Concept 3

Concept 3 (Figure 5.1-4) consists essentially of an inflatable shell mounted on
each side of a strongback. The strongback serves as a launch cradle,
(contains trunnions and keel fitting), a mounting platform for equipment, and
as a structural support for the airlocks and docking systems.

- INFLATABLE WITH A
  STRONG BACK
- AUTOMATIC DEPLOYMENT
- VOLUME STOWED   178 M³
- VOLUME DEPLOYED

  LIVING   216
  STOWAGE
    UNPRESSURIZED   16
    PRESSURIZED   42
  AIRLOCKS   8
                      ───
                     282 M³

4M

12.83M

RADIATORS & COVERS
FOR STOWED INFLATABLES

4M DIA

INFLATABLE   STRONGBACK

AIRLOCK

Figure 5.1-4. Habitat Module (Concept 3)

The inflatable shells are shown as 4.5 meters diameter but they can be larger. When stowed for launch, they are contained behind covers which conform to the shape of the orbiter payload bay. The covers are deployed to allow the shells to inflate and are then used as radiators. The deployed module forms two separate sections for safety/redundancy, with the strongback providing a long central floor. Equipment is mounted both inside and outside of the pressurized volumes. The two docking systems conform to standard habitat module practice for design and placement.

5.1.5.2 Habitat Concept 4

This design (Figure 5.1-5) is a combination of an inflatable section and a rigid body. When stowed, the module occupies all of the orbiter payload bay with the exception of space for the docking module and the OMS kit. The module is supported in the payload bay by standard trunnions and a keel fitting and requires no separate cradle.

The rigid body is used mainly for equipment, arranged around a central tunnel which runs the length of the module. The outside diameter of the rigid body is used as a radiator for the whole of the Habitat Module. The inflatable section is in the form of a torus which surrounds one end of the rigid body. The torus provides a large living volume which can be used in many ways. One requirement is probably to divide it into two spaces for safety/redundancy in the event of loss of pressure. It should be noted that there is space inside the rigid body which can be used in an emergency. A docking mechanism is provided at one end of the module while at the other end an airlock with a docking mechanism is provided.


Figure 5.1-5. Habitat Module (Concept 4)

This module can be used with or without a hard meteoroid cover over the inflatable torus. The cover is folded and stowed around the outside of the collapsed torus. When the torus inflates, the cover unfolds and expands along with it. Deployment of the cover is completed when the panels which form its end walls are released and swing into position under the influence of springs.

The shape and size of the torus can be chosen to suit requirements. It can be much larger and it does not have to be a circular cross section. The shape, as drawn, is a large circular room (10 m diameter) with a column in the middle. The column is a portion of the tunnel which can be used to stow equipment for launch. The equipment can be subsequently moved into the torus living space.

5.1.5.3 Habitat Concept 5

When stowed, Concept 5 (Figure 5.1-6) resembles a standard habitat module (i.e., as currently designed for the Space Station) which is roughly the same size and shape as the orbiter payload bay. There are two sections which deploy from opposite sides of the module and form the living volumes. They are of excellent shape and can be subdivided to provide separate sleeping quarters, wardroom, working areas, etc. The whole module divides naturally into two spaces for safety/redundancy. At each end of the module is a large airlock and docking mechanism. Some of the space currently allocated for airlocks can be directed to stowage of items outside of the pressurized volume.


Figure 5.1-6.   Habitat Module (Concept 5)

The structure is metallic, including the deployable sections and the close-out panels. The whole structure is supported in the orbiter by standard trunnions and a keel fitting. Expansion of the deployable sections can be obtained by either internal pressure or by mechanical means such as astronauts or screwjacks. Sealing between the deployable and the fixed sections can be realized either by a large internal pressure-tight bag and by sealing around individual joints. The area of the module available for use as a radiator is unusually large.

The ability to carry pressure-induced loads across the deployable joints is appreciated. These loads may be bending moments in addition to axial loads. EVA-installed, moment-carrying fittings are possibly needed with this concept.

5.2 TUNNELS

No study effort was devoted to tunnels since examination of Goodyear Aerospace Corporation accomplishments indicated ample work has been done relative to this component. The study time was better used in relation to hangars and habitats, for which no readily applicable effort is available.

5.3 OTV HANGAR

5.3.1 OTV Hangar Requirements

There are few really firm requirements for an OTV hangar beyond the obvious; i.e., it must remain in space for the same duration as the Space Station and it is launched using the orbiter.

Previous studies have indicated the infeasibility of pressurizing the hangar. The problems associated with opening/closing such a large pressurized volume are:

- o Sealing the hangar

- o The huge quantities of air lost each time the hangar is opened

- o Or alternatively, the very large power requirements if a pump is installed to recover the air before opening the hangar

The other hangar requirements listed are uncertain. They can be questioned:

- o Does the OTV require protection against meteoroids? Would it be more cost effective to accept a small risk of OTV damage than to build an expensive hangar?

- o If work platforms are required, is it reasonable to build a hangar for that purpose only; or would it be better to design the OTV so that astronauts attach themselves directly to its outside shell, rather than to hangar-mounted work platforms?

However, it was necessary to establish a basis for design studies, hence in spite of the lack of maturity in hangar and Space Station definition the following requirements were tentatively assumed:

o The OTVH size shall be suitable for the servicing/maintenance of an OTV. Assume an OTV size of 4.3 m diameter x 10 m long as a maximum, and work platform widths up to 2 meters.

o The OTVH will be unpressurized.

o The OTVH shall provide for a method of controlling the egress/ingress and stabilization of the OTV.

o Provisions shall be made for the following equipment:

   o Work platforms
   o Lighting
   o Electric power
   o OTV replacement items
   o OTV refueling
   o Minimum life support system (emergency)

o The OTVH shall provide radiation and micrometeoroid protection to the crew, OTV and equipment. (The end of the hangar pointing to earth is not subject to micrometeoroid bombardment and can be left open)

o Life in LEO for 10-20 years

o The OTVH shall be compatible with an orbiter launch

5.3.2 OTV Hangar Design Approach

There are two basic methods of designing the OTV hangar, i.e., inflatable or hard shell. The hard shell is a more conventional approach, and provides a firmer base for work platforms (reaction of astronaut loads). Its major problem is packaging in the orbiter and deploying from it. If the Hangar is to be packaged into a small portion of the orbiter instead of using the whole of the payload bay, the problem of deploying it becomes even more formidable.

While an inflatable hangar is relatively easy to deploy, present designs may not provide adequate stiffness for the work platforms. There are various methods of hardening an inflatable structure such as foaming between walls, use of a skin material which hardens on exposure to radiation, and an erectile shell. In the erectile shell, a film of aluminum is added over the inflatable which is then pressurized to stress the aluminum past its yield stress. After the gas escapes the structure maintains its shape.

Regardless of which structural concept is used, all of the auxiliary structure and equipment are to be built into the assembly and deployed with it. These items are the crew work stations, lighting provisions, OTV ingress/egress provisions, OTV stabilization provisions, crew ingress/egress provisions, OTV refueling, and attachment to space station.

An alternative to automatic deployment of the hangar is erection or, more likely, a hybrid arrangement. The complications of automation must be balanced against the difficulties of EVA erection. If EVA erection is considered, it is better to use a method that requires a minimum of orbiter support.

5.3.3 Meteoroid Impact Analysis

Since one of the purposes of a hangar is to provide protection for the OTV against the impact of micrometeoriods, it is pertinent to examine the potential damage to the OTV if an OTV hangar is not present.

The critical parts of the OTV are the LH$_2$ and LO$_2$ tanks which are contained inside an unpressurized structural shell as shown (Figure 5.3-1). Present designs (ground-based and space-based) utilize a graphite composite faced sandwich construction with a 0.035 gm/cm^3 (2.2 lb/ft^3) aluminum honeycomb core. A rigid polyurethane foam core is expected to be structurally adequate for a space-based OTV design and provides superior meteoroid shielding capability over that of the honeycomb core. The foam core does not have sufficient shear and compression stiffness to stabilize the face sheets against wrinkling during Shuttle launch of a ground-based OTV.

SPACE-BASED DESIGN CONSTRUCTION

Figure 5.3-1. OTV Construction

The Rockwell Space Station studies are pursuing a space-based OTV which will be returned to earth after 16 missions (6 to 18 months). The micrometeoroid analysis for this design indicates there is a 1% probability the space-based OTV tank wall will be punctured in six months, and a 3% probability it will be punctured in an 18-month lifetime. This analysis is regarded as conservative since most of the tank wall is located a significant distance from the outer shell. Furthermore, even if a tank containing LH$_2$ or LO$_2$ is punctured by a micrometeoroid there will not be a catastrophic failure. The tank wall materials (2219-T87 or 2014-T6) are thin gauges and have a "leak before

5-11

failure" characteristic that precludes explosive decompression. More than
100 cycles of pressure are required for a crack 0.04 cm deep by 0.38 cm wide
to propagate to a through-crack.

The additional protection of a hangar wall for the OTV is illustrated in
Figure 5.3-2. This figure also shows the cost implications of a hangar versus
replacement of an OTV. Clearly, the cost of a conventional hangar cannot be
justified on the basis of meteoroid protection alone. Only if the cost of
launching a hangar can be drastically reduced by tight packaging in the
orbiter or by other means, does the project become reasonable (if meteoroid
protection is the only significant requirement).

ADDITION OF HANGAR STRUCTURE
(WITHOUT FOAM)

HANGAR WALL ┌─ 0.050 cm

5 cm

0.15 cm

1 TO 2 m

OTV
OUTER
SHELL

1% PROBABILITY
METEOROID
PARTICLES WILL
GET PAST INNER
FACE OF H.C.
OUTER SHELL
ONCE IN 10 YR

┌─ 0.05 TO 0.10 cm
ALUM. TANK WALL

```
S HANGAR REALLY COST EFFECTIVE IF METEOROID PROTECTION
IS PRIMARY JUSTIFICATION?

ONLY WITH RELIABLE TIGHTLY PACKAGED CONFIGURATION
REQUIRING 3 TO 5 m OF PAYLOAD BAY.
```

| COSTS	($M)
OTV REPLACEMENT*	25
OTV LAUNCH	48
TOTAL	73
HANGAR LAUNCH	48
HANGAR COST	10
TOTAL	58
*SPACE-BASED DESIGN	

Figure 5.3-2. OTV Meteoroid Protection/Hangar Cost

To date the studies of the Space Station have not produced hard requirements
for an OTV hangar. However, recognizing the possibility that requirements may
be developed, the OTV hangar concept development was continued.

5.3.4 Candidate Concepts for OTV Hangar

Seven OTV hangar concepts are presented (Figure 5.3-3). The concepts may be classified into three categories, i.e., deployable Hangars, rigid nondeployable hangars, and deployable/erectable hangars.

The four deployable hangar concepts, i.e., Concepts 1, 2, 3 and 7 are discussed below.

Concept 1 is a rigid shell which packages from a shape which is essentially cylindrical (8.2 m dia.) to a star shape which fits into the orbiter bay. An extendable truss which is used for ingress/egress of the OTV is part of the deployable shell. The stowed hangar occupies all of the orbiter payload bay.

Concept 2 is a rigid shell which consists of four half cylinders stowed in the form of one cylinder inside another. It, too, occupies all of the orbiter payload bay when stowed.

Concept 3 is an inflatable shell which expands from a module which contains the interface for docking to the Space Station, and the mechanism/structure for OTV ingress/egress. There are various methods which may be used to harden or rigidize an inflatable structure which otherwise might be too soft for a working interface. The stowed hangar occupies approximately 1/4 of the orbiter payload bay.


Figure 5.3-3. OTV Hangar Concepts

Concept 7 is similar to Concept 1 except that it has a double fold (i.e., longitudinal as well as lateral) which enables it to occupy only a short length of the orbiter payload bay. (This concept is, subsequently, discussed in greater detail.)

Concept 4 is a rigid nondeployable hangar in the shape of a clam-shell which fits closely around the OTV. The OTV is launched in the orbiter inside the hangar, and exits from the hangar by means of an extending truss. Normal servicing/fueling of the OTV is performed through the aft end of the Space Station which is docked to the OTV. Access to other areas of the OTV is by doors and foot holds strategically located in the shell of the Hangar.

Concept 5 is a deployable/erectable system built out of the orbiter. A deployable section with an interface for the Space Station is raised incrementally by an extendable truss which also rotates about its major axis. There is an EVA astronaut work station in the orbiter bay with storage for a number of rigid panels which are attached manually to build up the hangar as it rotates and raises.

Concept 6 is similar to Concept 5 except that the hangar is constructed from the Space Station instead of from the orbiter. For both Concepts 5 and 6, it is estimated that approximately 1/3 of the orbiter bay is used for stowage.

None of these concepts represents design that Rockwell favors. In an additional study effort superior configurations can be developed. However, to provide further understanding of the design problems to be encountered, three of the foregoing concepts are discussed in further detail in the next section. (The drawings are provided in Volume II).

5.3.4.1 Hangar Concept 1

This concept (Figure 5.3-4) is a hard shell structure which folds laterally for stowage. When folded it occupies all of the orbiter payload bay. The operational sequence is:

o Use the RMS to remove the hangar from the orbiter

o Attach to the Space Station using the docking interface

o Unfold the panels of the main structure using the actuators built into the hangar

o The working platforms on the inside wall of the hangar may be deployed either by springs or by actuators

The extendable/retractable astromast is used for ingress/egress of the OTV, for which purpose it is equipped with a docking mechanism to interface with the OTV. Lighting power outlets and similar items may be built into the wall of the hangar.

- HARD STRUCTURE, NO INFLATABLES
- AUTOMATIC DEPLOYMENT
- OCCUPIES ALL OF THE PAYLOAD BAY

Figure 5.3-4. OTV Hangar (Concept 1)

Although the basic deployment is automatic, it is quite possible that EVA astronauts could profitably be used to lock the wall panels together for increased structural integrity, to install equipment, spares, etc.

5.3.4.2 Hangar Concept 6

This concept (Figure 5.3-5) uses EVA astronauts to erect the hangar walls around a deployable base. When stowed in the orbiter, approximately 6.0 meters of the payload bay is used. The stowed package consists of a deployable base or hub and cradle. The deployable base contains a docking interface for the Space Station, an astromast with a docking interface at its free end, deployable "umbrella type" ribs, and a hub structure. The cradle contains 40 separate panels which form the main structure of the hangar, a docking mechanism to interface with the astromast, a mechanism to dispense the panels as required during the hangar erection, and work stations/foot restraints, etc., suitable for EVA astronauts.

The deployment sequence is as follows:

o Remove the two units from the orbiter using the RMS (the two units are coupled together by the astromast and temporary fasteners)

o Attach the hub end of the hangar to the Space Station.

o Automatically deploy the umbrella ribs.

Figure 5.3-5. OTV Hangar (Concept 6)

-o EVA astronauts begin to remove panels from the cradle and form the hangar structure. The panels attach to the umbrella ribs to form the end wall of the hangar. The wall panels attach to the end wall and to each other.

o The cradle rotates on the astromast and the astromast advances as required to enable the EVA astronauts to attach successive panels

o The cradle is removed and returned to the orbiter (alternatively it may remain with the Space Station and be used for logistics stowage).

There are many methods which may be used for joining the panels together such as spring loaded "click-in" joints, hand-held power tools for tightening joints, over-center locks, or gang latches.

5.3.4.3   Hangar Concept 7

This design (Figure 5.3-6) is a development of Concept 1. The difference is the incorporation of a double-fold system (instead of a single fold) to reduce the space occupied in the orbiter payload bay. In this version, the stowed length is reduced from 14.4 meters to 5.6 meters with a significant cost saving. The installation procedure is:

o Use the RMS to remove the stowed package from the orbiter

o Attach the hangar to the space station using the docking interface

o Deploy the first fold in the same manner as described for Concept 1

o Deploy the second fold as shown in Figure 5.3-6

Figure 5.3-6. OTV Hangar (Concept 7)

The second fold is a series of telescoping sections of the main hangar wall.
Extension of the telescoping sections can be accomplished by a series of stem
actuators at each panel to provide a pushing action, or by the use of the
astromast (with a suitable attachment) to draw out the telescoping sections.

It is recognized that the double folding of such a large volume poses
formidable problems, and that much investigation remains to be done before
such a system could be rated as reasonably feasible.

5.4 MAJOR DESIGN ISSUES

The major design issues that have surfaced during this study applicable to
habitats and OTV hangars are listed below. The issue of OTV hangar
justification is dependent on what probability of no puncture is desired, and
the relative costs of OTV replacement versus the cost of a hangar.

Habitats

o Means for installation of equipment in inflatable structures

o Capability and frequency of repair of inflatable inner wall due to
micrometeoroid puncture

o   Rigidity of unpressurized inflatable structures

o   Inflatable materials suitability in space environment for 10 to
    20 years and compatibility with crew (non-flammability, non-toxic)

o   Provision of radiation shielding for crew protection

o   For hard metallic shells, the capability to sustain pressure-
    induced loads across deployable joints

OTV Hangars

o   Requirements favoring the need for an OTV hangar have not been
    developed in Rockwell Space Station studies

o   Justification for the hangar as a meteoroid bumper is dependent
    on the extent of design conservatism desired by NASA.

o   Cost of OTV possible replacement vs. the cost of hangar develop-
    ment and launch

o   Rigidity of inflatable OTV hangars relative to crew EVA imposed
    loads

5.5   POTENTIAL TECHNOLOGY DEVELOPMENT NEEDS

The potential new technology development needs that have surfaced during the
course of this study are shown below. Rockwell is aware, through much of the
design information gratuitously furnished by Goodyear Aerospace Corporation,
that some of these items have been addressed by Goodyear to various stages
of completion but to different requirements (in general, for smaller volumes,
reduced pressures, shorter lifetimes). The time devoted to this activity
did not permit a screening of the applicability and status of these needs,
but this should be done in future studies.

o   Habitats Utilizing Inflatables

    - Assurance of no serious propagation of meteoroid
      puncture hole size

    - Repair of pressure containing wall

    - Micrometeoroid puncture resistance

    - Material suitability to crew and 10 to 20 years exposure
      in space environment

    - Maintainence of structural rigidity despite loss of
      pressure

o   Habitats Using Metallic Structures

    - None applicable at this time

o   OTV Hangars

    - For inflatables—maintenance of structural rigidity
    compatible with crew-induced foot loads, equipment
    attachment, space platform inertia loads

    - On-orbit foam in-place techniques

5.6   CONCLUSIONS

The following major conclusions pertinent to the use of deployable volumes are
evident from the foregoing discussions:

o   Application to habitats appears attractive—large useful
    volumes achievable.

o   Metallic structures (can be sealed) provide ample meteoroid
    radiation protection and equipment mounting surfaces, but
    are constrained by pressure loads/packaging requirements.

o   Metallic structures may require subsequent EVA for moment-
    carrying capability to withstand pressure.

o   Inflatables alone are not sufficient—hard structure required
    for mounting of consoles, orbiter and space station integra-
    tion, heat rejection.

o   Inflatables in conjunction with rigid core module provide
    variety of feasible large volume designs, provided:

    - Materials are suitable to crew safety/space environment

    - Foam micrometeoroid stopping power is comparable to existing
    data

    - Repair of puncture or use of meteoroid bumper is feasible

    - Additional 0.24 grms/cc^2 for protection to crewman eyes
    is provided

o   Hangar requirements are ill-defined—OTV meteoroid protection
    alone is not sufficient justification.

o   Most attractive OTV hangar concept appears to be metallic
    deployable/erectable or inflatable with foam core (provided
    stiffness is adequate).

6. REFERENCES

1. Satellite Power Systems (SPS), Final Report (Exhibit E), LSST Systems Analysis and Integration Task for SPS Flight Test Article, Rockwell Report, SSD 80-0102, dated August, 1980.

2. LSST System Analysis and Integration Task for an Advanced Science and Application Space Platform (Contract NAS8-33592), Final Report, McDonnell Douglas, MDC G8533, dated July, 1980.

3. Geostationary Platform Systems Concepts Definition Follow-On Study, Final Report, Vol. IIA-Technical, Task 11, LSST Special Emphasis, General Dynamics, GDC-GPP-79-010 (IIA), dated September, 1980.

4. Space Platform Design Requirements Summary, NASA/MSFC report, dated December 31, 1980.

5. Geostationary Platform Systems, Concepts Definition Study, Final Report, General Dynamics, GDC-GPP-79-006 (I) (Contract NAS9-33527), June, 1980.

6. Meteoroid Environment Model-Near Earth to Lunar Surface, NASA SP-8013, March, 1969.

7. Review of Physical Processes in Hypervelocity Impact and Penetration, Rand Report RM-3529-PR, July, 1963.

8. Development and Application of Space Deployable Box Truss Structures, Martin Marietta MMA Report No. 78-52411-01, December, 1978.

9. Neutral Buoyancy Test Results of a Deployable Space Beam, AIAA-81-0437.

10. Efficient Structures For Geosynchronous Spacecraft Solar Arrays, Phase I, II, and III Final Report, Astro Research Corp., Sept. 14, 1981.

11. Erectable Concepts for Large Space Systems Technology, Vought Technical Report, 2-51400/OR-LSS-02, dated March 3, 1980.

12. Technology for Large Space Systems (NAS SP-7046).

13. "Nuclear and Space Radiation Effects on Materials", NASA SP-8053, June, 1970.

14. Space Construction Systems Analysis, Part 2, Final Report, Platform Definition, NAS9-15718, Rockwell International, April, 1980.

15. An Analysis of the Space Debris Problem - Present and Future, SSD82-0011, January 29, 1982, Dr. J. W. Haffner.