

ABSTRACT

Dual-Spool Turbine Facility Design Overview

Paul Giel
QSS Group, Inc.

and

Pete Pachlhofer
NASA Glenn Research Center

*Presented at the AIAA TETWOG Meeting
May 1-2, 2003
Cincinnati, OH*

The next generation of aircraft engines, both commercial and military, will attempt to capitalize on the benefits of close-coupled, vaneless, counter-rotating turbine systems. Experience has shown that significant risks and challenges are present with close-coupled systems in terms of efficiency and durability. The UEET program needs to demonstrate aerodynamic loading and efficiency goals for close-coupled, reduced-stage HP/LP turbine systems as a Level 1 Milestone for FY05. No research facility exists in the U.S. to provide risk reduction for successful development of close-coupled, high and low pressure turbine systems for the next generations of engines.

To meet these objectives, the design, construction, and integrated systems testing of a Dual-Spool Turbine Facility (DSTF) facility has been initiated at the NASA Glenn Research Center. The facility will be a warm (~1000°F), continuous flow facility for overall aerodynamic performance and detailed flow field measurement acquisition. The facility will have state-of-the-art instrumentation to capture flow physics details. Accurate and reliable speed control will be achieved by utilizing the existing Variable Frequency Drive System. Utilization of this and other existing GRC centralized utilities will reduce the overall construction costs. The design allows for future installation of a turbine inlet combustor profile simulator.

This presentation details the objectives of the facility and the concepts used in specifying its capabilities. Some preliminary design results will be presented along with a discussion of plans and schedules.



Ultra-Efficient Engine Technology Program

AIAA TETWOG



Dual-Spool Turbine Facility Design Overview

Paul Giel & Pete Pachlhofer
QSS Group, NASA Glenn
Inc. Research Center

Giel: (216) 977-1340

Paul.W.Giel@grc.nasa.gov

Pachlhofer: (216) 433-5705

Peter.M.Pachlhofer@nasa.gov

May 1-2, 2003

Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

Objective

Ultra-Efficient Engine Technology Program

AIAA TETWOG

- **Next generation of engines, both commercial and military, will attempt to capitalize on the benefits of close-coupled, vaneless, counter-rotating turbine systems**
- **Experience has shown significant risks and challenges with close-coupled systems in terms of efficiency and durability**
- **Needed to demonstrate the UEET aerodynamic loading & efficiency goals for close-coupled, reduced-stage HP/LP turbine system (Level I Milestone for FY05)**
- **No research facility exists in the USA to provide risk reduction for successful development of closely-coupled, high and low pressure turbine systems for next generation of engines**

Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

Objective

Ultra-Efficient Engine Technology Program

AIAA TETWOG

- Design, construction, and integrated systems testing of a Dual Spool Turbine Facility (DSTF) at the Glenn Research Center (Engine Research Building No. 23, Cell W2)
- Warm ($\sim 1000^{\circ}\text{F}$) continuous-flow type facility for overall aero performance & detailed flow field measurement capability
- State-of-the-art instrumentation for flow physics details
- Accurate speed control utilizing existing Variable Frequency Drive System (Building No. 23)
- Utilization of existing GRC centralized utilities reduces overall construction costs
- Configuration allows for future installation of a combustor profile simulator



Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

Objective

Ultra-Efficient Engine Technology Program

AIAA TETWOG

Dual Spool Turbine Facility



- Research facility to provide validation data
- High pressure ratio capability (~twice the current capability at industry)
- Capacity to accommodate entire HP/LP turbine groups

Validation facility for CFD tools & models relevant to industry

Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

Objective

Ultra-Efficient Engine Technology Program

AIAA TETWOG

Customer Support

Interfaced with Industry to Establish Facility Capabilities

Partner

Position

- **GEAE**
Supportive, since DSTF will have capabilities beyond their Cell A7 facility; Transmitted engine data for facility sizing.
- **P&W**
Supportive; offered military test articles; Transmitted engine data for facility sizing.
- **Honeywell**
Supportive, although concerned about suitability at small size end of product range; Transmitted engine data for facility sizing.
- **AADC**
Supportive; identified hardware for testing.
- **AFRL**
Supportive; complementary to TRF.

Establishing DSTF Facility Capabilities

Facility sized to meet...

- Industrial partner's needs
DSTF capabilities "must exceed those of existing facility"
- UEET goals (55:1 OPR engine)
UEET engine configuration data obtained from
Airbreathing Systems Analysis Office (ASAO)
- Research objectives:
 - Detailed data
 - Accuracy
 - Spatial resolution

DSTF Facility Sizing Methodology

Given engine cruise and take-off parameters

(Diameters, power, speed, temperatures, pressures, flow)...

Match engine parameters...

- Reynolds number
- Mach number
- power coefficient

Subject to facility sizing constraints on...

- Inlet and exhaust air mass flows
- Power absorption
- Rotational speed
- Temperatures
- Pressures
- Cost

Sizing variables...



- geometric scale
- inlet temperature

Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

DSTF Torque vs. Speed Curves

Ultra-Efficient Engine Technology Program

AIAA TETWOG





Symbol	Configuration	T _{in} '	T _{exit}	N _{HPT}	N _{LPT}
●	Mid Commercial, scale=0.8734	1200	455	10016	2540
○	Mid Commercial, scale=0.6551	1200	458	13327	3384
■	UEET 300 PAX, Current Tech.	1100	454	5252	1474
□	UEET 300 PAX, UEET Tech.	1200	457	6328	2987
▲	UEET 50 PAX, Current Tech.	1460	699	11550	6216
△	UEET 50 PAX, UEET Tech.	1460	664	14031	5339
+	Original 50% Scale Mil. Config.	800	500	15000	8000
▼	HSCT, Current Tech., 50% scale	800	500	7388	5004
▽	HSCT, UEET Tech., 75% scale	800	485	5727	3407
▲	SBJ, Current Technology	1000	553	6339	3959
△	SBJ, UEET Technology	1000	524	8024	4448
▲	Small Commercial, scale=1.0	1460	787	21791	14143
△	Small Commercial, scale=2.0	1460	787	10896	7072
◆	Mil. Fighter, Current Tech.	1200	709	8741	4856

Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

DSTF Mass Flow Requirements

Ultra-Efficient Engine Technology Program

AIAA TETWOG




Symbol	Configuration	T'_{in}	T_{exit}	N_{HPT}	N_{LPT}
●	Mid Commercial, scale=0.8734	1200	455	10016	-2540
○	Mid Commercial, scale=0.6551	1200	458	13327	-3384
■	UEET 300 PAX, Current Tech.	1100	454	5252	1474
□	UEET 300 PAX, UEET Tech.	1200	457	6328	2987
▲	UEET 50 PAX, Current Tech.	1460	699	11550	6216
△	UEET 50 PAX, UEET Tech.	1460	664	14031	5339
+	Original 50% Scale Mil. Config.	800	500	15000	-8000
▼	HSCT, Current Tech., 50% scale	800	500	7388	5004
▽	HSCT, UEET Tech., 75% scale	800	485	5727	3407
▶	SBJ, Current Technology	1000	553	6339	3959
▷	SBJ, UEET Technology	1000	524	8024	4448
◀	Small Commercial, scale=1.0	1460	787	21791	14143
◁	Small Commercial, scale=2.0	1460	787	10896	7072
◆	Mil. Fighter, Current Tech.	1200	709	8741	4856

Highly Loaded Turbomachinery, GRC Altitude Exhaust Capability and Dual-Spool Turbine Facility DSTF Requirements

Ultra-Efficient Engine Technology Program

AIAA TETWOG



Highly Loaded Turbomachinery, Dual-Spool Turbine Facility


Planned Use of GRC Central Services for DSTF

Ultra-Efficient Engine Technology Program

AIAA TETWOG

Test Article	Variable Frequency*	150 psig Comb. Air	Altitude Exhaust
Mid. Commercial, 87% Scale	B -	C	C
Mid. Commercial, 66% Scale	B	C	C
Military Fighter, Current Tech.	B	C	C
Small Commercial, Scale=2.0	C - B	C	C
UEET 50 PAX, Curent Tech.	C - B	C	C
UEET 50 PAX, UEET Tech.	B	C	C
UEET 300 PAX, Current Tech.		C	C
UEET 300 PAX, UEET Tech.		C	C
SBJ, Current Tech.	B	C	B
SBJ, UEET Tech.	C - B	C	C
HSCT, Current Tech.	B	B	B
HSCT, UEET Tech.	B	B	B

*most
likely*



*less
likely*

B: DSTF requires 40% to 80% of GRC Capability

C: DSTF requires less than 40% of GRC Capability


Converters Available		
FY04 - FY05	FY06 - FY07	FY08 - FY09
10	11	12 *

Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

Technical Results

Ultra-Efficient Engine Technology Program

AIAA TETWOG



DSTF Free Body Diagram


Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

Ultra-Efficient Engine Technology Program


Technical Results

AIAA TETWOG

- Preliminary Design Report completed (Jan 01).
- Detailed Design contract initiated Aug 01 (ASE/Belcan).
- 30% design of Dual Spool Turbine Facility was completed, reviewed.
- Separate PDR was held (Apr 02).
- PDR team included industry, NASA, and DoD personnel.
- PDR recommendation resulted in gov't redirection of inlet plenum/bearing support design, facility instrumentation design.
- 60% final design completed Dec 02.
- Detailed design will continue to completion.
- IST hardware will continue to be defined.
- 90% Design due end of May 02.





Most recent PDR concept for DSTF



Capability for Proposed Test Articles

**Aero Performance Design
For the DSTF**



Inlet Manifold & Transition Piece

Flow Path Definition

CFD Analysis Performed to Define Flow Path
(Ensure uniform Airflow Velocity, Pressure, and
Temperature Profiles Into the Inlet of the High
Pressure Turbine)

Exhaust Manifold & Transition Piece

Flow Path Definition

CFD Analysis Performed to Define Flow Path
(Ensure That There are no Backpressure
Effects from the Exhaust Manifold)



Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

Technical Results


Ultra-Efficient Engine Technology Program

AIAA TETWOG

Mechanical Design of Inlet & Exhaust Manifolds for the DSTF



Support Structure Designed
for Fine Adjustments to
Ensure Proper Alignments



Facility Inlet Hardware Mounted on
Translating Cart to Simplify Test
Hardware Assembly Procedures

Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

Technical Results

Ultra-Efficient Engine Technology Program



AIAA TETWOG

HPT/LPT Bearing Cartridge Design Details

Pressurized
Isolation to Prevent
Oil Ingestion into
Test Article

Axial Thrust
Balance Pistons

Secondary Flow
Supply Lines




Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

Ultra-Efficient Engine Technology Program


AIAA TETWOG

DSTF Facility Piping Design



Bldg. 23, Cell W2 Sectional View

Exhaust Piping (Shown in Green)
Exits Through the Roof of Cell W2,
Runs Above SW Wing, Ties Into
Existing Altitude Exhaust Header



Bldg. 23, Cell W2 Plan View

150 PSIG Combustion Air Piping
(Shown in Blue) Splits and Two
Feeds Supply the DSTF Inlet
Manifold

Plans for Next Year & Beyond

AIAA TETWOG

Event	Duration	2002				2003				2004				2005				
		Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	
Final Design	9/01 - 7/03																	
60% Review Meeting	10/22/2002				☆													
Motor Procurement Package	4/03 - 6/03																	
Heater Procurement Package	4/03 - 6/03																	
90% Review Meeting	6/03							☆										
100% Submittals	7/03							☆										
Constr. Procurement	7/03-11/03																	
CBD Announcement	7/03 - 8/03																	
Solicitation	8/03 - 10/03																	
Award Contract	11/03								☆									
CoF Construction	12/03-4/05																	
Need Heater	7/15/2004									☆								
Need Motors	7/15/2004									☆								
Collector Delivery (best)	8/15/2004										☆							
Bearing Cart. Deliv. (best)	8/15/2004										☆							
Integrated Syst. Test	4/05-11/05																	
Subsystems Tests	4/05 - 8/05																	
Rotating Hardware	8/05 - ...																	

Highly Loaded Turbomachinery, Dual-Spool Turbine Facility

Conclusion

Ultra-Efficient Engine Technology Program

AIAA TETWOG

- **No Technical or Other Barriers
Preventing Completion of Final Design**
- **Industry Partners Involved in Design
(Helped Solve Technical Issues)**
- **Industry Partner to Furnish Rotating
Hardware for Use During Integrated
Systems Testing (IST)**
- **Phased Research Test Article SOW
Development underway.**