

National Aeronautics and Space Administration



# Bruce K. Tiller

Ares First Stage  
Deputy Manager

September 16, 2009



# Ares First Stage Element Status



# Ares I First Stage Overview




## ◆ Shuttle-Derived Five-Segment Solid Rocket Booster

- Increased performance
- Extensibility to Ares V


## ◆ Metal and Composite Materials

## ◆ Specs

- Mass: 732 mT (1,614 K lbm)
- Max thrust (vac): 16 MN (3.6 M lbf)
- Burn duration: 126 sec
- Height: 53 m (174 ft)
- Diameter: 3.7 m (12 ft)



Thrust trace comparison: Shuttle versus Ares I





# Ares I First Stage



**C-Spring isolators**

**Tumble motors (from Shuttle)**



**Asbestos-free insulation/liner.  
Thickness changes will be modified  
during Development Motor testing**



**Same aft skirt and thrust  
vector control as Shuttle**



**New 150-ft diameter  
Kevlar parachutes**



**Modern state-of-the-art electronics**


**PBAN propellant optimized  
for Ares application**

**Same cases and joints as Shuttle.  
O-ring materials change eliminated heaters**

**Booster deceleration motors (from Shuttle)**




# Ares First Stage Upgrades




## Propellant


- Formulation was modified
- Burn rate lowered to meet Ares I requirements
- New grain design
- 8-year propellant life certification



Propellant chamfers on aft and center segments




Modified height and thickness of inhibitor



Joint O-ring upgrades  
Added segment

## New Nozzle



Modified insulation and liner formulations to eliminate Chrysotile fibers

Lay-up optimized to provide additional thermal protection



# The Avionics System



## New State-of-the-art Electronics

- ◆ **3-channel single fault avionics system**
- ◆ **Six Line Replaceable Units (LRUs)**
  - BCPDU – Booster Controller and Power Distribution
  - DARU – Data Acquisition and Recording Unit
  - ISC – Ignition Separation Controller
  - RCU – Recovery Control Unit
  - HPUC – Hydraulic Power Unit Controller
  - ACU – Actuator Control Unit
- ◆ **All use the same chassis**
- ◆ **The connector cover plates will each be unique**
- ◆ **The LRUs all meet the 45-pound human factor requirement**
- ◆ **Subassemblies are removable and testable**




Built Up Data Acquisition System (DAS) Module  
Used within all Units



Built Up Initiator Firing Circuit (IFC) Module  
PWB - ISC/RCU



ISC/RCU Interface Module (IRIM) – ISC/RCU



Built Up Excitation Output Module (EOM)  
PWB - DARU

**Avionics Box Mock-up  
LRU 1<sup>st</sup> Generation Engineering Boards**



# First Stage Thrust Oscillation




## Status:

- ◆ June Program Review was completed with decision to baseline and implement Dual Plane (DP) Isolation
- ◆ Technical Solutions exist for multiple options
- ◆ Designs are in testing

## Four basic ways to attack problem:

- ◆ Reduce forcing function
- ◆ Detune system response away from forcing function frequency
- ◆ Actively create an opposing forcing function
- ◆ Passively absorb forcing function

◆ Mitigation Options    ◆ Baseline Design





# First Stage Testing Accomplishments





**Parachute Drop Testing**  
Yuma Proving Ground, AZ



**DM-1 Igniter Test**  
Promontory, UT



**Ares I-X Forward Skirt Extension Separation Test**  
Promontory, UT



**Thrust Oscillation Component Testing**



# DM-1 Test Conducted on Sept 10, 2009

Promontory, UT





# Ares I-X First Stage Accomplishments



**Ares I-X Motor En Route to KSC**  
Corinne, UT



**Ares I-X Forward Assembly Transfer to VAB**  
Kennedy Space Center, FL



**Ares I-X**  
Kennedy Space Center, FL



# First Stage Progress to Date



- ◆ **Ares I first stage design is robust and progressing rapidly**
  - Avionics
  - Major structures
  - Motor
  - Deceleration system
- ◆ **Major test program milestones achieved:**
  - Recovery system testing
    - 7 of 14 parachute drop tests completed to date (Drogue, Main, Cluster)
  - Avionics systems have begun testing
  - First of 4 development motors (DM-1) has been fired
    - Preliminary data looks good and well within expectations
    - DM-2 manufacture underway
- ◆ **Ares I-X hardware delivered and assembled at KSC**
  - Completed all Hardware Acceptance Reviews
  - Motor segments were completed and shipped to KSC in March 2009
  - Launch scheduled for no earlier than October 31, 2009



[www.nasa.gov/ares](http://www.nasa.gov/ares)

