

A detailed illustration of a futuristic space mission. A large, dark, multi-segmented structure, possibly a space station or a large satellite, is positioned in the upper left. A long, lattice-like boom extends from it towards the center. At the end of the boom is a complex assembly of spherical and rectangular components, with a bright light source emitting a powerful beam of light. In the lower left, a smaller, capsule-like spacecraft is shown, also emitting a bright light. The background is a vast, orange-hued sky or planetary surface, suggesting a Mars-like environment. The overall scene conveys a sense of advanced technology and exploration.

NASA Tech Briefs

Transferring Technology to
American Industry
and Government

July 1989
Volume 13
Number 7

**Mankind's Next
"Giant Leap"**

July 1989
Volume 13
Number 7



New! From OMEGA

CN1200 Series



**Universal
Digital
Controller**

From \$250

Model HH110



**Digital
Thermometer**

\$85

Model CN310



**Temperature
Controller**

\$199

Model CL-307



**Thermocouple
Calibrator**

\$495

CN350 Series



**1/16 DIN
Temperature
Controllers**

From \$99

CN9000 Series



**Miniature
Temperature
Controller**

From \$199

Thermocouple



**Wire
Teflon® Coated**

Priced by the Spool

Model HH-82



**Handheld
Digital
Thermometer**

\$169

TX90 Series



**Miniature
Transmitters**

From \$125

DP10 Series



**Digital Panel
Meter**

From \$425


Model 115



**Digital
Thermometer**

\$155

5-Dot Labels



**Non-
Reversible
Temp. Labels**

\$19/10-pack

Model DP462



**Temperature
Indicator**

\$328

OS60 Series



**Fixed Infrared
Temperature
Sensor**

From \$545


88000 Series



**Surface
Probes**

From \$110

SA1 Series



**Self-Adhesive
Thermocouples**

\$60/5-pack

CN380 Series



**PID Auto-Tune
Controllers**

From \$299



**All These Products
and Many More!**

For FREE Handbook Call (203) 359-RUSH.

Widest Selection of Temperature Measurement and Control Products Available

OMEGA Engineering provides customers the world over with the technology and innovation they need to master their temperature measurement and control requirements. OMEGA Handbooks and Encyclopedias have long been the trusted source for quality sensors and instrumentation for Industry, Research, and Education.

Our knowledgeable sales representatives and product engineers support OMEGA's unyielding commitment to complete customer satisfaction. Wherever you are, ordering from OMEGA is easy

with toll-free sales and technical assistance during business hours coast-to-coast in the U.S. and Canada, 24-hour FAX ordering, and a full staff of international specialists.

For your custom design requirements, let our applications engineering staff show you how we can custom design the right product to your exact specifications.

**Call Sales Toll-Free at
1-800-TC-OMEGA
IN CT (203) 359-1660**

Name _____
Address _____
City _____ State _____ Zip _____

Please send me the following FREE OMEGA Handbooks:

- ☐ Temperature ☐ pH
☐ Pressure ☐ Data Acquisition
☐ Flow ☐ Electric Heaters

Mail To

OMEGA ENGINEERING
One Omega Drive, P.O. Box 4047
Stamford, CT 06907
(203) 359-1660



**New! Lower prices and expanded product line.
Ask your local Ioline dealer for details.**

LP4000 with
Multi-pen Changer

Here's what to look for when you want great value

Ioline plotters are designed to give you more flexibility and features for less cost than any other machine of their kind.

For example, our plotters draw not only on A through E sizes of media, but also plot on hundreds of in-between sizes from 1.5" x 1.5" up to 37" wide roll stock. This saves you time and money by allowing you to make "check plots" on small, low-cost paper before committing to full-size media for final work.

It's easy also to set paper size, pen speed, micro-calibration, plot rotation—everything exactly as you want—by just tapping a few keys on the plotter's intelligent keypad. Plus, up to 3 sets of personalized defaults can be saved in its non-volatile memory.

They're fast, too. Our high-

performance LP4000™ draws at speeds selectable up to 20 inches per second (ips) axially with .001" resolution. For less demanding applications, our economical LP3700™ plots up to 10 ips axially with .0025" resolution.

Another feature is compatibility. Ioline plotters emulate both HP-GL and DM/PL plotter languages so they work with a host of software like AutoCAD, VersaCAD, and CADKEY, to name a few.

Furthermore, our Multi-pen Changer™ option holds up to 20

pens and, with our hyper-BUFFER™ option, you can dramatically increase plotting throughput with intelligent vector sorting and compression buffering of up to 1MB of plot data.

Now here's the clincher: Our top-gun, servo-driven LP4000 costs just \$4,995.* And there are other models priced even lower!

Why wait? Call us now at **206-821-2140**. Or, circle our reader service number and we'll gladly send you our brochure.

Remember, getting your money's worth—that's what Ioline plotters are all about.

IOLINE™
LARGE-FORMAT PEN PLOTTERS

IOLINE CORPORATION 12020 - 113th AVE. NE KIRKLAND, WA 98034 (206) 821-2140 TELEX 4949856 IC UI FAX (206) 823-8898
LP4000, LP3700, Multi-pen Changer, and hyperBUFFER are trademarks of Ioline Corporation. AutoCAD is a registered trademark of Autodesk, Inc.
VersaCAD is a registered trademark of T&W Systems. CADKEY is a registered trademark of MicroControl Systems, Inc. *Suggested U.S. List price.

Circle Reader Action No. 351



**Technology so
advanced it will
help answer some
big questions.**

THORNEL® Advanced Composites

Proprietary materials development. Our mesophase pitch fibers, based on unique technology patented worldwide, are now available in more forms than ever, including individual prepreg plies of one mil thickness. These materials and materials systems demonstrate properties essential for solving many of your most demanding problems when it comes to aero, outer and deep space applications.

New performance frontiers. So far, this new technology has shown stiffness characteristics far superior to current materials. It also imparts unsurpassed dimensional stability allowing you to tailor coefficients of expansion to 0 or negative if required. Plus, with thermal conductivity 3 to 5 times that of copper, it can solve many of the thermal management problems encountered in aerospace designs.

The attainable unknown. While current applications include laser hardening, low observable technology and use in space radiators, space panels and heat sinks, the potential of this material can take you far beyond today's design limits. With our ongoing research and the evolution of design the mysteries of space will, in time, be revealed.

We can help. Ask us questions. Our research people can guide you to materials solutions for your toughest design problems. You can reach us at Amoco Performance Products, Customer Service, 1-800-222-2448.

We do more than create the technology. We share the vision.



THE ALL AMERICAN SOLUTION



Amoco Performance Products

Circle Reader Action No. 336

Inframetrics infrared imaging: to see, to quantify, to understand.




ThermaGRAM® image of an automotive brake rotor.

Whether you're looking for pressure leaks in an aircraft fuselage or fluid ingress in the flaps; electrical system hot spots or excessive bearing friction; delamination in composite structures or shorts in a multilayer printed circuit board... the infrared diagnostic technology of Inframetrics systems will quickly give you the answers you need.

Our concentration on *practical infrared imaging and temperature measurement* — the delivery of useful results, under real-world conditions, at reasonable prices — has made us a leader in infrared imaging radiometers, and producers of the widest variety of thermal imaging instruments in the world.

A complete system, cart-mounted, with optional VCR and Polaroid hard copy system, goes anywhere.



commercially available today. Combine these capabilities with the most versatile image-processing system in the market; ThermaGRAM® performs histogram analysis, time vs. temperature studies, real time image analysis, and countless other functions.

Just consider the possibilities.

Inframetrics systems adapt to a wide variety of applications, including R&D, nondestructive testing, electronic diagnosis, quality control, facilities maintenance and medicine.



Model 445 high resolution thermal imager shows delamination in a composite panel. Ideal for qualitative analysis, nondestructive testing, security systems, more.

Inframetrics systems open the door to another engineering perspective on your problems. To learn more, tell us your application.

inframetrics The Infrared Specialists

16 Esquire Rd., No. Billerica MA 01862-2598 Offices worldwide
TEL 508-670-5555 • FAX 508-667-2702 • TWX 710-326-0659

Circle Reader Action No. 370

ThermaGRAM is a registered trademark of Thermoteknix Systems Ltd., Cambridge, England.

THE NEW GENERATION IN MULTICHANNEL WAVEFORM ACQUISITION

Instant turn-on.

That's the new easy-to-use, powerful and flexible System 500 from Nicolet. Better from the word go.


Better software turns start-up time from months to minutes, enabling you to gather data instantly from two or 200 channels. While greatly simplifying data analysis, display, and report generation.

Its two different 12-bit resolution digitizer boards produce maximum sampling rates of 1 and 10 MS/S. The System 500 can perform lightning-fast calculations without waiting for lengthy data transfers to a host computer. And the IEEE-488.2 command set makes writing your own custom software easier than ever.

So be a giant step ahead in waveform acquisition in no time. Send now for details.

It takes time to get the new Nicolet System 500 up and running.

About two minutes.



Nicolet Test Instruments Division

25-2 Verona Road, Madison, WI 53711, 608/273-5008 or 800/356-3090

Circle Reader Action No. 696

Nicolet
INSTRUMENTS OF DISCOVERY

SPECIAL FEATURE

Project Pathfinder 16

TECHNICAL SECTION

✓	New Product Ideas	12
U	NASA TU Services	14
▶	Electronic Components and Circuits	20
⚡	Electronic Systems	32
⚙	Physical Sciences	44
⬜	Materials	56
💻	Computer Programs	62
⚙	Mechanics	64
⚙	Machinery	72
🏗	Fabrication Technology	76
Σ	Mathematics and Information Sciences	85
◀	Subject Index	94




Photo courtesy NASA

NASA is developing super-tough astronaut suits for Space Station extravehicular activity and for lunar and Mars surface exploration. The above photo shows underwater testing of the Ames Center's new X-5 space suit, which is made of aluminum and stainless steel with no soft fabric parts. See page 16.

DEPARTMENTS

On The Cover: A nuclear-electric-propulsion cargo vehicle approaches Mars in this artist's conception. NASA contemplates using electrically-driven vehicles to support a manned Mars mission early next century. Turn to page 16.

New Literature ... 92

New on the Market 90

Advertisers' Index 98

Lewis Center researchers have simulated the unsteady flow surrounding advanced turboprop airfoil sections. See page 66.

New This Month

For your convenience, we have combined the Subscription/Technical Support Package Form and the Reader Action Card into a single, easy-to-use form (page 81).



Photo courtesy NASA

This document was prepared under the sponsorship of the National Aeronautics and Space Administration. Neither Associated Business Publications Co., Ltd. nor anyone acting on behalf of Associated Business Publications Co., Ltd. nor the United States Government nor any person acting on behalf of the United States Government assumes any liability resulting from the use of the information contained in this document, or warrants that such use will be free from privately owned rights. The U.S. Government does not endorse any commercial product, process, or activity identified in this publication.

Permissions: Authorization to photocopy items for internal or personal use, or the internal or personal use of specific clients, is granted by Associated Business Publications, provided that the flat fee of \$3.00 per copy is paid directly to the Copyright Clearance Center (21 Congress St., Salem, MA 01970). For those organizations that have been granted a photocopy license by CCC, a separate system of payment has been arranged. The fee code for users of the Transactional Reporting Service is: ISSN 0145-319X/89 \$3.00 + .00.

NASA Tech Briefs, ISSN 0145-319X, USPS 750-070, copyright © 1989 in U.S., is published monthly by Associated Business Publications Co., Ltd. 41 E. 42nd St., New York, NY 10017-5391. The copyrighted information does not include the individual Tech Briefs which are supplied by NASA. Editorial, sales, production and circulation offices at 41 E. 42nd Street, New York, NY 10017-5391. Subscriptions for non-qualified subscribers in the U.S., Panama Canal Zone, and Puerto Rico, \$75.00 for 1 year; \$125.00 for 2 years; \$200 for 3 years. Single copies \$10.00. Remit by check, draft, postal or express orders. Other remittances at sender's risk. Address all communications for subscriptions or circulation to NASA Tech Briefs, 41 E. 42nd Street, New York, NY 10017-5391. Second-class postage paid at New York, NY and additional mailing offices.

POSTMASTER: please send address changes to NASA Tech Briefs, 41 E. 42nd Street, Suite 921, New York, NY 10017-5391.

CLOSER SHEET AND STRIP TOLERANCES. JUST ONE FORM INCO ALLOYS INTERNATIONAL TECHNOLOGY TAKES.

High-performance alloys are increasingly used as sheet and strip, for applications requiring ever-higher quality. Users of heat- and corrosion-resistant alloys want economical sheet/strip sizes, weld-free coils, improved surface quality, more precise section shape, and closer tolerances. Inco Alloys International has taken steps to meet these demands.

A new hot-strip reversing mill, unsurpassed among producers of high-performance alloys, combines with a recently acquired cold-rolling facility to offer you high-quality sheet and strip in thicknesses from .005" to .250" and widths from .750" to 48". In addition to close dimensional tolerances, you get a superior surface finish and weld-free lengths in coil weights that can exceed 20,000 lb. And every production step is state-of-the-art, to give you the best product available.

This total in-house production permits strict quality control and traceability of your order from melting to shipment. And with the world's widest selection of high-performance alloys to choose from, you'll find exactly the properties you need. Corrosion resistance, high-temperature strength, superior dimensional stability — whatever it takes to get the job done.

Inco Alloys International also provides the performance and cost-efficiency you demand in a range of other forms such as rod, bar, plate, section, pipe, tubing, wire, and companion welding products. All available through a worldwide sales network including distribution centers located near you.

To find out more, write for a free copy of "High-Quality Superalloy Sheet and Strip." Inco Alloys International, Inc., Huntington, West Virginia 25720. Or, for a quicker reply, FAX us at (304) 526-5441.



**INCO ALLOYS
INTERNATIONAL**

Distributors in the USA: Castle Metals,
Metal Goods, Tubesales, and Williams & Co.
In Canada: Atlas Alloys and Drummond
McCall Inc.

Data Acquisition and Controls.



For the last forty years Wyle Laboratories has developed data acquisition and control systems for hundreds of applications.

A Wyle real-time data acquisition and control system will provide easier and quicker test setup. It will completely automate test sequencing, control, and monitoring as well as provide for data recording, analysis, and report generation. Wyle can provide requirements definition, system design, development, and installation along with software and integration functions to ensure a working system that fits your specific needs. Our complete documentation and training courses

allow you to use the system productively and maintain it effectively.

A Wyle system will greatly reduce the time and cost required for the testing cycle in the same manner a CAD/CAM system improves the product design cycle. Now testing, the longest and most important phase of the product development timetable, can be accomplished more rapidly, reliably, and with less cost than ever before.

For more information about Wyle data acquisition and control systems, call Ray Rec in Hampton, VA at (804) 865-0000. Our staff of specialists will be waiting to meet you.

WYLE
LABORATORIES

SCIENTIFIC SERVICES
& SYSTEMS
GROUP

3200 Magruder Boulevard, Hampton, VA 23666, (804) 865-0000



The Test and Engineering Company.

Circle Reader Action No. 522

New for PROPULSION ENGINEERS

“A modular pressure scanning system with these powerful new features!”

❑ **Ultra High Speed Data Acquisition Rates** with parallel processing! Its 68020 microprocessor controls up to 64 plug-in input units for 400,000 meas./sec. Throughput rates up to 20,000 E.U./sec are possible while simultaneously acquiring raw data.

❑ **Guaranteed Accuracy** of .05% FS with on-line calibration. It's user programmable and maximum accuracy is insured by an internal quartz secondary standard.

❑ **Any Analog Or Digital Input**; pressure, flow, temperature, etc., (in any media) can be measured with dedicated input units. Each has its own microprocessor and special acquisition hardware. All data packets are time correlated in common formats.

❑ **Easy Installation And Expansion** with remote processors, local slaves, and input unit racks. The 8400 System's mainframe has a VME bus, IEEE interface with DMA rates of 500,000 BPS. Software drivers are available for HP, DEC, and IBM computers.



For a
Demonstration
or Full Color
Brochure...



CALL
1-800-678-SCAN

PRESSURE SYSTEMS

34 Research Drive
Hampton, VA 23666
(804) 865-1243
Fax 804-766-2644 Telex 901406




*The
8400 System*

AURORA BEARINGS and ROD ENDS— FOR BETTER PRODUCT PERFORMANCE!


- Precision-ground balls to ensure close radial clearances.
- Swaged steel on steel construction for greater wear life
- TFE liners optional
- Many alloy steels available

Let us supply your complete linkages for easy assembly.

STANDARD ROD ENDS



SPECIALLY DESIGNED LINKAGES



SIZES
1/8" to 2"

Write for FREE
current catalog



MADE IN U.S.A.!

AURORA
TM

AURORA BEARING COMPANY

970 South Lake Street

Aurora, Illinois 60506 · Ph. 312 859-2030

TELEX: 280079 AUR BRGS/FAX 312-859-0971

NASA Tech Briefs

National Aeronautics and
Space Administration

ABP **BPA**

NASA Tech Briefs:

Published by **Associated Business Publications**
Editor-in-Chief/Publisher **Bill Schnirring**
Associate Publisher **Frank Nothaft**
Associate Publisher **Robin J. DuCharme**
Managing Editor **R. J. Laer**
Senior Editor **Joseph T. Pramberger**
Technical Advisor **Dr. Robert E. Waterman**
Production Manager **Rita Nothaft**
Traffic Manager **James E. Cobb**
Circulation Director **Anita Weissman**
Advertising Coordination Manager **Erving Dockery, Jr.**
Telecommunications Specialist **Evelyn Mars**
Reader Service Manager **Sylvia Ruiz**

Technical Staff:

Briefs provided to National Aeronautics and Space Administration by
International Computers & Telecommunications, Inc., NY, NY with
assistance from **Logical Technical Services, NY, NY**

Technical/Managing Editor **Ted Selinsky**
Art Director **Ernest Gillespie**
Administrator **Elizabeth Texeira**
Chief Copy Editor **Lorne Bullen**
Staff Writers/Editors **Dr. James Boyd, Dr. Larry Grunberger,
Dr. Theron Cole, Jordan Randjelovich,
George Watson, Oden Browne**

Graphics **Luis Martinez, Vernald Gillman,
Charles Sammartano**

Editorial & Production **Bill Little, Ivonne Valdes, Frank Ponce**

NASA:

NASA Tech Briefs are provided by the National Aeronautics and Space
Administration, Technology Utilization Division, Washington, DC:

Administrator **Dr. James C. Fletcher**
Assistant Administrator for Commercial Programs **James T. Rose**
Deputy Assistant Administrator (Programs) **Henry J. Clarks**
Deputy Director TU Division (Publications Manager) **Leonard A. Ault**
Manager, Technology Utilization Office, NASA Scientific and
Technology Information Facility **Walter M. Heiland**

Associated Business Publications

41 East 42nd Street, Suite 921, New York, NY 10017-5391

(212) 490-3999 FAX (212) 986-7864

President **Bill Schnirring**
Executive Vice President **Frank Nothaft**
Vice President **Domenic A. Mucchetti**
Vice President Marketing **Mark J. Seitman**
Operations Manager **Rita Nothaft**
Controller **Felecia Lahey**

Advertising:

New York Office: (212) 490-3999 FAX (212) 986-7864

National Sales Manager **James G. McGarry**
Regional Sales Manager (South) **Robin DuCharme**

at (214) 871-2130.

Regional Sales Manager (Mid-Atlantic) **Michelle Larsen**

Account Executive **Debby Crane** at (201) 967-9838

Account Executives (Midwest) **Jack Cartwright** or **Paul Leshner**

at (312) 501-4140

Account Executives (Eastern MA, NH, ME, RI) **Lee Arpin** or **Paul Gillespie**

at (617) 899-5613; **Bill Doucette** at (617) 278-7792

Account Executive (Western MA, CT, VT) **George Watts** or **David Haggett**

at (413) 253-9881

Account Executive (No. Calif., WA, OR) **Janice Richey King**

at (415) 656-3613

Account Executives (So. Calif., AZ, NV, NM) for Area Codes 818/213/805


Thomas Stillman or **Melanie Binkley**

and for Area Codes 619/714—**Leslie Alley** at (213) 372-2744


NTBM-Research Center

Account Supervisor **Lourdes Del Valle**

Codonics brings you the first affordable graphics terminal without the jaggies



The competition's 1024 x 780 pixel display



Codonics' true-line™ display



The Codonics 4096. Finally, a graphics terminal with Tektronix 4010/4014 emulation, DEC VT320/220/100 alphanumerics and no jaggies.

A few features:

- ▶ 16,000 x 12,000 effective resolution, utilizing Codonics' true-line™ beam geometry hardware
- ▶ True 4096 x 4096 sub-pixel addressability
- ▶ DEC VT320/220/100 emulation with high definition fonts
- ▶ Flawless Tektronix 4010/4014 emulation
- ▶ True pan and zoom with display list cache
- ▶ 73 Hz non-interlaced flickerless display
- ▶ Built in hardcopy support utilizing Codonics' true-line™ technology
- ▶ Mouse included as a standard feature

Our team of sales engineers are awaiting your call. 1-800-444-1198

See us at DEXPO South
Booth #3417



CODONICS
We bring the Future into Focus

Computer Graphics Division
18001 Englewood Drive
Middleburg Hts., Ohio 44130
Telephone (216) 243-1198
Telex 650-292-8429

Codonics and true-line are trademarks of Cleveland Codonics, Inc.
DEC VT320/220/100 are trademarks of Digital Equipment Corporation.
Tektronix is a tradename of Tektronix, Inc.

Circle Reader Action No. 440

New Product Ideas

New Product Ideas are just a few of the many innovations described in this issue of *NASA Tech Briefs* and having promising commercial applications. Each is discussed further on the referenced page in the appropriate

section in this issue. If you are interested in developing a product from these or other NASA innovations, you can receive further technical information by requesting the TSP referenced at the end of the full-

length article or by writing the Technology Utilization Office of the sponsoring NASA center (see page 14). NASA's patent-licensing program to encourage commercial development is described on page 14.

Carbon/Carbon Panels Cooled by Heat Pipes

A new cooling structure considered for hypersonic aircraft combines high-temperature heat-pipe and carbon/carbon tech-

nologies. With new coatings that are being developed, maximum operating temperatures will reach 3,000 °F (1,649 °C). (See page 64).

Heat-Flux Sensor for Hot Engine Cylinders

A heat-flux sensor includes a buried wire thermocouple and a thin-film surface thermocouple, both made of platinum and platinum with 13 percent rhodium. The sensor is intended for use in a ceramic-insulated, low-heat-rejection diesel engine at temperatures of about 1,000 K. (See page 48).

Making a Precisely Level Floor

A floor-pouring procedure, mainly for laboratories and special installations, yields a large surface that is level, smooth, and hard. The method has been used to fabricate a 1,200-ft² (111-m²) floor that varies locally in elevation less than 0.015 in. in 16 horizontal in. (0.038 cm in 0.41 horizontal m). (See page 78).

Circularity-Measuring System

A shape gauge and an associated computer constitute a system that measures the deviations of large cylinders from roundness. The system can be used to measure the straightness, roundness, or complicated shapes of such large geometrical objects as the surfaces of aircraft, the hulls of ships, and buildings. (See page 83).

Field-Sequential Color Converter

An electronic conversion circuit enables the display of signals from a field-sequential color-television camera on a color video camera. The field-sequential technique of encoding color video signals reduces the size, weight, and power consumption of a video camera by requiring only one image sensor instead of the usual three. (See page 24).

Whistle Gauge Measures Flow and Temperature

A simple, rugged gauge is used to measure the speed of flow and the temperature of steam or other gas flowing through pipes of arbitrary diameter. The gauge is a specially designed, instrumented whistle that generates intense sound for use in the measurements. (See page 65).

From Silos to Space Stations

We developed air blast and soil pressure time histories for the Air Force's Nuclear Missile Silo Hardening Program. We're testing structural materials for the NASP, components and systems for MX, SICBM, Titan IV, and the Space Station. From Stealth to the 21st Century.

We provide unique, engineering and test capabilities: shakers that generate more than 45,000 force-lbs, 200 g's continuously. 750 g centrifuges. 20,000 g's pyroshock.

Acoustic levels exceeding 170 dB. EMI/EMC, nuclear, FMEA, modal/finite element analysis.

NTS -- single components or completely integrated test programs.



NTS
National
Technical
Systems

Call National Technical Systems.
In the West (714) 879-6110
In the East (508) 263-2933
Or write NTS,
1536 E. Valencia Dr., Fullerton, CA 92631
Or 533 Main St., Acton, MA 01720

Climb Aboard The Most Awesome Combat Aircraft in the World.
Be there...

IN THE COCKPIT

The Video Library
of Today's Airpower

Spectacular
Air Combat
Action!




Attack Aircraft in Action!
Carrier Launched Strikes!
Soviet Aircraft Up Close!
High Flying Spy Planes!
...And Much More!



F/A-18 HORNET

BONUS!
Includes Actual
Footage of Jan. 4, 1989
Shootdown of Libyan
MiG-23's.



©1989 MBI

fly the Air Force's F-15 Eagle and F-16 Falcon on air superiority missions. In **Fly Low, Hit Hard** see ground attack action in Vietnam with the nimble A-4 Skyhawk and the most feared ground attack aircraft in the world like the Thunderbolt II and the battle-proven Israeli Kfir. And in **Target Tank**, witness combat helicopter action on the modern battlefield.

Six Action-Packed Videos

You'll receive six exciting videos, filled with authentic, breathtaking action. Go on a mission aboard the finest reconnaissance aircraft built, the incredible SR-71 Blackbird in **Spies in the Skies**. Fly with dedicated spy planes like the ones used over Cuba and Vietnam. In **Red Star** see close-ups of the new Soviet MiG-29. See the Famous Hind and Halo attack helicopters in remarkable footage from Nicaragua and Afghanistan. Fly carrier launched air strikes against North Vietnam in **Flat Tops**, and search for Soviet submarines in the Hawkeye.

In **Eagles in the Sky**, fire Phoenix missiles from the Navy's F-14 Tomcat, and

Attractively Priced, Convenient Monthly Installments

IN THE COCKPIT is available exclusively from Easton Press Video. Each set of six videos-60 minutes each- comes in a handsome library case and is priced at just \$149.75[†] payable in convenient monthly installments. To order, simply return the attached coupon or call the Toll-Free number. If you are not totally satisfied, return your set within 15 days for a full refund. Order today to avoid disappointment!

[†] plus 4.75 shipping/handling per set.

CALL TOLL FREE 1-800-367-4534

Easton Press Video
47 Richards Avenue
Norwalk, Conn. 06857

Satisfaction
Guaranteed

For Fastest Service Call Toll-Free: 1-800-367-4534

Yes! Please send me the **IN THE COCKPIT** video library. I understand only VHS format is available.

Name _____ PLEASE PRINT CLEARLY

Address _____

City/State/Zip _____

Signature _____ (All orders subject to acceptance)

Charge each of 6 equal monthly installments of \$25.75* to my credit card:

☐ VISA ☐ MasterCard ☐ American Express ☐ Diners Club

Credit Card No. _____ Exp Date _____

☐ I prefer not to use a credit card and will pay by check. Enclosed is my deposit of \$50.00*. I will pay the balance of \$104.50* in three monthly installments of \$34.83* each.

*Conn. residents add 8%; TN residents add 7% sales tax. Allow 2 to 4 weeks for shipment. 172



HOW YOU CAN BENEFIT FROM NASA'S TECHNOLOGY UTILIZATION SERVICES

If you're a regular reader of TECH BRIEFS, then you're already making use of one of the low- and no-cost services provided by NASA's Technology Utilization (TU) Network. But a TECH BRIEFS subscription represents only a fraction of the technical information and applications/engineering services offered by the TU Network as a whole. In fact, when all of the components of NASA's Technology Utilization Network are considered, TECH BRIEFS represents the proverbial tip of the iceberg.

We've outlined below NASA's TU Network—named the participants, described their services, and listed the individuals you can contact for more information relating to your specific needs. We encourage you to make use of the information, access, and applications services offered by NASA's Technology Utilization Network.

How You Can Utilize NASA's Industrial Applications Centers—A nationwide network offering a broad range of technical services, including computerized access to over 100 million documents worldwide.

You can contact NASA's network of Industrial Applications Centers (IACs) for assistance in solving a specific technical problem or meeting your information needs. The "user friendly" IACs are staffed by technology transfer experts who provide computerized information retrieval from one of the world's largest banks of technical data. Nearly 500 computerized data bases, ranging from NASA's own data base to Chemical Abstracts and INSPEC, are accessible through the ten IACs located throughout the nation. The IACs also offer technical consultation services and/or linkage with other experts in the field. You can obtain more information about these services by calling or writing the nearest IAC. User fees are charged for IAC information services.

Aerospace Research Applications Center (ARAC)

Indianapolis Center for Advanced Research
611 N. Capitol Avenue
Indianapolis, IN 46204
Dr. F. Timothy Janis, Director
(317) 262-5036

Rural Enterprises, Inc. Central Industrial Applications Center/NASA (CIAC)

P.O. Box 1335
Durant, OK 74702
Steve R. Hardy, President
(405) 924-5094

North Carolina Science and Technology Research Center (NC/STRC)

Post Office Box 12235

Research Triangle Park, NC 27709

H. Lynn Reese, Director
(919) 549-0671

NASA Industrial Applications

Ctr. 823 William Pitt Union
University of Pittsburgh
Pittsburgh, PA 15260
Dr. Paul A. McWilliams, Exec. Director
(412) 648-7000

NASA/Southern Technology Applications Center

Box 24
Progress Ctr., One Progress Blvd.
Alachua, FL 32615
J. Ronald Thornton, Director
(904) 462-3913
(800) 354-4832 (FL only)
(800) 225-0308 (toll-free US)

NASA/UK Technology Applications Program

University of Kentucky
109 Kinthead Hall
Lexington, KY 40506-0057
William R. Strong, Director
(606) 257-6322

NERAC, Inc.

One Technology Drive
Tolland, CT 06084
Dr. Daniel U. Wilde, President
(203) 872-7000

Technology Application Center (TAC)

University of New Mexico
Albuquerque, NM 87131
Dr. Stanley A. Morain, Director
(505) 277-3622

NASA Industrial Applications Center (WESRAC)

University of Southern California
Research Annex
3716 South Hope Street, Room 200

Los Angeles, CA 90007-4344
Radford G. King, Exec. Director
(213) 743-8988
(800) 642-2872 (CA only)
(800) 872-7477 (toll-free US)

NASA/SU Industrial Applications Center

Southern University Department of Computer Science
P.O. Box 9737
Baton Rouge, LA 70813-9737
Dr. John Hubbell, Director
(504) 771-6272

If you represent a public sector organization with a particular need, you can contact NASA's Application Team for technology matching and problem solving assistance. Staffed by professional engineers from a variety of disciplines, the Application Team works with public sector organizations to identify and solve critical problems with existing NASA technology. **Technology Application Team, Research Triangle Institute, P.O. Box 12194, Research Triangle Park, NC 27709. Doris Rouse, Director, (919) 541-6980**

How You Can Access Technology Transfer Services At NASA Field Centers:

Technology Utilization Officers & Patent Counsels—Each NASA Field Center has a Technology Utilization Officer (TUO) and a Patent Counsel to facilitate technology transfer between NASA and the private sector.

If you need further information about new technologies presented in NASA Tech Briefs, request the Technical Support Package (TSP). If a TSP is not available, you can contact the Technology Utilization Officer at the NASA Field Center that sponsored the research. He can arrange for assistance in applying the technology by putting you in touch with the people who developed it. If you want information about the patent status of a technology or are interested in licensing a NASA invention, contact the Patent Counsel at the NASA Field Center that sponsored the research. Refer to the NASA reference number at the end of the Tech Brief.

Ames Research Ctr.

Technology Utilization

Officer: Laurance Milov

Mail Code 223-3

Moffett Field, CA 94035

(415) 694-4044

Patent Counsel:

Darrell G. Brekke

Mail Code 200-11

Moffett Field, CA 94035

(415) 694-5104

Lewis Research Center

Technology Utilization

Officer: Harvey

Schwartz (acting)

Mail Stop 7-3

21000 Brookpark Road

Cleveland, OH 44135

(216) 433-5567

Patent Counsel:

Gene E. Shook

Mail Code 301-6

21000 Brookpark Road

Cleveland, OH 44135

(216) 433-5753

John C. Stennis

Space Center

Technology Utilization

Officer: Robert M.

Barlow

Code HA-00, Bldg. 1103

Stennis Space Center,

MS 39529

(601) 688-1929

John F. Kennedy

Space Center

Technology Utilization

Officer: Thomas M.

Hammond

Mail Stop PT-PMO-A

Kennedy Space

Center, FL 32899

(407) 867-3017

Patent Counsel:

James O. Harrell

Mail Code PT-PAT

Kennedy Space

Center, FL 32899

(407) 867-2544

Langley Research Ctr.

Technology Utilization

Officer: John Samos

Mail Stop 139A

Hampton, VA 23665

(804) 864-2484

Patent Counsel:

George F. Helfrich

Mail Code 279

Hampton, VA 23665

(804) 864-3523

Goddard Space Flight

Center

Technology Utilization

Officer: Donald S.

Friedman

Mail Code 702.1

Greenbelt, MD 20771

(301) 286-6242

Patent Counsel:

R. Dennis Marchant

Mail Code 204

Greenbelt, MD 20771

(301) 286-7351

Jet Propulsion Lab.

NASA Resident Office

Technology Utilization

Officer: Gordon S.

Chapman

Mail Stop 180-801

4800 Oak Grove Drive

Pasadena, CA 91109

(818) 354-4849

Patent Counsel:

Paul F. McCaul

Mail Code 180-801

4800 Oak Grove Drive

Pasadena, CA 91109

(818) 354-2734

Technology Utilization

Mgr. for JPL: Dr. Norman L. Chaffin

Mail Stop 156-211

4800 Oak Grove Drive

Pasadena, CA 91109

(818) 354-2240

George C. Marshall

Space Flight Center

Technology Utilization

Officer: Ismail Akbay

Code AT01

Marshall Space Flight

Center,

AL 35812

(205) 544-2223

FAX (205) 544-3151

Patent Counsel:

Bill Sheehan

Mail Code CC01

Marshall Space Flight

Center,

AL 35812

(205) 544-0021

Lyndon B. Johnson

Space Center

Technology Utilization

Officer: Dean C. Glenn

Mail Code IC-4

Houston, TX 77058

(713) 483-3809

Patent Counsel:

Edward K. Fein

Mail Code AL3

Houston, TX 77058

(713) 483-4871

NASA Headquarters

Technology Utilization

Officer: Leonard A. Ault

Code CU

Washington, DC 20546

(202) 453-8377

Assistant General

Counsel for Patent

Matters: Robert F.

Kempf, Code GP

Washington, DC 20546

(202) 453-2424

A Shortcut To Software: COSMIC®—For software developed with NASA funding, contact COSMIC, NASA's Computer Software Management and Information Center. New and updated programs are announced in the Computer Programs section. COSMIC publishes an annual software catalog. For more information call or write: **COSMIC® 382** East Broad Street, Athens, GA 30602 *John A. Gibson, Dir.,* (404) 542-3265

If You Have a Question . . . NASA Scientific & Technical Information Facility can answer questions about NASA's Technology Utilization Network and its services and documents. The STI staff supplies documents and provides referrals. Call, write or use the feedback card in this issue to contact: **NASA Scientific and Technical Information Facility**, Technology Utilization Office, P.O. Box 8757, Baltimore, MD 21240-0757. *Walter M. Heiland, Manager,* (301) 859-5300, Ext. 242, 243

Without Compromise . . . The Modgraph GX-2000

High Resolution Graphics Terminal



A Quality High-Resolution Image . . .

The GX-2000 is the latest in Modgraph's series of high-resolution graphics terminals. In a contemporary low profile enclosure, the GX-2000 offers our field proven TEK 4010/4014 and DEC VT220/100 emulation in a reliable low cost graphics terminal backed by a full one year warranty.

Additional standard features provided in the GX-2000 include windowing capabilities and DEC SIXEL graphics. Standard hardcopy interfaces are dot matrix, inkjet, and laser.

An extra large 15" flat screen produces a crisp 1024 × 780 resolution image with TRUE ZOOM capability standard. Optional features include: memory for three additional fully independent graphics screens, TEK 4631 hardcopy interface, composite video output, mouse, data tablet, or trackball.




Trademarks:

Tektronix, Inc. - 4010/4014/4631

Digital Equipment Corp. - VT100, VT220,
SIXEL

149 Middlesex Turnpike, Burlington, MA 01803
(617) 229-4800, outside MA (800) 327-9962

Image courtesy of
Computervision Corp.



Over the next decade, Project Pathfinder will develop the enabling technologies for bold new space missions.

Illustration courtesy NASA

Project Pathfinder

NASA Plans For Man's Next "Giant Leap"

As the nation commemorates the historic Apollo moon landing, NASA is preparing for the next "giant leap" into the solar system. In partnership with U.S. industry and universities, the Space Agency has embarked on a major research project called "Pathfinder" that will develop the enabling technologies for piloted mis-

sions to Mars, lunar outposts, and the advanced robotic exploration of the solar system.

Project Pathfinder will provide a base for wise decisions on future missions and goals, said program manager John Mankins. "We'll address the critical technology issues and assess the costs involved before any final deci-

sions are made regarding mission designs," he explained. "That will save a lot of time and money in the long run."

Pathfinder complements the ongoing Civil Space Technology Initiative (CSTI), which focuses on technologies needed for operations in low Earth orbit. Through pathfinder, NASA's Office of Aeronautics and Space Technology

will develop capabilities in the areas of surface exploration, space transfer systems, in-space operations, and human factors.

Surface Exploration

One objective of the Surface Exploration Program is to develop a robotic roving vehicle that would explore the Martian terrain as a precursor to manned missions. Rovers could support construction of a moon base as well.

Under a contract with NASA's Jet Propulsion Laboratory, Martin Marietta is studying designs for both wheeled and walking rovers. One promising concept is the "walking beam," a collapsible T-beam structure designed for easy storage on a lander spacecraft. As envisioned, the vehicle will travel at about 300 feet per hour, its telescoping legs able to step up five feet to avoid obstacles. Onboard computers will detect boulders, craters, and other hazards and send the rover instructions to avoid them. Along the way, the rover will use its scientific instruments and robotic arms to test soil and rock samples, the most interesting to be returned to Earth via small rockets.

The vehicle's route will be preplanned using information captured by the Mars Observer spacecraft. Slated for launch in 1992, the craft will orbit Mars, mapping the planet in detail and gathering data on its atmosphere, magnetic field, and soil composition.

The Mars Rover/Sample Return study will guide development of such key technologies as surface mobility, onboard autonomy, and power generation. Pathfinder will integrate the autonomous rover research performed by Carnegie Mellon University's Robotics Institute, and will build upon the Department of Energy's modular radioisotope thermoelectric generator (RTGs) program. Modular RTGs are viewed as the most likely power source for robotic rovers—if more efficient thermoelectric conversion materials can be produced.

In concert with the rover project, NASA will develop methods for acquiring, analyzing, and preserving surface samples. This will require imaging and ranging devices to pinpoint sample location; semi-autonomous machines to pick up and/or drill samples; onboard instruments to analyze the sample's chemical and physical properties in order to determine its scientific worth; and storage systems resistant to extreme temperatures, radiation, and vibration for the long journey back to Earth.

Space Transfer

Pathfinder's Transfer Vehicle Program will provide the means for transporting robots and humans to and from planets, and for transfer between different Earth orbits. One of NASA's

main goals is to minimize the propellant mass needed to reach orbit, land on a planet, and return to Earth, which will reduce launch costs while providing more space for scientific payloads. NASA hopes to accomplish this by developing highly efficient chemical and electric propulsion systems, and by employing the fuel-saving technique of aerobraking, in which the atmospheres of Earth or other solar system bodies are used to slow a spacecraft in order to achieve the necessary velocity for orbiting the body.

NASA's Lewis Research Center will lead the propulsion work. One objective is to build liquid oxygen/hydrogen engines that are fault-tolerant and serviceable in space. Research will focus on high-heat combustors, high-pressure turbomachinery, and integrated diagnostic sensors and controls.

For electric propulsion systems, Lewis will develop advanced magnetoplasmadynamic (MPD) and ion thrusters. NASA wants to apply electric propulsion to cargo vehicles supporting a manned Mars mission. Studies have shown that high-performance electric propulsion with a specific impulse over 4000 sec at multi-megawatt power levels could significantly reduce the amount of onboard propellant a cargo vehicle would need while still providing acceptable transit time performance. Key technical issues to be resolved include MPD cathode longevity, the ability to create self-induced magnetic fields at megawatt levels, and the availability of high-fidelity ground test facilities.

In-Space Operations

Both piloted and robotic missions to Mars would use small craft to shuttle to and from the planet's surface. Because round-trip-light time delays in deep space communications will preclude real-time Earth-based control of these vehicles, NASA must develop automated rendezvous and docking techniques. This will require advanced sensors for long- and short-range tracking and relative navigation from several hundred kilometers down to the contact point of docking. A prototype laser docking sensor being built for a 1991 flight experiment shows promise for ranges from zero to more than five kilometers. Space Agency researchers will work to improve the range of laser-based sensors while reducing power, weight, and volume requirements, and will explore other candidate sensors, including millimeter-wave radar and robotic video image recognition systems.

Advanced sensors also will be needed for in-space robotic assembly and construction of fuel depots, repair "garages," and other orbiting structures that will support future solar system

missions. Under the Langley Center's direction, robot end effectors and holding fixtures will be created for precision welding, bonding, and mechanical joining of parts in space. NASA additionally will develop transporters, space cranes, and other methods for telerobotically manipulating and positioning the parts to be joined, and will also evaluate methodologies for in-space construction of generic spacecraft parts, such as aerobrakes and pressurized modules, that can be applied to many different missions.

Assembling and constructing structures in space will limit dependence on Earth-to-orbit launch vehicles, as will the development of surface pilot plants to process extraterrestrial resources. Such facilities would dramatically reduce the amount of material launch vehicles would need to cart into space. For example, lunar rocks and soil contain an abundance of oxygen, metals, and glasses that could be processed into life support supplies, fuels, construction materials, and shielding for general use in space as well as on the lunar surface. This might include resupply of orbiting space stations, outfitting solar system missions originating from the moon, and supporting a lunar settlement. In coming years, NASA will demonstrate telerobotic methods for collecting, handling, and sorting lunar materials, and will validate various material processing technologies, including a process for creating fiberglass and bricks from lunar soil through heating and compaction.


Humans In Space

Pathfinder's Humans In Space thrust will provide the engineering systems to enable effective performance and good health during long-duration missions. One element is directed towards technologies that will permit humans to operate for extended periods outside the protection of their pressurized habitats. It focuses on developing lightweight yet rugged extravehicular activity (EVA) suits with portable life support systems. NASA is currently

The "walking beam" would move nimbly over Martian terrain, collecting soil and rock samples for eventual analysis on Earth.



Three Things You Shouldn't Have To Share At The Office



In the workplace you would never think of sharing your mug or chair. So why are you running down the hall to find out if there is a terminal available for your mainframe graphics applications? With TGRAF software and your desktop computer there's no reason to ever share a terminal; you can now have a powerful graphics terminal on your desk, inexpensively.

TGRAF accurately duplicates a Tektronix graphics terminal without sacrificing terminal functionality. Now mainframe graphics power is available for your PC, PS/2, Macintosh II, or workstation in RS-232 or networked computer environments, for only a fraction of what a terminal would cost.

TGRAF's comprehensive Tektronix terminal emulation and Grafpoint's superior customer support, puts the terminal sharing blues behind you forever. Call Grafpoint for the name of your local distributor and order a no-risk 30-day evaluation copy.

Current TGRAF users call us for information on how to upgrade to our latest product - TGRAF-4200



GRAFPOINT

1485 Saratoga Avenue

San Jose, CA 95129

1-800-426-2230

In California 408-446-1919

Grafpoint and TGRAF are trademarks of Grafpoint. PC and PS/2 are trademarks of International Business Machines Corporation. Tektronix is a trademark of Tektronix, Inc. Macintosh is a trademark of Apple Computer, Inc.



Illustration courtesy NASA

evaluating two prototype EVA suits developed by the Ames Research Center and Johnson Space Center. Ames' version is made of aluminum and stainless steel with no soft parts that could be damaged by atomic oxygen or by rocket propellants spilled into space, while the Johnson Center suit features both hard and soft elements and stresses wearer comfort. Both models eliminate the existing requirement that astronauts prebreathe pure oxygen to disperse nitrogen from body tissues before beginning EVA, and therefore would operate at much higher pressures than current Space Shuttle EVA suits. A review team will select one suit or the other, or possibly a new hybrid design that combines elements of both, for further development in Pathfinder.

Another part of the Humans In Space effort involves developing technologies to accommodate human physiological requirements and adaptive changes during long-term confinement, exposure to unnatural gravity and dangerous ionizing radiation, and unaccustomed risk and stress. Research into human capabilities and limitations for physical and cognitive work will be conducted; in addition, vital technologies such as artificial gravity systems and radiation shields will be explored.

A third aspect of the program deals with techniques for air revitalization, water reclamation, and waste treatment. These will be integrated in a physical-chemical closed-loop life support system that will substantially reduce the mass of consumables and,

High-energy aerobraking would reduce fuel consumption and allow for larger payloads on future solar system exploration missions.

hence, resupply costs for long-duration missions. A concurrent effort will construct a bioregenerative life support system which will produce food, potable water, and a breathable atmosphere from metabolic and other wastes. Photosynthesis will be used to generate food, with resultant production of oxygen and water and removal of carbon dioxide.


Spinoff Benefits

Pathfinder technologies will find broad use outside of NASA, both on Earth and in space. Planetary rover technologies such as autonomy and mobility may be applied to toxic waste disposal and firefighting, for example, while in-space assembly and construction methods will be of great benefit for future commercial communications satellites.

Moreover, space transfer technologies such as advanced chemical propulsion and aerobraking, although specialized for space applications, will provide further engineering expertise in materials and structures, as well as in design of high-speed aircraft. And Humans-In-Space studies of physical-chemical and bioregenerative life support systems will provide insight on how ecological systems work, and perhaps why they fail.

Across a wide spectrum of disciplines, Pathfinder will "push American technology forward," said Mankins, "just as the Apollo program did in the 1960s." □

DATATAPE's New Generation of Digital Cassette Tape Recorders meets the ANSI-ID-1, MIL-STD-2179 and IRIG 106-XX Recording Formats




DCTR-A120 (Airborne)

Selected by Control Data Corporation for the United States Air Force ATARS (Advanced Tactical Air Reconnaissance System), to record tactical IR and EO Sensor Imagery.

Data Rate Range Record..... 10-120 Mbit/s
Variable with External Clock
Data Rate Range Reproduce..... Any 4 Rates
10-120 Mbit/s
Read-After-Write..... Yes
Bit Error Rate..... 1×10^{-10}
Record Time at ATARS Rate
Medium Cassette D-1M..... 74 Min at 80 Mbit/s
Power..... 28 VDC per MIL-STD-704
Airborne Environment..... MIL-E-5400


The DCTR is ideally suited for use in military reconnaissance, anti-submarine warfare, electronic intelligence gathering and communications data acquisition. The recorder may also be used with electro-optic and FLIR sensors, synthetic aperture and conventional radar image data, ELINT, sonar passive arrays, and other data sources.

MIL STD-2179 Format



0° Azimuth Recording

IRIG 106-XX and
ANSI-ID-1 Format



± 15° Azimuth Recording

DCTR-LP Series

Format..... D-1 Cassette- ANSI X3B6 ID-1,
IRIG 106-XX, or MIL-STD-2179

Data Rate Record/Reproduce

- DCTR-LP200..... 25-200 Mbit/s
- DCTR-LP300..... 37.5-300 Mbit/s
- DCTR-LP400..... 50-400 Mbit/s

Read-After-Write..... Yes

Bit Error Rate..... 1×10^{-10}

Cassette Compatibility..... D-1S, D-1M, D-1L

Size..... 14 inches high
19-inch rack mount

■ TAPE

- Coercivity: 850 O_e
- Enhanced iron oxide

■ CASSETTE STORAGE

	16 μ m TAPE	13 μ m TAPE
D-1S	1.1×10^{11} bits	1.5×10^{11} bits
D-1M	3.4×10^{11} bits	4.5×10^{11} bits
D-1L	7.6×10^{11} bits	1×10^{12} bits

■ MASS STORAGE SYSTEMS

Robotics-controlled automatic cassette handlers can adapt the DCTR-L series to mass storage systems to build library archives with 10^{15} to 10^{16} bit data storage capacity.

■ DATA RATES TO 1600 Mbit/s


Data rates of 1600 Mbit/s can be achieved by clustering and synchronizing four DCTR-L400's in a single 19-inch rack.

360 Sierra Madre Villa, Pasadena, CA 91109-7014
(818) 796-9381, Fax (818) 351-5329
For information on our International Offices please call
(818) 796-9381 Ext. 2593

Kodak leading technology: the DATATAPE advantage.

DATATAPE
INCORPORATED
A KODAK COMPANY





Electronic Components and Circuits

Hardware Techniques, and Processes

20 Multichannel, Active Low-Pass Filters

22 Efficient Cavity-Dumped, Frequency-Doubled Nd:YAG Laser

24 Synchronous Half-Wave Rectifier

24 Field-Sequential Color Converter

28 Hotspot Endurance of Solar-Cell Modules

30 Twisted Pair of Insulated Wires Senses Moisture

Multichannel, Active Low-Pass Filters


Multichannel integrated circuits are cascaded to obtain matched characteristics.

NASA's Jet Propulsion Laboratory, Pasadena, California

The gain and phase characteristics of the channels of a multichannel, multistage, active, low-pass filter can be matched by making the filter of cascaded multichannel integrated-circuit operational amplifiers. This concept takes advantage of inherent


equality of electrical characteristics of nominally-identical circuit elements made on the same integrated-circuit chip. Moreover, the characteristics of the channels vary identically with changes in temperature.

The concept was motivated by the design requirements of a radar-target simulator for use at frequencies from 200 Hz to 450 kHz to process Doppler modulation. The gain and phase characteristics of the two channels in the simulator had to be as



This **Cascade of Dual-Operational-Amplifier Integrated Circuits** constitutes a dual-channel active low-pass filter having a 410-kHz 3-dB-cut-off frequency and a 30-dB/octave rolloff. The gain and phase of channel A match those of channel B. Although the operational amplifiers in this filter are adjusted for unit gain, a larger gain would produce a similarly flat response in the passband.


High Accuracy Positioning Systems *Custom Engineered From Standard Components*



TYPICAL TURNKEY SYSTEMS

5 Axis
Machining
Center

Automatic
Vision
Inspection
System



MULTI-AXIS SYSTEMS



Tuning Robot:
XYZ θ vision



ANOGLIDE™
air bearing
system

CONTROLS




ANOMATIC™
CNC Controller



ANOTRONIC™
custom
controller

POSITIONING TABLES



ANORIDE™ X-Y
positioning
table



ANORAIL™
high speed
& long travel



ANOROUND™
rotary tilt option

POSITIONING COMPONENTS



Encoder



Vision
Camera



Intelligent
Axis Card

At Anorad, we specialize in understanding your positioning requirements, and translating those needs into custom engineered solutions using our standard, pre-engineered products. Leading manufacturers rely on Anorad for cost-effective positioning solutions for some of their most demanding applications.

Standard, high precision linear and rotary positioning tables form the foundation of our building block approach to system design. Our ANORIDE™ tables employ an extremely reliable crossed roller design while ANOGLIDE™ tables incorporate precision air bearings for friction-free motion. The ANORAIL™ series is utilized for very high speed, long travel applications and features ANOLINE™ linear DC servo motors.

What's more, all of our positioning tables are easily configured into multi-axis, custom engineered positioning systems.

Control can be provided by Anorad's ANOMATIC™ CNC controller, an Intelligent Axis Interface to a host computer, or a controller specially designed for the application. Depending upon the application, sensors, vision systems and work performing devices can be incorporated to provide turnkey systems.

Call an Anorad Application Engineer today to discuss your individual requirement. We will consult, layout, propose, firm bid and deliver a positioning system custom engineered to your specific applications.



ANORAD CORPORATION

110 Oser Avenue, Hauppauge, New York 11788 (516) 231-1995 TWX: 510-227-9894

For Information Circle 508.

To have an application engineer call, Circle 509.



closely matched as possible; otherwise, gain and phase errors would degrade the rejection of sidebands.

Each stage in each channel of the active filter consists of an operational amplifier set for unit gain. The operational amplifier provides a flat response in the passband and a smooth transition from passband to stopband. Five two-channel operational amplifiers are cascaded to produce the required cutoff frequency and 30-dB/octave rolloff rate for each channel (see figure).

If such a filter were made of discrete components, it would be extremely bulky

because of the sizes of components required for operation at the low frequencies in the passband. Moreover, it would be difficult and expensive to match every part with the corresponding part in the other channel.

If additional matched channels are needed, chips containing more than two operational amplifiers apiece (e.g., commercial quad operational amplifiers) could be used. The concept is applicable to a variety of equipment requiring matched gain and phase in multiple channels — radar, test instruments, communication circuits, and

equipment for electronic countermeasures.

This work was done by James J. Lev of Caltech for **NASA's Jet Propulsion Laboratory**. For further information, Circle 142 on the TSP Request Card.

This invention is owned by NASA, and a patent application has been filed. Inquiries concerning nonexclusive or exclusive license for its commercial development should be addressed to the Patent Counsel, NASA Resident Office-JPL [see page 14]. Refer to NPO-17290.

Efficient Cavity-Dumped, Frequency-Doubled Nd:YAG Laser

Undoubled light is returned to the primary cavity.

NASA's Jet Propulsion Laboratory, Pasadena, California


A new design is expected to increase the efficiency of a cavity-dumped, frequency-doubled Nd:YAG laser. The frequency-doubling crystal is placed outside the primary resonator cavity to reduce the loss that it would cause if placed there, and the light in the external frequency-doubling cavity at the fundamental laser frequency (the "undoubled" light) is returned to the primary resonator cavity to contribute additional laser gain.

The primary resonator cavity is bounded by mirrors 1 and 2 and contains an electro-optical modulator, an Nd:YAG laser rod, and a polarizing beam splitter (see figure). Mirrors 1 and 3 define the secondary resonator cavity, part of which coincides with part of the primary resonator cavity and the rest of which contains the external frequency-doubling crystal.

As in normal cavity dumping, energy at the fundamental laser frequency (wavelength of $1.064 \mu\text{m}$) is stored in the photon field of the primary resonator; pulses of light are extracted from the primary resonator by application of switching voltage pulses to the electro-optical modulator. The polarizing beam splitter polarizes horizontally the initial beam of light on the optical path of the primary resonator.

The application of the transverse switching electric field to the electro-optical modulator introduces a quarter-wave retardation to the beam. A double pass through the modulator causes a half-wave phase shift and concomitantly rotates the polarization to vertical. The vertically polarized light is reflected by the beam splitter out of the primary resonator and through the frequency-doubling crystal, which rotates the polarization of the doubled portion of the light by 90° .

Mirror 3 reflects the doubled and undoubled light back toward the beam splitter, which is dichroic and allows the doubled light to pass through. Because the



In the **Cavity-Dumped, Frequency-Doubled Nd:YAG Laser**, the frequency is doubled outside the primary laser resonator, and the portion of fundamental-frequency light not used by the doubler is returned to the primary laser cavity to increase the efficiency.

undoubled reflected light is still vertically polarized, it is reflected by the beam splitter back into the primary resonator. As long as the electric field remains on in the electro-optical modulator, this returned light is rotated back to horizontal polarization and returned to the initial beam. Applications of this laser are foreseen in data communications, laser ranging, studies of the atmosphere, remote sensing, and laboratory studies.

This work was done by D. L. Robinson and D. L. Sipes of Caltech for **NASA's Jet Propulsion Laboratory**. For further information, Circle 79 on the TSP Request Card.

In accordance with Public Law 96-517, the contractor has elected to retain title to this invention. Inquiries concerning rights for its commercial use should be addressed to

Edward Ansell
Director of Patents and Licensing
Mail Stop 305-6
California Institute of Technology
1201 East California Boulevard
Pasadena, CA 91125

Refer to NPO-17286, volume and number of this NASA Tech Briefs Issue, and the page number.

SOLID STATE RELAY

Now a cheap off-the-shelf SSR that puts you in control. It lets you control the cost and the system's function in military applications.


**#2
IN A SERIES**

Here's what you get.

- Short Circuit Protection
- Status Indication
- Current Overload Protection
- Optical Isolation
- TTL & CMOS Compatible Control
- Built to meet the requirements of MIL-R-28750.
- Cost Effective



ACTUAL SIZE
CERAMIC PACKAGE




PART # CD21CDW

Review the electrical characteristics and call us for immediate application assistance.*

ELECTRICAL CHARACTERISTICS (-55°C to +105°C unless otherwise noted)				
	Min	Max	Units	
Bias Voltage (V_{BIAS})	3.8	6.0	V_{DC}	See Note 1
Bias Current (I_{BIAS})		15.0	mA	$V_{BIAS} = 5V_{DC}$
Control Voltage (V_{IN})	0	18.0	V_{DC}	
Control Current (I_{IN})		250	μA	$V_{IN} = 5V_{DC}$
Turn-Off Voltage ($V_{IN(OFF)}$)	3.2		V_{DC}	
Turn-On Voltage ($V_{IN(ON)}$)		0.3	V_{DC}	
Continuous Load Current		1.2	A	-55°C to +25°C
I_{LOAD} @ 60VDC		0.7	A	+85°C
Output Trip Current (I_{TRIP})	2.4 (Typ.)		A	+25°C, 100ms
On-Resistance (R_{ON})		0.65	Ohms	
Turn-On Time (T_{ON})		1.5	ms	
Turn-Off Time (T_{OFF})		0.25	ms	
Status Voltage (V_{STATUS})	1	18	V_{DC}	
Status Current (I_{STATUS})		2	mA	$V_{SAT} \leq 0.3V_{DC}$ See Note 2

Notes: 1. Series resistor is required for bias voltages above 6V_{DC}. $R_S = (V_{BIAS} - 6V_{DC})/15mA$
 2. A pull up resistor is required for the status output. $R_{STATUS} = (V_{STATUS} - 0.3)/I_{STATUS}$
 3. Output will drive loads connected to either terminal (sink or source).
 4. Status circuit is a built-in test feature checking the input circuitry of the relay. Status output is low (on) when the input is on.

All power FET relays may drive loads connected to either positive or negative referenced power supply lines (source or sink modes).



TELEDYNE SOLID STATE
A Division of Teledyne Relays

*For immediate application assistance call 1-800-284-7007.

Teledyne Solid State, 12525 Daphne Avenue, Hawthorne, California 90250.

Circle Reader Action No. 537

Synchronous Half-Wave Rectifier

An active circuit acts like a highly efficient diode.


NASA's Jet Propulsion Laboratory, Pasadena, California

A synchronous rectifying circuit behaves like a diode that has an unusually low voltage drop during forward-voltage (conducting) half cycles. The circuit would be particularly useful in power supplies with potentials of 5 Vdc or less, where the normal forward-voltage drops in ordinary diodes can be unacceptably large. The circuit could be fabricated as a monolithic assembly or as a hybrid.

The circuit (see figure) includes main-current-controlling field-effect transistor Q_2 , which is controlled in part by current-sensing comparator IC_1 . The combination of capacitor C_1 , resistor R_1 , Zener diode D_2 , and transistor Q_1 constitutes a conventional voltage-regulating power supply for IC_1 . C_1 is charged through diode D_1 during the reverse (nonconducting) half cycle and discharges through the regulator so that the regulator supplies a nearly constant voltage, V_{CC} , to IC_1 throughout the cycle.

During the reverse half cycle, the combination of positive bias from voltage divider R_2, R_3 and the more negative input to the positive terminal through R_5 forces the output of the comparator low. Because the output of the comparator is fed to the gate of Q_2 , Q_2 remains turned off.

At the beginning of the forward half cycle, I_2 begins to flow in diode D_3 (a parasitic integral body diode in Q_2), in parallel with current I_3 through resistors R_6 and R_7 and diode D_4 . The resulting voltage drop across R_6 is sensed by IC_1 . When the total forward current I_1 reaches a threshold value, the comparator toggles on (output high), aided by regenerative feedback through R_4 . This turns Q_2 on hard, bypassing parasitic diode D_3 because Q_2 has a smaller resistance when conducting. Q_2 then conducts the main load current dur-



The **Synchronous Half-Wave Rectifier** includes active circuits to attain a low forward voltage drop and, consequently, high rectification efficiency.

ing the remainder of the half cycle.

As the voltage drops to a low value toward the end of the forward half cycle, I_1 falls below the threshold and IC_1 turns off, again aided by regenerative feedback through R_4 . This turns off Q_2 . Both turnon and turnoff thresholds can be set at desired values by the appropriate choices of resistors R_2 through R_7 .

Tests of a "breadboard" version of the circuit made of discrete components indicated that very high rectification efficiency

is attainable. If fabricated as a monolithic assembly, the circuit should be at least as efficient as the "breadboard" version.

This work was done by Wally E. Rippel of Caltech for NASA's Jet Propulsion Laboratory. For further information, Circle 15 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, NASA Resident Office-JPL [see page 14]. Refer to NPO-17220.

Field-Sequential Color Converter

Size, weight, and power consumption are reduced.

Lyndon B. Johnson Space Center, Houston, Texas

An electronic conversion circuit enables the display of signals from a field-sequential color-television camera on a color video camera. Designed for incorporation into a color-television monitor on the Space Shuttle, the circuit weighs less, takes up less space, and consumes less power than the previous conversion equipment, which had to remain on the ground. The circuit (see figure), which incorporates state-of-the-art memory devices, could also be used in terrestrial stationary or portable closed-


circuit television systems.

The field-sequential technique of encoding color video signals reduces the size, weight, and power consumption of a video camera by requiring only one image sensor instead of the usual three. A wheel in front of the camera lens holds a red, a green, and a blue filter and turns in synchronism with the video-field rate to image the red, green, and blue components onto the image sensor during successive video fields. Each of the fields in the resulting

video signal contains the corresponding single color component. For display on a color video monitor, this signal must be converted to a standard color video signal that contains all three colors simultaneously.

The first stage of the converter performs the balanced-to-unbalanced conversion, amplification, and buffering of the input video signal. One of the U_3 dual voltage comparators provides the composite synchronization signal, on which two phase-locked loops (PLL's) are locked. One PLL locks a 14.318-MHz oscillator to the horizontal-line rate and is used to provide the majority of the timing of the circuit. The

The best vacuum valve is the right vacuum valve.



For extreme ultra high vacuum, coarse vacuum, or something in between...


For millions of cycles, or only a few...

For easy to handle gases, or the very worst...

Where there is plenty of room, or mounting restrictions...

Where cost is secondary, or a critical concern...

VAT, the world's leading manufacturer of vacuum valves, offers the widest choice available.



Call today for our new catalog, and choose the right valve for your application.

**VAT, Incorporated,
600 West Cummings Park
Woburn, MA 01801**

Tel. (617) 935-1446
(800) 828-5625
Fax (617) 935-3940


VAT AG, CH-9469 Haag, Schweiz

Tel. (085) 7 01 61
Twx. 855 162
Fax (085) 7 48 30

The new catalog "Vacuum Valves 90"



FROM COPPER TO FIBER, COVER THE FREQUENCY RANGE FROM 700 MHz TO 8 GHz...



700 MHz



900 MHz

AND BEYOND.



8 GHz

5 GHz

3 GHz

PATTERN GENERATION FOR SYSTEM EVALUATION AND ANALYSIS HAS NEVER BEEN EASIER OR MORE COMPLETE.

Anritsu has a complete range of pattern generators and receivers that cover 1 MHz to 8 GHz and beyond, manual or full GPIB control.

Virtually any type of pattern can be generated including pseudorandom, variable mark ratios and programmable patterns up to 16 kps. Pattern and clock

output levels, as well as offset voltage, can be user controlled. In addition, delay can be set on all the units to permit flexible interfaces.

Anritsu helps you every step of the way whatever your test requirement. From high speed digital ICs to high speed optical devices...from electrical to optical transmission systems.

So take the first step and contact Anritsu today at 1-800-255-7234 or in NJ 201-337-1111. Anritsu America, Inc. 15 Thornton Rd., Oakland, NJ 07436, Fax 201-337-1033.

Anritsu

second PLL provides the pixel clock, which has an oscillator selected to give approximately 512 sampling pixels along each active video line. This signal provides analog-to-digital (A/D) and digital-to-analog (D/A) conversion sampling and line-address-counter clocking.

Most of the signals required for subsequent timing and logic control are provided by a video-synchronization generator locked to the incoming video signal by the 14.318-MHz PLL. An associated logic circuit maintains the even/odd field status and vertical-interval status. A 9-bit horizontal-line-pixel counter is built into the left programmable-array logic (PAL) circuit, which provides the lower bits of static random-access-memory (SRAM) addresses. The right PAL circuit contains an 8-bit

counter that counts the video-line number.


The left PAL uses the pixel-counter data to derive the position in the line of a green-field-synchronization signal. This signal is encoded on line 18 of every third video field and indicates the start of a field of green-color information. This command is stripped off the video data by the second voltage comparator in U_3 . The left PAL provides the line-18 location, which is logically combined with green-field synchronization data and position to provide a color-field-reset signal. This signal is used as a field-counter reset, indicating the start of a green field of data. The signals for the green, red, and blue field lines are then processed into signals that control the SRAM's.

Each of the six SRAM's serves as a video-field buffer. Six video fields are re-

quired to align the three color components with their even and odd video fields. Three circuits act as "prebuffers" by separating the three color components of the output of the A/D converter. New data from the current incoming field are written into either the even- or the odd-field memory. Data for the other two color components are read from the respective even- or odd-field memory. The three color components of digital data are sent to the D/A converter, which produces an RS-170 standard output for display by a red/green/blue color monitor.

This work was done by Victor J. Studer of Johnson Space Center. For further information, Circle 88 on the TSP Request Card.

MSC-21346



The **Field-Sequential Color Converter** processes field-sequential color video signals into standard video signals that can be used by a color video monitor.


Hotspot Endurance of Solar-Cell Modules

A procedure for evaluating modules for use with concentrators is now available.

NASA's Jet Propulsion Laboratory, Pasadena, California

A procedure for testing modules of photovoltaic cells to be used with solar concentrators determines their ability to endure hotspots. Although procedures for testing flat-plate solar-cell modules have been available for some time, the new procedure is the first for concentrator modules.

A hotspot occurs in a photovoltaic cell when the current in a module of series-connected cells that contains the cell in question exceeds the short-circuit current of that cell. This condition forces the cell into reverse bias, increasing its power dissipation and raising its temperature. Hotspots can be created by cracks or shadow-



The **Solar Simulator** illuminates photovoltaic cells through the Fresnel lens of the concentrator module.

WHY BUY A NEW CAR WHEN YOU DON'T HAVE TO?

USE **Tufoil**[®] AND YOUR ENGINE WILL LAST... AND LAST...AND LAST!

You've seen the price of new cars...they go up every year! Cars get flimsier ... prices get higher...it never seems to end. There are lots of reasons to keep that nice car of yours on the road as long as possible.

Now it's easy to make your engine run better, last longer. Just add **TUFOIL** to the crankcase. You don't have to shake the container or add an engine flush. Just pour it in and drive away.

Your throttle will get silky smooth ...acceleration will improve. One customer said his car *"takes off like a scared rabbit!"*

TUFOIL works wonders for all known engine oils. It's actually slipperier than Teflon[®]. (according to a famous US government laboratory.)

You'll get astonishingly fast starts on cold mornings with both diesels and gas engines. The Canadian government tested TUFOIL at it's cold regions lab. They showed *faster cranking and significant fuel savings with TUFOIL.*

I keep getting telephone calls from owners of very expensive German diesels wanting to buy stock in our company. They say *their diesels are accelerating like nothing they've ever seen before.* One said he doesn't have to down shift any more on an annoying hill in his area.

Your car can have more power like that too.

What about additives that claim to be one time treatments that will last the life of an engine? Well, I've been following the scientific literature on lubrication for a very long time. As far as I know, there isn't a shred of scientific evidence for such a claim. So don't believe it!



TRY ONE 8 OZ BOTTLE OF TUFOIL FOR 30 DAYS OR 1000 MILES

If you don't notice quieter-smoother operation, quicker starting, snappy acceleration. Just send us proof of purchase with a note describing the year and make of your car. We'll refund your money immediately.

Send for TUFOIL today and prove to yourself the amazing increase in your car's performance. Fill in the coupon today or call TOLL-FREE any time, 24 hours a day.

1-800-922-0075.
(in New Jersey, call 201-825-8110.)



Stay in tune with your car!

Engines last longer with TUFOIL... Our 1976- 476 T-Bird is now at **190,000** miles and purring.

A bunch of customers' cars have now passed **250,000** miles.

Several months ago, a nice man I'd never seen before walked into my office, big smile on his face, sat down and said, "Would you believe **340,000** miles on a Tufoil engine?" He went on to rave about how well his engine has been running all these years. I couldn't get a word in edgewise.

It made me very proud.

Recently, a truck driver called in with over **1,000,000** miles on a diesel using TUFOIL - Wow!

A customer from Vermont added 10% TUFOIL to his sticky mechanical transmission, called in and said he couldn't believe it...*"Shifting is like slicing butter now!"*, he said.

SAAB owners are writing letters praising TUFOIL in their "NINES" magazine. They report spectacular improvements in their engines and transmissions!

Don't forget! TUFOIL is the result of over 15 years of research and development. *The U.S. government has awarded us 6 patents so far...* so have Germany, England, France and Canada.

No other lubricant even comes close.
One customer put it nicely when he said, *"You can hear it...you can feel it!"*

PS--Our loyal customers wrote this ad for us. Its full of their comments!

Thanks!

FREE ... Products based on **TUFOIL** technology. Check one with each order of 2 bottles or a quart. Check 2 for each gallon order. Values range from \$3.98 to \$9.95.

- ☐ TUFOIL Gun-Coat — Super rust inhibited, smooth action
- ☐ TUFOIL Compu-Lube — Low viscosity for computer mechanisms
- ☐ TUFOIL Lightning Grease — Easily sheared grease for instruments
- ☐ TUFOIL Lubit-8 — General purpose, household use lubricant

FREE brochures ...

- ☐ 30 Questions/Answers about TUFOIL
- ☐ "Fun with Superconductors"—we're leading that field too!

See NASA Tech Briefs for technical details, 1986, 1987 and 1988.

©1987 Fluoramics, Inc.

FLUON[®] is reg. T.M. of ICI Americas Inc.

TEFLON[®] is reg. T.M. of DuPont[®]

TUFOIL[®] is reg. T.M. of Fluoramics

U.S. Patent No. 4,284,518

U.S. Patent No. 4,224,173

U.S. Patent No. 3,933,656

Other U.S. Patents issued and pending.

YES

rush my **TUFOIL** order:

- ☐ ONE 8 oz. bottle ... treat one car for \$14.25 (plus \$3.50 shipping and handling). See money back guarantee.
- ☐ TWO 8 oz. bottles ... treat two cars for \$25.00 (plus \$4.00 shipping and handling) **SAVE \$6.00**
- ☐ ONE Quart bottle ... treat 4 cars for \$34.95 (plus \$4.00 shipping and handling)
- ☐ ONE GALLON ... treat 16 cars for \$125.00 (plus \$6.00 shipping and handling.)

We ship within days!

*over the single bottle price **BIG SAVINGS**

When
POPULAR MECHANICS
tested TUFOIL, it reported
"TUFOIL is absolutely
spectacular!"

Fluoramics, Inc. NTB-79

103 Pleasant Avenue

Upper Saddle River, N.J. 07458

My check or money order for \$ _____ is enclosed.
Charge my credit card:

☐ Am. Express ☐ MasterCard ☐ Visa

Card No. _____

Exp. Date _____

Signature _____

Name _____

Address **UPS Shipping Address**

City _____

State _____ Zip _____

(N.J. residents please add 6% sales tax). Canadians:
Call for the name of our Canadian distributor.

ing of cells in normal service, even in highly reliable arrays. It is therefore important to ensure that a hotspot does not propagate to other cells or present electrical hazards.

The procedure begins with the selection of three cells in a module: one that has the highest shunt resistance, one that has nearly average shunt resistance, and one that has the lowest shunt resistance. Each of the three cells is then connected to a separate power supply in such a way that the heat-transfer characteristics of the cells and the hotspot endurance are disrupted as little as possible.

The next step is to select the hotspot test level; that is, the level of heating that will stress the module as severely as it would be stressed by a hotspot during use. The principal test parameters include the re-

verse voltage, the ambient temperature, and, for cells that have reverse-breakdown voltages higher than the maximum available reverse voltages (those with generally high shunt resistances), the overall irradiance. Cells with breakdown voltages less than the available reverse voltages (those with generally low shunt resistances) tend to develop hotspots when shaded.

An infrared lamp heats the heat sink of the module to simulate the ambient temperature. Power is applied to the test cells. A solar simulator (see figure) illuminates the appropriate cells, and the cells to be shadowed are tested in ordinary laboratory light. A timer turns the power supplies, the infrared lamp, and the solar simulator on and off. The "on" time is 1 h; the "off" time is long enough to allow the cell to cool to

within 10°C of the ambient air temperature. The timer repeats the cycle until 100 h of "on" time have been accumulated.

The module and test cells are inspected visually at 24-h intervals during the test and again when the test is completed. The inspector looks for evidence of degradation, including cracking, delamination, outgassing or blistering of encapsulants, and melted solder. After the test, the electrical characteristics of the module are measured for comparison with the pretest characteristics.

This work was done by C. C. Gonzalez, R. S. Sugimura, and R. G. Ross, Jr., of Caltech for NASA's Jet Propulsion Laboratory. For further information, Circle 157 on the TSP Request Card. NPO-17305

Twisted Pair of Insulated Wires Senses Moisture


Sensitivity to low levels of moisture is increased.

NASA's Jet Propulsion Laboratory, Pasadena, California

The sensitivity of an electronic moisture sensor to low levels of moisture is increased by a new electrode configuration. Instead of attempting to bond porous, flexible electrodes to metal films, the designers of the new sensor use plated solid wires as electrodes. The wires are encapsulated in

tubes of a polysulfonated polymer and twisted together in a tight spiral (see figure).

The moisture-sensing circuit was described in "Low-Cost Humidity Sensor" (NPO-16544), *NASA Tech Briefs*, Volume 9, No. 4 (Winter 1985), page 55. The new twisted pair of wires takes the place of a



Twisted-Wire Electrodes are sheathed with a polymer dielectric. The bare wire tips are for monitoring purposes.

flat-plate capacitor in that circuit. The capacitance varies with the humidity, thereby varying the frequency of the oscillator, which is read as an indication of the humidity.

The twisted-pair configuration allows for the thermal expansion and contraction of the polymer while maintaining a nearly constant area of contact between the polymer and the wires. The bare electrode wires are allowed to protrude at the ends of the twisted pair. These bare extensions enable the monitoring of the transducer and serve as convenient points for the introduction of forced signals to test the transducer.

This work was done by Eric G. Laue and James B. Stephens of Caltech for NASA's Jet Propulsion Laboratory. For further information, Circle 137 on the TSP Request Card.

In accordance with Public Law 96-517, the contractor has elected to retain title to this invention. Inquiries concerning rights for its commercial use should be addressed to


Edward Ansell
Director of Patents and Licensing
Mail Stop 305-6
California Institute of Technology
1201 East California Boulevard
Pasadena, CA 91125

Refer to NPO-17111, volume and number of this NASA Tech Briefs issue, and the page number.




NASA Tech Briefs, July 1989

CAN YOUR GRAPHICS SOFTWARE DO ALL THIS?

Shadow Contour of a Random 3-D Surface




Linear, Logarithmic, and Probabilistic Axes




"Graftool has the potential to be the ultimate graphics package, fulfilling everybody's needs."

- Ehud Kaplan
PC Magazine



Geographic Data Included For 2-D and 3-D Maps

Integrated 2D&3D graphics
Menu-driven user interface
Scientific spreadsheet
Presentation-quality fonts
Import from 1-2-3, Excel
Export to desktop publishers
Full zooming and panning



GRAFTOOL's unique 3-D graphics enable a user to plot complex data such as this spherical harmonic tessellation




GRAFTOOL \$495 • Demo Kit Available
Academic Discounts • Call (213) 540-8818 • FAX (213) 540-3492

3-D VISIONS

412 S. Pacific Coast Highway, Suite 201, Redondo Beach, CA 90277

* Reprinted with permission from PC Magazine, March 14th, Copyright © 1989 Ziff Communications Co.

Circle Reader Action No. 669



```

#)-FNR!q-" %6425,++:,61<+:5<
! . 38,4</
! YSWORPOHIRJKACK ./, (>( B
c`^h_?6?4 ^j<UV?HKDc ^0 ^Ez
<8ZA% :% # AAD@?=6E WqtOMac
6<G5(PM $ QG '156?6150010
4" 6= ^' 4?MX7 &# :
.& BsKL T ,2 F+ ( >A$, * I
^#v '8-z7>0-+K n2 ' )$ \ K 8
AFHL<232' De$ Az " ~ p'F JE
! kqxJ FKC:@FFT:P)uU I
51Dq&p A 3GM/=,5!~! A>) o:
,yJD*PNBE][ "2'OjIH{ ^FIB\X[M>E
1 9$! C4 dz s:tFEIEGBBGE@E
3"bs7J-Gc+i r+lR [NJ' G 6
# '4:yK ! 0: 1402& )321:
OIGD% 'G+^s ,VZ*11
7.Z:&CA_v#eD$ {\b6LOKHafS`^
>< -D >D] n1EAAA7:A( 88 $^Z
N1" #,=Q<9R ( ) # = 'e
/10.12((9 (I > $)$SS41L64
M,2@& <+"g! .A. " 8

```

Get the picture? Get the message?

You get both with Raytheon's latest generation TDU-850 Thermal Recorder. The TDU produces continuous tone, high quality images in up to 256 shades of grey. Or — it doubles as an ASCII printer (using Raytheon's new IEEE 488 interface) and turns out crisp, letter quality alphanumerics.

The TDU makes high resolution hard copy recordings at high speeds on paper, plastics and transparencies. Optional interfaces accommodate video, IEEE 488 and other formats. Prints to 8½ inch width. (Inquire about 12-inch version.)

Design modifications are available to meet individual application requirements. Typical uses include: aerial surveillance, equipment testing, hydrographic surveys, security systems, R&D programs and meteorological reporting. Today's most versatile thermal recorder, still for under \$5000.

Make hard copy easy. Call or write Marketing Manager, Recorder Products, Raytheon Company, Submarine Signal Division, 1847 West Main Road, Portsmouth, RI 02871-1087. Phone: (401) 847-8000.



Raytheon

Left. High altitude surveillance.

Right. Alphanumeric data presented in a random format.



Electronic Systems

Hardware Techniques, and Processes

- 32 Data-Processing System for Test Airplane
- 34 Adjusting Surfaces of Large Antenna Reflectors
- 36 General-Purpose Electronic System Tests Aircraft

- 37 Radar Polarimeter Measures Orientations of Retroreflectors
- 38 Pulse-Population Modulation for Induction Machines
- 40 Balanced-Load Real-Time Multiprocessor System

Books and Reports

- 41 Assessment of Digital Control for Helicopters
- 42 Multiple-Baseline Interferometric Synthetic-Aperture Radar
- 42 Detecting Impacts of Particles on Spacecraft

Data-Processing System for Test Airplane

Real-time display of data on performance supports decisions regarding maneuvers.

Ames Research Center, Moffett Field, California

The X-29A advanced-technology-demonstrator airplane and the associated ground control station have been equipped with electronic equipment (see Figure 1) for the acquisition, transmission, processing, and display (all in real time) of data relating to the performance in flight. The data-processing system calculates the in-flight measured drag polar, the lift curve, and aircraft-specific excess power. From these elements, many other measures of performance can be computed and analyzed.

Traditionally, data on the performances of airplanes during test flights have been calculated and analyzed after the flights. Such postflight analysis often reveals errors and other inadequacies in the data that require the repetition of a flight test. By enabling real-time evaluation of flight-test maneuvering techniques and the quality of data, the new data-processing system makes it possible to repeat a maneuver immediately, while flight-test conditions are still suitable.

The data-acquisition subsystem (see Figure 2) aboard the airplane uses both pulse code modulation (PCM) and frequency modulation (FM) for transmission of sensor data on the operation of the engine, the performance of the airplane, and the conditions in the atmosphere. No data are recorded on the aircraft. The 10-bit PCM system transmits at rates that vary from 25 to 400 samples per second, depending on the desired frequency range to be covered. The digital data are processed by five PCM units, and an interleaver device merges the stream of data along with the output from the bus of the flight-control computer. The data are telemetered as an uncalibrated serial PCM stream.

The constant-bandwidth FM system transmits high-response acceleration and vibration data. This FM signal is merged with the rest of the digital data from the interleaver and telemetered to the ground along with the pilot's voice signals. About 700 measured data parameters are telemetered to the ground for recording, anal-




Figure 1. Data From Sensors Aboard the Airplane are transmitted to the control station on the ground for immediate processing and display.

ysis in real time, and monitoring in the control room. The set of data parameters includes measurements for structural loads, structural dynamics, flight controls, stability and control, aircraft subsystems, propulsion and performance, wing deflections, buffet, and external pressure distributions.

An essential element of the software component of the system is the real-time, in-flight net-thrust algorithm, which is based on the simplified net-thrust method. The only inputs required by this algorithm are the free-stream static air pressure, the total temperature at the turbine-rotor discharge, the calculated true velocity, and the gas

pressures measured at three locations in the afterburner duct of the engine. The algorithm computes the gross thrust on the basis of a one-dimensional approximation of the flow in the afterburner and exhaust nozzle. Using additional inputs from the air-data subsystem, the algorithm also calculates the ram drag and the net thrust. The uncertainty in the real-time coefficient of drag has been estimated to be about 3 percent.

This work was done by R. J. Ray, J. W. Hicks, and R. I. Alexander of Ames Research Center. Further information may be found in NASA TM-100432 [N88-21151], "Development of a Real-Time Aeroper-

Genius should not go unrewarded.

CALL FOR PAPERS

THE 1989 IBM SUPERCOMPUTING COMPETITION

IBM invites you to submit your accomplishments. We seek to honor those individuals whose imagination has elevated the state of the art in analysis and modeling. Included are those who have contributed to creating new leading-edge uses of large-scale computers, innovative applications or algorithms and advances in numerically intensive computing.

The best papers on innovative uses of the IBM 3090 will be chosen in the following four divisions: physical sciences and mathematics; engineering; life and health sciences; social sciences, humanities and the fine arts. Each division will receive a first, second and third prize of \$25,000, \$15,000 and \$10,000, respectively. In addition, a "PROCEEDINGS" of selected papers will be published.




Universities that provide substantial support to first prize papers will receive a \$10,000 award as well.

Contestants must register an abstract of their paper, according to specifications, by October 2, 1989. Those who have properly registered their abstracts will then be invited to forward their papers by January 15, 1990.

To select the winners, IBM will retain a panel of independent authorities in each division. Winners will be announced by March 1, 1990.

Simply put, IBM would like to acknowledge those individuals who share the same interest we do...the unrelenting pursuit of knowledge.

For more information contact your IBM marketing representative, or call (914) 686-6318; in Canada, (416) 758-4136.



To obtain the general information package and an entry form write to:

Competition Administrator
IBM Corporation, Dept. 72/BNG
44 South Broadway
White Plains, NY 10601

Name _____

Affiliation _____

Address _____

City _____ State _____ Zip _____

NTB

The competition is open to any individual or team working or living in the U.S. or Canada, excluding employees of the IBM Corporation, IBM Canada LTD, and IBM related companies and their families. © 1989 IBM Corporation

IBM®




Figure 2. The Data-Acquisition and -Transmission subsystem of Figure 1 is shown here in more detail.

formance Analysis Technique for the X-29A Advanced Technology Demonstrator."

Copies may be purchased [prepayment required] from the National Technical Information Service, Springfield, Virginia

22161, Telephone No. (703) 487-4650. Rush orders may be placed for an extra fee by calling (800) 336-4700.

Inquiries concerning rights for the commercial use of this invention should

be addressed to the Patent Counsel, Ames Research Center [see page 14]. Refer to ARC-12212

Adjusting Surfaces of Large Antenna Reflectors

A new approach is more effective than the traditional rms-surface-distortion approach.

Langley Research Center, Hampton, Virginia

In the design and operation of large antenna reflectors for use in outer space, a principal issue is the precise control of the shape of the reflector surface required to guarantee satisfactory electromagnetic (EM) performance. While the need to control the shape is clear, the implementation is a subject of current research. In the past, the link between the loss of performance of an antenna and deformation of the structure of the antenna has been based on classical formulas in which the loss is related to the root-mean-square (rms) value of the distortion of the surface. Although a reduction in this rms value has a significant effect on the gain, it does not necessarily improve such other performance parameters as the shape or pointing direction of the beam and the levels and distribution of side lobes, which depend upon the details of the distortion throughout the surface of the reflector.

There is a new optimization procedure for control of the shape of the reflector of a large space antenna (LSA). The main fea-

ture that distinguishes this procedure from previous ones is that the shape-controlling mathematical mechanism is driven by the need to satisfy explicit EM design requirements rather than implicit limits on the rms accuracy of the surface.

The procedure uses standard finite-element structural analysis, aperture-integration EM analysis, and constrained optimization techniques to predict a set of actuator inputs that will improve the performance of an antenna while minimizing the applied control effort. The procedure was tested for a 55-meter tetrahedral-truss antenna designed for a microwave-radiometer mission. A radiometer design is an attractive test case because remote sensing is a driving force behind NASA's interest in LSA systems and because the constraints on EM performance are both critical and difficult to achieve.

In this test case, the shape of the surface of the radiometer is controlled by a set of actuators that can lengthen or shorten individual members of the backup struc-

ture. The optimization procedure must select a set of actuator inputs that smooths the surface of the reflector enough to satisfy criteria for EM performance while minimizing the total actuator effort. The results indicate that this procedure produces a much better set of actuator inputs than does the traditional approach based on constraints on rms distortion of the surface.

The procedure is applicable to a wide variety of LSA concepts. The only assumption is that the original distortion of the surface is known precisely at a discrete number of locations and that the change in this distortion for a prescribed change in actuator inputs can be predicted. The quality of the optimum design can be improved even further by refining the finite-element model of the structure, by increasing the number of discrete points used to describe the surface of the reflector, and by increasing the accuracy of calculations of EM performance.

This work was done by Sharon L. Padula, Howard M. Adelman, and Marion

THE INCREDIBLE COLOR QUALITY OF SONY'S XC-007 IS NO ILLUSION.

When true color representation is critical to your applications, don't settle for anything less than Sony's XC-007 video camera.

You not only gain razor-sharp color images via its three CCD chips, each with 768H x 493V resolution.

But also, color images that are true to life. Right down to the most subtle hues, tones and shades. Complete with true RGB output.

That's because the XC-007 achieves its color via "Co-Site Sampling." Unlike Spatial Offset techniques, the CCD chips are arranged congruently. Resulting in pixel-to-pixel-to-pixel representation of each red, green and blue color.

Of course, that's not all the XC-007 delivers. You also get a variable-speed electronic shutter, from 1/125 to 1/10,000 second. Multi-outputs (RGB, NTSC, R-Y/B-Y/Y, Y/C, VBS). Interlaced and non-interlaced scanning and external synch. Ultra-high



Spatial Offset of the RGB pixels.

XC-007's Co-Site Sampling is spatially congruent.

sensitivity. Superb signal/noise ratio (60 dB). Title generator. Video gain up to 18 dB. Auto/manual white balance. Detail control. Selectable gamma correction. Rugged, reliable bayonet mount. And square pixels with the XC-007P PAL version.

All within a rugged remote-head package with an incredibly small camera head (75 x 70 x 96 mm).

Sony's XC-007 is backed by the quality, reliability and responsive service you expect from any Sony product.

So specify the XC-007 camera from Sony. And let your images show their true colors.

For more details, call (800) 877-SONY/(201) 930-6575 today. Or write Sony Corporation of America, Govt. Systems Division, Sony Dr., Park Ridge, NJ 07656, Attn: Govt. Sales. FAX (201) 930-6941.

SONY®



C. Bailey of Langley Research Center and Raphael T. Hofka of Virginia Polytechnic Institute and State University. For further information, Circle 64 on the TSP Request Card.

This invention is owned by NASA, and a patent application has been filed. Inquiries concerning nonexclusive or exclusive

license for its commercial development should be addressed to the Patent Counsel, Langley Research Center [see page 14]. Refer to LAR-13851.

General-Purpose Electronic System Tests Aircraft

Versatile digital equipment supports research, development, and maintenance.


Ames Research Center,
Moffett Field, California

The extended aircraft interrogation and display system (XAIDS) is a general-purpose assembly of digital electronic equipment on the ground for the testing of digital electronic systems on advanced aircraft. The XAIDS is the enhanced, second-generation version of a prior system developed to support the integration of digital flight systems, the verification and validation of software, preflight and postflight testing, and maintenance. To perform the tasks now accomplished in a unified manner by the XAIDS, it was previously necessary to use special-purpose ground support equipment for each project and, therefore, to build and maintain an inventory of many different types of equipment of varying capability.

The system (see figure) has many advanced features, including multiple 16-bit microprocessors, pipeline data-flow architecture, advanced operating system, and resident software-development tools. The basic collection of software includes programs for handling many types of data and for displays in various formats. The user can easily extend this basic software library. Hardware and software interfaces to subsystems provided by the user have been designed for flexibility in configuration to meet the user's requirements.

An auxiliary remote data-acquisition subsystem (RDAS) serves as an input/output interface that can be located near the system to be tested. An RDAS is intended for use where direct cabling to the XAIDS would be too complicated or vulnerable to electromagnetic interference. An RDAS can be located as far as 5,000 ft (1.5 km) from the XAIDS, with control and data signals flowing at a 1-MHz rate over a local-area network that uses a single RG-59/U coaxial cable 3/16 in. (4.8 mm) in diameter.

The XAIDS has contributed greatly to the work on the X-29A forward-swept-wing airplane. It has centralized the operators' activities at a single work station, providing both analysis of telemetry data and control of the flight-computer test set. Software has been developed to enable operators to overlay the memory of the flight computer with test code and/or tables of data, so that test conditions can be altered and the telemetry stream can be remapped. In addition, several large modules of software have been incorporated to provide evalua-



Notes:
1. "I/O" means input/output.
2. "RAM" means random-access memory.
3. "PROM" means programmable read-only memory.

The Extended Aircraft Interrogation and Display System is pipelined, multiprocessor, general-purpose digital electronic ground support equipment for the testing of digital flight systems.

NASA Tech Briefs, July 1989

tions of the performance of the flight-control system.

This work was done by Richard D. Glover of **Ames Research Center**. Further information may be found in NASA

TM-86740 [N87-16820], "Design and Initial Application of the Extended Aircraft Interrogation and Display System."

Copies may be purchased [prepayment required] from the National Technical In-

formation Service, Springfield, Virginia 22161, Telephone No. (703) 487-4650. Rush orders may be placed for an extra fee by calling (800) 336-4700. ARC-12148

Radar Polarimeter Measures Orientations of Retroreflectors

Polarization signatures of targets are to be compared with known signatures at known angles.

NASA's Jet Propulsion Laboratory, Pasadena, California

Experiments have demonstrated the use of radar polarimetry to measure the orientation of a retroreflective target, even though the target is much smaller than the resolution element of the radar. The technique is based on the comparison of the angular dependencies of the measured and theoretically derived polarization signatures of the target. In principle, the polarization signature could also be used to identify a target.

As the term implies, the polarization signature of a target is proportional to the radar scattering cross section of the target as a function of the angles of polarization of the illuminating and reflected radiation. The scattering properties of the target are conveniently summarized by the scattering matrix, S , which expresses the relation between the amplitudes r_h and r_v of signals reflected or received in horizontal or vertical polarization, respectively, and amplitudes t_h and t_v of signals transmitted in horizontal or vertical polarization, respectively.

Matrix S and the radar cross section, which is easily calculated from S , vary as the target is rotated about the radar line of sight or, equivalently, as the radar antenna is rotated around the line of sight and/or the radar polarization is varied. For example, the left side of Figure 1 shows theoretical radar cross sections for copolarized reflections (identical transmitting and receiving polarizations) from a rough surface, from a dihedral corner reflector, and from a trihedral corner reflector as functions of the orientation of the polarization ellipse and of the ellipticity angles. (Ellipticity angles of $\pm 45^\circ$ denote circular polarization, while 0° denotes linear polarization.)

The right side of Figure 1 shows the signatures of a dry lakebed and two corner reflectors mounted on it, as measured by an airborne radar. The tilt of the reflector showing the two-bounce response can be inferred by integrating the squared differences between the measured signatures and the calculated two-bounce signatures over all states of polarization and noting the tilt angle that would minimize the error (see Figure 2).

This work was done by H. A. Zebker and L. Norikane of Caltech for **NASA's Jet Propulsion Laboratory**. For further information, Circle 20 on the TSP Request Card. NPO-17231




Figure 1. **Radar Cross Sections** were calculated theoretically and measured for three representative targets.




Figure 2. The **Tilt of a Reflector** can be inferred by finding the angle that minimizes a measure of the difference between theoretical and measured radar cross sections of the reflector.

Pulse-Population Modulation for Induction Machines

Low-frequency waveforms are synthesized as needed from a high-frequency power supply.

Lewis Research Center, Cleveland, Ohio

The power-distribution system for the proposed Space Station is a single-phase, 440-Vrms, 20-kHz system, with a regulated sinusoidal waveform. A single-phase power system minimizes the complexities of wiring, sensing, and control required in a multisource, redundantly-distributed-power system. The 20-kHz operating frequency was selected to be above the range of audibility, minimize the weight of reactive components, and yet allow the construction of single power stages of 25 to 30 kW.


With regulated voltages, most ac/dc conversions involve rather-simple transformer/rectifier applications. A sinusoidal distribution system, when used in conjunction with zero-crossing switching, represents a narrow-band source of electromagnetic interference (EMI). The present state of 20-kHz power technology includes computer controls of voltage and/or frequency, cables of low inductance, current-limiting protection of circuits, bidirectional flow of power, and motor/generator operation using standard induction machines.

A low-frequency synthesizer has been developed to provide a low-frequency waveform by synthesis from a high-frequency power system. The low-frequency waveform is assembled by allowing conduction of discrete half cycles of the high-frequency carrier. One advantage of this method of modulation is that the frequency of the synthesized wave is controlled by the pulse pattern (see Figure 1).


The ability to control the amplitude and frequency independently provides wide latitude for the operation of ac induction motors, inasmuch as the torque delivered at any shaft speed is a function of the slip frequency, and the power factor drawn by the motor at any given speed/load combination is a function of the terminal voltage.

In addition, by controlling the relationship between the slip and stator frequencies, one can operate the induction motor either as a motor or as a generator (see Figure 2). Such a bidirectional energy transducer could be used as a starter/generator for an engine wherein high starting torques are provided by high controlled slip frequencies and generation is provided by negative slip frequencies, or as a servomechanism for control of acceleration and deceleration. Other advantages include operation under controlled voltage-to-frequency ratios to maintain high-efficiency and high power factor, and no reflection of low-frequency noise into the 20-kHz distribution bus.

This work was done by Irving G. Hansen of Lewis Research Center. Further information



COMPUTER SIMULATION OF LOW-FREQUENCY SYNTHESIS



SPECTRUM OF FIRST SET OF SIDEBANDS IN OUTPUT OF BREADBOARD SYNTHESIZER

Figure 1. A Low-Frequency Waveform is synthesized from selected conduction half cycles of a high-frequency waveform.





Figure 2. The Torque-vs.-Speed (or Slip) Curve of an induction machine has both positive and negative regions, signifying operation as either a motor or a generator.

may be found in:
NASA TM-87346 [N86-31584], "Description of a 20 KiloHertz Power Distribution

System," and
NASA TM-89925 [N87-22004], "EMC and Power Quality Standards for 20-kHz

THERE'S A NEW STANDARD IN REAL-TIME COMPUTING FOR MEASUREMENT AND CONTROL



Find the 24-karat solution for your measurement and control applications at Concurrent Computer Corporation, the world leader in real-time computing.

Cost-effective real-time computing power coupled with standards like VMEbus,[™] X Window system,[™] DECnet,[™] and a real-time enhanced UNIX[®] operating system are just a few of the solid-gold competitive advantages you get from Concurrent. With Concurrent you can shorten your software development cycle, lower your support costs, and get your new projects up and running faster. And our gilt-edged product line, ranging in price from \$10,000 to more than \$1 million, is backed by a world wide support organization.

Go for the gold! For your real-time information starter kit for measurement and control applications, send in the coupon today or call **1-800-631-2154** toll-free. Concurrent Computer Corporation—the company that sets the standards for real-time computing.

Send to Concurrent Computer Corp., Dept. MC-2,
106 Apple Street, Tinton Falls, NJ 07724

- ☐ Send me my information starter kit for measurement & control applications
- ☐ Send me information on the Concurrent real-time UNIX operating system

Name _____

Title _____

Company _____

Address _____

City _____ ST _____ Zip _____

Phone _____

My application is _____



Concurrent
Computer Corporation

Balanced-Load Real-Time Multiprocessor System

Modularity and parallelism provide tolerance to faults and high throughput capacity.

NASA's Jet Propulsion Laboratory, Pasadena, California

A distributed computing system is tolerant of damage and temporary faults and offers a high throughput capacity and dynamic balancing of the computational load. This system, called MAX, is a network of interconnected computers. It is based on a distributed-data-flow execution model, a distributed operating system (HYPHOS), a multiple-access broadcast bus, and a point-to-point circuit-switched network.


In the data-flow architecture, a program comprises independent functions. The execution of a function is made possible by the presence of the data required by the function. These data are encapsulated in tokens that identify the functions for which the data are intended. The use of the token by the function consumes the token, and the functions produce results in the form of new tokens. The tokens flowing between functions are automatically queued. There is no correspondence between a datum and its location in the memory.

A particular function becomes "fireable" — that is, ready for execution — as soon as it has received all of the necessary input tokens specified by its firing rule. Therefore, several functions may be fireable at any one moment. If the functions are distributed over the processing units of the system, all fireable functions are executed in parallel at the earliest opportunity. A large assortment of firing rules is provided to support real-time programming and fault tolerance.

The data flow smoothly handles transient workloads that arise from asynchronous inputs and variable computing times. It offers parallel paths for simultaneous execution and allows processing of consecutive inputs to overlap.

The data-flow system is a low-resolution one; its structures and functions, written in a high-order language, are more complex than those of high-resolution systems. Although a low-resolution system extracts less concurrent operation from an algorithm, such a system also involves less scheduling and synchronization.

The data-flow token is the basic unit for most MAX system functions. Software modularity, communication, concurrency, memory partitioning, and data comparison for fault detection are all performed at the token level. Full exploitation of this unifying mechanism beyond any previous system



A **MAX Cluster** consists of a group of modules — each a semiautonomous computer. The modules are connected to each other and to other clusters by a global bus and a circuit-switched communication mesh.

is the essence of the MAX design.

Overall, the MAX system consists of clusters of computer modules connected by global buses and the switched communication mesh (see figure). Each module is a self-contained computer that operates autonomously, using the HYPHOS distributed operating system.

Special-purpose boards can be attached to a module to enhance its capability, or such devices can be incorporated into the communication mesh.

The HYPHOS operating system uses special features of the global buses for software synchronization. The communication mesh transports the data between the modules.

There is no central controller in the system. Instead, the HYPHOS operating system in each module acts in concert with the others, to support multitasking, communication, and related functions. A graph-execution manager schedules data-flow tasks within a module.

A module is implemented on a single board with dual 32-bit microprocessors —

one primarily for HYPHOS functions and the other for application-software functions. A module also contains fast floating-point hardware and intelligent multiple-channel direct-memory-access coprocessors. There are also six 10-Mb/s communication ports, priority interrupts, and programmable timers. System software resides in a read-only memory. At least 128 kilobytes of random-access memory (RAM) are available in each module, and connections are provided for external RAM and memory-mapped input/output.

This work was done by Robert D. Rasmussen, Robert M. Manning, Blair F. Lewis, Gary S. Bolotin, and Richard S. Ward of Caltech for NASA's Jet Propulsion Laboratory. For further information, Circle 3 on the TSP Request Card.

This invention is owned by NASA, and a patent application has been filed. Inquiries concerning nonexclusive or exclusive license for its commercial development should be addressed to the Patent Counsel, NASA Resident Office-JPL [see page 14]. Refer to NPO-17185.

Books and Reports

These reports, studies, handbooks are available from NASA as Technical Support Packages (TSP's) when a Request Card number is cited; otherwise they are available from the National Technical Information Service.

Assessment of Digital Control for Helicopters

Digital flight controls are essential for high performance in advanced military rotorcraft.

A report provides an assessment of digital electronic flight-control technology for advanced helicopters intended for use in combat. The overall goal is to describe practical methods for the analysis of high-gain digital control systems, with a view toward reducing the dependence on the flight tests and postdesign modifications that are commonplace in the development of first-generation digital systems for airplanes.

Digital flight-control systems are critical to the success of the mission of advanced combat rotorcraft. Single-pilot and nap-of-the-Earth operations require handling qualities that minimize the involvement of the pilot in the basic tasks of stabilization. Full-authority, high-frequency, high-gain, multi-

mode, multiply redundant digital flight-control systems are necessary to satisfy these requirements. The work described in this report is part of the effort to make the transition from the current low-authority, low-bandwidth flight-control technology to the technology that will satisfy these requirements.

The report reviews the state of the art of high-bandwidth digital flight-control systems for airplanes, with emphasis on topics of concern for the development of such systems for modern combat helicopters. Important aspects of the design and analysis of high-gain digital systems are illustrated by use of results from a detailed study of a current rotorcraft system. Frequency-domain methods for design and analysis are stressed as being essential for the practical implementation of high-gain control systems for rotorcraft. There is a description of approximate and exact methods for prediction of the behaviors of digital flight-control systems.

The following are among the conclusions reached during the study:

- The attainable bandwidth of high-gain flight-control systems has consistently been overestimated in design studies; this overestimation is generally not exposed until the equipment is tested in flight.
- Delays in responses to commands have historically been principal causes of deficiencies in the handling qualities of high-

bandwidth control systems. Such deficiencies are generally not exposed in piloted simulations conducted during the preliminary design phase. Therefore, careful design and analysis are needed to anticipate and minimize unnecessarily long delays.

- Rotorcraft are especially susceptible to biodynamic interference effects because of high levels of rotor and structural vibration.
- Frequency-domain mathematical modeling and analysis are effective for development of the physical understanding needed to make practical high-bandwidth control systems.
- Block diagrams developed in the preliminary design phase must anticipate the numerous special elements of a practical digital system to reduce the heavy and costly reliance on redesign and optimization of design during the flight-testing phase.
- Emulation analysis (which involves an analog half-sample-period-delay approximation of the performance of an analog-to-digital converter) is useful in preliminary design and performance tradeoff studies, but direct digital analysis is necessary to evaluate accurately the many important high-frequency dynamic characteristics of a modern digital system.
- The methods of analysis presented in the report require the availability of flexible, in-

MAXIMUM PERFORMANCE



MINIATURE TRANSDUCER

INTRODUCING MODEL 2211 PRESSURE TRANSDUCER

Get high performance and a wide pressure range in one small transducer, Model 2211 from Teledyne Taber.

Only one inch in diameter, Model 2211 utilizes the flight-proven, time-tested design of Models 2210 and 2215. This hybrid unit is completely symmetrical providing excellent thermal stability, and is available in

pressure ranges from 15 to 50,000 PSI.

Options include compensation from -65°F to $+400^{\circ}\text{F}$ and internal or external shunt tracking FSO throughout compensated temperature range.

For more information on Model 2211 and the complete line of pressure transducers, contact us today!

TELEDYNE TABER

455 Bryant Street, N. Tonawanda, NY 14120
716/694-4000, TWX: 710/264-1264, Telecopier: 716/694-1450
Call Toll Free 1-800-333-5300

Hardware

IEEE interfaces for PC, AT, 386, PS/2, Macintosh, HP, SUN & DEC. Converters from IEEE to RS-232, RS-422, modem, Centronics, SCSI, digital I/O and analog I/O. IEEE extenders, expanders & buffers.

Software

IEEE device drivers for DOS, UNIX, Macintosh & SUN. Drivers for Lotus 1-2-3 & Symphony. Macintosh IEEE desk accessory. PC menu-driven analysis.

Support

Free applications support. 30 day money-back guarantee. Two year warranty. IEEE seminars available.

Call for your FREE Technical Guide**Demo disks & application notes available**

(216) 439-4091

Telex 6502820864 • Fax (216) 439-4093
 IOtech, Inc. • 25971 Cannon Road • Cleveland, Ohio 44146
 London (0734)861287 • Paris (1348)0178 • Milan (02)4120360
 Brussels (02)3849062 • Linköping (0131)10140 • Helsinki (90)5215288
 Munich (089) 710029 • Zürich (0182)19444 • Vienna (022)2253626
 Garmisch (0183035333 • Oslo (02)649670 • Copenhagen (02)804200
 Madrid (91)4027060 • Lisbon (01)41013420
 Melbourne (03)5793622 • Toronto (416)6740444



teractive computational tools.

This work was done by M. B. Tischler of Ames Research Center. To obtain a copy of the report, "Assessment of Digital Flight Control for Advanced Combat Rotorcraft," Circle 14 on the TSP Request Card. ARC-12187

Multiple-Baseline Interferometric Synthetic-Aperture Radar

Performances of spaceborne systems and effects of phase errors are discussed.

A report discusses the performances of spaceborne interferometric synthetic-aperture radar (SAR) systems in terms of the utility of SAR echo data in the generation of topographic maps. In the interferometric SAR (INSAR) approach, conventional digital SAR echo data taken along nearly-repeat ground tracks are combined coherently to synthesize interferometric SAR data. The resulting interferograms yield data on the height of the terrain in each picture element.

Airborne INSAR has already been shown to yield maps comparable with conventional topographic contour maps. The purpose of the report is to demonstrate the potential utility of INSAR in a spaceborne setting to obtain global coverage. To illustrate the concept, the report uses a set of SEASAT data on the Cottonball Basin of Death Valley, taken from five orbits that were close enough to each other so that adjacent ones approximated the two-antenna configurations of airborne SAR. The Cottonball Basin was chosen because it is dry and, therefore, was not expected to change significantly during the 3-week interval that contained the nearly repeating orbits. (Any change would increase phase noise.)

The report discusses the processing of the raw SEASAT data, including such problems as the registration of the separate complex-amplitude SAR images. The accuracy of the resulting topographical measurements is assessed.

Particular attention is given to phase-measurement errors, a mathematical model of which is described. The model has important implications for the design of future spaceborne INSAR. It shows among other things that, although the sensitivity in the measurement of altitude increases with the baseline separation, so does the phase error. Indeed, there appears to be an optimal baseline separation that balances these two opposing factors. The model is compared with interferograms synthesized from the data obtained at the various baseline separations (between orbits), and it is found to agree qualitatively with the interferometric data.

This work was done by F. K. Li and R. M.

Goldstein of Caltech for NASA's Jet Propulsion Laboratory. To obtain a copy of the report, "Studies of Multi-baseline Spaceborne Interferometric Synthetic Aperture Radars," Circle 97 on the TSP Request Card. NPO-17416

Detecting Impacts of Particles on Spacecraft

The locations and types of impacts would be determined electronically.


A report describes a proposed network of acoustical sensors — in effect, a miniature seismographic system — to detect impacts of particles on the external panels of a spacecraft. Inexpensive thin-film vibration sensors would be placed on the insides of the panels and would be connected to a relatively-simple data-collection system. The meteoroid shields already planned for the Space Station would serve as the panels on that spacecraft.

As many as 10 panels on the Space Station logistics module, each 1.4 meters square and containing typically 10 sensors, would be used to show the feasibility of the concept. An integrated-circuit chip for each sensor would convert its output into digital format and feed the output through a data buffer to a trigger circuit, which would select signals from neighboring sensors when a sensor produces a signal above preset level. The system would use the signals to locate the position of an impact and to calculate the characteristics of the impact, such as its amplitude in time and frequency, its rise time, and its phase spectrum. The Space Station panels would be recovered every 6 months so that the impact craters could be examined directly.

The report describes tests of the concept in which small spheres impinged on aluminum panels. The tests showed that the sensor data can be used to determine the locations and characteristics of impacts and that the panels provide a suitable medium for detecting the low-probability impacts of interest. However, the success of the method depends on the further development of data processing. In addition, more-sensitive sensors — perhaps embedded acoustic waveguides — will be needed to raise the probability of detecting impacts of 0.1 g/s above the present level of 0.3 per panel per 6-month period.

This work was done by Brian M. Lempriere, Robert L. Carlsen, and James M. Nelson of Boeing Aerospace Co. for Marshall Space Flight Center. To obtain a copy of the report, "Final Report, Task 5, Space Debris Measurement, Mapping and Characterization System, Space Station Integrated Wall Damage and Penetration Damage Control," Circle 141 on the TSP Request Card. MFS-28278

First, there was the vision...



Space exploration began with a vision.

The fire of imagination—fused with superior technical proficiency—leading the way to limitless possibilities. A special vision that creates the kind of breakthroughs that characterize GE Astro Space.

Since the nation's first space communications adventure nearly 30 years ago, GE Astro Space has been a world leader in the design and manufacture of satellites for government and commercial communications, meteorological, navigational and scientific use. And, with over one hundred and fifty satellites currently circling the globe—and long-term, history-making projects such as the *Space Station* and *Mars Observer*—we can offer Engineers the kind of rare opportunities that few are destined to realize.

If you're the visionary Engineer we're seeking, join us as we pave the way for a new generation of emerging space technology. Our mission requires the technical proficiency of **Design Engineers** with a minimum of 3 years experience in the following areas:

- Thermal Design/Analysis
- Launch Vehicle Integration
- Spacecraft Attitude Control
- Propulsion Systems
- Power Systems/Solar Arrays
- Spacecraft Harness Design

Our New Jersey location offers all the advantages of nearby Princeton—within easy access to New York City and Philadelphia. Additionally, selected positions are open in historic Valley Forge, PA. In either location, you'll experience a lifestyle that complements your career, providing unlimited opportunities for both personal and professional growth.


As the largest employer of engineers and scientists in the world, GE provides competitive salaries and exceptional benefits including tuition refund and continuing education programs—so your expertise is always current and expanding. We're a company anxious to meet Engineers who want to cross the engineering frontier. Rush your resume, in professional confidence, to: Employee Relations, Dept. NTB, GE Astro Space, P.O. Box 800, Princeton, New Jersey 08543-0800.



GE Astro Space
Cross the engineering frontier

An equal opportunity employer

Circle Reader Action No. 662



Physical Sciences

Hardware Techniques, and Processes

- 44 Reducing Heating in High-Speed Cinematography
- 44 Four-Mode Squeezing for Optical Communications
- 46 Spatial Modulation of Light in GaAs
- 48 Heat Flux Sensor for Hot Engine Cylinders

- 49 Achromatical Optical Correlator
- 50 Boundary-Value Problem for Magnetic-Cutoff Rigidities
- 51 Fast Laser Holographic Interferometry for Wind Tunnels

Books and Reports

- 52 Calculating Response of a Tunable-Diode-Laser Spectrometer
- 54 Research in Thermoelectronic Materials

Reducing Heating in High-Speed Cinematography

Simple filters are effective.


Lewis Research Center, Cleveland, Ohio

Infrared-absorbing and infrared-reflecting glass filters are simple and effective means for reducing the rise in temperature during high-speed motion-picture photography. High-intensity lights are needed, but the heat generated by the lights can be excessive, sometimes damaging the objects to be photographed and creating an unsafe working environment.

High-speed photography involves rates of about 4,000 frames per second. Most film sequences are finished in less than 10 s, but the greatest temperature rise above the ambient temperature occurs during that interval.

In an experiment, a thermocouple with a digital readout was used to measure the rise in temperature caused by radiation from a 300-W tungsten lamp when a heat-reflecting mirror (a "hot" mirror) or a heat-transmitting mirror (a "cold" mirror) was placed between the lamp and the thermocouple (see figure). With a hot mirror perpendicular to the rays from the lamp, the temperature rose from an ambient 76.4 °F to 129 °F (54 °C) within 10 s after the lamp had been switched on. Without the mirror, the temperature rose to 163 °F (73 °C). The hot mirror, which passes most of the visible spectrum but reflects most infrared light away, thus reduced the rise in temperature by 39 percent.

A hot mirror at an angle of 45° to the optical path was even more effective. It allowed the temperature to rise to only 121 °F (67 °C) — a reduction of 48 percent below the rise in the unfiltered case. A cold mirror, which reflects most visible light and



These "Hot-Mirror" and "Cold-Mirror" Configurations, often employed in projection of images, can also help prevent excessive heating of scenes by powerful lamps used in high-speed photography.

allows most infrared to pass, was tested at an angle of 45°. It allowed the temperature to rise to 106 °F (41 °C) at 10 s — a reduction of 66 percent below the rise in the unfiltered case.

A single hot or cold mirror in combination with a heat-absorbing glass produces an even greater reduction in the rise in temperature. At 10 s, the temperature was 98 °F (37 °C), representing a reduction of 75 percent in the rise in temperature.

This work was done by Howard A. Slater of Lewis Research Center. Further information may be found in NASA TM-100222 [N88-11100], "Reduction of Temperature Rise in High-Speed Photography."

Copies may be purchased [prepayment required] from the National Technical Information Service, Springfield, Virginia 22161, Telephone No. (703) 487-4650. Rush orders may be placed for an extra fee by calling (800) 336-4700. LEW-14798

Four-Mode Squeezing for Optical Communications

Quantum noise and vulnerability to nonquantum noise can be reduced.

NASA's Jet Propulsion Laboratory, Pasadena, California

Experiments have demonstrated the potential of four-mode squeezing (a special example of ultrasqueezing) for increasing the immunity to noise in fiber-optical com-

munication systems and interferometric devices. Four-mode squeezing reduces quantum noise more than does ordinary (two-mode) squeezing and provides partial

immunity to non-quantum-mechanical phase noise that arises in such media as optical fibers. Ultrasqueezing can be a strong effect, even in devices in which ordi-

NON-DESTRUCTIVE TESTING: NOBODY ELSE OFFERS SO MANY WAYS TO LISTEN.

The extensive use of composite parts in the aerospace industry has created a need for fast, reliable, cost-efficient methods of testing.

As a major user of composites, McDonnell Douglas had reason to become a leader in ultrasonic testing.

We've developed four highly effective, state-of-the-art ultrasonic testing systems for our own needs. These systems are now available to you.

AUSS-IV, our fourth-generation Automated Ultrasonic Scanning System, is a computer-controlled machine and data handling system that automatically checks parts for anomalies.

AUSS-V adds totally new robotic, data imaging, and computer automation dimensions to ultrasonic testing.

ADIS, our Advanced Data Acquisition, Imaging, and Storage System, can update existing inspection units to provide state-of-the-art data acquisition, imaging, and plotting capabilities. Other features include depth measurements, cross sections, and histograms.

And MAUS, our Mobile Automated Ultrasonic Scanner, allows fast, in-place inspection of composite parts. It can scan the surface of compound curvatures without any special attachments.

To find out more about our systems, and how they can help you increase productivity while reducing costs, call or write:

*McDonnell Douglas Aircraft Company,
Dept. 080, P.O. Box 516, St. Louis, MO 63166
(314) 232-7454.*



AUSS-IV The industry standard.



AUSS-V Adds new dimensions to ultrasonic testing.




ADIS Updates existing inspection units.



MAUS Provides fast, in-place inspection of composite parts.

MCDONNELL DOUGLAS



Four-Mode Squeezing is produced in this experimental apparatus by four-wave mixing in the optical fiber.

nary squeezing is a weak effect.

Four-mode squeezing in a fiber or other Kerr medium is the product of a four-wave mixing interaction. The transmitter is a pair of modulated oscillators, which pump a nonlinear medium at two well-separated optical carrier frequencies. (Two-mode squeezing involves pumping at a single optical carrier frequency.) The sidebands of each pump frequency interact with each other and with those of the other pump frequency. The resulting nonclassical four-mode correlations produce light that is squeezed in a quantum mechanical sense. The quantity measured by a dual-frequency homodyne detector has smaller fluctuation than would be measured with light from a perfectly stable (except for quantum fluctuations) laser or with no light at all; i.e., vacuum.

The figure illustrates schematically an apparatus used in fiber experiments of four-mode squeezing. The oscillator signals were at the 647-nm and 676-nm laser wavelengths of singly ionized krypton. Both signals were coupled into a 114-m single-mode optical fiber, a nonlinear Kerr medium. The fiber was maintained at a temperature of 2 K to suppress thermal noise. A resonant phase modulator was used to

broaden the spectrum of each oscillator signal to avoid the stimulated Brillouin effect. (The strong phase modulation did not interfere with the squeezing because the relative phases of all significant excitations were preserved.) Typical power levels at the exit of the fiber were 140 to 160 mW at 647 nm and 50 to 60 mW at 676 nm.

After passing through the fiber, the two wavelengths were separated by a prism. One of the wavelengths was incident directly on photodiode D_1 in a heat sink. The other wavelength was reflected from a phase-shifting cavity (optical phase shift Φ), then detected by photodiode D_2 . The signals from both photodiodes were amplified, and the amplified signal from D_2 was subjected to a variable electrical phase shift ϕ before the currents from the two amplifiers were combined.

Experimental runs were distinguished by whether the less powerful beam (type I run) or the more powerful beam (type II run) was directed toward the phase-shifting cavity and detector D_2 . The combined detector outputs in the both types of runs exhibited four-mode squeezing, with the noise dipping to 20 ± 2 percent below the vacuum level. The type II runs gave more dramatic evidence of the effect of four-

mode over two-mode cancellations in producing the noise reduction. When $\phi = 0$, the parametric-mixing interaction responsible for two-mode squeezing reduced the net noise level near the optical phase of the four-mode-squeezing minimum, while when $\phi = \pi/2$, these effects opposed each other.

Phase noise due to thermal fluctuations of the index of refraction of the fiber, which is the major obstacle to the observation of four-mode squeezing, was minimized by choosing the optical phase shift Φ , the oscillator powers, and the amplifier gains so that the negative correlation between the two photocurrents predominated over the thermal phase-noise contribution from D_2 . Under these conditions, appreciable suppression of quantum noise due to four-mode squeezing could be observed.

This work was done by Bonny L. Schumaker of Caltech for NASA's Jet Propulsion Laboratory. For further information, Circle 58 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, NASA Resident Office-JPL [see page 14]. Refer to NPO-17170.

Spatial Modulation of Light in GaAs

An image is transferred from one beam of light to another.

NASA's Jet Propulsion Laboratory, Pasadena, California

The spatial modulation of light in gallium arsenide (GaAs) has been demonstrated by transferring an image from one of two coherent, crossing beams of light to the other one. The technique relies on cross-polarization beam coupling, which is a special case of beam coupling in a photorefractive crystal.

In the ordinary beam-coupling process, two beams intersect in a crystal of GaAs, which is photorefractive. The resulting interference pattern gives rise to a periodic distribution of trapped electrical-charge

carriers, the electric field of which varies the local index of refraction via the electro-optical effect. Thus, a refractive-index grating is formed, and it diffracts the beams of light in such a way that one of the diffracted beams interferes constructively with its incoming beam while the other interferes destructively with its incoming beam. The result is a net transfer of energy from one beam to the other. However, diffracted beams cannot be separated from the passing-through beams.


The image is transferred in a GaAs crys-

tal via cross-polarization beam coupling. The crystal is oriented so that the components of the electric fields of the two beams that lie in the plane of the two electro-optical axes bisect the angle between the two axes. The electric field of each beam can be decomposed mathematically into two equal components, each parallel to one of the two axes. Because the changes in the index of refraction along the two axes are equal in magnitude but opposite in sign, the diffracted beam of one component of a beam interferes constructively with that beam, while that of the other component interferes destructively. This causes the electric field of the resultant diffracted beam to rotate 90° from that of the incoming beam, resulting in a polarization rotation in each beam after the crystal. There is

REDUCING MAINTENANCE COSTS.

We're integrating a Depot Maintenance Management Information System (DMMIS) that will satisfy the unique requirements of seven Air Force logistics facilities. This system will schedule production, control workflow, forecast resource needs, and evaluate performance. It also will monitor the maintenance status of 865 aircraft, 1200 missiles and weapons systems, 6400 engines and 840,000 components and parts. The result: reduced repair turnaround, labor costs, and material handling expenses. For more information, contact Grumman Data Systems, 2850 Presidential Drive, Fairborn, OH 45324. Or call (513) 427-6600.


GRUMMAN



GRUMMAN

Data Systems

Circle Reader Action No. 363



An **Image Is Transferred** from one coherent beam of light to the other by crossbeam coupling, a product of the photorefractive effect in the GaAs crystal.

no net transfer of energy from one beam to the other. The diffracted component of each beam is separated from the beam by a polarizer. Then the transferred image in the diffracted component is observed.

The figure illustrates schematically a cross-polarization beam-coupling apparatus. The crystal is undoped GaAs grown by the Czochralski technique. Two coherent beams polarized along the [010] axis of the crystal are generated by a YAG:Nd laser. One beam passes through a transparent

slide that bears the letters "JPL." The polarizer can be adjusted to produce either a positive or a negative of the image on the slide.

This work was done by Li-Jen Cheng, Gregory Gheen, and Afshin Partovi of Caltech for NASA's Jet Propulsion Laboratory. For further information, Circle 102 on the TSP Request Card.

In accordance with Public Law 96-517, the contractor has elected to retain title to this invention. Inquiries concerning rights

for its commercial use should be addressed to

*Edward Ansell,
Director of Patents and Licensing
Mail Stop 301-6
California Institute of Technology
1201 East California Boulevard
Pasadena, CA 91125*

Refer to NPO-17228, volume and number of this NASA Tech Briefs issue, and the page number.

Heat-Flux Sensor for Hot Engine Cylinders

A small, rugged unit gives accurate data in a harsh environment.

Lewis Research Center, Cleveland, Ohio

A heat-flux sensor includes a buried wire thermocouple and a thin-film surface thermocouple, both made of platinum and platinum with 13 percent rhodium. The sensor is intended for use in a ceramic-insulated, low-heat-rejection diesel engine at temperatures of about 1,000 K.


The body of the sensor is an iron plug. One end of the plug is coated with yttria-stabilized zirconia. Thin films of Pt and 0.87 Pt/0.13 Rh are then sputter-deposited on the zirconia layer through a metal mask so that they form slightly overlapping circles (see figure). The relatively-large nonoverlapping area allows ample space for welding lead wires (and rewelding, if necessary) and for testing the adherence of the films without damaging the thermocouple junction. The circular configuration helps to minimize concentration of stress in the films. The wire thermocouple is embedded in the core of the plug.

Procedures have been established for preparing the surface of the plug, sputtering the films, and welding the lead wires in ways that maximize the adherence of the various layers. First, a bonding coat is applied to the plug. The zirconia is plasma-sprayed on the bonding coat, chemically cleaned in solvents in ultrasonic baths, baked, plasma-etched, and covered with an electrically insulating alumina bonding coat 2 μm thick. The platinum and plati-

num/rhodium films are sputtered to depths of 5 and 3 μm , respectively. The insulated

lead wires are exposed at their tips and attached to the films by a parallel-gap welder.

A prototype sensor performed reliably in engine tests for 10 hours at mean surface temperatures up to 950 K. When the maximum combustion-cycle temperature rose above 1,150 K, however, the all-platinum



A **Thermocouple Junction** that resists the environment in the cylinder of an advanced high-temperature diesel engine is created by depositing overlapping films of Pt and 0.87 Pt/0.13 Rh on an iron plug. The plug also contains an internal thermocouple.

film developed blisters. The adhesion of this film may be improved by deposition of a layer of platinum oxide 300 μm thick under the platinum film.

This work was done by Walter S. Kim, Richard F. Barrows, Floyd A. Smith, and

John Koch of **Lewis Research Center**. Further information may be found in NASA TM-100798 [N88-18892], "Prototype Thin-Film Thermocouple/Heat-Flux Sensor for a Ceramic-Insulated Diesel Engine."

Copies may be purchased [prepayment

required] from the National Technical Information Service, Springfield, Virginia 22161, Telephone No. (703) 487-4650. Rush orders may be placed for an extra fee by calling (800) 336-4700. LEW-14830

Achromatical Optical Correlator

The signal-to-noise ratio should exceed that of a monochromatic correlator.

NASA's Jet Propulsion Laboratory, Pasadena, California

An experimental optical image-correlating device is illuminated by multiple-pinhole diffraction of dispersed white light instead

of the monochromatic, coherent light usually employed in holographic systems. The use of noncoherent light is expected to in-

crease the signal-to-noise ratio by reducing the component of noise attributable to the unwanted component of interference in




Figure 1. The **Achromatical Optical Correlator** uses multiple-pinhole diffraction of dispersed white light to form superposed multiple correlations of the input and reference images in the output plane.

A Scientific MIRACLE...



and a
Work
Of
Art

EcoSphere

The world's first totally enclosed ecosystem. Originally developed by NASA, EcoSpheres are not only prototypes of future space colonies, but also elegant reminders of the potential for ecological balance on Earth. This carefree aquarium — a permanently sealed glass globe — contains live shrimp, algae, water, and air in bioregenerated balance. \$79.00 each plus shipping.

Rush me _____ EcoSpheres at \$79.00 each plus \$12.00 for overnight delivery. Total enclosed: \$ _____

Name _____

Address _____

City _____ State _____ Zip _____

Mail with payment to: NASA Tech Briefs, Dept. F
41 East 42nd Street, New York, NY 10017



**the right
environment**
for exceptional results...
both military and commercial

Blue M's line of quality environmental testing systems includes an exceptionally broad range of temperature/humidity cabinets, air-to-air and liquid-to-liquid thermal shock chambers, plus high/low temperature cabinets that cover a spectrum from -73 C to +204 C. All are available with control capabilities that run the gamut of testing needs. Let us help you create the right type of environment for your application.

For more information write, call or FAX: Blue M, A Unit of General Signal, Blue Island, Illinois 60406. Phone 312-385-9000 • FAX 312-331-2515.



789

coherent light. Furthermore, noncoherent illumination is suitable for applications involving the recognition of color and the determination of scale. When fully developed, achromatic correlators are likely to be useful for the recognition of patterns; for example, in industrial inspection and the search for selected features in aerial photographs.

The achromatic correlator is illustrated schematically in Figure 1. White light is condensed onto a pinhole, then converted by two lenses and a grating into a horizontal-line spectrum. A sampling mask is placed so that a horizontal linear array of pinholes lies in the line spectrum. Thus, each pinhole acts as a point source of light over the narrow range of wavelengths that illuminates it.

The light from the pinholes is recollimated into multiple plane waves of different tilts and passed through the input plane, which contains a transparency of the image to be tested. A lens then focuses the light into multiple discrete Fourier spectra of this input image, each such spectrum being the Fourier transform of the input object at the wavelength of one of the pinhole sources.

Essential to the achromatic correlator is a set of matched spatial filters. Each such filter contains the Fourier transform, at the wavelength of one of the pinhole sources, of a scaled version of the reference image with which the input image is to be compared. Provided that the set of matched spatial filters is aligned correctly in the Fourier-transform plane, the image formed in the output plane is a superposition of the correlations between the input and reference images at the wavelengths of the pinholes.

The matched spatial filters are made by using a laser to make a Fourier hologram




Figure 2. The **Set of Matched Spatial Filters** is made by a multiple-exposure holographic process, each exposure using a suitably-scaled input image and a suitable angle of the reference beam. The recording-aperture mask is translated to the appropriate horizontal position for each exposure.

at the Fourier-transform plane as shown in Figure 2. For this process, the input image to produce the filter for each pinhole wavelength is the reference image scaled by the ratio of the laser wavelength to the wavelength at the pinhole. A pivotable mirror is used to tilt the reference beam to the angle

appropriate to this wavelength.

This work was done by Tien-Hsin Chao and Hua-Kuang Liu of Caltech for NASA's **Jet Propulsion Laboratory**. For further information, Circle 33 on the TSP Request Card. NPO-17206

Boundary-Value Problem for Magnetic-Cutoff Rigidities

Field equations can yield an overview of motions of many charged particles.

NASA's Jet Propulsion Laboratory, Pasadena, California

An alternative approach has been developed for the calculation of the magnetic cutoff rigidities of electrically-charged particles in a static magnetic field. In contrast with the conventional formulation, in which the trajectories of particles are traced by solution of the equations of motion, the new formulation involves a partial differential field equation that is treated as a boundary-value problem. In this approach, the tracing of trajectories is needed only to supply boundary conditions.

"Rigidity" is used here in the astrophysical sense meaning the ratio of momentum of a particle to its electrical charge. Typically, the rigidities of particles arriving at a given location from a given

direction can be grouped into bands of rigidities, within which the particles cannot escape to infinity, and outside of or between which they can escape to infinity. "Cutoff rigidity" denotes the least upper bound or the greatest lower bound of such a band. Thus, the calculation of cutoff rigidities is important in such endeavors as estimating the degree to which magnetic fields could protect spacecraft from solar-flare particles, designing experiments in atomic physics, and extracting energy from nuclear-fusion reactions.

The mathematical development begins with the basic equation of motion of a relativistic charged particle in a magnetic field. The rigidity is substituted for the

momentum in this equation to obtain a differential equation in terms of the rigidity, the magnetic field, and displacement along the trajectory. Another differential equation is introduced to express the constancy of rigidity along the trajectory. The foregoing equations are combined and manipulated to yield two alternate forms of the partial differential field equation for the cutoff rigidity:

$$\hat{\mathbf{P}} \cdot \nabla_x F + (\hat{\mathbf{P}} \times \mathbf{B}) \cdot (P/F) \nabla_p F = 0$$

and

$$\hat{\mathbf{P}} \cdot [\nabla_x F + \mathbf{B} \times (P/F) \nabla_p F] = 0$$

where P is the rigidity (magnitude of the rigidity vector $P\hat{\mathbf{P}}$), $\hat{\mathbf{P}}$ is the unit vector tangent to the trajectory in the direction of the

rigidity, F is the cutoff rigidity, ∇_x is the gradient operator in position space, ∇_p is the gradient operator in rigidity space, and $\mathbf{B}$ is the magnetic-flux-density vector.

Once the field equation is supplemented by boundary conditions, and subject to requirements of existence and uniqueness of solutions, a solution should be obtainable. When the magnetic field is axisymmetric (e.g., in a cylindrical solenoid or in a dipole approximation of the magnetic field of the Earth), the equations can be simplified considerably when one considers the generalized Störmer cutoff. It can be shown that

the vertical cutoff, which is the generalized Störmer cutoff evaluated in a direction perpendicular to magnetic east, is constant on a magnetic-field line. This means that the cutoff can be evaluated at an arbitrary location by following the magnetic-field line that passes through that location until it intersects a surface on which the cutoff has been specified as a boundary condition.

Analytic solutions for the cutoffs can be obtained for a large class of problems with axial symmetry. A procedure for finding the magnetic field that provides the best pro-

tection against charged particles, subject to a certain kind of constraint, has been derived. Each application of this procedure yields an inequality that can be used as an upper-bound estimate of the protection that can be provided by a given axially-symmetric magnetic field.

This work was done by Larry D. Edmonds of Caltech for NASA's Jet Propulsion Laboratory. For further information, Circle 25 on the TSP Request Card.
NPO-17294

Fast Laser Holographic Interferometry for Wind Tunnels

Holograms would be made rapidly in situ.


Ames Research Center, Moffett Field, California

A proposed system would make holographic interferograms quickly in wind tunnels. The holograms would reveal two-dimensional flows around airfoils and would provide information on distributions of pressure, the structures of wake and boundary layers, and the density contours of flow fields. Some of the technology needed to build the system is already available. With a concerted effort, a prototype system could be developed in about 2 years.

Because a wind tunnel is a high-vibration, noisy environment, the optics would be mounted on vibration-isolated tables. A laser having a pulse duration very short compared with the vibration period would be used, and the laser would have to be stable — its beam should not wander, and its intensity should remain constant from shot to shot. A neodymium:yttrium-aluminum garnet (Nd:YAG) laser operating at 5,300 Å with 100-ns pulses is a likely candidate.

Recording, processing, and reconstruction of the hologram would be done in place (see figure). The holograms could be formed on photographic film or plates in a commercially-available, self-contained wet-developing unit. Even better, the holograms could be formed in thermoplastic plates in a modified version of a commercially available thermoplastic holocamera. Based on a dry process in which the hologram is developed by heating, the holocamera can produce reconstructed images in less than a minute, instead of the hours required for the usual wet development followed by reconstruction of the image in a laboratory away from the wind tunnel. Moreover, vibration can be compensated simply by adjusting the position of one of the thermoplastic plates in the holocamera.

The system would process and analyze images quickly. A semiautomatic microcomputer-based desktop image-processing unit now undergoing development will be



Holograms Would Be Formed Quickly in thermoplastic plates in a wind tunnel. The plates would be rigid and left in place so that neither vibrations nor the photographic-development process would degrade the accuracy of the holograms.

moved easily to the wind tunnel, and its speed and memory will probably be adequate for flows about airfoils. A fully automatic minicomputer-based image processor also undergoing development will incorporate expert-system computer programs to detect fringes, determine the orders of fringes, enhance pictures when necessary, and eliminate noise. An expert-system rules base is now being developed;

when complete, it will draw on domain-specific knowledge, relate to past experience, use information from each step of the analysis to select the next step, and make intelligent guesses.

This work was done by George Lee of Ames Research Center. For further information, Circle 156 on the TSP Request Card.
ARC-11840

Books and Reports

These reports, studies, handbooks are available from NASA as Technical Support Packages (TSP's) when a Request Card number is cited; otherwise they are available from the National Technical Information Service.

Calculating Response of a Tunable-Diode-Laser Spectrometer

The response function is calculated from measurements by an iterative deconvolution procedure.

A report describes measurements made with a tunable-diode-laser spectrometer and the processing of the measurement data to calculate the response function, which characterizes the component of broadening in the measured spectral peaks due to the spectrometer itself. This broadening results from instabilities in the diode-laser output frequency. By use of a procedure developed to enhance the resolution of spectra and described in a previous publication, the response function is deconvolved from the spectral measurements. The procedure is fast and simple enough to be used to make routine

corrections for broadening in diode-laser spectrometers.

In the experiments, two tunable-diode stripe-geometry lasers in a cold head on a vibration-isolation mount were used to cover the spectral regions around wavelengths of 5.8 and 7.5 μm . Rotational/vibrational absorption spectra of CH_4 and HNO_3 were measured in two ways: averaging of multiple scans by the sweep integration technique and by a lock-in amplifier coupled to an x-y chart recorder for conventional phase-sensitive detection. Pressures were kept in the range of 10 to 50 mtorr (1.3 to 6.7 Pa) to minimize pressure broadening and were adjusted to yield absorptances of 10 to 40 percent at the centers of the rotational/vibrational peaks. A relative-frequency scale was provided by recording the pattern of interference fringes from a solid 7.62-cm Ge etalon. The relative positions of the spectral peaks of CH_4 , which are known to within a wave number of 10^{-4} cm^{-1} , were used to confirm the free spectral range (0.016 cm^{-1}) of the etalon.

The measured (broadened) absorption spectrum $A_m(\nu)$ is given by

$$A_m(\nu) = \int_{-\infty}^{\infty} A_t(\nu') R(\nu - \nu') d\nu'$$

where ν and ν' are frequencies or wave numbers, A_t is the true absorption spec-

trum of the gas, and $R(\nu - \nu')$ is the desired time-independent response function of the spectrometer. Because a reference gas (CH_4 or HNO_3) of known spectral characteristics is used, one can calculate $A_t(\nu')$ from the known absorption lines and the Doppler-broadening function for the wavelength of the line and the temperature and molecular weight of the gas.

The algorithm for the deconvolution of the response function from the measurements involves sampling at 15 to 25 points over the half width at half maximum of an absorption peak. Typically, averaging the data from 512 sweeps proved sufficient to yield a signal-to-noise ratio of ~ 400 . The signal-to-noise ratio was limited to ~ 500 by the 9-bit resolution of the signal averager. Smoothing-filter subalgorithms were applied to the data before and during deconvolution to suppress high-frequency noise.

The response functions calculated for various laser modes had half widths at half maximums ranging from 25 to 35 MHz and had shapes ranging from Gaussian to roughly trapezoidal. A Gaussian shape would be expected where the broadening is due to random phenomena like acoustical vibrations or noise in the diode current. In the absence of such broadening mechanisms, the output frequency spectrum of the tunable-diode laser would be expected to be Lorentzian, with a width 1 to 2 orders

THE FIRST FAMILY IN LINEAR MOTION:



**AUTOMATION
GAGES, INC.
BALL AND
ROLLER SLIDES**

**NOW
63 MODELS
AVAILABLE
FROM STOCK
FOR IMMEDIATE
DELIVERY!**

When it comes to smooth, precise linear motion, come to the original: Automation Gages. We're the experts in ball and roller slide assemblies. In fact, AG invented the patented single wedge pre-load adjustment technique which permits perfect adjustment with one screw and eliminates all play and backlash. For durability, repeatability, and long term value, AG ball and roller slides have no competition.

AG offers nine basic lines and a total of 63 models available from stock. Travels range from $\frac{1}{2}$ " to 15" for light, medium and heavy duty applications. And if AG doesn't have exactly what you need, we'll design and manufacture it for you to your

specifications.

In addition to ball and roller slides, AG has positioning and measuring stages and accessories, all available with a phone call. For the best in linear motion, call the first family, Automation Gages, first.

WRITE OR CALL FOR FREE CATALOG

"got a problem...call"

1-800-922-0329. IN NEW YORK STATE, CALL 716-544-0400

CALL FOR AREA DISTRIBUTORS NEAREST YOU

AUTOMATION GAGES, INC. 850 HUDSON AVENUE ROCHESTER, NY 14621

Dept. 247



THE CHALLENGE: "MACHINE HIGHLY COMPLEX AEROSPACE COMPONENTS WITH PRECISE REPEATABILITY. AND REDUCE COSTS SIGNIFICANTLY."

We were able to meet this challenge because at Howmet we work closely with our customer-partners. Our engineer-to-engineer approach allows us to take charge from concept through prototype to finished product and provide our customers with capabilities our competitors can't match.




ECM equipment is integrated with customer CAD/CAM data.

GREATER DESIGN FREEDOM AND COST EFFECTIVENESS. At our New England Aircraft Products Division, in Farmington, CT, we produce airfoils up to 14" in length by electrochemical machining (ECM). As a "stress-free" process, ECM permits thinner, more complex shapes which are otherwise extremely costly or impossible to manufacture. And our CAD/CAM technology permits your design to be duplicated precisely. With no final polishing required and a low scrap rate, manufacturing costs are reduced as much as 10%.

ECM'd fan and compressor blades for P&W jet engines.


Howmet's Winsted Machining Center, in Winsted, CT, specializes in small to medium airfoils. Our state-of-the-art encapsulation system and CNC continuous dress creep feed grinders triple the removal rates while improving accuracy and throughput.

At Whitehall, MI, our Whitehall Machining Division specializes in medium to large airfoils and integral nozzles and rotors. We also run small lots and prototype work, offering fast turn time and low cost for special needs. Our creep feed grinders reduce machining time while increasing precision and flexibility.



CNC-controlled YAG laser performs cutting, welding and drilling.

IMPOSSIBLE? CHALLENGE US. At Howmet, we employ the most advanced technologies to meet the strict requirements of our customer-partners. We will work closely with you, engineer to engineer, to



These retainers plates are typical of our precision-machined hardware.

bring your product cost-effectively from prototype work into production. For more information on our machining capabilities, write our Sales Department, Howmet Corporation, 475 Steamboat Road, Greenwich, CT 06836-1960. Or phone the Sales Manager at New England Aircraft Products Division, (203) 677-1376, Whitehall Machining Division, (616) 894-5686, or Winsted Machining Center, (203) 379-3314.



Partners. Challenge by Challenge.

New England Aircraft Products Division,
Farmington, CT
Whitehall Machining Division, Whitehall, MI
Winsted Machining Center, Winsted, CT

of magnitude below the widths observed. In this case, the broadening was attributed to noise in the diode current, caused in part by electromagnetic interference from nearby laboratory equipment and by acoustical shocks associated with the piston movement in the closed-cycle cooler.

This work was done by Randy D. May of Caltech for NASA's Jet Propulsion Laboratory. To obtain a copy of the report, "Response Function of a Tunable Diode Laser Spectrometer From an Iterative Deconvolution Procedure," Circle 37 on the TSP Request Card.
NPO-17375

Research in Thermoelectric Materials

Knowledge of microstructures is necessary for further improvements.

A report reviews current research in thermoelectric materials with a view toward the development of materials of greater energy-conversion efficiency. These substances are generally fine polycrystalline conglomerates of high-temperature semiconductors, formed by such standard ceramic-making techniques as the hot pressing of the fine powders of elemental constituents or prereacted powders. The properties depend on the constituents and the fabrication

process, which affect the microstructure. The emphasis in the report is on the effort to understand and manipulate the microstructure to increase the thermoelectric figure of merit, Z .

The thermoelectric properties of three broad categories of materials are discussed. The first category includes the alloys of group IV elements like silicon and germanium, which have large energy gaps, high chemical stability, and high melting temperatures that make them suitable candidates for high-temperature thermoelectric generation of power.

Si/Ge alloys are the materials of choice for operation at temperatures up to 1,300 K. The suitable heat treatment of $\text{Si}_{0.8}\text{Ge}_{0.2}$ doped with GaP has resulted in a Z as high as $1 \times 10^{-3} \text{ K}^{-1}$. Analysis of the microstructure has shown that these alloys are quite inhomogeneous — a property that may be essential to improved performance.

The second category is the rare-earth chalcogenides. These compounds have the general chemical formula R_{3-x}X_4 ($0 < x < 1/3$) and the crystalline structure of ThP_4 and are important thermoelectric materials because of their high melting temperatures, capabilities for self-doping, and low thermal conductivities. In $\text{La}_{3-x}\text{Te}_4$, a Z as high as $1 \times 10^{-3} \text{ K}^{-1}$ has been achieved. The optimum Z appears to occur at $x \approx 0.2$, but analysis of the microstructure

shows that the exact value of x cannot be defined, partly because of the presence of La_2O_3 . Consequently, a reproducible, high- Z material cannot be made until contamination by oxygen can be controlled or eliminated.

The third category includes the narrow-band semiconductors, especially the boron carbides, in which electrical conduction occurs by the hopping of quasi-free charge carriers in the form of small polarons. The boron carbides are preferred for operation at temperatures up to 2,000 K. A p-type Z as high as $5 \times 10^{-4} \text{ K}^{-1}$ has been achieved at a temperature of $\sim 1,200 \text{ K}$, with the promise of a higher Z at 2,000 K. The degree of microstructural and compositional disorder appears to influence the thermoelectric properties strongly. Knowledge of the disorder through analysis of the microstructure and correlation of the foregoing with transport properties is essential to further progress with the boron carbides.

This work was done by Charles Wood of Caltech for NASA's Jet Propulsion Laboratory. To obtain a copy of the report, "Materials Problems in High Temperature Thermoelectric Energy Conversion," Circle 103 on the TSP Request Card.
NPO-17403

NAG®

Numerical Algorithms Group

NAG Fortran Library products enable you to spend your time and talents on genuine problem solving, not software development. 200 experts, recognized worldwide as the leaders in their fields, create the solutions in the NAG Library. The accuracy, performance, and total capabilities of NAG software are unmatched in the industry. Take advantage of NAG's expertise in any of these fine products:

NAG FORTRAN LIBRARY

More than 700 user-level routines covering the principal areas of mathematics and statistics. Available on over 90 different computers from PC's to supercomputers.

NAG ONLINE SUPPLEMENT

An interactive query system enabling the user to make maximum use of the NAG Library. The Online system provides hints on choice of routines, syntax assistance, and other forms of help.

NAG Ada Library

The first commercially available math library designed and written completely in Ada. Shortens the development cycle for embedded math operations in Ada programs.

NAG GRAPHICAL SUPPLEMENT



A convenient and versatile means for displaying numerical results generated by the Library. A facility not available with other libraries.

NAG VECPAR_77

An interactive CASE tool for vectorizing and parallelizing Fortran programs. Attain performance improvements beyond what optimizing compilers may provide. Ideal for "rejuvenating" older applications.


GENSTAT and GLIM

Interactive statistical analysis systems used for data exploration, linear modelling, time series analysis...useful applications in statistical quality control and product survival analysis.



THE NAG PRODUCT LINE OFFERS NUMERICAL AND GRAPHICAL ALGORITHMS FOR MANY SCIENTIFIC AND ENGINEERING APPLICATIONS INCLUDING:

- SIGNAL PROCESSING
- OPERATIONS RESEARCH
- APPLICATIONS DEVELOPMENT
- COMPUTATIONAL CHEMISTRY
- ECONOMETRIC MODELS
- STATISTICAL ANALYSIS



Double Assurance

**MONITORING BOTH THE PRODUCT AND
PROCESS MEANS NEW LEVELS OF ASSURANCE
IN AEROSPACE ALUMINUM.**

STATISTICAL PROCESS CONTROL

There are two big hurdles in manufacturing aerospace-grade aluminum.

The first is meeting the industry's rigid specs.


The other is making sure that quality is consistent.

The problem with taking a sample from a coil of aluminum is that up until now, there's been no way to be confident that the sample is representative of the whole.

Well, all that's changed.

Kaiser has revamped its Trentwood, Washington plant to produce aluminum with a quality and consistency unsurpassed by any other supplier.

Using the latest advances in electronics and monitoring technology, we not only test the finished product, we monitor the aluminum-making process every step of the way using real-time statistical analysis. Kaiser personnel measure continuously, analyze the product, and make



Production personnel can see at a glance what is happening in process with Kaiser's unique "scorecard," which shows the history of each order run through the mill, turning SPC data into a graphic presentation.

on-line adjustments.

To the aerospace company, this means, for instance, when you review specs for gauge and flatness, you're assured they apply consistently across the entire plate or coil.

No wonder aluminum from Kaiser Trentwood is the premier product within the aerospace industry. Quality is doubly assured because we bring the latest methods of quality man-

agement to both the process and the product.

To learn more, contact Kaiser Aluminum, 300 Lakeside Drive, Oakland, CA 94643. (415) 271-3300.

**KAISER
ALUMINUM**

ALUMINUM FOR THE 21ST CENTURY

Circle Reader Action No. 353

STATISTICAL EXPERIMENT DESIGN

Stat-Ease makes it easy for you to use statistically designed experiments. We offer two menu-driven programs that combine power and ease of use:

DESIGN-EASE™ software for two-level factorial, fractional factorial and Plackett-Burman designs. (\$300)

DESIGN-EXPERT™ software for response surface (central composite and Box-Behnken) and mixture (simplex and extreme vertices) designs. (\$495)

These programs help you choose, set up and analyze experimental designs. They run on IBM personal computers and compatibles.

To purchase or receive more information contact:

Stat-Ease, Inc.
4108 Aldrich Ave. So.
Minneapolis, MN 55409
(612) 822-5574

STAT-EASE
INC.

Site license, quantity discount,
training, consulting also available.

Circle Reader Action No. 393



OUTER SPACE ADVENTURE

Experience the thunderous power of Space Shuttle launches, bouncing moon walks, and weightless space ballet — all in the action-packed VHS videotape **SPACE SCAPES**, featuring rare footage gleaned from NASA's film archives. This visual treat is set to the award-winning music of Jan Hammer. (Color, 30 minutes) Only \$19.95 each plus \$3.00 postage and handling.


Name _____
Address _____
City _____

State _____ Zip _____

Total Enclosed: \$ _____
for _____ (quantity) Space
Scapes videotapes.

Send check or money order to:

NASA Tech Briefs, Dept. F
41 East 42nd St.
New York, NY 10017



Materials

Books and Reports

- 56 PMR Resin
Compositions for High
Temperatures
- 56 Electrochemical
Studies of Aluminum
Coated With Primer

- 58 Rapid Annealing of
Amorphous
Hydrogenated Carbon
- 60 Measuring Mechanical
Properties of Optical
Glasses

Books and Reports

These reports, studies, handbooks are available from NASA as Technical Support Packages (TSP's) when a Request Card number is cited; otherwise they are available from the National Technical Information Service.

PMR Resin Compositions for High Temperatures

One composition showed no deterioration in mechanical properties after 200 hours at 700 °F (371 °C).

A report describes experiments to identify polymer matrix resins suitable for making graphite-fiber laminates that could be used at 700 °F (371 °C) in such applications as aircraft engines to achieve higher thrust-to-weight ratios than are now possible. Two particular high-molecular-weight formulations of PMR (polymerization of monomer reactants) resins appear to be the most promising.

In the experiments, neat resin moldings were prepared with various monomer reactants and screened for thermo-oxidative stability at a temperature of 700 °F (371 °C) in air under both ambient pressure and 4 atmospheres (0.4053 MPa) of pressure. The resins that exhibited the best overall balance of processability, glass-transition temperature, and thermo-oxidative stability were used to prepare unidirectional-graphite-fiber laminates. The laminates were evaluated for thermo-oxidative stability and mechanical properties.

Each of the resins contained a dimethyl ester and the monomethyl ester of 5-norbornene-2,3-dicarboxylic acid (NE), and some resins contained one or two diamines. The stoichiometric proportions of the reactants used in each resin were $n:(n+1):2$, where n = the number of moles of dimethyl ester, $n+1$ = the number of moles of diamine, and the number of moles of NE was 2. The formulated molecular weights (FMW's) of the end-capped prepolymers prior to final curing of the resin ranged from 1,270 to 7,500.

The formulation of the most promising resin, designated PMR-II-30, was a dimethyl ester of 4,4'-(hexafluoroisopropylidene)-

bis(phthalic acid), p-phenylenediamine, and NE in the mole ratio of 5:6:2. After an exposure to air for 200 hours at a temperature of 700 °F (371 °C) and a pressure of 4 atm (0.4053 MPa), laminates made with this resin showed no decrease in interlaminar shear strength or flexural strength and had a weight loss of only 11 percent.

In general, the experiments showed that the PMR compositions of higher FMW exhibit enhanced thermo-oxidative stability. The formation of high-quality laminates with these compositions requires the use of curing pressures higher than those suitable for the compositions of lower FMW.

This work was done by Raymond D. Vannucci of Lewis Research Center. Further information may be found in NASA TM-88942 [N87-16071/NSP], "PMR Polyimide Compositions for Improved Performance at 371 °C."

Copies may be purchased [prepayment required] from the National Technical Information Service, Springfield, Virginia 22161, Telephone No. (703) 487-4650. Rush orders may be placed for an extra fee by calling (800) 336-4700.
LEW-14658

Electrochemical Studies of Aluminum Coated With Primer

The ac-impedance method is used to investigate corrosion rates and mechanisms.


A technical paper describes experiments using the ac-impedance method of analyzing the corrosion of metal surfaces and the breakdown of protective coatings. Direct-current methods, in use for at least 15 years, enable the quick determination (30 to 60 minutes) of corrosion currents that translate into corrosion rates of mils per year (1 mil/yr $\approx 8 \times 10^{-13}$ m/s). Alternating-current-impedance scans provide more detailed information, which can indicate changes in corrosion rates, progressive deterioration of coatings, changes in metal surfaces, and reaction mechanisms. Moreover, changes in the conditions of coatings can be detected by the ac method before dc methods show an increase in metal-corrosion current.

After centuries of practice, mankind perfects engineering calculations: MathCAD.

Announcing MathCAD 2.5: The Dawn of a New Age.

What the historians will call it, only time will tell.

Perhaps the Century of Speed, or the Era of Ease. But whatever the name, this is the age of MathCAD 2.5, the only math package that looks and works the way you think.



MathCAD 2.5 includes 3-D plotting, HPGL sketch import, and PostScript output.

MathCAD is far and away the best-selling math package in the world. Because it lets you perform engineering and scientific calculations in a way that's faster, more natural and less error-prone than the way you're doing them now—whether you're using a scratchpad, calculator, spreadsheet or program that you wrote yourself.

And now we've made the best even better. MathCAD 2.5 is a dramatically improved version that includes three-dimensional plotting, enhanced numerical analysis, and the ability to import HPGL files from most popular CAD programs, including AutoCAD.* And now you can print on PostScript® compatible printers.

And like before, MathCAD's live document interface™ lets you enter



equations anywhere on the screen, add text to support your work, and graph the results. Then print your analysis in presentation-quality documents.

It has over 120 commonly used functions built right in, for handling equations and formulas, as well as exponentials, differentials, cubic splines, FFTs and matrices.

No matter what kind of math you do, MathCAD 2.5 has a solution for you. In fact, it's used by over 50,000 engineers and scientists, including electrical, industrial, and mechanical engineers, physicists, biologists, and economists.

But don't take our word for it; just ask the experts. PC Magazine recently described MathCAD as "everything you have ever dreamed of in a mathematical toolbox."

And for Macintosh® users, we present MathCAD 2.0, rewritten to take full advantage of the Macintosh interface. Entering operators and Greek letters into equations is pure simplicity!

Look for MathCAD 2.5 at your local software dealer, or give us a call. For more information, a free demo disk, or upgrade information,* dial 1-800-MATHCAD (in MA, 617-577-1017).

**If you purchased MathCAD 2.0 between 5/1/89 and 6/16/89, you can get a FREE upgrade to version 2.5 (otherwise, the upgrade cost is \$99.00 until June 30, 1989; afterwards, the cost will be \$149.00).*



March 14,
1989 issue.
Best of '88
Best of '87

MathCAD®

MathSoft, Inc. One Kendall Square, Cambridge, MA 02139

For purposes of interpretation of measurements of the ac impedance of a corroding specimen, the equivalent circuit of an uncoated metal specimen immersed in aqueous solution is a resistor (representing the solution) in series with a parallel combination of a capacitor and a resistor (representing the layers of charge at and near the surface of the metal). The equivalent circuit of a coated specimen is more complicated and includes four resistors and four capacitors. The resistances and capacitances change with time as corrosion proceeds.

Measurements of the impedance as a function of frequency provide sufficient data to enable the resistances and capacitances to be determined by performing a least-squares fit. A knowledge of the dependence of these values on time can lead to a more detailed understanding of the corrosion process.

The specimens for the experiments were 2219-T87 aluminum disks coated with TT-P-1757 aerosol zinc chromate primer. The disks were immersed in 3.5-percent NaCl solutions buffered at pH 5.5 and pH 8.2 and monitored for 40 days by both the ac-impedance method and the dc polarization-resistance method.

The ac-impedance data indicate that a charge-transfer mechanism predominates in the kinetics at both pH values. The changes in one of the resistive components have been tentatively attributed to

the buildup of corrosion products in the paint film and the subsequent dissolution of those products. The variations in the capacitive components are tentatively attributed to changes in the thickness of the layer of Al_2O_3 on the surface of the aluminum. The resistive curves from the measurements of the ac impedance and the dc polarization resistance are consistent with each other.

This work was done by Merlin D. Danford of Marshall Space Flight Center and Ward W. Knockemus of Huntington College. Further information may be found in NASA TP-2715 [N87-21076/NSP], "The Corrosion Mechanisms for Primer Coated 2219-T87 Aluminum."

Copies may be purchased [prepayment required] from the National Technical Information Service, Springfield, Virginia 22161, Telephone No. (703) 487-4650. Rush orders may be placed for an extra fee by calling (800) 336-4700. MFS-27184

Rapid Annealing of Amorphous Hydrogenated Carbon

Effects on selected optical properties are discussed.

A report describes experiments to determine the effects of rapid annealing on

films of amorphous hydrogenated carbon (a-C:H). This study represents some of the first efforts to provide information for applications of a-C:H films where rapid thermal processing may be required.

For the experiments, a-C:H films were deposited from a methane plasma onto quartz and silicon substrates. Each of these specimens was placed in a rectangular quartz annealing chamber 5 in. (12.7 cm) wide, 8.5 in. (21.6 cm) long, and 1 in. (2.5 cm) high and heated rapidly from the top and the bottom by a bank of 13 1.5-kW tungsten/halogen lamps.

The specimens were mounted on a silicon wafer coated with gold and tungsten to speed heating through enhanced absorption of light from the lamps. Some specimens were mounted with the film side up and some with the film side down. The temperature was measured by a thermocouple attached to the silicon wafer, and the lamps were operated under control of a microprocessor to obtain the desired variation of temperature with time. Annealing temperatures of 400 or 600 °C were maintained for various intervals from 20 s to 0.5 h.

Annealed and unannealed specimens on quartz substrates were examined with an ultraviolet-and-visible absorption spectrometer. The optical band gaps of these films were inferred from the variations of their absorbencies as functions of the

New 1700 C large chamber box furnace



Large chamber capacity handles all your high temperature needs. Space-saving cabinet combines both furnace and control.

- 11" W x 9" H x 14" D chamber
- Safe, stable swing-away door
- 16 segment programmable control
- RS232 digital communications
- Over-temperature protection

Contact your local laboratory distributor or Lindberg/Blue M, 304 Hart Street, Watertown, WI 53094. Phone 414-261-7000 • FAX 414-261-0925.

9L30A

LINDBERG/BLUE M
A UNIT OF GENERAL SIGNAL



**The
Dream
Is
Alive**

Colorful T-Shirt For All Ages

Celebrate America's return to space with this official T-shirt from the movie "The Dream Is Alive™." Gorgeous full-color graphics against a white background. Machine-washable cotton and polyester. Only \$11.50 each! Order yours today using this convenient coupon.

Enclosed is \$_____ (Add \$2.50 for shipping and handling. NY residents add sales tax.)

Rush me _____ T-shirt(s) in the following size(s):

Adult: _____ S _____ M _____ L _____ XL

Children: _____ XS _____ S _____ M _____ L


Name _____

Address _____

City _____ State _____ Zip _____

Clip and mail with payment to:

**NASA Tech Briefs, Fulfillment Dept.
41 East 42nd Street, New York, NY 10017**



They don't put it to the test in space until we help put it to the test on Earth.

When your product's in space orbit 300 miles above the Earth, structural integrity takes on a whole new meaning.

Which is precisely the reason so many contractors back on Earth use Bruel & Kjaer test, measurement and stress analysis equipment.

They know Bruel & Kjaer high-performance test equipment offers unparalleled accuracy, reliability and consistency. They also know Bruel & Kjaer instruments and systems are engineered and built to the most exacting

standards in the world. With a 45-year reputation of excellence behind them.

From vibration testing to modal analysis, from sound and noise measurement to environmental monitoring. On land, sea, air or, for that matter, in space, no one helps you get from 'mission possible' to 'mission accomplished' like Bruel & Kjaer.

For our most recent catalog, or to discuss a specific application, call us.

Brüel & Kjaer 

Bruel & Kjaer Instruments, Inc.

185 Forest Street, Marlborough, Massachusetts 01752 • 508-481-7000 • FAX: 508-485-0519

MA - 508-481-7737; NJ - 201-227-6100; MD - 301-948-0494; GA - 404-422-5200; MI - 313-522-8600; IL - 312-358-7582; TX - 214-751-1700;
CA - 714-978-8066; CA - 415-574-8100; WA - 206-324-5905; OH - 513-831-8878; AZ - 602-431-1606; CO - 303-469-7914; NM - 505-242-0316

Circle Reader Action No. 319

photon energy. Annealed and unannealed specimens on silicon substrates were examined with a rotating-analyzer ellipsometer, and the resulting measurements were used to infer the extinction and absorption coefficients, index of refraction, density-of-states parameter, thicknesses, and optical band gaps of these films.

The major finding is that annealing causes an abrupt increase in the absorption and a concomitant decrease in the optical band gap. Most of the change occurs during the first 20 s, though it continues during longer annealing times. The extent of the change increases with the annealing temperature. The researchers hypothesize that the abrupt initial change is caused by the loss of hydrogen, while the gradual subsequent change is due to polymerization of the remaining carbon into crystallites or sheets of graphite.

The optical band gaps of unannealed specimens on silicon substrates were lower than those of specimens on quartz substrates. Because silicon is a conductor while quartz is an insulator, the plasma above the substrates during fabrication is believed to be different, leading to differences between the films, including the observed differences in the band gaps.

This work was done by Samuel A. Alterovitz, John J. Pouch, and Joseph D. Warner of Lewis Research Center. Fur-

ther information may be found in NASA TM-89859 [N87-20821], "Rapid Thermal Annealing of Amorphous Hydrogenated Carbon (a-C:H) Films."

Copies may be purchased [prepayment required] from the National Technical Information Service, Springfield, Virginia 22161, Telephone No. (703) 487-4650. Rush orders may be placed for an extra fee by calling (800) 336-4700. LEW-14664

Measuring Mechanical Properties of Optical Glasses

Several tests will yield data relevant to reliabilities and lifetimes under stress.

A report discusses mechanical tests that measure the parameters of strength and fracture mechanics of optical glasses. The data from these tests will be used to predict the reliabilities and lifetimes of glass optical components of several proposed spaceborne instruments.

The inherent brittleness of glass leads to a large variability in measured strength and to a dependence of strength upon time (static fatigue). The rate of loading also affects the strength. Glass that supports

loads during long intervals is weaker than glass that is loaded suddenly. Expressing this in terms of fracture mechanics, the purpose of a rapid-loading test is to cause the glass to fail before significant growth of cracks occurs. However, the strength decreases with a decrease in the rate of loading, pursuant to substantial extension of cracks. These properties complicate the structural design of glass components.

Thus, to obtain the required tables of mechanical properties of each glass of interest, both initial-strength and delayed-fracture techniques are used. The modulus of rupture is measured by the well-known four-point bending method. The initial bending strength is measured by the lesser-known double-ring method, in which a disk of glass is supported on one face near its edge by a larger ring and pressed on its other face by a smaller concentric ring. This method maximizes the stress near the center, making it more likely that the specimen will fracture there, and thereby suppresses edge effects.

Fracture-mechanics studies generally involve the measurement of the velocities of propagation of cracks as functions of selected loads and parameters of the environment (e.g., temperature and humidity). Such studies are often directed toward the determination of stress-intensity factors. The crack-tip stresses that cause a crack to grow are directly proportional to the stress-intensity factor, and the critical stress-intensity factor at which fracture occurs is usually expected to be a parameter of the material in question.

In a typical delayed-fracture study, a specimen that contains an initial crack of known length is stressed in a double-cantilever or simple three-point-bending apparatus. The stress-intensity factor is determined by monitoring the growth of the crack relative to a controlled load. The advantages of the double-cantilever-beam technique are that the strain-energy-release rate is independent of the length of the crack and that corrections for shear or rotation of the beam are unnecessary.

For a more complete characterization of properties related to strength, it is also desirable to obtain data on the distribution of sizes of flaws. Flaws on the surface of a specimen can be examined by electron microscopy of a replica of the surface. Thus far, a suitable method to investigate flaws within the specimen has not been selected.

This work was done by Dennis S. Tucker and Ronald L. Nichols of the University of Alabama for Marshall Space Flight Center. To obtain a copy of the report, "The Development of Test Methodology for Testing Glassy Materials," Circle 94 on the TSP Request Card. MFS-27206

SONEX

SONEX kills any noise.


SONEX acoustical foam's absorption coefficient is four times that of conventional materials. Send for the tests, charts, specs, and color examples from 3800 Washington Ave. N., Minneapolis, MN 55412, or call 612/521-3555.

illbruck

Class 1 fire-rated material now available. Send for free color literature.

**ANOTHER ASTRO-MED FIRST
IN 8-CHANNEL RECORDERS**

LASER PRINTER RESOLUTION!



- Laser Quality Writing—300 dpi
- 20 kHz Frequency Response
- Automatic Self-Calibration—Traceable to NBS
- Expandable to 16 Channels
- Data Capture with 200 kHz Sample Rate Per Channel
- Built-In Programmable Signal Conditioners

From its laser-sharp charts to its unparalleled frequency response, this remarkable new 8-channel recorder brings you the technology of the Twenty-First Century today! It outperforms even Astro-Med's MT-9500, which in 1987 was heralded as the first breakthrough in 8-channel recorders in 20 years. It has 50% more reso-

lution, 4 times higher frequency response, and 8 times more memory than the MT-9500. With automatic self-calibration traceable to NBS, expandability to 16 channels, and a host of other important features. We call it the MT-95000, a product so unique that it is protected by U.S. Patent No. 4,739,344.

Phone, Fax or Write for details!




Astro-Med, Inc.

Astro-Med Industrial Park, West Warwick Rhode Island 02893
Telephone (401) 828-4000 • Toll Free 800-343-4039
Telex No. 710-382-6409 • Fax (401) 822-2430

12.5 MFLOPS

32-bit Floating Point Array Processor
for PC, XT, AT, & Compatibles



- 473 functions callable from C, FORTRAN, or Turbo Pascal
- Software designed for up to 8 PL1250s, running in parallel

1K Complex Floating Point FFT 8.35ms

Complete with Software—\$2695

For more information & benchmarks, contact:

Eighteen Eight Laboratories

771 Gage Drive, San Diego, CA 92106
(619) 224-2158 • FAX (619) 224-3958

In Australia: Comp. Trans. Sys.
(03) 51 7789

In Japan: Kyokuto Boeki Kaisha (KBK)
(03) 244-3790 • FAX (03) 246-1846

In Europe: Assentoft Electronics
(06) 16 29 26

Circle Reader Action No. 675



Show Your Pride

This quality poplin cap features a striking red and blue embroidered logo against a white background. Leather adjustment strap and cord give added pizzazz. One size fits all. Only \$11.95 each. The perfect gift!

Rush me _____ cap(s). Enclosed is \$ _____ plus \$3.00 postage and handling. (NY residents add sales tax.)
Total enclosed: \$ _____

Name _____

Address _____

City _____

State _____ Zip _____

Mail with payment to:

NASA Tech Briefs, Dept. F
41 East 42nd Street
New York, NY 10017



Computer Programs

62 Predicting the Propagation of Cracks

COSMIC: Transferring NASA Software

COSMIC, NASA's Computer Software Management and Information Center, distributes software developed with NASA funding to industry, other government agencies and academia.

COSMIC's inventory is updated regularly; new programs are reported in *Tech Briefs*. For additional information on any of the programs described here, circle the appropriate TSP number.

If you don't find a program in this issue that meets your needs, call COSMIC directly for a free

review of programs in your area of interest. You can also purchase the 1988 *COSMIC Software Catalog*, containing descriptions and ordering information for available software.

COSMIC is part of NASA's Technology Utilization Network.

COSMIC — John A. Gibson, Director, (404) 542-3265

The University of Georgia, 382 East Broad Street, Athens, Georgia 30602

Computer Programs

These programs may be obtained at a very reasonable cost from COSMIC, a facility sponsored by NASA to make computer programs available to the public. For information on program price, size, and availability, circle the reference number on the TSP and COSMIC Request Card in this issue.



Mechanics

Predicting the Propagation of Cracks

Safe operating lives of components of structures can be estimated.

Flaws and cracks in a structure can grow under fatigue-inducing loads and, upon reaching a critical size, cause the structure to fail. The growth of these flaws and cracks may occur at load levels well below the ultimate load-bearing capabilities of the structure. The Advanced Crack Propagation Predictive Analysis Program, FLAGRO4, was developed as an aid in predicting the growth of preexisting flaws and cracks in structural components. FLAGRO4 provides the fracture-mechanics analyst with a computerized method of evaluation of the "safe crack-growth life" capabilities of structural components. FLAGRO4 could also be used to evaluate the tolerance-to-damage aspects of a given structural design.

The propagation of an existing crack is governed by the stress field in the vicinity of the tip of the crack. The stress-intensity factor is defined in terms of the relationship between the magnitude of the stress field and the size of the crack. The propagation of the crack becomes catastrophic when the local stress-intensity factor reaches the fracture toughness of the material.

FLAGRO4 predicts the growth of a crack by use of a two-dimensional model

that independently predicts the growth of the flaw in two directions based on the calculation of stress-intensity factors. The analyst can specify that the rate of growth be controlled by Collipriest's equation, Forman's equation, Paris' equation, or tabulated data supplied by the user.

FLAGRO4 can model partly-through, through, and corner cracks located on panels, on edges of panels, at open holes, at holes or lugs loaded with pins, and on tub or bar surfaces. The mathematical modeling of the growth of a crack can be continued until propagation becomes catastrophic. FLAGRO4 can accommodate transitions from partly-through to through cracks, gradients of stress across the width and thickness, residual stresses at cold-worked holes, variations in the properties of materials due to changes in the environment, and Willenberg retardation.

The input to FLAGRO4 consists of the initial definition of a crack (which can be defined automatically), type of rate solution, type and geometry of flaw, properties of the material (if they are not in the built-in material table), data on the load spectrum, load-stress functions, and design-limit stress levels. The output from FLAGRO4 includes an echo of the input with any error or warning messages and a history of propagation of the crack.

FLAGRO4 is written in FORTRAN IV for batch execution and is available in CDC, IBM, and DEC machine versions. The CDC version has been implemented on a CDC 6000-series machine with a central-memory requirement of approximately 150K (octal) of 60-bit words. The IBM version has been implemented on an IBM 360-series machine with a central-memory requirement of approximately 260K (octal) of 8-bit bytes. The DEC version has been implemented on a DEC VAX 11/780 computer operating under VMS. The FLAGRO4 program was developed in 1979.

This program was written by Hu Tianlai of Rockwell International Corp. for Goddard Space Flight Center. For further information, Circle 145 on the TSP Request Card.

GSC-13084

MATH ADVANTAGE[®]

FORTRAN VERSION

TOOLSMITH SERIES[®]



FUEL EFFICIENT.

Get maximum compute-engine performance for every application, with Math Advantage[®] from QTC.

Math Advantage is the de facto standard for math libraries in high-speed computing environments. It's developed and optimized by QTC's team of mathematicians, applications engineers, and supercomputer experts. It features over 260 frequently used but hard-to-program subroutines. And it runs on over 40 systems ranging from Cray X-MP

to IBM PC, Cyber to VAX, Sun to Mac.

Best of all, Math Advantage gives you FORTRAN, C, and Ada versions of algorithms like FFTs, eigensolvers, matrix operations, and BLAS, all completely *ready-to-run*. So it helps you optimize the most valuable resource of all—your time.

Because it's from QTC, the experts in high-performance development


tools, Math Advantage also comes with unmatched documentation, support, and technical excellence.

See for yourself—over 10,000 Math Advantage users already have. Contact QTC at 1-800-234-0168, or

Telex 910 240 2827 for more information.



QTC
Quantitative
Technology
Corporation



Mechanics

Hardware Techniques, and Processes

- 64 Carbon/Carbon Panels Cooled by Heat Pipes
- 65 Whistles Gauge Measures Flow and Temperature
- 66 Navier-Stokes Calculations With Deforming Grid

67 Predictions of Fatigue Damage From Strain Histories

- 68 Measuring Laminar-Separation Bubbles on Airfoils
- 69 Navier-Stokes Simulation of Turbine Rotor/Stator Interaction

- 70 Compression Pylon Reduces Interface Drag
- 71 Upwind Swirl Coupling in Navier-Stokes Calculations Computer Programs
- 62 Predicting the Propagation of Cracks

Carbon/Carbon Panels Cooled by Heat Pipes

Heat pipes are embedded to suppress hotspots.

Langley Research Center, Hampton, Virginia

A durable and reusable high-temperature carbon/carbon heat-pipe structure operates at temperatures above 3,000 °F (1,649 °C) in a vacuum or inert environment and up to 2,800 °F (1,537 °C) in an oxidizing environment. The maximum heat-flux capability of a carbon/carbon structure is currently limited by the temperature capability (about 2,800 °F) of its oxidation protection system. The new concept combines high-temperature heat-pipe and carbon/carbon technologies to extend both the thermal structural capabilities of refractory-metal heat pipes and the maximum heat-flux capability of carbon/carbon structures.

This new design uses refractory-metal heat pipes embedded within a carbon/carbon structure (see figure). The walls of the heat pipes are thin and contain the working fluid (lithium or sodium) of the heat pipe. The carbon/carbon acts as the primary load-carrying part of the structure.

The primary application considered for such a structure is the cooling of the leading edges and/or nose cap of a hypersonic aerospace vehicle. The embedded heat pipes remove high local heat from a

leading edge and transport it to cooler aft surfaces, where it can be removed by radiation and/or active cooling. The heat pipes help to eliminate local hotspots and associated thermal gradients and stresses and to reduce peak surface temperatures of the carbon/carbon to levels within the capability of the oxidation-resisting system.

Since the maximum structural-reuse temperature of carbon/carbon [2,800 °F (1,537 °C)] is much higher than that of refractory metals [2,400 °F (1,315 °C)], or superalloys [1,800 °F (982 °C)], the carbon/carbon concept requires less area for radiation and consequently weighs much less. In addition, because carbon/carbon is structurally efficient at high temperatures, this passive design would reduce structural weight and eliminate the need for complex active cooling systems.


Since carbon/carbon is a composite material, its mechanical and thermophysical properties can be tailored to specific requirements by selection of the type of the weave and of the type and condition of the fibers. The optimum choice of properties of the composite and of the size of the heat

pipes can result in a minimum-mass design that satisfies peak-temperature and thermal-stress constraints.


Panels can be made by laminating individual heat pipes between layers of carbon fabric to form two-dimensional reinforced carbon/carbon structural components, or the heat pipes can be incorporated into three-dimensional woven-carbon-fiber preforms by weaving the fibers around the prepositioned heat pipes. The three-dimensional approach provides much higher thermal conductivity and higher strength, which may be required to withstand thermal stresses and prevent delamination.

The most-attractive refractory metal for the fabrication of heat pipes is tungsten because of its compatibility with liquid metal working fluids, its low rate of reaction with carbon, its good mechanical and thermophysical properties at high temperature, and its low coefficient of thermal expansion. Its coefficient of expansion is close to that of carbon/carbon, thereby minimizing thermal stresses.

Since the primary application will likely involve exposure to oxidizing environments, which could rapidly consume the carbon and the refractory metal, the structures must contain systems to protect against oxidation. State-of-the-art systems of this type could protect this structure ef-



CARBON/CARBON LEADING EDGE CONTAINING REFRACTORY-METAL HEAT PIPES



OPERATION OF LEADING-EDGE HEAT PIPE

The **Leading Edge of a Wing** of a hypersonic airplane is cooled by metal heat pipes integrated into the carbon/carbon structure of the wing.

fectively, in cyclic applications, at temperatures up to 2,800°F (1,500°C). Coatings currently under development will extend the maximum temperature to 3,000°F.

This work was done by Charles J.

Camarda and Philip O. Ransone of Langley Research Center. No further documentation is available.

This invention is owned by NASA, and a patent application has been filed. Inquiries

concerning nonexclusive or exclusive license for its commercial development should be addressed to the Patent Counsel, Langley Research Center [see page 14]. Refer to LAR-13761.

Whistle Gauge Measures Flow and Temperature

Features include simplicity, ruggedness, and compactness.

NASA's Jet Propulsion Laboratory, Pasadena, California

A simple, rugged gauge is used to measure the speed of flow and the temperature of steam or other gas flowing through pipes of arbitrary diameter, from 1 to 28 in. or larger. The gauge — essentially a specially designed, instrumented whistle — has no moving parts, is small, is nonobstructing, can operate at high temperature and pressure, and cleans itself. The gauge does not operate at zero flow, but at moderate flows (tens of meters per second) it can generate intense sound for use in the measurements.

The gauge (see figure) consists of a slanted ring groove of depth D and pressure taps in the wall of the pipe that carries the flow to be measured. The resonant wavelength, λ , of the sound generated by the ring groove depends primarily on the size and shape of the groove and is approximately equal to $4D$.

The pressure taps are openings into narrow tubes separated from each other by an integral multiple of $\lambda/2$ along the axis of the pipe. The sound travels along the tubes to a convenient location at room temperature, where it is sensed by microphones and analyzed to determine the difference in phase between the sound waves at the two pressure taps. Using the Doppler relation for the propagation of waves upstream and downstream from the ring groove, the difference in phase, $\Delta\phi$, is given by


$$\Delta\phi = \pi(1 + nu/c) \text{ when } n \text{ is odd and}$$

$$\Delta\phi = \frac{n\pi}{c} \text{ when } n \text{ is even}$$

where n = the number of half wavelengths between the pressure taps, u = the speed of flow, and c = the speed of sound.

The frequency, f , of the sound is measured, and the speed of sound is estimated by $c = 4fD$. The absolute temperature, T , is then estimated from $T = Mc^2/\gamma R$, where γ = the specific heat of the gas at constant pressure divided by the specific heat at constant volume, R = the gas constant, and M = the mass of one mole of the gas in the pipe.

Experimental versions of the gauge have been tested successfully. For example, one gauge exhibits a resonance at 1,380 Hz at flow speeds of 35 to 110 m/s, and the phase differences were as predicted for pressure taps with one- and two-



The Flow Past the Ring Groove generates a tone that propagates upstream and downstream. The difference in the phase of the tone measured by the two microphones indicates the speed of flow.

There's almost no flow you can't model with Boeing supercomputers.



We have a computational fluid dynamics lab that can predict flows for everything from airplanes to racing yachts. And it's available for contracting through Boeing Technology Services. For information, call Chris MacRae at (206) 234-5000.

BOEING

wave-length separations. The introduction of secondary flows of the same gas through a modified ring source at a pressure slightly higher than the local value has extended

the range of operation of the sensor down to zero speed.

This work was done by Parthasarathy Shakkottai and Eug Y. Kwack of Caltech for

NASA's Jet Propulsion Laboratory. For further information, Circle 164 on the TSP Request Card.
NPO-17243

Navier-Stokes Calculations With Deforming Grid

The specification of boundary conditions is simplified.

Lewis Research Center, Cleveland, Ohio

A scheme for numerical simulation of the transonic, compressible, viscous flow about a two-dimensional cascade of oscillating rigid airfoils involves the finite-difference solution of the Navier-Stokes equations on a coordinate grid that deforms with the motions of the airfoils. The scheme is expected to contribute to understanding of the flows around advanced turboprop airfoil sections. It is needed because no experimental data are yet available to determine the extent of unsteady effects in such flows, and the linearized potential-flow codes used thus far to study transonic cascades are not expected to represent the true physical phenomena.

The cascade is represented by a periodic coordinate grid, which conforms to periodic boundaries and to the airfoil surfaces (see figure). Periodic boundary conditions (including blades pitching and/or plunging in unison) are assumed. Thus, the flow about each airfoil can be simulated numerically by applying finite-difference Navier-Stokes-solution techniques previously developed for an isolated airfoil.



The outer boundary is considered fixed. The grid is initially fitted to the outer boundary and a stationary inner boundary (airfoil surface) by a numerical solution of Poisson's equation. The inner boundary is then allowed to move by some prescribed pitching or plunging motion. As the inner boundary moves with the airfoil, the gridlines that connect the inner and outer boundaries deform by amounts that depend on the distance from the airfoil. The total velocity of the flow at any point on the grid equals the local velocity of the deformation plus the velocity of the flow with respect to the grid. The geometric conservation law can be invoked to calculate the effects of the change in the Jacobian of the transformation between the fixed Cartesian grid and the moving computational grid due to the motion of the computational grid.

The inlet boundary conditions are assumed to include the free-stream total pressure and temperature. The direction of the flow across the upstream boundary is approximated as that of a steady flow, using an upstream-running Riemann invariant extrapolated from the interior to give a nonreflecting-boundary condition on the total velocity. The static pressure and density are found by assuming isentropic flow, and the energy density is calculated as the

sum of pressure and kinetic-energy-density terms.

The exit boundary conditions are found by extrapolation of the mass density and

momentum density from the interior and by specification of a free-stream static pressure to calculate the energy density. (An exit Riemann invariant cannot be specified



A Cascade is Represented by a periodic grid that conforms to the airfoils and to the outer boundaries. The oscillation of an airfoil is represented by a deformation of the grid.

because it would vary across a viscous wake.) Other boundary conditions include the usual solid-wall boundary conditions on the airfoil surface and averaging of flow conditions across the slit aft of the airfoil.

The results of test computations using the deforming-grid technique were found to agree well with results from an isolated-airfoil calculation using a rigid grid. The in-

clusion of the geometric conservation law had little effect. Future applications of the deforming-grid technique may include turbomachinery and aeroelastic modeling of nonrigid airfoils.

This work was done by Dennis L. Huff of Lewis Research Center. Further information may be found in NASA TM-89890 [N87-24435], "Numerical Simulations of

Unsteady, Viscous Transonic Flow Over Isolated and Cascaded Airfoils Using a Deforming Grid."

Copies may be purchased [prepayment required] from the National Technical Information Service, Springfield, Virginia 22161, Telephone No. (703) 487-4650. Rush orders may be placed for an extra fee by calling (800) 336-4700. LEW-14711

Predictions of Fatigue Damage From Strain Histories

Cycle-by-cycle analysis is better than statistical characterization.

Marshall Space Flight Center, Alabama

A semiempirical mathematical model of fatigue damage in stressed objects uses experimental histories of strains in those objects to predict their fatigue lives. The model accounts for the initiation and propagation of fatigue cracks on a cycle-by-cycle basis. When the model is calibrated against proper test data for each type of object to be characterized, its predictions of fatigue lives are superior to those of such statistical models as one based on root-mean-square strain.


An object to be characterized is instru-

mented with strain gauges and placed in operation or in a fatigue-testing apparatus. The strain measurements are digitized and fed to a computer operating under the Strain History Life Evaluation Program (SHLEP), which processes the measurements according to the model. The first step in the analysis is to convert the input strain history to a history of turning points (peaks and valleys) of the strain cycles (see figure). The data between the turning points are irrelevant in the model and are removed, thereby significantly reducing the processing time and the number of data to be stored.


Sets of strain cycles are selected for analysis by the ordered-overall-range method, in which the turning-point history

is reduced to a history of strain ranges that exceed specified fractions of the range between the maximum and minimum peaks. This method gives an indication of whether or not a large fraction of the total fatigue damage in a particular case is caused by a relatively small number of cycles.


The "rainflow" counting method is used to determine the number of fatigue cycles of various amplitudes after the strain history has been screened for significant ranges. This method involves the counting of cycles that are mathematically equivalent to closed stress-versus-strain hysteresis loops. It is called "rainflow" because a graphical representation of the counting algorithm resembles the path of rain being shed by a plot of the turning-point strain



ANALOG STRAIN HISTORY



DIGITIZED STRAIN HISTORY



TURNING-POINT STRAIN HISTORY

A Measured Strain History is first digitized, then converted to a history of turning-point strains for purposes of the analysis. The data between the turning points are not used.

There's almost nothing you can't test in Boeing wind tunnels.



We have superb subsonic, transonic, supersonic and hypersonic wind tunnels. All available for contracting through Boeing Technology Services. For information, call Chris MacRae at (206) 234-5000.

BOEING

history with time running downward along the vertical axis.

For the purpose of the model, the fatigue-crack-initiation life is defined as the fatigue life required to produce a fatigue crack of a preselected depth. In a given case, strain-gauge data may have to be related via a stress-concentration factor to strains and stresses at a fatigue-critical location that cannot be instrumented but which is assumed to undergo strain cycles proportional to those of the instrumented location. The fatigue-crack-initiation algorithm is based on the strain range versus the number of cycles to failure from constant-amplitude fatigue tests. For variable-

amplitude fatigue, the damage is evaluated according to a damage fraction, d , given by

$$d = \sum_{j=1}^m n_j / N_j$$

where m is the number of strain cycles of all amplitudes in a history, n_j is the number of cycles of the j th amplitude, and N_j is the number of constant-amplitude cycles to failure at the j th amplitude.

The propagation of a crack is considered to begin when the crack-initiation algorithm predicts initiation, defined as the achievement of an arbitrarily-specified damage fraction between 0 and 1. The total

fatigue life is the sum of the initiation and propagation lives. Using linear elastic fracture mechanics, the growth of the crack during each cycle is computed for each cycle of a strain history. The sequence is repeated until the crack grows to a critical size at which the part fails. Both the total propagation life and the critical crack size are computed.

This work was done by Robert A. Sire, Philip M. Besuner, and Tim Toomey of Failure Analysis Associates for Marshall Space Flight Center. For further information, Circle 6 on the TSP Request Card. MFS-26060

Measuring Laminar-Separation Bubbles on Airfoils

A nonintrusive multielement heat-transfer sensor overcomes limitations of previous methods.

Langley Research Center, Hampton, Virginia

Laminar separation is the major cause of rapid deterioration in aerodynamic characteristics of airfoils at chord Reynolds numbers less than 10^6 . At such a chord Reynolds number, a boundary layer is generally stable, and an adverse pressure gradient, as in the rear pressure-rise area, is most likely to result in a laminar separation with or without turbulent reattachment.

A laminar-separation bubble is formed when a turbulent reattachment takes place upstream of the trailing edge of the airfoil, as shown in the upper part of Figure 1. Many flow and geometric parameters affect the laminar-separation bubble, and a good understanding of its characteristics is essential to develop effective practical techniques to control or eliminate laminar separation.

The lower part of Figure 1 is a schematic diagram of a typical laminar-separation bubble. The bubble includes a reverse-flow region close to the solid surface and a zero-mean line that divides the reverse-flow region from the upper entrainment layer wherein the streamlines follow the general outer flow. The height of the bubble is usually a small fraction of a percent of the chord.

The smallness of the height and the complexity of the flow field make conventional measuring instruments like hot-wire anemometers and pitot tubes unsuitable for determination of the characteristics of the bubble because such instruments can perturb the flow significantly. Laser velocimetry is perhaps the most-effective nonintrusive technique, though there are still some problems associated with it. Flush-mounted hot-film sensors have also been ineffective.

A new nonintrusive technique involves a multielement heat-transfer sensor. In tests of the new technique, only small amounts of heat were introduced, and the heated thin films caused little disturbance to the




Figure 1. The **New Technique Determines Simultaneously** the extent of the laminar boundary layer and the locations of laminar separation, transition in the separated layer, and turbulent reattachment.

shear layer or to each other. The extent of the laminar boundary layer, the location of laminar separation, the transition in the separated shear layer, and the turbulent reattachment were determined simultaneously.

When using the new sensor, there is no need to know a priori the location of the laminar separation; and, in view of the simultaneous measurement, a clear picture of the characteristics of the bubble, including its dynamic behavior, is obtained. In the tests, simultaneous measurements of dynamic shear stress on the surface of the airfoil led to the discovery of a new phenomenon associated with the dynamics of the bubble — a 180° phase shift of

low-frequency perturbations was observed across the laminar-separation and reattachment points (see Figure 2). This phenomenon is crucial to the detection of laminar separation by use of a multielement sensor, and its discovery has greatly simplified and advanced the state of the art of multielement surface-film instrumentation as a diagnostic tool to study boundary layers and separated shear layers on an airfoil.

The multielement, surface-film sensor appears to be a promising tool for measurements of the stability of laminar boundary layers, separated shear layers, and transitional separation bubbles. The technique is simple and is capable of providing a comprehensive picture of the state of the

shear flow along the entire surface. There is, thus, a significant saving in tunnel (or flight) test time with a corresponding saving in cost.

The idea can be extended to the diagnostics of more-complex steady and unsteady flow structures at the surface, such as interactions between shocks and boundary layers, wing/fuselage junctures, and other three-dimensional surface-shear layers. The discovery of the phase-reversal phenomenon has made it possible to interpret the characteristics of the surface shear layer in an unambiguous manner and has led to the development of a non-intrusive and cost-effective multielement sensor that can be used in regular wind-tunnel, ground-test, and flight-test applications and may also lead to the discovery of more, hitherto unknown, phenomena in the characteristics of shear flows.

This work was done by John P. Stack of Langley Research Center and Sivaramakrishnan M. Mangalam of Analytical Services and Materials, Inc. For further information, Circle 109 on the TSP Re-




Figure 2. Differences Between the Phases of low-frequency sensor outputs show $\sim 180^\circ$ phase shifts across the points of separation and reattachment.

quest Card.

This invention is owned by NASA, and a patent application has been filed. Inquiries concerning nonexclusive or exclusive

license for its commercial development should be addressed to the Patent Counsel, Langley Research Center [see page 14]. Refer to LAR-13952.

Navier-Stokes Simulation of Turbine Rotor/Stator Interaction

The patched-grid method is applied to a complicated configuration.


Ames Research Center, Moffett Field, California

The patched-grid method has been used to effect a three-dimensional Navier-Stokes numerical simulation of a flow that interacts with both a rotor and a stator in a turbine. The ability to perform such calculations can contribute to the understanding of complicated turbomachinery flows and to consequent improvements in designs of turbomachinery.

The patched-grid method involves the use of two or more grids or sets of grids to solve the finite-difference versions of the Navier-Stokes or other equations of fluid flow. One grid or a set of grids is attached to the stationary portion of the machinery (in this case, the stator vanes and the housing), while another grid or set of grids is attached to the moving parts (in this case, rotating with the rotor blades and hub). Information is transferred between grids via boundary conditions that satisfy several requirements including numerical stability, spatial and temporal accuracy, easy applicability to generalized coordinates, and flux conservation (in the sense that discontinuities in the flow can move from one grid to another without distortion).

A system of patched and overlaid grids was used to discretize the complicated three-dimensional configuration, including the three-dimensional shapes of the rotor and stator blades, the rotor-tip clearance, and the end walls. An implicit, upwind, third-order-accurate algorithm was used to solve the unsteady, thin-layer Navier-Stokes equations. A modified version of the

There's
almost nothing you
can't test in Boeing
acoustics labs.



We have one of the world's best aeroacoustic laboratories. And it's available for contracting through Boeing Technology Services. For information, call Chris MacRae at (206) 234-5000.

BOEING

Baldwin-Lomax algebraic model of turbulence was included.


About five blade-passage cycles were required to eliminate the initial transients and establish a periodic solution. The numerical results were expressed in terms of time-averaged pressures at the midspans of the blades and compared with experi-

mental values. As shown in the figure, there was close agreement between theory and experiment.

This work was done by Man Mohan Rai of **Ames Research Center**. Further information may be found in NASA TM-100081 [N88-29750], "Three-Dimensional Navier-Stokes Simulations of Turbine Rotor-Stator Interaction."

Interaction."

Copies may be purchased [prepayment required] from the National Technical Information Service, Springfield, Virginia 22161, Telephone No. (703) 487-4650. Rush orders may be placed for an extra fee by calling (800) 336-4700. ARC-12185



Time-Averaged Pressure Coefficients as a function of position along the chords of the rotor and stator blades at midspan were obtained from a Navier-Stokes simulation and from an experiment. The comparison between the experimental and numerical data is very good.


Compression Pylon Reduces Interference Drag

A new design reduces total drag by 4 percent.

Langley Research Center, Hampton, Virginia

The propulsion/airframe integration for a transport airplane normally employs a pylon to attach and position the engine beneath the wing. The side of the fuselage, the underside of the wing between fuselage and pylon, the inboard surface of the pylon, and the nacelle of the jet engine form a channel that influences the aerodynamic flow under the wing. The result is a loss in lift of the wing as well as an increase in drag caused by compressibility effects (wave drag) plus any associated separation of the flow around the pylon.

A new pylon reduces the fuselage/wing/pylon/nacelle-channel compressibility losses without creating additional drag associated with other areas of the pylon. The pylon is designed to compress the flow beneath the wing by reducing the velocity in this channel, thereby reducing the shock-wave losses and, in addition, providing an increase in wing lift. The afterbody of the pylon extends aft of the trailing edge of the wing and is designed to assist the flow in its return to ambient conditions with minimum separation. This additional pylon area may also improve the overall area distribution of the aircraft.



With the **Compression Pylon**, the minimum cross-sectional area of the channel occurs at the trailing edge of the wing. Therefore, the velocity of flow in the channel is always nearly subsonic, reducing the compressibility losses associated with supersonic flow. The flow goes past the trailing edge before returning to ambient conditions, resulting in no additional drag to the aircraft.

Recent wind-tunnel tests were conducted with pylons of various cross-sectional shapes mounted beneath the wing of a high-wing transport configuration. These tests were conducted in the NASA Langley Research Center 16-ft (4.9-m) wind tunnel at the cruise-lift coefficient of 0.43 and mach numbers of 0.70 and 0.80. Because earlier investigations have shown that the drag caused by the wing/pylon/nacelle installation is due mainly to the pylon rather than to the nacelle, these wind-tunnel tests were conducted without nacelles.

The photograph shows the lower surface of the wing with the compression pylon installed. By progressively increasing the thickness of the pylon from the leading

edge to the trailing edge of the wing, the minimum channel area is made to occur at the trailing edge. As a result, nearly subsonic velocities are maintained in this area, reducing the compressibility losses associated with pylon installations.

The installed drag for three different pylon configurations was determined. A pylon having a National Advisory Committee for Aeronautics (NACA) 0012 airfoil section was used as a baseline. Cambering an NACA 4412 airfoil section caused a small increase in drag, while contouring the pylon (so that the pylon section followed the natural streamlines under the basic wing alone) resulted in a small decrease. The reduction in compressibility losses

achieved by the compression pylon, on the other hand, resulted in a reduction of approximately 4 percent of the total drag of the aircraft model tested.

This work was done by James C. Patterson, Jr., and John R. Carlson of Langley Research Center. For further information, Circle 53 on the TSP Request Card.

This invention is owned by NASA, and a patent application has been filed. Inquiries concerning nonexclusive or exclusive license for its commercial development should be addressed to the Patent Counsel, Langley Research Center [see page 14]. Refer to LAR-13777.

Upwind Swirl Coupling in Navier-Stokes Calculations

Convergence in axisymmetric flows is speeded.

Marshall Space Flight Center, Alabama

An improved treatment has been devised for the swirl-coupling source terms in finite-difference Navier-Stokes calculations of axisymmetric flow. The essence of the improvement is to treat the radial- and swirl-velocity source terms in an implicit manner wherever possible, because implicit treatment results in faster convergence and in convergence in some cases in which explicit treatment does not yield convergence at all.

The discretized radial and swirl momentum equations are written as

$$a_i V_i^* + a_{i+1} V_{i+1}^* + a_{i-1} V_{i-1}^* = S_V^n + AW^2$$

and

$$a_i W_i^* + a_{i+1} W_{i+1}^* + a_{i-1} W_{i-1}^* = S_W^n + BVW$$

for all i from 1 to i_{max} , where V represents the radial velocity; W represents the swirl velocity; asterisks denote the predicted values; the subscript indices represent the locations of the nodes; the a 's are the discretization coefficients; S_V^n and S_W^n are the radial- and swirl-equation source terms, respectively, at the old iteration level; and AW^2 and BVW are the swirl-coupling terms.

Equations (1) and (2) constitute an implicit system for the predicted velocities V^* and W^* . Because segregated solutions of these equations do not account for the interdependence of the sources, convergence can be impeded where $d(AW^2)/dW$

and $d(BVW)/dV$ are large.

To increase convergence, the radial and swirl source terms are treated in an implicit or explicit manner, depending on the sign of the linearization coefficient. The source term for equation (2) is written as

$$2BVW = BV(1-e)W^* + BV(1+e)W^n$$

where $e = \text{sign}(BV)$. A similar expression is written for equation (1). Thus, when BV

< 0 , the source term is treated implicitly, and the numerical solution converges better than it would if the source term were treated explicitly.

This work was done by Morgan Williams of Rockwell International Corp. for Marshall Space Flight Center. No further documentation is available. MFS-29542

There's almost nothing you can't test in Boeing propulsion labs




We have excellent nozzle test facilities, dual flow rigs, propulsion integration wind tunnels and more. And they're all available for contracting through Boeing Technology Services. For information, call Chris MacRae at (206) 234-5000.

BOEING

For Your Convenience

We've now combined the Subscription/TSP Form and the Reader Action Card into a single, easy-to-use form. See page 81.



Machinery

Books and Reports

- 72 Microencapsulated Phase-Change Materials for Storage of Heat
- 73 Survey of Cooling Techniques

74 Predicting Flutter of a Propfan

Books and Reports

These reports, studies, handbooks are available from NASA as Technical Support Packages (TSP's) when a Request Card number is cited; otherwise they are available from the National Technical Information Service.

Microencapsulated Phase-Change Materials for Storage of Heat

Investigations concentrate on the feasibility of practical, safe, lightweight systems.

A report describes research on engineering issues related to the storage and transport of heat in slurries containing phase-change materials in microscopic capsules. The specific goal of this project is to develop lightweight, compact, heat-management systems that could be used

safely in the inhabited areas of spacecraft. Further development of the obvious potential of this technology can be expected to lead to commercialization and use in aircraft, electronic equipment, machinery, industrial processes, and other systems in which the requirements for the management of heat compete with severe restrictions on weight or volume.

The basic principle of operation is simple: to reduce the size and weight of a heat-transport/heat-storage system by taking advantage of the high density of the latent heat of fusion of a material that melts and freezes near the temperature of interest. Techniques that exploit this principle have been investigated since 1932. Work on the microencapsulation/slurry concept began in the early 1970's but was abandoned because of concerns over costs and the premature breakup of the capsules.

For the purposes of this investigation, the choice of materials for the slurry is dic-

tated not only by heat-transfer characteristics but also by the requirements that the materials not be toxic, pose no fire hazard, undergo little or no change of volume in the phase change, and be chemically stable. Also of interest are the rheological properties of the slurry and the specific gravities of the components (with the consequent tendency of the capsules to separate from the liquid in the presence of gravitation and acceleration). The durability of the capsules (partly a function of size and shape and partly a function of the materials) and the costs of materials still give rise to concern as they did during the earlier investigations. A typical candidate slurry that may fulfill most of the requirements could be made of a paraffin wax in polymer capsules suspended in water. A soap or other dispersant could be added to prevent the settling or flotation of the capsules.

The investigation also addressed a number of other topics, including the following:

- Characteristics of the processes and materials used in microencapsulation;
- The storage of heat in modules containing packed beds of phase-change particles through which phase-change slurries are circulated;
- Procedures to test the slurries;
- The development of pumping systems;
- Laboratory data-gathering and experimental fluid systems; and
- The design of experiments to be flown aboard the Space Shuttle.

The achievements include the demonstration of a slurry with a thermal capacitance 10 times that of water and a heat-transfer coefficient twice that of water. An efficient phase-change heat-storage unit was designed, and it was shown that the pump work required to maintain a given overall thermal condition can be reduced as much as 90 percent below that of a comparable system based on water alone. In addition, the enhanced transport and storage of heat in a phase-change slurry take place under conditions that are nearly isothermal in comparison with those of older systems.

This work was done by David P. Colvin of Triangle Research and Development Corp. for **Marshall Space Flight Center**. To obtain a copy of the report, "Investigation and Development of a Phase Change Thermal Energy Storage System Using Microencapsulated Phase Change Materials," Circle 10 on the TSP Request Card.


MFS-27198

Accurate

DT-470 Series Silicon Diode Temperature Sensors (1.4K to 475K)

Lake Shore guarantees the accuracy of the DT-470 series sensors over their entire temperature range — not just at specific temperatures.

"Off-the-shelf" DT-470 sensors follow a standardized curve with accuracies to within $\pm 0.25K$. Or they can be individually calibrated to accuracies within ± 50 millikelvin or better. So you get a sensor with accuracy that's guaranteed.



Look to
Lake Shore
High
performance
in low
temperature
technology

LakeShore

CRYOTRONICS, INC.

64 East Walnut Street, Westerville, Ohio 43081 USA (614) 891-2243
Telex: 24-5415 Cryotron WTVL Fax: (614) 891-1392
©1989 Lake Shore Cryotronics, Inc.

Survey of Cooling Techniques

Methods of maintaining electronics at the best operating temperatures are reviewed.

A paper surveys cooling techniques for electronic components and sensors that must be kept at temperatures ranging from thousandths of a kelvin to room temperature. The paper discusses the characteristics of the various coolers in terms of ground and space applications, cooling capacity, reliability, and temperature range. It discusses briefly the cooling of conventional electronic circuitry operating a few degrees above the environmental temperature by natural or forced convection of air or liquid. At greater length, it discusses the passive and active refrigeration of "cold" electronic circuitry operating below the environmental temperature.

The simplest and most reliable cooler is a passive radiator. Radiators are seldom used at temperatures below 100 K when the heat load is more than 100 mW because the radiative area required becomes too large.

Other passive coolers depend on such stored cryogenics as helium or nitrogen in solid or liquid form. As in melting in an old-fashioned ice box, vaporization or sublimation of the cryogen removes heat. The useful life of a stored-cryogen cooler depends on how quickly the cryogen becomes exhausted, if it cannot be replenished. The paper includes a table of operating temperatures and boiloff rates of common cryogenics.

The Joule-Thomson refrigerators are half passive and half active. They cool by expansion of high-pressure gases through nozzles. They can be made very small. However, they depend on constant supplies of gas at high pressures.

Active coolers (closed-cycle refrigerators) are machines that require work to transfer heat from devices to hotter reservoirs. In household refrigerators, the work is done by electric motors. Commercial thermoelectric coolers in cascade can attain temperatures of about 170 K. Cryocoolers, which are fairly well developed, can cool to about 4 K.

Cooling below 10 K is best performed by a closed-cycle Joule-Thomson refrigerator or a magnetic refrigerator, which involves changing the magnetic field in a salt. Below 1 K, either $^3\text{He}/^4\text{He}$ dilution refrigeration or adiabatic demagnetization can be used.

This work was done by Chung K. Chan of Caltech for NASA's Jet Propulsion Laboratory. To obtain a copy of the report, "Survey of Cooling Techniques for Electronic and Sensor Devices," Circle 158 on the TSP Request Card. NPO-17457

ARE YOUR IDEAS AHEAD OF OUR TIME?



Stonehenge, one of the most famous of all the classical megalith monuments, has long been an important part of the popular and scientific imagination. Its origin has been the cause of speculation for years, as scientists try to discern who had the intellect and ingenuity to create a celestial observatory of such astronomical significance and exactness.

The construction of Stonehenge required remarkable genius and ability — and so will the endeavors we have planned at General Dynamics Space Systems Division.

You can now be a part of our exciting time in history. Your ideas and accomplishments could be chronicled for future generations to study as hallmarks of a brilliant epoch in space exploration.

We currently have opportunities available for individuals with a technical degree or the equivalent combination of formal education and related experience. Government or aerospace industry background is preferred.

If you have experience in one or more of the areas listed below, please send your resume to: Professional Staffing, GENERAL DYNAMICS SPACE SYSTEMS DIVISION, MZ 21-7143-1434, P.O. Box 85990, San Diego, CA 92138. (Opportunities also exist in Huntsville, AL, Harlingen, TX, Cape Canaveral Air Force Station, FL, and Vandenberg Air Force Base, CA.)

AVIONICS

- AI/Expert Systems Applications
- EMI/EMC
- Electrical Power
- Instrumentation
- Parts Engineering
- Harness Design/Installation
- Liaison
- Digital Circuit Design
- Avionics Systems
- Mechanical Packaging
- Control Systems
- Guidance & Navigation

QUALITY ENGINEERING

- Tool Design/Proofing
- Software Quality Assurance
- Process Control
- Radiographic Inspection

FLUID SYSTEMS DESIGN

- Pneumatic
- Hydraulic
- Propulsion
- Cryogenics

STRESS ANALYSIS

- Hand Analysis
- Finite Element Modeling
- Structural Test Support
- CAE Methods
- Advanced Composites

SYSTEMS

- Systems Requirements
- Systems Safety
- Environmental Engineering
- Software

STRUCTURAL DESIGN

- Advanced Composite Structures
- Tank Structures
- Adapters
- Fairings
- Materials & Processes
- Pre-Design
- Mechanical Liaison
- Superconducting Magnets
- Drawing Checkers
- Liaison

DYNAMICS/ANALYSIS

- Launch Vehicle Transient Load
- Environmental Dynamics
- Acoustics
- Jettison Trajectory
- IRAD & CRAD
- CAE

THERMAL/FLUIDS ANALYSIS

- Systems Modeling
- Space Environments
- Propulsion
- Cryogenics

TEST & EVALUATION

- Launch Support Analysis

ENVIRONMENTAL/HAZARDOUS WASTE ENGINEERING

MANUFACTURING TECHNOLOGY/PRODUCTIBILITY

- Manufacturing Engineering
- Industrial Engineering

GENERAL DYNAMICS Space Systems Division

Equal Opportunity Employer/Principals Only

Predicting Flutter of a Propfan

Stability decreases as the number of blades increases.

A report discusses a theoretical model and an associated computer program for the prediction of subsonic bending-torsion cascade flutter in propfans. The predictions of the model are compared with the results of experiments. Additional parametric studies illustrate the effects upon the flutter speed of steady aeroelastic deformations, the angle at which the blade is set, the speed of rotation, structural damping, and the number of vibrational modes.

The nonlinear equations of aeroelastic motion are written for a finite-element model of a blade. They are valid for calculating the speeds of stalled and unstalled flutter, forced response, aeroelastic performance, steady-state deflections, and the frequencies and shapes of vibrational modes. Because it is computationally inefficient to integrate them directly in the time domain, the nonlinear equations are treated by a standard perturbation approach, yielding a nonlinear set of equations for the steady-state configuration and a linear set for the perturbations about the steady state. The steady-state deflections and effective total stiffnesses obtained from the solution of

the nonlinear equation are used to find the normal vibrational modes. The general vibratory motion is calculated as a superposition of normal modes.

The calculations are performed by parts of the ASTROP computer code: ASTROP 2, based on two-dimensional, subsonic, unsteady aerodynamics; and ASTROP 3, based on three-dimensional, subsonic, steady and unsteady aerodynamics. In ASTROP 2, the blade is divided into discrete aerodynamic strips, within each of which its properties are constant. Each swept strip undergoes plunging and pitching motions. In ASTROP 3, the blade is discretized with nine (radial) times eight chordwise panels for calculating aerodynamic loads.

In general, the flutter speeds and interblade phase angles predicted by the computer code agree well with experimental values. However, the flutter frequencies predicted by a three-dimensional, unsteady aerodynamical theory are slightly higher than measured ones, and those predicted by two-dimensional theory are less accurate than are those predicted by three-dimensional theory. Other findings include the following:

- Steady-state aerodynamics exert significant influence on the steady-state configurations, vibrational modes, and flutter in some cases.

- Both theory and experiment show that stability decreases with an increase in the number of blades, apparently due to effects of cascades.
- Both theory and experiment show that an increase in the angle at which the blade is set is destabilizing.
- For the rotor considered, the flutter mode is dominated by the first two normal vibrational modes of the blades, and there is strong coupling between these modes.
- Both theory and experiment show that under certain conditions, two interblade-phase-angle modes with slightly different frequencies may be present during flutter. The flutter interblade phase angle is a function of the angle at which the blades are set and of the number of blades.

This work was done by K. R. V. Kaza and O. Mehmed of Lewis Research Center, G. V. Narayanan of Sverdrup Technology, Inc., and D. V. Murthy of the University of Toledo. Further information may be found in NASA TM-88944 [N87-18115/NSP], "Analytical Flutter Investigation of a Composite Propfan Model."

Copies may be purchased [prepayment required] from the National Technical Information Service, Springfield, Virginia 22161, Telephone No. (703) 487-4650. Rush orders may be placed for an extra fee by calling (800) 336-4700. LEW-14659

COIL'S PRE-ANODIZED ALUMINUM: IT'S WHAT YOUR WORLD IS COMING TO.



NOW, ANODIZING BEFORE FABRICATION

Pre-Anodized Aluminum creates an explosion of new applications. It's being used right now to replace:

Brass	Stainless
Bronze	Hard-coats
Copper	Painted Surfaces

IT'S ECONOMICAL

As a lightweight metal, pre-anodized aluminum helps you save. Save 50% in material handling alone, and triple your yield per pound.

COIL IS YOUR SINGLE SOURCE

From base metal to fabricating and finishing, Coil Anodizers is the world's largest single source for pre-anodized aluminum.


Call or write for a FREE brochure, or send \$4.00 for a complete "Engineer's Guide" to...



COIL ANODIZERS INC.

1960 S. Roberts / Muskegon, MI 49442
1-800-654-1159
In Mich. 616-722-1631
Fax. 616-726-6186

A Division of Lorin Industries, Inc.



Use the Established Force to measure the progress of a field in constant motion!

From archaeology to aerospace... food processing to factory automation... agriculture to automotive... mining to manufacturing... the applications of sensor technology are virtually limitless.

There's no better place to discover all of the innovative uses for hundreds of different types of sensing products than SENSORS EXPO... the Established Force for tracking everything and anything dealing with sensor and transducer technology.

Whether you integrate sensors as components in end-products or systems, or need to monitor processes, manufacturing and other operations, SENSORS EXPO can show you how to use machine perception technology more effectively than ever before.

Develop specific solutions to your application requirements in discussions with more than 250 leading suppliers... see live demonstrations of the latest sensing devices and get in-depth information on technologies and trends in Conference seminars.

SENSORS EXPO is sponsored by *Sensors* magazine and is produced by Expocon Management Associates, Inc.

Put the Established Force to work for you... complete and return the coupon below to receive all the facts on SENSORS EXPO! For immediate information, call 203/374-1411. (FAX: 203/374-9667)

SENSORS EXPO

THE FOURTH INTERNATIONAL CONFERENCE AND EXPOSITION
OF MACHINE PERCEPTION TECHNOLOGY
INTERNATIONAL EXPOSITION CENTER
CLEVELAND • SEPTEMBER 12-14, 1989

☐ Send complete attendance information.

☐ Send information on exhibit space.

Name

Title

Company

Street


City

State Zip

Phone () AE

Mail to: **SENSORS EXPO**

Expocon Management Associates, Inc.
P.O. Box 1019, Trumbull, CT 06611



Fabrication Technology

Hardware Techniques, and Processes

76 Chemical-Vapor Deposition of $\text{Cd}_{1-x}\text{Mn}_x\text{Te}$

78 Making a Precisely Level Floor

80 Making Multicore, Multishell Microspheres

83 Circularity-Measuring System

84 Keeping Wax Liquid for Application

Chemical-Vapor Deposition of $\text{Cd}_{1-x}\text{Mn}_x\text{Te}$

An experimental process makes films with interesting magnetic and magneto-optical properties.

NASA's Jet Propulsion Laboratory, Pasadena, California

Films of the dilute magnetic semiconductor alloy $\text{Cd}_{1-x}\text{Mn}_x\text{Te}$ have been deposited on glass and GaAs substrates by metalorganic chemical-vapor deposition (MOCVD). Devices made with $\text{Cd}_{1-x}\text{Mn}_x\text{Te}$ films are known to exhibit strong photoluminescence, stimulated emission, and magnetically-tunable lasing action. In addition, the energy-band gaps of such a material can be tailored by altering its composition — a property that gives flexibility in the development of high-efficiency cascade solar photovoltaic cells.

Dilute magnetic semiconductors have been previously deposited by molecular-

beam epitaxy, which requires a high vacuum. MOCVD can be performed at atmospheric pressure, resulting in more-uniform films, covering a larger area, and enabling a higher production rate.

The experimental deposition system was contained in a horizontal quartz reactor tube equipped with a graphite susceptor heated by radio-frequency energy. The source of cadmium was dimethylcadmium (DMCd) held at a temperature of 0 °C, and the source of the tellurium was diethyltellurium (DETe) at 27 °C. The DMCd and DETe were carried into the tube by highly pure H_2 .




Figure 1. The Optical Transmissions of $\text{Cd}_{1-x}\text{Mn}_x\text{Te}$ films were measured and plotted as a function of wavelength to find the photon energy that equals the band-gap energy.




Figure 2. The Photoluminescence Spectrum of a specimen of $\text{Cd}_{0.75}\text{Mn}_{0.25}\text{Te}$ at a temperature of 10 K has a full width at half maximum of about 33 meV, indicating that the film has good crystalline quality.

The source of Mn was tricarbonyl(methylcyclopentadienyl) manganese (TCPMn), which is a liquid at room temperature. The hydrogen was bubbled through the TCPMn, which was heated to various temperatures between 120 and 140 °C to control the vapor pressure and, consequently, the concentration of the TCPMn. The tubes and valves carrying the TCPMn-laden H_2 and the front end of the reactor tube were heated to about 100 °C to prevent the TCPMn from condensing on them. The substrates were heated to temperatures of 410 to 450 °C, at which the metalorganic compounds decompose.

A series of depositions was made on glass substrates, and the optical transmissions were measured to determine the energy-band gaps, E_g (see Figure 1). Using the previously-known relation $E_g = 1.50 + 1.34x$ eV, it was then possible to determine the mole fractions, x , of Mn. X-ray diffraction scans of $\text{Cd}_{1-x}\text{Mn}_x\text{Te}$ films grown by MOCVD on GaAs matched those of $\text{Cd}_{1-x}\text{Mn}_x\text{Te}$ grown on GaAs by molecular-beam epitaxy. These films exhibited strong photoluminescence at temperatures of 10 to 15 K (see Figure 2).



Thomson Saginaw ball screw actuators... when only the best will do.

A machine's performance is only as good as its components. That's why Thomson Saginaw ball screws have been specified most in demanding aviation and aerospace applications since 1941.

Today, Thomson Saginaw is the new name for high-efficiency linear actuators – products formerly manufactured by the Actuator Products Group, Saginaw Division, General Motors Corporation. Now Thomson Saginaw is making machines more reliable in the manufacturing plant as well.

Operating at over 90 percent efficiency, Thomson Saginaw ball screws convert rotary motion to linear motion. Assemblies come in telescoping or miniature designs, with ground or rolled threads, or even lightweight tubular screws. Diameters range from $\frac{3}{16}$ inch to 4 inches.

From milling machines to flying machines, the names "Thomson" and "Saginaw" are synonymous with reliable, quality performance. We welcome your inquiries. For a copy of our new catalog – or for expert application assistance – call us at (517) 776-4123.

Or write Thomson Saginaw Ball Screw Company, Inc., Box 9550, Saginaw, MI 48608. Telex: 71425543. Fax: (517) 776-3632.



Circle Reader Action No. 413

THOMSON SAGINAW
First in Linear Actuator Technology

Although CdTe films have smooth, mirrorlike surfaces, the addition of Mn sometimes causes ripples with dimensions of a few thousand Angstroms and a hazy appearance. However, better control of process conditions should eliminate these im-

perfections.

This work was done by Akbar Nouhi and Richard J. Stirn of Caltech for **NASA's Jet Propulsion Laboratory**. For further information, Circle 49 on the TSP Request Card.

This invention is owned by NASA, and a

patent application has been filed. Inquiries concerning nonexclusive or exclusive license for its commercial development should be addressed to the Patent Counsel, NASA's Jet Propulsion Laboratory [see page 14]. Refer to NPO-17399.

Making a Precisely Level Floor

A sequence of pouring operations ensures flatness and smoothness.

Marshall Space Flight Center, Alabama

A floor-pouring procedure yields a large surface that is level, smooth, and hard. The method has been used to fabricate a 1,200-ft² (111-m²) floor that varies locally in elevation less than 0.015 in. in 16 horizontal in. (0.038 cm in 0.41 horizontal m) and slopes less than 20 s of arc from side to side.

The floor supports a 1,500-lb (680-kg) object on air bearings. The floor must be extremely level so that the object does not drift. The floor must also be extremely smooth so that an air-bearing gap of only 0.002 in. (0.0051 cm) can be maintained for adequate stiffness of the bearing.


The floor is made of a self-leveling, slow-curing epoxy with added black pigment. The epoxy is poured to a thickness no greater than 0.33 in. (0.84 cm) on a concrete base. The base floor should be seasoned, reasonably smooth and level, and at least 4 in. (10 cm) thick. The base should rest on a thermal barrier of gravel or cinders and should contain no steel plates, dividers, or bridges so as to minimize thermal distortion.

A metal retaining wall surrounds the base. The wall should be at least 1/2 in. (1.3 cm) higher than the poured floor. It should be sealed to contain the freshly poured mixture of epoxy and pigment and strong enough to absorb bumping by the object on the air bearings.

During pouring, two formulating machines supply epoxy through hoses while workers direct the flow. Workers continually supply the machines with raw materials until the job is done. A crew of 14 workers can pour the floor in 1 1/2 h.

Even a self-leveling epoxy cannot spread itself out uniformly over such a large area. Accordingly, before pouring, the workers mark off the concrete subfloor with a grid of 3-ft by 3-ft (0.91-m by 0.91-m) squares and partial squares (see figure). They surround a square or partial square with a sand-filled tube and fill it with the epoxy mixture, counting pulses from the pump to meter the correct amount. At the flow rate of about 6.3 in.³ (103 cm³) per pulse, 68 pulses furnish the approximate amount of material for one square.

When a square or partial square has been filled, workers quickly rearrange the sand-filled tube to surround an adjacent



A Grid Defines Incremental Areas for pouring the epoxy floor. Workers use the block numbers to follow a systematic pouring sequence, as shown by the serpentine arrows. One team pours the right half while the other pours the left half. The generally circular area is for maneuvering the test object. The smaller, trapezoidal area is for storage, entry, and egress.


square or partial square and fill it with the number of pulses necessary to cover the increment of area. Two groups of workers systematically fill blocks starting at opposite sides of the floor, each using a hose from one of the two formulating machines.

When all blocks have been filled, the machinery is turned off to minimize vibration and avoid kicking up dust while the epoxy cures. Meanwhile, workers eliminate air bubbles that rise to the surface. Moving on a catwalk suspended over the floor, they direct hot-air guns on extension handles into the bubbles to burst them.

The newly poured floor is then left totally undisturbed — even by strong air currents — for 10 days. Another 20 days of hardening should be allowed before heavy loads are placed on the floor.

This work was done by William G. Simpson, William H. Walker, Jim Cather, John B. Burch, Keith M. Clark, and Dwight Johnston of **Marshall Space Flight Center** and David E. Henderson of Sperry-Rand Corp. For further information, Circle 56 on the TSP Request Card.

MFS-28306



Top Gun: The Real Story

Top Gun, America's best aviators, train for perilous air-to-air combat in this thrilling video, which features actual dogfights, crashes, and MIG confrontations. Color. 35 minutes. (\$19.95)

Striking Back

Large radio-controlled models of aircraft, tanks, and ships recreate

the battle for the South Pacific during WWII. Explosions, machine-gun fire, and torpedo launches. Color. 40 minutes. (\$19.95)

Skydiving—The Ultimate Thrill

All aspects of skydiving—from preparation, jumping and freefall to stunts and landings—are covered, with close-up photography. Color. 30 minutes. (\$19.95)

JOIN THE ADVENTURE

NASA Tech Briefs Aviation/Space Videotapes put you at the center of the action: Climb into the cockpit of a high-flying jet and perform daring and dangerous stunts; Experience the thunderous launch of a Space Shuttle; Explore the fiery atmosphere of Jupiter or the frozen terrain of Mars. The choice is yours... The adventure awaits.



B-17: The Flying Fortress

See actual footage of the plane used most often in the raids over Germany. Includes interviews with the men who flew over Europe. Color/BW. 30 minutes. (\$19.95)

The History Of Flight

Produced by NASA, this exciting videotape examines man's quest to fly farther, faster, and higher. Includes footage of the Wright Bros., Charles Lindbergh, and other innovators. Color/BW. 30 minutes. (\$31.95)

Touch The Sky

Christopher Reeve goes inside the cockpit with the world's fastest and most spectacular stunt flying team, the Navy's Blue Angels. Color. 60 minutes. (\$34.95)

Space Shuttle—Satellite Rescue

You're a part of the action as the Space Shuttle Columbia's crew rescues and repairs an injured satellite. Color. 30 minutes. (\$19.95)



Apollo XI... The Eagle Has Landed

Clips of America's triumphant lunar landing. Produced by NASA, using actual commentary and footage by the astronauts. Color. 30 minutes. (\$19.95)

Landing On Mars

Actual Martian landscape captured in close-up, ground-level photography from the Viking mission. Color. 30 minutes. (\$19.95)

NASA: The 25th Year

Traces the steps of the Explorer I, Mercury, Gemini, Apollo, Viking, Voyager, Skylab, Space Shuttle, and Space Station programs. Color. 50 minutes. (\$29.95)




The Universe: A Journey Through Space And Time

Journey to the Milky Way Galaxy and beyond. Investigate the origin of the universe, pulsars, black holes, and more. Narrated by William Shatner. Color. 30 minutes. (\$29.95)

The Voyager Missions

Travel a billion miles to Jupiter, Saturn, and Uranus, as seen through the eyes of the Voyagers 1 and 2. Explore the planets, their rings and moons. Color. 28 minutes. (\$29.95)



Rush me the following VHS videotapes: (indicate quantity)

☐ Top Gun (\$19.95)	☐ Striking Back (\$19.95)	☐ Skydiving (\$19.95)
☐ B-17: The Flying Fortress (\$19.95)	☐ History of Flight (\$31.95)	☐ Touch the Sky (\$34.95)
☐ Space Shuttle Satellite Rescue (\$19.95)	☐ Apollo XI (\$19.95)	☐ Landing On Mars (\$19.95)
☐ NASA: The 25th Year (\$29.95)	☐ The Universe (\$29.95)	☐ The Voyager Missions (\$29.95)

I have enclosed \$_____ plus \$3.00 for postage and handling. Total enclosed: \$_____ (NY residents add sales tax)

Name _____

Company _____

Address _____

City _____ State _____ Zip _____

Send check or money order to: **NASA Tech Briefs, Dept. F, 41 East 42nd Street, New York, NY, 10017**

Making Multicore, Multishell Microspheres

Multiple streams of fluids would be combined to produce various structures.


NASA's Jet Propulsion Laboratory, Pasadena, California

Spherical or nearly spherical microshells containing two or more discrete inclusions, like eggs with more than one yolk, would be produced by a proposed technique. For example, a glass shell might hold a bubble of hydrogen adjacent to one of oxygen.

If desired, the spheres could be designed so that the cores combine to mix or react only after leaving the shell generator. Similarly, two or more shell-wall materials could mix or react after leaving the generator.

The technique would involve two (or more) pairs of coaxial nozzles (see figure). The converging jets of fluids from the separate nozzles would combine by surface tension, forming a liquid bridge of dog-bone-shaped cross section. The stream would eventually contract into a round cross section and break up into droplets. The apparatus could deliver one, two, or more different outer-shell-material streams with one, two, or more different core materials, each entrained in its own outer stream.

The droplet shells would solidify by freezing or by chemical reaction. The shell would be more or less spherical, but the precise shapes would depend on centering forces, surface tensions, temperatures, and aerodynamic and gravitational forces acting on the falling droplets. The extent of mixing or reaction of the shell and



Pairs of Coaxial Nozzles would be combined in arrays of two or more. Each pair of nozzles would generate an inner jet surrounded by a sheath of fluid. The multiple jets would combine to form droplets composed of shells and cores.

filler materials would depend on such properties of the materials as the viscosity and surface tension and on such controllable system parameters as the temperature, velocities, and volumes of the droplets.

This work was done by Andrew D. Morrison of Caltech for NASA's Jet Propulsion Laboratory. For further informa-

tion, Circle 44 on the TSP Request Card.

This invention is owned by NASA, and a patent application has been filed. Inquiries concerning nonexclusive or exclusive license for its commercial development should be addressed to the Patent Counsel, NASA Resident Office-JPL [see page 14]. Refer to NPO-17203.

Sleek New Design
In response to your suggestions,
we've combined the
Subscription/Technical Support
Package Form and the Reader Action
Card into a single convenient form.
Now you can renew your
subscription, order TSPs, and
request product information – all in a
single stroke.

Circularity-Measuring System

A shape gauge is designed especially for use on large objects.

Marshall Space Flight Center, Alabama

A shape gauge and an associated computer constitute a system that measures the deviations of large cylinders from roundness. Intended originally for use on the solid rocket boosters of the Space Shuttle, the system can also be used to measure the straightness, roundness, or complicated shapes of such large geometrical objects as the surfaces of aircraft and the hulls of ships.

The gauge (see Figure 1) has arms with two fixed end points, the distance between which is precisely 36 in. (914.4 mm). An outwardly-spring-loaded probe slides along the perpendicular bisector of the line between the fixed points and measures small displacements within 0.0001 in. (0.0025 mm). Roll and pitch sensors help the technician to level the gauge for maximum accuracy. Pins can be attached to the arms near the end points and to points near the probe, to mate with guide holes (if provided) in the object to be measured.

The technician measures the displacements at a sequence of positions around the circumference of the object. This could be done most conveniently by using the guide pins and indexing the gauge to a circumferential string of guide holes. The measured displacements are sent to the computer.


For each measurement, the portion of the measured surface between the end points can be approximated by the circular arc tangent to the end points and to the end of the probe. The computer calculates the arc for each measurement. It pieces together the arcs from the sequence of measurements to obtain a curve, consisting of circular-arc segments, that approximates the measured surface (see Figure 2).

This work was done by Walter B. Whippo, G. R. RohrKaste, and John E. Miller of Morton Thiokol, Inc., for **Marshall Space Flight Center**. For further information, Circle 129 on the TSP Request Card.


Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Marshall Space Flight Center [see page 14]. Refer to MFS-28313 (See page 84 for Figure 2)

**Are you reading
someone else's copy?**

Get your own copy by filling in
the qualification form bound into
this issue.




TECHNICIAN DISPLAYING MEASURING POINTS OF GAUGE



TECHNICIAN PREPARING TO INSERT GAUGE IN GUIDE HOLES

Figure 1. Shaped and Held Somewhat Like a Crossbow, the shape gauge measures the relative locations of three points on the surface of a large, round object. By making a connected series of measurements around the periphery, a technician using the gauge can determine the deviation of the object from perfect circularity.


CRYOGENIC RESEARCH SYSTEMS




Liquid Transfer Systems
Closed Cycle Refrigerators
Multiple Pin Leadless
Carrier Dewars
Pourfill Dewars
Custom Systems
Engineering/Design
Support
Equipment Rental
Temperature Cycling
Cryogenic Instrumentation
and Sensors

R.G. HANSEN & ASSOCIATES

631 Chapala Street
Santa Barbara, CA 93101
(805) 564-3388 FAX (805) 963-0733



CONSTRUCTION OF ARC FROM MEASUREMENT



CONNECTION OF ARCS

Figure 2. The **Shape of the Object** is approximated by piecing together the circular arcs computed from the sequence of measurements around its periphery.

Keeping Wax Liquid for Application

An applicator gun prevents wax from congealing prematurely.

Marshall Space Flight Center, Alabama

A "hot gun" applies masking wax and similar materials in a liquid state, unlike conventional methods of application. The gun, available commercially for applying hot glue, can be used to ensure that the wax penetrates and fills holes, flow passages, and manifold passages so that contamination is sealed off during manufacturing operations.

The usual method of applying masking wax is to spoon or pour it in liquid form from a hot pot into a hole. However, the wax starts to solidify as soon as it leaves the pot. When it reaches the hole, much of it is in a solid or near-solid state. It adheres poorly to the wall of the hole, and it flows sluggishly into the hole. Often, the hardening wax must be pushed into the hole. As a result, the seal is imperfect, and repeated applications are needed. Meanwhile, an ex-

cess of wax builds up and must be removed for inspection of the seal.

With the hot gun, in contrast, the holding chamber and the nozzle supply continuous heat to the wax, and the wax can be injected directly into the hole as a liquid. Nozzles of various sizes can be interchanged so that one can select a nozzle that has an opening suited to the viscosity of the wax and the size of the hole in a particular application. The trigger mechanism of the gun meters the wax so that excess material does not build up. The hot gun is fast, eliminates repeated application, and greatly reduces cleanup time.

This work was done by Russell V. Meyer of Rockwell International Corp. for Marshall Space Flight Center. No further documentation is available.
MFS-29238



Mathematics and Information Sciences

Hardware Techniques, and
Processes

85 Automatic Parametric
Testing of Integrated
Circuits

Book and Reports

85 Exponential Finite-
Difference Technique
88 Inversion of Jacobian
Matrix for Robot
Manipulators

Automatic Parametric Testing of Integrated Circuits

A software system generates its own test instructions and teaches itself new tests.


NASA's Jet Propulsion Laboratory, Pasadena, California

A computer program for parametric testing saves time and effort in research and development of integrated circuits. The software system automatically assembles various types of test structures and lays them out on a silicon chip, generates a sequence of test instructions, and interprets the test data. The system employs self-programming software; it needs a minimum of human intervention. It can be adapted to the needs of different laboratories and can readily accommodate new test structures.

The designer of an integrated circuit decides on the type and number of test structures — transistors of various polarities and sizes, split-bridge resistors, van der Pauw crosses, and the like. With this information, the system automatically generates the geometrical specifications for the test structures that are to be built into the integrated circuit. The specifications are used to fabricate silicon wafers containing the circuit (see figure). Meanwhile, the system produces instructions for testing the chip.

If the engineer devises a new test structure, the system teaches itself how to specify and lay out the new structure and determines how it should be tested. The engineer merely adds a few lines about the new structure in a declaration file; the engineer does not have to make any changes in the test-program-generator portion of the software.

The program reduces the large amount of data on the structures to statistical summaries for individual wafers and for entire lots of wafers. Additional programs use the statistical summaries to perform such tasks



The **Parametric-Testing Software System** proceeds from the engineer's selection to control automatically the fabrication of test structures in integrated circuits, the operation of the testing equipment, and the analysis of the test data. The system also produces program listings in easily read form.

as high-level analysis, extraction of parameters, and mapping of wafers.

The program codes are designed to be adaptable to most computers and test equipment now in use. They are written in high-level languages to enhance transportability.

This work was done by Glenn A. Jennings and Cesar A. Piña of Caltech for NASA's Jet Propulsion Laboratory. For further information, Circle 68 on the TSP Request Card.
NPO-16783

Books and Reports

These reports, studies, handbooks are available from NASA as Technical Support Packages (TSP's) when a Request Card number is cited; otherwise they are available from the National Technical Information Service.

Exponential Finite-Difference Technique

Various partial differential equations are solved numerically.

A report discusses the use of an explicit exponential finite-difference technique to solve various diffusion-type partial differential equations. Previously, the technique was applied only to transient-heat-transfer problems in one dimensional Cartesian coordinates. This study extends the tech-


nique to transient-heat-transfer problems in one dimensional cylindrical coordinates and two and three dimensional Cartesian coordinates and to some nonlinear problems in one or two Cartesian coordinates.

As an application of the finite difference technique, the linear, two-dimensional Cartesian, transient, diffusion-type equation for temperature in an isotropic medium is treated by the classical method of separation of dependent variables. The separated-variable ratio that contains the temporal derivative leads immediately to

forced case: $y'' + y + \varepsilon y^3 = \varepsilon \delta \cos(t)$
 $y \sim \frac{36}{3} \delta \cos(t) + \frac{\varepsilon \delta}{72} (-\cos(t) + 3 \cos(3t)) + \dots$
 $+ PV' \left(\frac{2V'}{r} + V^2 \cot(\Theta) \right)$
 $+ V' \left(V' \frac{\partial P}{\partial r} + V^2 \frac{\partial P}{\partial \Theta} + V^3 \frac{\partial P}{\partial \varphi} \right) + \text{VISCO TERM}$
 control pitch thru $\vec{u}: \vec{y}' = A\vec{y} + B\vec{u}$
 $TFM_{1,1} = \frac{\alpha}{s^3 - 2s^2 + s - 2\alpha}$
 $\left[\begin{matrix} \text{Matrix} & t \\ e & \end{matrix} \right]_{1,2} = \frac{6e^{5/2}}{\sqrt{33}} \sinh\left(\frac{\sqrt{33}}{2} t\right)$ from Macsyma
 $|TFM_{ij}|$

 Fourier $|\sin(t)| \rightarrow \frac{2}{\pi} \left(1 - \sum_{n=1}^{\infty} \frac{(1+(-1)^n) \cos(nt)}{n^2 - 1} \right)$

Macsyma[®] the most powerful math software in the world of mainframes, *now on* *PC's.*



Circle Reader Action No. 524

Until now, if you wanted to combine symbolic and numerical analyses into a powerful approach to mathematical modeling, there was only one way to do it — MACSYMA and a *big* computer.

Now we've taken all the power, performance and productivity of MACSYMA and created a PC version, one that runs on any 386/DOS-based PC*.

So now you can perform complex symbolic, numerical, and graphical calculations automatically — in applications ranging from plasma physics to aeronautics, from economics to fluid mechanics and more — right at your desk. Such as differential and integral equations, Laplace and Fourier transforms, vector and tensor calculus. The same calculations that used to require mainframe performance.

There's one thing about MACSYMA that isn't complex — using it. In fact, using MACSYMA is so easy, you can get right to work using our On-line Help and Quick Reference Card — without even opening a book.

MACSYMA on a PC. As easy as π .
 Call 1-800-MACSYMA (in
 Massachusetts, 617-221-1250).

symbolics, Inc.

Computer Aided Mathematics Group
 8 New England Executive Park East
 Burlington, MA 01803 U.S.A.

MACSYMA is a registered trademark of Symbolics, Inc.
 * 100% IBM compatibles.

the expression of the transient effect in a multiplicative exponential term in time. The separated-variable ratio that contains the partial spatial second derivatives is approximated by a finite-difference term for the temperatures at four adjacent grid points at one time step.

The two separated-variable ratios are equated to the exponential time parameter and thus combined to obtain the single explicit, finite-difference expression for the temperature at the next time step:

$$T_{ij}^{n+1} = T_{ij}^n \exp\{\Omega M_{ij}\}$$

where T = temperature, the superscripts denote the time steps, the subscripts denote the grid points, M_{ij} is the four-grid-point, finite-difference form of the separated-variable ratio for the Laplacian of temperature at the n th time step, and Ω is a dimensionless time parameter that combines the effects of the diffusivity and the grid spacing. The time step can be divided into $m + 1$ subintervals to improve the convergence of the solution by writing

$$T_{ij}^{n+1} = T_{ij}^n \exp\left\{\left[\frac{\Omega}{m+1}\right] \sum_{p=0}^m M_{ij}^{n+p/(m+1)}\right\}$$

The equations obtained in an analysis of the cylindrical problem are similar, except that M_{ij} is reduced to the one-dimensional form M_i and contains a radial-expansion term.

The time step and grid spacing must be made small enough to assure numerical stability. The divergence or convergence of the solution is easily expressed in terms of the growth of the exponential at each step, and, as a result, the criteria for stability are conveniently expressed as conditions on M_i or M_{ij} , or on the size of the dimensionless time subinterval $\Omega/(m+1)$.

Boundary and initial conditions are treated in a straightforward manner by suitable numbering of grid points and substitutions of known temperature values into the expressions for M_i^n and M_{ij}^n . Where a flux of heat is specified at a boundary, the use of that specified difference of temperature across the boundary that determines the specified flux must be used.

The nonlinear cases considered in this study are the viscous Burger's equation and the steady-state equation for boundary-layer flow over a flat plate. In both cases, the differential equation must be linearized.

The exponential finite-difference technique was compared with several other numerical techniques and with exact solutions (where available) in application to several heat-transfer and flow problems. The exponential-finite-difference solutions were closer than the others to the exact solutions in those problems for which exact solutions were available.

This work was done by Robert F. Handschuh of the U.S. Army Aviation Research and Technology Activity for Lewis Research Center. Further information

Only one company has it: Alcatel

Clean, efficient,
10⁻⁶ mbar ultimate
vacuum

Clean room compatible -
no contamination
even in a power failure

Oil free - requires
no pump fluids



High throughput
for all gases

Compact and
portable

Totally field
serviceable

New Drytel 30 oil free, portable pumping unit


A new concept in oil free pumping based on Alcatel's exclusive molecular drag principle . . . Alcatel can now offer all the advantages of its unique molecular drag pump in a totally oil free portable pumping unit. DRYTEL 30 interstages an oil free mechanical pump with the MDP booster to provide soft start evacuation from atmosphere to mid range vacuum levels and clean 16 cfm throughput from 10⁻¹ to 10⁻⁶ mbar. DRYTEL 30 not only provides clean, oil free evacuation but also is most effective in a range where conventional mechanical pumps have limited or reduced efficiency and a tendency to backstream their lubricating fluid.

Applications:

- Cryogenics
- Regeneration of cryopumps
- Oil-free roughing of ultrahigh vacuum installations
- Mass spectrometry
- Differential pumping for RGA's
- Fast oil-free pumping of load locks
- Backing of turbomolecular pumps
- Leak Detection
- Roughing for AUGER, SIMS, MBE
- Electron tubes/CRT's

Write or call for specifications and pricing.

Alcatel Vacuum Products, Inc.,
40 Pond Park Road,
Hingham, MA 02043
Tel: 617-749-8710 (MA);
408-746-2947 (CA);
609-596-3377 (NJ).



Circle Reader Action No. 566

may be found in NASA TM-89874 [N87-24930], "An Exponential Finite Difference Technique for Solving Partial Differential Equations."

Copies may be purchased [prepayment required] from the National Technical Information Service, Springfield, Virginia 22161, Telephone No. (703) 487-4650. Rush orders may be placed for an extra fee by calling (800) 336-4700. LEW-14737

Inversion of Jacobian Matrix for Robot Manipulators

A closed-form transformation from task space to joint space is computed efficiently.

A report discusses the inversion of the Jacobian matrix for a class of six-degree-of-freedom arms with spherical wrist, i.e., with the last three joints intersecting. The authors show that by taking advantage of the simple geometry of such arms, the closed-form solution of $\mathbf{Q} = \mathbf{J}^{-1}\mathbf{X}$, which represents a linear transformation from task space to joint space, can be obtained efficiently.

The inverse transformation, represent-

ed as $\mathbf{Q} = \mathbf{J}^{-1}\mathbf{X}$, is essential for the implementation of the advanced task-space control schemes since the actuation; i.e., the application of forces/torques is ultimately performed at the joints level. However, while the forward transformation, given as $\mathbf{Q} = \mathbf{J}\mathbf{X}$, presents no major problem, the computation of the inverse transformation is more difficult, and previous authors have studied ways to perform it efficiently. The main motivation in the development of the previous methods has been to avoid the prohibitive computational cost, which arises from the symbolic or numerical computation of the Jacobian and its numerical inversion.

The theoretical development in this paper involves the derivation of the Jacobian vectorial matrix, which is a general form of the Jacobian from which specific Jacobians can be derived by a set of appropriate transformation, i.e., velocity reference point transformation as well as projection onto the applicable coordinates. The authors develop a relatively simple method in which the Jacobian vectorial matrix and corresponding transformations are derived by relating the velocity of two points. It is shown that any specific Jacobian can be described in terms of another Jacobian with arbitrary choice of velocity reference point and coordinate frame, which can be chosen to yield the Jacobian in its simplest symbolical form leading to its symbolic inversion and the closed-form solution of $\mathbf{Q} = \mathbf{J}^{-1}\mathbf{X}$.

The report presents solutions for a PUMA arm, a JPL/Stanford arm, and a six-revolute-joint coplanar arm along with all singular points. The solution for each joint variable is found as an explicit function of the singular points, thus providing better insight into the effect of the singular points on the motion of, and force/torque exerted by, each joint.

The main contribution of this paper is to show that the simple geometry of this type of arms can be exploited in performing the inverse transformation without any need to compute the Jacobian or its inverse explicitly. The cost of computing the inverse transformation becomes of the same order as that of the cost of computing forward kinematic position transformation, and it is significantly reduced if this transformation is already performed. The implication of this computational efficiency is that advanced task-space control schemes for spherical-wrist arms can be implemented more efficiently.

This work was done by Amir Fijany and Antal K. Bejczy of Caltech for NASA's Jet Propulsion Laboratory. To obtain a copy of the report, "Efficient Jacobian Inversion for the Control of Simple Robot Manipulators," Circle 125 on the TSP Request Card. NPO-17544

AMCO CABINETS

Design and craftsmanship now comes in wide array of sizes and colors

Intelligent design and fine craftsmanship are the hallmarks of Amco Cabinets. Now, Amco Cabinets for Electronics—desk, bench, and portable—are available to you in a very wide variety of off-the-shelf sizes styles and colors.

Custom sizes and colors are available in a range to fit most any need—without affecting quality.

Call us now for your free full color #900 Catalog.

Dial 1-800/833-3156
In Illinois
1-312/671-6670*


*As of Nov. 11, 1989—New Area Code will be 708.



AMCO Engineering Co.
3801 N. Rose Street
Schiller Park, IL
60176-2190



Burr-Brown's World of DSP SOLUTIONS



Any way you look at it, we have the tools to give you a broad range of digital signal processing solutions.

DSP Code Generation, The Easiest Way

Our DSPlay XL™ software package revolutionizes code generation for DSP applications. You don't need the extensive knowledge you once did for DSP algorithm development. Now you can quickly create *highly efficient* code for AT&T's DSP32 processor through the creation of a simple block diagram. Then, with a simple keystroke, you can download the code to our ZPB32 Floating Point Processor board for execution.

DSPlay XL features a fully integrated development environment. It includes graphic editor, large function libraries, extensive display capabilities, code generator, assembler, debugger, disassembler, filter design capability, and test editor. It supports data converters and multiple DSP32 processors, too.

Floating Point DSP Power for the VMEbus

Now you can have floating point DSP power for the VMEbus. Our new ZPB3200 series boards offer 32-bit processing using the AT&T DSP32 (160ns) processor.

Two versions are available: the ZPB3201 features a single DSP32 processor, while the ZPB3202 has two. They provide 12 and 24 million floating point calculations/second, respectively. Buffered serial I/O ports facilitate connection with our growing line of high-performance ADC and DAC products, or interconnection between VME DSP processor boards. Each processor comes complete with 64K Bytes of zero-wait state SRAM, and parallel interface to the VMEbus. The ZPB3200 is ideal for SONAR, RADAR, Speech, and machine monitoring applications.

can get it through your local bookseller (ISBN 0-13-212853-5) or through Burr-Brown.

Part Numbers:

DSPlay XL: #ZPM32
VME Boards: #ZPB3201
 #ZPB3202
PC Boards: #ZPB32 (250ns)
 #ZPB32-HS (160ns)
DSP Book: #Book-05


Look to Burr-Brown for a full line of DSP solutions. You'll find they'll give you the shortest route from development to integration. For complete details, write Burr-Brown Corporation, P.O. Box 11400, Tucson, Arizona 85734. Or, call **1-800-548-6132** toll free.

DSPlay XL™, DSPlay™,
Burr-Brown Corporation



Primer on Digital Signal Processing

Prentice-Hall's new book, "Digital Signal Processing Experiments," presents easy to learn DSP fundamentals. Its 100+ pages contain a concise overview of DSP functions and Algorithms, 12 exercises, and a special educational version of our popular DSPlay™ software. You



BURR-BROWN®
BB

New on the Market



Melles Griot Inc., Irvine, CA, has developed a compact 120-watt **carbon dioxide laser** for industrial applications. The laser head weighs 60 pounds and is completely sealed, requiring only 280 VAC power and 6 liters/minute cooling water. The portable unit offers +8% long-term amplitude stability, a 5.5 mm beam diameter, and a 350-nanosecond standard pulse decay time, with optional 150-nanosecond performance available.

Circle Reader Action Number 750.



The Model 2220 solid-state **monochrome video camera** from CIDTEC Inc., Liverpool, NY, features a progressively scanned 256 x 256 binary format CID array that matches standard memories for efficient computer interfacing. The camera's square pixels simplify processing algorithms and its contiguous structure ensures accurate image detail. A frame reset function allows users to adjust frame size for high-speed variable output.

Circle Reader Action Number 790.




Triumph, a new **rust converter** and primer coating from United Laboratories Inc., Addison, IL, instantly turns rust into phosphates for easy removal without scraping or sandblasting. The phosphating paint, which cures rock-hard, covers up to 530 square feet per gallon and can be applied with a brush or diluted with water for spray applications. It contains no lead or solvents, is compatible with wet surfaces, and tolerates extreme temperature changes without cracking or peeling. A gallon costs \$59.00.

Circle Reader Action Number 794.


NCUBE, Beaverton, OR, has unveiled a **massively parallel supercomputer** with unprecedented processing speed. The 6400 Series Scalar Supercomputer uses up to 8192 processors to achieve a maximum performance of 100 billion instruction executions per second and 27 billion scalar floating point operations per second. Because the processors can operate independently in parallel, the 6400 is ideally suited to simulating and performing calculations upon dynamic processes involving many different variables. Potential applications include structural and chemical analysis, fluid dynamics, artificial intelligence, signal processing, and robotics.

Circle Reader Action Number 782.




The Diplomat™, an aerodynamic **blower** developed by Comair Rotron, Saugerties, NY, features a diffuser mounting that reduces noise and improves air flow, a foam scroll that deadens sound, and a seven-bladed propeller with a patented feather edge. Targeted for the mini-mainframe computer market, the Diplomat can be custom-configured to fit a wide range of dimension and air flow requirements.

Circle Reader Action Number 784.




The Seatek Company Inc., Stamford, CT, has combined a gripping vise and a miniature hacksaw to create a new labor-saving **hand tool** called the Swing-Saw Sealtite Cutter. The top lever, which actuates the saw blade, provides leverage for a strong cutting action, while the hacksaw hinged to the vise makes precise square cuts each time. The Swing-Saw can cut copper and steel tubing, threaded rods, and cables up to 1.5 inches in diameter.

Circle Reader Action Number 780.



The new KH 500 **fluorescent work light** with 13-watt U-lamp produces as much light as a 60-watt caged incandescent but lasts ten times longer, according to the manufacturer, KH Industries of Angola, NY. Available with a 25 or 50 foot neophrem jacket, the portable light is sealed against moisture, dust, and vapors. Its shatterproof butyrate tubeshield protects against damage from falling objects, flying glass, and sparks.

Circle Reader Action Number 798



Metron Optics Inc., Solana Beach, CA, has developed a **three-dimensional video system** that forms realistic images in mid air. Especially useful for remote viewing of hazardous areas, the stereoptical system employs two video cameras and a 3D monitor to create flicker-free color pictures with natural depth. Metron also manufactures a 3D video microscope with 360 degree rotation and plans to offer 3D recording on videotape using a super VHS recorder with stereophonic sound.

Circle Reader Action Number 788.


AT&T Microelectronics has unveiled the fastest **digital signal processor** (DSP) to date—a 25-nanosecond chip that processes data at 40 million instructions per second. Since just one 25-ns DSP chip can perform jobs that previously required several devices, designers can use the new chip to conserve valuable board space. Now available in sample quantities, the processor is suited for telecommunications and computer applications, such as modems, digital cellular phones, laser printers, and optical character recognizers.

Circle Reader Action Number 760.



Charleswater Products Inc., West Newton, MA, is offering samples of REZTORE™, an **antistatic cleaner** that removes dust, grime, solder, grease, and fingerprints from conductive and insulative work surfaces. The product features zero ionic contamination, contains no amines, cleans without abrasion, and leaves no insulative residue or film. Effective at cleaning vinyl and rubber mats, high-pressure laminates, metal, glass, and plastic, REZTORE comes in an 8-ounce pump spray, trigger spray quart bottle, or gallon container.

Circle Reader Action Number 796.



The Spirflame, a self-contained **gas production unit** from Solder Absorbing Technology Inc., Springfield, MA, can generate a flame small enough to thread through the eye of a needle or large enough to cut 2 mm steel. Flame temperature and size are electronically stabilized at the selected intensity. The device produces gas from the electrolysis of water and is useful for soft soldering, brazing, fusion welding, flame polishing, and other industrial applications.

Circle Reader Action Number 778.

A powerful new software product that **extends hypertext technology** into the realm of true information analysis has been introduced by the Envos Corp., Mountain View, CA. The software, called Envos Note-cards, is useful for organizing and analyzing large amounts of textual data. Among its features are graphics editors for creating onscreen "notecards" of whole documents; overlapping windows that allow multiple notecards to be viewed concurrently; a "browsing" function that enables users to view and manipulate the entire card network, and automatic conversion of cards into printed documents. Envos Note-cards runs on Sun workstations.

Circle Reader Action Number 766.

New on the Market



The 700 Series Polycorder®, a portable data logger designed for industrial testing, is now available from Omnidata International Inc., Logan, UT. The battery-powered unit contains up to 448 K-bytes of memory and a 12-bit A-D section that can scan more than 75,000 samples per second. Standard features include an RS-232 port, ten analog channels, eight digital I/Os, a synchronous hardware trigger, and two direct accelerometer inputs. The Polycorder is fully programmable, enabling the user to develop an infinite number of data collection algorithms.

Circle Reader Action Number 800.

Science/Electronics, Dayton, OH, is marketing a line of battery-powered data loggers with direct RS-232 serial interface. The systems, dubbed Squirrel Meter/Loggers, offer multiple input and can store up to 42,000 readings on board in RAM. Users can record temperature, voltage, current, pulses, 8-bit inputs, or events. Logging includes real-time documentation. The low-power CMOS circuitry permits unattended recording runs for up to six months.

Circle Reader Action Number 764.



A new series of subminiature precision DC-DC rate gyroscopes has been developed by Humphrey Inc., San Diego, CA. Fluid-filled for precise damping and shock protection, the tiny (2.0" x 2.0" x 3.5") gyros are designed for demanding rate control requirements, such as fire control systems, antenna stabilization, aircraft control, and missile systems. They come in rate ranges from 40 to 1000 degrees per second with natural frequency of 20 to 140 Hz.

Circle Reader Action Number 758.

The 400 Series digital oscilloscope from Nicolet Test Instruments, Madison, WI, offers a record 256K work memory per channel and permits cascading together four channels for memory as long as 1 megasample. This memory is complemented by a standard 32-bit CPU, providing waveform processing up to 100 times faster than interfacing with a PC. Available in two- and four-channel models, the 400 Series also features a 44-megabyte hard disk, a transportable floppy drive for automated testing, easy-to-use front panel controls, and IEEE-488.2 interface software.

Circle Reader Action Number 756.



The new Challenge 3000 modular workstations can be tailored to each operation or task, resulting in more cost-efficient and productive use of factory space. Designed by Advance Engineering, North Hollywood, CA, the stations can be configured as individual units or single- and double-sided assembly lines. A unique utility distribution system allows power, air, and other utilities to be passed from one unit to another. Work surfaces, light fixtures, and shelving are adjustable for maximum operator efficiency and convenience.

Circle Reader Action Number 762.



Working from a palette of 16.7 million colors, Polaroid's new Bravo Computer Slide Maker (BCSM) creates boardroom-quality images with up to 8,000 lines of addressable resolution. The digital film recorder produces both instant and conventionally-processed 35mm slides at a fraction of the cost of outside slide services, according to the manufacturer. Available in either IBM- or Apple Macintosh-compatible versions, the BCSM simply plugs into the host computer and is ready to go.


Circle Reader Action Number 792.

Optimize Filter Response to Fit Your Design Target!

COMTRAN® - Now on a PC*

- Designs filters with custom-shaped responses
- Magnitude, Phase, Zin, Zout, or combination
- Fits any precision response using available capacitor values (by recalculating resistors)
- Derives equivalent circuit from measured data
- Cuts opamp count in half (4 poles per opamp)
- Tolerance, Time Domain, Waveform Digitizing
- FAST - Less than 1 second per point typical


*Requires AT compatible w/ HP 82300B BASIC Language Processor card w/1 MB RAM, & HP 9122 floppy drive. This card adds HP Rocky Mountain BASIC, w/ HP-IB interface, to your PC. Lets your PC run HP 200/300 BASIC software. COMTRAN previously ran only on HP computers.



COMTRAN® Integrated Software

A Division of Jensen Transformers, Inc.
10735 BURBANK BOULEVARD, NORTH HOLLYWOOD, CA 91601
FAX (818) 763-4574 • PHONE (213) 876-0059

Circle Reader Action No. 480



Get your new enclosure catalogs from Optima.

- ☐ E.I.A. Rack Mounting
- ☐ RFI Shielding
- ☐ Vertical Cabinets
- ☐ Desk Systems
- ☐ Custom Applications
- ☐ Small Cases
- ☐ TEMPEST

Call (404) 496-4025

(or circle the reader service number below).

See our product data in EEM.



Gichner

Optima® Enclosures

2166 Mountain Industrial Blvd., Tucker, GA 30084-5088
(404) 496-4000 • FAX: (404) 496-4041 • *We make you look better!*

Circle Reader Action No. 624


MINCO PROBLEM SOLVER #11

PRODUCT:

Flex-Circuits

Now certified to
MIL-P-50884(C), Type 4!

DRAWING:



Wire-Wound
Inductive Coil

Stiffener For
Component Insertion

APPLICATION:

Aerospace, medical, military instruments.

FEATURES:

Multilayers: Plated through-hole interconnects.
Complete Assemblies: Stiffeners, connectors, pins.
Quality Assurance: Stringent documentation.

SPECS: MIL-P-50884(C), Type 4; NHB5300.4(1B); FDA Regulation Part 820; MIL-Q-9858.

USER NOTES: Use for greater wiring density, reduced space and weight, high reliability in critical applications.

When quality and performance are as important as price, call...

MINCO PRODUCTS, INC.

7300 Commerce Lane/Minneapolis, Minnesota 55432 U.S.A.
Telephone: (612) 571-3121/TWX: 910-576-2848/FAX: (612) 571-0927

Circle Reader Action No. 388

WE WRITE MANUALS

Information Development Incorporated specializes in providing high quality technical writing and documentation.

By using our services, you

SAVE TIME
SAVE MONEY
CONSERVE TALENT

For half a decade, IDI has provided superior documentation for Fortune 500 companies, engineering and research groups, and government agencies.

Call today:
INFORMATION DEVELOPMENT, INC.
4219 Richmond Avenue, Suite 290
Houston, Texas 77027
(713) 623-8735

Circle Reader Action No. 488

New Literature



A 32-page catalog of **electronic testing and prototyping equipment** is now available from Global Specialties, a division of Interplex Electronics, New Haven, CT. Offered free of charge, the catalog features Global's breadboarding products, logic test devices, power supplies, test instruments, and accessories. New products include the DSA-250, a low-cost digital storage adapter, and a line of data communications equipment.

Circle Reader Action Number 702.



A 24-page catalog describes **cleaning and preventive maintenance products** from the Texwipe Company, Upper Saddle River, NJ. Distributed free of charge, the publication is divided into seven product categories: wipers, clean room wipers, solvents and cleaning solutions, swabs and facemasks, premoistened pads, compressed gas, and cleaning kits. A color-coded index enables users to quickly match applications to products.

Circle Reader Action Number 712.

Electrospec Inc., Dover, NJ, is offering a free 216-page **network communications catalog**. Featured products include baluns, cable assemblies, connectors, couplings, interconnect hardware, fiber optic components, switch boxes, cabinets, panels, and networking tools. The catalog contains product photographs and a glossary.

Circle Reader Action Number 722.

A new line of **super precision bearings** is described in a catalog from the Torrington Company, Torrington, CT. The 95-page publication provides specifications for 20 styles of precision bearings for machine tools, pumps, compressors, and other exacting applications. In addition, the catalog reviews key considerations in bearing selection, such as mounting arrangement, balance, bearing geometry, alignment of rotating parts, and lubrication.

Circle Reader Action Number 716.

Extra and Super
Precision Bearings



NYRIM®, a new **thermoplastic** designed to withstand heavy wear and tear in hostile environments, is featured in a free brochure from CUE Inc., Mars, PA. Produced by chemically bonding a copolymer of nylon -6 to an impact-resistant elastomer, NYRIM is easily cast into stock shapes—including rod, tube, and sheet—which can then be machined into such finished parts as automotive cooling fans, gears, pulleys, machine housings, pump impellers, and filter plates. The four-color brochure outlines advantages the thermoplastic offers over metals, and includes a list of typical properties.


Circle Reader Action Number 724.



A guide to **aerospace propulsion forgings** is available from the Shultz Steel Company, South Gate, CA. Product highlights include rotating part forgings (shafts, disks, and impellers) for gas turbine engines; turbine rings, casings, domes, and nozzles; and rocket engine parts. The free brochure also details the company's quality control of metallurgical microstructures and computer simulation capabilities.

Circle Reader Action Number 708.

New Literature



A four-color engineering manual and catalog from Disogrin Industries, Manchester, NH, provides design, selection, and application data for a variety of **hydraulic seals**, including U-cup seals, rod wipers, piston seals, flange packings, O-rings, and wear rings. Schematic drawings clarify design and installation procedures, while tables, graphs, and curves offer information on chemical compatibility, tear strength, abrasion resistance, and other key factors in seal selection.

Circle Reader Action Number 710.



US Technology Corp., Danielson, CT, has produced a brochure that explains the benefits of **dry stripping** paint and other surface contaminants from aircraft and electronic components. As a replacement for hazardous chemical strippers, dry stripping eliminates expensive disposal problems, according to the brochure, which includes sample packets of three media hardness grades: PolyPlus®, PolyExtra®, and Type III®. Relative hardness is discussed and correlated to performance on a variety of surfaces, including composites.


Circle Reader Action Number 718.

"Magnetics For Telecommunications," a new catalog from Prem Magnetics Inc., McHenry, IL, features more than 80 **coupling transformers for voice and data applications**. Products include feedbridge inductors, single hybrid transformers, and a new series of telephone interconnect transformers that have received British Standard Institute (BSI) approval.

Circle Reader Action Number 714

Heat transfer equipment for aircraft, aerospace, electronics, and other high-technology industries is highlighted in a color brochure from the affiliated companies of Lytron and Alpha United. Aluminum heat exchangers are displayed in many configurations, including oil coolers, evaporators, condensers, cryogenic heat exchangers, and bleed air coolers. The free brochure also describes cold plates, cold walls, and cooling enclosures for high-density electronics systems.

Circle Reader Action Number 720.




More than 2,000 **programmable devices** are featured in a new booklet from Logical Devices Inc., Fort Lauderdale, FL. Organized by manufacturer and device architecture, the booklet specifies which LDI programmer supports each device, or if future support is planned. Information on device technology includes number of pins, array size, and voltage.

Circle Reader Action Number 706.

Applications for more than 200 **thermal spray and plasma transferred-arc coatings** are outlined in a free brochure from General Plasma, East Windsor, CT. The four-page publication lists OEM specifications for wear-resistant, corrosion-resistant, thermal barrier, abradable, dielectric, conductive, dimensional restoration, and medical implant coatings.

Circle Reader Action Number 726.



The Yokogawa Corp. of America, Newnan, GA, is offering a free **strip chart recorder selection guide**. The fold-out wall poster identifies and defines recording methods, higher-level functions, signal inputs, and printing options.

Circle Reader Action Number 704.

INFRARED TEST INSTRUMENTATION



CUSTOM OR STANDARD

DEWARS (4-300K)

POUR FILL

DEMAND FLOW

CLOSED CYCLE

VACUUM PUMP STATIONS

RADIOMETRIC TEST SYSTEMS

CRYOGENIC PROBE STATIONS

ISI INTEGRATED SENSORS, inc.

69 Santa Felicia Drive, Goleta, CA 93117

Circle Reader Action No. 342



Put a Lid on EMI

Sensitive field electronics need EMI containment and protection to get the job done safely, and correctly.

The Zero Centurion® Elite Series 200 sets a new standard for good looks and shielding safety.


Choose from 16 sizes, and a wide host of options, including special environmental seal. **FIVE DAY SHIPMENT FROM STOCK.**

Call Today for Additional Information.

818 897-7777

ZERO HALLIBURTON


12224 Montague, Pacoima, CA 91331



New! Collector's Edition Poster

Space Shuttle

NASA Facts



**Actual
Size:
42"
wide by
30"
high—
in full
color!**

**Only
\$8.95**

Both artistic and educational, this beautifully illustrated full-color poster presents a cutaway view of the Space Shuttle that reveals its inner workings. Provides size, wingspan, weight, and thrust data. 42 by 30 inches. Folded.

Special introductory price only \$8.95 each!

BONUS: Order now and receive three prints for only \$23.95.

Please rush me _____ Space Shuttle posters.

I have enclosed \$ _____ plus \$2.50 for postage and handling.

Total enclosed: \$ _____ (New York residents add sales tax)

Name _____

Address _____

City _____ State _____ Zip _____

Send payment to: NASA Tech Briefs, Shuttle Poster Offer
41 East 42nd St., New York, NY 10017-5391



Subject Index

A

ACOUSTIC MEASUREMENT
Detecting impacts of particles on spacecraft
page 42 MFS-28278

AIRFOILS
Measuring laminar-separation bubbles on airfoils
page 68 LAR-13952
Navier-Stokes calculations with deforming grid
page 66 LEW-14711

ANNEALING
Rapid annealing of amorphous hydrogenated carbon
page 58 LEW-14664

ANTENNAS
Adjusting surfaces of large antenna reflectors
page 34 LAR-13851

AXISYMMETRIC FLOW
Upwind swirl coupling in Navier-Stokes calculations
page 71 MFS-29542

B

BOUNDARY LAYER SEPARATION
Measuring laminar-separation bubbles on airfoils
page 68 LAR-13952

BOUNDARY PROBLEMS
Boundary-value problem for magnetic-cutoff rigidities
page 50 NPO-17294

C

CADMIUM TELLURIDES
Chemical-vapor deposition of $Cd_{1-x}Mn_xTe$
page 76 NPO-17399

CARBON
Rapid annealing of amorphous hydrogenated carbon
page 58 LEW-14664

CARBON FIBER REINFORCED PLASTICS
PMR resin compositions for high temperatures
page 56 LEW-14658

CHARGED PARTICLES
Boundary-value problem for magnetic-cutoff rigidities
page 50 NPO-17294

CINEMATOGRAPHY
Reducing heating in high-speed cinematography
page 44 LEW-14798

CIRCULAR CYLINDERS
Circularity-measuring system
page 83 MFS-28313

Laser Scanning Components For New Applications Yet To Be Discovered.

We're ready to explore new scanning territory with you! New applications are constantly being discovered utilizing Lincoln's laser scanning technology... already proven for laser printing, photocopying, bar code scanning, inspection processing, typesetting and much more. **A leading supplier of:** ♦ Motors ♦ Controllers ♦ Hydro-Dynamic and Hydro-Static Air Bearing Assemblies ♦ Diamond Machined or Conventionally Polished Polygonal Mirrors ♦ Complete Motor Polygon Assemblies

We excel at meeting new challenges and welcome the opportunity to quote on your single piece prototype or large quantity production requirements.



LINCOLN LASER COMPANY


234 East Mohave, Phoenix, Arizona 85004, FAX: (602) 257-0728, Phone: (602) 257-0407

HIGH PERFORMANCE, HIGH PRECISION BALL SCREWS

Thomson Saginaw ball screws give you:

- precision – lead accuracies to .0002"/ft. and custom preloads for optimum stiffness
- smoothness – 90% plus efficiency, zero backlash for uniform feed
- repeatability – precise positioning time after time
- dependable service – operating life measured in millions of cycles

Send your drawings or sketches for a free proposal and estimate. Or, ask for our new Linear Actuator Technology Guide. Thomson Saginaw Ball Screw Company, Inc., P.O. Box 9550, Saginaw, MI 48608. (517) 776-4123.




THOMSON SAGINAW™
First in Linear Actuator Technology

Circle Reader Action No. 573

Conductive Rubber Products For ESD Protection

*Static
Build up...*

a nuisance in
electronic assembly
... danger in
rocket motor production.



Our conductive rubber products solve your ESD problems in the Aerospace, Electronic and Process Industries.

- Fabricated cushions, gaskets, and conductive sheet rubber.
- Conductive adhesives.
- Conductive films, foil laminates and tapes.

Briefly describe your ESD concern, and we'll tailor a sample packet for you.

Write or Fax for free specification guide.



Stockwell Rubber Company
4749 Tolbut St./Phila., PA 19136
215-335-3005 FAX 215-335-9433

Circle Reader Action No. 561

HPIB/RS-232 Intelligent Interfaces



Time savers... HP 9000/PC professional...

- Buffers, HPIB & RS232 • HP 200/300 Memory Boards
 - HPIB-Centronics Converters • IEEE 488/PC Interface Cards...
- All backed with a full ONE YEAR WARRANTY & 30 DAY MONEY BACK GUARANTEE!

call 800-842-0888



**INTELLIGENT
INTERFACES Inc.**
P.O. Box 1486 • Stone Mountain, GA 30086

Circle Reader Action No. 679

PolyAWK™ The Toolbox Language

PolyAWK is perfect for data manipulation, list parsing and tool building. Its simple pattern{action} syntax and default file processing (AWK assumes you want to read a file one line at a time) means code for even complex jobs is just a few lines written in minutes. PolyAWK is available in MS-DOS (\$99.00) and OS/2 (\$199.00).

30 Day Money Back Guarantee

To Order: 1-800-547-4000 Dept. NTB
Send Checks and P.O.s To: POLYTRON Corp., 1700 NW 167th Pl., Beaverton, OR 97006 (503) 645-1150, FAX (503) 645-4576, TELEX 325800 POLYTRON

POLYTRON
High Quality Software Since 1982

Circle Reader Action No. 458



**FREE!
130
Page
Catalog**

**"Optics
for
Industry"**

Free 130 page product catalog from Rolyn, world's largest supplier of "Off-the-Shelf" optics. 24-hour delivery of simple or compound lenses, filters, prisms, mirrors, beamsplitters, reticles, objectives, eyepieces plus thousands of other stock items. Rolyn also supplies custom products and coatings in prototype or production quantities. **ROLYN OPTICS Co.**, 706 Arrowgrand Circle, Covina, CA 91722-2199, (818)915- 5707, FAX (818)915-1379

Circle Reader Action No. 551

MIL-STD-45662A

**calibration system requirements
video training program**

Partial list of topics:

- * System Survey & Audit
- * Calibration System Requirements
- * Revision "A" Changes
- * Significance of Revision "A"
- * Standard Procedures
- * Traceability
- * Calibration System Description
- * Adequacy of Calibration System
- * Measurement Standards
- * Measuring and Test Equipment

**TWO HOUR VIDEO TRAINING PROGRAM
AND REFERENCE MANUAL**



FEDERAL PROCUREMENT SERVICES
A Division of Midwest Marketing Services
810 EAST STATE STREET
ROCKFORD, IL 61104
(800) 833-3776

Circle Reader Action 447

COLOR TELEVISION

Field-sequential color converter

page 24 MSC-21346

COMPOSITE MATERIALS

Carbon/carbon panels cooled by heat pipes

page 64 LAR-13761

CONCURRENT PROCESSING

Balanced-load real-time multiprocessor system

page 40 NPO-17185

COOLING SYSTEMS

Survey of cooling techniques

page 73 NPO-17457

CORRELATION

Achromatic optical correlator

page 49 NPO-17206

CORROSION

Electrochemical studies of aluminum coated with primer

page 56 MFS-27184

CRACK PROPAGATION

Predicting the propagation of cracks

page 52 GSC-13084

CRACKING (FRACTURING)

Predictions of fatigue damage from strain histories

page 67 MFS-26060

D

DATA PROCESSING

Data-processing system for test airplane

page 32 ARC-12212

DEFECTS

Predicting the propagation of cracks

page 52 GSC-13084

DIESEL ENGINES

Heat-flux sensor for hot engine cylinders

page 48 LEW-14830

DIGITAL SYSTEMS

Assessment of digital control for helicopters

page 41 ARC-12187

DIODES

Synchronous half-wave rectifier

page 24 NPO-17220

DRAG

Compression pylon reduces interference drag

page 70 LAR-13777

E

ELECTRO-OPTICAL EFFECT

Spatial modulation of light in GaAs

page 56 NPO-17228

ELECTRONIC EQUIPMENT

Survey of cooling techniques

page 73 NPO-17457

ELECTRONIC EQUIPMENT TESTS

Automatic parametric testing of integrated circuits

page 85 NPO-16783

EPOXY RESINS

Making a precisely level floor

page 78 MFS-28306

F

FATIGUE (MATERIALS)

Predictions of fatigue damage from strain histories

page 67 MFS-26060

FIBER OPTICS

Four-mode squeezing for optical communications

page 44 NPO-17170

FINITE DIFFERENCE THEORY

Exponential finite-difference technique

page 85 LEW-14737

FLIGHT CONTROL

Assessment of digital control for helicopters

page 41 ARC-12187

FLIGHT TESTS

Data-processing system for test airplane

page 32 ARC-12212

General-purpose electronic system tests aircraft

page 36 ARC-12148

FLOORS

Making a precisely level floor

page 78 MFS-28306

FLOW MEASUREMENT

Whistle gauge measures flow and temperature

page 65 NPO-17243

FLUID FILLED SHELLS

Making multicore, multishell microspheres

page 80 NPO-17203

FLUID FLOW

Upwind swirl coupling in Navier-Stokes calculations

page 71 MFS-29542

FLUTTER

Predicting flutter of a propfan

page 74 LEW-14659

FRACTURE STRENGTH

Measuring mechanical properties of optical glasses

page 60 MFS-27206

FREE FLIGHT TEST APPARATUS

Data-processing system for test airplane

page 32 ARC-12212

FREQUENCY SYNTHESIZERS

Pulse-population modulation for induction machines

page 38 LEW-14669

G

GALLIUM ARSENIDES

Spatial modulation of light in GaAs

page 56 NPO-17228

GAS FLOW

Whistle gauge measures flow and temperature

page 65 NPO-17243

GLASS

Measuring mechanical properties of optical glasses

page 60 MFS-27206

H

HEAT FLUX

Heat-flux sensor for hot engine cylinders

page 48 LEW-14830




TOP GUN: THE REAL STORY

Join the action as Top Gun, America's best aviators, train for perilous air-to-air combat. This thrilling VHS videotape features actual dogfights, crashes, and MIG confrontations, as well as real Top Gun pilots over Libya, the Indian Ocean, and off the Soviet Union. (Color, 35 minutes) \$19.95 each plus \$3.00 postage and handling.

Name _____
Address _____
City _____ State _____ Zip _____

Total Enclosed: \$ _____ for _____ (quantity) Top Gun videotapes.

Send check or money order to: **NASA Tech Briefs, Fulfillment Dept.,
41 East 42nd Street, New York, NY 10017**



*Reliable, Affordable
CAD Peripherals
from Houston Instrument*

Now you can buy full-size drafting plotters from an industry leader at prices as low as \$3,295.

Call for our complete guide to plotters, scanners, and graphics digitizers.

1-800-444-3425

512-835-0900

Circle Reader Action No. 550



MAGNETOMETERS for direction and detection

A complete line of magnetometers for use in a wide range of operational environments... in the air... on land... or under water. Included are: single-axis, dual-axis, and three-axis models; strapdown three-axis hybridized models; digital heading sensors; magnetic underwater sensors; and special application units for detecting magnetic anomalies in equipment and for magnetic signatures to profile ships.

**For more information
write or call:**


Humphrey, Inc., Dept. NTB 789
9212 Balboa Ave., San Diego, CA 92123 U.S.A.
Telephone: (619) 565-6631
TWX: (910) 335-2001 • FAX: (619) 565-6873



Humphrey Inc.

SAN DIEGO • WICHITA
WORLDWIDE REPRESENTATION

Domain Magnetics products from England are distributed exclusively in the U.S. by Humphrey, Inc.



HEAT PIPES
Carbon/carbon panels cooled by heat pipes
page 64 LAR-13761

HEAT STORAGE
Microencapsulated phase-change materials for storage of heat
page 72 MFS-27198

HEAT TRANSFER
Exponential finite-difference technique
page 85 LEW-14737

HELICOPTERS
Assessment of digital control for helicopters
page 41 ARC-12187

HIGH SPEED PHOTOGRAPHY
Reducing heating in high-speed cinematography
page 44 LEW-14798

HOLOGRAPHIC INTERFEROMETRY
Fast laser holographic interferometry for wind tunnels
page 51 ARC-11840

HYGROMETERS
Twisted pair of insulated wires senses moisture
page 30 NPO-17111

IMAGE PROCESSING
Achromatic optical correlator
page 49 NPO-17206

IMPINGEMENT
Detecting impacts of particles on spacecraft
page 42 MFS-28278

INDUCTION MOTORS
Pulse-population modulation for induction machines
page 38 LEW-14669

INTEGRATED CIRCUITS
Automatic parametric testing of integrated circuits
page 85 NPO-16783

Multichannel, active low-pass filters
page 20 NPO-17290

INTERFERENCE DRAG
Compression pylon reduces interference drag
page 70 LAR-13777

INTERFEROMETRY
Multiple-baseline interferometric synthetic-aperture radar
page 42 NPO-17416

INTERROGATION
General-purpose electronic system tests aircraft
page 36 ARC-12148

JACOBI MATRIX METHOD
Inversion of Jacobian matrix for robotic manipulators
page 88 NPO-17544

LAMINAR FLOW
Measuring laminar-separation bubbles on airfoils
page 68 LAR-13952

LASER INTERFEROMETRY
Fast laser holographic interferometry for wind tunnels
page 51 ARC-11840

LASER SPECTROMETERS
Calculating response of a tunable-diode-laser spectrometer
page 52 NPO-17375

LASERS
Efficient cavity-dumped, frequency-doubled Nd:YAG laser
page 22 NPO-17286

LIGHT MODULATION
Spatial modulation of light in GaAs
page 56 NPO-17228

LOW PASS FILTERS
Multichannel, active low-pass filters
page 20 NPO-17290

M

MAGNETIC FIELDS
Boundary-value problem for magnetic-cutoff rigidities
page 50 NPO-17294

MANIPULATORS
Inversion of Jacobian matrix for robotic manipulators
page 88 NPO-17544

MASKING
Keeping wax liquid for application
page 84 MFS-29238

MEASURING INSTRUMENTS
Circularity-measuring system
page 83 MFS-28313

Survey of cooling techniques
page 73 NPO-17457

Twisted pair of insulated wires senses moisture
page 30 NPO-17111

MECHANICAL PROPERTIES
Measuring mechanical properties of optical glasses
page 60 MFS-27206

METAL SURFACES
Electrochemical studies of aluminum coated with primer
page 56 MFS-27184

MICROBALLOONS
Making multicore, multishell microspheres
page 80 NPO-17203

Microencapsulated phase-change materials for storage of heat
page 72 MFS-27198

MICROSTRUCTURE
Research in thermoelectric materials
page 54 NPO-17403

MICROWAVE FILTERS
Multichannel, active low-pass filters
page 20 NPO-17290

MOISTURE METERS
Twisted pair of insulated wires senses moisture
page 30 NPO-17111

MULTIPROCESSING (COMPUTERS)
Balanced-load real-time multiprocessor system
page 40 NPO-17185

N

NAVIER-STOKES EQUATION
Navier-Stokes calculations with deforming grid
page 66 LEW-14711

Navier-Stokes simulation of turbine rotor/stator interaction
page 69 ARC-12185

Upwind swirl coupling in Navier-Stokes calculations
page 71 MFS-29542

NEODYMIUM LASERS
Efficient cavity-dumped, frequency-doubled Nd:YAG laser
page 22 NPO-17286

NONDESTRUCTIVE TESTS
Automatic parametric testing of integrated circuits
page 85 NPO-16783

OPTICAL COMMUNICATIONS
Four-mode squeezing for optical communications
page 44 NPO-17170

OPTICAL DATA PROCESSING
Achromatical optical correlator
page 49 NPO-17206

PARTIAL DIFFERENTIAL EQUATIONS
Exponential finite-difference technique
page 85 LEW-14737

PHASE CHANGE MATERIALS
Microencapsulated phase-change materials for storage of heat
page 72 MFS-27198

PHOTOVOLTAIC CELLS
Hotspot endurance of solar-cell modules
page 28 NPO-17305

POLARIMETRY
Radar polarimeter measures orientations of retroreflectors
page 37 NPO-17231

POURING
Making a precisely level floor
page 78 MFS-28306

POWER SUPPLY CIRCUITS
Synchronous half-wave rectifier
page 24 NPO-17220

PROPELLER FANS
Predicting flutter of a propfan
page 74 LEW-14659

PROTECTIVE COATINGS
Electrochemical studies of aluminum coated with primer
page 56 MFS-27184

PULSE MODULATION
Pulse-population modulation for induction machines
page 38 LEW-14669

PYLONS
Compression pylon reduces interference drag
page 70 LAR-13777

RADAR
Radar polarimeter measures orientations of retroreflectors
page 37 NPO-17231

REAL TIME OPERATION
Balanced-load real-time multiprocessor system
page 40 NPO-17185

RECTIFIERS
Synchronous half-wave rectifier
page 24 NPO-17220

REFLECTORS
Adjusting surfaces of large antenna reflectors
page 34 LAR-13851

REMOTE MANIPULATOR SYSTEM
Inversion of Jacobian matrix for robotic manipulators
page 88 NPO-17544

RESIN MATRIX COMPOSITES
PMR resin compositions for high temperatures
page 56 LEW-14658

RETROREFLECTORS
Radar polarimeter measures orientations of retroreflectors
page 37 NPO-17231

ROTOR BLADES (TURBOMACHINERY)
Navier-Stokes simulation of turbine rotor/stator interaction
page 69 ARC-12185

SATELLITE-BORNE RADAR
Multiple-baseline interferometric synthetic-aperture radar
page 42 NPO-17416

SEALING
Keeping wax liquid for application
page 84 MFS-29238

SEMICONDUCTOR DEVICES
Hotspot endurance of solar-cell modules
page 28 NPO-17305

SEMICONDUCTORS (MATERIALS)
Research in thermoelectric materials
page 54 NPO-17403

SHAPES
Circularity-measuring system
page 83 MFS-28313

SHAPES
Adjusting surfaces of large antenna reflectors
page 34 LAR-13851

SIGNAL PROCESSING
Field-sequential color converter
page 24 MSC-21346

SOLAR CELLS
Hotspot endurance of solar-cell modules
page 28 NPO-17305

SPACECRAFT INSTRUMENTS
Detecting impacts of particles on spacecraft
page 42 MFS-28278

SPECTROMETERS
Calculating response of a tunable-diode-laser spectrometer
page 52 NPO-17375

STATOR BLADES
Navier-Stokes simulation of turbine rotor/stator interaction
page 69 ARC-12185

STRAIN MEASUREMENT
Predictions of fatigue damage from strain histories
page 67 MFS-26060

STRUCTURAL FAILURE
Predicting the propagation of cracks
page 52 GSC-13084

SUBSONIC FLUTTER
Predicting flutter of a propfan
page 74 LEW-14659

SYNTHETIC APERTURE RADAR
Multiple-baseline interferometric synthetic-aperture radar
page 42 NPO-17416

SYNTHETIC RESINS
PMR resin compositions for high temperatures
page 56 LEW-14658

TELECOMMUNICATION
Four-mode squeezing for optical communications
page 44 NPO-17170

TELLURIDES
Chemical-vapor deposition of $Cd_{1-x}Mn_xTe$
page 76 NPO-17399

TEMPERATURE CONTROL
Carbon/carbon panels cooled by heat pipes
page 64 LAR-13761

TEMPERATURE MEASUREMENT
Reducing heating in high-speed cinematography
page 44 LEW-14798

TEMPERATURE MEASUREMENT
Whistle gauge measures flow and temperature
page 65 NPO-17243

THERMOCOUPLES
Heat-flux sensor for hot engine cylinders
page 48 LEW-14830

THERMOELECTRIC MATERIALS
Research in thermoelectric materials
page 54 NPO-17403

THIN FILMS
Rapid annealing of amorphous hydrogenated carbon
page 58 LEW-14664

THIN WALLED SHELLS
Making multicore, multishell microspheres
page 80 NPO-17203

TRANSONIC FLOW
Navier-Stokes calculations with deforming grid
page 66 LEW-14711

TUNABLE LASERS
Calculating response of a tunable-diode-laser spectrometer
page 52 NPO-17375

TURBINES
Navier-Stokes simulation of turbine rotor/stator interaction
page 69 ARC-12185

VAPOR DEPOSITION
Chemical-vapor deposition of $Cd_{1-x}Zn_xTe$
page 76 NPO-17399

VIDEO SIGNALS
Field-sequential color converter
page 24 MSC-21346

WAXES
Keeping wax liquid for application
page 84 MFS-29238

WIND TUNNELS
Fast laser holographic interferometry for wind tunnels
page 51 ARC-11840

X-29 AIRCRAFT
General-purpose electronic system tests aircraft
page 36 ARC-12148

YAG LASERS
Efficient cavity-dumped, frequency-doubled Nd:YAG laser
page 22 NPO-17286

Time Code Instrumentation

Professionals in many disciplines rely on recorded time code as a primary reference in data correlation and control applications. For nearly 20 years we've supplied quality timing instrumentation to customers in fields as diverse as entertainment, medical research, flight test and deep space exploration.

Datum produces a comprehensive line of timing instrumentation products, from rack mounted units designed for moderate environments, to ruggedized equipment for airborne, shipboard and mobile applications. Manufactured to commercial standards or military specifications requiring QPL certification, these instruments include time code translators and generators, tape search units, digital clocks and displays. A host of options enables the designer to maintain cost effectiveness while achieving optimum system configuration.

We also design and manufacture complete range timing systems to customer specifications.

For more information or applications assistance, call or write.

datum inc
Timing Division

1363 S. State College Blvd., Anaheim, CA 92806-5790
(714) 533-6333

Today's most powerful data acquisition system . . .



. . . is also a flexible industry standard allowing you to:

- digitize signals to 100 megasamples/second
- transfer data at rates to 9.6 megabytes/second
- connect up to 1000 I/O channels per card cage
- distribute 62 card cages to 10,000 feet apart

Our high-performance CAMAC systems meet your most demanding realtime industrial, scientific, aerospace, or defense needs. Based on a series of international IEEE/ANSI/IEC standards, CAMAC interfaces to Digital, Gould, H-P, MODCOMP, Control Data, and most personal computers.

Choose from over 150 CAMAC modules including 16-bit A/D and D/A converters, high-speed transient recorders, counters, digital I/O, and both ARINC-429 and MIL-STD-1553 interfaces. Transfer data at three megabytes/second over a fiber optic highway to distances of 10,000 feet between I/O locations. Use our new **Tachion-ITM** system to precisely sample long-duration analog signals for digital storage to disk at a throughput of 9.6 megabytes/second.

For nearly 20 years, KSC has supplied powerful CAMAC data acquisition systems for such customers as *General Electric, Boeing, LTV Steel, McDonnell-Douglas, AT&T, Bell Labs, Westinghouse, General Motors, and NASA.*

Call us *now* to discuss your application needs.

digital™ Cooperative
Marketing
Program

**KineticSystems
Corporation**

11 Maryknoll Drive, Lockport, Illinois 60441
(815) 838 0005

Circle Reader Action No. 334

Advertiser's Index

Alcatel Vacuum Products Inc.	(RAC 566)	87
Amco Engineering Co.	(RAC 500)	88
Amoco Performance Products	(RAC 336)	2-3
Anorad Corporation	(RAC 508, 509)	5
Anritsu	(RAC 492)	26-27
Astro-Med, Inc.	(RAC 405)	61
Aurora Bearings	(RAC 540)	10
Automation Gages	(RAC 453)	52
Blue M	(RAC 386)	49
Boeing Technology Services		65, 67, 69, 71
Bruel & Kjaer Instruments, Inc.	(RAC 319)	59
Burr-Brown	(RAC 313)	89
Codonics	(RAC 386)	11
Coil Anodizers Inc.	(RAC 332)	74
Comtran Integrated Software	(RAC 480)	91
Concurrent Computer Corporation	(RAC 581)	39
Datatype	(RAC 374)	19
Datum Inc.	(RAC 543)	97
Easton Press Video	(RAC 440)	13
Eighteen Eight Laboratories	(RAC 675)	62
Federal Procurement Services	(RAC 447)	95
Fluoramics	(RAC 364)	29
General Dynamics		
Space Systems Division	(RAC 305)	73
GE Recruitment	(RAC 662)	43
Grafpoint	(RAC 686)	18
Grumman Data Systems	(RAC 363)	47
Heath Tecna Aerospace Co.	(RAC 414)	COV III
Houston Instrument	(RAC 550)	96
Howmet Corporation	(RAC 325)	53
Humphrey Inc.	(RAC 626)	96
IBM Corporation		33
IOTech, Inc.	(RAC 303)	42
Illbruck	(RAC 466)	60
Inco Alloys International Inc.	(RAC 569)	7
Information Development, Inc.	(RAC 488)	92
Inframetrics	(RAC 370)	4
Integrated Sensors, Inc.	(RAC 342)	93
Intelligent Interfaces Inc.	(RAC 679)	95
Ioline Corporation	(RAC 351)	1
Kaiser Aluminum	(RAC 353)	55
Kinetic Systems Corporation	(RAC 334)	98
Lake Shore Cryotronics, Inc.	(RAC 579)	72
Lincoln Laser Company	(RAC 593)	94
Lindberg/Blue M	(RAC 671)	58
MACSYMA/SYMBOLICS	(RAC 524)	86
MathSoft, Inc.	(RAC 628)	57
McDonnell Douglas	(RAC 501)	COV IV
McDonnell Douglas AUSS	(RAC 372)	45
Minco Products, Inc.	(RAC 308)	92
Modgraph	(RAC 337)	15
National Technical Systems	(RAC 358)	12
Nicolet Instruments	(RAC 696)	21
Numerical Algorithms Group	(RAC 377)	54
Omega Engineering, Inc.	(RAC 617)	COV II
Optima Enclosures	(RAC 624)	91
Polytron Corp.	(RAC 458)	95
Pressure Systems	(RAC 381)	9
Quantitative Technology Corporation	(RAC 570)	63
R. G. Hanson & Associates	(RAC 688)	84
Raytheon Company	(RAC 512)	31
Rolyn Optics Company	(RAC 551)	95
Sony Corporation of America	(RAC 532)	35
Sensors Expo	(RAC 677)	75
Stat-Ease Inc.	(RAC 393)	56
Stockwell Rubber Company	(RAC 561)	95
Teledyne Taber	(RAC 474)	41
Teledyne Solid State	(RAC 537)	23
Thomson Saginaw	(RAC 413, 573)	77, 95
3-D Visions	(RAC 669)	30
VAT Incorporated	(RAC 518)	25
Wyle Laboratories	(RAC 522)	8
Zero/Halliburton Division	(RAC 654)	93

*RAC stands for **Reader Action Card**. For further information on these advertisers, please circle the RAC number on the Reader Action Card elsewhere in this issue. This index has been compiled as a service to our readers and advertisers. Every precaution is taken to ensure its accuracy, but the publisher assumes no liability for errors or omissions.

***The autoclave tool
that gives your program
a run for its money.***

Hard Working Tools

Make your thermoset or thermoplastic structures program more productive with Heath Tecna Comtek® tools. Comtek outperforms monolithic graphite and composite tools. And, unlike conventional ceramics, Comtek is both durable and tough, with an elastic modulus of 6 MSI.



Vacuum Integrity to 800° F

Heath Tecna Comtek tools hold critical dimensional tolerances during cures of up to 800° because they're formulated to match the CTE of the parts to be fabricated. They're also castable to net shape, with high quality surfaces and inherent vacuum integrity—meaning no secondary sealing is necessary.

30 Years of Heath Tecna Expertise

You may find the best part of Comtek tools to be Heath Tecna. Our tooling abilities have been demonstrated through over three decades of com-

posites program support to the primes. The result: Comtek tools are designed and built with a real understanding of the manufacturing environment.

FREE Technical Brochure


Get more facts about the tooling that works harder. Call VP Jim Martenson at (206) 872-7500, ext. 116, and ask for our FREE new brochure describing Comtek tooling.



Advanced Tools for Aerospace

**HEATH TECNA
AEROSPACE CO.**

A CIBA-GEIGY Company



"It's not easy for an astronaut to build anything up there...what they really needed was a fastener that would help them put those space structures together quick and easy.

My job is solving these puzzles. This time I designed a self-aligning bolt for them. But I couldn't help thinking those gloves they wear could be trouble. So I went home and did some work on my own. Cut up a cookie sheet and found an old gear in the garage—used them to make some modifications on a cordless screwdriver. Turned it into a push-button wrench that'll let anybody—astronaut or robot—screw that bolt together in seconds.

If you keep on thinking, one interesting idea just naturally seems to lead right on to the next one."

—Earl Cooney, Space Station, Industrial Engineer Advisor

MCDONNELL DOUGLAS
A company of leaders.