
Boundary Layer Transition Flight Experiment Implementation on OV-103

Theodoros A. Spanos
Kennedy Space Center, Florida
10 DEC 09

Copyright © 2009 by United Space Alliance, LLC. These materials are sponsored by the National Aeronautics and Space Administration under Contract NNJ06VA01C. The U.S. Government retains a paid-up, nonexclusive, irrevocable worldwide license in such materials to reproduce, prepare, derivative works, distribute copies to the public, and perform publicly and display publicly, by or on behalf of the U.S. Government. All other rights are reserved by the copyright owner.



Boundary Layer Transition Flight Experiment

⁴ *“The design of hypersonic vehicles today is greatly dependant on the use of CFD. The primary reason for this is the lack of experimental ground test facilities that can simultaneously simulate Mach numbers, Reynolds number, and high temperature levels associated with hypersonic flight”*
– John D. Anderson, Jr.

Objective:

To obtain hypersonic aero-thermodynamic data for the purpose of bettering the understanding of flow transition from a laminar to turbulent boundary layer using a known height protuberance.

Targeted Mach number transitions:

- First Flight – Mach 15
- Second Flight – Mach 18
- Third Flight – Mach 19



Boundary Layer Transition Flight Experiment

¹Four *Hypotheses* are being tested:

- BLT cannot be initiated with a discrete protuberance at hypersonic non-equilibrium conditions
- There is not a ground to flight environment scaling effect on discrete protuberance induced BLT at hypersonic non-equilibrium conditions
- High Mach number / high enthalpy non-laminar heating is not fully turbulent
- High Mach number / high enthalpy heating for turbulent boundary layers and surface catalysis interact and are dependant upon each other



³ Historical Activities / Parameters



The design team had to account for several parameters:

- Ensure design will meet Space Shuttle safety requirements for nominal ascent, flight, entry, and landing
- Ensure design can be removed during an EVA
- Ensure the peak heat is acceptable for the protuberance, local protuberance tile, tiles downstream, and aluminum skin of the Orbiter is acceptable in an abort case and in worst and nominal entry cases
- Ensure design of supportive hardware meet functional and performance requirements



Project Overview

In order to obtain the flight data, a unique tile had to be installed on the undercarriage of *Discovery* that would have a protuberance of a known geometry that would not change during entry. Thermocouples will need to be installed downstream to obtain temperature data.



OBD
FWD



System Integration

Groups involved in the implementation of BLT FE at KSC:

- *Thermal Protection System (TPS)*
- *Airframe Structures (STR)*
- *Orbiter Electrical (OEL)*
- *Orbiter Instrumentation (INS)*
- *Optics*



Overview / Responsibilities of TPS





Figure 3 Orbiter TPS Configuration
(Approximate Location)

- Discovery* has approximately 24,000 tiles
- Each has a unique geometry
- Each has unique aero-thermal criteria
- Installation procedures may vary
- Twenty one total tiles removed
- Thirteen had thermocouples installed
- Six acted as cover tiles
- Two / Three changed for thermal reasons
- Sequencing critical to success of FE

Responsibilities of STR

- Locate and drill penetration holes
- Install grommets
- Install Thermocouple Reference Junction (TRJ)
- Install Temp-i-labels





Overview / Responsibilities of OEL / INS / Optics


- INS responsible for interfacing tile thermocouples to TRJ and individual channelization / calibration.
- OEL responsible for interfacing the TRJ to the Modular Auxiliary Data System (MADS) – on board recorder
- Optics responsible for obtaining high resolution 3-D images of the pre-flight and post-flight protuberance as well as surrounding tiles. HYTHRM team obtained IR images of *Discovery* on entry.




Boundary Layer Transition Flight Experiment STS-119 OV-103 FLT-36 Layout




Tile Removals / Processing Discussion




TPS Processing Discussion




TPS Processing Discussion




TPS Processing Discussion




TPS Processing Discussion




STR Discussion





STR Discussion: TRJ Installation



TPS Processing Discussion





Boundary Layer Transition Flight Experiment STS-119 OV-103 FLT-36 Layout



5 Optics Discussion Metris post flight scan to pre flight Surface

(Front)



3D Deviation

Max +/-: 0.047519 / -0.049906 in

Average +/-: 0.006619 / -0.016141 in


Standard Deviation: 0.005780 in

RAM: 752 free / 2047


Virtual: 3929 free / 4095



5^{Optics Discussion}



FWD Side



AFT Side



STS-119: First Flight of BLT

STS-119 launched on 15 March 2009 and had early success. Engineers were able to review data from the MADS, while the mission was ongoing that revealed the MADS recorded ascent heating as expected.

Summary:

- All ten active thermocouples performed as expected.
- First indication BLT Onset for TC#1 (Most AFT and Outboard) was Mach 15.6 ± 0.1 (969 sec)
- Protuberance TC tripped at Mach 7.71 ± 0.3 (1224 sec)
- BLT Protuberance Peak: ~ 2000 F (lower than predictions ~ 2900 F)
- Comparison of pre and post-flight OPTIGO scans did not show any significant change in protuberance geometry.
- No damage or slumping was identified within the turbulent wedge as a result of the flight experiment



STS-119 Runway Photo

LING336-0554-203B-19
V070-191011-001

LING336-0554-203B-21
V070-191011-040
7EC025

LING336-0554-203B-20
V070-191011-036
7EC024


LING336-0554-203A-1
V070-191011
-001 70C1F5

LING336-0554-203A-2
V070-191011-035
70C1F6


LING336-0554-203A
V070-191011
-121 70C1F7

LING336-0554-203A-3
V070-191011-017
70C1F4

6 HYTHRM Image



HYTHRM Image



Plan for BLT-2 on STS-128

Preparations

- Expected to fly a protuberance of increased height
- Several changes:
 - Change location of TC # 5 to fit flight observed streamline of max heating.
 - Change several tiles to higher density material due to the projected increase in temperature caused by the taller protuberance
 - Deactivate TC #3 and TC #8 and Activate TC #3a and TC # 8a for better turbulent wedge resolution and to better accommodate the C742 catalytic coating experiment



STS-128: Second Flight of BLT

STS-128 landed at Edwards AFB on 11 SEP 09

Data obtained not as clear cut as STS-119

Summary:

- Several thermocouple had data drop-offs (Protuberance included)
- Attributed to MADS anomaly – sporadic occurrence on fleet
- Asymmetrical BLT occurred on vehicle
- Estimate BLT on protuberance occurred around Mach 18

Plan Forward (STS-131):

- Re-fly same protuberance as STS-128 (0.35 inches)
- Installation on OV-103 is currently in work



Questions



References:

1. Campbell, Charles H., et al. Orbiter Entry Boundary Layer Flight Testing American Institute of Aeronautics and Astronautics, 2006
2. Available from: <http://www.nasaspaceflight.com/2009/06/discovery-handed-special-heatshield-coating-dto-on-behalf-of-orion/>
3. BLT FE “First Flight Critical Design Review” Boeing Huntington Beach, CA
4. Anderson, John D. Jr. Fundamentals of Aerodynamics 3rd ed. 2001
5. Brad Wilson Pitch to BLT IPT
6. <http://www.cbsnews.com/network/news/space/119/119graphics/fd14/blt1.jpg>
7. <http://www.nasaspaceflight.com/2009/05/sts-119-blt-test-success-gains-greater-understanding-reentry/>

