


"Safe and Green" at the National Aeronautics and Space Administration, NASA Johnson Space Center

American Industrial Hygiene Association Conference and Exposition

Sean Keprta CIH MS
Chief Clinical Services Branch
NASA Johnson Space Center
Houston Texas





Consolidating an Agency LEED Requirement and a robust Construction Safety and Health process into a win-win scenario for workers and occupants in the JSC "Master Plan" Building Revitalization Program



Agenda

History of the Construction of Facilities (COF)

Safety and Health (S&H) process at JSC




- Review the NASA LEED mandate and how it works into the COF process.
- Show how our diverse stakeholder team works together and share some Case Studies and Lessons Learned

















National Aeronautics and Space Administration, NASA, Centers





JSC Statistics




- South of Houston Texas "Clear Lake"
- •1600 acre main campus, 130+ buildings
- Main facility built in the late 1960's and early 1970's
- Approximately 10,000 team members on-site
- Shuttle (retiring and International Space Station (ISS)Programs
- Home Center for the Astronaut Corp
- Engineering Labs and Test Facilities
- Curation of Lunar and other Planetary Materials












JSC Statistics



 Occupational Safety and Health Administration (OSHA) Voluntary Protection Program (VPP) Star Site (since 1999)

VPP Star Certification for ~20 Team
 Contractors











- JSC "Mall" buildings, most built in the late 60's and 70's, are in need of significant upgrades, roofs, air handlers, exterior, inefficient energy systems
- Several thousand employees housed off-site.





Facilities Operations

Many Temporary Buildings are at risk from hurricanes.













Facilities Operations

- Center Operations Directorate has developed a "Master Plan" intended to meet the current and future facility needs of JSC programs. Construction will primarily be "Renovate and Refurbish".
- Included in this 20 year plan is a stand alone building designed to house employee organizations displaced as their building is under renovation



Building 20





Defining Event

- > 2002 significant construction mishap resulted in a review of the JSC Safety and Health Construction process.
- Findings resulted in an overhaul of how S&H is incorporated into the Construction of Facilities (COF) process.



Finding


Existing Culture

 COD Construction safety and health effectiveness is diminished by inconsistent Government stakeholder involvement. This negatively influences construction contractor's management commitment to place emphasis on safety and health, which in turn allows default to unsafe work

practices.







Finding

Desired COD Construction S&H Culture

COD construction stakeholders
 consistently apply the same safety and
 health values and expectations to
 construction contractors as JSC does
 to our entire JSC team.



Corrective Actions

Brought together a team with experience in Project Management, Contract Procurement & Administration, Construction Management & Inspection, and Construction Safety & Health (S&H) with the purpose to draft:

- A new Johnson Space Center (JSC) S&H contract procurement solicitation for use on all "Best Value" construction contracts.
- A new JSC Construction S&H Master Specification for use on all construction contracts.
- Federal Acquisition Regulations (FAR), NASA S&H FAR Supplements & Policy, JSC S&H Policy, Requirements & Guidelines, and OSHA Policy & Requirements into one unified document. Contractor S&H past performance was an important factor.
- Stakeholder involvement required from PER through construction and final building acceptance by the Government.



Follow up teams : Summary



- Implemented new S&H specification for all CoF Construction work.
- Mandatory S&H training prior to Site Access for all CoF construction Personnel, training level dependent on duties
- Utilizes Houston Area Safety Council (HASC) for the Mandatory Training and testing
- Utilized findings from Construction Industry Institute Study funded by NASA HQ's






















Current Process

NASA NPR (NASA Procedural Requirement) 8820.2F Facility Project Requirements was revised in 2008:

- Mandates HSE involvement
- Best Practices Expectation for Construction S&H
 - "Making Zero Incidents a Reality"
- JSC Specific Process Compliments NPR





NASA LEED Mandate

NASA Procedural Requirement NPR 8820.2F Facility Project Requirements, January 2008

Sustainability- NASA has adopted the US Green Building Councils Leadership in Energy and Environmental Design (LEED) as its performance measure for sustainable development.

All building and renovation projects awarded after October 1, 2005 shall meet the minimum LEED Silver ratings.




> Team

- NASA Center Operations , A/E Firm, Engineering Support Services
- Occupational Health, Safety, Environmental
- Procurement

> Tools

- PtD Prevention Through Design "Concepts"
- Buy Quiet, Quiet by Design Requirement
- CII benchmarking
- Lessons Learned
- Case Studies
- HASC Teaming
- Strong HSE network
- Green Building Council





- Focal point for all construction S&H issues and the NASA Project Manager and the Contract Engineering Support Services Project Lead, who is also the LEED Accredited Professional.
- >One stop shopping for all Health, Safety and Environmental issues.

Since Then We have Gotten a lot of Practice

Several Hurricane Close Calls, and then
2 Direct bit from "IKE"


a Direct hit from "IKE"
























- American Re-Investment and Recovery Act ARRA/ Stimulus
 - We received a some stimulus funds that allowed us to complete repairs on many of the hurricane damaged roofs.
- Construction of Facilities (COF) Plus the ongoing work on buildings in the "Pipeline" for the JSC Master Plan























JSC LEED Facilities

27 Certified (Built prior to the LEED Silver)

requirements)

207A - Silver

- 265 - Gold

- 2N - Gold

20 - Platinum (NASA's first ever LEED Platinum building)

ON PUBLIC AFFAIRS

- 26 - Gold

29 - Silver (waiting for the final certification)

12 - Striving for Gold (In Progress)

No "Live" roofs, yet.. One possibility in the works..



















From JSC Construction Management

- Generally Speaking- "Green" construction is not significantly different... Build to the design, Material Procurement was difficult at first, however the supply network to meet the specs is growing....However, we have not constructed a "living" roof, yet..
- Materials Low VOC requirements have translated into a noticeably less "toxic" smelling building during construction. Glues, Adhesives, Paints, Texturing, Flooring, etc..
- Material Submittals have to go through 3 reviews- Meet Quality Specs, Meet LEED Specs, Meet S&H Specs..
- Incorporating S&H into the LEED criteria viewed as a positive benefit by our Engineering Support Services Team. Aligns closely with our JSC values to sustainability and worker and occupant protection...















During Construction

- Submittal and Material Safety Data Sheet MSDS Review-
 - Three levels of product review- Quality Review, Green Review, S&H review-
 - Requires a good HSE professional to tease out any potential hazards to workers in some of the "Green", or labeled "Green" Products.
 - Glue MSDS for common glue "VOC not determined", looked green to the contractor, Hazardous Component- MDI?? What is that...
- Cisterns (in ground) for water collection and redistribution- Confined Space issues
- Sky Light and light transmitting roof materials- well know hazards















Occupancy

- Sky light Guarding- During construction and afterward- well recognized Hazard
- Energy Conservation-
 - Re-circulating hot water system- colonized by legionella, facility had showers.
 "Pasteurized" the system and then sampled. Took several cycles to eliminate the legionella.
 - Lighting- late night operations
- LEED requirement for showers... Potential for legionella, aersolization when used by employees.. Need to periodically sample???
- Automatic Outside Air systems- CO2 monitor in the air handler, opens outside air when CO2 "trigger level" is reached, Usually 1000PPM, must be careful, especially in Texas, that the Outside Air is PTOA, (Pre-Treated
- Glare
- Temperature sometimes harder to maintain



>We fully embrace the concept of adding construction S&H to LEED certification criteria, consider it a win-win benefit.





BACK UP
































- Building Age JSC Revitalization
- Hurricanes (IKE)
- Stimulus Lots of Roof












Building 20

Verde Veinte V^2






Overview

- Three story, approximately 83,000 square feet.
- Building 20 was designed with "less is more". Only applied material if materials was necessary.
- Project is registered with United States Green Building Council (USGBC) as a Leadership in Energy and Environmental Design (LEED) "Gold" rating but was upgraded to "Platinum".
 - Designed by Hellmuth, Obata, and Kassabaum, Inc.
- •Provides for a permanent location for 120 employees on the third floor and can house 400 employees on the other two floors.
- •Office Building project supports the building refurbishment program to provide "flex" space for employees temporarily relocated due to refurbishment of their building.

Improving Acoustics



•Ceiling is exposed concrete with ceiling clouds

•The clouds help improve the acoustics of the open office and provide a surface for the indirect lighting to reflect the light back into the work area

Preserving Our Forests





•The 'rapidly renewable' material Bamboo is utilized throughout the building's cabinetry and millwork.

•90% of the wood used in the building is Forest Stewardship Council (FSC) approved showing that they were harvested in a responsible manner that minimized the impact on our forests

•Almost 20% of the materials used on this job were manufactured within 500 miles of JSC, stimulating local business and minimizing fuel consumed in shipping

Reducing Water








•Plumbing fixtures were selected based on their water savings potential through the use of waterless urinals, dual flush flushometers for the water closets and 0.5 GPM electronic faucets with controls to operate in 10 second durations

•Water efficient landscaping uses no potable water, irrigation water is captured from the air handlers condensate system





- •Approximately 90% of the floor area in the building will have access to natural light and a view of the world outside
- •Solar shading devices engineered to not only provide more daylight, done so to minimize glare and discomfort when working at computer monitors
- •Building orientation reduces area facing the sun directly during its most intense periods; thereby reducing heat gain and glare



•Glass is high efficiency, great light transmittance and coated to reduce heat gain. More glass reducing the need for artificial lighting.

•Lighting is automatic and will increase and decrease in intensity based on the amount of daylight harvested through the glass and via the solar shading devices.

Highly energy efficient envelope.

 Enough energy is saved to power approximately 55 average sized homes annually.



•The building utilizes a solar water heating system that transmits heat generated from roof mounted solar panels into the building's hot water system, reducing the buildings foreign energy consumption.

•Roof coating that reflects the sun heat and energy back into the atmosphere.





- Bike Storage and Shower/Changing rooms. This encourages riding bicycles to conserve energy.
- CO₂ monitors in the HVAC systems that will automatically introduce outdoor air when CO₂ levels are high, thereby making the space better for working and more efficient in energy usage when not occupied or occupied with fewer individuals.
- Supply air temperature reset-improves efficiency by using the air and energy actually needed.
- High efficiency filters provides better air for occupants and keeps the HVAC system cleaner longer

Cool Features





 Each office has an eraser board built into the wall •Entry mats at the two main entrances have a cavity below them that capture particles from the shoes of incoming occupants, minimizing the particles floating around the building









- •Approximately 95% of the waste generated by the construction of this project has been recycled.
- •Permanent recycling Receptacles are centrally located to encourage occupant participation.
- •Over 25% of the materials used in this building are recycled materials.
 - Some items used that contain recycled materials are:

○Ceiling tiles
 ○Countertops (recycled glass)
 ○Reinforcing steel and structural steel
 ○Concrete




Current Status

- The project has a tentative completion date of December 18, 2009.
- •Grand opening is scheduled for January 7, 2010.
 - •Occupant move-in is scheduled for January 11, 2010.









7 6 1 Sustainable Sites (20%) Commontion Admity Publish Prevention
Commontion Admity Publish Prevention
Development Develop A Community Commonting
Development Commontion Commontion
Administry Transportation, Public Transportation Access
Administry Transportation, Public Transportation Access
Administry Transportation, Public Commontion
Development Compt., Common Commontion
Development Commontion
Development Commontion
The Administry Commontion
That Indian Commontion Will evaluate if project can meet Development Density option Need to confirm with Gilbane if asbestos abstement has been approved on other LEED projects Per J.White, shutfie bus exist on campus. Verify stop location proximity to \$12 If project earns SSc2, the amount of open space needed is only 20% including green roof IVII need to review calcs again - very difficult to achieve (need to reduce stormaster rate & quantity 25% from current levels). Not feasible for project alte 5Piloti Connecta Water Efficient Landscaping, Reduce by 50% Water Efficient Landscaping, No Posible Use or No Irrigation Innovative Wastewater Technologies Water Use Reduction, 20% Reduction Water Use Reduction, 20% Reduction A Leads 4 4 2 ---1 2 Storage & Collection of Recyclables
Building Reuse, Maintain 75% of Eletting Walls, Floors & Roof
Building Reuse, Maintain 95% of Existing Walls, Floors & Roof
Building Reuse, Maintain 95% of Enterior Non-Structural Elements Very unlikely due to replacement of old, susbstandard and hazzardous interior materials by design Building Roses, Monten OSV of Indica Nov-Docksard Elements
Constructive Wall Management, David Toh from Disposal
Harding Roses, 196
Harding Roses, Need to verify realined materials amount and viability for recognition Difficult to achieve per project type al Quality (22%) Nethronical Onformation
Controlled Thatas State STS Central
Environment Thatas Central
Environment Thatas Central
Law Central Environment Thata Scattery
Law Central Maries Anni & Central
Law Central Maries State State State
Law Central Maries State State
Law Central Maries State State
Law Central Maries State
Environment Thatas Central
Central Maries State
Central Maries State
Central Maries State
Central Maries
Cent Quick review of occupied office spaces indicates possible point with additional T-state and some fan units at each floor 3 | Process (7%) 5 Points Comments Innovation in Design: UV Lights in NVAC +1 yr. IVO testing Innovation in Design: Examp Perform MR 2 Constr Water Mg: Innovation in Design: Examp. Perform WECI Water Use Reduct Innovation in Design: Creen Education LEED® Accredited Professional Need to confirm with Gilbane this can be achieved.



- What has been done in COD to improve Construction Safety:
- COD chartered a Team to Improve construction contractor S&H
 - Low Hanging fruit- Owner involvement
 - S&H orientation was implemented Construction Contractors before Access to the Center 7 AM each morning with a PM
 - Implemented requirement for project specific S&H plans, and review, prior to Notice To Proceed with construction work
 - Five onsite MEI construction Safety professionals added for QA of safety at construction sites
 - Implemented trending of safety and health violations at construction sites, and follow-up proactive intervention with contractors
 - Renewed training for all Project Managers





- Charted sub-team to diagnose problems and improve configuration control of facility: designs, documentation, and procedures.
- Implemented joint S&H meetings with Construction Contractors and JSC personnel to improve communications with active construction contractors
- Chartered sub-team to review outage process and utility procedure process to improve and control execution of procedures.
- Implemented project technical peer reviews
- URR's for critical facilities modifications to ensure system engineering
- Follow up team actions
- Implemented a new Johnson Space Center (JSC) S&H contract procurement solicitation for use on all "Best Value" construction
- combined all S&H requirements Federal Acquisition Regulations (FAR), NASA S&H FAR Supplements & Policy, JSC S&H Policy, Requirements & Guidelines, and OSHA Policy & Requirements into one unified document. Decide what had the greatest importance and say it twice:

> Clarify the safety references

- > Expand on the salient features in a Safety & Health Technical Provision
 - implemented the applicable results of the research study performed by the Construction Industry Institute address the Owners Involvement In Construction Safety:
 - Set a TRIR requirement for construction contractor selection.
 - Set an EMR requirement for construction contractor selection.
 - Set a DART requirement for construction contractor selection



Process


- Clarify the safety references
- Expand on the salient features in a Safety & Health Technical Provision
- The Team products were to implement the applicable results of the research study performed by the Construction Industry Institute address the Owners Involvement In Construction Safety:
- Contractor's safety performance makes a difference in contract award.

Set a TRIR requirement for construction contractor selection.


Set an EMR requirement for construction contractor selection.


Set a DART requirement for construction contractor selection.

- Specify and Review the qualification of the Contractor Safety Staff.
- Require full time safety representatives on the project.
- Require submission and review of S&H experience of Safety Staff.
- Set the minimum standard for the Site Specific S&H Plan. ()
- Require the Contractor to submit a S&H Policy signed by the CEO.
- Require a minimum specified amount of S&H training for the construction workers and supervisors.
- Put a greater emphasis on prevention and preparation with pre-task S&H planning.
- Require the contractor to implement a substance abuse program.
- Furnish and maintain injury statistics.



SUBCONTRACTOR S&H PLAN and 1413







Communicate, Communicate



