



# Structural Heat Intercept, Insulation, and Vibration Evaluation Rig (SHIIVER)

Wesley Johnson, SHIIVER Technologist

Joe Zoekler, SHIIVER Product Lead Engineer

Lauren Ameen, SHIIVER Deputy Product Lead Engineer

NASA GRC


July 6, 2017

Space Cryogenics Workshop





# Structural Heat Intercept, Insulation, and Vibration Evaluation Rig (SHIVER)





# Structural Heat Intercept, Insulation, and Vibration Evaluation Rig (SHIVER)



## Objectives:

- Perform sub-scale engineering development to ensure that the heat intercept approaches for the large-scale rig are stage-representative.
- Build a large stage-representative rig capable of testing cryogenic fluid management technologies.
- Perform an initial test of the large rig under mission-representative environmental conditions using one configuration of a possible stage-like heat intercept system (vapor cooling and multilayer insulation).


## Status

- ✓ Tank Engineering Design Approved: Dec 2016
- ✓ MLI Preliminary Design Review: Feb 2017
- ✓ Stakeholders Reviews: June 2015, July 2016
- ✓ SHIVER Concept Review: August 2015

## Schedule:

- Receive Tank at MSFC: July 2017
- Finish Sub-scale Vapor Cooling Testing: Aug 2017
- SOFI Installation completed: October 2017
- Testing Starting: August 2018
- Testing Completed: May 2019
- Final Report: April 2020

KPP	State of the Art	Project Goal
MLI Thermal Performance on a 4 m tank	SOFI baseline testing done by eCryo	40% boil-off reduction after exposure to acoustic vibration loads
MLI Mass on a 4 m tank	Thick MLI has not been demonstrated in a manner representative of an upper stage flight application.	MLI added mass of not more than 2% of tank fluid mass
Vapor Based Heat Intercept Thermal Performance on a 4 m tank	Small flight helium dewars (<2 m). CRYOTE testing (0.75 m)	15% boil-off reduction on 4 m tank at 50% full
Vapor Based Heat Intercept Mass on a 4 m tank	CRYOTE testing (.75 m tank) 9% of tank fluid mass (using LH2 density)	Not more than 5% of tank fluid mass



SHIVER tank installed in B2



Subscale vapor cooling test (skirt section hanging below calorimeter)

SHIVER is developing the baseline for thermal performance both of existing upper stages and technology enhancements





# Sub-scale Vapor Cooling Testing

- **Looking at two different flow channels:**
  - Welded, with flow directly on skirt surface
  - Bolted channel assembly
- **Preliminary results from welded flow channel shows a 50%+ reduction in heat load through the skirt. Heat load appears to be more strongly correlated to the inlet coolant temperature.**
- **Remaining tests:**
  - Bolted channel assembly – July 2017



# Multilayer Insulation

- **Design, Fabrication, and Install by Aerospace Fabrication and Materials**
  - Three pieces:
    - MLI for domes – needed for pre-acoustic thermal vacuum testing
    - MLI for curtains – needed for baseline testing
    - MLI for interior of skirts – needed for baseline testing
  - Coupon Testing Feb – June 2017 to verify performance and help scale/analyze data
- **Specifications**
  - 30 layers
  - Attached at outer diameter on skirts
  - Attached near inner manway
  - Expected heat flux less than  $1 \text{ W/m}^2$
- **Current projected mass: 40 kg**





# SHIVER Components




Forward Skirt w/  
cooling loops

4 m tank

Aft Skirt

B2 Support  
Structure



Forward Skirt:

- Design in progress (dependent on SLICE activity)
- Fabrication planned at GRC
- Anticipated Delivery: 12/17

Test Tank:

- Includes manways & “shipping skirts”
- Awarded to Didion on 10/16
- Fabrication completed
- Cold shock completed
- Cleaning/leak test prior to shipment
- Anticipated Delivery to MSFC: 7/17

Aft skirt:

- Design complete
- Fabrication at MSFC/Votaw
- Anticipated Delivery: 9/17


Support structures (3 – 1 for B2, 1 for RATF, 1 for transportation):

- B2 support structure design complete
  - Fabrication in progress @ GRC
  - Anticipated Delivery: 9/17
- Transportation Support Stand
  - Anticipated Delivery: 2/18
- RATF Support Stand
  - Initial requirements evaluated
  - Design not started
  - Anticipated Delivery: 2/18





# Predicted Benefits from Heat Intercept Technology





SHIIVER Tank During Cold Shock

Machining Tank Flanges







# TEST PLAN



# SHIVER Instrumentation

- **Temperature**

- 190 silicon diodes ordered and delivered in FY16
  - +/- 0.1 K:  $4\text{ K} < T < 30\text{ K}$
  - +/- 0.5 K:  $30\text{ K} < T < 400\text{ K}$
- Ordered with ~13 ft leads to minimize extensions needed
- Locations for 146 assigned diodes on test system have been identified and assigned by SN to P&ID

- **Liquid Level**

- Capacitance probe ordered and delivered in FY16
- RFMG installed to demonstrate scaling of hardware
- Will also have diode rake every 5%

- **Heat Flux Sensors**

- Heat flux sensors have been identified and purchased for comparative testing
- Calibration to 20 K this summer

- **Accelerometers**

- Accelerometers ordered and delivered in FY16
- Locations still being worked by SHIVER team

- **Boil-off and Vapor flow**


- Flow meters have been identified and ordered
- Covers range of expected heat loads on SHIVER

- **Pressure**

- Pressure transducers have been spec'd and identified
- Quantity and locations on P&ID identified
- Procurement and placement in B2 in progress

# Tank & SOFI


- Tank wall sensor, temperature
- SOFI surface sensor, temp
- Heat Flux Sensor





# FWD Skirt/Vapor Cooling Temperatures

- FWD skirt sensor, temperature





## Testing split into four distinct categories

- Baseline Testing:
  - Show system performance with SOFI only (sprayed to EUS dimensions and tolerances)
  - Demonstrate vapor cooling performance benefits with SOFI only
- Pre-Acoustic Testing:
  - Demonstrate performance benefits with MLI compared to baseline
  - Demonstrate vapor cooling performance benefits in conjunction with MLI
- Acoustic Testing:
  - Demonstrate that MLI survives SLS/EUS anticipated acoustic loads
  - Demonstrate that MLI survives transportation between facilities
- Post-Acoustic Testing:
  - Demonstrate performance losses due to acoustic loads on MLI system



# Thermal Vacuum Testing Priorities - Required

Tests required to meet KPPs:

- Insulation performance at 90% full
- Vapor cooling performance at 50% full

Test Name	Vapor Cooling (On/Off)	Liquid Level (%)	Curtain (Up/Down)	Baseline Testing (SOFI)	Pre-Acoustic Testing	Post-Acoustic Testing
Fill of warm tank (in Vacuum)	Off	0 – 90	Up	X	X	█
Boil-off/Heat Load High Fill	Off	90	Up	X	X	X
Boil-off/Heat Load Med Fill	Off	50	Up	X	X	X
Vapor Cooling max flow	On	50	Up	X	X	█
Vapor Cooling – Nominal	On (partial flow)	50	Up	X	X	?





# Thermal Vacuum Testing Priorities - Needed

Without these tests SHIIVER may be programmatically successful, but leave infusion targets partially satisfied.

Test Name	Vapor Cooling (On/Off)	Liquid Level (%)	Curtain (Up/Down)	Baseline Testing (SOFI)	Pre-Acoustic Testing	Post-Acoustic Testing
Boil-off/Heat Load High Fill w/curtain	Off	90	Down	X	X	X
Vapor Cooling/ High fill	On	90	Up	X	X	█
Pressure Rise, High Fill	Off	90	Up	?	X	█
Vapor Cooling- Nominal/Curt	On	50	Down	X	X	█
Transient Vapor Cooling	On	70	Up	X	X	█
Transient No Vapor Cooling	Off	70	Up	X	X	█
Fill of warm tank (in Vacuum) with cooling	On (partial flow)	0 – 90	Up	█	█	X



# Thermal Vacuum Testing Priorities - Other

Desired

Test Name	Vapor Cooling (On/Off)	Liquid Level (%)	Curtain (Up/Down)	Baseline Testing (SOFI)	Pre-Acoustic Testing	Post-Acoustic Testing
Cycling Flow	On	50	Up		X	
Boil-off Low Fill	Off	25	Up	X		X
Vapor Cooling – Low Fill	On	25	Up	X		X



# Acoustic Test Matrix



Test Name	Profile	Duration
Launch	EUS	40 s
Aero acoustics	EUS	20 s





# SHIIVER Conclusions



- **The SHIIVER test articles are making progress in development including the beginning of fabrication**
- **Performance goals and targets are show with projected performance meeting all performance goals**
- **A prioritized test matrix is laid out to meet all project and performance needs**
- **Testing should begin in late 2018**