

Assessment of a Surface Water Transportation System Concept for ISRU Operations on Mars

National Aeronautics and
Space Administration



Jared Congiardo

NASA/Kennedy Space Center

AIAA Scitech Forum


January 8-12, 2024



Introduction



- Mars Ascent Vehicle (MAV) likely largest indivisible payload predeployed to Martian surface
- Entry, Descent, and Landing limitations may make landing MAV without ascent propellant advantageous
- Options for strategies to acquire ascent propellant prior to crew arrival being studied




Trade Space



- 75t payload capacity vertical lander
- Integrated ascent vehicle
- Cryogenic propellant (LOX/LCH₄)
 - 300 t cryo propellant required for MAV launch
- Propellant manufacturing using In-situ Resource Utilization technologies*
 - Earth-delivered resources plus local resources
 - Requires plentiful power

*Oleson, S., et. al., “Kiloton Class ISRU Systems for LOX/LCH₄ Propellant Production on the Mars Surface,” *AIAA SciTech Forum*, Submitted for Publication, AIAA, Orlando, FL, 2024.


Concept of Operations



- Water delivery Mars Ascent and Landing Vehicles (MALVs) (Water-1 and Water-2) arrive at first two opportunities
- Payload remains quiescent
 - i.e. no deployment activity
- Some amount of housekeeping/heater power needed, unless payload water is allowed to freeze.
- Cargo-1 MALV delivers 1x Mobility Transport Chassis, 5x 40 kW Fission Surface Power (FSP) units and 1x Surface Water Transportation Pallet
- Mobility Transport Chassis Deploys FSPs and cabling systems
- FSPs provide power to Water MALVs
 - Allows water to thaw if frozen
- Cargo-2 delivers second Mobility Transport Chassis, 1x 40kW FSP, 3x ISRU Propellant Production Plants, 2x Liquefaction Pallets and 1x Surface Water Transportation Pallet
- Mobility Chassis Deploys FSPs, cabling systems, ISRU Pallets and Cryocoolers
- Cargo-2 also serves as the MAV and will be loaded with propellant
- Water delivery MALVs deploy downcomer hose/mating system via elevator
- Water transportation pallets aboard MT chassis alternate delivering 5t water to ISRU plants
 - Approx. 30 trips required
- Estimated water consumption of ISRU plants is ~13kg/hr (approx. 16 Earth days to empty tanker)
 - Water Transportation Pallet pressurization maintained with local atmosphere pressurized by small onboard scroll compressor
- ISRU pallets have 1 sol water capacity onboard to allow for tanker swap.
- Second water tanker on standby. Takes on water prior to switching operation.
 - Fill rate of 4.5 kg/min to fill tanker within 1 sol period. (Goal to allow tanker pallet failure contingency)

*Notional Site Planning Layout
(1 km radius circles)*

Concept of Operations (cont'd)



-104 Months

-78 Months

-52 Months

-26 Months

-23 Months

-1 Month

Departure (-0 Months)


Notional Site Planning Layout

(1 km radius circles)

Strategy & Architecture Office


- MAV ISRU operation MUST be complete prior to crew landing
- ISRU, cryocooler, and tanker systems moved by mobility to safe distance and placed in standby mode for possible reuse.
- Water-1, Water-2, and Cargo-1 are abandoned in place.

Surface Water Transportation Pallet




- Two pallets landed to support ISRU operations
- 5m³ tank pressurized with local atmosphere via scroll compressor.
- Two hose management assemblies (OSAM-1 derived) to mate to ISRU units.
 - Water connection
 - CO2 connection (to support leak checks)
 - Power connection
- Dust Tolerant Automated Umbilical connections at mating surfaces
- Electrical jack stands
- Carrier chassis interface common to all pallets




Fluid Handling and Pressurization Elements




Water Transport Pallet Electrical System Block Diagram



Thermal Design



Mobility Transport Chassis




- Two chassis landed to support surface operations
- 7.1t estimated payload capacity
- Manipulator arm adapted from Robotic Umbilical Arm studied for fluid servicing between Artemis pressurized rover and surface habitat elements.
- Translation rail/cart analogous to ISS Mobile Transporter
- Load/offload rail system to enable pallet deployment




Manipulator Arm




- Make/break connections between various surface elements, particularly the Water Transportation Pallet and the ISRU propellant plant.
- 5m reach + translation rail
- End effector toolkit for other operations as needed
- Inspection/alignment camera at tip




Load/Offload Rail System




Energetics




Water-1 to ISRU



Water-2 to ISRU






Water Delivery Lander



- Two Delivery MALVs landed to supply water for ISRU
 - Water connection
 - CO2 connection (to support leak checks)
 - Power connection
- DTAU connection at umbilical interface plate

Water Delivery Lander Thermal Analysis



Technological Needs



- Systems would operate in a Martian environment and would be critical for successful crew return for an ISRU-based return architecture
 - System reliability
 - Fault detection, isolation, and recovery
 - Repeated, reliable umbilical mating/demating
 - Autonomous robotics/operations
 - Autonomous navigation, path planning, and maneuvering
 - Autonomous task processing and scheduling
 - Autonomous manipulator system operations

Concept Animation





Questions?