



# Multi-Element Integrated Project Planning at Kennedy Space Center

Bob Mullan

Project Manager – Integrated Scheduling Lead  
ASRC Aerospace



## Introduction:

- Bob Mullon, Project Manager – Integrated Scheduling Lead
  - Currently supporting NASA with developing and maintaining an integrated critical path schedule for the design, construction and validation of Ground Systems and Elements for the new Constellation Program at Kennedy Space Center
  - Utilizing Primavera 6.0 and P6 Web Access.
  - Using Primavera products since 1987.
  - Project planner/scheduler for construction or modification of five launch pads for four different launch vehicles both for NASA and commercial construction contractors.

# Multi-Element Integrated Project Planning at Kennedy Space Center

- Introduction
- Disclaimer
- What is Constellation?
- Space Shuttle to Constellation Transition at KSC
- Constellation Program at KSC
  - Elements
  - Other Projects
- Element Schedule Development in P6
- Integration of Multiple Elements in P6
- Integrated Critical Path Analysis and Reporting
- Communicating Project Status via P6 Web
- Questions

## Introduction:

- ASRC Aerospace
  - ASRC Aerospace Corporation is a subsidiary of Arctic Slope Regional Corporation (ASRC) out of Anchorage, Alaska.
  - An Alaska Native Corporation headquartered in Greenbelt, Maryland, ASRC Aerospace is providing technical design support and project planning to the Constellation Ground Operations Project Office and the Engineering Directorate at Kennedy Space Center.
  - Winner of NASA's George M. Low Award - 2008

## Disclaimer:

- Schedule information contained in this presentation is not representative of any current NASA launch manifests or program schedules. All dates and status are for display purposes only and do not portray any current NASA commitments or obligations.

# Multi-Element Integrated Project Planning at Kennedy Space Center

- Overview
  - NASA consists of several centers and facilities spread across 10 different states from the east coast to the west coast and the Gulf of Mexico to Cleveland, Ohio.
  - The work force consists of civil servants (NASA employees) and numerous support contractors and contractor personnel. It also involves a large number of independent suppliers and contractors providing materials and services to keep up with current program needs.
  - Acronyms and abbreviations are a key part of day to day operations at the Kennedy Space Center. There is not a key center, facility, building, system, process or meeting that can be referred to without the use of an acronym or abbreviation. Kennedy Space Center, more commonly known as KSC, is just one example. NASA is another. There are many more to follow.
  - Kennedy Space Center (KSC) is located on the east coast of Florida and is the designated launch site for all of NASA's manned space flights.



# Map of Constellation content across NASA




# Constellation:

- What is Constellation?
  - Constellation represents the next phase of manned space flight for NASA and the USA
    - Involves the design and development of the Ares I and Ares V launch vehicles, the Orion Crew Module and Lunar Lander. These vehicles will provide service to the International Space Station and continue manned space exploration to the moon, Mars and beyond
    - Involves the design, development and construction of new hardware and infrastructure to process, launch and recover these launch vehicles
    - Involves the transition of existing facilities and infrastructure at Kennedy Space Center (KSC) from current Space Shuttle configurations to the new Ares I and V configurations



# Building on a Foundation of Proven Technologies - Launch Vehicle Comparisons -



## Transition:

- Space Shuttle to Constellation Transition at KSC
  - KSC is currently scheduled to process and launch Space Shuttles through 2010
  - Constellation will use the same launch complexes (LC-39A and LC-39B) and many of the same systems and facilities that are used for the Space Shuttle
  - LC-39B will be the first launch complex to be modified for Constellation. Following the launch of the Hubble Space Telescope Repair mission, LC-39B will begin modifications for the first test flight of the new launch vehicle configuration
  - The first Constellation test flight, Ares I-X, will launch from LC-39B in early to mid 2009
  - LC-39A is scheduled to begin modifications for the Constellation cargo vehicle, Ares V-Y, following the last Shuttle flight in 2010
  - The first manned flight for Constellation is scheduled for 2015

# Constellation Program at Kennedy Space Center (KSC):

- Constellation Program at KSC - EPS/WBS
  - Involves the Ground Operations node of the Constellation Program EPS/WBS
  - Within this node is the Ground Systems Development and Sustaining node which contains the Ground Systems and Elements that will process, launch and recover the new launch vehicle and spacecraft, Ares and Orion
  - Ground Systems Development is the primary WBS for the Constellation schedules to be discussed today
  - Within that node we will focus on the development of the project schedules and critical path to Ground Systems Initial Operational Capability (IOC) for the launch of the first “full stack” of the Ares Launch Vehicle – Ares I-Y

## Constellation Ground Operations EPS/WBS:

+	◆	NASAIP	NASA Interlink Projects	NASAIP	
=	◆	292360	Ground Operations	292360	
+	◆	STS	STS Summary	292360	
+	◆	292360.L3	Ground Operations Level III	292360.L3M	
	◆	292360.01	Project Management	292360.01	
+	◆	292360.02	Systems Engineering & Integration	292360.02	
	◆	292360.03	Safety & Mission Assurance	292360.03	
+	◆	292360.05	Future Elements Development & Operatio	292360.05	
+	◆	292360.06	Orion Dev Support & Ground Operations	292360.06	
+	◆	292360.07	KSC Integrated Operations	292360.07	
+	◆	292360.08	Launch Vehicle Dev Support & Operations	292360.08	
=	◆	292360.09	Ground Systems Development & Sustaining	292360.09	
+	◆	292360.09 INT	Ground Systems Integration	292360.09	
=	◆	292360.09.20	Ground Systems CLV	292360.09.20	
	+	◆	292360.09.20.01	VAB HB#3 CLV	292360.09.20.01
	+	◆	292360.09.20.02	KSC-Mobile Launcher CLV	292360.09.20.02
	+	◆	292360.09.20.03	Pad B CLV	292360.09.20.03
		◆	292360.09.20.04	LCC CLV	292360.09.20.04
	+	◆	292360.09.20.05	KSC-Hangar AF CLV	292360.09.20.05
+	◆	292360.09.21	KSC-Ground Sys Spacecraft Process & Pay	292360.09.21	
+	◆	292360.09.22	KSC-Ground Systems CaLV	292360.09	
=	◆	292360.09.24	Ground Systems Common Support Sys	292360.09	
	+	◆	292360.09.24.04	Launch Equipment Test Facility	292360.09
+	◆	292360.09.25	KSC-Command, Control and Communications	292360.09.25	
+	◆	292360.09.30	Ares I-X Development	292360.09.30	

## Constellation Program at KSC:

- Ares I-Y Ground Systems Development Elements
  - Mobile Launcher Element (MLE)
  - Launch Pad Element (LPE)
  - Vertical Integration Element (VIE)
  - Solid Rocket Processing Element (SRPE)
  - Spacecraft Processing Element (SPE)
  - Command, Control and Communications Element (CCCE)
- Other Projects
  - Ares I-X Test Flight
  - Launch Equipment Test Facility (LETF)

## Ground Systems Development Elements:

- Mobile Launcher Element (MLE)
  - New mobile launcher compatible with LC 39B and existing capacity transporter & crawlerway
  - Consists of Mobile Launcher Base (MLB), Tower (MLT) and facility systems along with launch accessories and spacecraft related fluid, gas, electrical, communication, imagery and launch control systems to service the Ares launch vehicle and Orion spacecraft
  - 385' tall and approximately 12,000,000 lbs


- Mobile Launcher with Ares I-Y




# Ground Systems Development Elements

- Launch Pad Element (LPE)
  - Both launch pads are currently operational and used by the Space Shuttle program. LC-39B will be used to launch Ares I, LC-39A will be used to launch Ares V
  - LC-39B project consists of modifying existing systems to interface with the new Mobile Launcher, installing new instrumentation, lightning protection, emergency egress system and demolition of the existing Fixed and Rotating Service Structures

- Launch Complex 39B - Current



- Launch Complex 39B - Future



## Ground Systems Development Elements:

- Vertical Integration Element (VIE)
  - The Vehicle Assembly Building (VAB) will be used to assemble and integrate launch vehicles and spacecraft in vertical mode.
  - The Ares I VAB project will rework High Bay #3 for Ares I stacking with a new platform concept allowing 360° access to the Ares and Orion spacecraft
  - Project consists primarily of installing new platforms, modifying existing systems and installing new Ground Support Equipment (GSE) to interface with the new Mobile Launcher and spacecraft

- Vehicle Assembly Building (VAB)



## Ground Systems Development Elements:

- Solid Rocket Processing Element (SRPE)
  - The Solid Rocket Processing Element is composed of the facilities and systems necessary to process solid rocket components (boosters).
  - Consists of the existing Assembly Refurbishment Facility (ARF), existing Rotation Processing Surge Facility (RPSF), construction of new Rotation Processing Surge Facility (RPSF) and modifications to existing Hangar AF Complex.
  - Modifications to the Hangar AF Complex for the Ares I-X test flight in 2009 are currently under way.

## Ground Systems Development Elements:

- **Spacecraft Processing Element (SPE)**
  - The Spacecraft Processing Element (SPE) is composed of the facilities, systems and Ground Support Equipment (GSE) necessary to transport, service, fuel and integrate the Orion Crew Module with the Ares launch vehicle and other Elements in preparation for launch.
  - Consists of design, procurement, fabrication, installation and validation of above GSE along with Multi-Payload Processing Facility (MPPF) modifications, Multi-Mission Support Equipment (MMSE), Prime Mover for Launch Abort System (LAS) and all systems and support equipment for the Lunar Lander (future missions).

- Orion Crew Module – Short Stack



# Ground Systems Development Elements

- Command, Control and Communications Element (CCCE)
  - The Command, Control and Communications Element is composed of two parts
    - Command and Control or Launch Control System (LCS), consists of computer hardware and software used for operation of ground systems and launch vehicles in support of launch processing and launch
    - Communications consists of providing infrastructure for voice, imagery (video and film), and data to support launch processing along with leveraging existing communications systems for all Constellation Support throughout the development efforts of Command and Control as well as the other Ground Systems Elements


## Other Projects:

- **Launch Equipment Test Facility (LETF)**
  - The LETF will be used to provide prototype Ground Support Equipment (GSE) and element development, testing and qualification for mechanical, umbilical systems, fluids, electrical GSE systems and components.

## Other Projects:

- Ares I-X
  - Ares I-X is the initial demonstration flight of the Ares launch vehicle configuration. Ares I-X demonstration flight ground systems will utilize existing infrastructure, modifying only what is necessary to support the mission. All modifications will be done on a non-interference basis and will allow the Space Shuttle Program (SSP) to preserve Launch On Need capability for the Hubble Space Telescope mission.

- Ares I-X



## Ground Systems Development Elements:

- Schedule Development in P6
  - Constellation program office made the decision to use Primavera Project Management software as its scheduling tool 2 – 3 years ago
  - Element and Other Project schedules were required to be completed and managed as stand alone projects with “control” milestones established for reporting to upper levels of the program
  - Schedules were also required to establish “sound” logic defining inter-project dependencies as well as external dependencies (ie. Program deliverables)

## Ground Systems Development Elements:


- Schedule Development in P6
  - The Constellation database and Primavera software exists at Marshall Space Flight Center in Huntsville, AL.
  - The system operates on the NASA Citrix Access Platform in the NASA secure Integrated Collaborative Environment (ICE)

## Elements and Other Projects within EPS/WBS:

292360.09	<b>Ground Systems Development &amp; Sustaining</b>	292360.09
292360.09 INT	<b>Ground Systems Integration</b>	292360.09
GE Rqmts-29	Ground Elements Integration	TS Cx Ground Operations
W06.292360.09.99-1	Ground Systems Project - Ares 1-Y ORD	IS 0089
292360.09.20	<b>Ground Systems CLV</b>	292360.09.20
292360.09.20.01	<b>VAB HB#3 CLV</b>	292360.09.20.01
W06.VAB-1	VAB HB-3 - PMR	IS 0089
292360.09.20.02	<b>KSC-Mobile Launcher CLV</b>	292360.09.20.02
W06.292360.09.20.02-1	Mobile Launcher - PMR	IS 0089
292360.09.20.03	<b>Pad B CLV</b>	292360.09.20.03
W06.292360.09.20.03-1	CLV Pad B - PMR	IS 0089
292360.09.20.04	<b>LCC CLV</b>	292360.09.20.04
W06.LCC-1	LCC CLV - PMR	IS 0089
292360.09.20.05	<b>KSC-Hangar AF CLV</b>	292360.09.20.05
W06.HAF-1	Hangar AF CLV - PMR	IS 0089
292360.09.21	<b>KSC-Ground Sys Spacecraft Process &amp; Pay</b>	292360.09.21
W06.SPE 09-1	Spacecraft Processing - PMR	IS 0089
W06.SPE MPPF 09-1	Spacecraft Processing MPPF - PMR	IS 0089
292360.09.22	<b>KSC-Ground Systems CaLV</b>	292360.09
GS CaLV 09-3	Ground Systems CaLV	292360.09
292360.09.24	<b>Ground Systems Common Support Sys</b>	292360.09
292360.09.24.04	<b>Launch Equipment Test Facility</b>	292360.09
W06.LETF-2	LETF CxP Program Support - PMR	IS 0089
292360.09.25	<b>KSC-Command, Control and Communications</b>	292360.09.25
W06.292360.09.25.01-1	Command and Control - PMR	IS 0089
W0608.COMM-1	Communications - PMR	IS 0089
292360.09.30	<b>Ares I-X Development</b>	292360.09.30
W06.292360.09.30-1	Ares I-X GS Development - PMR	IS 0089

LC 39B, Mobile Launcher and VAB High Bay #3  
 Level IV Summary w/ Milestones  
 Current Project Schedule through ORD

Date: 00/00/00  
 Page 1 of 6  
 Data Date: 00/00/00




- ⊙ L1C MS Open
- ⊙ L2C MS Closed
- △ L3C MS Open
- ▽ L3N MS Closed
- ◇ Level V Open
- ◆ Baseline Milestone
- ⊙ L1C MS Closed
- ▽ L2N Open
- ▲ L3CMS Closed
- ◇ L4C MS Open
- ◆ Level V Closed
- Current Bar
- ⊙ L2C MS Open
- ▽ L2N MS Closed
- ⊕ L3N MS Open
- ◆ L4C MS Closed
- Project Baseline
- % Complete



LC 39B, Mobile Launcher and VAB High Bay #3  
 Level IV Summary w/ Milestones  
 Current Project Schedule through ORD

Date: 00/00/00  
 Page 2 of 6  
 Data Date: 00/00/00




- ⊙ L1C MS Open      ⊙ L2C MS Closed      △ L3C MS Open      ▾ L3N MS Closed      ◇ Level V Open      ◆ Baseline Milestone
- ⊙ L1C MS Closed      ▽ L2N Open      ▲ L3CMS Closed      ◇ L4C MS Open      ◆ Level V Closed      [Green Bar] Current Bar
- ⊙ L2C MS Open      ▾ L2N MS Closed      ▽ L3N MS Open      ◆ L4C MS Closed      [Yellow Bar] Project Baseline      [Blue Bar] % Complete



LC 39B, Mobile Launcher and VAB High Bay #3  
 Level IV Summary w/ Milestones  
 Current Project Schedule through ORD

Date: 00/00/00  
 Page 3 of 6  
 Data Date: 00/00/00




- ⊙ L1C MS Open      ⊕ L2C MS Closed      △ L3C MS Open      ▾ L3N MS Closed      ◇ Level V Open      ◆ Baseline Milestone
- ⊙ L1C MS Closed      ▽ L2N Open      ▲ L3CMS Closed      ◇ L4C MS Open      ◆ Level V Closed      █ Current Bar
- ⊙ L2C MS Open      ▾ L2N MS Closed      ▽ L3N MS Open      ◆ L4C MS Closed      █ Project Baseline      █ % Complete



LC 39B, Mobile Launcher and VAB High Bay #3  
 Level IV Summary w/ Milestones  
 Current Project Schedule through ORD

Date: 00/00/00  
 Page 4 of 6  
 Data Date: 00/00/00




- ⊙ L1C MS Open
- ⊙ L1C MS Closed
- ⊙ L2C MS Open
- ⊙ L2C MS Closed
- ⊙ L3C MS Open
- ⊙ L3CMS Closed
- ⊙ L3N MS Open
- ⊙ L3N MS Closed
- ⊙ L4C MS Open
- ⊙ L4C MS Closed
- ◇ Level V Open
- ◆ Level V Closed
- ◇ Baseline Milestone
- [Green Bar] Current Bar
- [Yellow Bar] Project Baseline
- [Dark Green Bar] % Complete



LC 39B, Mobile Launcher and VAB High Bay #3  
 Level IV Summary w/ Milestones  
 Current Project Schedule through ORD

Date: 00/00/00  
 Page 5 of 6  
 Data Date: 00/00/00



⊙ L1C MS Open	⊙ L2C MS Closed	△ L3C MS Open	▽ L3N MS Closed	◇ Level V Open	◇ Baseline Milestone
⊙ L1C MS Closed	▽ L2N Open	▲ L3CMS Closed	◇ L4C MS Open	◆ Level V Closed	[Green Bar] Current Bar
⊙ L2C MS Open	▽ L2N MS Closed	▽ L3N MS Open	◆ L4C MS Closed	[Yellow Bar] Project Baseline	[Dark Green Bar] % Complete



LC 39B, Mobile Launcher and VAB High Bay #3  
 Level IV Summary w/ Milestones  
 Current Project Schedule through ORD

Date: 00/00/00  
 Page 6 of 6  
 Data Date: 00/00/00

Activity Name	Year							
	2	3	4	5	6	7	8	
■ Pad Ready to Receive ML						◆		
■ ML to Pad						◆	▽	
■ Integrated Systems Act/Val Finish							▽	

- ⊕ L1C MS Open
- ⊙ L2C MS Closed
- △ L3C MS Open
- ∇ L3N MS Closed
- ◇ Level V Open
- ◆ Baseline Milestone
- ⊙ L1C MS Closed
- ▽ L2N Open
- ▲ L3CMS Closed
- ◇ L4C MS Open
- ◆ Level V Closed
- Current Bar
- ⊕ L2C MS Open
- ▼ L2N MS Closed
- ∇ L3N MS Open
- ◆ L4C MS Closed
- Project Baseline
- % Complete



## Ground Systems Development Elements:

- Integration of Multiple Elements
  - P6 allows for easy analysis of multiple schedules in order to identify and assign relationships between projects
  - User-defined text fields allows you to define relationships and give explanations in regards to direction and purpose of these relationships along with filtering data based on these fields
  - Although unique, intelligent activity ID's are preferred, having separate projects allows you use non-unique ID's across different projects within your Master Schedule

## Ground Systems Development Elements:

- Integration of Multiple Elements
  - Initiated weekly schedulers meetings
  - Prepared scheduling standards and work instructions
    - Standardize levels of detail
    - Set baseline standards
    - Standardize layouts, naming conventions, coding, etc.
  - Completed Local Admin training and obtained privileges
  - Integration of Multiple Elements requires integration at all levels inside and outside of Primavera

## Ground Systems Development Elements:

- Integration of Multiple Elements
  - Created an Integrated “ORD” project to allow critical path to be calculated through one ORD as opposed to each project ORD
  - Adjust Must Finish by dates for each project to on, or after, the Must Finish By Date for the integrated ORD project
  - Change all Mandatory and Start/Finish On constraints in all projects to soft constraints (Start/Finish on or after)
  - Change or remove On or Before constraints except for the Ares I-Y ORD Milestone in the integrated ORD project
  - Tag all interproject ties with user defined text field with “To Project/From Project” designator
  - Make sure all projects are updated properly through current data date and all data dates are the same
  - See the following layout

 <b>Ground Systems Project          Integrated Master Schedule          Inter-Project Relationships</b>					Date: 00/00/00 Page 1 of 4 Data Date: 00/00/00						
Activity ID	Activity Name	From/To	Predecessors	Successors	Year						
					3	4	5	6	7	8	9
<b>Ground Systems Project - Ares 1-Y ORD</b>											
GS9000	Ground Systems Projects ORD	To GO Ares 1-Y GORR	A2350, MLA1960, A10500, SP10680, SP4220, CC10590	A1990							
<b>Mobile Launcher - PMR</b>											
MLC1580	Communications Fabrication & Installation De...	To Comm	MLE10330	MLC1730, A16180							
MLF1400	Structural & Facility	To GSE Install	MLF1380, MLM2600, MLF1382	ML10480, ML10480, MLM2120, MLC1730, MLU1700, MLF1405, MLF1405, MLG1710, MLI1720, MLH1740							
MLF2590	ML - Pad Interflows Design Requirements	TBD	MLF2010	MLA1960, MLU1505							
MLU1505	Umbilical GSE Testing (LETF)	From LETF ORD	MLU1500, MLU1490, MLU1450, MLF2590, LE1290	MLU2250, MLU1705, MLM2125							
MLM2125	ML GSE M&E Installation Contract	To ML Act/Val	MLU1505, MLM1681	MLM2130, MLM2126, MLM2126							
MLC1730	Communications Fabrication & Installation Contract	To Comm	MLC1580, MLE1410, MLF1400	ML10490, ML10490, MLC1860, MLC1870, MLC1880, MLA10430, MLC1735, MLC1735, A9580, A9590, A9600, A9620, A9630, A9660, A9670, A9640, A9650							
MLM2120	Start ML GSE M&E Installation	To Comm ML Install	MLF1400								
MLM2130	Finish ML GSE M&E Installation	To ML Act/Val	MLM2125	MLA10430, MLA10400, MLA1780, MLA1770, MLI1760							
MLA10400	Crawler Transporter Need Date	No CT Data	MLM2130								
MLA1780	LCC Firing Room Need Date	No LCC Data	MLM2130								
MLA10430	Start ML Activation and Validation	From VAB	MLH1740, MLC1730, MLG1710, MLM2130, MLU1700, A2310, MLA2520	MLA2149, ML10500, MLG1810, MLG1820, MLG1830, MLG1840, MLG1850, MLI2240, MLC1860, MLC1870, MLC1880, MLU2250, GSML1000							
MLA1770	VAB High Bay Need Date	To ML VAB Testing	MLE1410, MLM2130	MLG1810, MLG1820, MLG1830, MLG1840, MLG1850							
MLI1760	GSE PLC Software Drop Need Date	To ML A/V	MLM2130	MLI2240							
MLG1850	Coolants Connect, Leak and Flow Tests	To ML to Pad	MLA1770, MLA10430	MLA2150, MLA10410, A10650							
MLG1840	SRB Hydraulics Connect, Leak and Flow Tests	To ML to Pad	MLA1770, MLA10430	MLA2150, MLG1920, MLA10410, A10650							
MLG1810	ECS Flow and Balance Test - VAB	To ML to Pad	MLA1770, MLA10430	MLA2150, MLG1890, MLG1805, MLG1804, MLA10410, A10650, GSML1000							
MLG1820	Gaseous Nitrogen Connect, Leak and Flow T...	To ML to Pad	MLA1770, MLA10430	MLA2150, MLA10410, A10650							
MLG1830	Gaseous Helium Connect, Leak and Flow Tests	To ML to Pad	MLA1770, MLA10430	MLA2150, MLA10410, A10650							





Ground Systems Project  
 Integrated Master Schedule  
 Inter-Project Relationships

Date: 00/00/00  
 Page 3 of 4  
 Data Date: 00/00/00



Activity ID	Activity Name	From/To	Predecessors	Successors	Year											
					3	4	5	6	7	8	9					
A1330	Power Construction	From Ares 1-X	A1320, AIX1010	A3140, A3140, A2830												
A1370	Compressed Air Construction	From Ares 1-X	A1360, AIX1010	A3140, A3140, A2830												
A1410	Chilled Water Construction	From Ares 1-X	A1400, AIX1010	A3140, A3140, A2830												
A1660	Special Power for GSE Installation	From Ares 1-X	A1650	A3170, A3170, A2830												
A2830	Integrated System Testing and Activation (by contractor)	To A/V	A2770, A1200, A1450, A1580, A2510, A2820, A2600, A10910, A2690, A2480, A2480, A1660, A1740, A1820, A1900, A2060, A2140, A2220, A2300, A2460, A1250, A1410, A1370, A1330, A1290	A10710, A10830												
A10710	Integrated Systems Act/Val Start	From C&C	A2480, A2830, A10670, CC10580	A2840												
A2840	Integrated Systems Act / Val	From Pad SS's/ML	A10710, MLG1920, MLG1910	A10880, A10880, A10720, GSPB1020, GSPB1020												
A10830	Pad Ready to Receive ML	To ML to Pad	A2480, A2830	A10650												
A10650	ML to Pad	To ML A/V @ Pad	A10830, MLG1810, MLG1820, MLG1830, MLG1840, MLG1850	MLG1890, MLG1900, MLG1910, MLG1920, GSML1010												
A10500	Pad B ORD	To Ares 1-Y ORD	A10720	GS9000												
A10720	Integrated Systems Act/Val Finish	To Pad B ORD	A2840, A10770, A10680, A10760, A10730, A3250, A2390, A10510, A2470, A10490, A10640, A1040	A10500												
<b>LCC CLV - PMR</b>																
A2430	LCC FR-1 CCC Joint Occupancy	To Ares 1-X	A2480	A10640, AIX1050												
A10500	LCC FR-1 Modification Project ORD	To Ares 1-X	A2995	AIX1050												
<b>Hangar AF CLV - PMR</b>																
A1190	Hangar AF ORD	To Ares 1-X	A2510, A2500, A1205, HAF1900, HAF1310, HAF2030	AIX9730												
<b>Spacecraft Processing - PMR</b>																
SP1250	Quick Disconnects (LM) Need Date	TBD	SP1700, SP1960	SP1750, SP2010												
SP4190	Spacecraft Transporter Need Date	TBD	SP3470													
SP1270	ECLSS (LM) Need Date	TBD	SP1260	SP2370												
SP1280	Orion Electrical GSE (LM) Need Date	From C&C	SP1030	SP2510												
SP1260	Misc GSE (LM) Need Date	TBD	SP1030	SP1270, SP2230												
SP4220	ORD Orion GSE	To Ares 1-Y ORD	SP1600, SP1860, SP2120, SP2400, SP2260, SP2540, SP1640, SP1900, SP2160, SP2440, SP2580, SP2300	GS9000												
SP4150	LL Electrical GSE Need Date (LM)	TBD		SP4030, SP3900												
<b>LETF CxP Program Support - PMR</b>																



## Ground Systems Development Elements:

- Integrated Critical Path Analysis and Reporting
  - P6 allows for easy analysis of multiple float paths even through different calendars across multiple projects
  - Basic principals of critical path analysis apply to each project as well as to all projects
  - Verify above requirements have been implemented
  - Open all schedules involved with the Integrated Master Schedule
  - Calculate the schedules making sure interproject relationships are considered
  - See following layouts



Ground Systems Project  
 Integrated Master Schedule  
 IMS Critical Paths by Project, Total Float & Start

Date: 00/00/00  
 Page 1 of 3  
 Data Date: 00/00/00

Activity ID	Activity Name	Total Float	Year						
			3	4	5	6	7	8	9
<b>Ground Systems Project - Ares 1-Y ORD</b>									
GS9000	Ground Systems Projects ORD	0.0d							
<b>Command and Control - PMR</b>									
CC21680	System Design Development Drop 2	0.0d							
CC21690	System Design Verification Drop 1	0.0d							
A4320	Design/Implementation for Verification Drop 1	0.0d							
CC21700	System Design Verification Drop 2	0.0d							
CC24610	Formal Test Verification Drop 1	0.0d							
A4330	Design/Implementation for Verification Drop 2	0.0d							
CC11090	Design/Implementation for Release 1	0.0d							
CC24630	Formal Test Verification Drop 2	0.0d							
CC24620	Formal Test Release 1	0.0d							
CC1070	Implementation Release 1.1	0.0d							
CC31000	Validation Testing Release 1	0.0d							
CC1080	Informal Test Release 1.1	0.0d							
CC11010	Formal Test Release 1.1	0.0d							
CC31200	Validation Testing Release 1.1	0.0d							
CC10590	LCS-CEV/CLV ORD	0.0d							
<b>CLV Pad B - PMR</b>									
A1720	Kennedy Ground Control System (KGCS) Design	6.0d							
A1730	Kennedy Ground Control System (KGCS) Fabrication	6.0d							
A1740	Kennedy Ground Control System (KGCS) Installation	6.0d							
A2830	Integrated System Testing and Activation (by contract...	6.0d							
A10710	Integrated Systems Act/Val Start	6.0d							
A2840	Integrated Systems Act / Val	6.0d							
A10500	Pad B ORD	6.0d							
A10720	Integrated Systems Act/Val Finish	6.0d							
A1180	ECS Design	11.0d							
A1230	GN2/GHe Design	11.0d							
A1270	Potable Water/Sewer/Firex Design	11.0d							
A1310	Power Design	11.0d							
A1350	Compressed Air Design	11.0d							
A1390	Chilled Water Design	11.0d							
A1190	ECS A&A	11.0d							
A1240	GN2/GHe A&A	11.0d							
A1280	Potable Water/Sewer/Firex A&A	11.0d							
A1320	Power A&A	11.0d							
A1360	Compressed Air A&A	11.0d							
A1400	Chilled Water A&A	11.0d							



Ground Systems Project  
 Integrated Master Schedule  
 IMS Critical Paths by Project, Total Float & Start


Date: 00/00/00  
 Page 2 of 3  
 Data Date: 00/00/00

Activity ID	Activity Name	Total Float	Year						
			3	4	5	6	7	8	9
█ A1200	ECS Construction	11.0d							
█ A1250	GN2/GHe Construction	11.0d							
█ A1290	Potable Water/.Sewer/Firex Construction	11.0d							
█ A1330	Power Construction	11.0d							
█ A1370	Compressed Air Construction	11.0d							
█ A1410	Chilled Water Construction	11.0d							
➤ Mobile Launcher - PMR									
█ MLF1370	TCRMSF PDQ	9.0d							
█ MLF1380	ARNTPDQ	9.0d							
█ MLF1400	Structural & Facility	9.0d							
█ MLM1610	M&E Install Contr Draft Solicitation Release	9.0d							
█ MLM1620	M&E Install Contr Final Solicitation	9.0d							
█ MLM1630	Receive M&E Install Contr Offers	9.0d							
█ MLM1640	Evaluate M&E Install Contr Offers	9.0d							
█ MLM1650	Competitive Range Determination	9.0d							
█ MLM1660	Conduct M&E Install Contr Discussions	9.0d							
█ MLM1670	Receive Final Proposal Revisions	9.0d							
█ MLM1680	M&E Installation Contract Award	9.0d							
█ MLM1681	Limited Notice to Proceed	9.0d							
█ MLH1740	Handling & Access GSE Fabrication & Installation	9.0d							
█ MLM2125	ML GSE M&E Installation Contract	9.0d							
█ MLG1710	Propellants & Gases GSE Installation	9.0d							
█ MLC1730	Communications Fabrication & Installation Contract	9.0d							
█ MLM2130	Finish ML GSE M&E Installation	9.0d							
█ MLA10430	Start ML Activation and Validation	9.0d							
█ MLA1770	VAB High Bay Need Date	9.0d							
█ MLG1850	Coolants Connect, Leak and Flow Tests	9.0d							
█ MLG1840	SRB Hydraulics Connect, Leak and Flow Tests	9.0d							
█ MLG1810	ECS Flow and Balance Test - VAB	9.0d							
█ MLG1820	Gaseous Nitrogen Connect, Leak and Flow Tests	9.0d							
█ MLG1830	Gaseous Helium Connect, Leak and Flow Tests	9.0d							
█ MLA2520	ML PLC Software Drop from CCC	10.0d							
█ MLU1700	Umbilical GSE Installation	10.0d							
█ MLA2149	ML Activation and Validation	12.0d							
█ MLU2250	Umbilical Activation / Validation	12.0d							
█ MLA1940	ML Water Tests (SRB IOP, Firex, deck quench, towe...	12.0d							
█ MLA1950	CEV Emergency Egress Test	12.0d							
█ MLA10410	ML Pad B Need Date	12.0d							
█ MLG1890	ECS Flow and Balance Test - Pad	12.0d							



Ground Systems Project  
 Integrated Master Schedule Critical Paths  
 Tertiary - VAB HB #3/ML/Pad B - TF > 8 < 13 work days

Date: 00/00/00  
 Page 1 of 1  
 Data Date: 00/00/00



- ⊙ L1C MS Open
- ▽ L2N Open
- ▲ L3CMS Closed
- ◇ L4C MS Open
- ◆ Level V Closed
- Project Baseline
- ⊙ L2C MS Open
- ▼ L2N MS Closed
- ⚡ L3N MS Open
- ◆ L4C MS Closed
- ◇ Baseline Milestone
- % Complete
- ⊙ L2C MS Closed
- △ L3C MS Open
- ⚡ L3N MS Closed
- ◇ Level V Open
- Current Bar Labels




# Communicating Project status via P6 Web / MyPrimavera

- Purpose:
  - P6 Web / MyPrimavera was rolled out to give NASA Project Managers 24x7 visibility into their project schedules and minimize the need for the scheduler to run ad-hoc schedule reports
  - Also gives the responsible manager the ability to run their own what-if analysis via P6 Web
- Implementation:
  - ASRC scheduler is given access to responsible manager's individual sandbox
  - ASRC scheduler sets up portfolios and basic dashboards so responsible manager only sees what he needs/wants to see
  - Current and working (what if) schedules are placed in the responsible managers individual sandbox
  - Layouts and filters are set up so that schedule views are what the responsible manager is used to seeing
  - Responsible manager can view project and schedule information and modify schedules and views with minimal training and appropriate security clearance


# P6 Web Customized Dashboard:

The screenshot displays a web browser window titled "Primavera - Dashboards". The main content area is titled "GS - Project Dashboard" and includes a filter set to "Portfolio: Proj Portfolio - KSC A". The dashboard features several expandable sections: "Project Statistics", "My Projects", "My Risks", and "My Issues". A prominent "NASA Web Interface" section contains a security warning: "This Is a U.S. Government Computer. This system is for the use of authorized users only. By accessing and using the computer system you are consenting to system monitoring, including the monitoring of keystrokes. Unauthorized use of, or access to, this computer system may subject you to disciplinary action and criminal prosecution." Below this is a "Log in" form with fields for "User name:" and "Password:". A "Welcome" message follows, stating "Please log in. To log in to Citrix, enter the credentials required, and then click Log In. If you have problems using an application, please contact the IMCC at 1-866-986-4778." The bottom section, "Tool Help", features a banner for "EXPLORATION SYSTEMS ICE Portal" with the slogan "Moon, Mars, and Beyond...". It includes navigation links for "ICE Portal Home", "ICE Tool Support", "ICE Applications", "Sites", "Reviews", and "My Pages". At the bottom, there are three "Helpful Documents" sections: "Windchill Help", "Primavera Help", and "Cradle Help".

# P6 Web Customized View:



# P6 Web Customized View:



# Multi-Element Integrated Project Planning at Kennedy Space Center

- Questions?

08-476

**REPORT DOCUMENTATION PAGE**

Form Approved  
OMB No. 0704-0188

The public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0704-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.

PLEASE DO NOT RETURN YOUR FORM TO THE ABOVE ADDRESS.

<b>1. REPORT DATE (DD-MM-YYYY)</b>		<b>2. REPORT TYPE</b> presentation		<b>3. DATES COVERED (From - To)</b> November 16-19, 2008	
<b>4. TITLE AND SUBTITLE</b> Multi-Element Integrated Project Planning at Kennedy Space Center				<b>5a. CONTRACT NUMBER</b> NAS10-03006	
				<b>5b. GRANT NUMBER</b>	
				<b>5c. PROGRAM ELEMENT NUMBER</b>	
<b>6. AUTHOR(S)</b> Robert Mullon, ASRC Aerospace				<b>5d. PROJECT NUMBER</b>	
				<b>5e. TASK NUMBER</b>	
				<b>5f. WORK UNIT NUMBER</b>	
<b>7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)</b> ASRC Aerospace ASRC-50 Kennedy Space Center, FL 32899				<b>8. PERFORMING ORGANIZATION REPORT NUMBER</b>	
<b>9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)</b> National Aeronautics and Space Administration Engineering Directorate (LX) Kennedy Space Center, FL 32899				<b>10. SPONSORING/MONITOR'S ACRONYM(S)</b>  NASA/KSC	
				<b>11. SPONSORING/MONITORING REPORT NUMBER</b>	
<b>12. DISTRIBUTION/AVAILABILITY STATEMENT</b>					
<b>13. SUPPLEMENTARY NOTES</b>					
<b>14. ABSTRACT</b> This presentation demonstrates how the ASRC Scheduling team developed working practices to support multiple NASA and ASRC Project Managers using the enterprise capabilities of Primavera P6 and P6 Web Access. This work has proceeded as part of Kennedy Ground Systems' preparation for its transition from the Shuttle Program to the Constellation Program. The presenters will cover Primavera's enterprise-class capabilities for schedule development, integrated critical path analysis, and reporting, as well as advanced Primavera P6 Web Access tools and techniques for communicating project status.					
<b>15. SUBJECT TERMS</b> Primavera, integrated critical path, multiple element integration					
<b>16. SECURITY CLASSIFICATION OF:</b>			<b>17. LIMITATION OF ABSTRACT</b>	<b>18. NUMBER OF PAGES</b>  1	<b>19a. NAME OF RESPONSIBLE PERSON</b> Robert Mullon
<b>a. REPORT</b>	<b>b. ABSTRACT</b>	<b>c. THIS PAGE</b>			<b>19b. TELEPHONE NUMBER (Include area code)</b>  (321) 867-9903