


NASA/TM-2015-218809
NESC-RP-15-01039



Glenn Extreme Environments Rig (GEER) Independent Review

*Robert S. Jankovsky/NESC and Michael D. Smiles/NESC
Langley Research Center, Hampton, Virginia*

*Mark A. George
Glenn Research Center, Cleveland, Ohio*

*Mimi C. Ton
Jet Propulsion Laboratory, Pasadena, California*

*Son K. Le
Stennis Space Center, Mississippi*

NASA STI Program . . . in Profile

Since its founding, NASA has been dedicated to the advancement of aeronautics and space science. The NASA scientific and technical information (STI) program plays a key part in helping NASA maintain this important role.

The NASA STI program operates under the auspices of the Agency Chief Information Officer. It collects, organizes, provides for archiving, and disseminates NASA's STI. The NASA STI program provides access to the NTRS Registered and its public interface, the NASA Technical Reports Server, thus providing one of the largest collections of aeronautical and space science STI in the world. Results are published in both non-NASA channels and by NASA in the NASA STI Report Series, which includes the following report types:

- **TECHNICAL PUBLICATION.** Reports of completed research or a major significant phase of research that present the results of NASA Programs and include extensive data or theoretical analysis. Includes compilations of significant scientific and technical data and information deemed to be of continuing reference value. NASA counter-part of peer-reviewed formal professional papers but has less stringent limitations on manuscript length and extent of graphic presentations.
- **TECHNICAL MEMORANDUM.** Scientific and technical findings that are preliminary or of specialized interest, e.g., quick release reports, working papers, and bibliographies that contain minimal annotation. Does not contain extensive analysis.
- **CONTRACTOR REPORT.** Scientific and technical findings by NASA-sponsored contractors and grantees.


- **CONFERENCE PUBLICATION.** Collected papers from scientific and technical conferences, symposia, seminars, or other meetings sponsored or co-sponsored by NASA.
- **SPECIAL PUBLICATION.** Scientific, technical, or historical information from NASA programs, projects, and missions, often concerned with subjects having substantial public interest.
- **TECHNICAL TRANSLATION.** English-language translations of foreign scientific and technical material pertinent to NASA's mission.

Specialized services also include organizing and publishing research results, distributing specialized research announcements and feeds, providing information desk and personal search support, and enabling data exchange services.

For more information about the NASA STI program, see the following:

- Access the NASA STI program home page at <http://www.sti.nasa.gov>
- E-mail your question to help@sti.nasa.gov
- Phone the NASA STI Information Desk at 757-864-9658
- Write to:
NASA STI Information Desk
Mail Stop 148
NASA Langley Research Center
Hampton, VA 23681-2199

NASA/TM-2015-218809
NESC-RP-15-01039



Glenn Extreme Environments Rig (GEER) Independent Review

*Robert S. Jankovsky/NESC and Michael D. Smiles/NESC
Langley Research Center, Hampton, Virginia*

*Mark A. George
Glenn Research Center, Cleveland, Ohio*

*Mimi C. Ton
Jet Propulsion Laboratory, Pasadena, California*

*Son K. Le
Stennis Space Center, Mississippi*

National Aeronautics and
Space Administration

Langley Research Center
Hampton, Virginia 23681-2199

October 2015

Acknowledgments

The NESC team would like to acknowledge Mrs. Lori Arnett for assuring that the NESC team had access to whomever and whatever information was requested. Her efforts were essential to the efficient completion of this assessment. The NESC team also would like to acknowledge the following individuals for their openness during the facility inspections and tabletop discussion:

- Leah Nakley – Lead Operations
- Ken Gregg – Mechanical Design
- Joe Rymut – Electrical Design
- Alex Sgondea – Electrical Design
- Jim Mullins – Facility Engineer
- Rodger Dyson – Mechanical Design
- Lori Arnett – Facility Manager
- Dan Vento – Project Manager
- Jim Hritz – Safety/Hazard Analysis
- Tim Fiorilli – Industrial Hygienist
- Chuck Druesedow – Pressure Systems Office

The use of trademarks or names of manufacturers in the report is for accurate reporting and does not constitute an official endorsement, either expressed or implied, of such products or manufacturers by the National Aeronautics and Space Administration.

Available from:

NASA STI Program / Mail Stop 148
NASA Langley Research Center
Hampton, VA 23681-2199
Fax: 757-864-6500

	<p align="center">NASA Engineering and Safety Center Technical Assessment Report</p>	<p align="center">Document #: NESC-RP- 15-01039</p>	<p align="center">Version: 1.0</p>
<p>Title: GEER Independent Review</p>		<p>Page #: 1 of 22</p>	

Glenn Extreme Environments Rig (GEER) Independent Review

September 10, 2015

	<p align="center">NASA Engineering and Safety Center Technical Assessment Report</p>	<p>Document #: NESC-RP- 15-01039</p>	<p>Version: 1.0</p>
<p>Title: GEER Independent Review</p>			<p>Page #: 2 of 22</p>

Report Approval and Revision History

NOTE: This document was approved at the September 10, 2015, NRB. This document was submitted to the NESC Director on September 17, 2015, for configuration control.

<p>Approved: _____</p>	<p align="center">Original Signature on File _____ NESC Director</p>	<p align="center">9/17/15 _____ Date</p>
------------------------	--	--

Version	Description of Revision	Office of Primary Responsibility	Effective Date
1.0	Initial Release	Mr. Robert Jankovsky, NESC Chief Engineer, GRC	9/10/15

	NASA Engineering and Safety Center Technical Assessment Report	Document #:	Version:
		NESC-RP-15-01039	1.0
Title:		GEER Independent Review	
		Page #: 3 of 22	

Table of Contents

Technical Assessment Report

1.0	Notification and Authorization	4
2.0	Signature Page	5
3.0	Team List	6
3.1	Acknowledgements.....	6
4.0	Executive Summary	7
5.0	Rig/Facility Description	8
6.0	Documentation	14
7.0	Findings and NESC Recommendations	18
7.1	Findings.....	18
7.2	NESC Recommendations.....	20
8.0	Alternate Viewpoint	20
9.0	Other Deliverables	20
10.0	Lessons Learned	20
11.0	Recommendations for NASA Standards and Specifications	20
12.0	Definition of Terms	21
13.0	Acronyms List	21
14.0	References	21

List of Figures

Figure 5.0-1.	GRC GEER.....	8
Figure 5.0-2.	GRC Building 334.....	9
Figure 5.0-3.	Pressure Vessel.....	10
Figure 5.0-4.	Gas Cabinets.....	11
Figure 5.0-5.	Mixing Cabinet.....	11
Figure 6.0-1.	Electronic Folders with All Documentation Provided for Review.....	15
Figure 6.0-2.	Review Documents Folder Contents.....	15
Figure 6.0-3.	Released Electrical Drawings Folder Contents.....	15
Figure 6.0-4.	PSO Supporting Documentation Folder Contents.....	16
Figure 6.0-5.	PSO Drawings Folder Contents.....	16
Figure 6.0-6.	Checksheets Folder Contents.....	17
Figure 6.0-7.	7150 Documents Folder Contents.....	17
Figure 6.0-8.	On-line Safety Permit System with Links to PSO Certifications and Operation Procedures.....	18
Figure 7.1-1.	Pressure System Component Tags.....	19

	NASA Engineering and Safety Center Technical Assessment Report	Document #: NESC-RP- 15-01039	Version: 1.0
Title: GEER Independent Review		Page #: 4 of 22	

Technical Assessment Report

1.0 Notification and Authorization

The Chief of the Space Science Project Office at Glenn Research Center (GRC) requested support from the NASA Engineering and Safety Center (NESC) to satisfy a request from the Science Mission Directorate (SMD) Associate Administrator and the Planetary Science Division Chief to obtain an independent review of the Glenn Extreme Environments Rig (GEER) and the operational controls in place for mitigating any hazard associated with its operation.

Mr. Robert Jankovsky, NESC Chief Engineer at NASA GRC, was selected to lead this assessment.

The key stakeholders for this assessment are the NASA SMD, GRC, and the planetary science community.

	NASA Engineering and Safety Center Technical Assessment Report	Document #: NESC-RP-15-01039	Version: 1.0
Title: GEER Independent Review		Page #: 5 of 22	

2.0 Signature Page

Submitted by:

Team Signature Page on File – 9/22/15

Mr. Robert S. Jankovsky Date

Significant Contributors:

Mr. Michael D. Smiles Date

Mr. Mark A. George Date

Ms. Mimi C. Ton Date

Mr. Son K. Le Date

Signatories declare the findings, observations, and NESC recommendations compiled in the report are factually based from data extracted from program/project documents, contractor reports, and open literature, and/or generated from independently conducted tests, analyses, and inspections.

	NASA Engineering and Safety Center Technical Assessment Report	Document #:	Version:
		NESC-RP-15-01039	1.0
Title:		Page #:	
GEER Independent Review		6 of 22	

3.0 Team List

Name	Discipline	Organization
Core Team		
Robert Jankovsky	NESC Lead	GRC
Michael Smiles	NESC Chief Engineer	SSC
Mark George	Hazards Analyses	NSC
Mimi Ton	Industrial Hygiene	JPL
Son Le	Pressure Systems	SSC
Linda Moore	MTSO Program Analyst	LaRC
Administrative Support		
Erin Moran	Technical Writer	LaRC/AMA

3.1 Acknowledgements

The NESC team would like to acknowledge Mrs. Lori Arnett for assuring that the NESC team had access to whomever and whatever information was requested. Her efforts were essential to the efficient completion of this assessment. The NESC team also would like to acknowledge the following individuals for their openness during the facility inspections and tabletop discussion:

- Leah Nakley – Lead Operations
- Ken Gregg – Mechanical Design
- Joe Rymut – Electrical Design
- Alex Sgondea – Electrical Design
- Jim Mullins – Facility Engineer
- Rodger Dyson – Mechanical Design
- Lori Arnett – Facility Manager
- Dan Vento – Project Manager
- Jim Hritz – Safety/Hazard Analysis
- Tim Fiorilli – Industrial Hygienist
- Chuck Druessedow – Pressure Systems Office

	NASA Engineering and Safety Center Technical Assessment Report	Document #: NESC-RP-15-01039	Version: 1.0
Title: GEER Independent Review		Page #: 7 of 22	

4.0 Executive Summary

Ms. Ann Over, Chief of the Space Science Project Office at Glenn Research Center (GRC), requested this assessment to satisfy a request from the Science Mission Directorate (SMD) Headquarters leadership for an independent review of the Glenn Extreme Environments Rig (GEER) hazards due to its large scale compared to what historically has been done [ref. 1].

The assessment included a review of existing GEER documentation (Section 6.0 Documentation) and a 1-day on-site inspection of the rig/facility (Section 5.0 Rig/Facility Description), including a tabletop review with the project/facility engineering team that designed and built the GEER.

The NASA Engineering and Safety Center (NESC) team found the hazards (high temperature, high pressure, toxic gases) inherent to GEER had been thoroughly and systematically addressed and concurred the transition from commissioning to operations should continue. All other findings were considered minor. Three of the remaining findings were minor discrepancies between documents and the as-built rig, or documented procedures, and those verbally discussed. These discrepancies should be eliminated and changes to procedures reviewed with the operators. Four findings had to do with the main pressure vessel (referred to as TM9001), and maintaining its integrity and history for future recertification. The first of these four findings was that although the facility engineering team considered creep of the TM9001, they did not have a procedure for documenting the cycles, pressure, and temperature to support potential future analyses at different operating conditions.

In the second of the four related findings, the NESC team noted that although the facility engineering team had identified the facility sprinkler system activation while at temperature as a possible hazard, and closed it after testing, the hot vessel could not set off the sprinklers even without the ventilation system operating. The team did not consider other inadvertent sprinkler system activation, and as such have not completely considered the potential for rapid cooling of the TM9001 causing loss of containment.

In the third related finding, the NESC team also found that in at least one instance pressure drop calculations on a pressure relief valve did not consider pipe diameter in accordance with American Society of Mechanical Engineer (ASME) Section VIII, Division 1 allowances.

In the final related finding, the NESC team found that corrosion under the TM9001 insulation was not considered in accordance with American Petroleum Institute (API)-571 and is recommending an inspection/monitoring procedure be added.

Lastly, it was found that the control room had no visual monitoring of the test cell. Although procedures are in place to ensure the area is clear before flowing gases, the NESC team recommends that a video system be installed.

In all cases, the Space Science Project Office and facility engineering team at GRC has accepted all of the findings and NESC recommendations and has either already completed them or they are in work.

	NASA Engineering and Safety Center Technical Assessment Report	Document #: NESC-RP-15-01039	Version: 1.0
Title: GEER Independent Review		Page #: 8 of 22	

5.0 Rig/Facility Description

NASA recently started the commissioning process of the GEER (Figure 5.0-1), located in Building 334 (Figure 5.0-2) at GRC. The GEER is designed to simulate the temperature, pressure, and atmospheric compositions of bodies in the solar system, including those with acidic and hazardous elements.

The GEER consists of a 0.79m³ (28ft³), 304 stainless steel pressure vessel with Inconel[®] sheathed resistance heaters and a Maximum Allowable Working Pressure (MAWP) of 10.47 MPa (1518 psia) at 538°C (1000°F) (Figure 5.0-3); four gas cabinets to store up to eight gas cylinders (Figure 5.0-4); a gas mixing cabinet to precisely mix the desired gas chemical composition (Figure 5.0-5); a gas booster to maintain the test conditions over a long period of time with allowable leaks (Figure 5.0-6); a Fourier Transform Infrared (FTIR) Spectrometer to measure chemical composition (Figure 5.0-7); and a vent stack to exhaust gases outside the facility (Figure 5.0-8).




Figure 5.0-1. GRC GEER



NASA Engineering and Safety Center Technical Assessment Report

Document #:
**NESC-RP-
15-01039**

Version:
1.0

Title:

GEER Independent Review

Page #:
10 of 22



Figure 5.0-3. Pressure Vessel



NASA Engineering and Safety Center Technical Assessment Report

Document #:
**NESC-RP-
15-01039**

Version:
1.0

Title:

GEER Independent Review

Page #:
11 of 22



Figure 5.0-4. Gas Cabinets



Figure 5.0-5. Mixing Cabinet



NASA Engineering and Safety Center Technical Assessment Report

Document #:
**NESC-RP-
15-01039**

Version:
1.0

Title:

GEER Independent Review

Page #:
12 of 22




Figure 5.0-6. Gas Booster



Figure 5.0-7. FTIR Spectrometer



NASA Engineering and Safety Center Technical Assessment Report

Document #:
**NESC-RP-
15-01039**

Version:
1.0

Title:

GEER Independent Review

Page #:
13 of 22



Figure 5.0-8. Vent Stack

	NASA Engineering and Safety Center Technical Assessment Report	Document #:	Version:
		NESC-RP-15-01039	1.0
Title:		GEER Independent Review	
		Page #: 14 of 22	

Currently, GEER is configured for Venus surface conditions (Table 5.0-1) and is in the commissioning phase.

Table 5.0-1. GEER Configuration during Commissioning

Chemical Species	96.5% carbon dioxide (CO ₂)
	~3.4% nitrogen (N ₂)
	130 ppm sulfur dioxide (SO ₂)
	5 ppb hydrogen fluoride (HF)
	0.5 ppm hydrogen chloride (HCl)
	15 ppm carbon monoxide (CO)
	27 ppm carbonyl sulfide (OCS)
	30 ppm water (H ₂ O)
Temperature	470°C (878°F)
Pressure	9.24 MPa (1340 psi)

A simplified outline of operations for the GEER is as follows: 1) the test operations start by purging and evacuating the TM9001; 2) component gasses are then blended using the gas mixer; 3) the TM9001 is filled with the desired gas mixture up to 3.45 MPa (500 psi) (at ambient temperature) for the desired end-state chemistry; 4) heat is applied and controlled autonomously to bring the system to a steady-state operating point; and 5) after testing, chamber and plumbing are vented and purged.

6.0 Documentation

The NESC team was provided access to all project documentation for review. Figures 6.0-1 through 6.0-8 summarize the documentation that was made available to the NESC team. The NESC team selectively reviewed these documents with a focus on the hazards analyses, pressure systems, industrial hygiene, and procedures (e.g., startup, shutdown, and operating/emergency).

	NASA Engineering and Safety Center Technical Assessment Report	Document #:	Version:
		NESC-RP-15-01039	1.0
Title:		GEER Independent Review	
		Page #: 15 of 22	

Glenn Extreme Environments Rig (GEER) NESC Review

Team Leader & Coordinator: Lori Arnett (216-433-2947)

Welcome to eRoom!

Help with eRoom: GRC KWI Support: KWI-Support@lists.nasa.gov or 216-433-9702 or Online: [Working in your eRoom](#)



Figure 6.0-1. Electronic Folders with All Documentation Provided for Review

Review Documents

a folder created by ARNETT, LORI (GRC-FTH0) on 9 Jun 15

June 19th Meeting Documents

Name	Modified	Owner	Size
CRT-13-0087 PV2001 Statement Of Vessel Recertification with ISI Table.pdf	10 Jun 15 1:41pm	ARNETT, LORI (GRC-FTH0)	417 k
GEER Alarms And Shutdowns Current.xlsx	10 Jun 15 1:41pm	ARNETT, LORI (GRC-FTH0)	32 k
GEER FHA Update 4-20-15.pdf	10 Jun 15 4:37pm	ARNETT, LORI (GRC-FTH0)	88 k
GEER Operations and Hazards RevC.pdf	10 Jun 15 1:41pm	ARNETT, LORI (GRC-FTH0)	223 k
GEER PHA 4-20-15 report.pdf	10 Jun 15 4:38pm	ARNETT, LORI (GRC-FTH0)	214 k
Glenn Extreme Environments Rig Overview revA.pptx	9 Jun 15 5:05pm	ARNETT, LORI (GRC-FTH0)	657 k (v1)
RAC-13-0087 dated 06-11-2015.pdf	11 Jun 15 11:44am	ARNETT, LORI (GRC-FTH0)	3912 k
Safety Permit 334-13-0004_c919.pdf	10 Jun 15 1:42pm	ARNETT, LORI (GRC-FTH0)	48 k

Figure 6.0-2. Review Documents Folder Contents

Released Electrical Drawings

a folder created by ARNETT, LORI (GRC-FTH0) on 2 Dec 14

81 released electrical drawings for GEER


Name	Modified	Owner	Size
0334-TF1303x_141202_Release set.pdf	3 Dec 14 10:14am	ARNETT, LORI (GRC-FTH0)	14219 k
0334-TF1303x_141202_Release set.zip	2 Dec 14 2:42pm	ARNETT, LORI (GRC-FTH0)	9571 k

Figure 6.0-3. Released Electrical Drawings Folder Contents

	NASA Engineering and Safety Center Technical Assessment Report	Document #:	Version:
		NESC-RP-15-01039	1.0
Title:		GEER Independent Review	
		Page #: 16 of 22	

PSO Questions_Answers_Supporting Documentation

a folder created by Nick Lalli on 17 Apr 14



Name	Modified	Owner	Size
AMI_Venus Test Vessel_Job071.pdf	18 Apr 14 1:22pm	Nick Lalli	59201 k
Audit Question Responses 2 - 3-17-14 Final.pdf	18 Apr 14 1:32pm	Nick Lalli	250 k
Audit question responses 3-17-14 Final.pdf	18 Apr 14 1:32pm	Nick Lalli	460 k
GEER Audit Documentation Supplement 1.pdf	18 Apr 14 1:23pm	Nick Lalli	9141 k
GEER Audit Documentation Supplement 2.pdf	18 Apr 14 1:23pm	Nick Lalli	9981 k
MTI 2013 18_PSO_CO2.pdf	18 Apr 14 1:27pm	Nick Lalli	54780 k
MTI 2013 19_PSO_GN.pdf	18 Apr 14 1:27pm	Nick Lalli	49167 k
MTI 2013 20_PSO_HP_GN.pdf	18 Apr 14 1:27pm	Nick Lalli	47158 k
MTI 2013 23_PSO_MGS.pdf	18 Apr 14 1:28pm	Nick Lalli	135379 k
Obsolete Chromalox Heater & New 3 Heater Configuration.pptx	18 Apr 14 1:28pm	Nick Lalli	2154 k
Pressure Vessel PV2001_PSO_GEER.pdf	18 Apr 14 1:28pm	Nick Lalli	150775 k
PSO_B334_MGS_MTI 2013 23.pdf	18 Apr 14 1:29pm	Nick Lalli	135379 k
PSO_PV2004_PV1818.pdf	18 Apr 14 1:29pm	Nick Lalli	17646 k
PV2000_GEER Accumulator.pdf	18 Apr 14 1:29pm	Nick Lalli	33994 k
PV2003_PV1819.pdf	18 Apr 14 1:29pm	Nick Lalli	17971 k

Figure 6.0-4. PSO Supporting Documentation Folder Contents

PSO Drawings

a folder created by Nick Lalli on 17 Apr 14



Name	Modified	Owner	Size
0334-00192301-M-801_CE_01 Layout1 (1).pdf	17 Apr 14 4:20pm	Nick Lalli	233 k
0334-00192301-M-801_CE_02 Layout1 (1).pdf	17 Apr 14 4:21pm	Nick Lalli	237 k
0334-00192301-M-801_CE_03 Layout1 (1).pdf	17 Apr 14 4:21pm	Nick Lalli	278 k
0334-00192301-M-801_CE_04 Layout1 (1).pdf	17 Apr 14 4:21pm	Nick Lalli	192 k
0334-00192301-M-801_CE_05 Layout1 (1).pdf	17 Apr 14 4:22pm	Nick Lalli	146 k
0334-W1022743-M-801_CE_01 Layout1 (1).pdf	17 Apr 14 4:22pm	Nick Lalli	203 k
0334-W1022743-M-802_CE_01 Layout1 (1).pdf	17 Apr 14 4:22pm	Nick Lalli	250 k
0334-W1022743-M-803_CE_01 Layout1 (1).pdf	17 Apr 14 4:23pm	Nick Lalli	239 k
0334-W1022743-M-804_CE_01 Layout1 (1).pdf	17 Apr 14 4:23pm	Nick Lalli	219 k
0334-W1022743-M-805_CE_01 Layout1 (1).pdf	17 Apr 14 4:23pm	Nick Lalli	204 k
0334-W1022743-M-806_CE_01 Layout1 (1).pdf	17 Apr 14 4:24pm	Nick Lalli	288 k
0334-W1022743-M-807_CE_01 Layout1 (1).pdf	17 Apr 14 4:24pm	Nick Lalli	266 k
0334-W1022743-M-808_CE_01 Layout1 (1).pdf	17 Apr 14 4:25pm	Nick Lalli	273 k
0334-W1022743-M-809_CE_01 Layout1 (1).pdf	17 Apr 14 4:25pm	Nick Lalli	258 k
0334-W1022743-M-810_CE_01 Layout1 (1).pdf	17 Apr 14 4:25pm	Nick Lalli	183 k
0334-W1022743-M-811_CE_01 Layout1 (1).pdf	17 Apr 14 4:26pm	Nick Lalli	190 k
0334-WON20251-M-801_CE_01 FULLSIZE (1).pdf	17 Apr 14 4:26pm	Nick Lalli	214 k

Figure 6.0-5. PSO Drawings Folder Contents

Checksheets

a folder created by  ARNETT, LORI (GRC-FTHO) on 10 Jun 15

Name	Modified	Owner	Size
 Rig Procedures (ALL)-7-14-14.docx	10 Jun 15 4:41pm	ARNETT, LORI (GRC-FTHO)	16642 k
 Rig Procedures-GRC-GEER-PROC-001-Test Run Sheet 03272015.docx	10 Jun 15 4:41pm	ARNETT, LORI (GRC-FTHO)	31 k
 Rig Procedures-GRC-GEER-PROC-002-ControlSystem 09192013.docx	10 Jun 15 4:41pm	ARNETT, LORI (GRC-FTHO)	3771 k
 Rig Procedures-GRC-GEER-PROC-003 Tube Trailer Operation 07022014.docx	10 Jun 15 4:41pm	ARNETT, LORI (GRC-FTHO)	108 k
 Rig Procedures-GRC-GEER-PROC-004-CO2 Supply System 07022014.docx	10 Jun 15 4:42pm	ARNETT, LORI (GRC-FTHO)	36 k
 Rig Procedures-GRC-GEER-PROC-005-Gas-Panels_10292013.docx	10 Jun 15 4:42pm	ARNETT, LORI (GRC-FTHO)	31 k
 Rig Procedures-GRC-GEER-PROC-006-Mixer_02232014.docx	10 Jun 15 4:42pm	ARNETT, LORI (GRC-FTHO)	34 k
 Rig Procedures-GRC-GEER-PROC-007-GEEV_03052015 lmn.docx	10 Jun 15 4:42pm	ARNETT, LORI (GRC-FTHO)	14340 k
 Rig Procedures-GRC-GEER-PROC-008-BOOSTER_07022014.docx	10 Jun 15 4:42pm	ARNETT, LORI (GRC-FTHO)	35 k
 Rig Procedures-GRC-GEER-PROC-009-FTIR.docx	10 Jun 15 4:42pm	ARNETT, LORI (GRC-FTHO)	23 k
 Rig Procedures-GRC-GEER-PROC-010-TEST SAFETY_06052015.docx	10 Jun 15 4:42pm	ARNETT, LORI (GRC-FTHO)	37 k
 Rig Procedures-GRC-GEER-PROC-011-Emissions.docx	10 Jun 15 4:43pm	ARNETT, LORI (GRC-FTHO)	34 k
 Rig Procedures-GRC-GEER-PROC-012-Collecting Gas in a Sample Vessel.docx	10 Jun 15 4:43pm	ARNETT, LORI (GRC-FTHO)	33 k
 Rig Procedures-GRC-GEER-PROC-013-LOTO_02272014.docx	10 Jun 15 4:43pm	ARNETT, LORI (GRC-FTHO)	30 k
 Rig Procedures-GRC-GEER-PROC-List 3-18-15.docx	10 Jun 15 4:43pm	ARNETT, LORI (GRC-FTHO)	17 k

Figure 6.0-6. Checksheets Folder Contents

7150 Documents

a folder created by  Nick Lalli on 24 Apr 14

Name	Modified	Owner	Size
 Configuration Management Guidelines.pdf	24 Apr 14 2:39pm	Nick Lalli	11 k
 GEER Alarm and Shutdown check sheet 10282013 5KB.xlsx	24 Apr 14 2:39pm	Nick Lalli	25 k
 GEER Alarm and Shutdown summary 10242013.docx	24 Apr 14 2:39pm	Nick Lalli	36 k
 GEER Process and BOM PRELIM 6-08-13.xlsx	24 Apr 14 2:40pm	Nick Lalli	73 k
 GEER_Perm_and_Interlocks_in_progress.pdf	24 Apr 14 2:40pm	Nick Lalli	201 k
 Link to PLC_software_assurance_plan_GEER.docx	28 Apr 14 1:55pm	Rymut, Joseph E. (GRC-FTHO)	
 NPR 7150 as applied to safety-critical PLC applications_GEER.docx	24 Apr 14 2:40pm	Nick Lalli	31 k
 plc_control_system_safety_standard_8713_19C_GEER.xlsx	24 Apr 14 2:40pm	Nick Lalli	22 k
 PLC_functions_design_purpose_7150_stuff_rev1.doc	24 Apr 14 2:40pm	Nick Lalli	31 k
 PLC_Implementation_in_GRC_GEER.doc	24 Apr 14 2:40pm	Nick Lalli	58 k
 PLC_software_assurance_plan_GEER.docx	24 Apr 14 2:41pm	Nick Lalli	78 k
 PLC_test_procedure_GRC_GEER.doc	24 Apr 14 2:41pm	Nick Lalli	992 k
 Relative Size of GEER vs Major Facility.pptx	9 May 14 5:03pm	Nick Lalli	4234 k
 Software Documentation (9-10-13).pdf	24 Apr 14 2:41pm	Nick Lalli	404 k
 software_assurance_compliance_martix_GEER.xls	24 Apr 14 2:41pm	Nick Lalli	59 k
 software_management_plan_plc_control_systems_GEER.docx	24 Apr 14 2:41pm	Nick Lalli	232 k

Figure 6.0-7. 7150 Documents Folder Contents

	NASA Engineering and Safety Center Technical Assessment Report	Document #:	Version:
		NESC-RP-15-01039	1.0
Title:		GEER Independent Review	
		Page #: 18 of 22	




Figure 6.0-8. On-line Safety Permit System with Links to PSO Certifications and Operation Procedures

7.0 Findings and NESC Recommendations

7.1 Findings

The following findings were identified:

- F-1.** The Process Hazards Analysis (PHA) and Facility Hazards Analysis (FHA) were complete and up to date. The inherent hazards of high pressure, high temperature, and toxic gases were thoroughly and systematically addressed.
- F-2.** No procedure exists for documenting the operational history (e.g., cycles, pressure, and temperature) of the 304 stainless steel TM9001.
- F-3.** There is a potential for thermal shock to the GEER TM9001 if the wet fire suppression system in the test cell is inadvertently activated.
- F-4.** The pressure system relief valve inlet piping pressure drop calculation did not consider changes in pipe diameter.
- F-5.** The cited MAWP were not consistent across data sources (e.g., Piping and Instrumentation Diagram (P&ID), relief device data sheets, Pressure Systems Office (PSO) data book).

	NASA Engineering and Safety Center Technical Assessment Report	Document #:	Version:
		NESC-RP-15-01039	1.0
Title:		Page #:	
GEER Independent Review		19 of 22	

- F-6.** Corrosion of the TM9001 under the insulation material was not considered in inspection or maintenance planning. In accordance with API-571, for 304-type stainless steel equipment that are insulated, operate intermittently, or operate between 60°C (140°F) and 204.4°C (400°F), corrosion under insulation is a concern.
- F-7.** The written procedure for manually drawing a gas sample from the TM9001 was inconsistent with the procedure described by the qualified operator during the rig/facility inspection.
- F-8.** The relief valve (TM2703/RV6094) from the booster vessel was not installed in accordance with the P&ID.
- F-9.** Facility engineering's component tags were not secured permanently and were not found in some locations on the rig (Figure 7.1-1).
- F-10.** Two configuration management systems (PSO and facility engineering) are being used for pressure system components (Figure 7.1-1).




Figure 7.1-1. Pressure System Component Tags

- F-11.** There is no means to visually monitor the test cell from the control room.
- F-12.** The test cell ventilation assessment was thorough and included multiple smoke tests.

	NASA Engineering and Safety Center Technical Assessment Report	Document #: NESC-RP- 15-01039	Version: 1.0
Title: GEER Independent Review		Page #: 20 of 22	

7.2 NESC Recommendations

The following NESC recommendations were identified and directed toward GRC's Facility, Test and Manufacturing Directorate unless otherwise identified:

- R-1.** Due to prolonged operation at elevated temperatures, procedures should be modified to include the documentation of the TM9001 operational history (cycles, pressure, and temperature) for consideration of material deformation below yield strength (creep) during future recertification or delta certifications. *(F-2)*
- R-2.** Determine the risk associated with rapid cooling of the TM9001 while at temperature by the existing wet fire suppression system. Consider a dry fire suppression system as an alternative if risk is unacceptable as currently installed. *(F-3)*
- R-3.** Verify inlet and discharge piping pressure drop do not exceed ASME Section VIII, Division 1 allowances for all relief valves on rig. *(F-4)*
- R-4.** Update analyses and any required design, inspection, and monitoring procedures to include consideration of external corrosion over the range of anticipated environments for the TM9001. *(F-6)*
- R-5.** Update all documentation to be consistent with present design and operating procedures and review the changes with all qualified operators before the rig is operated each time. *(F-5, F-7, F-8)*
- R-6.** Install a video monitoring system between the test cell and the control room as a verification of no personnel in the area before flowing gas and to facilitate compliance with the buddy system requirement. *(F-11)*

8.0 Alternate Viewpoint

There were no alternate viewpoints identified during the course of this assessment by the NESC team or the NRB quorum.

9.0 Other Deliverables

No unique hardware, software, or data packages, outside those contained in this report, were disseminated to other parties outside this assessment.

10.0 Lessons Learned

No applicable lessons learned were identified for entry into the NASA Lessons Learned Information System (LLIS) as a result of this assessment.

11.0 Recommendations for NASA Standards and Specifications

No recommendations for NASA standards and specifications were identified as a result of this assessment.

	NASA Engineering and Safety Center Technical Assessment Report	Document #:	Version:
		NESC-RP-15-01039	1.0
Title:		GEER Independent Review	
		Page #: 21 of 22	

12.0 Definition of Terms

Finding	A relevant factual conclusion and/or issue that is within the assessment scope and that the team has rigorously based on data from their independent analyses, tests, inspections, and/or reviews of technical documentation.
Lessons Learned	Knowledge, understanding, or conclusive insight gained by experience that may benefit other current or future NASA programs and projects. The experience may be positive, as in a successful test or mission, or negative, as in a mishap or failure.
Observation	A noteworthy fact, issue, and/or risk, which may not be directly within the assessment scope, but could generate a separate issue or concern if not addressed. Alternatively, an observation can be a positive acknowledgement of a Center/Program/Project/Organization's operational structure, tools, and/or support provided.
Problem	The subject of the independent technical assessment.
Recommendation	A proposed measurable stakeholder action directly supported by specific Finding(s) and/or Observation(s) that will correct or mitigate an identified issue or risk.

13.0 Acronyms List

API	American Petroleum Institute
ASME	American Society of Mechanical Engineer
FTIR	Fourier Transform Infrared
GEER	Glenn Extreme Environments Rig
GRC	Glenn Research Center
JPL	Jet Propulsion Laboratory
MAWP	Maximum Allowable Working Pressure
MTSO	Management Technical Support Office
NESC	NASA Engineering and Safety Center
NRB	NESC Review Board
NSC	NASA Safety Center
P&ID	Piping and Instrumentation Diagram
ppm	Parts Per Million
psi	Pound Per Square Inch
psia	Pounds Per Square Inch Absolute
PSO	Pressure Systems Office
SMD	Science Mission Directorate
SSC	Stennis Space Center

	<p align="center">NASA Engineering and Safety Center Technical Assessment Report</p>	<p>Document #: NESC-RP- 15-01039</p>	<p>Version: 1.0</p>
<p>Title: GEER Independent Review</p>		<p>Page #: 22 of 22</p>	

14.0 References

1. Kremic, Vento, Lalli, Palinski. *Extreme Environment Simulation – Current and New Capabilities to Stimulate Venus and other Planetary Bodies*, (2014).
2. API-571, *Damage Mechanisms Affecting Fixed Equipment in the Refining Industries*, April 1, 2011.

REPORT DOCUMENTATION PAGE

*Form Approved
OMB No. 0704-0188*

The public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0704-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.
PLEASE DO NOT RETURN YOUR FORM TO THE ABOVE ADDRESS.

1. REPORT DATE (DD-MM-YYYY) 01-10-2015			2. REPORT TYPE Technical Memorandum		3. DATES COVERED (From - To) May 2015 - September 2015	
4. TITLE AND SUBTITLE Glenn Extreme Environments Rig (GEER) Independent Review					5a. CONTRACT NUMBER	
					5b. GRANT NUMBER	
					5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S) Jankovsky, Robert S.; Smiles, Michael D.; George, Mark A.; Ton, Mimi C.; Le, Son K.					5d. PROJECT NUMBER	
					5e. TASK NUMBER	
					5f. WORK UNIT NUMBER 869021.05.03.05.99	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) NASA Langley Research Center Hampton, VA 23681-2199					8. PERFORMING ORGANIZATION REPORT NUMBER L-20620 NESC-RP-15-01039	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) National Aeronautics and Space Administration Washington, DC 20546-0001					10. SPONSOR/MONITOR'S ACRONYM(S) NASA	
					11. SPONSOR/MONITOR'S REPORT NUMBER(S) NASA/TM-2015-218809	
12. DISTRIBUTION/AVAILABILITY STATEMENT Unclassified - Unlimited Subject Category 18 Spacecraft Design, Testing and Performance Availability: NASA STI Program (757) 864-9658						
13. SUPPLEMENTARY NOTES						
14. ABSTRACT The Chief of the Space Science Project Office at Glenn Research Center (GRC) requested support from the NASA Engineering and Safety Center (NESC) to satisfy a request from the Science Mission Directorate (SMD) Associate Administrator and the Planetary Science Division Chief to obtain an independent review of the Glenn Extreme Environments Rig (GEER) and the operational controls in place for mitigating any hazard associated with its operation. This document contains the outcome of the NESC assessment.						
15. SUBJECT TERMS Glenn Extreme Environments Rig; NASA Engineering and Safety Center; Hazard Mitigation						
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT	18. NUMBER OF PAGES	19a. NAME OF RESPONSIBLE PERSON	
a. REPORT	b. ABSTRACT	c. THIS PAGE			STI Help Desk (email: help@sti.nasa.gov)	
U	U	U	UU	27	19b. TELEPHONE NUMBER (Include area code) (443) 757-5802	